

2001 Eleanor Avenue, Saint Paul, MN 55116

Chart C - All Materials List

The following list contains all events observed by the inspector, whether or not they actually contained asbestos, and are grouped by homogeneous area (material type).

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
B1A	Air Cell Pipe Insulation 1930 Original Building					Total Amount - 10 Lin Ft
	14	1930 ORIGINAL BUILDING TUNNEL	ASSUMED			10 Lin Ft
B2C	Millboard Pipe Insulation 1954 Addition					Total Amount - 1 Lin Ft
	42	1954 ADDITION 2ND FLOOR HALLWAY 2100	5 CH	2001-1501-MN-4, 5	ROOM 1301 (SINCE REMOVED).	1 Lin Ft
I2D	2' x 2' Acoustical Ceiling Tile Textured w/Revealed Edge (2018)					Total Amount - 20000 Sq Ft
	2	THROUGHOUT BUILDING	NEW			20000 Sq Ft
I2E	2' x 2' Acoustical Ceiling Tile Pock Marks w/Pin Holes (2018)					Total Amount - 40000 Sq Ft
	3	THROUGHOUT BUILDING	NEW			40000 Sq Ft
I2F	2' x 2' Acoustical Ceiling Tile Lightly Textured (2018)					Total Amount - 1500 Sq Ft
	53	THROUGHOUT 2017 ADDITION KITCHEN	NEW			1500 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
I4A	Acoustical Ceiling Tile 4'x4' Lightly Textured					Total Amount - 2000 Sq Ft
	52	THROUGHOUT 2017 ADDITION CAFETERIA	NEW			2000 Sq Ft
I4B	Acoustical Ceiling Tile 4' X 12' Tectum Wall Panels					Total Amount - 1500 Sq Ft
	49	1995 ADDITION GYMNASIUM	NEW			1500 Sq Ft
K1B	Sheet Vinyl Flooring & Adhesive Gray (2018)					Total Amount - 2000 Sq Ft
	8	THROUGHOUT BUILDING RESTROOMS	NEW			2000 Sq Ft
K3A	Miscellaneous Flooring 2' X 2' Gray Rubber (2018)					Total Amount - 32000 Sq Ft
	4	THROUGHOUT BUILDING	NEW			30000 Sq Ft
	51	THROUGHOUT 2017 ADDITION	NEW			2000 Sq Ft
M0A	Plaster 1930 Original Building					Total Amount - 15000 Sq Ft
	11	THROUGHOUT 1930 ORIGINAL BUILDING	NONE DETECTED	050218-BF-9; 022509-MA-11; 2001-01364-01, 02; 510-H1, H2, H3; 1140-8	BF-9: HALLWAY BY ROOM 1203. MA-11: 1ST FLOOR HALLWAY. H1: EAST STAIRWELL. H2: SOUTHWEST STAIRWELL. H3: STAIRWELL TO BOILER ROOM.	15000 Sq Ft
M0B	Plaster 1939 Addition					Total Amount - 15000 Sq Ft
	16	THROUGHOUT 1939 ADDITION	NONE DETECTED	022509-MA-24, 26, 27, 28, 29; 518-8	MA-24: ROOM 2211. MA-26: ROOM 1202. MA-27: ROOM 1209. MA-28: ROOM 0210. MA-29: ROOM 0205.	15000 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
M0C	Plaster 1954 Addition	Total Amount - 20000 Sq Ft				
	22	THROUGHOUT 1954 ADDITION	NONE DETECTED	022509-MA-25, 32, 33, 34; 518-2, 3; 1140-3, 9	MA-25: ROOM 1301. MA-32: ROOM 1002. MA-33: WEST STAIRWELL CLOSET. MA-34: 2ND FLOOR BOYS' RESTROOM FAN ROOM.	20000 Sq Ft
N0A	Drywall/Joint Compound	Total Amount - 10000 Sq Ft				
	1	THROUGHOUT BUILDING	NONE DETECTED	510-H4; 518-13, 15	510-H4: ROOM 1205C.	10000 Sq Ft
N0B	Drywall/Joint Compound 1995 Addition	Total Amount - 10000 Sq Ft				
	46	THROUGHOUT 1954 ADDITION	NONE DETECTED	061917BF-13	BF-13: CORRIDOR 1400.	10000 Sq Ft
Q0C	Carpet Adhesive Black, Gray w/Multi-Colored Stripes Carpet Squares (2018)	Total Amount - 30000 Sq Ft				
	5	THROUGHOUT BUILDING	NEW			30000 Sq Ft
Q0D	Carpet Adhesive Black & Gray Carpet Squares	Total Amount - 500 Sq Ft				
	7	THROUGHOUT BUILDING ENTRANCES	NEW			500 Sq Ft
R0A	Baseboard/Mopboard Adhesive 4" Gray Baseboard	Total Amount - 500 Sq Ft				
	6	THROUGHOUT BUILDING	NONE DETECTED			500 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
R0G	Baseboard/Mopboard Adhesive Black 90 Degree (2018)					Total Amount - 50 Sq Ft
	48	1995 ADDITION GYMNASIUM	NEW			50 Sq Ft
S0A	Wood Floor Felt / Vapor Barrier 1930 Original Building					Total Amount - 5000 Sq Ft
	24	THROUGHOUT 1930 ORIGINAL BUILDING 1ST FLOOR	NONE DETECTED	040518-BF-1	BF-1: ROOM 1204.	2500 Sq Ft
	31	THROUGHOUT 1930 ORIGINAL BUILDING 2ND FLOOR	NONE DETECTED	040518-BF-2	BF-2: ROOM 2206.	2500 Sq Ft
S0B	Wood Floor Felt / Vapor Barrier 1939 Addition (On-Grade)					Total Amount - 1740 Sq Ft
	17	ROOM 0210A	NONE DETECTED			140 Sq Ft
	18	ROOM 0210	NONE DETECTED			860 Sq Ft
	19	ROOM 0206	NONE DETECTED			220 Sq Ft
	20	ROOM 0204	NONE DETECTED	040518-BF-3	BF-3: ROOM 0204.	520 Sq Ft
S0BB	Wood Floor Felt / Vapor Barrier 1939 Addition (Elevated)					Total Amount - 2000 Sq Ft
	28	THROUGHOUT 1939 ADDITION 1ST FLOOR	NONE DETECTED	040518-BF-4	BF-4: ROOM 1209.	2000 Sq Ft
VOA	Sink Undercoating Gray					Total Amount - 9 Sq Ft
	30	ROOM 1202	NONE DETECTED			5 Sq Ft
	50	NURSE'S OFFICE AREA	NONE DETECTED	061917-BF-3; 022509-MA-13	BF-3: ROOM 1401.	4 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
X0A	Miscellaneous Material Wood Frame Chalkboard Adhesive (1930)					Total Amount - 40 Sq Ft
	25	ROOM 1204	NONE DETECTED			5 Sq Ft
	33	ROOM 2205	NONE DETECTED	052318-BF-1	BF-1: ROOM 2205.	15 Sq Ft
	35	ROOM 2206	NONE DETECTED			20 Sq Ft
X0B	Miscellaneous Material Wood Frame Chalkboard Adhesive (1939)					Total Amount - 20 Sq Ft
	37	ROOM 2202	ASSUMED			20 Sq Ft
X0C	Miscellaneous Material Metal Frame Chalkboard Adhesive (1954)					Total Amount - 5 Sq Ft
	26	ROOM 1204	ASSUMED			5 Sq Ft
X0D	Miscellaneous Material White Material Between Metal Window Panels					Total Amount - 600 Sq Ft
	10	THROUGHOUT BUILDING	NONE DETECTED	022509-MA-10	MA-10: BOILER ROOM.	600 Sq Ft
X0E	Miscellaneous Material Wood Frame Corkboard Adhesive (1930)					Total Amount - 340 Sq Ft
	27	ROOM 1205	NONE DETECTED			140 Sq Ft
	34	ROOM 2205	NONE DETECTED	052318-BF-2	BF-2: ROOM 2204 (SINCE REMOVED).	80 Sq Ft
	36	ROOM 2206	NONE DETECTED			120 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
X0F	Miscellaneous Material Wood Frame Corkboard Adhesive (1939)					Total Amount - 120 Sq Ft
	29	ROOM 1202	NONE DETECTED			40 Sq Ft
	38	ROOM 2202	NONE DETECTED	052318-BF-3	BF-3: ROOM 2202.	80 Sq Ft
X0G	Miscellaneous Material Metal Frame Corkboard Adhesive (1954)					Total Amount - 480 Sq Ft
	39	ROOM 1101	ASSUMED			80 Sq Ft
	40	ROOM 1102	ASSUMED			80 Sq Ft
	41	ROOM 1103	ASSUMED			80 Sq Ft
	43	ROOM 2103	ASSUMED			80 Sq Ft
	44	ROOM 2104	ASSUMED			80 Sq Ft
	45	ROOM 2105	ASSUMED			80 Sq Ft
X0H	Miscellaneous Material Black Wall Coating					Total Amount - 275 Sq Ft
	12	COAL STORAGE 0208B	NONE DETECTED	061917BF-19		125 Sq Ft
	15	1930 ORIGINAL BUILDING TUNNEL	NONE DETECTED			150 Sq Ft
X0I	Miscellaneous Material Poured Rubber Flooring (2018)					Total Amount - 5000 Sq Ft
	47	1995 ADDITION GYMNASIUM	NEW			5000 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
X1A	Miscellaneous Material 6" X 6" Light Brown Quarry Tile System					Total Amount - 2000 Sq Ft
	54	THROUGHOUT 2017 ADDITION KITCHEN	NEW			2000 Sq Ft
X1C	Miscellaneous Material 6" X 6" White Ceramic Wall Tile System (2018)					Total Amount - 5000 Sq Ft
	9	THROUGHOUT BUILDING RESTROOMS	NEW			5000 Sq Ft
X1D	Miscellaneous Material 3" X 3" Gray Ceramic Floor Tile System					Total Amount - 240 Sq Ft
	21	RESTROOM 0209	NEW			80 Sq Ft
	32	RESTROOM 2106	NEW			160 Sq Ft
X1E	Miscellaneous Material 2" X 2" Brown Ceramic Floor Tile System					Total Amount - 35 Sq Ft
	13	CUSTODIAL RESTROOM 0208B	NEW			35 Sq Ft
X1H	Miscellaneous Material 6" X 6" Brownish Red Quarry Tile System					Total Amount - 120 Sq Ft
	23	THROUGHOUT 1954 ADDITION STAIRWELLS	ASSUMED			120 Sq Ft