

1760 Ames Place, Saint Paul, MN 55106

Chart C - All Materials List

The following list contains all events observed by the inspector, whether or not they actually contained asbestos, and are grouped by homogeneous area (material type).

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
A2C	Mudded Pipe Joints on Millboard Insulation 1954 Addition					Total Amount - 1 Joints
	67	1954 ADDITION 1ST FLOOR HALLWAY	ASSUMED			1 Joints
A4A	Mudded Pipe Joints on Fiberglass Insulation Unknown Installation Date					Total Amount - 1 Joints
	45	BOILER ROOM (101) WEST END	NONE DETECTED	111108-MA-03		1 Joints
B2C	Millboard Pipe Insulation 1954 Addition					Total Amount - 10 Lin Ft
	66	1954 ADDITION 1ST FLOOR HALLWAY	ASSUMED			10 Lin Ft
B3C	Pre-Formed Pipe Insulation 1954 Addition					Total Amount - 8 Lin Ft
	65	1954 ADDITION 1ST FLOOR WEST STAIRWELL LANDING 2299A	20 AM	100N-3A	3A: 1ST FLOOR HALLWAY (SINCE REMOVED).	3 Lin Ft
	111	1954 ADDITION 2ND FLOOR WEST STAIRWELL LANDING 3299A	20 AM			5 Lin Ft
I1A	1' x 1' Acoustical Ceiling Tile Pockmarks & Pin Holes (1954)					Total Amount - 800 Sq Ft
	58	1954 ADDITION WEST STAIRWELL	NONE DETECTED	071718RR-01	RR-01: 1954 ADDITION WEST STAIRWELL.	800 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
I2A	2' x 2' Acoustical Ceiling Tile Gouges & Pin Holes					Total Amount - 500 Sq Ft
	51	GROUND FLOOR HALLWAY 1220 WEST OF CAFETERIA	NONE DETECTED	111108-MA-15	MA-15: ROOM 1111 (SINCE REMOVED).	500 Sq Ft
I2B	2' x 2' Acoustical Ceiling Tile Vinyl-Coated Gypsum					Total Amount - 315 Sq Ft
	42	ROOM 1201A (KITCHEN)	NSM			315 Sq Ft
I2C	2' x 2' Acoustical Ceiling Tile Bumpy w/Nail Holes (20XX)					Total Amount - 2400 Sq Ft
	54	ROOM 1221 (GYMNASIUM)	NEW			2400 Sq Ft
I2D	2' x 2' Acoustical Ceiling Tile Gouges & Pin Holes w/Revealed Edge (2009)					Total Amount - 1400 Sq Ft
	68	1954 ADDITION 1ST FLOOR HALLWAY	NEW			700 Sq Ft
	97	1954 ADDITION 2ND FLOOR HALLWAY	NEW			700 Sq Ft
I3A	2' x 4' Ceiling Tile 2' x 2'-Look Gouges & Pin Holes w/Revealed Edge					Total Amount - 40000 Sq Ft
	1	THROUGHOUT BUILDING	NONE DETECTED	112508-MA-01	HALLWAY OUTSIDE ROOM 1111.	40000 Sq Ft
I3C	2' x 4' Ceiling Tile Gouges & Pin Holes					Total Amount - 725 Sq Ft
	48	GROUND FLOOR HALLWAY 1200 (SOUTH OF CAFETERIA)	NONE DETECTED	111108-MA-26		725 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
K1A	Sheet Vinyl Flooring & Adhesive Tan w/Brown Swirls					Total Amount - 35 Sq Ft
	87	ROOM 2202A	NONE DETECTED	111208-MA-03		35 Sq Ft
K2A	12" x 12" Vinyl Floor Tile & Mastic Beige w/Black Pits					Total Amount - 2530 Sq Ft
	61	1954 ADDITION WEST STAIRWELL	NONE DETECTED			700 Sq Ft
	69	1954 ADDITION 1ST FLOOR HALLWAY	NONE DETECTED			600 Sq Ft
	81	1924 ADDITION 1ST FLOOR HALLWAY	NONE DETECTED	111208-MA-01		630 Sq Ft
	98	1954 ADDITION 2ND FLOOR HALLWAY	NONE DETECTED			600 Sq Ft
K2B	12" x 12" Vinyl Floor Tile & Mastic Gray w/Black Pits					Total Amount - 480 Sq Ft
	62	1954 ADDITION WEST STAIRWELL	2 CH (MASTIC)	111108-MA-08		80 Sq Ft
	70	1954 ADDITION 1ST FLOOR HALLWAY	2 CH (MASTIC)			200 Sq Ft
	99	1954 ADDITION 2ND FLOOR HALLWAY	2 CH (MASTIC)			200 Sq Ft
K2E	12" x 12" Vinyl Floor Tile & Mastic Small Gray Mottle					Total Amount - 700 Sq Ft
	88	1924 ADDITION 2ND FLOOR HALLWAY	NONE DETECTED	112508-MA-07		700 Sq Ft
K2F	12" x 12" Vinyl Floor Tile & Mastic Large Gray & Black Mottle					Total Amount - 1400 Sq Ft
	6	1916 ORIGINAL BUILDING GROUND FLOOR HALLWAY	NONE DETECTED	111108-MA-19	OUTSIDE CUSTODIAL OFFICE.	1000 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	37	1924 ADDITION HALLWAY OUTSIDE 1101	NONE DETECTED	413-7	413-7: BY DRINKING FOUNTAIN.	400 Sq Ft
K2G	12" x 12" Vinyl Floor Tile & Mastic Beige/Tan Mottle					Total Amount - 2400 Sq Ft
	55	ROOM 1221 (GYMNASIUM)	NONE DETECTED	111108-MA-32		2400 Sq Ft
K2H	12" x 12" Vinyl Floor Tile & Mastic Speckled Gray w/Squares					Total Amount - 230 Sq Ft
	80	1ST FLOOR HALLWAY RAMP BETWEEN 1924 & 1954 ADDITIONS	NONE DETECTED	111208-MA-01		230 Sq Ft
K2I	12" x 12" Vinyl Floor Tile & Mastic Gray & White Mottle (2009)					Total Amount - 1320 Sq Ft
	19	1916 ORIGINAL BUILDING STAIRWELLS	NEW			1320 Sq Ft
K3A	Miscellaneous Flooring 2' x 2' Light Gray w/Black & White Specks					Total Amount - 900 Sq Ft
	33	1ST, 2ND & 3RD FLOOR ELEVATOR LANDINGS	NEW			200 Sq Ft
	47	RAMP/HALLWAY SOUTH OF CAFETERIA	NEW			700 Sq Ft
K3B	Miscellaneous Flooring Tan Stair Treads (20XX)					Total Amount - 1000 Sq Ft
	20	1916 ORIGINAL BUILDING STAIRWELLS	NEW			1000 Sq Ft
K3C	Miscellaneous Flooring 2' x 2' Tan w/Gray & White Specks (20XX)					Total Amount - 13685 Sq Ft
	8	MAIN OFFICE COPY ROOM 1125	NEW			100 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	9	ROOM 1111	NEW			400 Sq Ft
	11	ROOM 1109	NEW			400 Sq Ft
	13	ROOM 1105	NEW			400 Sq Ft
	16	ROOM 1103	NEW			350 Sq Ft
	28	ROOM 3105	NEW			625 Sq Ft
	38	ROOM 1101	NEW			850 Sq Ft
	71	ROOM 2218	NEW			950 Sq Ft
	73	ROOM 2217	NEW			950 Sq Ft
	76	ROOM 2216	NEW			950 Sq Ft
	78	ROOM 2215	NEW			950 Sq Ft
	82	ROOM 2214	NEW			1000 Sq Ft
	83	ROOM 2212	NEW			300 Sq Ft
	85	ROOM 2202	NEW			1000 Sq Ft
	94	ROOM 3212	NEW			660 Sq Ft
	100	ROOM 3215	NEW			950 Sq Ft
	103	ROOM 3216	NEW			950 Sq Ft
	106	ROOM 3217	NEW			950 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	108	ROOM 3218	NEW			950 Sq Ft
LOA	Flexible Duct Connector Coarse Brown Fabric					Total Amount - 10 Sq Ft
	41	ROOM 1102 (MECHANICAL)	NONE DETECTED	2001-1501-AM-1	AM-1: FAN ROOM BY OFFICE	10 Sq Ft
M0A	Plaster 1916 Original Building					Total Amount - 53600 Sq Ft
	4	THROUGHOUT 1916 ORIGINAL BUILDING	NONE DETECTED	111108-MA-11, 12, 13, 20, 22; 111208-MA-09, 10; 509A6	MA-11: ROOM 3101 (CEILING). MA-12: ROOM 3102 (CEILING). MA-13: ROOM 2106. MA-20: CUSTODIAL OFFICE WALL. MA-22: ROOM 1101. MA-09: HALLWAY 2100 (CEILING). MA-10: HALLWAY 2100 (WALL).	53600 Sq Ft
M0B	Plaster 1924 Addition					Total Amount - 40600 Sq Ft
	34	THROUGHOUT 1924 ADDITION	NONE DETECTED	111108-MA-23, 24; 111208-MA-02, 04, 05; 509A7; 413-11	MA-23: MECH BY OFFICE (WALL). MA-24: OFFICE CLOSET (WALL). MA-02: ROOM 2210, MA-04: ROOM 3201. MA-05: ROOM 3210. 413-11: CUSTODIAL ROOM WALL HATCH.	40600 Sq Ft
M0C	Plaster 1954 Addition					Total Amount - 50640 Sq Ft
	63	THROUGHOUT 1954 ADDITION	NONE DETECTED	111108-MA-34, 36; 111208-MA-06, 07, 08; 509A8; 413-12	MA-06: ROOM 3215. MA-07: ROOM 3217. MA-08: STAIRWELL 2299A (WEST WALL). MA-34: WEST ENTRANCE OFF GYMNASIUM. MA-36: ROOM 2218. 413-12: ROOM 102 BEHIND LIGHT SWITCH.	50640 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
MOD	Plaster Unknown Installation Date	Total Amount - 250 Sq Ft				
	44	BOILER ROOM (101) WEST END	NONE DETECTED	111108-MA-04, 05, 06		250 Sq Ft
NOA	Drywall/Joint Compound 1997 Installation	Total Amount - 1080 Sq Ft				
	32	THROUGHOUT 1997 ELEVATOR ADDITION	NONE DETECTED	413-16	413-16: UPPER LANDING BEHIND VENT.	1080 Sq Ft
POA	Fire Doors Metal 1 Hr Rating -Curries	Total Amount - 20 Sq Ft				
	46	BOILER ROOM (101) WEST END	ASSUMED			20 Sq Ft
Q0A	Carpet Adhesive Blue Carpet Squares (20XX)	Total Amount - 1760 Sq Ft				
	12	IMC 1106	NEW			1100 Sq Ft
	95	ROOM 3214	NEW			660 Sq Ft
Q0B	Carpet Adhesive Blue/Green Carpet	Total Amount - 1500 Sq Ft				
	7	MAIN OFFICE AREA	NEW			1500 Sq Ft
ROA	Baseboard/Mopboard Adhesive 4" Black Baseboard	Total Amount - 500 Sq Ft				
	2	THROUGHOUT BUILDING	NEW			500 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
S0A	Wood Floor Felt / Vapor Barrier 1916 Original Building (Elevated)					Total Amount - 8600 Sq Ft
	18	THROUGHOUT 1916 ORIGINAL BUILDING 1ST & 2ND FLOOR CLASSROOMS	NSM			8600 Sq Ft
S0B	Wood Floor Felt / Vapor Barrier 1924 Addition (Elevated)					Total Amount - 1160 Sq Ft
	86	ROOM 2203	NONE DETECTED	110811-BF-1	BF-1: ROOM 3212.	80 Sq Ft
	89	ROOM 3201	NONE DETECTED			240 Sq Ft
	90	ROOM 3202	NONE DETECTED			660 Sq Ft
	91	ROOM 3202A	NONE DETECTED			120 Sq Ft
	92	ROOM 3204	NONE DETECTED			60 Sq Ft
S0C	Wood Floor Felt / Vapor Barrier 1954 Addition (Elevated)					Total Amount - 900 Sq Ft
	57	ROOM 1225 (STAGE)	ASSUMED			900 Sq Ft
S0E	Wood Floor Felt / Vapor Barrier 1924 Addition (On-Grade)					Total Amount - 25 Sq Ft
	40	ROOM 1101A STORAGE	ASSUMED			25 Sq Ft
T0A	Light Cord Insulation Fuzzy White					Total Amount - 51 Lin Ft
	56	ROOM 1221 (GYMNASIUM)	ASSUMED			51 Lin Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
VOA	Sink Undercoating Gray					Total Amount - 66 Sq Ft
	23	ROOM 2101	NONE DETECTED			6 Sq Ft
	27	ROOM 2107	NONE DETECTED			6 Sq Ft
	29	ROOM 3105	NONE DETECTED	111108-MA-09		6 Sq Ft
	72	ROOM 2218	NONE DETECTED			6 Sq Ft
	74	ROOM 2217	NONE DETECTED			6 Sq Ft
	77	ROOM 2216	NONE DETECTED			6 Sq Ft
	79	ROOM 2215	NONE DETECTED			6 Sq Ft
	101	ROOM 3215	NONE DETECTED			6 Sq Ft
	104	ROOM 3216	NONE DETECTED			6 Sq Ft
	107	ROOM 3217	NONE DETECTED			6 Sq Ft
	109	ROOM 3218	NONE DETECTED			6 Sq Ft
VOB	Sink Undercoating Light Gray					Total Amount - 25 Sq Ft
	10	ROOM 1111	NEW			5 Sq Ft
	15	ROOM 1105	NEW			10 Sq Ft
	31	ROOM 3101	NEW			10 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
W1A	1' x 1' Ceiling Tile Adhesive Associated w/I1A					Total Amount - 200 Sq Ft
	59	1954 ADDITION WEST STAIRWELL	NONE DETECTED	071718RR-02	RR-02: 1954 ADDITION WEST STAIRWELL.	200 Sq Ft
W1D	1' x 1' Ceiling Tile Adhesive Associated w/I1D (Brown)					Total Amount - 35 Sq Ft
	52	MEN'S & WOMEN'S RESTROOMS BY GYMNASIUM	NONE DETECTED	111108-MA-28		35 Sq Ft
X0C	Miscellaneous Material Wood Frame Tackboard Adhesive (1916)					Total Amount - 102 Sq Ft
	14	ROOM 1105	NONE DETECTED	092712MV-02	MV-02: ROOM 2102.	24 Sq Ft
	17	ROOM 1103	NONE DETECTED			24 Sq Ft
	22	HALLWAY ACROSS FROM ROOM 2102	NONE DETECTED	070213BF-2		24 Sq Ft
	24	OUTSIDE ROOM 2103	NONE DETECTED	070213BF-1		6 Sq Ft
	30	2ND FLOOR STAIRWELL LANDING	NONE DETECTED			24 Sq Ft
X0E	Miscellaneous Material Tan Stone Panel Adhesive (1916)					Total Amount - 1000 Sq Ft
	21	1916 ORIGINAL BUILDING 2ND FLOOR HALLWAY	ASSUMED			1000 Sq Ft
X0H	Miscellaneous Material Brown Interior/Exterior Window/Door Caulk					Total Amount - 300 Sq Ft
	3	THROUGHOUT BUILDING	3 CH	092712MV-09, 10, 11; 111108-MA-30		300 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
XOI	Miscellaneous Material Interior Light Gray Door/Window Frame Caulk					Total Amount - 1 Sq Ft
49	SOUTH ENTRANCE BY CAFETERIA	4 CH	111108-MA-31			1 Sq Ft
XOK	Miscellaneous Material Tackboard Adhesive (1954)					Total Amount - 660 Sq Ft
64	THROUGHOUT 1954 ADDITION	NONE DETECTED	092712MV-07	MV-07:		640 Sq Ft
75	ROOM 2217	NONE DETECTED				5 Sq Ft
102	ROOM 3215	NONE DETECTED				5 Sq Ft
105	ROOM 3216	NONE DETECTED				5 Sq Ft
110	ROOM 3218	NONE DETECTED				5 Sq Ft
XOL	Miscellaneous Material Slate Chalkboard Adhesive (1924)					Total Amount - 120 Sq Ft
35	THROUGHOUT 1924 ADDITION	NONE DETECTED	092712MV-03	MV-03:		120 Sq Ft
XOM	Miscellaneous Material Tackboard Adhesive (1924)					Total Amount - 24 Sq Ft
39	ROOM 1101	3 CH (BEHIND GYPSUM)	092712MV-04, 05	MV-04,05:		24 Sq Ft
XOO	Miscellaneous Material Black Wall Dampproofing					Total Amount - 1000 Sq Ft
36	THROUGHOUT 1924 ADDITION	NONE DETECTED	121912BF-01			1000 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
X0P		Miscellaneous Material Gray Exterior Window Caulk				Total Amount - 50 Sq Ft
	5	THROUGHOUT 1916 ORIGINAL BUILDING	NONE DETECTED	092712MV-08	MV-08:	50 Sq Ft
X0Q		Miscellaneous Material Light Weight Concrete Ceiling Deck				Total Amount - 5000 Sq Ft
	96	THROUGHOUT 1954 ADDITION 2ND FLOOR CEILING DECK	NONE DETECTED	062719-BF-1	BF-1: HALLWAY NEAR ROOM 3217.	5000 Sq Ft
X1A		Miscellaneous Material Gray Rectangle Pattern Ceramic Floor Tile System				Total Amount - 100 Sq Ft
	25	ROOM 2103 RESTROOM	ASSUMED			50 Sq Ft
	26	ROOM 2105 RESTROOM	ASSUMED			50 Sq Ft
X1B		Miscellaneous Material Maroon Quarry Tile (20XX)				Total Amount - 1335 Sq Ft
	43	ROOM 1201A (KITCHEN)	NEW			315 Sq Ft
	50	SOUTH ENTRANCE & HALLWAY 1220	NEW			900 Sq Ft
	60	1954 ADDITION STAIRWELL LOWER LANDING	NEW			120 Sq Ft
X1C		Miscellaneous Material Orange Quarry Tile				Total Amount - 140 Sq Ft
	53	MEN'S & WOMEN'S RESTROOMS BY GYMNASIUM	ASSUMED			140 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
X1D		Miscellaneous Material 2" Brown Ceramic Floor Tile System				Total Amount - 460 Sq Ft
	84	2ND FLOOR BOYS' & GIRLS' RESTROOMS	NEW			460 Sq Ft
X1E		Miscellaneous Material 2" Gray Ceramic Floor Tile System				Total Amount - 460 Sq Ft
	93	3RD FLOOR BOYS' & GIRLS' RESTROOMS	NEW			460 Sq Ft