Chart C - All Materials List

The following list contains all events observed by the inspector, whether or not they actually contained asbestos, and are grouped by homogeneous area (material type).

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
A2A	Mudded Pipe Joints on Millboard Insulation 1958 Original Building					**Total Amount - 12 Joints**
	30	ROOM 1407	ASSUMED			2 Joints
	34	ROOM 1406	ASSUMED			2 Joints
	38	ROOM 1405	ASSUMED			2 Joints
	42	ROOM 1404	ASSUMED			2 Joints
	46	ROOM 1403	ASSUMED			2 Joints
	51	ROOM 1402	ASSUMED			2 Joints
A3A	Mudded Pipe Joints on Pre-formed Insulation 1958 Original Building					**Total Amount - 2 Joints**
	58	BOYS' RESTROOM 1402B	70 AM	328A2A		2 Joints
A4A	Mudded Pipe Joints on Fiberglass Insulation 1958 Original Building					**Total Amount - 2 Joints**
	67	RESTROOM 1307B	NONE DETECTED	121709ML-17		2 Joints

© 2024 Institute for Environmental Assessment, Inc. All Rights Reserved.

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
B2A	Millboard Pipe Insulation 1958 Original Building					**Total Amount - 106 Lin Ft**
	29	ROOM 1407	5 CH, 10 AM, 10 CR	2001-01146-3	BOILER ROOM (WHITE OUTER LAYER)	16 Lin Ft
	33	ROOM 1406	5 CH, 10 AM, 10 CR			16 Lin Ft
	37	ROOM 1405	5 CH, 10 AM, 10 CR			16 Lin Ft
	41	ROOM 1404	5 CH, 10 AM, 10 CR			16 Lin Ft
	45	ROOM 1403	5 CH, 10 AM, 10 CR			16 Lin Ft
	50	ROOM 1402	5 CH, 10 AM, 10 CR			16 Lin Ft
	60	GIRLS' RESTROOM 1402A	5 CH, 10 AM, 10 CR			10 Lin Ft
B3A	Pre-Formed Pipe Insulation 1958 Original Building					**Total Amount - 15 Lin Ft**
	49	ROOM 1402	20 CH, 30 AM			8 Lin Ft
	54	HALLWAY OUTSIDE ROOM 1402	20 CH, 30 AM	328A7A		1 Lin Ft
	57	BOYS' RESTROOM 1402B	20 CH, 30 AM			6 Lin Ft
D1A	Boiler Gaskets Burner Gasket (1992)					**Total Amount - 2 Sq Ft**
	87	BOILER ROOM 2201	NONE DETECTED	121709ML-11		2 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
D2A	Interior Boiler Insulation Interior Refractory (1992)					**Total Amount - 30 Sq Ft**
	88	BOILER ROOM 2201	ASSUMED			30 Sq Ft
I2A	2' x 2' Acoustical Ceiling Tile Scattered Small Holes					**Total Amount - 20000 Sq Ft**
	2	THROUGHOUT BUILDING	NONE DETECTED	2001-1501-NOK-5	NOK-5: END OF HALLWAY.	20000 Sq Ft
I2C	2' x 2' Acoustical Ceiling Tile Chicken Scratch					**Total Amount - 7500 Sq Ft**
	28	ROOMS 1305, 1307 & 1401-1407	NONE DETECTED	121709ML-09	ML-09: ROOM 1407.	7500 Sq Ft
I2D	2' x 2' Acoustical Ceiling Tile Fissures w/Revealed Edge					**Total Amount - 1200 Sq Ft**
	27	1958 ORIGINAL BUILDING HALLWAY 1400 FROM ROOMS 1401-1407	NONE DETECTED	121709ML-08	ML-08: OUTSIDE ROOM 1405.	1200 Sq Ft
I2E	2' x 2' Acoustical Ceiling Tile Small Pock Marks & Pin Holes (2011)					**Total Amount - 270 Sq Ft**
	19	OFFICE RECEPTION	NEW			270 Sq Ft
I2F	2' x 2' Acoustical Ceiling Tile Vinyl-Coated Gypsum (2015)					**Total Amount - 700 Sq Ft**
	14	KITCHEN AREAS 1101-1104	NEW			700 Sq Ft
I2G	2' x 2' Acoustical Ceiling Tile Textured w/Pinholes					**Total Amount - 225 Sq Ft**
	79	STORAGE ROOM 1302	NONE DETECTED	021122SW-05	SW-05: STORAGE ROOM 1302.	225 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
K2A	12" x 12" Vinyl Floor Tile & Mastic White w/Multi-Colored Smudges (1992)					**Total Amount - 5625 Sq Ft**
	18	CAFETERIA/GYMNASIUM 1111/1113	NONE DETECTED	121709ML-02	ML-02: STORAGE ROOM 1114.	4800 Sq Ft
	23	ROOM 1006 WORK ROOM	NONE DETECTED			160 Sq Ft
	25	ROOM 1008 LOUNGE	NONE DETECTED			170 Sq Ft
	77	STORAGE ROOM 1305B	NONE DETECTED			25 Sq Ft
	78	STORAGE ROOM 1304	NONE DETECTED			120 Sq Ft
	81	ROOM 1301A	NONE DETECTED			350 Sq Ft
K3A	Miscellaneous Flooring 2' x 2' Multi-Colored Floor Tile (201X)					**Total Amount - 20000 Sq Ft**
	3	THROUGHOUT BUILDING	NEW			20000 Sq Ft
L0A	Flexible Duct Connector Black					**Total Amount - 5 Sq Ft**
	90	BOILER ROOM 2201	NSM			5 Sq Ft
M0A	Plaster 1958 Original Building					**Total Amount - 800 Sq Ft**
	55	RESTROOMS 1402A & 1402B	NONE DETECTED			200 Sq Ft
	64	ROOM 1307	NONE DETECTED	121709ML-15, 16		300 Sq Ft
	70	ROOM 1305	NONE DETECTED	121709ML-14		300 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
N0A	Drywall/Joint Compound					**Total Amount - 10000 Sq Ft**
	1	THROUGHOUT BUILDING	NONE DETECTED	511-H3		10000 Sq Ft
P0A	Fire Doors Wood - 1 Hr Rating (Warnock Hersey)					**Total Amount - 200 Sq Ft**
	10	THROUGHOUT BUILDING	NEW			200 Sq Ft
Q0B	Carpet Adhesive Multi-Colored Berber Carpet					**Total Amount - 5000 Sq Ft**
	12	THROUGHOUT 1958 ORIGINAL BUILDING	NONE DETECTED	121709ML-06	ML-06: MAIN OFFICE.	5000 Sq Ft
Q0C	Carpet Adhesive Carpet Squares (2012)					**Total Amount - 10000 Sq Ft**
	4	THROUGHOUT BUILDING	NEW			10000 Sq Ft
R0A	Baseboard/Mopboard Adhesive Blue Baseboard					**Total Amount - 100 Sq Ft**
	13	THROUGHOUT 1958 ORIGINAL BUILDING	NONE DETECTED	2001-1901-XX-11B	XX-11B: GYMNASIUM.	100 Sq Ft
R0B	Baseboard/Mopboard Adhesive 4" Dark Gray Baseboard (2012)					**Total Amount - 500 Sq Ft**
	5	THROUGHOUT BUILDING	NEW			500 Sq Ft
R0C	Baseboard/Mopboard Adhesive 4" Dark Brown Baseboard					**Total Amount - 500 Sq Ft**
	6	THROUGHOUT BUILDING	NEW			500 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
V0A	Sink Undercoating Gray					**Total Amount - 43 Sq Ft**
	11	THROUGHOUT BUILDING	NONE DETECTED	121709ML-07	ML-07: TEACHERS' LOUNGE.	30 Sq Ft
	20	NURSE'S OFFICE	NONE DETECTED			5 Sq Ft
	26	ROOM 1008 LOUNGE	NONE DETECTED			5 Sq Ft
	82	ROOM 1301A	NONE DETECTED			3 Sq Ft
X0A	Miscellaneous Material Red Fire Stop					**Total Amount - 200 Sq Ft**
	7	THROUGHOUT BUILDING	NONE DETECTED	121709ML-03	ML-03: BOILER ROOM.	200 Sq Ft
X0B	Miscellaneous Material Wired Window Glaze (1992)					**Total Amount - 100 Sq Ft**
	8	THROUGHOUT BUILDING	NONE DETECTED	121709ML-05	ML-05: ROOM 1407.	100 Sq Ft
X0C	Miscellaneous Material Wood Frame Chalkboard Adhesive					**Total Amount - 140 Sq Ft**
	31	ROOM 1407	ASSUMED			20 Sq Ft
	35	ROOM 1406	ASSUMED			20 Sq Ft
	39	ROOM 1405	ASSUMED			20 Sq Ft
	43	ROOM 1404	ASSUMED			20 Sq Ft
	47	ROOM 1403	ASSUMED			20 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	52	ROOM 1402	ASSUMED			20 Sq Ft
	65	ROOM 1307	ASSUMED			10 Sq Ft
	71	ROOM 1305	ASSUMED			10 Sq Ft
X0D	Miscellaneous Material Wood Frame Corkboard Adhesive					**Total Amount - 1040 Sq Ft**
	32	ROOM 1407	ASSUMED			130 Sq Ft
	36	ROOM 1406	ASSUMED			130 Sq Ft
	40	ROOM 1405	ASSUMED			130 Sq Ft
	44	ROOM 1404	ASSUMED			130 Sq Ft
	48	ROOM 1403	ASSUMED			130 Sq Ft
	53	ROOM 1402	ASSUMED			130 Sq Ft
	66	ROOM 1307	ASSUMED			130 Sq Ft
	72	ROOM 1305	ASSUMED			130 Sq Ft
X0E	Miscellaneous Material Tectum					**Total Amount - 1600 Sq Ft**
	17	CAFETERIA/GYMNASIUM 1111/1113	NONE DETECTED	121709ML-10	ML-10: GYMNASIUM.	1600 Sq Ft
X0F	Miscellaneous Material Gray Duct Seam Cement					**Total Amount - 5 Sq Ft**
	89	BOILER ROOM 2201	NONE DETECTED	121709ML-01	ML-01: BOILER ROOM.	5 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
X0G	Miscellaneous Material Milkboard Adhesive					**Total Amount - 300 Sq Ft**
	15	KITCHEN AREAS 1101-1104	NONE DETECTED	121709ML-12	ML-12: KITCHEN.	300 Sq Ft
X0H	Miscellaneous Material Tan Fire Stop					**Total Amount - 30 Sq Ft**
	9	THROUGHOUT BUILDING	NONE DETECTED	121709ML-13	ML-13: ROOM 1305.	30 Sq Ft
X0I	Miscellaneous Material Wood Frame Chalkboard Adhesive (1991)					**Total Amount - 510 Sq Ft**
	75	ROOM 1303	NEW			10 Sq Ft
	86	ROOMS 1202-1205 AND 1207	NEW			500 Sq Ft
X0J	Miscellaneous Material Wood Frame Corkboard Adhesive (1991)					**Total Amount - 630 Sq Ft**
	76	ROOM 1303	NEW			130 Sq Ft
	94	SECOND FLOOR ROOMS 2203-2208	NEW			500 Sq Ft
X1A	Miscellaneous Material 6" X 6" Quarry Tile System (200x)					**Total Amount - 925 Sq Ft**
	16	KITCHEN AREAS 1101-1104	NEW			700 Sq Ft
	80	STORAGE ROOM 1302	NEW			225 Sq Ft
X1B	Miscellaneous Material 1" X 1" Green Ceramic Floor Tile System					**Total Amount - 120 Sq Ft**
	59	BOYS' RESTROOM 1402B	ASSUMED			120 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
X1C	Miscellaneous Material 4" X 4" Green/Yellow Ceramic Wall Tile System					**Total Amount - 480 Sq Ft**
	56	RESTROOMS 1402A & 1402B	ASSUMED			400 Sq Ft
	68	RESTROOM 1307B	ASSUMED			40 Sq Ft
	73	RESTROOM 1305A	ASSUMED			40 Sq Ft
X1D	Miscellaneous Material Multi-Sized Ceramic Floor Tile System					**Total Amount - 200 Sq Ft**
	61	GIRLS' RESTROOM 1402A	ASSUMED			120 Sq Ft
	69	RESTROOM 1307B	ASSUMED			40 Sq Ft
	74	RESTROOM 1305A	ASSUMED			40 Sq Ft
X1E	Miscellaneous Material 2" X 2" Gray Ceramic Floor Tile System					**Total Amount - 1020 Sq Ft**
	21	NURSE'S OFFICE RESTROOM	NEW			50 Sq Ft
	24	ROOM 1006 WORK ROOM RESTROOM	NEW			75 Sq Ft
	83	RESTROOM 1208	NEW			45 Sq Ft
	84	RESTROOMS 1202A AND 1202B	NEW			400 Sq Ft
	91	RESTROOMS 2202A AND 2202B	NEW			400 Sq Ft
	93	RESTROOM 2208A	NEW			50 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
X1F	Miscellaneous Material 4" X 4" White Ceramic Wall Tile System					**Total Amount - 850 Sq Ft**
	22	NURSE'S OFFICE RESTROOM	NEW			50 Sq Ft
	85	RESTROOMS 1202A AND 1202B	NEW			600 Sq Ft
	92	RESTROOMS 2202A AND 2202B	NEW			200 Sq Ft
X1G	Miscellaneous Material 6" X 6" Sage Ceramic Wall Tile System					**Total Amount - 80 Sq Ft**
	62	HANDWASH AREA OUTSIDE RESTROOMS 1402A/B	ASSUMED			80 Sq Ft
X1H	Miscellaneous Material 6" X 6" Beige Ceramic Wall Tile System					**Total Amount - 80 Sq Ft**
	63	HANDWASH AREA OUTSIDE RESTROOMS 1402A/B	ASSUMED			80 Sq Ft