

2180 Knapp Street, Saint Paul, MN 55108

Chart C - All Materials List

The following list contains all events observed by the inspector, whether or not they actually contained asbestos, and are grouped by homogeneous area (material type).

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
A4A	Mudded Pipe Joints on Fiberglass Insulation Unknown Installation Date					Total Amount - 2 Joints
	30	1953 ORIGINAL BUILDING TUNNEL	NONE DETECTED	557-JJT-10, 11, 12, 13, 14; 557-JJT-23	JJT-10: ROOM 1216 MIDDLE ELBOWS EAST (SINCE REMOVED). JJT-11: ROOM 1216 MIDDLE ELBOWS WEST(SINCE REMOVED). JJT-12,13: ROOM 1216 SOUTHEAST CORNER ABOVE DOOR (SINCE REMOVED). JJT-23: WEST TUNNEL WEST VALVE.	2 Joints
I2C	2' x 2' Acoustical Ceiling Tile Smooth w/Revealed Edge (2015)					Total Amount - 1920 Sq Ft
	24	1953 ORIGINAL BUILDING MULTI-PURPOSE ROOM 1101	NEW			1920 Sq Ft
I2D	2' x 2' Acoustical Ceiling Tile Dents w/Pin Holes (2017)					Total Amount - 1000 Sq Ft
	38	ROOM 1302	NEW			1000 Sq Ft
I2F	2' x 2' Acoustical Ceiling Tile Dents w/Pin Holes (2018)					Total Amount - 75000 Sq Ft
	2	THROUGHOUT BUILDING	NEW			75000 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
I2G	2' x 2' Acoustical Ceiling Tile Light Texture w/Revealed Edge (2018)					Total Amount - 28000 Sq Ft
	3	THROUGHOUT BUILDING	NEW			28000 Sq Ft
I2H	2' x 2' Acoustical Ceiling Tile Smooth Texture (2018)					Total Amount - 5500 Sq Ft
	13	MEDIA CENTER	NEW			3000 Sq Ft
	28	ROOM 1103 KITCHEN	NEW			2500 Sq Ft
K2F	12" x 12" Vinyl Floor Tile & Mastic Blue Mottle					Total Amount - 50 Sq Ft
	18	MAINTENANCE CLOSET (1202)	NONE DETECTED	102210-JC-10	JC-10: ROOM 1123 (STAFF WORK ROOM) (SINCE REMOVED).	50 Sq Ft
K2G	12" x 12" Vinyl Floor Tile & Mastic Beige/Tan Mottle					Total Amount - 60 Sq Ft
	21	1953 ORIGINAL BUILDING MULTI-PURPOSE ROOM STAGE 1101A	NONE DETECTED	102210-JC-09	JC-09: 1953 ORIGINAL BUILDING MULTI-PURPOSE ROOM 1101 (SINCE REMOVED).	60 Sq Ft
K3C	Miscellaneous Flooring Gray Stair Treads (20XX)					Total Amount - 240 Sq Ft
	17	THROUGHOUT ORIGINAL BUILDING STAIRWELLS	NEW			240 Sq Ft
K3D	Miscellaneous Flooring 2' x 2' Gray w/Pink & White Flecks					Total Amount - 40000 Sq Ft
	4	THROUGHOUT BUILDING	NEW			40000 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
K3E	Miscellaneous Flooring Black Flooring Mastic	Total Amount - 50 Sq Ft				
	16	1953 ORIGINAL ROOM 2208 CLOSET	ASSUMED			40 Sq Ft
	19	MAINTENANCE CLOSET (1210)	ASSUMED			10 Sq Ft
L0A	Flexible Duct Connector Black Vinyl (20xx)	Total Amount - 25 Sq Ft				
	34	ROOM 1113, UPPER MECHANICAL	NEW			25 Sq Ft
M0A	Plaster 1953 Original Building	Total Amount - 5000 Sq Ft				
	14	THROUGHOUT 1953 ORIGINAL BUILDING	NONE DETECTED	100410-ML-14, 20, 21; 557-JJT-1, 2, 3, 4, 24; ACB450I-B5, B6, B7, B8, B9	ML-14: OUTSIDE ROOM 1216. ML-20: ROOM 2214. ML-21: HALLWAY OUTSIDE ROOM 2207. JJT-1: ROOM 2207 BELOW MIDDLE WINDOW BELOW RADIATOR. JJT-2: ROOM 2202 PIPE CHASE NORTH WALL. JJT- 3: ROOM 2202 PIPE CHASE SOUTH WALL. JJT-24: ROOM 1121 ABOVE LOUDSPEAKER.	5000 Sq Ft
M0C	Plaster 1974 Addition	Total Amount - 180 Sq Ft				
	31	1974 ADDITION GYMNASIUM (1109)	NONE DETECTED	102210-JC-06; 100410- ML-04; 2001-1501-F-6; 100410-ML-06	JC-06: 1974 ADDITION LOADING DOCK STORAGE (1104B) (SINCE REMOVED). ML- 04: BOILER ROOM (SINCE REMOVED). ML-06: ROOM 1111 (SINCE REMOVED).	120 Sq Ft
	46	1974 ADDITION ROOM 1407 (ELEVATOR EQUIPMENT)	NONE DETECTED	051717-BF-31; 100410- ML-11	ML-11: ROOM 1401 (LIBRARY) ELECTRICAL CLOSET (SINCE REMOVED). BF-31: ROOM 1401 (LIBRARY) (SINCE REMOVED).	60 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
NOC	Drywall/Joint Compound 1974 Addition		Total Amount - 3650 Sq Ft			
	39	ROOM 1303	NONE DETECTED			700 Sq Ft
	41	ROOM 1304	NONE DETECTED			700 Sq Ft
	42	ROOM 1305	NONE DETECTED			450 Sq Ft
	43	ROOM 1306	NONE DETECTED	557-JJT-38	JJT-38: ROOM 115 BEHIND BASEBOARD BELOW PHONE (SINCE REMOVED).	600 Sq Ft
	44	1974 ADDITION HALLWAY 1400 OUTSIDE ROOMS 1301-1306	NONE DETECTED	4501-B3	B3: ROOM 1041 (LIBRARY) (SINCE REMOVED).	1200 Sq Ft
N0CC	Drywall/Joint Compound Vinyl-Coated (1974)		Total Amount - 1200 Sq Ft			
	40	ROOM 1307	NONE DETECTED			500 Sq Ft
	45	1974 ADDITION HALLWAY 1400 OUTSIDE ROOMS 1301-1306	NONE DETECTED	557-JJT-37	JJT-37: ROOM 1403 IN NORTHEAST CORNER (SINCE REMOVED).	700 Sq Ft
N0F	Drywall/Joint Compound 2018 Installation		Total Amount - 10000 Sq Ft			
	1	THROUGHOUT BUILDING	NEW			10000 Sq Ft
P0C	Fire Doors Steel (Cecodoor) -1.5 Hour Rating (2017)		Total Amount - 260 Sq Ft			
	10	THROUGHOUT BUILDING	NEW			260 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
P0D	Fire Doors Wood Door (Vt Industries) -1 Hour Rating (2017)					Total Amount - 160 Sq Ft
	11	THROUGHOUT BUILDING	NEW			160 Sq Ft
Q0S	Carpet Adhesive Striped Carpet Squares (2018)					Total Amount - 20000 Sq Ft
	5	THROUGHOUT BUILDING	NEW			20000 Sq Ft
R0F	Baseboard/Mopboard Adhesive 4" Gray (2018)					Total Amount - 1000 Sq Ft
	6	THROUGHOUT BUILDING	NEW			1000 Sq Ft
SOA	Wood Floor Felt / Vapor Barrier Elevated (1953)					Total Amount - 700 Sq Ft
	22	1953 ORIGINAL BUILDING MULTI-PURPOSE STAGE 1101A	ASSUMED			700 Sq Ft
T0A	Light Cord Insulation Large White Cords					Total Amount - 40 Lin Ft
	25	1953 ORIGINAL BUILDING MULTI-PURPOSE ROOM 1101	ASSUMED			40 Lin Ft
T0B	Light Cord Insulation Small White Cords					Total Amount - 10 Lin Ft
	23	1953 ORIGINAL BUILDING MULTI-PURPOSE ROOM STAGE 1101A	ASSUMED			10 Lin Ft
X0C	Miscellaneous Material Foam Glass Adhesive					Total Amount - 600 Sq Ft
	35	1974 ADDITION TUNNEL	NONE DETECTED	100410-ML-05	ML-05: 1974 ADDITION TUNNEL	600 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
X0L	Miscellaneous Material Gray Caulking					Total Amount - 50 Sq Ft
	12	THROUGHOUT BUILDING	ASSUMED			50 Sq Ft
X0N	Miscellaneous Material Black Exterior Water Proofing					Total Amount - 100 Sq Ft
	26	SECOND FLOOR AHU ABOVE STAGE ROOM 1101C	ASSUMED			100 Sq Ft
X1G	Miscellaneous Material Multi-Sized Brown & White Ceramic Floor Tile System					Total Amount - 695 Sq Ft
	32	1974 ADDITION GYMNASIUM STORAGE (1111)	NONE DETECTED	060518ML-05	ML-05: KITCHEN RESTROOM 1106A (SINCE REMOVED).	230 Sq Ft
	33	1974 ADDITION GYMNASIUM STORAGE (1112)	NONE DETECTED			225 Sq Ft
	36	1974 ADDITION RESTROOM 1114A	NONE DETECTED			120 Sq Ft
	37	1974 ADDITION RESTROOM 1114B	NONE DETECTED			120 Sq Ft
X1H	Miscellaneous Material 1' X 2' Gray Marble Look Quarry Floor Tile System (2018)					Total Amount - 5000 Sq Ft
	7	THROUGHOUT BUILDING	NEW			5000 Sq Ft
X1I	Miscellaneous Material 6" X 12" White Ceramic Wall Tile System (2018)					Total Amount - 10000 Sq Ft
	8	THROUGHOUT BUILDING	NEW			10000 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
X1J	Miscellaneous Material 6" X 6" Ceramic Wall Tile System (2018)					Total Amount - 1800 Sq Ft
9	THROUGHOUT BUILDING	NEW				1800 Sq Ft
X1O	Miscellaneous Material Glazed Block Wall & Grout (1953)					Total Amount - 10000 Sq Ft
15	THROUGHOUT 1953 ORIGINAL BUILDING	NONE DETECTEC	060518ML-04	ML-04: CUSTODIAL 1201.		10000 Sq Ft
X1P	Miscellaneous Material 6" Quarry Tile System (2017)					Total Amount - 2500 Sq Ft
29	ROOM 1103 KITCHEN	NEW				2500 Sq Ft
X1Q	Miscellaneous Material 2" X 2" Cream Ceramic Floor Tile System					Total Amount - 10 Sq Ft
20	MAINTENANCE CLOSET (1104)	ASSUMED				10 Sq Ft
Y0A	Miscellaneous Material Gray Flashing Caulk					Total Amount - 5 Sq Ft
27	SECOND FLOOR AHU ABOVE STAGE.	ASSUMED				5 Sq Ft