

160 East Isabel Street, Saint Paul, MN 55107

Chart C - All Materials List

The following list contains all events observed by the inspector, whether or not they actually contained asbestos, and are grouped by homogeneous area (material type).

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
B1A	Air Cell Pipe Insulation 1923 Original Building					Total Amount - 75 Lin Ft
	23	ORIGINAL BUILDING TUNNELS	ASSUMED			75 Lin Ft
B2A	Millboard Pipe Insulation 1923 Original Building					Total Amount - 150 Lin Ft
	24	ORIGINAL BUILDING TUNNELS	ASSUMED			150 Lin Ft
D1A	Boiler Gaskets Access Panel Gaskets					Total Amount - 5 Sq Ft
	18	BOILER ROOM (0112)	NONE DETECTED	092712MV-24	MV-24: BOILER ROOM (0112).	5 Sq Ft
D2A	Interior Boiler Insulation White Mineral Wool & Sealant					Total Amount - 200 Sq Ft
	19	BOILER ROOM (0112)	NONE DETECTED	092712MV-25	MV-25: BOILER ROOM (0112).	200 Sq Ft
D2B	Interior Boiler Insulation Gray Mineral Wood Behind White Layer					Total Amount - 100 Sq Ft
	20	BOILER ROOM (0112)	NONE DETECTED	092712MV-26	MV-26: BOILER ROOM (0112).	100 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
I1A	1' x 1' Acoustical Ceiling Tile Pegboard	Total Amount - 1700 Sq Ft				
	103	ROOMS 3109 & 3111	NONE DETECTED	510-T-4-P		1700 Sq Ft
I2B	2' x 2' Acoustical Ceiling Tile Light Texture w/Revealed Edge (2013)	Total Amount - 2400 Sq Ft				
	50	THROUGHOUT MAIN OFFICE AREAS	NEW			1000 Sq Ft
	89	ROOM 2111 (IMC)	NEW			1400 Sq Ft
I2C	2' x 2' Acoustical Ceiling Tile Vinyl Coated Gypsum (201x)	Total Amount - 820 Sq Ft				
	48	ROOM 1101 (KITCHEN STORAGE)	NEW			200 Sq Ft
	61	ROOM 1108 (KITCHEN)	NEW			420 Sq Ft
	64	ROOM 1106 (DISH ROOM)	NEW			200 Sq Ft
I3B	2' x 4' Ceiling Tile 2' x 2'-Look w/ Gouges & Pin Holes	Total Amount - 600 Sq Ft				
	54	ROOMS 1003-1005	NONE DETECTED	032309ML-19		600 Sq Ft
I4A	Acoustical Ceiling Tile 4' X 8' Tectum Panel (1997)	Total Amount - 2560 Sq Ft				
	107	1997 ROOM 3114 GYMNASIUM	NEW			2560 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
K0E	9" x 9" Vinyl Floor Tile & Mastic Light Gray w/Dark Gray & White Streaks					Total Amount - 1950 Sq Ft
	56	AREA UNDER MAIN OFFICE	5-8 CH (TILE), 10 CH (MASTIC)	032309ML-18; 2001-1901-XX-20B	ML-18: ROOM 1007 (SINCE REMOVED). 20B: FORMER CUSTODIAL OFFICE.	1950 Sq Ft
K2D	12" x 12" Vinyl Floor Tile & Mastic Tan w/Brown & Beige Flecks (1997)					Total Amount - 200 Sq Ft
	106	1997 ELEVATOR ADDITION	NONE DETECTED	032309ML-26		200 Sq Ft
K2G	12" x 12" Vinyl Floor Tile & Mastic 2' x 2' Green w/Multi-Colored Specks					Total Amount - 180 Sq Ft
	102	ROOM 3119	NEW			180 Sq Ft
K2H	12" x 12" Vinyl Floor Tile & Mastic Gray Mottle					Total Amount - 5108 Sq Ft
	30	ROOM 1201	NONE DETECTED			720 Sq Ft
	32	ROOM 1202	NONE DETECTED			1104 Sq Ft
	34	ROOM 1204	NONE DETECTED	032309ML-23	ROOM 1205 (SINCE REMOVED).	864 Sq Ft
	41	ROOM 1206	NONE DETECTED			960 Sq Ft
	43	ROOM 1207	NONE DETECTED			960 Sq Ft
	73	ROOM 1302	NONE DETECTED			250 Sq Ft
	94	ROOM 2205	NONE DETECTED			250 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
K2I	12" x 12" Vinyl Floor Tile & Mastic Light Gray w/Dark Gray & White Streaks					Total Amount - 2 Sq Ft
	55	ROOM 1007	ASSUMED			2 Sq Ft
K3C	Miscellaneous Flooring Tan Stair Treads					Total Amount - 50 Sq Ft
	60	STAGE (1112)	NONE DETECTED	2001-1501-I-9	EAST STAIRS, TOP SOUTH CORNER	50 Sq Ft
K3D	Miscellaneous Flooring 2' x 2' Tan w/Multi-Colored Specks (2013)					Total Amount - 7203 Sq Ft
	29	1ST FLOOR HALLWAY (1100, 1200, 1300)	NEW			1955 Sq Ft
	36	ROOM 1205	NEW			288 Sq Ft
	69	ROOM 1301	NEW			250 Sq Ft
	75	ROOM 1304	NEW			250 Sq Ft
	79	ROOM 1306	NEW			300 Sq Ft
	82	ROOM 1308	NEW			250 Sq Ft
	88	2ND FLOOR HALLWAY	NEW			1955 Sq Ft
	97	3RD FLOOR HALLWAY	NEW			1955 Sq Ft
K3E	Miscellaneous Flooring 2' x 2' Beige w/Blue, White & Brown Specks (2014)					Total Amount - 970 Sq Ft
	53	ROOM 1001	NEW			250 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	98	ROOM 3201	NEW			720 Sq Ft
K3F	Miscellaneous Flooring 2' x 2' Red w/Multi-Colored Specks					Total Amount - 190 Sq Ft
	92	ROOM 2105	NEW			190 Sq Ft
L0A	Flexible Duct Connector Dark Canvas					Total Amount - 94 Sq Ft
	13	FAN ROOM OFF BOILER ROOM (0110)	NONE DETECTED	2001-1501-I-08	FAN ROOM BY BOILER ROOM.	90 Sq Ft
	100	PENTHOUSE MECHANICAL (4210)	NONE DETECTED			4 Sq Ft
M0A	Plaster 1923 Original Building					Total Amount - 100000 Sq Ft
	9	THROUGHOUT 1923 ORIGINAL BUILDING	NONE DETECTED	032309ML-13; 554-3, 6, 7, 8; 510T-1-P, 2, 5	ML-13: ROOM 2111 (CEILING). 554-6: STORAGE BY ROOM 307. 554-7: ROOM 112 RESTROOM. 554-8: OLD ELEVATOR SHAFT.	100000 Sq Ft
N0A	Drywall/Joint Compound Renovation					Total Amount - 13000 Sq Ft
	1	THROUGHOUT BUILDING	NONE DETECTED	554-3, 4, 5	3: ROOM 3206. 4: ROOM 1305/1307. 5: FORMER OFFICE.	13000 Sq Ft
P0A	Fire Doors Pieced Metal w/Wood Core					Total Amount - 80 Sq Ft
	17	BOILER ROOM (0112)	NONE DETECTED	032309ML-01	FELT LAYER BETWEEN WOOD CORE PIECES ON DOOR TO COAL ROOM.	40 Sq Ft
	101	PENTHOUSE MECHANICAL (4210)	NONE DETECTED			20 Sq Ft
	105	PENTHOUSE MECHANICAL (4310)	NONE DETECTED			20 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
Q0A	Carpet Adhesive Berber Carpet					Total Amount - 10000 Sq Ft
	3	THROUGHOUT BUILDING	NONE DETECTED	2001-1901-RE-1	MAIN OFFICE BY DOOR.	10000 Sq Ft
Q0B	Carpet Adhesive Berber Carpet (200X)					Total Amount - 20000 Sq Ft
	2	THROUGHOUT BUILDING	NONE DETECTED	032309ML-07	ML-07: ROOM 3201.	20000 Sq Ft
Q0D	Carpet Adhesive Green Carpet (2013)					Total Amount - 1758 Sq Ft
	78	ROOM 1303	NEW			98 Sq Ft
	90	ROOM 2111 (IMC)	NEW			1400 Sq Ft
	91	ROOM 2111A	NEW			80 Sq Ft
	95	ROOM 2205	NEW			180 Sq Ft
Q0E	Carpet Adhesive Red with Earth Tone Carpet Squares (2013)					Total Amount - 3774 Sq Ft
	51	THROUGHOUT MAIN OFFICE AREAS	NEW			1000 Sq Ft
	70	ROOM 1301	NEW			440 Sq Ft
	76	ROOM 1304	NEW			440 Sq Ft
	80	ROOM 1306	NEW			440 Sq Ft
	83	ROOM 1308	NEW			440 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	85	ROOM 1307	NEW			690 Sq Ft
	87	ROOM 1320	NEW			174 Sq Ft
	93	ROOM 2106	NEW			150 Sq Ft
ROB	Baseboard/Mopboard Adhesive Black Baseboard					Total Amount - 300 Sq Ft
	4	THROUGHOUT BUILDING	NONE DETECTED	2001-1901-XX-18B	OFFICE	300 Sq Ft
ROC	Baseboard/Mopboard Adhesive 4" Light Grayish Brown					Total Amount - 430 Sq Ft
	31	ROOM 1201	NEW			80 Sq Ft
	33	ROOM 1202	NEW			80 Sq Ft
	35	ROOM 1204	NEW			80 Sq Ft
	42	ROOM 1206	NEW			80 Sq Ft
	44	ROOM 1207	NEW			80 Sq Ft
	96	ROOM 2205	NEW			30 Sq Ft
ROD	Baseboard/Mopboard Adhesive 4" Light Brown (2012)					Total Amount - 520 Sq Ft
	37	ROOM 1205	NEW			40 Sq Ft
	71	ROOM 1301	NEW			80 Sq Ft
	77	ROOM 1304	NEW			80 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	81	ROOM 1306	NEW			80 Sq Ft
	84	ROOM 1308	NEW			80 Sq Ft
	86	ROOM 1307	NEW			80 Sq Ft
	99	ROOM 3201	NEW			80 Sq Ft
R0E	Baseboard/Mopboard Adhesive 6" Light Gray					Total Amount - 80 Sq Ft
	74	ROOM 1302	ASSUMED			80 Sq Ft
R0F	Baseboard/Mopboard Adhesive 6" Orangish Brown (2013)					Total Amount - 55 Sq Ft
	52	THROUGHOUT MAIN OFFICE AREAS	NEW			50 Sq Ft
	72	ROOM 1301	NEW			5 Sq Ft
S0A	Wood Floor Felt / Vapor Barrier 1923 Original Building (Elevated)					Total Amount - 40000 Sq Ft
	10	THROUGHOUT 1923 ORIGINAL BUILDING	NONE DETECTED	092712MV-16, 18, 23	MV-16: ROOM 1305. MV-18: ROOM 3201. MV-23: CAFETERIA.	40000 Sq Ft
T0A	Light Cord Insulation Fuzzy White					Total Amount - 86 Lin Ft
	57	ROOM 1110 (CAFETERIA)	ASSUMED			32 Lin Ft
	58	STAGE (1112)	ASSUMED			54 Lin Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
T0B	Light Cord Insulation Fuzzy Green and Black Cords					Total Amount - 162 Lin Ft
59	STAGE (1112)		ASSUMED			162 Lin Ft
V0A	Sink Undercoating Gray (20xx)					Total Amount - 60 Sq Ft
25	THROUGHOUT FIRST FLOOR CLASSROOMS		NEW			60 Sq Ft
W1A	1' x 1' Ceiling Tile Adhesive Associated w/I1A					Total Amount - 400 Sq Ft
104	ROOMS 3109 & 3111		NONE DETECTED	092712MV-19; 032309ML-24	MV-19: CAFETERIA.	400 Sq Ft
X0B	Miscellaneous Material Pyrobar Block					Total Amount - 5000 Sq Ft
8	THROUGHOUT 1923 ORIGINAL BUILDING		NSM			5000 Sq Ft
X0C	Miscellaneous Material Slate Chalkboard Adhesive (1923)					Total Amount - 350 Sq Ft
11	THROUGHOUT 1923 ORIGINAL BUILDING		NONE DETECTED	092712MV-12, 13	MV-12: THINSET. MV-13: BLACK ADHESIVE. BOTH SAMPLES COLLECTED IN ROOM 1302.	350 Sq Ft
X0D	Miscellaneous Material Tackboard Adhesive (1923)					Total Amount - 1000 Sq Ft
12	THROUGHOUT 1923 ORIGINAL BUILDING		NONE DETECTED	092712MV-14	MV-14: ROOM 1302.	1000 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
X0E	Miscellaneous Material Marble Adhesive					Total Amount - 20 Sq Ft
67	1ST FLOOR BOYS' RESTROOM (1121)	NONE DETECTED	032309ML-09	ML-09: 3RD FLOOR BOYS' RESTROOM (3121) (SINCE REMOVED).	20 Sq Ft	
X0F	Miscellaneous Material Metal Frame Tackboard Adhesive					Total Amount - 500 Sq Ft
5	THROUGHOUT BUILDING	NONE DETECTED	092712MV-15	MV-15: HALLWAY BY ROOM 1304.	500 Sq Ft	
X0G	Miscellaneous Material Red Fire Stop					Total Amount - 20 Sq Ft
7	THROUGHOUT BUILDING	NONE DETECTED	021523JA-01, 02	JA-01: BOILER ROOM. JA-02: ROOM 1007.	20 Sq Ft	
X0H	Miscellaneous Material Window Caulking and Glazing Compound (2022)					Total Amount - 300 Sq Ft
6	THROUGHOUT BUILDING	NEW			300 Sq Ft	
X0I	Miscellaneous Material Light Gray Ahu Seam Caulk (20xx)					Total Amount - 10 Sq Ft
15	FAN ROOM OF BOILER ROOM (0110)	NEW			10 Sq Ft	
X0J	Miscellaneous Material Gray Ahu Seam Caulk (20xx)					Total Amount - 5 Sq Ft
16	FAN ROOM OF BOILER ROOM (0110)	NEW			5 Sq Ft	
X1A	Miscellaneous Material Pipe & Valve Flange Gaskets					Total Amount - 44 Sq Ft
14	FAN ROOM OF BOILER ROOM (0110)	ASSUMED			10 Sq Ft	

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	21	BOILER ROOM (0112)	ASSUMED			10 Sq Ft
	22	ELECTRICAL/MECHANICAL ROOM OFF BOILER ROOM (0116)	ASSUMED			24 Sq Ft
X1B	Miscellaneous Material 12" X 12" Quarry Floor Tile System (2014)					Total Amount - 470 Sq Ft
	26	THROUGHOUT FIRST FLOOR CLASSROOM RESTROOMS	NEW			300 Sq Ft
	38	UNISEX RESTROOM BETWEEN ROOMS 1205 & 1207	NEW			60 Sq Ft
	45	ROOM 1207A (UNISEX RESTROOM)	NEW			50 Sq Ft
	68	ROOM 1121 (WOMEN'S RESTROOM)	NEW			60 Sq Ft
X1C	Miscellaneous Material 6" Quarry Tile System					Total Amount - 820 Sq Ft
	49	ROOM 1101 (KITCHEN STORAGE)	NEW			200 Sq Ft
	62	ROOM 1108 (KITCHEN)	NEW			420 Sq Ft
	65	ROOM 1106 (DISH ROOM)	NEW			200 Sq Ft
X1D	Miscellaneous Material 6" x 6" Yellow Ceramic Wall Tile System (2014)					Total Amount - 376 Sq Ft
	27	THROUGHOUT FIRST FLOOR CLASSROOM RESTROOMS	NEW			300 Sq Ft
	39	UNISEX RESTROOM BETWEEN ROOMS 1205 & 1207	NEW			36 Sq Ft
	46	ROOM 1207A (UNISEX RESTROOM)	NEW			40 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
X1E	Miscellaneous Material 6" x 6" White Ceramic Wall Tile System (2014)					Total Amount - 1410 Sq Ft
	28	THROUGHOUT FIRST FLOOR CLASSROOM RESTROOMS	NEW			450 Sq Ft
	40	UNISEX RESTROOM BETWEEN ROOMS 1205 & 1207	NEW			90 Sq Ft
	47	ROOM 1207A (UNISEX RESTROOM)	NEW			70 Sq Ft
	63	ROOM 1108 (KITCHEN)	NEW			450 Sq Ft
	66	ROOM 1106 (DISH ROOM)	NEW			350 Sq Ft