

2102 University Avenue West, Saint Paul, MN 55114

Chart C - All Materials List

The following list contains all events observed by the inspector, whether or not they actually contained asbestos, and are grouped by homogeneous area (material type).

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
A4B		Mudded Pipe Joints on Fiberglass Insulation				Total Amount - 4 Joints
	56	ROOM 2218	NONE DETECTED	111810-ML-01	ML-01: ROOM 218.	3 Joints
	62	ROOM 2216	NONE DETECTED			1 Joints
D1B		Boiler Gaskets 197X Installation				Total Amount - 4 Sq Ft
	4	BOILER ROOM (1104)	95 CH	111810-ML-02	ML-02: BOILER ROOM.	4 Sq Ft
G1A		Sprayed-On Acoustical Finish White Texture				Total Amount - 3120 Sq Ft
	74	1936 ORIGINAL BUILDING 2ND FLOOR HALLWAY (2205) & ENTRY (2202)	NONE DETECTED	111810-ML-05	ML-05: STAIRWELL LANDING.	400 Sq Ft
	76	ROOM 2206	NONE DETECTED	111810-ML-04	ML-04: ROOM 206.	320 Sq Ft
	77	ROOM 2201 & COPY ROOM (2200)	NONE DETECTED	111810-ML-03	ML-03: ROOM 201.	720 Sq Ft
	80	1936 ORIGINAL BUILDING 3RD FLOOR HALLWAY (3300) & STAIRS (3300A)	NONE DETECTED			200 Sq Ft
	81	ROOM 3301 & OFFICE	NONE DETECTED	111810-ML-06	ML-06: ROOM 301.	720 Sq Ft
	85	ROOM 3302	NONE DETECTED			280 Sq Ft
	86	ROOM 3306	NONE DETECTED			120 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	88	ROOM 3305	NONE DETECTED			180 Sq Ft
	90	ROOM 3303	NONE DETECTED	111810-ML-07	ML-07: ROOM 303.	180 Sq Ft
G1B	Sprayed-On Acoustical Finish Thick, White Texture (1978)					Total Amount - 1330 Sq Ft
	29	ROOM 122 & HALLWAY	NONE DETECTED	111810-ML-12	ML-12: ROOM 122 ENTRY.	500 Sq Ft
	30	ROOM 1118	NONE DETECTED	111810-ML-08	ML-08: ROOM 118.	100 Sq Ft
	31	ROOM 1119	NONE DETECTED			100 Sq Ft
	32	ROOM 1120	NONE DETECTED	111810-ML-09	ML-09: ROOM 120.	140 Sq Ft
	34	ROOM 1121	NONE DETECTED			250 Sq Ft
	36	ROOM 1123	NONE DETECTED	111810-ML-10	ML-10: ROOM 123.	120 Sq Ft
	37	ROOM 1124	NONE DETECTED	111810-ML-11	ML-11: ROOM 124.	120 Sq Ft
I1A	1' x 1' Acoustical Ceiling Tile Rough w/Holes					Total Amount - 150 Sq Ft
	65	AREA 2215 (LOBBY)	NONE DETECTED	111810-ML-13	ML-13: ROOM 215 (RECEPTIONIST).	150 Sq Ft
I3A	2' x 4' Ceiling Tile Widthwise Fissures & Pin Holes					Total Amount - 5160 Sq Ft
	19	ROOM 1106 (ELEVATOR LOBBY)	NONE DETECTED			215 Sq Ft
	39	ROOM 2234	NONE DETECTED			870 Sq Ft
	40	ROOM 2229	NONE DETECTED			180 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	41	ROOM 2230	NONE DETECTED			180 Sq Ft
	42	1978 ADDITION 2ND FLOOR HALLWAY (2231)	NONE DETECTED			180 Sq Ft
	43	ROOM 2232	NONE DETECTED			180 Sq Ft
	44	ROOM 2233	NONE DETECTED			170 Sq Ft
	45	1975 ADDITION ENTRY (2228)	NONE DETECTED			120 Sq Ft
	48	1975 ADDITION 2ND FLOOR HALLWAY (2225)	NONE DETECTED			400 Sq Ft
	51	ROOM 2223	NONE DETECTED			120 Sq Ft
	52	ROOM 2222	NONE DETECTED			120 Sq Ft
	53	ROOM 2221	NONE DETECTED			120 Sq Ft
	54	ROOM 2220	NONE DETECTED			120 Sq Ft
	55	ROOM 2219	NONE DETECTED			140 Sq Ft
	57	ROOM 2218	NONE DETECTED			140 Sq Ft
	58	RESTROOM 2219A	NONE DETECTED			55 Sq Ft
	61	ROOM 2217	NONE DETECTED			130 Sq Ft
	63	ROOM 2213/2216 (LOBBY/COMMONS)	NONE DETECTED			1200 Sq Ft
	67	MAIN ENTRY (2214)	NONE DETECTED			80 Sq Ft
	70	ROOM 2211 (ELEVATOR LOBBY)	NONE DETECTED			160 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	83	ROOM 3307 (HALLWAY)	NONE DETECTED	111810-ML-14	ML-14: ROOM 307.	60 Sq Ft
	84	ROOM 3308 (ELEVATOR LOBBY)	NONE DETECTED			220 Sq Ft
K2A	12" x 12" Vinyl Floor Tile & Mastic Beige w/Tan & Brown Flecks					Total Amount - 1000 Sq Ft
	6	ROOM 1101	NONE DETECTED			300 Sq Ft
	8	ROOM 1101A	NONE DETECTED			115 Sq Ft
	10	ROOM 1101B	NONE DETECTED			100 Sq Ft
	12	ROOM 1103	NONE DETECTED			320 Sq Ft
	15	ROOM 1105	NONE DETECTED			65 Sq Ft
	17	ROOM 1108B	NONE DETECTED			30 Sq Ft
	78	ROOM 2208	NONE DETECTED	111810-ML-15	ML-15: ROOM 208.	70 Sq Ft
K3A	Miscellaneous Flooring Tan Stair Treads					Total Amount - 600 Sq Ft
	38	EAST STAIRWELL (2235)	NEW			200 Sq Ft
	46	1975 ADDITION ENTRY (2228)	NEW			100 Sq Ft
	72	SOUTHWEST STAIRWELL (2212)	NEW			300 Sq Ft
LOA	Flexible Duct Connector Black Vinyl					Total Amount - 3 Sq Ft
	14	ROOM 1103	NSM			3 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
M0A	Plaster 1936 Original Building					Total Amount - 10000 Sq Ft
	2	THROUGHOUT 1936 ORIGINAL BUILDING	NONE DETECTED	111810-ML-16, 17, 18, 19, 20, 21, 22	ML-16: BOILER ROOM CEILING. ML-17: ROOM 201 WALL. ML-18: ROOM 204 WALL. ML-19: ROOM 206 CLOSET WALL. ML-20: ROOM 303 CLOSET CEILING. ML-21: ROOF ACCESS ROOM CEILING. ML-22: BOILER ROOM WALL.	10000 Sq Ft
N0B	Drywall/Joint Compound 1975 Addition					Total Amount - 3000 Sq Ft
	18	THROUGHOUT 1975 ADDITION	NONE DETECTED	111810-ML-23	ML-23: HALLWAY OUTSIDE ROOM 223 ABOVE CEILING.	3000 Sq Ft
N0C	Drywall/Joint Compound 1978 Addition					Total Amount - 2000 Sq Ft
	28	THROUGHOUT 1978 ADDITION	NONE DETECTED	111810-ML-24	ML-24: HALLWAY OUTSIDE ROOM 232 ABOVE CEILING.	2000 Sq Ft
P0A	Fire Doors Metal -1 Hr (Curries)					Total Amount - 20 Sq Ft
	5	BOILER ROOM (1104)	ASSUMED			20 Sq Ft
P0B	Fire Doors Metal -1.5 Hr Rating (Warnock Hersey)					Total Amount - 80 Sq Ft
	20	HALLWAY OUTSIDE ROOM 1112	ASSUMED			40 Sq Ft
	49	1975 ADDITION 2ND FLOOR HALLWAY (2225)	ASSUMED			20 Sq Ft
	75	1936 ORIGINAL BUILDING 2ND FLOOR HALLWAY (2205) & ENTRY (2202)	ASSUMED			20 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
POC	Fire Doors Wood -1 Hr Rating (Warnock Hersey)					Total Amount - 40 Sq Ft
	50	1975 ADDITION 2ND FLOOR HALLWAY (2225)	ASSUMED			40 Sq Ft
Q0A	Carpet Adhesive Multi-Colored Berber Carpet					Total Amount - 10000 Sq Ft
	1	THROUGHOUT BUILDING	NEW			10000 Sq Ft
Q0B	Carpet Adhesive Streaked Gray/Tan Carpet Squares (201x)					Total Amount - 1360 Sq Ft
	64	ROOM 2213/2216 (LOBBY/COMMONS)	NEW			1200 Sq Ft
	71	ROOM 2211 (ELEVATOR LOBBY)	NEW			160 Sq Ft
ROA	Baseboard/Mopboard Adhesive 4" Dark Brown					Total Amount - 61 Sq Ft
	7	ROOM 1101	ASSUMED			10 Sq Ft
	9	ROOM 1101A	ASSUMED			8 Sq Ft
	11	ROOM 1101B	ASSUMED			8 Sq Ft
	13	ROOM 1103	ASSUMED			10 Sq Ft
	16	ROOM 1105	ASSUMED			5 Sq Ft
	69	MAIN ENTRY (2214)	ASSUMED			5 Sq Ft
	73	SOUTHWEST STAIRWELL (2212)	ASSUMED			10 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	79	ROOM 2208	ASSUMED			5 Sq Ft
SOA	Wood Floor Felt / Vapor Barrier 1936 Original Building					Total Amount - 480 Sq Ft
	87	ROOM 3306	ASSUMED			120 Sq Ft
	89	ROOM 3305	ASSUMED			180 Sq Ft
	91	ROOM 3303	ASSUMED			180 Sq Ft
VOA	Sink Undercoating Gray					Total Amount - 14 Sq Ft
	21	ROOM 1112	NONE DETECTED	111810-ML-25	ML-25: ROOM 112.	6 Sq Ft
	33	ROOM 1120	NONE DETECTED			4 Sq Ft
	35	ROOM 1121	NONE DETECTED			4 Sq Ft
W1A	1' x 1' Ceiling Tile Adhesive Associated w/11A					Total Amount - 35 Sq Ft
	66	AREA 2215 (LOBBY)	NONE DETECTED	111810-ML-13	ML-13: ROOM 215 (RECEPTIONIST).	35 Sq Ft
X0A	Miscellaneous Material Pipe/Valve Flange Gaskets					Total Amount - 11 Sq Ft
	3	BOILER ROOM (1104)	ASSUMED			11 Sq Ft
X0B	Miscellaneous Material Loose Fiberglass					Total Amount - 2000 Sq Ft
	82	1936 ORIGINAL BUILDING ATTIC	NONE DETECTED	111810-ML-26	ML-26: ATTIC.	2000 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
X1A	Miscellaneous Material 4" X 4" Beige Ceramic Wall Tile System					Total Amount - 1160 Sq Ft
	22	MEN'S RESTROOM 1114	ASSUMED			400 Sq Ft
	24	WOMEN'S RESTROOM 1115	ASSUMED			400 Sq Ft
	26	CUSTODIAL STORAGE 1116	ASSUMED			200 Sq Ft
	59	RESTROOM 2219A	ASSUMED			160 Sq Ft
X1B	Miscellaneous Material 9" X 9" Tan Ceramic Floor Tile System (201x)					Total Amount - 315 Sq Ft
	23	MEN'S RESTROOM 1114	NEW			100 Sq Ft
	25	WOMEN'S RESTROOM 1115	NEW			100 Sq Ft
	27	CUSTODIAL STORAGE 1116	NEW			60 Sq Ft
	60	RESTROOM 2219A	NEW			55 Sq Ft
X1C	Miscellaneous Material 4" X 8" Brown Quarry Floor Tile System					Total Amount - 175 Sq Ft
	47	1975 ADDITION ENTRY (2228)	ASSUMED			75 Sq Ft
	68	MAIN ENTRY (2214)	ASSUMED			100 Sq Ft