

1863 East Clear Avenue, Saint Paul, MN 55119

Chart C - All Materials List

The following list contains all events observed by the inspector, whether or not they actually contained asbestos, and are grouped by homogeneous area (material type).

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
A2C	Mudded Pipe Joints on Millboard Insulation 1954 Addition					Total Amount - 8 Joints
	212	HALLWAY OUTSIDE ROOMS 1105 & 1107	45 CH, 5 AM			2 Joints
	220	ROOM 1105	45 CH, 5 AM			2 Joints
	230	ROOM 1107	45 CH, 5 AM			2 Joints
	238	ROOM 1109	45 CH, 5 AM	021109ML-60		2 Joints
A4D	Mudded Pipe Joints on Fiberglass Insulation 1966 Addition					Total Amount - 10 Joints
	248	1966 ADDITION TUNNEL	NONE DETECTED	021109ML-78, 79		6 Joints
	250	ROOM 1111	NONE DETECTED			2 Joints
	258	ROOM 1114	NONE DETECTED	021109ML-80		2 Joints
B2C	Millboard Pipe Insulation 1954 Addition					Total Amount - 49 Lin Ft
	211	HALLWAY OUTSIDE ROOMS 1105 & 1107	5 CH	ACB-450T-A012		10 Lin Ft
	219	ROOM 1105	5 CH			15 Lin Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	229	ROOM 1107	5 CH			12 Lin Ft
	237	ROOM 1109	5 CH			12 Lin Ft
B5A	Misc. Thermal Pipe Insulation Hard-Woven Pipe Wrap					Total Amount - 2 Lin Ft
	69	1924 ORIGINAL BUILDING 1ST FLOOR HALLWAY OUTSIDE ROOMS 2254 & 2255	NONE DETECTED			1 Lin Ft
	79	ROOM 2254	NONE DETECTED	021109ML-49		1 Lin Ft
D1A	Boiler Gaskets White, Shiny					Total Amount - 8 Sq Ft
	6	BOILER ROOM (1351)	NONE DETECTED	021109ML-18		8 Sq Ft
D2A	Interior Boiler Insulation Door Refractory					Total Amount - 6 Sq Ft
	7	BOILER ROOM (1351)	NONE DETECTED	021109ML-19		6 Sq Ft
D2B	Interior Boiler Insulation Interior Burner Refractory					Total Amount - 6 Sq Ft
	8	BOILER ROOM (1351)	ASSUMED			6 Sq Ft
H1A	Sprayed-On Structural Fireproofing Gray, Fluffy (1999)					Total Amount - 8190 Sq Ft
	26	1999 ADDITION MECHANICAL ROOM (1344A)	NONE DETECTED	021109ML-34, 35, 36		2000 Sq Ft
	32	HALLWAY TO ROOMS 2241 & 2244	NONE DETECTED			50 Sq Ft
	35	ROOM 2241	NONE DETECTED	021109ML-37		1000 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	38	ROOM 2244	NONE DETECTED	021109ML-38		1000 Sq Ft
	84	HALLWAY TO ROOMS 3243 & 3244	NONE DETECTED			70 Sq Ft
	87	ROOM 3243	NONE DETECTED	021109ML-39		1000 Sq Ft
	91	ROOM 3244	NONE DETECTED			1000 Sq Ft
	149	HALLWAY TO ROOMS 4244 & 4245	NONE DETECTED			70 Sq Ft
	152	ROOM 4245	NONE DETECTED			1000 Sq Ft
	156	ROOM 4244	NONE DETECTED	021109ML-40		1000 Sq Ft
I1A	1' x 1' Acoustical Ceiling Tile Large & Medium Holes in Rows (1954)					Total Amount - 3840 Sq Ft
	215	1954 ADDITION GYMNASIUM/LUNCH ROOM (1110)	NONE DETECTED			3000 Sq Ft
	268	RAMP (TA5)	NONE DETECTED	2001-1501-AD-5		400 Sq Ft
	302	ROOM 2102	NONE DETECTED			40 Sq Ft
	310	STORAGE ROOM 2102A	NONE DETECTED			180 Sq Ft
	314	ROOM 2104	NONE DETECTED			40 Sq Ft
	322	STORAGE ROOM 2104A	NONE DETECTED			180 Sq Ft
I1B	1' x 1' Acoustical Ceiling Tile Light Fissures					Total Amount - 1165 Sq Ft
	13	1941 ADDITION GYMNASIUM (1251)	NONE DETECTED	021109ML-76; 206-X7A	X7A: GYMNASIUM CEILING.	1165 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
I1C	1' x 1' Acoustical Ceiling Tile Pegboard (1941)					Total Amount - 900 Sq Ft
	27	1941 ADDITION NORTHEAST STAIRWELL	NONE DETECTED	488-10		900 Sq Ft
I1D	1' x 1' Acoustical Ceiling Tile Pegboard (1924)					Total Amount - 6000 Sq Ft
	64	1924 ORIGINAL BUILDING EAST STAIRWELL	NONE DETECTED			900 Sq Ft
	67	1924 ORIGINAL BUILDING 1ST FLOOR HALLWAY OUTSIDE ROOMS 2254 & 2255	NONE DETECTED			480 Sq Ft
	71	ROOM 2255	NONE DETECTED	021109ML-48		600 Sq Ft
	76	ROOM 2254	NONE DETECTED			600 Sq Ft
	133	1924 ORIGINAL BUILDING 2ND FLOOR HALLWAY OUTSIDE ROOMS 3254 & 3257	NONE DETECTED			480 Sq Ft
	136	ROOM 3257	NONE DETECTED			600 Sq Ft
	142	ROOM 3254	NONE DETECTED			660 Sq Ft
	192	1924 ORIGINAL BUILDING 3RD FLOOR HALLWAY OUTSIDE ROOMS 4258 & 4259	NONE DETECTED			480 Sq Ft
	196	ROOM 4259	NONE DETECTED			600 Sq Ft
	202	ROOM 4258	NONE DETECTED			600 Sq Ft
I1E	1' x 1' Acoustical Ceiling Tile Deep Fissures w/Dents					Total Amount - 35 Sq Ft
	15	1941 ADDITION GYMNASIUM (1251)	NONE DETECTED	021109ML-77		35 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
I1F	1' x 1' Acoustical Ceiling Tile Large & Medium Holes in Rows (1966)					Total Amount - 180 Sq Ft
	370	1ST FLOOR ELEVATOR LOBBY (2117)	NONE DETECTED	021109ML-72		180 Sq Ft
I2A	2' x 2' Acoustical Ceiling Tile Fissures w/Pin Holes (2008)					Total Amount - 300 Sq Ft
	282	ROOM 2304	NEW			240 Sq Ft
	297	ROOM 2308	NEW			60 Sq Ft
I2B	2' x 2' Acoustical Ceiling Tile Textured w/Pin Holes w/Revealed Edge (2008)					Total Amount - 2200 Sq Ft
	374	THROUGHOUT 2008 ADDITION	NEW			2200 Sq Ft
I3A	2' x 4' Ceiling Tile Chicken Scratch (1997)					Total Amount - 2424 Sq Ft
	23	ROOM 1346	NONE DETECTED			624 Sq Ft
	210	1954 ADDITION GROUND FLOOR HALLWAY FROM STORAGE ROOM 1101 TO ROOM 1111	NONE DETECTED	488-8		1800 Sq Ft
I3B	2' x 4' Ceiling Tile Widthwise Rough Crevices & Pin Holes					Total Amount - 3810 Sq Ft
	251	ROOM 1111	NONE DETECTED	ACB-450T-E1		900 Sq Ft
	259	ROOM 1114	NONE DETECTED			900 Sq Ft
	264	GROUND FLOOR ELEVATOR LANDING (1118)	NONE DETECTED			90 Sq Ft
	360	ROOM 2114	NONE DETECTED			960 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	366	ROOM 2115	NONE DETECTED	ACB-450T-E2, 3	2: ROOM 215. 3: ROOM 218.	960 Sq Ft
I3C	2' x 4' Ceiling Tile Widthwise Fissures (1997)					Total Amount - 1830 Sq Ft
	24	MEZZANINE FLOOR ELEVATOR LOBBY (1344)	NONE DETECTED			80 Sq Ft
	29	1ST FLOOR ELEVATOR LOBBY (2246)	NONE DETECTED			90 Sq Ft
	82	2ND FLOOR ELEVATOR LOBBY (3246)	NONE DETECTED			80 Sq Ft
	147	3RD FLOOR ELEVATOR LOBBY (4246)	NONE DETECTED	021109ML-75		80 Sq Ft
	267	RAMP (TA5)	NONE DETECTED			360 Sq Ft
	275	STORAGE ROOM 2302	NONE DETECTED			160 Sq Ft
	278	ROOM 2303	NONE DETECTED			300 Sq Ft
	286	HALLWAY 2306	NONE DETECTED			100 Sq Ft
	288	OFFICE NORTH OF ROOM 2304	NONE DETECTED			150 Sq Ft
	299	ROOM 2309	NONE DETECTED			300 Sq Ft
	372	1ST FLOOR ELEVATOR LOBBY (2117)	NONE DETECTED			130 Sq Ft
I3D	2' x 4' Ceiling Tile Lightly Textured w/Pin Holes					Total Amount - 19965 Sq Ft
	42	1ST FLOOR HALLWAY FROM ROOMS 2243-2254	NONE DETECTED			1400 Sq Ft
	45	ROOM 2243	NONE DETECTED			260 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	49	ROOM 2245	NONE DETECTED			900 Sq Ft
	54	LIBRARY (2250)	NONE DETECTED			2000 Sq Ft
	61	COMMUNICATION ROOM (2248)	NONE DETECTED			65 Sq Ft
	70	ROOM 2255	NONE DETECTED			660 Sq Ft
	75	ROOM 2254	NONE DETECTED			660 Sq Ft
	95	2ND FLOOR HALLWAY FROM ROOMS 3245-3254	NONE DETECTED			1400 Sq Ft
	100	ROOM 3245	NONE DETECTED	488-9	ROOM 3245 SOUTHWEST CORNER.	1000 Sq Ft
	107	ROOM 3248	NONE DETECTED			720 Sq Ft
	113	ENTRANCE TO ROOM 3250	NONE DETECTED			65 Sq Ft
	121	ROOM 3253	NONE DETECTED			730 Sq Ft
	127	ROOM 3252	NONE DETECTED			720 Sq Ft
	135	ROOM 3257	NONE DETECTED			600 Sq Ft
	141	ROOM 3254	NONE DETECTED			600 Sq Ft
	160	4TH FLOOR HALLWAY OUTSIDE ROOM 4247 TO 4258	NONE DETECTED			1400 Sq Ft
	163	ROOM 4247	NONE DETECTED			880 Sq Ft
	169	ROOM 4250	NONE DETECTED			800 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	175	ROOM 4250A	NONE DETECTED			140 Sq Ft
	177	ROOM 4255	NONE DETECTED			640 Sq Ft
	183	ROOM 4252	NONE DETECTED			840 Sq Ft
	195	ROOM 4259	NONE DETECTED			600 Sq Ft
	201	ROOM 4258	NONE DETECTED			600 Sq Ft
	272	1ST FLOOR HALLWAY FROM RAMP TO ROOM 2115	NONE DETECTED			2000 Sq Ft
	326	1954 ADDITION NORTHEAST STAIRWELL	NONE DETECTED			260 Sq Ft
	357	HALLWAY 2100A	NONE DETECTED			25 Sq Ft
I3E	2' x 4' Ceiling Tile Vinyl-Coated Sheetrock					Total Amount - 600 Sq Ft
	213	1954 ADDITION KITCHEN (1102)	NSM			600 Sq Ft
I3F	2' x 4' Ceiling Tile Widthwise Fissures w/Pin Holes (1999)					Total Amount - 4410 Sq Ft
	33	HALLWAY TO ROOMS 2241 & 2244	NONE DETECTED	021109ML-44		70 Sq Ft
	36	ROOM 2241	NONE DETECTED			700 Sq Ft
	39	ROOM 2244	NONE DETECTED			700 Sq Ft
	85	HALLWAY TO ROOMS 3243 & 3244	NONE DETECTED			70 Sq Ft
	88	ROOM 3243	NONE DETECTED			700 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	92	ROOM 3244	NONE DETECTED			700 Sq Ft
	150	HALLWAY TO ROOMS 4244 & 4245	NONE DETECTED			70 Sq Ft
	153	ROOM 4245	NONE DETECTED			700 Sq Ft
	157	ROOM 4244	NONE DETECTED			700 Sq Ft
I3G	2' x 4' Ceiling Tile Dents w/Pin Holes					Total Amount - 3600 Sq Ft
	221	ROOM 1105	NONE DETECTED			900 Sq Ft
	231	ROOM 1107	NONE DETECTED	021109ML-58		900 Sq Ft
	239	ROOM 1109	NONE DETECTED			900 Sq Ft
	330	ROOM 2109	NONE DETECTED			450 Sq Ft
	334	ROOM 2109A	NONE DETECTED			450 Sq Ft
I3H	2' x 4' Ceiling Tile Dents w/Pin Holes					Total Amount - 4020 Sq Ft
	304	ROOM 2102	NONE DETECTED	021109ML-65		1050 Sq Ft
	316	ROOM 2104	NONE DETECTED			1050 Sq Ft
	343	ROOM 2111	NONE DETECTED			960 Sq Ft
	350	ROOM 2113	NONE DETECTED			960 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
J3A	Miscellaneous Cementitious Material Black Window Sill (1941)		Total Amount - 258 Sq Ft			
	19	1941 ADDITION GYMNASIUM (1251)	NONE DETECTED	021109ML-33		15 Sq Ft
	60	LIBRARY (2250)	NONE DETECTED			50 Sq Ft
	105	ROOM 3245	NONE DETECTED			30 Sq Ft
	111	ROOM 3248	NONE DETECTED			25 Sq Ft
	117	ROOM 3250	NONE DETECTED			4 Sq Ft
	120	ROOM 3251	NONE DETECTED			4 Sq Ft
	131	ROOM 3252	NONE DETECTED			25 Sq Ft
	167	ROOM 4247	NONE DETECTED			30 Sq Ft
	173	ROOM 4250	NONE DETECTED			25 Sq Ft
	181	ROOM 4255	NONE DETECTED			20 Sq Ft
	189	ROOM 4252	NONE DETECTED			30 Sq Ft
K0A	9" x 9" Vinyl Floor Tile & Mastic Dark Brown with Red Streaks		Total Amount - 400 Sq Ft			
	284	ROOM 2304	8 CH (TILE), NONE DETECTED (MASTIC)			250 Sq Ft
	290	OFFICE NORTH OF ROOM 2304	8 CH (TILE), NONE DETECTED (MASTIC)	081121CW-01	CW-01: OFFICE NORTH OF ROOM 2304.	150 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
K1A	Sheet Vinyl Flooring & Adhesive Orange, Green, Tan & Blue (2008)					Total Amount - 1200 Sq Ft
	376	THROUGHOUT 2008 ADDITION	NEW			1200 Sq Ft
K2B	12" x 12" Vinyl Floor Tile & Mastic Blue w/Dark Blue & White Streaks					Total Amount - 40 Sq Ft
	358	HALLWAY 2100A	NONE DETECTED	021109ML-25	ML-25: 1954 ADDITION GYMNASIUM/LUNCH ROOM STORAGE (1110A) (SINCE REMOVED).	40 Sq Ft
K2C	12" x 12" Vinyl Floor Tile & Mastic Light Gray w/Gray & White Smudges					Total Amount - 7670 Sq Ft
	43	1ST FLOOR HALLWAY FROM ROOMS 2243-2254	NONE DETECTED			700 Sq Ft
	96	2ND FLOOR HALLWAY FROM ROOMS 3245-3254	NONE DETECTED			700 Sq Ft
	161	4TH FLOOR HALLWAY OUTSIDE ROOM 4247 TO 4258	NONE DETECTED			700 Sq Ft
	273	1ST FLOOR HALLWAY FROM RAMP TO ROOM 2115	NONE DETECTED	021109ML-29	ML-29: 1954 ADDITION GROUND FLOOR HALLWAY FROM STORAGE ROOM 1101 TO GYMNASIUM/LUNCH ROOM (SINCE REMOVED).	2400 Sq Ft
	287	HALLWAY 2306	NONE DETECTED			100 Sq Ft
	292	ROOM 2005	NONE DETECTED			200 Sq Ft
	293	STAFF ROOM 2307	NONE DETECTED			200 Sq Ft
	298	ROOM 2308	NONE DETECTED			100 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	305	ROOM 2102	NONE DETECTED			700 Sq Ft
	312	STORAGE ROOM 2102A	NONE DETECTED			180 Sq Ft
	317	ROOM 2104	NONE DETECTED			700 Sq Ft
	324	STORAGE ROOM 2104A	NONE DETECTED			180 Sq Ft
	344	ROOM 2111	NONE DETECTED			600 Sq Ft
	373	1ST FLOOR ELEVATOR LOBBY (2117)	NONE DETECTED			210 Sq Ft
K2D	12" x 12" Vinyl Floor Tile & Mastic Cream w/Black Smudges					Total Amount - 65 Sq Ft
	236	ROOM 1107	NONE DETECTED			20 Sq Ft
	241	ROOM 1109	NONE DETECTED	021109ML-30	ML-30: 1954 ADDITION GROUND FLOOR NORTHEAST ENTRANCE NEAR STORAGE ROOM 1101 (SINCE REMOVED).	30 Sq Ft
	338	ROOM 2109A	NONE DETECTED			15 Sq Ft
K2E	12" x 12" Vinyl Floor Tile & Mastic Blue Mottle (2008)					Total Amount - 50 Sq Ft
	274	HAND WASHING AREA OUTSIDE ROOM 2109	NONE DETECTED	032019-BF-2	BF-2: HAND WASHING AREA OUTSIDE ROOM 1105 (SINCE REMOVED)	50 Sq Ft
K2G	12" x 12" Vinyl Floor Tile & Mastic Light Gray w/Gray & White Streaks					Total Amount - 2100 Sq Ft
	17	1941 ADDITION GYMNASIUM (1251)	NONE DETECTED	021109ML-32		2100 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
K2H	12" x 12" Vinyl Floor Tile & Mastic Gray, Beige & White	Total Amount - 830 Sq Ft				
	22	GROUND FLOOR ELEVATOR LOBBY (1247)	NONE DETECTED	021109ML-88		80 Sq Ft
	25	MEZZANINE FLOOR ELEVATOR LOBBY (1344)	NONE DETECTED			80 Sq Ft
	30	1ST FLOOR ELEVATOR LOBBY (2246)	NONE DETECTED	021109ML-54		90 Sq Ft
	34	HALLWAY TO ROOMS 2241 & 2244	NONE DETECTED			140 Sq Ft
	83	2ND FLOOR ELEVATOR LOBBY (3246)	NONE DETECTED			80 Sq Ft
	86	HALLWAY TO ROOMS 3243 & 3244	NONE DETECTED			140 Sq Ft
	148	3RD FLOOR ELEVATOR LOBBY (4246)	NONE DETECTED			80 Sq Ft
	151	HALLWAY TO ROOMS 4244 & 4245	NONE DETECTED			140 Sq Ft
K2K	12" x 12" Vinyl Floor Tile & Mastic Tan w/Brown & White Streaks	Total Amount - 3110 Sq Ft				
	46	ROOM 2243	NONE DETECTED			260 Sq Ft
	50	ROOM 2245	NONE DETECTED			900 Sq Ft
	184	ROOM 4252	NONE DETECTED			900 Sq Ft
	222	ROOM 1105	NONE DETECTED			900 Sq Ft
	359	ROOM 2116	NONE DETECTED	021109ML-73		150 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
K3B	Miscellaneous Flooring Black Floor Mastic (1941)					Total Amount - 1200 Sq Ft
	57	LIBRARY (2250)	10 CH	021109ML-47		1200 Sq Ft
K3D	Miscellaneous Flooring 2' x 2' Gray w/White Streaks					Total Amount - 3700 Sq Ft
	331	ROOM 2109	NONE DETECTED			450 Sq Ft
	335	ROOM 2109A	NONE DETECTED			450 Sq Ft
	351	ROOM 2113	NONE DETECTED			880 Sq Ft
	361	ROOM 2114	NONE DETECTED	021109ML-71		960 Sq Ft
	367	ROOM 2115	NONE DETECTED			960 Sq Ft
K3E	Miscellaneous Flooring Light Blue w/Blue & White Specks Stair Treads (2012)					Total Amount - 1395 Sq Ft
	11	STAIRWELL (1250) OUTSIDE BOILER ROOM	NEW			50 Sq Ft
	98	BOOT RACK OUTSIDE ROOM 3245	NEW			15 Sq Ft
	270	RAMP (TA5)	NEW			800 Sq Ft
	327	1954 ADDITION NORTHEAST STAIRWELL	NEW			280 Sq Ft
	356	STAIRWELL NEAR ROOM 2113	NEW			250 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
K3F	Miscellaneous Flooring 2' X 2' Gray w/White Specks (2019)					Total Amount - 3720 Sq Ft
	232	ROOM 1107	NEW			900 Sq Ft
	240	ROOM 1109	NEW			900 Sq Ft
	252	ROOM 1111	NEW			900 Sq Ft
	256	ROOM 1116	NEW			120 Sq Ft
	260	ROOM 1114	NEW			900 Sq Ft
K3G	Miscellaneous Flooring Gray with Gray and White Specks (2019)					Total Amount - 30 Sq Ft
	266	ELEVATOR - WEST OF 1966 ADDITION	NEW			30 Sq Ft
L0A	Flexible Duct Connector Green Canvas					Total Amount - 4 Sq Ft
	342	MECHANICAL ROOM 2112	NONE DETECTED	021109ML-17		4 Sq Ft
L0B	Flexible Duct Connector Tan Canvas					Total Amount - 8 Sq Ft
	9	BOILER ROOM (1351)	NONE DETECTED	2001-1504-S1		4 Sq Ft
	10	FAN ROOM (TE13) OFF OF CUSTODIAL OFFICE	NONE DETECTED			4 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
M0A	Plaster 1924 Original Building	Total Amount - 20000 Sq Ft				
	4	THROUGHOUT 1924 ORIGINAL BUILDING	NONE DETECTED	021109ML-01, 02, 03, 04, 05; 2001-01376-14; 509V3;	ML-01: ROOM 2255. ML-02: 1ST FLOOR HALLWAY. ML-03: HALLWAY NEAR ROOM 3257. ML-04: HALLWAY NEAR ROOM 4259. ML-05: HALLWAY NEAR ROOM 4258.	20000 Sq Ft
M0B	Plaster 1941 Addition	Total Amount - 30000 Sq Ft				
	12	THROUGHOUT 1941 ADDITION	NONE DETECTED	021109ML-06, 07, 08, 09, 10; 2001-1501-AD-10; 2001-01276-15	ML-06: HALLWAY BY IMC. ML-07: ROOM 2249. ML-08: HALLWAY BY ROOM 3253. ML-09: ROOM 4250. ML-10: HALLWAY BY 3RD FLOOR STAIRWELL.	30000 Sq Ft
M0C	Plaster 1954 Addition	Total Amount - 30000 Sq Ft				
	207	THROUGHOUT 1954 ADDITION	NONE DETECTED	021109ML-11, 12, 13, 14, 15, 16; 2001-1501-AD-9	ML-11: ROOM 1107. ML-12: HALLWAY BY ROOM 1109. ML-13: NORTH ENTRY. ML-14: ROOM 2112. ML-15: HALLWAY BY ROOM 2109. ML-16: ROOM 2104.	30000 Sq Ft
M0D	Plaster 1966 Addition	Total Amount - 4800 Sq Ft				
	246	THROUGHOUT 1966 ADDITION	NONE DETECTED	021109ML-83, 84, 85, 86, 87; 2001-1501-AD-8	ML-83: HALLWAY BY ROOM 2117. ML-84: HALLWAY BY ROOM 2115. ML-85: ROOM 2115. ML-86: HALLWAY BY ROOM 1111. ML-87: ROOM 1114.	4800 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
N0A	Drywall/Joint Compound					Total Amount - 10000 Sq Ft
	1	THROUGHOUT BUILDING	NONE DETECTED	021109ML-74	ML-74: ROOM 1344A.	10000 Sq Ft
P0B	Fire Doors Metal - 1-1/2 Hr Rating (Underwriter's Laboratories)					Total Amount - 20 Sq Ft
	281	MECHANICAL ROOM (2303A)	ASSUMED			20 Sq Ft
P0C	Fire Doors Wood - Rating Unknown (No Tag)					Total Amount - 40 Sq Ft
	341	MECHANICAL ROOM 2112	NONE DETECTED	021109ML-68		40 Sq Ft
P0D	Fire Doors Warnock Hersey -Wood 1 Hr Rating					Total Amount - 180 Sq Ft
	63	1924 ORIGINAL BUILDING EAST & WEST STAIRWELL	ASSUMED			180 Sq Ft
Q0A	Carpet Adhesive Tan & Gray Berber Carpet (1999)					Total Amount - 5260 Sq Ft
	37	ROOM 2241	NONE DETECTED			700 Sq Ft
	40	ROOM 2244	NONE DETECTED			700 Sq Ft
	89	ROOM 3243	NONE DETECTED			700 Sq Ft
	93	ROOM 3244	NONE DETECTED	021109ML-43		700 Sq Ft
	154	ROOM 4245	NONE DETECTED			700 Sq Ft
	158	ROOM 4244	NONE DETECTED			700 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	306	ROOM 2102	NONE DETECTED			350 Sq Ft
	318	ROOM 2104	NONE DETECTED			350 Sq Ft
	345	ROOM 2111	NONE DETECTED			360 Sq Ft
Q0B	Carpet Adhesive Tan, Gray & Green Berber					Total Amount - 2000 Sq Ft
	55	LIBRARY (2250)	NONE DETECTED	021109ML-53		2000 Sq Ft
Q0C	Carpet Adhesive Reddish-Gray Berber Carpet					Total Amount - 610 Sq Ft
	276	STORAGE ROOM 2302	NONE DETECTED	021109ML-61	ML-61: RAMP (TA5) (SINCE REMOVED).	160 Sq Ft
	279	ROOM 2303	NONE DETECTED			300 Sq Ft
	289	OFFICE NORTH OF ROOM 2304	NONE DETECTED			150 Sq Ft
Q0D	Carpet Adhesive Red, Gray & Tan Carpet (2008)					Total Amount - 1040 Sq Ft
	283	ROOM 2304	NEW			240 Sq Ft
	375	THROUGHOUT 2008 ADDITION	NEW			800 Sq Ft
R0B	Baseboard/Mopboard Adhesive 4" Black Baseboard					Total Amount - 140 Sq Ft
	18	1941 ADDITION GYMNASIUM (1251)	NONE DETECTED			40 Sq Ft
	209	THROUGHOUT 1954 ADDITION	NONE DETECTED	021109ML-27	ML-27: ROOM 2111.	100 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
ROC	Baseboard/Mopboard Adhesive 4" Gray/Tan Baseboard					Total Amount - 40 Sq Ft
	31	THROUGHOUT 1999 ADDITION	NONE DETECTED	021109ML-42	ML-42: ROOM 4245.	40 Sq Ft
R0D	Baseboard/Mopboard Adhesive 6" Brown Baseboard					Total Amount - 10 Sq Ft
	47	ROOM 2243	NONE DETECTED	021109ML-46		10 Sq Ft
R0E	Baseboard/Mopboard Adhesive 4" Tan Baseboard					Total Amount - 40 Sq Ft
	21	THROUGHOUT 1997 ADDITION ELEVATOR LANDINGS	NONE DETECTED	021109ML-52		40 Sq Ft
R0F	Baseboard/Mopboard Adhesive 4" Red Baseboard					Total Amount - 30 Sq Ft
	277	STORAGE ROOM 2302	NONE DETECTED	021109ML-62	ML-62: RAMP (TA5) (SINCE REMOVED).	10 Sq Ft
	280	ROOM 2303	NONE DETECTED			10 Sq Ft
	291	OFFICE NORTH OF ROOM 2304	NONE DETECTED			10 Sq Ft
R0G	Baseboard/Mopboard Adhesive 4" Dark Gray Baseboard					Total Amount - 100 Sq Ft
	208	THROUGHOUT 1954 ADDITION	NONE DETECTED	021109ML-64		100 Sq Ft
R0H	Baseboard/Mopboard Adhesive 4" Orange Baseboard (2008)					Total Amount - 115 Sq Ft
	285	ROOM 2304	NEW			15 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	377	THROUGHOUT 2008 ADDITION	NEW			100 Sq Ft
R0I	Baseboard/Mopboard Adhesive 6" Bright Green Baseboard (2008)					Total Amount - 50 Sq Ft
	378	THROUGHOUT 2008 ADDITION	NEW			50 Sq Ft
R0J	Baseboard/Mopboard Adhesive 4" Blue Baseboard (2012)					Total Amount - 25 Sq Ft
	99	BOOT RACK OUTSIDE ROOM 3245	NEW			5 Sq Ft
	271	RAMP (TA5)	NEW			20 Sq Ft
S0A	Wood Floor Felt / Vapor Barrier 1924 Original Building					Total Amount - 11015 Sq Ft
	56	LIBRARY (2250)	NONE DETECTED			800 Sq Ft
	62	COMMUNICATION ROOM (2248)	NONE DETECTED			65 Sq Ft
	73	ROOM 2255	NONE DETECTED			660 Sq Ft
	78	ROOM 2254	NONE DETECTED	062111-BF-1	BF-1: ROOM 2254.	660 Sq Ft
	138	ROOM 3257	NONE DETECTED			660 Sq Ft
	144	ROOM 3254	NONE DETECTED			660 Sq Ft
	194	ROOM 4257	NONE DETECTED			200 Sq Ft
	198	ROOM 4259	NONE DETECTED			660 Sq Ft
	204	ROOM 4258	NONE DETECTED			6650 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
S0B	Wood Floor Felt / Vapor Barrier 1941 Addition					Total Amount - 7520 Sq Ft
	20	1941 ADDITION STAGE (1253)	ASSUMED			300 Sq Ft
	101	ROOM 3245	ASSUMED			880 Sq Ft
	108	ROOM 3248	ASSUMED			800 Sq Ft
	114	ROOM 3250	ASSUMED			200 Sq Ft
	118	ROOM 3251	ASSUMED			200 Sq Ft
	122	ROOM 3253	ASSUMED			800 Sq Ft
	128	ROOM 3252	ASSUMED			800 Sq Ft
	164	ROOM 4247	ASSUMED			1000 Sq Ft
	170	ROOM 4250	ASSUMED			800 Sq Ft
	176	ROOM 4250A	ASSUMED			140 Sq Ft
	178	ROOM 4255	ASSUMED			700 Sq Ft
	185	ROOM 4252	ASSUMED			900 Sq Ft
T0A	Light Cord Insulation 1954 Addition					Total Amount - 5 Lin Ft
	217	1954 ADDITION GYMNASIUM/LUNCH ROOM (1110)	ASSUMED			5 Lin Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
VOA	Sink Undercoating Gray					Total Amount - 10 Sq Ft
	159	ROOM 4244	NONE DETECTED			5 Sq Ft
	218	SMALL KITCHEN (1108) OFF OF 1954 ADDITION GYMNASIUM/LUNCH ROOM	NONE DETECTED	021109ML-26		5 Sq Ft
VOB	Sink Undercoating Gray (1999)					Total Amount - 20 Sq Ft
	41	ROOM 2244	NONE DETECTED	021109ML-41		5 Sq Ft
	90	ROOM 3243	NONE DETECTED			5 Sq Ft
	94	ROOM 3244	NONE DETECTED			5 Sq Ft
	155	ROOM 4245	NONE DETECTED			5 Sq Ft
VOC	Sink Undercoating Black					Total Amount - 20 Sq Ft
	51	ROOM 2245	5 CH			15 Sq Ft
	190	ROOM 4252	5 CH	021109ML-50		5 Sq Ft
VOD	Sink Undercoating Off-White (2008)					Total Amount - 8 Sq Ft
	294	STAFF ROOM 2307	NEW			4 Sq Ft
	379	ROOM 2004	NEW			4 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
VOE	Sink Undercoating Gray (2011)					Total Amount - 72 Sq Ft
	81	ROOM 2254	NEW			6 Sq Ft
	106	ROOM 3245	NEW			6 Sq Ft
	112	ROOM 3248	NEW			6 Sq Ft
	125	ROOM 3253	NEW			6 Sq Ft
	132	ROOM 3252	NEW			6 Sq Ft
	140	ROOM 3257	NEW			6 Sq Ft
	146	ROOM 3254	NEW			6 Sq Ft
	168	ROOM 4247	NEW			6 Sq Ft
	174	ROOM 4250	NEW			6 Sq Ft
	182	ROOM 4255	NEW			6 Sq Ft
	200	ROOM 4259	NEW			6 Sq Ft
	206	ROOM 4258	NEW			6 Sq Ft
W1A	1' x 1' Ceiling Tile Adhesive Associated w/I1A					Total Amount - 960 Sq Ft
	216	1954 ADDITION GYMNASIUM/LUNCH ROOM (1110)	3 CH			750 Sq Ft
	269	RAMP (TA5)	3 CH	021109ML-31		100 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	303	ROOM 2102	3 CH			10 Sq Ft
	311	STORAGE ROOM 2102A	3 CH	031709-ML-01		45 Sq Ft
	315	ROOM 2104	3 CH			10 Sq Ft
	323	STORAGE ROOM 2104A	3 CH			45 Sq Ft
W1B	1' x 1' Ceiling Tile Adhesive Associated w/I1B					Total Amount - 290 Sq Ft
	14	1941 ADDITION GYMNASIUM (1251)	NONE DETECTED	021109ML-76		290 Sq Ft
W1C	1' x 1' Ceiling Tile Adhesive Associated w/I1C					Total Amount - 225 Sq Ft
	28	1941 ADDITION NORTHEAST STAIRWELL	NONE DETECTED	021109ML-45		225 Sq Ft
W1D	1' x 1' Ceiling Tile Adhesive Associated w/I1D					Total Amount - 1485 Sq Ft
	65	1924 ORIGINAL BUILDING EAST STAIRWELL	NONE DETECTED			225 Sq Ft
	68	1924 ORIGINAL BUILDING 1ST FLOOR HALLWAY OUTSIDE ROOMS 2254 & 2255	NONE DETECTED			120 Sq Ft
	72	ROOM 2255	NONE DETECTED	021109ML-48		150 Sq Ft
	77	ROOM 2254	NONE DETECTED			150 Sq Ft
	134	1924 ORIGINAL BUILDING 2ND FLOOR HALLWAY OUTSIDE ROOMS 3254 & 3257	NONE DETECTED			120 Sq Ft
	137	ROOM 3257	NONE DETECTED			150 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	143	ROOM 3254	NONE DETECTED			150 Sq Ft
	193	1924 ORIGINAL BUILDING 3RD FLOOR HALLWAY OUTSIDE ROOMS 4258 & 4259	NONE DETECTED	021109ML-51		120 Sq Ft
	197	ROOM 4259	NONE DETECTED			150 Sq Ft
	203	ROOM 4258	NONE DETECTED			150 Sq Ft
W1E	1' x 1' Ceiling Tile Adhesive Associated w/I1E					Total Amount - 9 Sq Ft
	16	1941 ADDITION GYMNASIUM (1251)	NONE DETECTED	021109ML-77		9 Sq Ft
W1F	1' x 1' Ceiling Tile Adhesive Associated w/I1F					Total Amount - 45 Sq Ft
	371	1ST FLOOR ELEVATOR LOBBY (2117)	NONE DETECTED	021109ML-72		45 Sq Ft
X0A	Miscellaneous Material Gray Smeared Duct Caulk					Total Amount - 100 Sq Ft
	2	THROUGHOUT BUILDING	NONE DETECTED	021109ML-28		100 Sq Ft
X0B	Miscellaneous Material Wood Frame Chalkboard Adhesive (1924)					Total Amount - 105 Sq Ft
	59	LIBRARY (2250)	ASSUMED			15 Sq Ft
	74	ROOM 2255	ASSUMED			15 Sq Ft
	80	ROOM 2254	ASSUMED			15 Sq Ft
	139	ROOM 3257	ASSUMED			15 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	145	ROOM 3254	ASSUMED			15 Sq Ft
	199	ROOM 4259	ASSUMED			15 Sq Ft
	205	ROOM 4258	ASSUMED			15 Sq Ft
X0C	Miscellaneous Material Wood Frame Chalkboard Adhesive (1941)					Total Amount - 145 Sq Ft
	102	ROOM 3245	5 CH	072511MV-02	MV-02: ROOM 3245.	20 Sq Ft
	109	ROOM 3248	5 CH			20 Sq Ft
	115	ROOM 3250	5 CH			10 Sq Ft
	123	ROOM 3253	5 CH			15 Sq Ft
	129	ROOM 3252	5 CH			15 Sq Ft
	165	ROOM 4247	5 CH			20 Sq Ft
	171	ROOM 4250	5 CH			20 Sq Ft
	179	ROOM 4255	5 CH			15 Sq Ft
	186	ROOM 4252	5 CH			10 Sq Ft
X0D	Miscellaneous Material Metal Frame Chalkboard Adhesive (1954)					Total Amount - 130 Sq Ft
	224	ROOM 1105	ASSUMED			20 Sq Ft
	233	ROOM 1107	ASSUMED			20 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	242	ROOM 1109	ASSUMED			20 Sq Ft
	308	ROOM 2102	ASSUMED			5 Sq Ft
	320	ROOM 2104	ASSUMED			5 Sq Ft
	332	ROOM 2109	ASSUMED			10 Sq Ft
	336	ROOM 2109A	ASSUMED			10 Sq Ft
	347	ROOM 2111	ASSUMED			20 Sq Ft
	352	ROOM 2113	ASSUMED			20 Sq Ft
X0E	Miscellaneous Material Red Fire Stop					Total Amount - 200 Sq Ft
	3	THROUGHOUT BUILDING	NONE DETECTED	021109ML-59		200 Sq Ft
X0F	Miscellaneous Material Tan Terrazzo-Look Sheet Vinyl					Total Amount - 12 Sq Ft
	244	ROOM 1109	30 CH	021109ML-56		12 Sq Ft
X0G	Miscellaneous Material Green & Cream Marble-Look Sheet Vinyl					Total Amount - 50 Sq Ft
	245	ROOM 1109	NONE DETECTED	021109ML-57		50 Sq Ft
X0H	Miscellaneous Material Yellow Terrazzo-Look Sheet Vinyl					Total Amount - 50 Sq Ft
	223	ROOM 1105	NONE DETECTED	021109ML-55		30 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	235	ROOM 1107	NONE DETECTED			20 Sq Ft
X0I	Miscellaneous Material Metal Frame Chalkboard Adhesive (1966)					Total Amount - 80 Sq Ft
	253	ROOM 1111	ASSUMED			20 Sq Ft
	261	ROOM 1114	ASSUMED			20 Sq Ft
	362	ROOM 2114	ASSUMED			20 Sq Ft
	368	ROOM 2115	ASSUMED			20 Sq Ft
X0J	Miscellaneous Material Gray Terrazzo Sheet Vinyl					Total Amount - 32 Sq Ft
	307	ROOM 2102	NONE DETECTED	021109ML-66		32 Sq Ft
X0K	Miscellaneous Material Gray & Tan Sheet Vinyl					Total Amount - 47 Sq Ft
	319	ROOM 2104	NONE DETECTED	021109ML-90		32 Sq Ft
	346	ROOM 2111	NONE DETECTED			15 Sq Ft
X0L	Miscellaneous Material Beige, White & Blue Sheet Vinyl					Total Amount - 64 Sq Ft
	349	ROOM 2111	NONE DETECTED	021109ML-69		32 Sq Ft
	354	ROOM 2113	NONE DETECTED			32 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
XOM	Miscellaneous Material Tan Sheet Vinyl					Total Amount - 60 Sq Ft
	355	ROOM 2113	NONE DETECTED	021109ML-70		60 Sq Ft
XON	Miscellaneous Material Gray w/Multi-Colored Sheet Vinyl					Total Amount - 60 Sq Ft
	255	ROOM 1111	NONE DETECTED			30 Sq Ft
	263	ROOM 1114	NONE DETECTED	021109ML-89		30 Sq Ft
XOO	Miscellaneous Material Black Damp Proofing					Total Amount - 20 Sq Ft
	249	1966 ADDITION TUNNEL	NONE DETECTED	021109ML-81		20 Sq Ft
XOP	Miscellaneous Material Black Pipe Coating					Total Amount - 100 Sq Ft
	247	1966 ADDITION TUNNEL	NONE DETECTED	021109ML-82		100 Sq Ft
XOQ	Miscellaneous Material Corkboard Adhesive & Plaster					Total Amount - 400 Sq Ft
	5	THROUGHOUT 1924 ORIGINAL BUILDING	NONE DETECTED	072511MV-03	MV-03: ROOM 3248.	400 Sq Ft
XOR	Miscellaneous Material Tan Chalkboard Adhesive					Total Amount - 5 Sq Ft
	103	ROOM 3245	NONE DETECTED	072511MV-02	MV-02: ROOM 3245.	5 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
X0S	Miscellaneous Material Thin Metal Framed Corkboard Adhesive					Total Amount - 340 Sq Ft
	44	1ST FLOOR HALLWAY FROM ROOMS 2243-2254	NONE DETECTED	082112ML-01	ML-01: HALLWAY OUTSIDE LIBRARY.	100 Sq Ft
	48	ROOM 2243	NONE DETECTED			25 Sq Ft
	53	ROOM 2245	NONE DETECTED			75 Sq Ft
	126	2ND FLOOR HALLWAY OUTSIDE ROOM 3252	NONE DETECTED			25 Sq Ft
	188	ROOM 4252	NONE DETECTED			40 Sq Ft
	191	3RD FLOOR HALLWAY OUTSIDE ROOM 4252	NONE DETECTED			25 Sq Ft
	257	ROOM 1116	NONE DETECTED			50 Sq Ft
X0T	Miscellaneous Material Wood Frame Corkboard Adhesive (1941)					Total Amount - 1013 Sq Ft
	52	ROOM 2245	ASSUMED			40 Sq Ft
	58	LIBRARY (2250)	ASSUMED			100 Sq Ft
	97	2ND FLOOR HALLWAY OUTSIDE ROOM 3245	ASSUMED			18 Sq Ft
	104	ROOM 3245	ASSUMED			120 Sq Ft
	110	ROOM 3248	ASSUMED			100 Sq Ft
	116	ROOM 3250	ASSUMED			30 Sq Ft
	119	ROOM 3251	ASSUMED			10 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	124	ROOM 3253	ASSUMED			70 Sq Ft
	130	ROOM 3252	ASSUMED			70 Sq Ft
	162	4TH FLOOR HALLWAY OUTSIDE ROOM 4247	ASSUMED			25 Sq Ft
	166	ROOM 4247	ASSUMED			120 Sq Ft
	172	ROOM 4250	ASSUMED			150 Sq Ft
	180	ROOM 4255	ASSUMED			110 Sq Ft
	187	ROOM 4252	ASSUMED			50 Sq Ft
X0U	Miscellaneous Material Metal Frame Corkboard Adhesive (1954)					Total Amount - 890 Sq Ft
	225	ROOM 1105	ASSUMED			90 Sq Ft
	234	ROOM 1107	ASSUMED			90 Sq Ft
	243	ROOM 1109	ASSUMED			90 Sq Ft
	309	ROOM 2102	ASSUMED			175 Sq Ft
	321	ROOM 2104	ASSUMED			175 Sq Ft
	333	ROOM 2109	ASSUMED			60 Sq Ft
	337	ROOM 2109A	ASSUMED			30 Sq Ft
	348	ROOM 2111	ASSUMED			90 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	353	ROOM 2113	ASSUMED			90 Sq Ft
X0V	Miscellaneous Material Metal Frame Corkboard Adhesive (1966)					Total Amount - 360 Sq Ft
	254	ROOM 1111	ASSUMED			90 Sq Ft
	262	ROOM 1114	ASSUMED			90 Sq Ft
	363	ROOM 2114	ASSUMED			90 Sq Ft
	369	ROOM 2115	ASSUMED			90 Sq Ft
X1A	Miscellaneous Material 6" X 6" Quarry Tile System (2012)					Total Amount - 600 Sq Ft
	214	1954 ADDITION KITCHEN (1102)	NEW			600 Sq Ft
X1B	Miscellaneous Material 6" X 6" Red Quarry Floor Tile System					Total Amount - 900 Sq Ft
	66	1924 ORIGINAL BUILDING EAST STAIRWELL	ASSUMED			900 Sq Ft
X1C	Miscellaneous Material Multi Sized Brown Ceramic Floor Tile System					Total Amount - 830 Sq Ft
	226	RESTROOMS 1104 AND 1106	ASSUMED			350 Sq Ft
	313	RESTROOM 2102B	ASSUMED			40 Sq Ft
	325	RESTROOM 2104B	ASSUMED			40 Sq Ft
	328	BOYS' RESTROOM 2108	ASSUMED			200 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	339	GIRLS' RESTROOM 2110	ASSUMED			200 Sq Ft
X1D	Miscellaneous Material 4" X 4" Teal Ceramic Wall Tile System					Total Amount - 750 Sq Ft
	227	RESTROOM 1104	ASSUMED			350 Sq Ft
	329	BOYS' RESTROOM 2108	ASSUMED			400 Sq Ft
X1E	Miscellaneous Material 4" X 4" Yellow Ceramic Wall Tile System					Total Amount - 630 Sq Ft
	228	RESTROOM 1106	ASSUMED			350 Sq Ft
	295	STAFF ROOM 2307 RESTROOM	ASSUMED			140 Sq Ft
	301	ROOM 2309 RESTROOM	ASSUMED			140 Sq Ft
X1F	Miscellaneous Material 6" X 6" Earth Brown Quarry Floor Tile System (1997)					Total Amount - 170 Sq Ft
	265	GROUND FLOOR ELEVATOR LANDING (1118)	NEW			90 Sq Ft
	296	STAFF ROOM 2307 RESTROOM	NEW			40 Sq Ft
	300	ROOM 2309 RESTROOM	NEW			40 Sq Ft
X1G	Miscellaneous Material 4" X 4" Pink Ceramic Wall Tile System					Total Amount - 400 Sq Ft
	340	GIRLS' RESTROOM 2110	ASSUMED			400 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
X1H		Miscellaneous Material 2" X 2" Brown Ceramic Floor Tile System				Total Amount - 75 Sq Ft
	364	RESTROOM BY ROOM 2116	NEW			75 Sq Ft
X1I		Miscellaneous Material 4" X 4" White with Black Specks Ceramic Wall Tile System				Total Amount - 225 Sq Ft
	365	RESTROOM BY ROOM 2116	NEW			225 Sq Ft