

1363 Bush Avenue, Saint Paul, MN 55106

Chart C - All Materials List

The following list contains all events observed by the inspector, whether or not they actually contained asbestos, and are grouped by homogeneous area (material type).

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
A4C	Mudded Pipe Joints on Fiberglass Insulation 1974 Addition/Installation					Total Amount - 599 Joints
	16	1925 ORIGINAL BUILDING 1ST FLOOR HALLWAY (1000)	NONE DETECTED	091410MV-1	MV-1: 1925 ORIGINAL BUILDING HALLWAY BY ROOM 1301.	10 Joints
	71	ROOM 2201 (1974 ADDITION BOILER ROOM)	NONE DETECTED	070709-ML-01; 2001-1901-PAEW-3A	ML-01: BOILER ROOM.	100 Joints
	79	ROOM 1299A (STAIRS TO 1974 ADDITION BOILER ROOM)	NONE DETECTED			2 Joints
	84	ROOM 1219 (LOADING DOCK)	NONE DETECTED			4 Joints
	85	ROOM 1219A (STORAGE)	NONE DETECTED			2 Joints
	89	ROOM 1217 (NORTH GYMNASIUM STORAGE)	NONE DETECTED			14 Joints
	92	ROOM 1213 (BOYS' LOCKER ROOM)	NONE DETECTED			14 Joints
	93	1974 ADDITION HALLWAY 1200 & 1200A	NONE DETECTED			35 Joints
	94	ROOMS 1207A-1212A	NONE DETECTED	070709ML-03	ML-03: ROOM 1212A ROOF DRAIN.	6 Joints
	95	ROOM 1212 (BOYS' RESTROOM)	NONE DETECTED			5 Joints
	103	ROOM 1207 (HEALTH SERVICES)	NONE DETECTED			8 Joints
	112	ROOM 1206	NONE DETECTED			5 Joints

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	113	ROOM 1203	NONE DETECTED			16 Joints
	115	RESTROOMS 1202/1201	NONE DETECTED			10 Joints
	118	HALLWAY 1000 BY MAIN OFFICE	NONE DETECTED			6 Joints
	120	THROUGHOUT MAIN OFFICE AREA	NONE DETECTED			14 Joints
	122	ROOM 1005	NONE DETECTED			3 Joints
	125	STAIRWELL 1099	NONE DETECTED			7 Joints
	126	HALLWAY 1100	NONE DETECTED			25 Joints
	131	ROOM 1119	NONE DETECTED			4 Joints
	134	ROOMS 1101/1102	NONE DETECTED			30 Joints
	137	ROOM 1103	NONE DETECTED			15 Joints
	139	RESTROOMS 1005/1006	NONE DETECTED			40 Joints
	144	ROOM 1109	NONE DETECTED			16 Joints
	145	ROOM 1111	NONE DETECTED			6 Joints
	146	ROOM 1112	NONE DETECTED	091410MV-2	MV-2: ROOM 1112.	16 Joints
	147	STAIRWELL 1199B	NONE DETECTED			4 Joints
	148	ROOM 1113	NONE DETECTED			18 Joints
	149	ROOM 1114	NONE DETECTED			6 Joints

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	150	ROOM 1115	NONE DETECTED			19 Joints
	151	ROOM 2306 (AHU ROOM)	NONE DETECTED	2001-1901-PAEW-1A		14 Joints
	155	ROOM 2118	NONE DETECTED			14 Joints
	156	ROOM 2102	NONE DETECTED			14 Joints
	157	ROOM 2117	NONE DETECTED			20 Joints
	158	ROOM 2103	NONE DETECTED			20 Joints
	159	2ND FLOOR STAFF RESTROOM BY ROOM 2115 (2104)	NONE DETECTED			8 Joints
	161	ROOM 2109	NONE DETECTED			11 Joints
	162	ROOM 2115	NONE DETECTED			6 Joints
	166	ROOM 2114	NONE DETECTED			7 Joints
	167	ROOM 2113	NONE DETECTED			8 Joints
	168	ROOM 2112	NONE DETECTED			7 Joints
	169	ROOM 2111	NONE DETECTED			10 Joints
D1A	Boiler Gaskets Door (LES Boiler)					Total Amount - 3 Sq Ft
	72	ROOM 2201 (1974 ADDITION BOILER ROOM)	NONE DETECTED	091410MV-37	MV-37: 1974 ADDITION BOILER ROOM.	3 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
D1B	Boiler Gaskets White Woven					Total Amount - 2 Sq Ft
	73	ROOM 2201 (1974 ADDITION BOILER ROOM)	55 CH	091410MV-38	MV-38: 1974 ADDITION BOILER ROOM.	2 Sq Ft
D2C	Interior Boiler Insulation LES Boiler Refractory					Total Amount - 20 Sq Ft
	74	ROOM 2201 (1974 ADDITION BOILER ROOM)	ASSUMED			20 Sq Ft
D2D	Interior Boiler Insulation Burnham Boiler Refractory					Total Amount - 50 Sq Ft
	75	ROOM 2201 (1974 ADDITION BOILER ROOM)	ASSUMED			50 Sq Ft
E0A	Stack Insulation Burnham Boiler					Total Amount - 10 Sq Ft
	76	ROOM 2201 (1974 ADDITION BOILER ROOM)	NONE DETECTED	091410MV-7; 2001-1901-PE-1D, 2D, 3D	MV-7: 1974 ADDITION BOILER ROOM.	10 Sq Ft
G1A	Sprayed-On Acoustical Finish White, Fluffy					Total Amount - 7000 Sq Ft
	86	ROOM 1215 (GYMNASIUM)	NONE DETECTED	080513BF-01, 02, 03	BF-01,02,03: GYMNASIUM.	7000 Sq Ft
I1A	1' x 1' Acoustical Ceiling Tile Fissures					Total Amount - 5340 Sq Ft
	27	ROOM 3303	NONE DETECTED			670 Sq Ft
	32	ROOM 3301	NONE DETECTED			670 Sq Ft
	48	ROOM 1308	NONE DETECTED	207512A	ROOM 1222 (KITCHEN STORAGE) (SINCE REMOVED).	200 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	53	ROOM 1311	NONE DETECTED	070709ML-4	ML-4: ROOM 1317 (SINCE REMOVED)..	100 Sq Ft
	55	1958 ADDITION HALLWAY 1300B	NONE DETECTED	207J-12A		1300 Sq Ft
	58	ROOM 1312 (ALL PURPOSE ROOM)	NONE DETECTED	12213BF-7	BF-7: ROOM 1315 (SINCE REMOVED).	2400 Sq Ft
I2A	2' x 2' Acoustical Ceiling Tile Revealed Edge					Total Amount - 1000 Sq Ft
	121	THROUGHOUT MAIN OFFICE AREA	NONE DETECTED	091410MV-6	MV-6: ROOM 1001.	1000 Sq Ft
I2B	2' x 2' Acoustical Ceiling Tile Light Texture w/Revealed Edge (2011)					Total Amount - 2400 Sq Ft
	57	ROOM 1312 (ALL PURPOSE ROOM)	NEW			2400 Sq Ft
I2C	2' x 2' Acoustical Ceiling Tile Light Texture w/Revealed Edge (2013)					Total Amount - 40130 Sq Ft
	1	THROUGHOUT BUILDING	NEW			20000 Sq Ft
	50	ROOM 1309	NEW			130 Sq Ft
	69	THROUGHOUT 1974 ADDITION	NEW			20000 Sq Ft
I2D	2' x 2' Acoustical Ceiling Tile Cloth-Covered Fiberglass					Total Amount - 20000 Sq Ft
	2	THROUGHOUT BUILDING	NSM			20000 Sq Ft
I2E	2' x 2' Acoustical Ceiling Tile Vinyl-Covered Sheetrock					Total Amount - 1407 Sq Ft
	41	GIRLS' RESTROOM 1307	NSM			200 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	43	DISHWASHING ROOM 1319	NSM			135 Sq Ft
	46	CAFETERIA STORAGE 1316	NSM			72 Sq Ft
	65	KITCHEN	NSM			1000 Sq Ft
I3A	2' x 4' Ceiling Tile Gouges, Nail & Pin Holes		Total Amount - 10000 Sq Ft			
	68	THROUGHOUT 1974 ADDITION	NONE DETECTED	12213BF-2; 091410MV-40; 207J-11A	BF-2: ROOM 2119. MV-40: HALLWAY BY ROOM 1110. 11A: MAIN OFFICE (SINCE REMOVED).	10000 Sq Ft
I3B	2' x 4' Ceiling Tile Widthwise Fissures		Total Amount - 300 Sq Ft			
	62	ROOM 1313 (OLD STAGE)	NONE DETECTED	2001-1504-R3		300 Sq Ft
I3C	2' x 4' Ceiling Tile Vinyl-Coated Sheetrock		Total Amount - 400 Sq Ft			
	81	ROOM 1221 (KITCHEN)	NSM			400 Sq Ft
I3D	2' x 4' Ceiling Tile Small Pockmarks & Pin Holes		Total Amount - 142 Sq Ft			
	31	ROOM 3304A/3304	NONE DETECTED	091410MV-5	MV-5: HALLWAY 1000 (SINCE REMOVED).	100 Sq Ft
	143	ROOM 1108	NONE DETECTED			42 Sq Ft
I3E	2' x 4' Ceiling Tile Pockmarks w/Nail & Pin Holes		Total Amount - 1302 Sq Ft			
	19	ROOM 1302/1303	NEW			240 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	104	ROOM 1207 (HEALTH SERVICES)	NEW			400 Sq Ft
	107	ROOM 1204	NEW			136 Sq Ft
	111	ROOM 1206	NEW			64 Sq Ft
	123	ROOM 1005	NEW			240 Sq Ft
	128	RESTROOM 1121	NEW			180 Sq Ft
	165	ROOM 2108	NEW			42 Sq Ft
I3F	2' x 4' Ceiling Tile Fiberglass					Total Amount - 150 Sq Ft
	114	ROOM 1203	NSM			150 Sq Ft
K2D	12" x 12" Vinyl Floor Tile & Mastic White w/Gray					Total Amount - 3065 Sq Ft
	60	ROOM 1312 (ALL PURPOSE ROOM)	NONE DETECTED	12213BF-9; 091410MV-24	BF-9: CAFETERIA. MV-24: CAFETERIA 1312.	2400 Sq Ft
	63	ROOM 1313 (OLD STAGE)	NONE DETECTED	12213BF-10; 091410MV-28	BF-10: 3RD FLOOR HALLWAY. MV-28: HALLWAY 3300.	9 Sq Ft
	105	ROOM 1207 (HEALTH SERVICES)	NONE DETECTED	091410MV-29	MV-29: HALLWAY 1300B (SINCE REMOVED).	400 Sq Ft
	108	ROOM 1204	NONE DETECTED	091410MV-29	MV-29: HALLWAY 1300B (SINCE REMOVED).	136 Sq Ft
	142	ROOM 1107	NONE DETECTED	12213BF-4, 5	BF-4: ROOM 1119 (LOUNGE) (SINCE REMOVED). BF-5: 1ST FLOOR HALLWAY BY ROOM 1115 (SINCE REMOVED).	120 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
K3A	Miscellaneous Flooring 24" x 24" Tan Speckled Rubber (2013)					Total Amount - 20336 Sq Ft
	3	THROUGHOUT BUILDING	NEW			20000 Sq Ft
	132	ROOM 1119	NEW			336 Sq Ft
K3B	Miscellaneous Flooring Beige Rubber Flooring (2014)					Total Amount - 5000 Sq Ft
	87	ROOM 1215	NEW			5000 Sq Ft
L0C	Flexible Duct Connector Canvas					Total Amount - 4 Sq Ft
	14	ROOM 0320A (FAN ROOM)	NONE DETECTED	091410MV-12	MV-12: ROOM 0320A (FAN ROOM).	4 Sq Ft
L0D	Flexible Duct Connector Green Canvas					Total Amount - 2 Sq Ft
	61	ROOM 1313	NONE DETECTED	2001-0301-JC-13		2 Sq Ft
L0E	Flexible Duct Connector Black Vinyl					Total Amount - 32 Sq Ft
	77	ROOM 2201 (1974 ADDITION BOILER ROOM)	NSM			20 Sq Ft
	152	ROOM 2306 (AHU ROOM)	NSM			12 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
M0A	Plaster 1925 Original Building	Total Amount - 20000 Sq Ft				
	9	THROUGHOUT 1925 ORIGINAL BUILDING	NONE DETECTED	091410MV-13, 14, 15, 16, 17, 18; 51003	MV-13,14: HALLWAY BY ROOM 2301. MV-15,16: HALLWAY BY ROOM 3301. MV-17: HALLWAY BY ROOM 1302. MV-18: HALLWAY BY ROOM 1301.	20000 Sq Ft
M0AA	Plaster Plaster Patch	Total Amount - 4 Sq Ft				
	20	ROOM 1302	NONE DETECTED	073123BF-2, 3	BF-2,3: ROOM 1302.	4 Sq Ft
M0B	Plaster 1958 Addition	Total Amount - 900 Sq Ft				
	37	THROUGHOUT 1958 ADDITION	NONE DETECTED	091410MV-19, 20; 538-3	MV-19: ROOM 1312B. MV-20: HALLWAY BY ROOM 1316.	900 Sq Ft
N0A	Drywall/Joint Compound 1925 Original Building	Total Amount - 5000 Sq Ft				
	10	THROUGHOUT 1925 ORIGINAL BUILDING	<1 CH (COMPOSITE)	091410MV-21, 22, 23	MV-21: HALLWAY BY ROOM 2301. MV-22: HALLWAY BY ROOM 1301. MV-23: HALLWAY BY ROOM 3301.	5000 Sq Ft
N0B	Drywall/Joint Compound 1958 Addition	Total Amount - 1000 Sq Ft				
	38	THROUGHOUT 1958 ADDITION	NONE DETECTED	538-1		1000 Sq Ft
N0C	Drywall/Joint Compound 1974 Addition	Total Amount - 15000 Sq Ft				
	67	THROUGHOUT 1974 ADDITION	NONE DETECTED	2001-1501-N1	N1: ROOM 2306.	15000 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
P0A	Fire Doors Pieced Metal w/ Solid Wood Core					Total Amount - 60 Sq Ft
	12	ROOM 0320 (1925 ORIGINAL BUILDING BOILER ROOM)	NSM			60 Sq Ft
P0B	Fire Doors Hollow Metal -1.5 Hr Rating (Underwriters Laboratories)					Total Amount - 20 Sq Ft
	80	ROOM 1299A (STAIRS TO 1974 ADDITION BOILER ROOM)	NSM			20 Sq Ft
P0C	Fire Doors Composite -1.5 Hr Rating (Underwriters Laboratories)					Total Amount - 20 Sq Ft
	98	CUSTODIAL CLOSET 1211	ASSUMED			20 Sq Ft
Q0A	Carpet Adhesive					Total Amount - 2000 Sq Ft
	4	THROUGHOUT BUILDING	NONE DETECTED	12213-BF-11; 091410MV-8, 9; 2001- 1901-PW-1	BF-11: ROOM 2101. MV-8: ROOM 1311. MV-9: ROOM 3302.	2000 Sq Ft
Q0B	Carpet Adhesive Multi-Colored Carpet Squares (2013)					Total Amount - 15000 Sq Ft
	5	THROUGHOUT BUILDING	NEW			15000 Sq Ft
Q0C	Carpet Adhesive 2' X 2' Red Grey Striped Carpet Squares (202x)					Total Amount - 12240 Sq Ft
	99	MEDIA CENTER 1208	NEW			2000 Sq Ft
	124	ROOM 1005	NEW			240 Sq Ft
	127	THROUGHOUT THE 1100 CLASSROOMS	NEW			5000 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	153	THROUGHOUT 2100 CLASSROOM	NEW			5000 Sq Ft
ROA	Baseboard/Mopboard Adhesive 3" Brown Baseboard					Total Amount - 50 Sq Ft
	6	THROUGHOUT BUILDING	NONE DETECTED	091410MV-32	MV-32: HALLWAY 1300B.	50 Sq Ft
ROB	Baseboard/Mopboard Adhesive 4" Brown Baseboard					Total Amount - 100 Sq Ft
	7	THROUGHOUT BUILDING	NONE DETECTED	2001-1901-ZZ-36C		100 Sq Ft
ROC	Baseboard/Mopboard Adhesive 4" Gray Baseboard (201x)					Total Amount - 200 Sq Ft
	8	THROUGHOUT BUILDING	NEW			200 Sq Ft
ROD	Baseboard/Mopboard Adhesive 6" Black Baseboard (2014)					Total Amount - 210 Sq Ft
	88	ROOM 1215	NEW			200 Sq Ft
	91	SOUTH GYMNASIUM STORAGE 1214	NEW			10 Sq Ft
ROE	Baseboard/Mopboard Adhesive 4" Black Baseboard (2014)					Total Amount - 60 Sq Ft
	90	ROOM 1217 (NORTH GYMNASIUM STORAGE)	NEW			10 Sq Ft
	100	MEDIA CENTER 1208	NEW			50 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
R0F	Baseboard/Mopboard Adhesive 6" Blue Baseboard					Total Amount - 13 Sq Ft
	102	HALLWAY FROM NURSE'S OFFICE 1207 TO MAIN ENTRY HALLWAY 1000C	ASSUMED			13 Sq Ft
S0A	Wood Floor Felt / Vapor Barrier 1925 Original Building					Total Amount - 5000 Sq Ft
	11	THROUGHOUT 1925 ORIGINAL BUILDING	ASSUMED			5000 Sq Ft
V0B	Sink Undercoating Black					Total Amount - 36 Sq Ft
	51	ROOM 1310	5 CH			5 Sq Ft
	106	ROOM 1207 (HEALTH SERVICES)	5 CH			5 Sq Ft
	133	ROOM 1119	5 CH			6 Sq Ft
	135	ROOM 1101	5 CH			10 Sq Ft
	136	ROOM 1102	5 CH	2001-1504-R2	ROOM 1109 (SINCE REMOVED).	5 Sq Ft
	138	ROOM 1103	5 CH			5 Sq Ft
V0C	Sink Undercoating Gray					Total Amount - 12 Sq Ft
	36	ROOM 3301	ASSUMED			6 Sq Ft
	154	ROOM 2307	ASSUMED			6 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
W1A	1' x 1' Ceiling Tile Adhesive Associated w/I1A					Total Amount - 1325 Sq Ft
	28	ROOM 3303	NONE DETECTED			150 Sq Ft
	33	ROOM 3301	NONE DETECTED			200 Sq Ft
	49	ROOM 1308	NONE DETECTED			50 Sq Ft
	54	ROOM 1311	NONE DETECTED			25 Sq Ft
	56	1958 ADDITION HALLWAY 1300B	NONE DETECTED	073123BF-1; 070709ML-4	BF-1: 1958 ADDITION HALLWAY 1300B. ML-4: ROOM 1317 (SINCE REMOVED).	300 Sq Ft
	59	ROOM 1312 (ALL PURPOSE ROOM)	NONE DETECTED			600 Sq Ft
X0A	Miscellaneous Material Brown Adhesive					Total Amount - 8 Sq Ft
	15	ROOM 0320B (STORAGE)	NONE DETECTED	091410MV-35	MV-35: ROOM 0320B.	8 Sq Ft
X0B	Miscellaneous Material Pipe/Valve Flange Gaskets					Total Amount - 20 Sq Ft
	13	ROOM 0320 (1925 ORIGINAL BUILDING BOILER ROOM)	ASSUMED			10 Sq Ft
	78	ROOM 2201 (1974 ADDITION BOILER ROOM)	ASSUMED			10 Sq Ft
X0C	Miscellaneous Material Wood Frame Chalkboard Adhesive					Total Amount - 105 Sq Ft
	17	ROOM 1304	ASSUMED			20 Sq Ft
	21	ROOM 1301	ASSUMED			20 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
	23	ROOM 2303	ASSUMED			20 Sq Ft
	25	ROOM 2301	ASSUMED			20 Sq Ft
	29	ROOM 3303	ASSUMED			20 Sq Ft
	34	ROOM 3301	ASSUMED			5 Sq Ft
X0D	Miscellaneous Material Wood Frame Corkboard Adhesive					Total Amount - 90 Sq Ft
	18	ROOM 1304	ASSUMED			20 Sq Ft
	22	ROOM 1301	ASSUMED			5 Sq Ft
	24	ROOM 2303	ASSUMED			20 Sq Ft
	26	ROOM 2301	ASSUMED			20 Sq Ft
	30	ROOM 3303	ASSUMED			20 Sq Ft
	35	ROOM 3301	ASSUMED			5 Sq Ft
X0E	Miscellaneous Material Milkboard Adhesive					Total Amount - 200 Sq Ft
	45	DISHWASHING ROOM 1319	ASSUMED			200 Sq Ft
X0F	Miscellaneous Material Wood Grain Look Countertop					Total Amount - 10 Sq Ft
	52	ROOM 1310	ASSUMED			10 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
X0G	Miscellaneous Material Red Fire Stop					Total Amount - 20 Sq Ft
	70	THROUGHOUT 1974 ADDITION	ASSUMED			20 Sq Ft
X1A	Miscellaneous Material 6" Red Quarry Tile System					Total Amount - 2449 Sq Ft
	44	DISHWASHING ROOM 1319	ASSUMED			135 Sq Ft
	47	CAFETERIA STORAGE 1316	ASSUMED			72 Sq Ft
	64	CUSTODIAL OFFICE & HALLWAY (1312A/B)	ASSUMED			192 Sq Ft
	66	KITCHEN	ASSUMED			1000 Sq Ft
	82	ROOM 1221 (KITCHEN)	ASSUMED			500 Sq Ft
	83	ROOM 1223 (KITCHEN OFFICE)	ASSUMED			50 Sq Ft
	119	HALLWAY 1000 BY MAIN OFFICE	ASSUMED			500 Sq Ft
X1B	Miscellaneous Material 1" X 1" Multi-Shaded Brown Ceramic Floor Tile System					Total Amount - 240 Sq Ft
	96	ROOM 1212 (BOYS' RESTROOM)	ASSUMED			100 Sq Ft
	97	ROOM 1217 (GIRLS' RESTROOM)	ASSUMED			100 Sq Ft
	109	RESTROOM 1205 OFF OF ROOM 1204	ASSUMED			40 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
X1C	Miscellaneous Material 1" Blue Multi-Shaded Ceramic Floor Tile System					Total Amount - 300 Sq Ft
	116	RESTROOMS 1202/1201	ASSUMED			300 Sq Ft
X1D	Miscellaneous Material 4" Blue Ceramic Wall Tile System					Total Amount - 500 Sq Ft
	117	RESTROOMS 1202/1201	ASSUMED			500 Sq Ft
X1E	Miscellaneous Material 1" X 1" Multi-Shaded Yellow Ceramic Floor Tile System					Total Amount - 1075 Sq Ft
	140	RESTROOMS 1005/1006	ASSUMED			500 Sq Ft
	160	2ND FLOOR STAFF RESTROOM BY ROOM 2115 (2104)	ASSUMED			25 Sq Ft
	163	2ND FLOOR RESTROOMS BY ROOM 2115	ASSUMED			550 Sq Ft
X1F	Miscellaneous Material 4" X 4" Yellow Ceramic Wall Tile System					Total Amount - 1405 Sq Ft
	110	RESTROOM 1205 OFF OF ROOM 1204	ASSUMED			5 Sq Ft
	141	RESTROOMS 1005/1006	ASSUMED			700 Sq Ft
	164	2ND FLOOR RESTROOMS BY ROOM 2115	ASSUMED			700 Sq Ft
X1G	Miscellaneous Material Multi-Sized Light Gray w/Colored Accent Tiles Ceramic Floor Tile System					Total Amount - 250 Sq Ft
	39	BOYS' RESTROOM 1305	ASSUMED			250 Sq Ft

Homogeneous Area ID Code (Material Type)	IEA Event No.	Location	% Asbestos	Sample No.	Sample Location	Estimated Total Amount
X1H		Miscellaneous Material 4" X 4" Beige Ceramic Wall Tile System				Total Amount - 500 Sq Ft
	40	BOYS' RESTROOM 1305	ASSUMED			150 Sq Ft
	42	GIRLS' RESTROOM 1307	ASSUMED			350 Sq Ft
X1I		Miscellaneous Material 4" Multicolored Ceramic Wall Tile System				Total Amount - 190 Sq Ft
	101	HALLWAY FROM NURSE'S OFFICE 1207 TO MAIN ENTRY HALLWAY 1000C	ASSUMED			190 Sq Ft
X1J		Miscellaneous Material 2" X 2" Purple Ceramic Floor Tile System (2014)				Total Amount - 180 Sq Ft
	129	RESTROOM 1121	NEW			180 Sq Ft
X1K		Miscellaneous Material 4" X 4" Light Gray Ceramic Wall Tile System (2014)				Total Amount - 200 Sq Ft
	130	RESTROOM 1121	NEW			200 Sq Ft