

SECTION 00 9113 – ADDENDUM NO. 2

**Central Middle School
Greenwich, Connecticut**

S/L/A/M Project No. 22367.00

This Addendum, dated February 14, 2025, forms a part of the Contract Documents, and modifies the original Bidding Documents dated January 30th, 2025. Acknowledge receipt of this Addendum in the space provided on the Bid Form. Failure to do so may subject the Bidder to disqualification.

This Addendum is comprised of the following updates to:

1.1 BID RFI LOG (GCMS Phase 2- Bidders Question Log- Dated 2/14/25)

END OF DOCUMENT 00 9113 - ADDENDUM No. 2



GCMS Phase 2 - Bidder's Question Log

2/14/2025

Bidder Question Due Date: 2/10/2025

BQ #	Responsible Consultant	Reference	Date	Question	Answer	Date Item Responded	Answered By (Name / Company)	Attachment (SK# or Spec Section)	Date Closed	Status ("Closed")
1	SLAM	1B/A641	1/28/25	Detail 1B on A641 shows two arrows pointing to a vertical and horizontal line indicating "through wall flashing over aluminum sill flashing, 2-piece flashing/ plate sill". Then another line to the same horizontal line noting the "metal sill flashing". It also indicates for us to then go to detail 1A A 502. This detail looks to be similar but for a different condition.	The reference to the SIM detail is about placement of the through-wall (on-top) and the projected sill (on the bottom) and the mastics and butyl sealants required to complete the detail. See additional response below. TURNER: Following corresponding responses in BQ #2,3,4	1/29/2025	SLAM		2/11/2025	Closed
2	SLAM	1B/A641	1/28/25	Is the through flashing at Detail 1B/A641 two separate pieces that overlap on the horizontal or vertical area?	As noted on 1B/A641, these are two separate pieces, and they overlap on the horizontal.	1/29/2025	SLAM		2/11/2025	Closed
3	SLAM	1B/A641	1/28/25	Is the metal sill supposed to go underneath the through flashing at Detail 1B/A641?	As shown on the SIM detail, 1A/A502, the through-wall is on-top. This places the aluminum plate sill underneath the metal through-wall flashing.	1/29/2025	SLAM		2/11/2025	Closed
4	SLAM	1B/A641	1/28/25	Confirming that the metal sill is a separate material vs the through flashing?	Yes, as noted on 1B/A641, the metal sill at this detail is intended to be painted aluminum plate material and the through-wall is intended to be stainless steel.	1/29/2025	SLAM		2/11/2025	Closed
5	Turner	Invite to Bid	2/3/25	Are there any addenda on this project? What is the current bid date?	All current drawings are provided in the files folder of Building Connected. The bid due date information is located on the Invited to Bid document in 00-Project Manual folder. Addendum 1 will be issued to include the updated CT prevailing Wage rates.	2/3/2025	Turner		2/6/2025	Closed
6	Turner	Invite to Bid	2/6/25	Can the same bid bond be used for this 2/21 bid that was used in the first bid round (11/19)?	A seperate bid bond shall be included within the bid at the time of submission.	2/13/2025	Turner		2/13/2025	Closed
7										
8										