



August 26, 2021

Zach Nannestad
Douglas County School District
2812 N. Highway 85
Castle Rock, CO 80109

**Re: Douglas County High School
2842 Front Street in Castle Rock, CO 80104
August 2021 Follow-Up Radon Sampling Assessment**

Dear Mr. Nannestad:

Quality Environmental Services & Technologies Inc. (QUEST) is pleased to assist Douglas County School District with the ongoing radon survey of its schools. At your request, QUEST conducted follow-up radon testing at Douglas County High School, located at 2842 Front Street in Castle Rock, Colorado.

Three hundred and forty-seven (347) AirChek radon test kits were placed on June 1, 2020 and were retrieved on June 4, 2020. The attached laboratory report identifies the radon concentrations in three (3) of the sampled locations in the South building were above the EPA guideline of 4 pCi/L for acceptable radon concentrations: Faculty Lounge, Room 105, and the Theater Office. The detected radon concentrations in all other tested locations were below the EPA guideline. QUEST recommended that further radon mitigation efforts be undertaken, including inspection of the ventilation system. At your request, QUEST conducted follow-up radon testing in August 2021, at a time in which the school was occupied and the ventilation system was operational.

On August 18, 2021, QUEST placed four (4) AirChek radon test kits (including 1 duplicate) in the Faculty Lounge, Room 105, and the Theater Office. The test kits were retrieved on August 20, 2021. The attached laboratory report identifies that radon concentrations in all tested locations now meet the EPA guideline of 4 pCi/L for acceptable radon concentrations. As such, no additional mitigation or sampling is needed.

If you have any questions, or if we may be of additional assistance, please contact QUEST, Inc. at 303-935-1573. We look forward to our continued association.

Sincerely,

A handwritten signature in black ink, appearing to read "Robert A. Woellner".

Robert A. Woellner
Senior Scientist
NEHA: NRPP Certification #105324RT

A handwritten signature in black ink, appearing to read "Anatole Konowal".

Anatole Konowal
Project Manager

Attachment: Laboratory Report

Radon test result report for:
**DC HIGH SCHOOL
 NORTH**

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
9385380	30	2020-06-01 @ 9:00 am	2020-06-04 @ 9:00 am	< 0.3	2020-06-09
9385305	ART OFFICE	2020-06-01 @ 10:00 am	2020-06-04 @ 10:00 am	< 0.3	2020-06-09
9385492	ATHLETICS CONF. RM	2020-06-01 @ 11:00 am	2020-06-04 @ 11:00 am	< 0.3	2020-06-09
9385475	AV CONF. RM	2020-06-01 @ 11:00 am	2020-06-04 @ 11:00 am	< 0.3	2020-06-09
9385420	BACK IMPACT LAB	2020-06-01 @ 11:00 am	2020-06-04 @ 10:00 am	< 0.3	2020-06-09
9385477	BACK LAB	2020-06-01 @ 11:00 am	2020-06-04 @ 10:00 am	0.9 ± 0.4	2020-06-09
9385312	BACK LEFT RM	2020-06-01 @ 10:00 am	2020-06-04 @ 9:00 am	< 0.3	2020-06-09
9385392	BACK OF DARK RM	2020-06-01 @ 10:00 am	2020-06-04 @ 10:00 am	< 0.3	2020-06-09
9385339	BACK OFFICE	2020-06-01 @ 10:00 am	2020-06-04 @ 10:00 am	< 0.3	2020-06-09
9385430	BACK OFFICE	2020-06-01 @ 11:00 am	2020-06-04 @ 10:00 am	0.8 ± 0.4	2020-06-09
9385311	BACK RIGHT RM	2020-06-01 @ 10:00 am	2020-06-04 @ 9:00 am	< 0.3	2020-06-09
9385374	BAND	2020-06-01 @ 9:00 am	2020-06-04 @ 9:00 am	0.8 ± 0.4	2020-06-09
9385379	BAND	2020-06-01 @ 9:00 am	2020-06-04 @ 8:00 am	< 0.3	2020-06-09
9385382	BAND OFFICE	2020-06-01 @ 9:00 am	2020-06-04 @ 9:00 am	0.8 ± 0.4	2020-06-09
9385175	BIG OFFICE	2020-06-01 @ 1:00 pm	2020-06-04 @ 12:00 pm	< 0.3	2020-06-09
9385402	BIKE RM	2020-06-01 @ 1:00 pm	2020-06-04 @ 12:00 pm	< 0.3	2020-06-09
9385347	BOILER OFFICE	2020-06-01 @ 9:00 am	2020-06-04 @ 8:00 am	< 0.3	2020-06-09
9385363	BOYS DRESSING	2020-06-01 @ 9:00 am	2020-06-04 @ 8:00 am	< 0.3	2020-06-09
9385178	CAF. SERVING AREA	2020-06-01 @ 1:00 pm	2020-06-04 @ 12:00 pm	< 0.3	2020-06-09
9385189	CAFETERIA	2020-06-01 @ 1:00 pm	2020-06-04 @ 12:00 pm	1.0 ± 0.4	2020-06-09
9385177	CAFETERIA	2020-06-01 @ 1:00 pm	2020-06-04 @ 12:00 pm	0.6 ± 0.4	2020-06-09
9385416	CAMPBELL OFFICE	2020-06-01 @ 12:00 pm	2020-06-04 @ 12:00 pm	< 0.3	2020-06-09
9385183	CONCESSIONS	2020-06-01 @ 1:00 pm	2020-06-04 @ 12:00 pm	< 0.3	2020-06-09
9385446	CONF. OFFICE RIGHT	2020-06-01 @ 11:00 am	2020-06-04 @ 11:00 am	0.6 ± 0.4	2020-06-09
9385354	CONF. RM	2020-06-01 @ 9:00 am	2020-06-04 @ 9:00 am	< 0.3	2020-06-09
9385439	COPY RM	2020-06-01 @ 12:00 pm	2020-06-04 @ 12:00 pm	0.7 ± 0.4	2020-06-09
9385436	CORNER RIGHT	2020-06-01 @ 11:00 am	2020-06-04 @ 11:00 am	< 0.3	2020-06-09
9385353	COUNSELING 2	2020-06-01 @ 9:00 am	2020-06-04 @ 9:00 am	< 0.3	2020-06-09
9385350	COUNSELING 3	2020-06-01 @ 9:00 am	2020-06-04 @ 9:00 am	< 0.3	2020-06-09
9385376	COUNSELING 4	2020-06-01 @ 9:00 am	2020-06-04 @ 9:00 am	< 0.3	2020-06-09
9385393	COUNSELING 5	2020-06-01 @ 10:00 am	2020-06-04 @ 9:00 am	< 0.3	2020-06-09
9385335	COUNSELING 5	2020-06-01 @ 10:00 am	2020-06-04 @ 9:00 am	< 0.3	2020-06-09
9385394	COUNSELING 6	2020-06-01 @ 9:00 am	2020-06-04 @ 9:00 am	< 0.3	2020-06-09
9385361	COUNSELING 7	2020-06-01 @ 9:00 am	2020-06-04 @ 9:00 am	< 0.3	2020-06-09
9385385	COUNSELING 8	2020-06-01 @ 9:00 am	2020-06-04 @ 9:00 am	< 0.3	2020-06-09
9385342	CUSTODIAL	2020-06-01 @ 8:00 am	2020-06-04 @ 8:00 am	< 0.3	2020-06-09
9385182	CUSTODIAN OFFICE	2020-06-01 @ 1:00 pm	2020-06-04 @ 12:00 pm	< 0.3	2020-06-09

Radon test result report for:
**DC HIGH SCHOOL
 NORTH**

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
9385185	CUSTODIAN OFFICE	2020-06-01 @ 1:00 pm	2020-06-04 @ 12:00 pm	0.7 ± 0.4	2020-06-09
9385186	CUSTODIAN OFFICE	2020-06-01 @ 1:00 pm	2020-06-04 @ 12:00 pm	< 0.3	2020-06-09
9385184	CUSTODIAN SHOP	2020-06-01 @ 1:00 pm	2020-06-04 @ 12:00 pm	0.8 ± 0.4	2020-06-09
9385307	DARK RM 45	2020-06-01 @ 10:00 am	2020-06-04 @ 10:00 am	0.5 ± 0.4	2020-06-09
9385388	DECA	2020-06-01 @ 10:00 am	2020-06-04 @ 10:00 am	< 0.3	2020-06-09
9385482	DVD RM	2020-06-01 @ 11:00 am	2020-06-04 @ 11:00 am	0.9 ± 0.4	2020-06-09
9385414	F101	2020-06-01 @ 11:00 am	2020-06-04 @ 11:00 am	2.2 ± 0.5	2020-06-09
9385417	F101	2020-06-01 @ 11:00 am	2020-06-04 @ 11:00 am	1.0 ± 0.4	2020-06-09
9385470	F101A OFFICE	2020-06-01 @ 11:00 am	2020-06-04 @ 11:00 am	0.7 ± 0.4	2020-06-09
9385458	F102	2020-06-01 @ 11:00 am	2020-06-04 @ 11:00 am	0.7 ± 0.4	2020-06-09
9385493	F102A	2020-06-01 @ 11:00 am	2020-06-04 @ 11:00 am	< 0.3	2020-06-09
9385494	F106	2020-06-01 @ 11:00 am	2020-06-04 @ 11:00 am	< 0.3	2020-06-09
9385473	F109 GYM	2020-06-01 @ 11:00 am	2020-06-04 @ 11:00 am	0.9 ± 0.4	2020-06-09
9385466	F109 GYM	2020-06-01 @ 11:00 am	2020-06-04 @ 11:00 am	0.6 ± 0.4	2020-06-09
9385481	F109 GYM	2020-06-01 @ 11:00 am	2020-06-04 @ 11:00 am	1.3 ± 0.4	2020-06-09
9385474	F109 GYM	2020-06-01 @ 11:00 am	2020-06-04 @ 11:00 am	0.6 ± 0.4	2020-06-09
9385489	F109 GYM	2020-06-01 @ 11:00 am	2020-06-04 @ 11:00 am	1.0 ± 0.4	2020-06-09
9385480	F111 GYM	2020-06-01 @ 11:00 am	2020-06-04 @ 11:00 am	< 0.3	2020-06-09
9385488	F111 GYM	2020-06-01 @ 12:00 pm	2020-06-04 @ 11:00 am	< 0.3	2020-06-09
9385498	F111 GYM	2020-06-01 @ 12:00 pm	2020-06-04 @ 11:00 am	< 0.3	2020-06-09
9385479	F111 GYM	2020-06-01 @ 12:00 pm	2020-06-04 @ 11:00 am	< 0.3	2020-06-09
9385487	F111 GYM	2020-06-01 @ 11:00 am	2020-06-04 @ 11:00 am	< 0.3	2020-06-09
9385497	F111 GYM	2020-06-01 @ 12:00 pm	2020-06-04 @ 11:00 am	< 0.3	2020-06-09
9385471	F114 B WRESTLING	2020-06-01 @ 12:00 pm	2020-06-04 @ 11:00 am	1.7 ± 0.5	2020-06-09
9385370	GIRLS DRESSING	2020-06-01 @ 9:00 am	2020-06-04 @ 8:00 am	< 0.3	2020-06-09
9385362	GIRLS DRESSING	2020-06-01 @ 9:00 am	2020-06-04 @ 8:00 am	0.6 ± 0.4	2020-06-09
9385386	HAY OFFICE	2020-06-01 @ 9:00 am	2020-06-04 @ 9:00 am	< 0.3	2020-06-09
9385348	HOME EC FOOD RM	2020-06-01 @ 9:00 am	2020-06-04 @ 8:00 am	< 0.3	2020-06-09
9385349	HOME EC OFFICE	2020-06-01 @ 9:00 am	2020-06-04 @ 8:00 am	< 0.3	2020-06-09
9385338	HOME EC RM 1	2020-06-01 @ 9:00 am	2020-06-04 @ 8:00 am	< 0.3	2020-06-09
9385358	HOME EC RM 1	2020-06-01 @ 9:00 am	2020-06-04 @ 8:00 am	< 0.3	2020-06-09
9385337	HOME EC RM 1	2020-06-01 @ 9:00 am	2020-06-04 @ 8:00 am	< 0.3	2020-06-09
9385357	HOME EC RM 1	2020-06-01 @ 9:00 am	2020-06-04 @ 8:00 am	< 0.3	2020-06-09
9385345	KEYBOARD RM	2020-06-01 @ 9:00 am	2020-06-04 @ 9:00 am	0.7 ± 0.4	2020-06-09
9385200	KITCHEN	2020-06-01 @ 1:00 pm	2020-06-04 @ 12:00 pm	< 0.3	2020-06-09
9385199	KITCHEN OFFICE	2020-06-01 @ 1:00 pm	2020-06-04 @ 12:00 pm	1.2 ± 0.4	2020-06-09
9385462	LEFT LEFT	2020-06-01 @ 11:00 am	2020-06-04 @ 11:00 am	0.7 ± 0.4	2020-06-09

Radon test result report for:
**DC HIGH SCHOOL
 NORTH**

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
9385469	LEFT RIGHT	2020-06-01 @ 11:00 am	2020-06-04 @ 11:00 am	0.6 ± 0.4	2020-06-09
9385486	LIBRARY	2020-06-01 @ 11:00 am	2020-06-04 @ 11:00 am	0.7 ± 0.4	2020-06-09
9385478	MEDIA LEFT	2020-06-01 @ 11:00 am	2020-06-04 @ 11:00 am	0.8 ± 0.4	2020-06-09
9385476	MEDIA OFFICE 1	2020-06-01 @ 11:00 am	2020-06-04 @ 11:00 am	0.6 ± 0.4	2020-06-09
9385485	MEDIA OFFICE 2	2020-06-01 @ 11:00 am	2020-06-04 @ 11:00 am	0.9 ± 0.4	2020-06-09
9385491	MEDIA RIGHT	2020-06-01 @ 11:00 am	2020-06-04 @ 11:00 am	0.6 ± 0.4	2020-06-09
9385484	MEDIA RIGHT	2020-06-01 @ 11:00 am	2020-06-04 @ 11:00 am	< 0.3	2020-06-09
9385443	MEDIA RM	2020-06-01 @ 11:00 am	2020-06-04 @ 11:00 am	1.0 ± 0.4	2020-06-09
9385179	NORTH GYM	2020-06-01 @ 1:00 pm	2020-06-04 @ 12:00 pm	0.6 ± 0.4	2020-06-09
9385180	NORTH GYM	2020-06-01 @ 1:00 pm	2020-06-04 @ 12:00 pm	1.5 ± 0.4	2020-06-09
9385176	NORTH GYM	2020-06-01 @ 1:00 pm	2020-06-04 @ 12:00 pm	< 0.3	2020-06-09
9385181	NORTH GYM	2020-06-01 @ 1:00 pm	2020-06-04 @ 12:00 pm	1.0 ± 0.4	2020-06-09
9385381	OFFICE	2020-06-01 @ 9:00 am	2020-06-04 @ 9:00 am	< 0.3	2020-06-09
9385318	OFFICE ATTENDANCE	2020-06-01 @ 8:00 am	2020-06-04 @ 8:00 am	< 0.3	2020-06-09
9385317	OFFICE BORG	2020-06-01 @ 8:00 am	2020-06-04 @ 8:00 am	< 0.3	2020-06-09
9385325	OFFICE CONF RM	2020-06-01 @ 8:00 am	2020-06-04 @ 8:00 am	0.6 ± 0.4	2020-06-09
9385390	OFFICE COPY RM	2020-06-01 @ 8:00 am	2020-06-04 @ 8:00 am	< 0.3	2020-06-09
9385341	OFFICE DC	2020-06-01 @ 8:00 am	2020-06-04 @ 8:00 am	< 0.3	2020-06-09
9385315	OFFICE DC	2020-06-01 @ 8:00 am	2020-06-04 @ 8:00 am	< 0.3	2020-06-09
9385309	OFFICE FREEL	2020-06-01 @ 8:00 am	2020-06-04 @ 8:00 am	< 0.3	2020-06-09
9385445	OFFICE HALL	2020-06-01 @ 11:00 am	2020-06-04 @ 11:00 am	0.9 ± 0.4	2020-06-09
9385333	OFFICE HEALTH	2020-06-01 @ 8:00 am	2020-06-04 @ 8:00 am	< 0.3	2020-06-09
9385326	OFFICE KAPPAS	2020-06-01 @ 8:00 am	2020-06-04 @ 8:00 am	< 0.3	2020-06-09
9385330	OFFICE KOLLASCH	2020-06-01 @ 8:00 am	2020-06-04 @ 8:00 am	< 0.3	2020-06-09
9385334	OFFICE RODRIGUEZ	2020-06-01 @ 8:00 am	2020-06-04 @ 8:00 am	< 0.3	2020-06-09
9385329	OFFICE STEPHENS	2020-06-01 @ 8:00 am	2020-06-04 @ 8:00 am	< 0.3	2020-06-09
9385310	OFFICE VETO	2020-06-01 @ 8:00 am	2020-06-04 @ 8:00 am	0.8 ± 0.4	2020-06-09
9385409	OLD WEIGHT RM	2020-06-01 @ 12:00 pm	2020-06-04 @ 12:00 pm	< 0.3	2020-06-09
9385403	OLD WEIGHT RM	2020-06-01 @ 1:00 pm	2020-06-04 @ 12:00 pm	< 0.3	2020-06-09
9385404	OLD WEIGHT RM - LEFT	2020-06-01 @ 1:00 pm	2020-06-04 @ 12:00 pm	< 0.3	2020-06-09
9385356	PERFORMING ARTS LEFT	2020-06-01 @ 9:00 am	2020-06-04 @ 8:00 am	0.7 ± 0.4	2020-06-09
9385355	PERFORMING ARTS LEFT	2020-06-01 @ 9:00 am	2020-06-04 @ 8:00 am	< 0.3	2020-06-09
9385364	PERFORMING ARTS RIGHT	2020-06-01 @ 9:00 am	2020-06-04 @ 8:00 am	< 0.3	2020-06-09
9385372	PERFORMING ARTS RM 6	2020-06-01 @ 9:00 am	2020-06-04 @ 8:00 am	0.9 ± 0.4	2020-06-09
9385383	POTTERY OFFICE	2020-06-01 @ 10:00 am	2020-06-04 @ 10:00 am	< 0.3	2020-06-09
9385410	RM 10	2020-06-01 @ 12:00 pm	2020-06-04 @ 12:00 pm	< 0.3	2020-06-09
9385450	RM 110	2020-06-01 @ 12:00 pm	2020-06-04 @ 11:00 am	< 0.3	2020-06-09

Radon test result report for:
**DC HIGH SCHOOL
 NORTH**

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
9385457	RM 111	2020-06-01 @ 12:00 pm	2020-06-04 @ 11:00 am	< 0.3	2020-06-09
9385449	RM 112	2020-06-01 @ 12:00 pm	2020-06-04 @ 11:00 am	< 0.3	2020-06-09
9385500	RM 113	2020-06-01 @ 12:00 pm	2020-06-04 @ 11:00 am	< 0.3	2020-06-09
9385456	RM 113	2020-06-01 @ 12:00 pm	2020-06-04 @ 11:00 am	< 0.3	2020-06-09
9385496	RM 113	2020-06-01 @ 12:00 pm	2020-06-04 @ 11:00 am	< 0.3	2020-06-09
9385499	RM 113	2020-06-01 @ 12:00 pm	2020-06-04 @ 11:00 am	0.6 ± 0.4	2020-06-09
9385463	RM 114	2020-06-01 @ 12:00 pm	2020-06-04 @ 11:00 am	< 0.3	2020-06-09
9385490	RM 115	2020-06-01 @ 11:00 am	2020-06-04 @ 11:00 am	< 0.3	2020-06-09
9385422	RM 115	2020-06-01 @ 11:00 am	2020-06-04 @ 11:00 am	< 0.3	2020-06-09
9385418	RM 116	2020-06-01 @ 11:00 am	2020-06-04 @ 11:00 am	< 0.3	2020-06-09
9385411	RM 117	2020-06-01 @ 11:00 am	2020-06-04 @ 11:00 am	< 0.3	2020-06-09
9385412	RM 118	2020-06-01 @ 11:00 am	2020-06-04 @ 11:00 am	< 0.3	2020-06-09
9385434	RM 119	2020-06-01 @ 11:00 am	2020-06-04 @ 11:00 am	< 0.3	2020-06-09
9385427	RM 119	2020-06-01 @ 11:00 am	2020-06-04 @ 11:00 am	< 0.3	2020-06-09
9385413	RM 119	2020-06-01 @ 11:00 am	2020-06-04 @ 11:00 am	< 0.3	2020-06-09
9385426	RM 12 CONF. RM	2020-06-01 @ 12:00 pm	2020-06-04 @ 12:00 pm	< 0.3	2020-06-09
9385483	RM 121 COMP. LAB	2020-06-01 @ 11:00 am	2020-06-04 @ 11:00 am	< 0.3	2020-06-09
9385431	RM 12B	2020-06-01 @ 12:00 pm	2020-06-04 @ 12:00 pm	< 0.3	2020-06-09
9385408	RM 13	2020-06-01 @ 12:00 pm	2020-06-04 @ 12:00 pm	< 0.3	2020-06-09
9385407	RM 14	2020-06-01 @ 12:00 pm	2020-06-04 @ 12:00 pm	< 0.3	2020-06-09
9385405	RM 14	2020-06-01 @ 12:00 pm	2020-06-04 @ 12:00 pm	< 0.3	2020-06-09
9385406	RM 14	2020-06-01 @ 12:00 pm	2020-06-04 @ 12:00 pm	< 0.3	2020-06-09
9385433	RM 15	2020-06-01 @ 12:00 pm	2020-06-04 @ 12:00 pm	< 0.3	2020-06-09
9385440	RM 16	2020-06-01 @ 12:00 pm	2020-06-04 @ 12:00 pm	< 0.3	2020-06-09
9385425	RM 17	2020-06-01 @ 12:00 pm	2020-06-04 @ 12:00 pm	< 0.3	2020-06-09
9385455	RM 17 CLASSROOM	2020-06-01 @ 12:00 pm	2020-06-04 @ 11:00 am	0.5 ± 0.4	2020-06-09
9385442	RM 17 CORNER RM	2020-06-01 @ 12:00 pm	2020-06-04 @ 11:00 am	< 0.3	2020-06-09
9385448	RM 17 OFFICE	2020-06-01 @ 12:00 pm	2020-06-04 @ 12:00 pm	< 0.3	2020-06-09
9385432	RM 18	2020-06-01 @ 12:00 pm	2020-06-04 @ 12:00 pm	< 0.3	2020-06-09
9385423	RM 18	2020-06-01 @ 12:00 pm	2020-06-04 @ 12:00 pm	< 0.3	2020-06-09
9385424	RM 19	2020-06-01 @ 12:00 pm	2020-06-04 @ 12:00 pm	< 0.3	2020-06-09
9385378	RM 2	2020-06-01 @ 9:00 am	2020-06-04 @ 9:00 am	< 0.3	2020-06-09
9385369	RM 2	2020-06-01 @ 9:00 am	2020-06-04 @ 9:00 am	0.7 ± 0.4	2020-06-09
9385377	RM 2	2020-06-01 @ 9:00 am	2020-06-04 @ 9:00 am	< 0.3	2020-06-09
9385389	RM 20	2020-06-01 @ 10:00 am	2020-06-04 @ 9:00 am	< 0.3	2020-06-09
9385328	RM 21	2020-06-01 @ 10:00 am	2020-06-04 @ 9:00 am	< 0.3	2020-06-09
9385343	RM 22	2020-06-01 @ 10:00 am	2020-06-04 @ 9:00 am	< 0.3	2020-06-09

Radon test result report for:
**DC HIGH SCHOOL
 NORTH**

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
9385331	RM 22	2020-06-01 @ 10:00 am	2020-06-04 @ 9:00 am	< 0.3	2020-06-09
9385320	RM 22	2020-06-01 @ 10:00 am	2020-06-04 @ 9:00 am	< 0.3	2020-06-09
9385316	RM 23	2020-06-01 @ 10:00 am	2020-06-04 @ 9:00 am	< 0.3	2020-06-09
9385396	RM 24	2020-06-01 @ 10:00 am	2020-06-04 @ 10:00 am	< 0.3	2020-06-09
9385366	RM 3 - BACK LEFT	2020-06-01 @ 9:00 am	2020-06-04 @ 9:00 am	< 0.3	2020-06-09
9385365	RM 3 - FRONT LEFT	2020-06-01 @ 9:00 am	2020-06-04 @ 9:00 am	0.6 ± 0.4	2020-06-09
9385371	RM 3 - M476	2020-06-01 @ 9:00 am	2020-06-04 @ 9:00 am	< 0.3	2020-06-09
9385373	RM 3 - MOSEK	2020-06-01 @ 9:00 am	2020-06-04 @ 9:00 am	< 0.3	2020-06-09
9385324	RM 31	2020-06-01 @ 10:00 am	2020-06-04 @ 9:00 am	< 0.3	2020-06-09
9385327	RM 32	2020-06-01 @ 10:00 am	2020-06-04 @ 9:00 am	< 0.3	2020-06-09
9385323	RM 34	2020-06-01 @ 10:00 am	2020-06-04 @ 9:00 am	< 0.3	2020-06-09
9385340	RM 35	2020-06-01 @ 10:00 am	2020-06-04 @ 9:00 am	< 0.3	2020-06-09
9385302	RM 36	2020-06-01 @ 10:00 am	2020-06-04 @ 9:00 am	< 0.3	2020-06-09
9385306	RM 37	2020-06-01 @ 10:00 am	2020-06-04 @ 9:00 am	< 0.3	2020-06-09
9385395	RM 38	2020-06-01 @ 10:00 am	2020-06-04 @ 10:00 am	< 0.3	2020-06-09
9385319	RM 39	2020-06-01 @ 10:00 am	2020-06-04 @ 9:00 am	< 0.3	2020-06-09
9385387	RM 40	2020-06-01 @ 10:00 am	2020-06-04 @ 10:00 am	< 0.3	2020-06-09
9385375	RM 41 POTTERY	2020-06-01 @ 10:00 am	2020-06-04 @ 10:00 am	< 0.3	2020-06-09
9385368	RM 42	2020-06-01 @ 10:00 am	2020-06-04 @ 10:00 am	< 0.3	2020-06-09
9385367	RM 42	2020-06-01 @ 10:00 am	2020-06-04 @ 10:00 am	0.5 ± 0.4	2020-06-09
9385360	RM 43	2020-06-01 @ 10:00 am	2020-06-04 @ 10:00 am	< 0.3	2020-06-09
9385359	RM 43 OFFICE	2020-06-01 @ 10:00 am	2020-06-04 @ 10:00 am	< 0.3	2020-06-09
9385351	RM 44 AUTO	2020-06-01 @ 10:00 am	2020-06-04 @ 10:00 am	< 0.3	2020-06-09
9385352	RM 44 AUTO	2020-06-01 @ 10:00 am	2020-06-04 @ 10:00 am	< 0.3	2020-06-09
9385344	RM 45 AUTO	2020-06-01 @ 10:00 am	2020-06-04 @ 10:00 am	0.7 ± 0.4	2020-06-09
9385308	RM 46 ART	2020-06-01 @ 10:00 am	2020-06-04 @ 9:00 am	< 0.3	2020-06-09
9385391	RM 50	2020-06-01 @ 10:00 am	2020-06-04 @ 10:00 am	< 0.3	2020-06-09
9385384	RM 50 OFFICE	2020-06-01 @ 10:00 am	2020-06-04 @ 10:00 am	< 0.3	2020-06-09
9385336	RM 51 AUTO SHOP	2020-06-01 @ 10:00 am	2020-06-04 @ 10:00 am	0.6 ± 0.4	2020-06-09
9385304	RM 51 AUTO SHOP	2020-06-01 @ 11:00 am	2020-06-04 @ 10:00 am	< 0.3	2020-06-09
9385303	RM 52	2020-06-01 @ 11:00 am	2020-06-04 @ 10:00 am	< 0.3	2020-06-09
9385453	RM 52 BACK	2020-06-01 @ 11:00 am	2020-06-04 @ 10:00 am	< 0.3	2020-06-09
9385301	RM 52 FRONT OFFICE	2020-06-01 @ 11:00 am	2020-06-04 @ 10:00 am	< 0.3	2020-06-09
9385421	RM 52 SECOND OFFICE	2020-06-01 @ 11:00 am	2020-06-04 @ 10:00 am	< 0.3	2020-06-09
9385438	RM 53	2020-06-01 @ 11:00 am	2020-06-04 @ 10:00 am	< 0.3	2020-06-09
9385444	RM 60	2020-06-01 @ 11:00 am	2020-06-04 @ 10:00 am	< 0.3	2020-06-09
9385437	RM 60	2020-06-01 @ 11:00 am	2020-06-04 @ 10:00 am	0.9 ± 0.4	2020-06-09

Radon test result report for:
**DC HIGH SCHOOL
 NORTH**

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
9385468	RM 60 CHEM STORAGE	2020-06-01 @ 11:00 am	2020-06-04 @ 10:00 am	0.8 ± 0.4	2020-06-09
9385429	RM 61	2020-06-01 @ 11:00 am	2020-06-04 @ 10:00 am	0.7 ± 0.4	2020-06-09
9385435	RM 62	2020-06-01 @ 11:00 am	2020-06-04 @ 10:00 am	0.7 ± 0.4	2020-06-09
9385459	RM 62 GREENHOUSE	2020-06-01 @ 11:00 am	2020-06-04 @ 10:00 am	< 0.3	2020-06-09
9385428	RM 63	2020-06-01 @ 11:00 am	2020-06-04 @ 10:00 am	0.6 ± 0.4	2020-06-09
9385419	RM 64	2020-06-01 @ 11:00 am	2020-06-04 @ 10:00 am	< 0.3	2020-06-09
9385461	RM 65	2020-06-01 @ 11:00 am	2020-06-04 @ 10:00 am	0.6 ± 0.4	2020-06-09
9385454	RM 65	2020-06-01 @ 11:00 am	2020-06-04 @ 10:00 am	< 0.3	2020-06-09
9385460	RM 65	2020-06-01 @ 11:00 am	2020-06-04 @ 10:00 am	0.9 ± 0.4	2020-06-09
9385452	RM 65 OFFICE	2020-06-01 @ 11:00 am	2020-06-04 @ 11:00 am	0.6 ± 0.4	2020-06-09
9385467	RM 66	2020-06-01 @ 11:00 am	2020-06-04 @ 11:00 am	1.1 ± 0.4	2020-06-09
9385451	RM 67	2020-06-01 @ 11:00 am	2020-06-04 @ 11:00 am	< 0.3	2020-06-09
9385332	RM BETWEEN 20 & 21	2020-06-01 @ 10:00 am	2020-06-04 @ 9:00 am	< 0.3	2020-06-09
9385398	SECURITY	2020-06-01 @ 8:00 am	2020-06-04 @ 8:00 am	< 0.3	2020-06-09
9385397	SLATE OFFICE	2020-06-01 @ 10:00 am	2020-06-04 @ 9:00 am	< 0.3	2020-06-09
9385401	SMALL OFFICE	2020-06-01 @ 1:00 pm	2020-06-04 @ 12:00 pm	< 0.3	2020-06-09
9385441	SSN CENTRAL	2020-06-01 @ 12:00 pm	2020-06-04 @ 12:00 pm	< 0.3	2020-06-09
9385447	SSN OFFICE	2020-06-01 @ 12:00 pm	2020-06-04 @ 12:00 pm	< 0.3	2020-06-09
9385346	STAGE SHOP	2020-06-01 @ 9:00 am	2020-06-04 @ 8:00 am	< 0.3	2020-06-09
9385131	TEACHER'S LOUNGE	2020-06-01 @ 1:00 pm	2020-06-04 @ 12:00 pm	0.6 ± 0.4	2020-06-09
9385321	THEATER	2020-06-01 @ 9:00 am	2020-06-04 @ 8:00 am	0.6 ± 0.4	2020-06-09
9385322	THEATER	2020-06-01 @ 9:00 am	2020-06-04 @ 8:00 am	< 0.3	2020-06-09
9385313	THEATER	2020-06-01 @ 9:00 am	2020-06-04 @ 8:00 am	< 0.3	2020-06-09
9385314	THEATER / PROJECTION	2020-06-01 @ 9:00 am	2020-06-04 @ 8:00 am	???? IF2	2020-06-09
9385415	WORK RM	2020-06-01 @ 12:00 pm	2020-06-04 @ 12:00 pm	< 0.3	2020-06-09
9385495	WRESTLING	2020-06-01 @ 12:00 pm	2020-06-04 @ 11:00 am	1.0 ± 0.4	2020-06-09
9385472	WRESTLING	2020-06-01 @ 12:00 pm	2020-06-04 @ 11:00 am	0.8 ± 0.4	2020-06-09
9385465	WRESTLING	2020-06-01 @ 12:00 pm	2020-06-04 @ 11:00 am	0.9 ± 0.4	2020-06-09
9385464	WRESTLING OFFICE	2020-06-01 @ 12:00 pm	2020-06-04 @ 11:00 am	0.7 ± 0.4	2020-06-09

Radon test result report for:
DC HIGH SCHOOL
SOUTH

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
9385557	ATHLETIC BACK	2020-06-01 @ 3:00 pm	2020-06-04 @ 3:00 pm	1.8 ± 0.4	2020-06-09
9385556	ATHLETIC BACK	2020-06-01 @ 3:00 pm	2020-06-04 @ 3:00 pm	1.7 ± 0.4	2020-06-09
9385549	ATHLETIC OFFICE	2020-06-01 @ 3:00 pm	2020-06-04 @ 3:00 pm	1.9 ± 0.4	2020-06-09
9385550	ATHLETIC RIGHT	2020-06-01 @ 3:00 pm	2020-06-04 @ 3:00 pm	1.2 ± 0.4	2020-06-09
9385547	ATHLETIC RIGHT	2020-06-01 @ 3:00 pm	2020-06-04 @ 3:00 pm	2.5 ± 0.5	2020-06-09
9385187	AYWORTHY	2020-06-01 @ 2:00 pm	2020-06-04 @ 2:00 pm	1.4 ± 0.4	2020-06-09
9385506	CAFETERIA	2020-06-01 @ 3:00 pm	2020-06-04 @ 3:00 pm	1.7 ± 0.4	2020-06-09
9385513	CAFETERIA	2020-06-01 @ 3:00 pm	2020-06-04 @ 3:00 pm	1.2 ± 0.4	2020-06-09
9385514	CAFETERIA	2020-06-01 @ 3:00 pm	2020-06-04 @ 3:00 pm	1.2 ± 0.4	2020-06-09
9385505	CAFETERIA	2020-06-01 @ 3:00 pm	2020-06-04 @ 3:00 pm	1.3 ± 0.4	2020-06-09
9385174	CHEER	2020-06-01 @ 1:00 pm	2020-06-04 @ 1:00 pm	1.7 ± 0.4	2020-06-09
9385173	CHEER OFFICE	2020-06-01 @ 1:00 pm	2020-06-04 @ 1:00 pm	1.4 ± 0.4	2020-06-09
9385108	CLINIC	2020-06-01 @ 2:00 pm	2020-06-04 @ 2:00 pm	1.4 ± 0.4	2020-06-09
9385555	COACH OFFICE	2020-06-01 @ 3:00 pm	2020-06-04 @ 3:00 pm	0.6 ± 0.4	2020-06-09
9385573	COACH OFFICE 2	2020-06-01 @ 3:00 pm	2020-06-04 @ 3:00 pm	0.8 ± 0.4	2020-06-09
9385582	COACH OFFICE 2	2020-06-01 @ 3:00 pm	2020-06-04 @ 3:00 pm	0.7 ± 0.4	2020-06-09
9385125	CONCESSIONS	2020-06-01 @ 1:00 pm	2020-06-04 @ 1:00 pm	1.7 ± 0.5	2020-06-09
9385129	COPY/FILE RM	2020-06-01 @ 2:00 pm	2020-06-04 @ 2:00 pm	< 0.3	2020-06-09
9385591	CUSTODIAL OFFICE	2020-06-01 @ 3:00 pm	2020-06-04 @ 3:00 pm	1.1 ± 0.4	2020-06-09
9385584	CUSTODIAL OFFICE	2020-06-01 @ 3:00 pm	2020-06-04 @ 3:00 pm	1.1 ± 0.4	2020-06-09
9385519	DRAMA	2020-06-01 @ 3:00 pm	2020-06-04 @ 3:00 pm	2.6 ± 0.4	2020-06-09
9385120	FACULTY LOUNGE	2020-06-01 @ 2:00 pm	2020-06-04 @ 2:00 pm	4.5 ± 0.6	2020-06-09
9385117	FILE STORAGE	2020-06-01 @ 2:00 pm	2020-06-04 @ 2:00 pm	1.5 ± 0.4	2020-06-09
9385148	FOREIGN LANG. OFFICE	2020-06-01 @ 2:00 pm	2020-06-04 @ 2:00 pm	0.7 ± 0.4	2020-06-09
9385510	GYM	2020-06-01 @ 3:00 pm	2020-06-04 @ 3:00 pm	< 0.3	2020-06-09
9385583	GYM	2020-06-01 @ 3:00 pm	2020-06-04 @ 3:00 pm	1.0 ± 0.4	2020-06-09
9385581	GYM	2020-06-01 @ 3:00 pm	2020-06-04 @ 3:00 pm	0.8 ± 0.4	2020-06-09
9385574	GYM	2020-06-01 @ 3:00 pm	2020-06-04 @ 3:00 pm	1.5 ± 0.5	2020-06-09
9385509	GYM	2020-06-01 @ 3:00 pm	2020-06-04 @ 3:00 pm	< 0.3	2020-06-09
9385575	GYM	2020-06-01 @ 3:00 pm	2020-06-04 @ 3:00 pm	< 0.3	2020-06-09
9385516	KITCHEN	2020-06-01 @ 3:00 pm	2020-06-04 @ 3:00 pm	1.2 ± 0.4	2020-06-09
9385512	KITCHEN OFFICE	2020-06-01 @ 3:00 pm	2020-06-04 @ 3:00 pm	2.1 ± 0.4	2020-06-09
9385166	LEFT OFFICE	2020-06-01 @ 2:00 pm	2020-06-04 @ 2:00 pm	1.5 ± 0.4	2020-06-09
9385122	MATH OFFICE	2020-06-01 @ 2:00 pm	2020-06-04 @ 2:00 pm	2.0 ± 0.5	2020-06-09
9385520	OFFICE	2020-06-01 @ 3:00 pm	2020-06-04 @ 3:00 pm	1.0 ± 0.4	2020-06-09
9385158	OFFICE	2020-06-01 @ 1:00 pm	2020-06-04 @ 1:00 pm	1.2 ± 0.4	2020-06-09
9385126	OFFICE	2020-06-01 @ 1:00 pm	2020-06-04 @ 1:00 pm	1.5 ± 0.4	2020-06-09

Radon test result report for:
DC HIGH SCHOOL
SOUTH

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
9385127	OFFICE	2020-06-01 @ 2:00 pm	2020-06-04 @ 2:00 pm	1.0 ± 0.4	2020-06-09
9385113	OFFICE CONF RM	2020-06-01 @ 2:00 pm	2020-06-04 @ 2:00 pm	1.1 ± 0.4	2020-06-09
9385114	OFFICE CONF RM	2020-06-01 @ 2:00 pm	2020-06-04 @ 2:00 pm	1.1 ± 0.4	2020-06-09
9385165	OFFICERS	2020-06-01 @ 2:00 pm	2020-06-04 @ 2:00 pm	1.5 ± 0.4	2020-06-09
9385518	RM 1	2020-06-01 @ 3:00 pm	2020-06-04 @ 3:00 pm	1.0 ± 0.4	2020-06-09
9385534	RM 1	2020-06-01 @ 3:00 pm	2020-06-04 @ 3:00 pm	< 0.3	2020-06-09
9385517	RM 1	2020-06-01 @ 3:00 pm	2020-06-04 @ 3:00 pm	0.7 ± 0.4	2020-06-09
9385109	RM 10 CLASSROOM	2020-06-01 @ 2:00 pm	2020-06-04 @ 2:00 pm	1.9 ± 0.4	2020-06-09
9385188	RM 10 CORNER OFFICE	2020-06-01 @ 2:00 pm	2020-06-04 @ 2:00 pm	2.1 ± 0.5	2020-06-09
9385102	RM 10 OFFICE	2020-06-01 @ 2:00 pm	2020-06-04 @ 2:00 pm	1.2 ± 0.4	2020-06-09
9385511	RM 100 STAGE	2020-06-01 @ 3:00 pm	2020-06-04 @ 3:00 pm	1.4 ± 0.4	2020-06-09
9385599	RM 101 DANCE	2020-06-01 @ 3:00 pm	2020-06-04 @ 3:00 pm	< 0.3	2020-06-09
9385600	RM 101 DANCE	2020-06-01 @ 3:00 pm	2020-06-04 @ 3:00 pm	0.5 ± 0.4	2020-06-09
9385589	RM 102	2020-06-01 @ 3:00 pm	2020-06-04 @ 3:00 pm	< 0.3	2020-06-09
9385538	RM 102 OFFICE	2020-06-01 @ 3:00 pm	2020-06-04 @ 3:00 pm	1.7 ± 0.4	2020-06-09
9385566	RM 104	2020-06-01 @ 3:00 pm	2020-06-04 @ 3:00 pm	2.7 ± 0.5	2020-06-09
9385572	RM 104 OFFICE	2020-06-01 @ 3:00 pm	2020-06-04 @ 3:00 pm	3.3 ± 0.5	2020-06-09
9385535	RM 105	2020-06-01 @ 3:00 pm	2020-06-04 @ 3:00 pm	2.8 ± 0.5	2020-06-09
9385564	RM 105 CENTER	2020-06-01 @ 3:00 pm	2020-06-04 @ 3:00 pm	4.1 ± 0.6	2020-06-09
9385565	RM 105 LEFT	2020-06-01 @ 3:00 pm	2020-06-04 @ 3:00 pm	10.1 ± 0.7	2020-06-09
9385563	RM 105 RIGHT	2020-06-01 @ 3:00 pm	2020-06-04 @ 3:00 pm	3.5 ± 0.5	2020-06-09
9385110	RM 11 CLASSROOM	2020-06-01 @ 2:00 pm	2020-06-04 @ 2:00 pm	1.7 ± 0.4	2020-06-09
9385115	RM 11 OFFICE	2020-06-01 @ 2:00 pm	2020-06-04 @ 2:00 pm	1.4 ± 0.4	2020-06-09
9385168	RM 11 OFFICE	2020-06-01 @ 2:00 pm	2020-06-04 @ 2:00 pm	1.2 ± 0.4	2020-06-09
9385141	RM 11 OFFICE	2020-06-01 @ 2:00 pm	2020-06-04 @ 2:00 pm	< 0.3	2020-06-09
9385139	RM 12 CLASSROOM	2020-06-01 @ 2:00 pm	2020-06-04 @ 2:00 pm	1.8 ± 0.5	2020-06-09
9385138	RM 12 OFFICE	2020-06-01 @ 2:00 pm	2020-06-04 @ 2:00 pm	1.4 ± 0.4	2020-06-09
9385140	RM 13 CLASSROOM	2020-06-01 @ 2:00 pm	2020-06-04 @ 2:00 pm	1.1 ± 0.4	2020-06-09
9385116	RM 13 OFFICE	2020-06-01 @ 2:00 pm	2020-06-04 @ 2:00 pm	1.2 ± 0.4	2020-06-09
9385147	RM 19	2020-06-01 @ 2:00 pm	2020-06-04 @ 2:00 pm	???? FI	2020-06-09
9385146	RM 19 PRACTICE RM	2020-06-01 @ 2:00 pm	2020-06-04 @ 2:00 pm	0.8 ± 0.4	2020-06-09
9385526	RM 2	2020-06-01 @ 3:00 pm	2020-06-04 @ 3:00 pm	1.1 ± 0.4	2020-06-09
9385190	RM 20	2020-06-01 @ 2:00 pm	2020-06-04 @ 2:00 pm	1.6 ± 0.4	2020-06-09
9385191	RM 21	2020-06-01 @ 2:00 pm	2020-06-04 @ 2:00 pm	1.5 ± 0.4	2020-06-09
9385192	RM 22	2020-06-01 @ 2:00 pm	2020-06-04 @ 2:00 pm	1.4 ± 0.4	2020-06-09
9385193	RM 23	2020-06-01 @ 2:00 pm	2020-06-04 @ 2:00 pm	1.9 ± 0.5	2020-06-09
9385531	RM 3	2020-06-01 @ 2:00 pm	2020-06-04 @ 2:00 pm	2.1 ± 0.5	2020-06-09

Radon test result report for:
DC HIGH SCHOOL
SOUTH

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
9385130	RM 31	2020-06-01 @ 2:00 pm	2020-06-04 @ 2:00 pm	1.5 ± 0.4	2020-06-09
9385123	RM 32	2020-06-01 @ 2:00 pm	2020-06-04 @ 2:00 pm	2.0 ± 0.5	2020-06-09
9385142	RM 32	2020-06-01 @ 2:00 pm	2020-06-04 @ 2:00 pm	2.1 ± 0.4	2020-06-09
9385124	RM 32A	2020-06-01 @ 2:00 pm	2020-06-04 @ 2:00 pm	1.5 ± 0.4	2020-06-09
9385118	RM 33	2020-06-01 @ 2:00 pm	2020-06-04 @ 2:00 pm	1.7 ± 0.5	2020-06-09
9385598	RM 4	2020-06-01 @ 2:00 pm	2020-06-04 @ 2:00 pm	0.7 ± 0.4	2020-06-09
9385533	RM 40	2020-06-01 @ 3:00 pm	2020-06-04 @ 3:00 pm	0.9 ± 0.4	2020-06-09
9385540	RM 40 OFFICE	2020-06-01 @ 3:00 pm	2020-06-04 @ 3:00 pm	< 0.3	2020-06-09
9385133	RM 41	2020-06-01 @ 2:00 pm	2020-06-04 @ 2:00 pm	1.5 ± 0.5	2020-06-09
9385132	RM 42	2020-06-01 @ 2:00 pm	2020-06-04 @ 2:00 pm	2.0 ± 0.5	2020-06-09
9385143	RM 43	2020-06-01 @ 2:00 pm	2020-06-04 @ 2:00 pm	1.9 ± 0.5	2020-06-09
9385119	RM 43	2020-06-01 @ 2:00 pm	2020-06-04 @ 2:00 pm	???? IF2	2020-06-09
9385149	RM 43	2020-06-01 @ 2:00 pm	2020-06-04 @ 2:00 pm	1.5 ± 0.5	2020-06-09
9385167	RM 44	2020-06-01 @ 2:00 pm	2020-06-04 @ 2:00 pm	0.9 ± 0.4	2020-06-09
9385597	RM 4S	2020-06-01 @ 2:00 pm	2020-06-04 @ 2:00 pm	0.6 ± 0.4	2020-06-09
9385525	RM 5	2020-06-01 @ 3:00 pm	2020-06-04 @ 3:00 pm	0.8 ± 0.4	2020-06-09
9385532	RM 50	2020-06-01 @ 3:00 pm	2020-06-04 @ 3:00 pm	1.0 ± 0.4	2020-06-09
9385541	RM 50-1	2020-06-01 @ 3:00 pm	2020-06-04 @ 3:00 pm	0.5 ± 0.4	2020-06-09
9385542	RM 50-2	2020-06-01 @ 3:00 pm	2020-06-04 @ 3:00 pm	0.7 ± 0.4	2020-06-09
9385548	RM 50-3	2020-06-01 @ 3:00 pm	2020-06-04 @ 3:00 pm	< 0.3	2020-06-09
9385160	RM 51 AUTO SHOP	2020-06-01 @ 1:00 pm	2020-06-04 @ 1:00 pm	2.2 ± 0.5	2020-06-09
9385196	RM 52	2020-06-01 @ 1:00 pm	2020-06-04 @ 1:00 pm	1.6 ± 0.4	2020-06-09
9385162	RM 53	2020-06-01 @ 1:00 pm	2020-06-04 @ 1:00 pm	1.7 ± 0.5	2020-06-09
9385195	RM 53	2020-06-01 @ 1:00 pm	2020-06-04 @ 1:00 pm	1.7 ± 0.4	2020-06-09
9385161	RM 53	2020-06-01 @ 1:00 pm	2020-06-04 @ 1:00 pm	< 0.3	2020-06-09
9385163	RM 54	2020-06-01 @ 1:00 pm	2020-06-04 @ 1:00 pm	1.3 ± 0.4	2020-06-09
9385164	RM 54 OFFICE	2020-06-01 @ 1:00 pm	2020-06-04 @ 1:00 pm	1.2 ± 0.4	2020-06-09
9385515	RM 6	2020-06-01 @ 2:00 pm	2020-06-04 @ 2:00 pm	0.6 ± 0.4	2020-06-09
9385558	RM 60	2020-06-01 @ 3:00 pm	2020-06-04 @ 3:00 pm	0.9 ± 0.4	2020-06-09
9385172	RM 63	2020-06-01 @ 1:00 pm	2020-06-04 @ 1:00 pm	1.2 ± 0.4	2020-06-09
9385171	RM 63	2020-06-01 @ 1:00 pm	2020-06-04 @ 1:00 pm	1.3 ± 0.4	2020-06-09
9385198	RM 64 BACK	2020-06-01 @ 1:00 pm	2020-06-04 @ 1:00 pm	1.3 ± 0.4	2020-06-09
9385197	RM 64 FRONT	2020-06-01 @ 1:00 pm	2020-06-04 @ 1:00 pm	1.6 ± 0.4	2020-06-09
9385159	RM 65	2020-06-01 @ 1:00 pm	2020-06-04 @ 1:00 pm	1.2 ± 0.4	2020-06-09
9385157	RM 66	2020-06-01 @ 1:00 pm	2020-06-04 @ 1:00 pm	0.8 ± 0.4	2020-06-09
9385194	RM 70	2020-06-01 @ 2:00 pm	2020-06-04 @ 2:00 pm	1.4 ± 0.4	2020-06-09
9385145	RM 70 KITCHEN	2020-06-01 @ 2:00 pm	2020-06-04 @ 2:00 pm	1.0 ± 0.4	2020-06-09

June 9, 2020

**** LABORATORY ANALYSIS REPORT ****

Radon test result report for:
**DC HIGH SCHOOL
SOUTH**

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
9385156	RM 71	2020-06-01 @ 2:00 pm	2020-06-04 @ 2:00 pm	1.4 ± 0.4	2020-06-09
9385155	RM 72	2020-06-01 @ 2:00 pm	2020-06-04 @ 2:00 pm	1.1 ± 0.4	2020-06-09
9385144	RM 73	2020-06-01 @ 2:00 pm	2020-06-04 @ 2:00 pm	1.1 ± 0.4	2020-06-09
9385154	RM 74	2020-06-01 @ 2:00 pm	2020-06-04 @ 2:00 pm	2.0 ± 0.4	2020-06-09
9385151	RM 75	2020-06-01 @ 2:00 pm	2020-06-04 @ 2:00 pm	1.2 ± 0.4	2020-06-09
9385150	RM 76	2020-06-01 @ 2:00 pm	2020-06-04 @ 2:00 pm	2.8 ± 0.5	2020-06-09
9385152	RM 77	2020-06-01 @ 2:00 pm	2020-06-04 @ 2:00 pm	< 0.3	2020-06-09
9385153	RM 77 KITCHEN	2020-06-01 @ 2:00 pm	2020-06-04 @ 2:00 pm	???? IF2	2020-06-09
9385128	S. MAIN OFFICE	2020-06-01 @ 2:00 pm	2020-06-04 @ 2:00 pm	1.1 ± 0.4	2020-06-09
9385136	SCHUK	2020-06-01 @ 2:00 pm	2020-06-04 @ 2:00 pm	0.9 ± 0.4	2020-06-09
9385135	SCHUKARTH	2020-06-01 @ 2:00 pm	2020-06-04 @ 2:00 pm	1.4 ± 0.4	2020-06-09
9385121	SCIENCE OFFICE	2020-06-01 @ 2:00 pm	2020-06-04 @ 2:00 pm	3.5 ± 0.5	2020-06-09
9385137	SCIENCE SUPPLIES	2020-06-01 @ 2:00 pm	2020-06-04 @ 2:00 pm	1.9 ± 0.5	2020-06-09
9385169	TECH LAB OFFICE	2020-06-01 @ 1:00 pm	2020-06-04 @ 1:00 pm	1.5 ± 0.4	2020-06-09
9385170	TECHLAB	2020-06-01 @ 1:00 pm	2020-06-04 @ 1:00 pm	1.7 ± 0.4	2020-06-09
9385523	THEATER OFFICE	2020-06-01 @ 3:00 pm	2020-06-04 @ 3:00 pm	9.5 ± 0.7	2020-06-09
9385502	THEATER OFFICE	2020-06-01 @ 3:00 pm	2020-06-04 @ 3:00 pm	< 0.3	2020-06-09
9385503	THEATER OFFICE	2020-06-01 @ 3:00 pm	2020-06-04 @ 3:00 pm	9.7 ± 0.7	2020-06-09
9385504	THEATER STORAGE	2020-06-01 @ 3:00 pm	2020-06-04 @ 3:00 pm	1.5 ± 0.4	2020-06-09
9385134	TURNBAUGH	2020-06-01 @ 2:00 pm	2020-06-04 @ 2:00 pm	1.0 ± 0.4	2020-06-09
9385524	VIDEO PROD. MIDDLE OFFICE	2020-06-01 @ 3:00 pm	2020-06-04 @ 3:00 pm	2.3 ± 0.5	2020-06-09

August 26, 2021

**** LABORATORY ANALYSIS REPORT ****

Pg 1 of 1

P8643 / ROBERT WOELLNER

Kit Number	Start Date	Start Time	End Date	End Time	Temp.	Facility	Building	Room	Project ID	Floor	Result
9668527	2021-08-18	2:00 pm	2021-08-20	4:00 pm	70	DC HIGH SCHOOL	SOUTH	FACULTY LOUNGE	2108100-02	1	2.3
9668528	2021-08-18	3:00 pm	2021-08-20	5:00 pm	70	DC HIGH SCHOOL	SOUTH	RM 105	2108100-02	1	< 0.3
9668529	2021-08-18	3:00 pm	2021-08-20	5:00 pm	70	DC HIGH SCHOOL	SOUTH	THEATER OFFICE	2108100-02	1	0.6
9668530	2021-08-18	3:00 pm	2021-08-20	5:00 pm	70	DC HIGH SCHOOL	SOUTH	THEATER OFFICE	2108100-02	1	0.6

Air Chek 1936 Butler Bridge Rd, Mills River, NC 28759-3892 Phone: (828) 684-0893 Fax: (828) 684-8498