

NOTES

- REFER TO SHEET T1.00, TITLE SHEET, FOR RELATED GENERAL NOTES.
- CONTRACTOR SHALL VERIFY ALL EXISTING CONDITIONS PRIOR TO THE BIDDING.
- CONTRACTOR SHALL BE RESPONSIBLE FOR SHOOTING AND RECORDING EXISTING PAVEMENT SURFACE ELEVATIONS. ONCE BITUMINOUS PAVEMENT HAS BEEN REMOVED, THE CONTRACTOR SHALL BE RE-ESTABLISH ELEVATIONS THAT WILL ENSURE POSITIVE DRAINAGE AS APPROPRIATE.
- RESTRIPE PARKING LOT STALLS AS APPLICABLE. OBSERVE AND MAP EXISTING PRIOR TO BEGINNING WORK.

LEGEND

1
2.01

REFERENCE KEY TO SITE DETAILS
DETAIL I.D. NUMBER (TOP)
DETAIL SHEET NUMBER (BOTTOM)

4
C2.01

PROPOSED MEDIUM DUTY RECLAIM AND REPAVE

9
C2.01

PROPOSED CONCRETE VALLEY GUTTER

8
C2.01

PROPOSED CONCRETE SLAB REPLACEMENT

3
C2.01

PROPOSED ASPHALT PAVEMENT CRACKSEAL / SEALCOAT / FOG SEAL

NUTRITION CENTER QUANTITIES


THE CONTRACTOR SHALL VERIFY ALL EXISTING CONDITIONS, INCLUDING DETERMINATION OF ALL QUANTITIES, PRIOR TO THE WORK. BASE BID AMOUNT INCLUDES ALL WORK TO ACCOMPLISH THAT WHICH IS ILLUSTRATED ON THE PLAN, UNLESS OTHERWISE NOTED.

"ESTIMATED" QUANTITIES PROVIDED ARE FOR THE CONTRACTOR'S REFERENCE ONLY.
"ASSUMED" QUANTITIES SHALL BE INCLUDED IN THE CONTRACTOR'S BASE BID COST.
FINAL QUANTITIES WILL BE ADJUSTED USING UNIT PRICES.

- SOUTH PARKING LOT
 - ESTIMATED CONCRETE VALLEY GUTTER NEW = 80 S.Y.
 - ASSUMED MEDIUM DUTY RECLAIM AND REPAVE = 1500 S.Y.
 - ESTIMATED CONCRETE SLAB/APRON REMOVE AND REPLACE = 800 S.F.
- NORTHWEST PARKING LOT
 - ASSUMED MEDIUM DUTY RECLAIM AND REPAVE = 1100 S.Y.
- EAST PARKING LOT
 - ESTIMATED BITUMINOUS SEAL COAT / FOG SEAL = 1200 S.Y.
 - ASSUMED BITUMINOUS CRACK SEAL = 120 L.F.

© Bolton & Menk, Inc. 2025. All Rights Reserved.
PL1301.ED.MN1241.3834600(CAD)CSD\136514_C_PNT_NL.dwg 3/4/2025 4:07:04 PM

I HEREBY CERTIFY THAT THIS PLAN, SPECIFICATION, OR REPORT WAS PREPARED BY ME OR UNDER MY DIRECT SUPERVISION AND THAT I AM A DULY LICENSED LANDSCAPE ARCHITECT UNDER THE LAWS OF THE STATE OF MINNESOTA.


JAY R. POMEROY
LIC. NO. 23543 DATE 03/03/2025



3300 FERNBROOK LANE NORTH, SUITE 300
PLYMOUTH, MN 55447
Phone: (763) 544-7129
Email: Plymouth@bolton-menk.com
www.bolton-menk.com

| DESIGNED | NO. | ISSUED FOR | DATE |
|------------------|-----|------------|------|
| CDL | | | |
| DRAWN | | | |
| CA | | | |
| CHECKED | | | |
| JRP | | | |
| CLIENT PROJ. NO. | | | |
| OP#25-2521 | | | |

MINNEAPOLIS PUBLIC SCHOOLS
FY25 SITE AND PAVEMENT IMPROVEMENTS

NUTRITION SERVICE DEPARTMENT

SHEET

C1.06

