

SPECIFICATIONS FOR REHEAT COILS FOR AIRHANDLER UNIT

NONNEWAUG HIGH SCHOOL

April 4, 2025

Region 14 is soliciting bids for the installation, wiring, control, ductwork, and piping of a re-heat coils on four (4) air handler units as shown on the accompanying plans and specifications for DOA/ AHU 1-4. The contractor will be responsible to remove existing ductwork, fabricate new transition ductwork to accommodate the re-heat coils. The contractor shall also install coils, piping, electric and building management controls to allow for a minimum of 70 Degree F air temperature entering the occupied space. Disposal of all removed ductwork and construction waste is the contractor's responsibility. Please omit DOA#5 from the bid.

A mandatory pre-bid walk through of the project will be held on April 10, 2025 at 9am on the site starting at the Region 14 Central Office at Nonnewaug High School, 5 Minortown Road, Woodbury, CT 06798. All four (4) air handler units will be visited and the installation explained. No bids will be considered unless bidders have attended the pre-bid walk through and have signed the attendance list. Work on the project can occur during school hours, except when working on the unit above the Nurse's Office.

All controls shall be Andover/Schneider Electric Controls without exception. These controls must integrate seamlessly with the existing Andover building management control system. Both the heating and chiller lines have antifreeze in the system.

Bids shall be placed on Company Letterhead. No bid bonds are required for this project. Start dates for construction shall be coordinated with the Director of Facilities at Region 14 Schools. The contractor is responsible for obtaining a building permit and all associated fees with the building department for the Town of Woodbury.

All questions should be directed to Mike Molzon, Director of Facilities, Region 14 Schools at (203) 346-8659