

Bear Creek West Ballfield Fencing RFP

Lodi Unified School District · 209-810-3848

astroud@lodiUSD.net · lbrown@lodiUSD.net

Request for Proposals for Bear Creek Fencing Project

Bear Creek High School Address 10555 Thornton Rd. Stockton, CA 95209

SCOPE

OPEN TO C13, CONTRACTORS

Bear Creek High School

- Demo Approx. 400 Linear Feet of existing fencing fabric and dispose of.
- Install Approx. 600 Linear Feet of 8' High Galvanized fence with 1"x9 gauge fabric. (Red/Blue on map)
- Install Approx. 250 Linear Feet of 12' with 1"x9 gauge fabric. (Green/Orange on map)
- Sleeve Approx. 100 Linear Feet of 5' poles to 8' for 8' fabric (Purple on map)
- Sleeve Approx. 100 Linear Feet of 8' poles to 12' for 12' fabric (Orange on map)
- Install (1) man gate 8'x4' with bulldog hinges and fork latch. (Pink on map)
- Install (4) Equipment gate locations to have a 12'min overall opening. Double leaf with 8' with 1"x 9-gauge fabric. (Yellow on map)
- Install mid-rail at wall height on 12' fence by warning track. (Green on map)
- Fence installed on warning track to be 12" above ground for landscape maintenance. (Green on map)
- 10" mow strip to be placed under new fence (In grass areas, not at warning track)
- Concrete to be placed at Home Run fence, from the fence to the wall at same grade as warning track.
- Remove and reinstall foul pole to be in play in front of the new fence.
- All measurements to be verified by the contractor prior to installation.
- The contractor is responsible for having the area USA prior to installation.
- Contractor to locate/GPR prior to removal of existing fence.
- All man gates to be no smaller than 4 feet opening for ADA.
- Terminal Posts to be 2 7/8" or bigger.
- Line posts to be 2 3/8" (not smaller)
- Top Rail 1 5/8"
- 7 ga bottom wire
- Gate hinges shall be bulldog hinges so they can swing in both directions.
- All posts to be a minimum of 36" deep.
- Gates to be 8' with 1"x9 gauge fabric.
- Installers are responsible for keeping site secure with fence panels.
- Clean area and complete final inspection
- Construction Schedule based on 40-hour week.
- All Fencing to be completed before June 30th
- Provide Manufacturer's warranty and 1 year labor warranty