

STATE OF CONNECTICUT – COUNTY OF TOLLAND INCORPORATED 1786

#### TOWN OF ELLINGTON 55 MAIN STREET – PO BOX 187 ELLINGTON, CONNECTICUT 06029-0187

www.ellington-ct.gov

TEL. (860) 870-3120 TOWN PLANNER'S OFFICE FAX (860) 870-3122

#### INLAND WETLANDS AGENCY REGULAR MEETING AGENDA MONDAY, APRIL 21, 2025, 7:00 P.M.

#### IN-PERSON ATTENDANCE: TOWN HALL ANNEX, 57 MAIN STREET, ELLINGTON, CT REMOTE ATTENDANCE: VIA ZOOM MEETING, INSTRUCTIONS PROVIDED BELOW

- I. CALL TO ORDER
- II. PUBLIC COMMENTS (on non-agenda items):
- III. PUBLIC HEARING(S): None
- IV. OLD BUSINESS: None
- V. NEW BUSINESS:
  - IW202419 Abdulsalam Alsaleh and Zak Smith, owner/ Calito Development Group, LLC, applicant, request for modification to a permit to conduct regulated activity to construct a driveway crossing, parking lot, wetlands mitigation area, stormwater basin, and associated site improvements for a retail store on property to be subdivided on the west side of West Road across the street from 175 West Road. Property identified as Assessor Parcel Number 046-003-0002.
  - Request for positive referral to the Planning & Zoning Commission on a resubdivision to create one new 2.37+/- acre lot (S202502) pursuant to Conn. Gen. Stat. 8-26(e) at 20 Punkin Drive, APN 120-026-0004.
  - IW202503 Town of Ellington, owner/applicant, notification of permitted and nonregulated uses to repair the roadway accessing the State Forest and install a gravel parking area at 79 Kibbe Road, APN 142-002-0000.
  - Request to delegate authority to the Wetlands Agent Permit to conduct regulated activity for excavation and grading associated with an earth excavation operation at 90 Sadds Mill Road, APN 079-002-0000.

#### VI. ADMINISTRATIVE BUSINESS:

- 1. Approval of March 17, 2025, Regular Meeting Minutes.
- 2. Election of Officers.
- 3. Correspondence/Discussion:

#### VII. ADJOURNMENT:

Next Regular Meeting is scheduled for May 12, 2025.

Instructions to attend remotely via Zoom Meeting listed below. The agenda is posted on the Town of Ellington webpage (<u>www.ellington-ct.gov</u>) under Agenda & Minutes, Inland Wetlands Agency.

#### Join Zoom Meeting via link

Link: <u>https://us06web.zoom.us/j/82749024375</u> Meeting ID: 827 4902 4375 Passcode: 495735 Join Zoom Meeting by phone: +1 646 558 8656 US (New York) Meeting ID: 827 4902 4375 Passcode: 495735

#### RE: Property ID: 046 003 0002, West Road Requested Modification to IW202419 Calito Development Group, Applicant

#### Summary of Changes

The applicant is seeking a modification to the previously approved wetlands permit to address comments from the State of Connecticut that resulted from their review of the site plan for an Encroachment Permit.

The applicant previously obtained a wetlands permit because the proposed driveway has to cross an existing drainage ditch in order to conform to the Town of Ellington's Access Concept Plan for Route 83. To cross the drainage ditch, two 36" RCP culverts were proposed to be installed that would drain to a newly created wetlands mitigation area on the upstream side of the culverts, just to the west of West Road (CT Route #83). These activities (site grading, construction of the proposed parking lot/drive aisles, and construction of the stormwater basin/stormwater swale) would result in impacts to the upland review area and wetlands.

However, the State of Connecticut objected to the location of the wetlands mitigation area and is requiring that the applicant extend the two existing drainage pipes so that they cross both the drainage ditch and the new driveway. The extended culvert would drain into a riprap scour hole, allowing the water to pool in the vicinity of a wetlands mitigation area proposed to be created on the downstream side within the upland review area, southwest of the proposed building. The increased activity within the upland review area is due to the relocation of the mitigation area, as well as its construction. The existing drainage ditch along the westerly edge of West Road would be filled in to match the grade of the proposed driveway.

#### These changes will result in the following impacts:

Upland Review Area Activity: increase from 34,303 sq. ft. to 40,891 sq. ft. (an increase of 6,588 sq. ft.)

The permanent upland review area activity would be 13,913 sq. ft. This includes the proposed impervious area of the parking lot and drive aisles. The remaining area of 26,978 sq. ft. would be temporarily impacted as it will be lawn space or wetlands mitigation area post construction.

Wetlands Activity: remains at 2,148 sq. ft. (no change)

# **INLAND WETLANDS & WATERCOURSES AGENCY APPLICATION** FOR **PROPOSED 10,640 sq. ft. RETAIL USE BUILDING**

# **OWNER:**


ABDULSALAM M ALSALEH & ZAK SMITH **81 SPRING STREET** WINDSOR, CT 06096

# **APPLICANT & DEVELOPER**


CALITO DEVELOPMENT GROUP ATTN.: MATT EUCALITTO **59 FIELD STREET** TORRINGTON, CT 06790 PHONE NUMBER: 860-280-5825

# FOR PROPERTY LOCATED AT **PROPERTY ID: 046 003 0002** WEST ROAD (ROUTE #83) **ELLINGTON, CONNECTICUT**

DATE: SEP. 19, 2024



**LOCATION MAP** SCALE: 1" = 1,000'





PHONE: (860)-529-6812, FAX: (860)-721-7709


# **SHEET INDEX**


| SHEET # | DRAWING TITLE                                    |
|---------|--|
|         |  |
| 1A & 1B | PROPERTY AND TOPOGRAPHIC SURVEY                  |
| 2A & 2B | (OMMITTED FROM PLAN SET)                         |
| 3       | ZONING IMPROVEMENT LOCATION SURVEY               |
| 4       | SITE GRADING & DRAINAGE PLAN                     |
| 5       | SITE UTILITIES PLAN                              |
| 6       | EROSION & SEDIMENT CONTROL PLAN                  |
| 7       | GENERAL NOTES                                    |
| 8       | SEDIMENT AND EROSION CONTROL NARRATIVE AND NOTES |
| 9       | STORMWATER QUALITY BASIN DETAIL                  |
| 10-17   | SITE DETAILS                                     |
| 18      | CULVERT EXTENSION PLAN                           |
| MIT-1   | WETLANDS MITIGATION PLAN                         |
| PH-1    | SITE LIGHTING PLAN                               |
| A-1     | CONCEPTUAL BUILDING ELEVATIONS                   |
| 2.61    | SITE LANDSCAPING PLAN                            |


| 6   | 03/16/25 | PER CT DOT COMMENT      | JMP |
|-----|----------|-------------------------|-----|
| 5   | 03/12/25 | PER WPCA COMMENT        | JMP |
| 4   | 01/23/25 | PER ENGINEER COMMENT    | JMP |
| 3   | 01/10/25 | PER P&Z COMMENT         | JMP |
| 2   | 12/17/24 | PER TOWN COMMENT        | JMP |
| 1   | 11/06/24 | PER ENGINEERING COMMENT | JMP |
| NO. | DATE     | DESCRIPTION             | BY  |














|   | I IS DI                                       | IST MAY BE REMOVED ONCE THE<br>CONTRIBUTING DRAINAGE AREA IS<br>PERMANENTLY STABILIZED.   | ION TEMPORARY SEDIMENT BASINS THAT ARE<br>NOT TO FUNCTION AS PERMANENT<br>DETENTION BASINS MAY BE REMOVED<br>ONCE THE CONTRIBUTION DRAINAGE AREA<br>IS PERMANENTLY STABILIZED.   |   | TTON HAY BALES MAY BE REMOVED AFTER<br>NDERCUT UPHILL AND SENSITIVE AREAS HAVE<br>BEEN PERMANENTLY STABILIZED.<br>EVADING   | TEMPORARY DIVERSIONS MAY BE<br>REMOVED ONCE CONSTRUCTION HAS<br>CEASED AND THE CONTRIBUTING<br>DRAINAGE AREA HAS BEEN PERMANENTLY<br>STABILIZED.   | I TO SITE CONSTRUCTION ENTRANCE MAY BE REMOVED<br>ONCE THE SITE HAS BEEN PERMARENTLY<br>STABILIZED, AND ALL SECTIONS OF ROADWAY<br>HAVE BEEN PERMANENTLY PAVED.  | INLET PROTECTION MAY BE REMOVED ONCE THE<br>SITE HAS BEEN PERMANENTLY STABLIZED, AND<br>STORM ALL OTHER SECTIONS OF ROADWAY HAVE BEEN<br>PERMANENTLY PAVED.                                   | SHING DUE  | REFEAT APPLCATION OF DUST CONTROL<br>MEASURES UNTIL ALL AREAS ARE PERMANENTLY<br>STABILZED, VEGETATED, AND PAYED, OR AS<br>LONG AS THERE IS AIRBORNE DUST.  | =30° CHECKED BY: JPC | /. 20, 2024 DRAWN BY: JMP | 3486 ACAD FILE: 3486–ES | 6<br>٩.   | :<br>2024 PER TOWN COMMENT<br>2025 PER P&Z COMMENT<br>2025 PER ENGINEER COMMENT |
|---|---|---|--|---|---|--|--|---|--|---|----------------------|---------------------------|-------------------------|---|---|
| S.W.L.<br>S.W.L.<br>S.W.L.<br>S.W.L.<br>PROP. HYDRANT   |   | -TURBID WATER<br>-TURBID WATER<br>-EXCESSIVE SEDIMENT ACCUMULATION<br>-OVERTOPPING EVIDENCE   | -TURBID WATER<br>-TURBID WATER<br>-EXCESSIVE SEDMENT ACCUMULATION<br>-OVERTOPPING EVIDENCE<br>-EROSION OF EMBANKMENTS  | -PHYSICAL DAMAGE OR DECOMPOSITION<br>-EVIDENCE OF OVERTOPPED OR UNDERCUT<br>FENCE<br>-EVIDENCE OF SIGNIFICANT FLOWS EVADING<br>CAPTILINE.   | - HEFETITIVE FALLOR<br>- HYSICAL DAMAGE OR DECOMPOSITION<br>- ENVIENCE OF OVERTOPPED OR UNDERCUT<br>- ENVIENCE OF SIGNIFICANT FLOWS EVADING<br>- APTURE<br>- REPETITIVE FALLURE   | -PHYSICAL DAMAGE<br>-EXCESSIVE SCOURING/EROSION<br>-REPETITIVE FAILURE   | -SEDIMENT IN ROADWAY ADJACENT  | -RIPPED BAG<br>-RIPPED BAG<br>-FALED HAY BALES/SILT FENCE<br>-SIGNFICANT SILT PRESENCE IN<br>-SIGNFICANT SILT PRESENCE IN<br>DRAINAGE SYSTEM OUTFLOW.   | -EVIDENCE OF STOCK PILE DIMINISHING<br>TO RAIN EVENTS<br>-FAILURE OF SILT FENCE  | -AIRBORNE DUST  | SCALE: 1":           | DATE: NOV.                | JOB No.: 3486           | SHEET:  | REVISIONS:<br>DEC. 17, 2<br>JAN. 10, 23, 2                                      |
| S.W.L.<br>656<br>ROP. CL&P-POLE #24656<br>D BE RELOCATED PER<br>L&P REQUIREMENTS<br>PROP. C.B. #4<br>TYPE "C"  <br>T.F.=243.58<br>INV.=239.08<br>PROP. C.B. #1<br>TYPE "C"<br>T.F.=241.50 | INSPECTION/MAINTENANCE                        | INSPECT AT LEAST ONCE A WEEK AND WITHIN 24 HOURS OF THE END OF A STORM WITH<br>A RANFALL OF 0.5 INCHES OR MORE. STONE OUTLET SHOULD BE AT LEAST 1 FOOT<br>BELOW CREST OF EMBANKMENT. SEDIMENT MUST BE REMOVED WHEN ACCUMULATION<br>REACHES ½ OF THE REQUIRED WET STORAGE. | INSPECT AT LEAST ONCE A WEEK AND WITHIN 24 HOURS OF THE END OF A STORM WITH A<br>RAINFALL OF 0.5 INCHES OR GREATER. CLEAN OUT SEDIMENT WHEN ACCUMULATION EXCEEDS<br>\$ OF THE WET STORAGE CAPACITY OR WHEN DEPTH OF AVAILABLE POOL IS REDUCED TO<br>15. PLACE STAKES OR OTHER MEANS TO INDICATE THE THRESHOLD ELEVATION FOR<br>SEDIMENT CLEANOUT | INSPECT AT LEAST ONCE A WEEK AND WITHIN 24 HOURS OF THE END OF A STORM WITH A RAINFALL OF 0.5 INCHES OR MORE. ACCUMULATED SEDIMENT MUST BE REMOVED ONCE ITS DEPTH IS EQUAL TO ½ THE TRENCH HEIGHT, UNSPECT FREQUENTLY DURING FUMPING OPERATIONS OF FOR DEWATERING OPERATIONS. | INSPECT AT LEAST ONCE A WEEK AND WITHIN 24 HOURS OF THE END OF A STORM WITH A A STURKALL OF 0.5 INCHES OR MORE. ACCUMULATED SEDIMENT MUST BE REMOVED ONCE ITS DEPTH IS EQUAL TO ½ OF THE BARRIER. INSPECT FREQUENTLY DURING PUMPING OPERATIONS IF USED FOR DEWATERING OPERATIONS. | WHEN LOCATED WITHIN CLOSE PROXIMITY TO ON GOING CONSTRUCTION ACTIVITIES, INSPECT<br>AT THE END OF EACH WORK DAY AND IMMEDIATELY REPAIR DAMAGES. OTHERWISE INSPECT AT<br>LEAST ONCE A WEEK AND WITHIN 24 HOURS OF THE END OF A STORM WITH A RAINFALL OF<br>0.5 INCHES OR MORE. REPAIR THE TEMPORARY MEASURE AND ANY OTHER ASSOCIATED<br>MEASURES WITHIN 24 HOURS. | INSPECT AT THE END OF EACH WORK DAY AND INMEDIATELY REPAIR DAMAGES.<br>PERIODIC ADDITTON OF STONE OR LENGTHENING OF ENTRANCE MAY BE REQUIRED AS<br>CONDITION OF STONE OR LENGTHENING OF ENTRANCE MAY BE REQUIRED AS<br>DURACES AS A RESULT OF INEFFICIENCY OF CONSTRUCTION ENTRANCE SHALL BE IMMEDIATELY<br>REMOVED. | INSPECT AFTER ANY RAIN EVENT. IF FILTER BAG INSIDE CATCH BASIN CONTAINS MORE THAN 6" OF<br>SEDIMENT, REMOVE SEDIMENT FROM BAG. CHECK SURROUNDING SILT FENCE AND HAY BALES PER<br>NOTED ABOVE. | INSPECT SILT FENCE AT THE END OF EACH WORK DAY AND IMMEDIATELY REPAIR DAMAGES.<br>Periodic Reinforcement of Silt Fence, or addition of hay bales may be necessary. | USE MECHANICAL SWEEPING DAILY ON PAVED AREAS WHERE DUST AND FINE MATERIALS<br>ACCUMULATE, IF HEAVILY TRAFFICKED AND SEDIMENT ACCUMULATES QUICKLY. PERIODICALLY<br>MOISTEN UNPAVED TRAVEL WAYS TO CONTROL DUST WHEN EVIDENCE OF AIRBORNE DUST. |                      |                           | Y, PEARSON & CASSIDY    | ENGINEERS & LAND SURVEYORS<br>630 MAIN STREET. UNIT #1A | /ELL, CONNECTICUT<br>529–6812, FAX: (8  |
| INV.=238.10<br>PROP. S.W.Q.S #1<br>STORMCEPTOR STC450i<br>OR APPROVED EQUAL<br>T.F.= 241.50<br>FL = 238.10<br>STM. M.H. #1<br>243.13<br>NW)=237.62<br>SW)=237.62<br>SE)=237.72            | CONTROL OBJECTIVE                             | -DETAIN SEDIMENT-LADEN RUNOFF FROM SMALL<br>DISTURBED AREAS LONG ENOUGH TO ALLOW A<br>MAJORITY OF THE SEDIMENT TO SETTLE OUT  | -INTERCEPT/RETAIN SEDIMENT DURING CONSTRUCTION.<br>REEVENT TRANSPORT AND DEPOSITION OF<br>SEDIMENT OFF CONSTRUCTION SITE.  | -INTERCEPT AND REDIRECT/DETAIN SMALL AMOUNTS OF<br>SEDMENT FROM SMALL DISTURBED AREAS.<br>DECREASE VELOCITY OF SHEET FLOW.<br>-PROTECT SENSITIVE SLOPES OR SOLLS FROM EXCESSIVE<br>WATER FLOW.  | -INTERCEPT AND REDIRECT/DETAIN SMALL AMOUNTS OF<br>SEDMENT FROM SMALL DISTUBRED AREAS.<br>-DECREASE VELOCITY OF SHEET FLOW.<br>-PROTECT SENSITIVE SLOPES OR SOLLS FROM EXCESSIVE<br>WATER FLOW.   | -MINIMIZE VELOCITY AND CONCENTRATION OF SHEET<br>FLOW ACROSS CONSTRUCTION SITE TO A SEDIMENT<br>TRAPPING FACILITY.<br>-DIVERT WATER ORGINATING FROM UNDISTURBED AREA<br>AWAY FROM CONSTRUCTION.  | -REDUCE THE TRACKING OF SEDIMENT OFF-SITE<br>ON TO PAVED SURFACES.   | -PROHIBIT SILT IN CONSTRUCTION RELATED RUNOFF FROM<br>ENTERING STORM DRAINAGE SYSTEM.   | -RETAIN SOIL STOCKPILE IN LOCATIONS SPECIFIED AND<br>REDUCE WATER TRANSPORT.   | -TO PREVENT MOVEMENT OF DUST FROM EXPOSED SOIL<br>SUBRACES, WHICH MAY CAUSE BOTH OFF-STIE AND<br>ON-STIE DAMAGE, BE A HEALTH HAZARD TO HUMANS,<br>WILDLIFE, AND PLANT LIFE, OR CREATE A HAZARD BY<br>REDUCING TRAFFIC VISIBILITY.             |                      | <                         | HALLISE                 |   | CR<br>PHONE: (8   |
| icres<br>TIVITY<br>)F   | EROSION CONTROL<br>MEASURE                    | TEMPORARY SEDIMENT<br>TRAP (TST)  | temporary sediment basin<br>(detention basin) (SB/PST)   | SILT FENCE (GSF)<br>(RELATED: IP/STK)   | HAY BALES (HB)  | TEMPORARY DIVERSION<br>BERM/SWALE (TBS) OR<br>TEMPORARY SWALE (TSW)<br>OR WATER BAR (WB)   | CONSTRUCTION ENTRANCE<br>(CE)  | CATCH BASIN INLET<br>PROTECTION (IP)  | STOCKPILE PROTECTION (STK)   | DUST PROTECTION (DC)  | ╞                    |                           |                         |   |   |
| 8 BASIN<br>5- acı<br>7  |   | EROSIO  | N LEGEN  | ID  |   |  |  |   |  |   |                      | AN                        |                         |   |   |
|   |   | GSF   | SEDIMENT F   |   | CE  |  |  |   |  |   |                      | ב                         |                         | •   | _   |
|   |   | (HB)<br>(CE)  | STAKED HA  |   | ANCE  |  |  |   |  |   |                      | CONTROL                   |                         | ROUP  | ICUT  |
| REA :<br>LS)  |   | ECB   | EROSION CO<br>GREEN SC11<br>BLANKETS<br>CASE BASIS<br>ALTERNATE<br>SEDIMENT F  | 50 ALONG<br>SHALL BE<br>5. DEPENDI<br>STABILIZA   | SIDE AND<br>MONITOREI<br>ING ON TIN<br>TION PRAC  | REAR SLO<br>D ON A CA<br>ME OF YEAF  | PES)<br>ISE BY<br>R  | PTABLE.   |  |   |                      | SEDIMENT CON              |                         | <b>P</b>  | AD (RT. #83)<br>CONNECT   |
|   |   | STK   | TEMPORARY<br>BY SEDIMEN  |   |   | SURROUND   | ED   |   |  |   |                      | & SED                     |                         |   |   |
| ~~~~  |   | SCD   | STONE CHE  | CK DAM  |   |  |  |   |  |   |                      |                           |                         |   | S L   |
|   |   |   | INLET PROT   | ·   |   |  |  | RAINS)  |  |   |                      | EROSION                   |                         | CALITO<br>PRO   | ELLI  |
|   |   | TST   | TEMPORARY<br>PRIOR TO N<br>SEDIMENT [  | MASS EXC  | AVATION. C  |  |  |   |  |   |                      | SITE E                    |                         |   |   |
| *****   |   | WB  | WATER BAR  | 2   |   |  |  |   |  |   |                      | Ś                         |                         |   |   |
| /   |   | DB  | TEMPORARY  | Y DIVERSIO  | N BERM  |  |  |   |  |   |                      |                           |                         |   |   |
| EE SHEET #8 F<br><u>legend</u>  | =or e   | ROSK  | ON +   |   |   |  |  |   |  |   | F                    |                           |                         |   |   |
| ● <sup>I.P.</sup> FND.<br>◎ <sup>I.P.</sup> FND.<br>IRON F  | NG PROPERTY<br>NG EDGE OF F<br>PIN OR IRON PI | AVEMENT   | -  |   | — W — · · ·   | — PROPOS   | ED STORM I<br>ED WATER M.<br>ED PROPERTY   | 4 <i>IN</i>   | SYSTE  | м   |                      |                           |                         |   |   |
| C.M.S. FND.<br>C.M.S. FND.<br>or C.H.D. FND.<br>C.H.D. FND.   | MERESTONE O                                   |   |  | ····  |   |  | ED TREE LINE   |   |  |   |                      |                           |                         |   |   |
| So Pole / EXIST   | ING TELEPHO                                   | NE POLE   | -  |   |   | _  | ED BIT. CU   |   | ENT  |   |                      |                           | ₩ <sup>₩₩₩₩</sup><br>○F |   |   |
| C.B. PIPE (SIZE. TYPE)  | NG BIT. CURB<br>NG STORM DRA                  | NINAGE SYSTEM   | · · · · · ·  |   |   |  | HEAVY DU   |   |  |   |                      | AND SAN                   | AMES                    | r · CASS  | OL CE   |

PROPOSED CONCRETE

------ EXISTING FENCE

\_\_\_\_\_\_ · · · \_\_\_\_ · · · \_\_\_\_ w \_\_\_\_ · · · \_\_\_

EXISTING WATER MAIN

SOIL TEST LOCATION

#### SITE PLAN NOTES

CONCRETE SIDEWALKS AND RAMPS.

PROVIDED

- I. ALL CONSTRUCTION SHALL COMPLY WITH TOWN OF ELLINGTON. STATE OF CONNECTICUT DEPARTMENT OF TRANSPORTATION STANDARDS AND SPECIFICATIONS IN THE ABOVE REFERENCED HIERARCHY. IF SPECIFICATIONS ARE IN CONFLICT, THE MORE STRINGENT SPECIFICATION SHALL APPLY. ALL CONSTRUCTION SHALL BE PERFORMED IN ACCORDANCE WITH ALL APPLICABLE OSHA, FEDERAL, STATE AND LOCAL REGULATIONS.
- 2. THE OWNER IS RESPONSIBLE FOR OBTAINING ALL NECESSARY ZONING PERMITS REQUIRED BY GOVERNMENT AGENCIES PRIOR TO CONSTRUCTION. THE CONTRACTOR SHALL OBTAIN ALL TOWN CONSTRUCTION PERMITS, INCLUDING DOT PERMITS AND SEWER AND WATER CONNECTION PERMITS. THE CONTRACTOR SHALL POST ALL BONDS, PAY ALL FEES, PROVIDE PROOF OF INSURANCE AND PROVIDE TRAFFIC CONTROL NECESSARY FOR THIS WORK.
- 3. REFER TO OTHER PLANS, DETAILS AND NOTES FOR ADDITIONAL INFORMATION. THE CONTRACTOR SHALL VERIFY ALL SITE CONDITIONS IN THE FIELD AND CONTACT THE SITE ENGINEER IF THERE ARE ANY QUESTIONS OR CONFLICTS REGARDING THE CONSTRUCTION DOCUMENTS AND/OR FIELD CONDITIONS SO THAT APPROPRIATE REVISIONS CAN
- BE MADE PRIOR TO BIDDING. ANY CONFLICT BETWEEN THE DRAWINGS AND SPECIFICATIONS SHALL BE CONFORMED WITH THE LOCAL CONSTRUCTION MANAGER PRIOR TO BIDDING. 4. THE CONTRACTOR SHALL SUBMIT SHOP DRAWINGS OF ALL PRODUCTS, MATERIALS AND PLAN SPECIFICATIONS TO THE OWNER AND SITE ENGINEER FOR REVIEW AND APPROVAL PRIOR TO FABRICATION OR DELIVERY TO THE SITE. ALLOW A MINIMUM OF 14 WORKING DAYS FOR REVIEW.
- 5. THE CONTRACTOR SHALL FOLLOW THE SEQUENCE OF CONSTRUCTION NOTES PROVIDED ON THE EROSION CONTROL PLAN.
- 6. THE CONTRACTOR SHALL REFERENCE ARCHITECTURAL PLANS FOR EXACT DIMENSIONS AND CONSTRUCTION DETAILS OF BUILDINGS AND THE RAISED
- . SHOULD ANY UNCHARTED OR INCORRECTLY CHARTED, EXISTING PIPING OR OTHER UTILITY BE UNCOVERED DURING EXCAVATION, CONSULT THE ENGINEER IMMEDIATELY FOR DIRECTIONS BEFORE PROCEEDING FURTHER WITH WORK IN THIS AREA.
- 8. DO NOT INTERRUPT EXISTING UTILITIES SERVICING FACILITIES OCCUPIED AND USED BY THE OWNER OR OTHERS DURING OCCUPIED HOURS EXCEPT WHEN SUCH INTERRUPTIONS HAVE BEEN AUTHORIZED IN WRITING BY THE OWNER AND THE LOCAL MUNICIPALITIES. INTERRUPTIONS SHALL ONLY OCCUR AFTER ACCEPTABLE TEMPORARY SERVICE HAS BEEN
- 9. ALL SITE DIMENSIONS ARE REFERENCED TO THE FACE OF CURBS OR EDGE OR PAVING UNLESS OTHERWISE NOTED. ALL BUILDING DIMENSIONS ARE REFERENCED TO THE OUTSIDE FACE OF THE STRUCTURE.
- 10. THE CONTRACTOR SHALL PROVIDE AND MAINTAIN TRAFFIC DEVICES FOR PROTECTION OF VEHICLES AND PEDESTRIANS CONSISTING OF DRUMS, BARRIERS, SIGNS, LIGHTS, FENCES, TRAFFIC CONTROLLERS AND UNIFORMED TRAFFIC OFFICERS AS REQUIRED, ORDERED BY THE ENGINEER OR REQUIRED BY THE LOCAL GOVERNING AUTHORITIES.
- 11. REFER TO DETAIL SHEETS FOR PAVEMENT, CURBING, AND SIDEWALK INFORMATION.
- 12. TRAFFIC CONTROL SIGNAGE SHALL CONFORM TO THE STATE DOT STANDARD DETAIL SHEETS AND THE MANUAL OF UNIFORM TRAFFIC CONTROL DEVICES. SIGNS SHALL BE INSTALLED PLUMB WITH THE EDGE OF THE SIGN 2' OFF THE FACE OF THE CURB, AND WITH 7' VERTICAL CLEARANCE UNLESS OTHERWISE DETAILED OR NOTED. 3. THE CONTRACTOR SHALL ABIDE BY ALL OSHA FEDERAL STATE AND LOCAL REGULATIONS WHEN OPERATING CRANES, BOOMS, HOISTS, ETC, IN CLOSE PROXIMITY TO OVERHEAD
- ELECTRIC LINES. IF CONTRACTOR MUST OPERATE EQUIPMENT CLOSE TO ELECTRIC LINES, CONTACT POWER COMPANY TO MAKE ARRANGEMENTS FOR PROPER SAFEGUARDS. ANY UTILITY COMPANY FEES SHALL BE PAID FOR BY THE CONTRACTOR. 14. THE CONTRACTOR SHALL SUBMIT A SHOP DRAWING OF THE PAINT MIXTURE PRIOR TO STRIPING.
- 15. PAVEMENT MARKING KEY:
- 4' SOLID YELLOW DOUBLE LINE 4"SYDL
- 4"SYL 4' SOLID YELLOW LINE 4" SOLID WHITE LINE 4" SWI
- 12" SOLID WHITE STOP BAR 12" SWSB 4"BWL 4" BROKEN WHITE LINE 10' STRIPE 30' SPACE
- 16. PARKING SPACES SHALL BE STRIPED WITH 4" SWL; HATCHED AREA SHALL BE STRIPED WITH 4' SWL AT A 45' ANGLE, 2' ON CENTER. HATCHING SYMBOLS, AND STRIPING
- FOR HANDICAPPED SPACES SHALL BE PAINTED BLUE. OTHER MARKINGS SHALL BE PAINTED WHITE OR AS NOTED.
- 7. THE CONTRACTOR SHALL RESTORE ANY DRAINAGE STRUCTURE, PIPE, UTILITY, PAVEMENT, CURBS, SIDEWALKS, LANDSCAPED AREAS OR SIGNAGE DISTURBED DURING CONSTRUCTION TO THEIR ORIGINAL CONDITION OR BETTER, AS APPROVED BY THE ENGINEER.
- 18. THE CONTRACTOR SHALL PROVIDE AS-BUILT RECORDS OF ALL CONSTRUCTION (INCLUDING UNDERGROUND UTILITIES) TO THE OWNER AT THE END OF CONSTRUCTION. 19. THE ARCHITECT OR ENGINEER IS NOT RESPONSIBLE FOR SITE SAFETY MEASURES TO BE EMPLOYED DURING CONSTRUCTION. THE ARCHITECT AND ENGINEER HAVE NO CONTRACTUAL DUTY TO CONTROL THE SAFEST METHODS OR MEANS OF THE WORK, JOB SITE RESPONSIBILITIES, SUPERVISION OR TO SUPERVISE SAFETY AND DOES NOT VOLUNTARILY ASSUME ANY SUCH DUTY OR RESPONSIBILITY.
- 20. THE CONTRACTOR SHALL COMPLY WITH CFR 29 PART 1926 FOR EXCAVATION TRENCHING AND TRENCH PROTECTION REQUIREMENTS..
- 21. ALTERNATIVE METHODS AND PRODUCTS OTHER THAN THOSE SPECIFIED MAY BE USED IF REVIEWED AND APPROVED BY THE OWNER, SITE ENGINEER, AND APPROPRIATE REGULATORY AGENCY PRIOR TO INSTALLATION DURING THE BIDDING PROCESS.
- 22. INFORMATION ON EXISTING UTILITIES AND STORM DRAINAGE SYSTEMS HAS BEEN COMPILED FROM AVAILABLE INFORMATION INCLUDING UTILITY COMPANY AND MUNICIPAL RECORD MAPS AND/OR FIELD SURVEY AND IS NOT GUARANTEED CORRECT OR COMPLETE. UTILITIES AND STORM DRAINAGE SYSTEMS ARE SHOWN TO ALERT THE CONTRACTOR TO THEIR PRESENCE AND THE CONTRACTOR IS SOLELY RESPONSIBLE FOR DETERMINING ACTUAL LOCATIONS AND ELEVATIONS OF ALL UTILITIES AND STORM DRAINAGE SYSTEMS INCLUDING SERVICES. PRIOR TO DEMOLITION OR CONSTRUCTION. THE CONTRACTOR SHALL CONTACT "CALL BEFORE YOU DIG" 72 HOURS BEFORE COMMENCEMENT OF WORK AT "1(800)922-4455" AND VERIFY ALL UTILITY AND STORM DRAINAGE SYSTEM LOCATIONS.
- 23. PAVEMENT MARKINGS SHALL BE HOT APPLIED TYPE IN ACCORDANCE WITH CT DOT SPECIFICATIONS, UNLESS WHERE EPOXY RESIGN PAVEMENT MARKINGS ARE INDICATED. 24. AN EROSION CONTROL BOND IS REQUIRED TO BE POSTED BY THE CONTRACTOR BEFORE THE START OF ANY ACTIVITY ON OR OFF SITE.
- 25. THESE PLANS ARE FOR PERMITTING PURPOSES ONLY AND ARE NOT FOR CONSTRUCTION. NO CONSTRUCTION OR DEMOLITION SHALL BEGIN UNTIL APPROVAL OF THE FINAL PLANS IS GRANTED BY ALL GOVERNING AND REGULATORY AGENCIES.
- 26. THESE PLANS ARE FOR PERMITTING
- 27. THE SITE IS PROPOSED TO BE SERVICED BY PUBLIC WATER AND SEWER.
- 28. PROPERTY SHOWN ON F.I.R.M. NO. 09007C0129G. DATED: AUG. 28, 2008. THIS PROPORTY IS IN FLOOD ZONE "X". NOT A FLOOD ZONE
- 29. 12" SWSB (STOP BAR) AND 4" SYDL AND SWL PAVEMENT MARKINGS LOCATED IN DRIVEWAYS AND IN STATE HIGHWAY SHALL BE EPOXY RESIN TYPE ACCORDING TO CT DOT SPECIFICATIONS.
- 30. FIRE LANES SHALL BE ESTABLISHED AND PROPERLY DESIGNATED IN ACCORDANCE WITH THE REQUIREMENTS OF THE TOWN FIRE MARSHAL.
- 31. THE APPLICANT WILL PROVIDE AND MAINTAIN ADEQUATE SIGHT DISTANCES AT ALL DRIVEWAY INTERSECTIONS. CURRENT STATE OF CONNECTICUT HIGHWAY DESIGN STANDARDS WILL APPLY TO REQUIRED SIGHT DISTANCES.
- 32. THE APPLICANT WILL REGISTER BUILDING ALARMS PER TOWN ORDINANCE.
- 33. THE APPLICANT WILL CONTROL DUST AND DEBRIS ON THE SURROUNDING ROADWAYS DURING CONSTRUCTION. PROPER SAFETY PRECAUTIONS AND EQUIPMENT ARE TO BE UTILIZED WHEN WORKING ON PUBLIC ROADWAYS AND ARE THE APPLICANT'S RESPONSIBILITY TO PROVIDE.
- 34. THE APPLICANT WILL OBTAIN A CONNECTICUT DEPARTMENT OF TRANSPORTATION ENCROACHMENT PERMIT FOR ANY WORK DONE IN THE STATE RIGHT OF WAY.
- 35. THE APPLICANT MUST COMPLY WITH CONNECTICUT DEPARTMENT OF TRANSPORTATION STIPULATIONS/REGULATIONS WHEN APPLICABLE.
- 36. ALL DISTURBED PAVEMENT MARKINGS MUST BE REPLACED WITH EPOXY PAINT.
- 37. A BUILDING PERMIT FROM THE TOWN OF ELLINGTON IS REQUIRED FOR RETAINING WALLS IN EXCESS OF 30" IN HEIGHT. CONTRACTOR IS RESPONSIBLE FOR OBTAINING THE BUILDING PERMIT.

## GRADING AND DRAINAGE NOTES

- GRADING GENERAL NOTES:
- CONNECTION LOCATIONS AND DETAILS.

- STATE OF CONNECTICUT.
- PRODUCT NOTES:
- MANUFACTURERS RECOMMENDED PROCEDURE.

- THROUGHOUT THE PROJECT.
- OR DEMOLITION SHALL BEGIN UNTIL APPROVAL OF THE FINAL PLANS IS GRANTED BY ALL GOVERNING AND REGULATORY AGENCIES.

- TO ORDERING
- GENERAL NOTES
- DOCUMENTS AND/OR FIELD CONDITIONS.
- SERVICE HAS BEEN PROVIDED.

- DOES NOT VOLUNTARILY ASSUME ANY SUCH DUTY OR RESPONSIBILITY.

1. SEE THIS PLAN SHEET FOR ADDITIONAL SITE PLAN AND GENERAL NOTES.

THE GRADING AND DRAINAGE PLAN IS INTENDED TO DESCRIBE GRADING AND DRAINAGE ONLY. REFER TO SITE PLAN FOR GENERAL INFORMATION, AND DETAIL SHEETS FOR DETAILS. SEE MEP DRAWINGS FOR BUILDING

3. THE CONTRACTOR SHALL PRESERVE EXISTING VEGETATION WHERE POSSIBLE AND/OR AS NOTED ON DRAWINGS. REFER TO EROSION CONTROL PLAN FOR LIMIT OF DISTURBANCE AND NOTES. 4. TOPSOIL SHALL BE STRIPPED AND STOCKPILED FOR USE IN FINAL LANDSCAPING.

5. THE CONTRACTOR IS RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS REQUIRED BY GOVERNMENT AND LOCAL AGENCIES PRIOR TO CONSTRUCTION. THE CONTRACTOR SHALL OBTAIN ALL NECESSARY PERMITS FROM THE LOCAL MUNICIPALITIES REQUIRED TO PERFORM ALL REQUIRED WORK, INCLUDING FOR STREET CUTS AND CONNECTIONS TO EXISTING UTILITIES. THE CONTRACTOR SHALL POST ALL BONDS, PAY ALL FEES, PROVIDE PROOF OF INSURANCE AND PROVIDE TRAFFIC CONTROL NECESSARY FOR THIS WORK.

6. THE CONTRACTOR SHALL PROVIDE AND MAINTAIN TRAFFIC DEVICES FOR PROTECTION OF VEHICLES AND PEDESTRIANS CONSISTING OF DRUMS, BARRIERS, SIGNS, LIGHTS FENCES AND UNIFORMED TRAFFIC CONTROLLERS AS REQUIRED, ORDERED BY THE ENGINEER OR REQUIRED BY THE STATE AND LOCAL GOVERNING AUTHORITIES.

7. THE CONTRACTOR SHALL COMPACT FILL IN 12" MAXIMUM LIFTS UNDER ALL PARKING, BUILDING, AND DRIVE AREAS TO 95% OF THE MAXIMUM DRY DENSITY AS DETERMINED BY ASTM D1557 (MODIFIED PROCTOR TEST), OR AS DIRECTED BY THE GEOTECHNICAL ENGINEER.

8. UNDERDRAINS SHALL BE ADDED, IF DETERMINED NECESSARY IN THE FIELD BY THE DESIGN OR TOWN ENGINEER AFTER SUBGRADE IS ROUGH GRADED, AS APPROVED BY THE ELLINGTON TOWN STAFF. 9. VERTICAL DATUM IS NVGD 1988.

10. CLEARING LIMITS SHALL BE PHYSICALLY MARKED IN THE FIELD AND APPROVED BY THE TOWN OF ELLINGTON AGENT PRIOR TO THE START OF WORK ON THE SITE.

11. PROPER CONSTRUCTION PROCEDURES SHALL BE FOLLOWED ON ALL IMPROVEMENTS WITHIN THIS PARCEL SO AS TO PREVENT THE SILTING OF ANY WATERCOURSE OR WETLANDS IN ACCORDANCE WITH THE REGULATIONS OF THE DEPARTMENT OF ENVIRONMENTAL PROTECTION GUIDELINES FOR SOIL EROSION AND SEDIMENT POLLUTION CONTROL. IN ADDITION, THE CONTRACTOR SHALL STRICTLY ADHERE TO THE "EROSION CONTROL PLAN" CONTAINED HEREIN. THE CONTRACTOR SHALL BE RESPONSIBLE TO POST ALL BONDS AS REQUIRED BY THE LOCAL MUNICIPALITIES, OR SOIL CONSERVATION SERVICE WHICH WOULD GUARANTEE THE PROPER IMPLEMENTATION OF THE PLAN.

12. ALL SITE WORK, MATERIALS OR CONSTRUCTION, AND CONSTRUCTION METHODS FOR EARTHWORK STORM DRAINAGE AND UTILITY WORK SHALL CONFORM TO THE SPECIFICATIONS AND DETAILS AND APPLICABLE SECTIONS OF THE STATE OF CONNECTICUT DEPARTMENT OF TRANSPORTATION UNLESS OTHERWISE STATED IN THE PROJECT MANUAL SPECIFICATIONS. ALL FILL MATERIALS UNDER STRUCTURES AND PAVED AREAS SHALL BE PER THE SPECIFICATIONS, AND/OR PROJECT GEOTECHNICAL REPORT, AND SHALL BE PLACED IN ACCORDANCE WITH THE SPECIFICATIONS OF THE DOT, UNDER THE SUPERVISION OF A QUALIFIED PROFESSIONAL ENGINEER. MATERIAL SHALL BE COMPACTED IN 12" LIFTS TO 95% OF THE MAXIMUM DRY DENSITY AS DETERMINED BY ASTM D 1557 AT 3 +/- PERCENT OF OPTIMUM MOISTURE CONTENT.

13. ALL DISTURBANCE INCURRED TO TOWN OR STATE PROPERTY DUE TO CONSTRUCTION SHALL BE RESTORED TO ITS PREVIOUS CONDITION OR BETTER, TO THE SATISFACTION OF THE TOWN OF ELLINGTON AUTHORITY AND

14. ALL CONSTRUCTION SHALL COMPLY WITH THE LOCAL MUNICIPALITY'S STANDARDS AND STATE OF CONNECTICUT'S DOT SPECIFICATIONS. ALL CONSTRUCTION WITHIN A DOT RIGHT OF WAY SHALL COMPLY WITH ALL DEPARTMENT OF TRANSPORTATION STANDARDS. WHERE SPECIFICATIONS OR STANDARDS ARE IN CONFLICT, THE MORE STRINGENT SPECIFICATION OR STANDARD SHALL BE SUPERIOR.

1. SHOP DRAWINGS: THE CONTRACTOR SHALL SUBMIT SHOP DRAWINGS OF MATERIALS AND STRUCTURES FOR REVIEW AND APPROVAL PRIOR TO DELIVERY TO THE SITE. ALLOW 14 WORKING DAYS FOR REVIEW. 2. POLY VINYL CHLORIDE PIPE (PVCP) FOR STORM AND SANITARY PIPING SHALL HAVE BUILT-IN RUBBER GASKET JOINTS. PVCP SHALL CONFORM TO ASTM D-3034 (SDR35) WITH COMPRESSION JOINTS AND MOLDED FITTINGS. PVCP SHALL BE INSTALLED IN ACCORDANCE WITH THE DETAILS; ASTM-D2321 AND

3. ALL RCP SHALL CONFORM TO THE REQUIREMENTS OF ASTM C-76; ALL RCP SHALL BE CLASS IV UNLESS OTHERWISE SHOWN. JOINTS SHALL CONFORM TO THE REQUIREMENTS OF ASTM C-443. 4. MANHOLE SECTIONS AND CONSTRUCTION SHALL CONFORM TO ASTM C-478.

5. HIGH DENSITY POLYETHYLENE (HDPE) STORM SEWER 12" OR GREATER IN DIAMETER SHALL BE HI-Q SURE-LOK 10.8 PIPE AS MANUFACTURED BY HANCOR INC. OR APPROVED EQUAL. HDPE PIPE SHALL HAVE SMOOTH INTERIOR AND CORRUGATED EXTERIOR AND SHALL MEET THE REQUIREMENTS OF ASSHTO M294, TYPE PIPE SECTIONS SHALL BE JOINED WITH BELL-AND-SPIGOT JOINT MEETING THE REQUIREMENTS OF AASHTOS. M294. THE BELL SHALL BE AN INTEGRAL PART OF THE PIPE AND PROVIDE A MINIMUM PULL-APART STRENGTH OF 400 POUNDS. THE JOINT SHALL BE WATERTIGHT ACCORDING TO THE REQUIREMENTS OF ASTM D3212. GASKETS SHALL BE MADE OF POLYISOPRENE MEETING THE REQUIREMENTS OF ASTM F477. ALTERNATIVE HDPE PIPE MAY BE USED IF APPROVED BY THE ENGINEER AND CONSTRUCTION MANAGER PRIOR

6. HIGH DENSITY POLYETHYLENE (HDPE) STORM SEWER LESS THAN 12" IN DIAMETER SHALL BE HI-Q PIPE AS MANUFACTURED BY HANCOR INC. OR APPROVED EQUAL. HDPE PIPE SHALL HAVE SMOOTH INTERIOR AND CORRUGATED EXTERIOR AND SHALL MEET THE REQUIREMENTS OF AASHTO 252, TYPE S. PIPE SECTIONS SHALL BE JOINED WITH COUPLING BANDS OR EXTERNAL SNAP COUPLERS COVERING AT LEAST 2 FULL CORRUGATIONS ON EACH END OF THE PIPE. SILT-TIGHT (GASKET) CONNECTIONS SHALL INCORPORATE A CLOSED SYNTHETIC EXPANDED RUBBER GASKET. MEETING THE REQUIREMENTS OF AASHTO D1056 GRADE 2A2. GASKETS SHALL BE INSTALLED ON THE CONNECTION BY THE PIPE MANUFACTURER. ALTERNATIVE HDPE PIPE MAY BE USED IF APPROVED BY THE ENGINEER AND CONSTRUCTION MANAGER PRIOR TO ORDERING.

1. THE CONTRACTOR SHALL VERIFY ALL SITE CONDITIONS IN THE FIELD AND CONTACT THE SITE ENGINEER AND ARCHITECT IF THERE ARE ANY QUESTIONS OR CONFLICTS REGARDING THE CONSTRUCTION

2. DO NOT INTERRUPT EXISTING UTILITIES SERVICING FACILITIES OCCUPIED AND USED BY THE OWNER OR OTHERS DURING OCCUPIED HOURS EXCEPT WHEN SUCH INTERRUPTIONS HAVE BEEN AUTHORIZED IN WRITING BY THE OWNER AND THE LOCAL MUNICIPALITIES. INTERRUPTIONS SHALL ONLY OCCUR AFTER ACCEPTABLE TEMPORARY

3. THE CONTRACTOR SHALL ABIDE BY ALL OSHA FEDERAL STATE AND LOCAL REGULATIONS WHEN OPERATING CRANES, BOOMS, HOISTS, ETC. IN CLOSE PROXIMITY TO OVERHEAD ELECTRIC LINES. IF CONTRACTOR MUST OPERATE EQUIPMENT CLOSE TO ELECTRIC LINES, CONTACT POWER COMPANY TO MAKE ARRANGEMENTS FOR PROPER SAFEGUARDS. ANY UTILITY COMPANY FEES SHALL BE PAID FOR BY THE CONTRACTOR. 4. THE CONTRACTOR SHALL PROVIDE RECORD DRAWINGS OF ALL CONSTRUCTION (INCLUDING UNDERGROUND

UTILITIES) TO THE OWNER AT THE END OF CONSTRUCTION. 5. THE ARCHITECT OR ENGINEER IS NOT RESPONSIBLE FOR SITE SAFETY MEASURES TO BE EMPLOYED DURING CONSTRUCTION. THE ARCHITECT AND ENGINEER HAVE NO CONTRACTUAL DUTY TO CONTROL THE SAFEST METHODS OR MEANS OF THE WORK, JOB SITE RESPONSIBILITIES, SUPERVISION OR TO SUPERVISE SAFETY AND

6. INFORMATION ON EXISTING UTILITIES AND STORM DRAINAGE SYSTEMS HAS BEEN COMPILED FROM AVAILABLE INFORMATION INCLUDING UTILITY COMPANY AND MUNICIPAL RECORD MAPS AND/OR FIELD SURVEY AND IS NOT GUARANTEED CORRECT OR COMPLETE. UTILITIES AND STORM DRAINAGE SYSTEMS ARE SHOWN TO ALERT THE CONTRACTOR TO THEIR PRESENCE AND THE CONTRACTOR IS SOLELY RESPONSIBLE FOR DETERMINING ACTUAL LOCATIONS AND ELEVATIONS OF ALL UTILITIES AND STORM DRAINAGE SYSTEMS INCLUDING SERVICES. PRIOR TO DEMOLITION OR CONSTRUCTION, THE CONTRACTOR SHALL CONTACT "CALL BEFORE YOU DIG" 72 HOURS BEFORE COMMENCEMENT OF WORK AT "811" AND VERIFY ALL UTILITY AND STORM DRAINAGE SYSTEM LOCATIONS. 7. DO NOT SCALE DRAWINGS. DIMENSIONS GOVERN OVER SCALED DIMENSIONS.

8. IF PLANS AND OR SPECIFICATIONS ARE IN CONFLICT, THE MOST EFFECTIVE SHALL APPLY AS DETERMINED BY A LICENSED PROFESSIONAL AND APPROVED BY TOWN STAFF.

9. ALL CONTRACTORS AND SUBCONTRACTORS SHALL OBTAIN COMPLETE DRAWING PLAN SETS FOR BIDDING AND CONSTRUCTION. PLAN SETS SHALL NOT BE DISASSEMBLED INTO PARTIAL PLAN SETS FOR USE BY CONTRACTORS AND SUBCONTRACTORS OF INDIVIDUAL TRADES. IT SHALL BE THE CONTRACTOR'S AND SUBCONTRACTOR'S RESPONSIBILITY TO OBTAIN COMPLETE PLAN SETS FOR USE IN BIDDING AND CONSTRUCTION. 10. ALL NOTES AND DIMENSIONS DESIGNATED "TYPICAL" APPLY TO ALL LIKE OR SIMILAR CONDITIONS

11. CONTRACTOR'S TO TAKE AND VERIFY ALL DIMENSIONS AND CONDITIONS OF THE WORK AND BE RESPONSIBLE FOR COORDINATION OF SAME. FIELD VERIFY ALL EXISTING CONDITIONS PRIOR TO START OF WORK. 12. THESE PLANS ARE FOR PERMITTING PURPOSES ONLY AND ARE NOT FOR CONSTRUCTION. NO CONSTRUCTION

## UTILITIES NOTES

#### UTILITY CONSTRUCTION NOTES:

1. CONTRACTOR IS RESPONSIBLE FOR CONTACTING THE LOCAL MUNICIPALITIES TO SECURE PERMITS AND FOR PAYMENT OF FEES FOR STREET CUTS AND CONNECTIONS TO EXISTING UTILITIES.

- 2. THE CONTRACTOR SHALL PROVIDE AND MAINTAIN TRAFFIC DEVICES FOR PROTECTION OF VEHICLES AND PEDESTRIANS CONSISTING OF DRUMS, BARRIERS, SIGNS, LIGHTS FENCES AND UNIFORMED TRAFFIC CONTROLLERS AS REQUIRED, ORDERED BY THE ENGINEER OR REQUIRED BY THE LOCAL GOVERNING AUTHORITIES.
- 3. THIS PLAN DETAILS SITE INSTALLED PIPES UP TO 5' FROM THE BUILDING FACE. REFER TO DRAWINGS BY OTHERS FOR BUILDING CONNECTION POINT OR AT EXISTING UTILITY OR PIPE CONNECTION POINT.
- 4. THE CONTRACTOR SHALL VISIT THE SITE AND VERIFY THE ELEVATION AND LOCATION OF ALL UTILITIES BY VARIOUS MEANS PRIOR TO BEGINNING ANY EXCAVATION. TEST PITS SHALL BE DUG AT ALL LOCATIONS WHERE SEWERS CROSS UTILITIES, AND THE HORIZONTAL AND VERTICAL LOCATIONS OF THE UTILITIES SHALL BE DETERMINED. THE CONTRACTOR SHALL CONTACT THE SITE ENGINEER IN THE EVENT OF ANY DISCOVERED OR UNFORESEEN CONFLICTS BETWEEN EXISTING AND PROPOSED UTILITIES SO THAT AN APPROPRIATE MODIFICATION MAY BE MADE.
- 5. UTILITY CONNECTION DESIGN AS REFLECTED ON THE PLAN MAY CHANGE SUBJECT TO UTILITY CO. AND TOWN STAFF REVIEW.
- 6. THE CONTRACTOR SHALL ENSURE THAT ALL UTILITY COMPANIES AND TOWN STANDARDS FOR MATERIALS AND CONSTRUCTION METHODS ARE MET. THE CONTRACTOR SHALL PERFORM PROPER COORDINATION WITH THE RESPECTIVE UTILITY PROVIDER, TOWN OF ELLINGTON PUBLIC WORKS DEPARTMENT AND TOWN OF ELLINGTON WATER & SEWER DEPARTMENT.
- 7. THE CONTRACTOR SHALL ARRANGE FOR AND COORDINATE WITH THE RESPECTIVE UTILITY COMPANIES FOR SERVICE INSTALLATIONS AND CONNECTIONS. THE CONTRACTOR SHALL COORDINATE WORK TO BE PERFORMED BY THE VARIOUS UTILITY COMPANIES AND SHALL PAY ALL FEES FOR CONNECTIONS, DISCONNECTION, REALLOCATIONS, INSPECTIONS, AND DEMOLITION.
- 8. ALL EXISTING PAVEMENT WHERE UTILITY PIPING IS TO BE INSTALLED SHALL BE SAW CUT. AFTER UTILITY INSTALLATION IS COMPLETED THE SITE CONTRACTOR SHALL INSTALL TEMPORARY OR PERMANENT PAVEMENT REPAIR AS DETAILED ON THE PLANS OR AS REQUIRED BY THE AUTHORITY HAVING JURISDICTION. 9. ALL PIPES SHALL BE LAID ON STRAIGHT ALIGNMENTS AND EVEN GRADES USING A PIPE LASER OR OTHER
- ACCURATE METHOD. 10. SANITARY LATERAL SHALL MAINTAIN (10' MIN. HORIZONTAL 1.5' VERTICAL MIN.) SEPARATION DISTANCE
- FROM WATER LINES, OR ADDITIONAL PROTECTION MEASURES WILL BE REQUIRED WHERE PERMITTED. 11. RELOCATION OF UTILITY COMPANY FACILITIES SUCH AS POLES, TO BE DONE IN ACCORDANCE WITH THE REQUIREMENTS OF THE FACILITY OWNERS.
- 12. THE CONTRACTOR SHALL COMPACT THE PIPE BACKFILL IN 12" LIFTS ACCORDING TO THE PIPE BEDDING DETAILS. TRENCH BOTTOM SHALL BE STABLE IN HIGH GROUNDWATER AREAS. A PIPE FOUNDATION SHALL BE USED IN AREAS OF ROCK EXCAVATION. STORM SEWERS MAY BE PLACED PRIOR TO PLACING FILL.
- 13. CONTRACTOR TO PROVIDE SLEEVES UNDER FOOTINGS FOR UTILITY CONNECTIONS. 14. UTILITY PENETRATIONS AND LOCATIONS ARE SHOWN FOR THE CONTRACTOR'S INFORMATION AND SHALL BE VERIFIED WITH THE MEP DRAWINGS AND CONSTRUCTION MANAGER.
- 15. ALL UTILITY CONSTRUCTION IS SUBJECT TO INSPECTION FOR APPROVAL PRIOR TO BACKFILLING, IN ACCORDANCE WITH THE APPROPRIATE UTILITY COMPANY AND/OR THE LOCAL MUNICIPALITIES' REQUIREMENTS. 16. A ONE-FOOT MINIMUM CLEARANCE BETWEEN WATER, GAS, ELECTRICAL, AND TELEPHONE LINES AND STORM SEWERS SHALL BE PROVIDED. A ONE-FOOT MINIMUM CLEARANCE SHALL BE MAINTAINED BETWEEN STORM AND SANITARY SEWER WITH A CONCRETE ENCASEMENT.
- 17. CONTRACTOR SHALL PROVIDE ALL BENDS, FITTINGS, ADAPTERS, ETC., AS REQUIRED FOR PIPE CONNECTIONS TO BUILDING STUB OUTS, INCLUDING ROOF/FOOTING DRAIN CONNECTIONS TO ROOF LEADERS AND TO STORM DRAINAGE SYSTEM.
- 18. MANHOLE RIMS SHALL BE SET TO ELEVATIONS SHOWN. SET ALL EXISTING MANHOLE FRAMES AND VALVE COVERS TO BE RAISED OR LOWERED FLUSH WITH FINAL GRADE AS NECESSARY.
- 19. SITE CONTRACTOR SHALL COORDINATE INSTALLATION OF CONDUIT AND CABLES FOR SITE LIGHTING WITH THE BUILDING ELECTRICIAN / ELECTRICAL CONTRACTOR. 20. CONTRACTOR SHALL COORDINATE INSTALLATION FOR ELECTRICAL SERVICES TO PYLON SIGNS AND SITE
- LIGHTING WITH THE BUILDING ELECTRICIAL/ELECTRICAL CONTRACTOR. 21. THE CONTRACTOR SHALL RESTORE ANY UTILITY STRUCTURE, PIPE, UTILITY, PAVEMENT, CURBS, SIDEWALKS,
- OR LANDSCAPED AREAS DISTURBED DURING CONSTRUCTION, TO THEIR ORIGINAL CONDITION OR BETTER. 22. INFORMATION ON EXISTING UTILITIES HAS BEEN COMPILED FROM AVAILABLE INFORMATION INCLUDING UTILITY COMPANY AND MUNICIPAL RECORD MAPS AND/OR FIELD SURVEY AND IS NOT GUARANTEED CORRECT OR COMPLETE. UTILITIES ARE SHOWN TO ALERT THE CONTRACTOR TO THEIR PRESENCE. THE CONTRACTOR IS SOLELY RESPONSIBLE FOR DETERMINING ACTUAL LOCATIONS AND ELEVATIONS OF ALL UTILITIES INCLUDING SERVICES. CONTACT "CALL BEFORE YOU DIG" AT 1-(800)-922-4455 72 HOURS PRIOR TO CONSTRUCTION AND
- VERIFY ALL UNDERGROUND AN OVERHEAD UTILITY LOCATIONS. 23. THE CONTRACTOR SHALL ARRANGE AND COORDINATE WITH UTILITY COMPANIES AND THE TOWN OF ELLINGTON FOR WORK TO BE PERFORMED BY UTILITY COMPANIES OR BY THE TOWN OF ELLINGTON. THE CONTRACTOR SHALL PAY ALL UTILITY FEES AND REPAIR PAVEMENTS AS NECESSARY.
- 24. ELECTRIC, AND TELEPHONE SERVICES SHALL BE INSTALLED UNDERGROUND FROM SERVICE POLE CL&P #1543. THE CONTRACTOR SHALL INSTALL AND BACKFILL TWO 4" PVC CONDUITS FOR TELEPHONE SERVICE, FOUR 4" PVC CONDUITS FOR ELECTRIC SERVICE PRIMARY, PVC CONDUITS FOR ELECTRICAL SECONDARY PER BUILDING ELECTRICAL PLANS (SCHEDULE 80N UNDER PAVEMENT, SCHEDULE 40 IN NON PAVEMENT AREAS). SERVICES MAY BE INSTALLED IN A COMMON TRENCH WITH 1" CLEAR SPACE BETWEEN. MINIMUM COVER IS 36" ON ELECTRIC CONDUITS, AND 24" ON TELEPHONE CONDUITS. SERVICES SHALL BE MARKED WITH MAGNETIC LOCATOR TAPE AND SHALL BE BEDDED, INSTALLED, AND BACKFILLED IN ACCORDANCE WITH ELECTRIC COMPANY, AND PHONE COMPANY STANDARDS. GALVANIZED STEEL ELECTRICAL CONDUIT SHALL BE USED AT POLE AND TRANSFORMER LOCATIONS. INSTALL HANDHOLES AS REQUIRED. INSTALL CONCRETE ENCASEMENT ON PRIMARY ELECTRIC CONDUITS IF REQUIRED BY ELECTRIC COMPANY.
- 25. ALL WATER LINES TO HAVE A MINIMUM COVER OF 54-INCHES. ALL LINES SHALL BE BEDDED IN 6" SAND AND BACKFILLED WITH 12" SAND.
- 26. ALL WATER MAINS, WATER SERVICES AND SANITARY SEWER LATERAL SHALL CONFORM TO THE DEPARTMENT OF ENVIRONMENTAL HEALTH. APPLICABLE TOWN OF ELLINGTON WATER & SEWER DEPARTMENT SPECIFICATIONS, AS WELL AS TO OTHER APPLICABLE CODES AND SPECIFICATIONS FOR POTABLE WATER SYSTEMS 27. ALTERNATIVE METHODS AND PRODUCTS OTHER THAN THOSE SPECIFIED MAY BE USED IF REVIEWED AND
- APPROVED BY THE OWNER, ENGINEER, UTILITY PROVIDER AND APPROPRIATE REGULATORY AGENCIES PRIOR TO INSTALLATION.
- 28. THE CONTRACTOR SHALL MAINTAIN ALL UTILITY CONNECTIONS TO EXISTING ABUTTING HOUSES & COMMERCIAL BUILDINGS WITHOUT INTERRUPTION UNLESS/UNTIL AUTHORIZED TO DISCONNECT BY THE OWNERS, THE PROJECT ENGINEER, UTILITY PROVIDER AND GOVERNING AUTHORITIES.
- 29. ANY EXISTING POTABLE WATER WELLS AND SEPTIC TANKS/ABSORPTION AREAS SHALL BE ABANDONED AND REMOVED PER THE DEPARTMENT OR ENVIRONMENTAL PROTECTION AND HEALTH CODE REQUIREMENTS. 30. THE CONTRACTOR MAY SUBSTITUTE MASONRY STRUCTURES FOR PRECAST STRUCTURES IF APPROVED BY
- THE SITE ENGINEER AND ALLOWED BY THE TOWN ENGINEER OR BY GOVERNING AUTHORITY. 31. THE APPROVED SEWER CAPACITY FOR THE SUBJECT RETAIL BUILDING IS 1,064 GALLONS PER DAY.

## POST CONSTRUCTION STORM WATER POLLUTION PLAN

RESPONSIBLE PARTIES AND STORMWATER MANAGEMENT SYSTEM OWNER: CALITO DEVELOPMENT GROUP ATTN: MATT EUCALITTO 59 FIELD STREET, TORRINGTON, CT 06790 PHONE: 860-280-5825

THE FOLLOWING PROCEDURES WILL BE IMPLEMENTED CONTINUALLY BY THE OWNER:

- 1. PAVEMENT SWEEPING: PARKING LOTS AND DRIVES SHALL BE SWEPT A MINIMUM OF TWICE A YEAR (SPRING AND FALL) 2. CATCH BASINS: CATCH BASINS SHALL BE INSPECTED ON A REGULAR BASIS (AT LEAST TWICE PER YEAR) AND ANY SEDIMENT, OILS & FLOATABLES WILL BE REMOVED AS NECESSARY ( A MINIMUM OF ONCE A YEAR TO ENSURE FUNCTIONING
- OF THE SYSTEM, UTILIZING A VACUUM TRUCK) 3. THE COLLECTION SYSTEM PIPES SHALL BE AT SIX-MONTH INTERVALS. REGULAR MAINTENANCE INCLUDES THE FOLLOWING ITEMS:
- -INSPECTION OF THE OUTLET TO ENSURE THEY ARE NOT BLOCKED. -CHECKING THE OUTLETS FROM THE DRAINAGE SYSTEM IS CLEAR AND NOT ERODING. -REMOVING PAPER AND DEBRIS FROM INSIDE THE BASIN.
- 4. THE SEDIMENT FOREBAY SHALL BE INSPECTED A MINIMUM OF EVERY SIX MONTHS IN THE MONTHS OF APRIL AND OCTOBER. IF TRASH, DEBRIS, SEDIMENT DEPOSITS, ECT. SHALL BE NOTED AND ANY DEPOSITS FOUND TO BE 4 INCHES OR MORE, AS MEASURED FROM THE BOTTOM OF THE FOREBAY SHALL BE CLEANED AND REMOVED. ANY DEBRIS OR TRASH, ECT. SHALL BE REMOVED DURING NORMAL LANDSCAPE MAINTENANCE OPERATIONS. BARE AREAS SHALL BE SEEDED.
- 5. STORMWATER QUALITY BASIN SLOPES SHALL BE MOWED ONCE A YEAR. MORE FREQUENT MOWING WILL ELIMINATE NATIVE FORBS SEDGES FROM THE MEADOW COVER.
- 6. LANDSCAPING: LANDSCAPED AREAS WILL BE MAINTAINED, NORMAL LANDSCAPING MAINTENANCE WILL CONSIST OF PRUNING. MULCHING, PLANTING MOWING LAWNS, RAKING LEAVES, ECT.. USE OF FERTILIZERS AND PESTICIDE WILL BE CONTROLLED AND LIMITED TO MINIMAL AMOUNTS NECESSARY FOR HEALTHY LANDSCAPE MAINTENANCE. THE LAWN AREAS, ONCE ESTABLISHED, WILL BE MAINTAINED AT A TYPICAL HEIGHT OF 3 1/2". THIS WILL ALLOW THE THE GRASS TO BE MAINTAINED WITH A MINIMAL IMPACT FROM WEEDS AND/OR PEST. THE REAR (EASTERLY) SLOPE AREAS WILL BE MAINTAINED AS A MEADOW OR ALLOWED TO REVERT BACK TO WOODLANDS. PESTICIDE WILL ONLY BE USED AS A CONTROL METHOD WHEN A PROBLEM HAS BEEN IDENTIFIED AND OTHER NATURAL CONTROL METHODS ARE NOT SUCCESSFUL. ALL PESTICIDE APPLICATION SHALL BE BY LICENSED APPLICATORS, WHERE NECESSARY. TOPSOIL, BRUSH, LEAVES, CHIPPINGS, MULCH, EQUIPMENT, AND OTHER MATERIALS SHALL BE STORED OFF SITE.
- 7. MAINTAIN EXISTING NATIVE VEGETATION: EXISTING VEGETATION ALONG THE EASTERLY EDGE OF THE DEVELOPMENT, ADJACENT TO THE WETLANDS SHALL REMAIN IN ITS NATIVE CONDITIONS NO CLEARING, GRADING, STOCKPILING, STORAGE, OR DEVELOPMENT WILL OCCUR IN THESE AREAS WITHOUT PRIOR APPROVAL FROM THE APPROPRIATE AGENCIES.
- 8. TRASH COLLECTION: ALL TRASH WILL BE CONTAINED IN DUMPSTERS. ALL DUMPSTERS WILL BE EQUIPPED WITH COVERS. ALL TRASH WILL BE COLLECTED ON A REGULAR BASIS AND DISPOSED OF LEGALLY OFF-SITE.
- 9. OUTDOOR STORAGE: THERE WILL BE NO OUTDOOR OF HAZARDOUS CHEMICALS, FERTILIZER, PESTICIDES, OR HERBICIDE'S ANYWHERE AT THE FACILITY.
- 10. THE OWNER SHALL BE KEEP AN ON-SITE LOG OF STORMWATER MAINTENANCE MEASURES PERFORMED AND DATES THEY WERE IMPLEMENTED. THIS LOG BOOK SHALL BE AVAILABLE FOR THE TOWN OF ELLINGTON INSPECTION. CHECKLIST ENTITLED "STORMWATER PONDS AND WETLANDS" IN APPENDIX E OF THE 2004 STORMWATER QUALITY MANUAL SHALL BE USED TO LOG THE INSPECTION. CHECKLIST CAN BE FOUND ON SHEET #13 OF THE PLAN SET.

#### State of Connecticut Department of Transportation - 817 CONSTRUCTION NOTES

#### 817 CONSTRUCTION NOTES

Removal of pavement markings along state roadways shall be completed by a non-destructive method in compliance with the State of Connecticut Department of Transportation Standard Specifications for Road, Bridges, and Incidental Construction Form 817 Section 12.11 as


New pavement markings shall be painted with epoxy resin paint in compliance with the State of Connecticut Department of Transportation Standard Specifications for Roads, Bridges, and Incidental Construction Form 817 Section 12.10 as revised.

New sign material and sheeting shall be made of reflective material in compliance with State of Connecticut Department of Transportation Standard Specifications for Roads, Bridges, and Incidental Construction Form 817 Section 12.08 as revised. Type 1 Reflective Sheeting shall be used for signs with white background, Type 3 Reflective Sheeting shall be used for signs with colored background except for signs with red background that shall be Type 8 or 9 Reflective Sheeting.

All signs and pavement markings installed along the state road must conform to the "Manual on Uniform Traffic Control Devices," the latest State of Connecticut Catalog of Signs and standard as revised.

Any damage to the existing curb, sidewalk or any other highway appurtenances during the development of the permitted site will be replaced by the contractor as directed by the District 3 Permit Section at no cost to the state.

All work within the state right of way will comply with the State of Connecticut Department of Transportation Standard Specifications for Roads Bridges and Incidental Construction Form 817 with the latest Special Provisions and Typical State Standard Details



# **EROSION CONTROL NOTES**

<u>SEDIMENT & EROSION CONTROL NARRATIVE</u> THE SEDIMENT AND EROSION CONTROL PLAN WAS DEVELOPED TO PROTECT THE EXISTING ROADWAY AND STORM DRAINAGE SYSTEMS, ADJACENT PROPERTIES, AND THE WETLAND AREA FROM SURFACE RUNOFF AND EROSION. A CONSTRUCTION SEQUENCE IS PROVIDED TO PROVIDE SURFACE RUNOFF CONTROLS PRIOR TO THE PROJECT CONSTRUCTION BEGINNING. CONSTRUCTION SCHEDULE

THE ANTICIPATED STARTING DATE FOR CONSTRUCTION IS WINTER 2024 WITH COMPLETION ANTICIPATED FALL 2025. APPROPRIATE EROSION CONTROL MEASURES AS DESCRIBED HEREIN, SHALL BE INSTALLED BY THE CONTRACTOR PRIOR TO THE COMMENCEMENT OF ALL CONSTRUCTION ACTIVITY.

CONTINGENCY EROSION PLAN THE CONTRACTOR SHALL INSTALL ALL SPECIFIED EROSION CONTROL MEASURES AND WILL BE REQUIRED TO MAINTAIN THEM IN THEIR INTENDED FUNCTIONING CONDITION. THE AGENTS OF THE DIRECTOR OF PLANNING & DEVELOPMENT, INLAND WETLANDS AGENCY AND/OR SITE ENGINEER SHALL HAVE THE AUTHORITY TO REQUIRE SUPPLEMENTAL MAINTENANCE OR ADDITIONAL MEASURES IF FIELD CONDITIONS ARE ENCOUNTERED BEYOND WHAT WOULD NORMALLY BE ANTICIPATED.

CONSTRUCTION SEQUENCE THE FOLLOWING CONSTRUCTION SEQUENCE IS RECOMMENDED:

- 1. CONTACT TOWN OF ELLINGTON AGENT AT LEAST FORTY-EIGHT (48) HOURS PRIOR TO COMMENCEMENT OF ANY DEMOLITION, CONSTRUCTION OR REGULATED ACTIVITY ON the PROJECT. A PRE-CONSTRUCTION MEETING WITH LOCAL AND/OR STATE OFFICIALS NEEDS TO BE HELD PRIOR TO THE START OF CONSTRUCTION
- 2. CLEARING LIMITS SHALL BE PHYSICALLY MARKED IN THE FIELD AND APPROVED BY THE TOWN OF ELLINGTON AGENT PRIOR TO THE START OF WORK ON THE SITE. INSTALL TREE PROTECTION AND PERIMETER SILT FENCE & HAY BALE SEDIMENT BARRIERS.
- 3. CONSTRUCT TRACKING PADS AT ENTRANCES AND WRAP FILTER FABRIC AROUND GRATE OF CATCH BASINS OR INSTALL SILT SACKS ON CATCH BASIN INLETS ON OFF SITE ROADS. INSTALL SILT FENCE AT PERIMETER OF PROPOSED SITE DISTURBANCE AND INSTALL ALL EROSION CONTROL MEASURES AND TREE PROTECTION INDICATED ON THESE PLANS. INSTALL SEDIMENT TRAPS AND INSTALL SEDIMENT BASINS IN REQUIRED AT LOW AREAS OF SITE OR AS ORDERED BY THE ENGINEER OR AS SHOWN ON THESE PLANS.
- 4. CLEAR AND GRUB SITE. STOCK PILE CHIPS. STRIP AND STOCKPILE TOPSOIL.
- 5. INSTALL ADDITIONAL SILT FENCE AS REQUIRED, CONSTRUCT TEMPORARY DIVERSION BERMS AND AND SEDIMENT TRAPS.
- 6. CONTINUE EARTHWORK. CONSTRUCT FILL SLOPE. INSTALL ADDITIONAL EROSION CONTROL AS REQUIRED. TOPSOIL AND SEED SLOPES WHICH HAVE ACHIEVED FINAL SITE GRADING.
- 7. CONSTRUCTION STAKING OF ALL BUILDING CORNERS, UTILITIES, ACCESS DRIVES, AND PARKING AREAS.
- 8. ROUGH GRADING.
- 9. CONSTRUCT STORM WATER QUALITY BASIN AND FINAL OUTLET.
- 10. INSTALLATION OF STORM DRAINAGE.
- 11. FOUNDATION CONSTRUCTION. BEGIN SUPERSTRUCTURE.
- 12. REMOVE SEDIMENT FROM BEHIND SILT FENCES, AND FROM SEDIMENTATION BASINS AS REQUIRED. REMOVAL SHALL BE ON A PERIODIC BASIS (EVERY SIGNIFICANT RAINFALL). INSPECTION OF EROSION CONTROL MEASURES SHALL BE ON A WEEKLY BASIS. SEDIMENT COLLECTED SHALL BE DEPOSITED AND SPREAD EVENLY UPLAND ON SLOPES DURING CONSTRUCTION.
- 13. INSTALL SEPTIC, WELL AND ALL OTHER UTILITIES. COMPLETE STORM SEWERS.
- 14. INSTALL SITE LIGHTING, LOADING AREA AND TRASH ENCLOSURE.
- 15. FINISH GRADING AND CONSTRUCT PARKING AREA SUBGRADE
- 16. CONSTRUCT SIDEWALKS.
- 17. PAVING OF PARKING AREAS AND DRIVEWAYS
- 18. FINAL GRADING OF SLOPE AREAS.
- 19. PLACE 4" TOPSOIL ON SLOPES AFTER FINAL GRADING IS COMPLETED. FERTILIZE SEED AND MULCH. SEED MIXTURE TO BE INSTALLED APRIL 11 TO JUNE 1 OR AUGUST 15 TO OCTOBER 1 USE EROSION CONTROL BLANKETS AS REQUIRED OR ORDERED FOR SLOPES GREATER THAN 3:1. FOR TEMPORARY STABILIZATION BEYOND SEEDING DATES USE ANNUAL RYE AT 4.0 LBS/1,000 S.F. FERTILIZE WITH 10-10-10 AT 1.0 LBS. OF NITROGEN PER 1,000 S.F. AND LIME AT 100 LBS/1,000 S.F. (MAX.).
- 20. LANDSCAPE ISLANDS AND PERIMETER AREAS. INSTALL SIGNING AND PAVEMENT MARKINGS.
- 21. UPON DIRECTION OF THE TOWN OF ELLINGTON AGENT, EROSION AND SEDIMENT CONTROL MEASURES SHALL BE REMOVED FOLLOWING STABILIZATION OF THE SITE.

#### SECHENCE OF OPERATIONS OPERATION I - CLEARING AND GRUBBING

- 1. ALL SEDIMENTATION AND EROSION CONTROL MEASURES, INCLUDING THE CONSTRUCTION OF THE TEMPORARY SEDIMENT TRAPS AND ANTI-TRACKING PADS, WILL BE INSTALLED PRIOR TO THE START OF CLEARING AND GRUBBING AND DEMOLITION OPERATIONS.
- 2. FOLLOWING INSTALLATION OF ALL SEDIMENTATION AND EROSION CONTROL MEASURES, THE CONTRACTOR SHALL NOT PROCEED WITH OPERATION II UNTIL THE ENGINEER HAS INSPECTED AND APPROVED ALL INSTALLATIONS.
- 3. THE CONTRACTOR SHALL TAKE EXTREME CARE DURING OPERATION I. SO AS NOT TO DISTURB UNPROTECTED WETLAND AREAS OR SEDIMENTATION AND EROSION CONTROL STRUCTURES.

OPERATION II - ROUGH GRADING

1. DURING THE REMOVAL AND/OR PLACEMENT OF EARTH AS INDICATED ON THE SITE PLAN, TOPSOIL SHALL BE STRIPPED AND APPROPRIATELY STOCKPILED FOR REUSE.

2. ALL STOCKPILED TOPSOIL SHALL BE SEEDED, MULCHED WITH HAY, AND ENCLOSED BY A SILTATION FENCE.

OPERATION III - FILLING

- 1. PRIOR TO FILLING, ALL SEDIMENTATION AND EROSION CONTROL STRUCTURES SHALL BE PROPERLY IMPLEMENTED, MAINTAINED AND FULLY INSTALLED, AS DIRECTED BY THE ENGINEER AND AS SHOWN ON the PLAN.
- 2. ALL FILL MATERIAL ADJACENT TO ANY WETLAND AREAS SHALL BE GOOD QUALITY, WITH LESS THAN 5% FINES PASSING THROUGH A #200 SIEVE (BANK RUN), SHALL BE PLACED IN MAXIMUM ONE FOOT LIFTS, AND SHALL BE COMPACTED TO 95% MAX. DRY DENSITY MODIFIED PROCTOR OR AS SPECIFIED IN CONTRACT SPECIFICATIONS.
- 3. AS GENERAL GRADING OPERATIONS PROGRESS, THE TEMPORARY DIVERSION DITCHES SHALL BE RAISED OR LOWERED, AS NECESSARY, TO DIVERT SURFACE RUNOFF TO THE BASINS.
- OPERATION IV PLACEMENT OF DRAINAGE STRUCTURES, UTILITIES, AND BUILDING CONSTRUCTION.
- 1. STAKED SILT FENCES SHALL BE INSTALLED AT THE DOWNHILL SIDES OF BUILDING EXCAVATIONS, DEWATERING PUMP DISCHARGES, AND UTILITY TRENCH MATERIAL STOCKPILES.

OPERATION V - FINAL GRADING AND PAVING

- 1. ALL INLET AND OUTLET PROTECTION SHALL BE PLACED AND MAINTAINED AS DISCUSSED IN OPERATION IV.
- 2. NO CUT OR FILL SLOPES SHALL EXCEED 2:1 EXCEPT WHERE STABILIZED BY ROCK FACED EMBANKMENTS OR EROSION CONTROL BLANKETS, JUTE MESH AND VEGETATION. ALL SLOPES SHALL BE SEEDED, AND THE ROAD SHOULDER AND BANKS WILL BE STABILIZED IMMEDIATELY UPON COMPLETION OF FINAL GRADING UNTIL TURF IS ESTABLISHED.
- 3. PAVEMENT BASE COURSES SHALL BE INSTALLED OVER AREAS TO BE PAVED AS SOON AS FINAL SUB-GRADES ARE ESTABLISHED AND UNDERGROUND UTILITIES HAVE BEEN INSTALLED.
- 4. CONSTRUCT PAVEMENT, PLACE TOPSOIL, FINAL SEED, MULCH AND LANDSCAPING.
- 5. REMOVE ALL TEMPORARY EROSION CONTROL DEVICES ONLY AFTER ALL AREAS HAVE BEEN PAVED AND/OR GRASS HAS BEEN WELL ESTABLISHED AND THE SITE HAS BEEN INSPECTED AND APPROVED BY THE TOWN OR GOVERNING WETLAND AGENCY.

#### SEQUENCE FOR INSTALLATION OF SOIL EROSION & SEDIMENTATION CONTROL MEASURES

- 1. ERECT SILTATION FENCES, SEDIMENT TRAPS, DIVERSION DITCHES, AND ANTI-TRACKING PAD.
- 2. STRIP TOPSOIL AND STOCKPILE.
- 3. PERFORM CLEARING AND GRUBBING ACTIVITIES, AND DEMOLITION.
- 4. STABILIZE STOCK PILE.
- 5. INSPECT AND MAINTAIN SEDIMENTATION AND EROSION CONTROL STRUCTURES. 6. ROUGH GRADING.
- 7. INSPECT AND MAINTAIN SEDIMENTATION AND EROSION CONTROL STRUCTURES.
- 8. PERFORM FILLING ACTIVITIES.
- 9. INSPECT AND MAINTAIN SEDIMENTATION AND EROSION CONTROL STRUCTURES.
- 10. CONSTRUCT DRAINAGE STRUCTURES. CONSTRUCT DIVERSION BERMS, RIP RAPPED LINED DITCHES AND SEDIMENTATION BASINS.
- 11. INSPECT AND MAINTAIN SEDIMENTATION AND EROSION CONTROL STRUCTURES.
- 12. PERFORM FINAL GRADING AND PAVING.
- 13. INSPECT AND MAINTAIN SEDIMENTATION AND EROSION CONTROL STRUCTURES.
- 14. RESPREAD TOPSOIL.
- 15. LIME, FERTILIZE, AND SEED.
- 16. MULCH.
- 17. FINAL COVER.
- 18. MAINTAIN SILTATION FENCES UNTIL COVER IS COMPLETELY STABILIZED.
- 19. PERFORM FINAL INSPECTION.
- 20. REMOVE SILTATION FENCES, CLEAN, AND RESTORE ALL AREAS.

#### INSTALLATION OF SEDIMENTATION AND EROSION CONTROL MEASURES

- I. SILTATION FENCE A. DIG A SIX INCH TRENCH ON THE UPHILL SIDE OF THE DESIGNATED FENCE LINE LOCATION.
- B. POSITION THE POST AT THE BACK OF THE TRENCH (DOWNHILL SIDE), AND HAMMER THE
- C. LAY THE BOTTOM SIX INCHES OF THE FABRIC IN THE TRENCH TO PREVENT UNDERMINING BY STORM WATER RUN-OFF.
- D. BACKFILL THE TRENCH AND COMPACT.


POST AT LEAST 1.5 FEET INTO THE GROUND.


- OPERATION AND MAINTENANCE OF SEDIMENTATION AND EROSION CONTROL MEASURES I. SILTATION FENCE
- A. ALL SILTATION FENCES SHALL BE INSPECTED AS A MINIMUM WEEKLY OR AFTER EACH RAINFALL. ALL DETERIORATED FABRIC AND DAMAGED POSTS SHALL BE REPLACED AND PROPERLY REPOSITIONED IN ACCORDANCE WITH the PLAN.
- B. SEDIMENT DEPOSITS SHALL BE REMOVED FROM BEHIND THE FENCE WHEN THEY EXCEED A HEIGHT OF ONE FOOT.
- SEDIMENT TRAPS/BASINS A. CONTRACTOR TO KEEP WEEKLY CHECKLIST LOGS FOR INSPECTIONS OF ALL SEDIMENT AND EROSION CONTROL DEVICES AND HAVE THEM READILY AVAILABLE ON-SITE AT ALL TIMES FOR INSPECTION BY DEEP, LOCAL AUTHORITIES OR ENGINEER.
- B. ALL PONDS SHALL BE INSPECTED FOLLOWING EACH RAINFALL. REPAIR OF SLOPES SHALL BE PROMPTLY MADE AS NEEDED.
- C. SEDIMENT DEPOSITS SHALL BE REMOVED FROM PONDS WHEN THEY EXCEED A HEIGHT OF ONE FOOT.
- D. SEDIMENT SHALL BE DISPOSED OF ON-SITE OR AS DIRECTED BY THE ENGINEER AND LOCAL GOVERNING OFFICIALS. EROSION AND SEDIMENT CONTROL PLAN 1. SILTATION FENCE WILL BE INSTALLED AT ALL CULVERT OUTLETS AND ALONG THE TOE OF ALL CRITICAL CUT AND FILL
- SLOPES. 2. CATCH BASINS WILL BE PROTECTED WITH SILT SACKS OR HAY BALES THROUGHOUT THE CONSTRUCTION PERIOD AND
- UNTIL ALL DISTURBED AREAS ARE THOROUGHLY STABILIZED.
- 3. ALL EROSION AND SEDIMENT CONTROL MEASURES WILL BE INSTALLED IN ACCORDANCE WITH THE STANDARDS AND SPECIFICATIONS OF THE EROSION AND SEDIMENT CONTROL HANDBOOK, LATEST EDITION.
- 4. EROSION AND SEDIMENT CONTROL MEASURES WILL BE INSTALLED PRIOR TO CONSTRUCTION WHENEVER POSSIBLE.
- 5. ALL CONTROL MEASURES WILL BE MAINTAINED IN EFFECTIVE CONDITION THROUGHOUT THE CONSTRUCTION PERIOD.
- 6. ADDITIONAL CONTROL MEASURES WILL BE INSTALLED DURING THE CONSTRUCTION PERIOD, IF NECESSARY OR REQUIRED.
- 7. SEDIMENT REMOVED FROM CONTROL STRUCTURES WILL BE DISPOSED IN A MANNER WHICH IS CONSISTENT WITH THE INTENT OF THE PLAN.
- 8. CALITO DEVELOPMENT GROUP IS THE PERMITEE RESPONSIBLE FOR IMPLEMENTING the EROSION AND SEDIMENT CONTROL PLAN. the RESPONSIBILITY INCLUDES THE INSTALLATION AND MAINTENANCE OF CONTROL MEASURES, INFORMING ALL PARTIES ENGAGED ON THE CONSTRUCTION SITE OF THE REQUIREMENTS AND OBJECTIVES OF THE PLAN, NOTIFICATION OF THE ELLINGTON WETLANDS ENFORCEMENT OFFICER OR GOVERNING AUTHORITY OF THE TRANSFER OF the RESPONSIBILITY AND FOR CONVEYING A COPY OF THE EROSION AND SEDIMENT CONTROL PLAN IF THE TITLE TO THE LAND IS TRANSFERRED.


#### EROSION AND SEDIMENT CONTROL PLAN SED 1. THE DRAWING IS ONLY INTENDED TO DES SEDIMENT AND EROSION CONTROL DETAIL AND OTHER PLANS FOR APPROPRIATE II


- 2. CALITO DEVELOPMENT GROUP IS THE PI PLAN. the RESPONSIBILITY INCLUDES PARTIES ENGAGED WITH CONSTRUCTION GOVERNING AUTHORITY OR INLAND WETL COPY OF THE SEDIMENT & EROSION CO
- 3. THE CONTRACTOR SHALL CONSTRUCT A GUIDELINES FOR SOIL EROSION AND SE AND AS DIRECTED BY THE TOWN OF F REFERENCE DURING CONSTRUCTION.
- 4. ADDITIONAL AND/OR ALTERNATIVE SEDIM CONSTRUCTION PERIOD IF FOUND NECES GOVERNING AGENCY. THE CONTRACTOR IF ALTERNATIVE CONTROLS OTHER THAN
- 5. THE CONTRACTOR SHALL KEEP A SUPPL MAINTENANCE AND EMERGENCY REPAIRS
- 6. PROTECT EXISTING TREES THAT ARE TO ORANGE SAFETY FENCE, OR EQUIVALENT THAT AREA; FENCING SHALL BE MAINTA 7. INSTALL PERIMETER SEDIMENT CONTROLS
- WITHIN THE LIMIT OF DISTURBANCE, WHIC PRIOR TO CLEARING. CONSTRUCTION A SPECIFICALLY CALLED FOR ON THE DOW 8. ANTI-TRACKING PADS SHALL BE INSTAL
- CONSTRUCTION. THE LOCATION OF THE 9. TOPSOIL SHALL BE STRIPPED AND STOC SILT FENCE AROUND THE LIMIT OF PILE THAN 2 MONTHS.
- 10. SEDIMENTATION BASINS SHALL PROVIDE THE BASIN. PROVIDE BASIN VOLUMES
- 11. COMPLY WITH REQUIREMENTS OF CGS S AND WITH DEEP RECORD KEEPING AND
- 12. MINIMIZE LAND DISTURBANCES. SEED WEEK MAXIMUM UNSTABILIZED PERIOD AND SWALES WITH LOOSE HAY AT A EROSION CONTROL BLANKETS OR JUT STAGING AREAS MAY BE HYDROSEEDE
- 13. SILT FENCE AND OTHER SEDIMENT CON MANUFACTURER'S RECOMMENDATIONS
- 14. EXCAVATED MATERIAL FROM TEMPORAR 15. INSTALL SILT FENCE ACCORDING TO MA GROUND. SILT FENCE SHALL BE MIRAF
- FABRIC USED SHALL BE MIRAFI 100X O 16. INSTALL TEMPORARY DIVERSION DITCHE SHOWN AND AS NECESSARY DURING V STABILIZED. LOCATION OF TEMPORARY GOVERNING OFFICIAL.
- 17. DIRECT ALL DEWATERING PUMP DISCHAR OR GRASS FILTERS WITHIN THE APPRO SEDIMENT CONTROLS SHALL BE CLEAR.
- 18. BLOCK THE OPEN UPSTREAM ENDS OF BLOCK END OF STORM SEWERS IN EXP WHEN RAIN IS EXPECTED.
- 19. SWEEP AFFECTED PORTIONS OF OFF SIT A PROBLEM) DURING CONSTRUCTION. DOWN DISTURBED AREAS, USING CALCI
- 20. PERIODICALLY CHECK ACCUMULATED SE ACCUMULATED SILT WHEN NECESSARY FROM CATCH BASIN SUMPS AS NECES
- HALF THE HEIGHT OF THE FENCE. D 21. MAINTAIN ALL PERMANENT AND TEMPOR CONSTRUCTION PERIOD. UPON COMPL WHEN AUTHORIZED BY LOCAL GOVERN
- 22. THE PARTY RESPONSIBLE FOR THE EROS CALITO DEVELOPMENT GROUP ATTN: MATT EUCALITTO 59 FIELD STREET, TORRINGTON, CT 06790 PHONE: 860-280-5825
- 23. IF WIND EROSION OCCURS, THEN GROUNI AS REQUIRED TO CORRECT THE PROBLE


| EDMENT AND EROSION CONTROL NOTES<br>ESCREE, THE SEDMENT AND EROSION CONTROL TREATMENT FOR the SITE. SEE<br>ALLS AND CONSTRUCTION SEQUENCE. REFER TO SITE FLAN FOR GENERAL INFORMATION<br>INFORMATION.<br>THE PROPER INSTRUCTION SEQUENCE. REFER TO SITE FLAN FOR GENERAL INFORMATION<br>INFORMATION.<br>THE PROPER INSTRUCTION SEQUENCE. REFER TO SITE FLAN FOR GENERAL INFORMING THE<br>INFORMATION.<br>IN ON THE SITE OF THE REQURRENTIS AND OBJECTIVES OF the PLAN, INFORMING THE<br>ILLANDS AGENCY OF ANY TRANSFER OF the RESPONSIBILITY, AND FOR CONVING A<br>CONTROL PLAN F THE TITLE TO THE LAND IS TRANSFERED.<br>ALL SEDMENT AND EROSION CONTROL IN ACCORDANCE WITH THE CONNECTIONT<br>EDMENT CONTROL, LATEST EDITION IN ACCORDANCE WITH THE CONTRACT DOCUMENTS,<br>SUBJECT AND EROSION CONTROL IN ASCORDANCE WITH THE CONTRACT DOCUMENTS,<br>SUBJECT CONTROL, LATEST EDITION IN ACCORDANCE WITH THE CONTRACT DOCUMENTS,<br>SUBJECT AND EROSION CONTROL INFORMATIC GOVERNING AGENOLES FOR APPROVAL<br>INFORMATION THE PLANS ARE PROPOSED.<br>PLY OF EROSION CONTROL MARENINE, SITE ENGNEER, TOWN OFFICALS, OR ANY<br>PLY OF EROSION CONTROL MATERIAL (SILT FENCE, JUTE MESH, ETC.) ON-SITE FOR<br>RS.<br>ALL CONTACT THE OWNER AND APPROPRIME GOVERNING AGENOLES FOR APPROVAL<br>NUTHER AND REPARED DURING CONSTRUCTION, ALL CONSTRUCTION BEGINS IN<br>TARED AND REPARED DURING CONSTRUCTION, ALL CONSTRUCTION BEGINS IN<br>TARED AND REPARED DURING CONSTRUCTION, ALL CONSTRUCTION SHALL BE CONTAINED<br>HICH SHALL DO THE LEANDS CONSTRUCTION, ALL CONSTRUCTION SHALL BE CONTAINED<br>HICH SHALL BE LEWFORMARKER DISCHARGE FROM CONSTRUCTION BEGINS IN<br>TARED AND REPARED DURING CONSTRUCTION, ALL CONSTRUCTION SHALL BE CONTAINED<br>HICH SHALL BE LEWFORMARKER DISCHARGE FROM CONSTRUCTION SHALL HAVE<br>E. THES SHALL BE LEWFORMARKER DISCHARGE FROM CONSTRUCTION ARE COMPLETED.<br>DORPHILED FOR USE IN FINAL LANDSCAPING, ALL EARTH STOCKILES SHALL HAVE<br>E. THELES SHALL BE LEWFORMARKER DISCHARGE FROM CONSTRUCTION ARE COMPLETED.<br>DECENTING MODIFIES SHALL BE INSTALLED IN ACCORDANCE WITH SIDIATION AND ELESTICH<br>DI AND REFORMAL REFERRED.<br>SECTION 22, A 305 FO                                   | & CASSIDY       Scale: 1"=40°       CHECKED BY: JPC         & CASSIDY       Scale: 1"=40°       CHECKED BY: JPC         & CASSIDY       JOB No.: 3486       ACAD FILE: 3486-ES-N       TES         SURVEYORS       JOB No.: 3486       OC       ACAD FILE: 3486-ES-N       TES         #1A       OG       OF:       OF:       OF:       D       OF:       D         #1A       EEVISIONS:       EEVISIONS:       OF:       D       D       TES       D  |
|--|--|
| ESCREE THE SEDURENT AND EROSION CONTROL TREATMENT FOR the SITE. SEE<br>MILES AND CONSTRUCTION SEQUECE. REFER TO SITE PLAN. INFORMATION<br>INFORMATION.<br>PERINTER RESPONSIBLE FOR IMPLEMENTING the SEDIMENT AND EROSION CONTROL<br>THE PROPER INSTALLATION AND MAINTENANCE OF CONTROL MEASURES, INFORMING ALL<br>INFORMATION.<br>PERINTER CREATE OF THE REQUIRENTS AND OBLECTIVES OF the PLAN. INFORMING THE<br>DIAMOS AGENCY OF ANY TRANSFER OF the RESPONSIBILITY, AND FOR CONVEYING A<br>DIAMOS DATE OF THE REQUIRENTS AND OBLECTIVES OF the PLAN. INFORMING THE<br>DIAMOS AGENCY OF ANY TRANSFER OF the RESPONSIBILITY, AND FOR CONVEYING A<br>DIAMOS DATE OF THE REQUIRENTS AND CONTROL THE ADDIATION IN ACCORDANCE WITH THE CONTRACT DOLIMENTS,<br>LILINGTON. THE CONTRACTOR SHALL KEEP A COPY OF THE GUIDELINES ON-SITE FOR<br>DIMENT CATURAL PLANCE, LATEST EDITION IN ACCORDANCE WITH THE CONTRACT DOLIMENTS,<br>LILINGTON. THE CONTRACTOR, OWNERS, SITE ENGINEER, TOWN OFFICALS, OR ANY<br>DESIGNT CONTRACT, AND ENGINES MAY BE INSTALLED DURING THE<br>SESAR BY THE CONTRACTOR, OWNER, SITE ENGINEER, TOWN OFFICALS, OR ANY<br>AND THE CONTRACTOR, OWNERS, SITE ENGINEER, TOWN OFFICALS, OR ANY<br>AND THE PLANS ARE PROPOSED.<br>PLY OF EROSION CONTROL MATERIAL (SLIT FENCE, JUTE MESH, ETC.) ON-SITE FOR<br>RS.<br>O DE SAVED BY FENCING AT THE DRIP LINE OR AS SHOWN WITH SNOW FENCE,<br>INT FERCING. ANY LING THIMMING SHOULD BE DONE BEFORE CONSTRUCTION BEGINS IN<br>TAINED AND REPARED DURING CONSTRUCTION. ALL CONSTRUCTION SHALL BE CONTAINED<br>AND REPARED DURING CONSTRUCTION. ALL CONSTRUCTION SHALL BE CONTAINED<br>THIND MAD REPARED DURING CONSTRUCTION. ALL CONSTRUCTION SHALL BE CONTAINED<br>AND REPARED DURING CONSTRUCTION. ALL CONSTRUCTION SHALL BE CONTAINED<br>THIND MEADURED TO CLEARING ARE CONSTRUCTION AND MAINTAINED THROUGHOUT THE DURATION OF<br>THE TRACKING PADS MAY CHANGE AS VARIOUS PHASES OF CONSTRUCTION ARE COMPLETED.<br>DOKPLETOR USE IN FINAL LANDSCAPING. ALL EARTH STOCHLES SHALL HAVE<br>LE THLES SHALL BE TEMPORARIUS AREADS AND THE STORAGE FOR MORE<br>DE 134 CUBIC YARDS OF SEDIMENT STORAGE PER DISTURBED ACRE CONTRIBUTING TO<br>S FOR ALL DISTURBED A            | & CASE: 1"=40'       CHECKED BY: JPC         & CASSIDY       DATE: NOV. 20, 2024       DRAWN BY: JMP         BATE: NOV. 20, 2024       DRAWN BY: JMP         SURVEYORS       JOB No.: 3486       ACAD FILE: 3486         #1A       SHEET:       SHEET:       OF:       JB         66416       OF:       JAN.       Z3, 2025       PER TOWN COMMENT         60)-721-7709       JAN.       Z3, 2025       PER TOWN COMMENT   |
| THE ERESPONSIBLE FOR IMPLEMENTING the SEDIMENT AND EROSION CONTROL<br>THE PROPER INSTALLATION AND MAINTENANCE OF CONTROL MEASURES, INFORMING ALL<br>YOT THE STE OF THE REQUIREMENTS AND OBJECTIVES OF the PLAN, INFORMING THE<br>TLANDS ACENCY OF ANY TRANSFER OF the RESPONSIBILITY, AND FOR CONVENIG A<br>ONTROL PLAN THE THE TITLE TO THE LAND IS TRANSFERED.<br>ALL SEDIMENT AND EROSION CONTROLS IN ACCORDANCE WITH THE CONTRACT DOCUMENTS,<br>LIUNGTON. THE CONTRACTOR SHALL KEEP A COPY OF THE GUIDELINES ON–SITE FOR<br>MINENT AND EROSION CONTROL MEASURES MAY BE INSTALLED DURING THE<br>SSSARY BY THE CONTRACTOR, OWNER, SITE ENGINEER, TOWN OFFICIALS, OR ANY<br>RESALL CONTRACT THE CUMER AND APPROVANCE WITH THE CONTRACT DOCUMENTS,<br>LIUNGTON. THE CONTRACTOR, OWNER, SITE ENGINEER, TOWN OFFICIALS, OR ANY<br>RE SHALL CONTRACT THE CUMER AND APPROVANT EQUVERNING AGENCIES FOR APPROVAL<br>IN THOSE SHOWN ON THE PLANS ARE PROPOSED.<br>PLY OF EROSION CONTROL MATERIAL (SILT FENCE, JUTE MESH, ETC.) ON–SITE FOR<br>SS.<br>O DE SAVED BY FENCING AT THE DRIP LINE OR AS SHOWN WITH SNOW FENCE,<br>IT FENCING. ANY LIMB TRIMMING SHOULD BE DONE BEFORE CONSTRUCTION BEGINS IN<br>ANNO ECONSTRUCTION. ALL CONSTRUCTION. ALL CONSTRUCTION SHALL BE CONTAINED<br>INFORMED CONSTRUCTION. ALL CONSTRUCTION SHALL BE CONTAINED<br>INFORMED ADD MAY CHANGE AS VARIOUS PHASES OF CONSTRUCTION ARE COMPLETED.<br>XOPPLED FOR USE IN FINAL LANDSCAPING. ALL EARTH STOCKPLES SHALL HAVE<br>LE TRACKING PADS MAY CHANGE AS VARIOUS PHASES OF CONSTRUCTION ARE COMPLETED.<br>XOPPLED FOR USE IN FINAL LANDSCAPING. ALL EARTH STOCKPLES SHALL HAVE<br>LE TRACKING PADS MAY CHANGE AS VARIOUS PHASES OF CONSTRUCTION ARE COMPLETED.<br>XOPPLED FOR USE IN FINAL LANDSCAPING. ALL EARTH STOCKPLES SHALL HAVE<br>LE TRACKING PADS MAY CHANGE AS VARIOUS PHASES OF CONSTRUCTION ARE COMPLETED.<br>XOPPLED FOR USE IN FINAL LANDSCAPING. ALL EARTH STOCKPLES SHALL HAVE<br>LE TRACKING PADS MAY CHANGE AS VARIOUS PHASES OF CONSTRUCTION ARE COMPLETED.<br>XOPPLED FOR USE IN FINAL LANDSCAPING. ALL EARTH STOCKPLES SHALL HAVE<br>LE TRACKING PADS MAY CHANGE AS VARIOUS PHASES OF CONS   | & CASSIDY       SCALE: 1"=40'         & CASSIDY       DATE: NOV. 20, 202         SURVEYORS       JOB No.: 3486         #1A       SHEET:         #1A       SHEET:         60)-721-7709       DEC: 17, 2024 PER JAN. 23, 2025 PER JAN. 24, 2025 PER JAN. 24, 2025 PER JAN. 24, 25, 2025 PER JAN. 24, 24, 24, 24, 24, 24, 24, 24, 24, 24, |
| ALL SEDIMENT AND EROSION CONTROLS IN ACCORDANCE WITH THE CONNECTION<br>DIMENT CONTROL, LAIEST EDITION IN ACCORDANCE WITH THE CONTRACT DOCUMENTS,<br>LINGTON. THE CONTRACTOR SHALL KEEP A COPY OF THE GUIDELINES ON—SITE FOR<br>SARY BY THE CONTRACTOR, OWNER, SITE ENGINEER, TOWN OFFICALS, OR ANY<br>R SHALL CONTOCT THE DIMERSHING APPROPOSED.<br>PLY OF EROSION CONTROL MEASURES FOR PROPOSED.<br>PLY OF EROSION CONTROL MATERIAL (SILT FENCE, JUTE MESH, ETC.) ON—SITE FOR<br>SS.<br>D EE SAVED BY FENCING AT THE DRIP LINE OR AS SHOWN WITH SNOW FENCE.<br>IT FENCING. ANY LIMB TRIMMING SHOULD BE ODNE BEFORE CONSTRUCTION BEGINS IN<br>ANNEED AND REPARED DURING CONSTRUCTION.<br>LS PRIOR TO CLEARING OR CONSTRUCTION. ALL CONSTRUCTION SHALL BE CONTAINED<br>INFED MAN REPARED DURING CONSTRUCTION.<br>LS PRIOR TO CLEARING OR CONSTRUCTION.<br>ALLE DAT START OF CONSTRUCTION.<br>LIED AT START OF CONSTRUCTION.<br>LIED AT START OF CONSTRUCTION.<br>LIED AT START OF CONSTRUCTION. ALL CONSTRUCTION SHALL BE CONTAINED<br>ION SHALL BE MARKED WITH SILT FENCE. SAFETY FENCE, RIBBONS, OR OTHER MEANS<br>GUITTY SHALL BE MARKED WITH SILT FENCE. SAFETY FENCE, RIBBONS, OR OTHER MEANS<br>CRITTY SHALL BE LAWNOR ON THE UPHILL SIDE OF THE SILT FENCE UNLESS WORK. IS<br>WHILL SIDE OF THE FENCE.<br>LIED AT START OF CONSTRUCTION AND MAINTAINED THROUGHOUT THE DURATION OF<br>E TRACKING PADS MAY CHANGE AS VARIOUS PHASES OF CONSTRUCTION ARE COMPLETED.<br>CKPILED FOR USE INFINAL LANDSCAPING. ALL EARTH STOCKPILES SHALL HAVE<br>E. PILES SHALL BE TEMPORARILY SEEDED IF PILE IS TO REMAIN IN PILACE FOR MORE<br>IN SPECTION REQUIREMENTS.<br>D AND MULCH DISTURBED AREAS WITH TEMPORARY MIX AS SOON AS PRACTICABLE (2<br>)) USING PERTINIAL REFERSAS AT 40 LBS PER CONSTRUCTION ACTIVITIES<br>D INSPECTION REQUIREMENTS.<br>D AND MULCH DISTURBED AREAS WITH TEMPORARY MIX AS SOON AS PRACTICABLE (2<br>)) USING PERTINIAL REFERSAS AT 40 LBS PER CONSTRUCTION ACTIVITIES<br>D INSPECTION REQUIREMENTS.<br>D AND MULCH DISTURBED AREAS WITH TEMPORARY MIX AS SOON AS PRACTICABLE (2<br>)) USING PERTINIAL REFERSA WITH TEMPORARY MIX AS SOON AS PRACTICABLE (2<br>)) USING PERTINIAL REFERSAS AT 40 LBS PER CARE | & CASSIDY       SCALE: 1"=40'         & CASSIDY       DATE: NOV. 20, 202         SURVEYORS       JOB No.: 3486         #1A       SHEET:         #1A       SHEET:         60)-721-7709       DEC: 17, 2024 PER JAN. 23, 2025 PER JAN. 24, 2025 PER JAN. 24, 2025 PER JAN. 24, 25, 2025 PER JAN. 24, 24, 24, 24, 24, 24, 24, 24, 24, 24, |
| SSARY BY THE CONTRACTOR, OWNER, SITE ENGINEER, TOWN OFFICIALS, OR ANY<br>R SHALL CONTACT THE OWNER AND APPROPRIATE GOVERNING AGENCIES FOR APPROVAL<br>IN THOSE SHOWN ON THE PLANS ARE PROPOSED.<br>PLY OF EROSION CONTROL MATERIAL (SILT FENCE, JUTE MESH, ETC.) ON-SITE FOR<br>S.<br>D BE SAVED BY FENCING AT THE DRIP LINE OR AS SHOWN WITH SNOW FENCE.<br>T FENCING, ANY LIMB TRIMMING SHOULD BE DONE BEFORE CONSTRUCTION BEGINS IN<br>ANED AND REPAIRED DURING CONSTRUCTION. ALL CONSTRUCTION SHALL BE CONTAINED<br>ICH SHALL DE MARKED WITH SILT FENCE, SAFETY FENCE, RIBBONS, OR OTHER MEANS<br>ICH SHALL BE MARKED WITH SILT FENCE, SAFETY FENCE, RIBBONS, OR OTHER MEANS<br>ICH SHALL BE MARKED WITH SILT FENCE. SAFETY FENCE, RIBBONS, OR OTHER MEANS<br>ICH SHALL BE MARKED WITH SILT FENCE. SAFETY FENCE, RIBBONS, OR OTHER MEANS<br>ICH SHALL BE MARKED WITH SILT FENCE.<br>ILED AT START OF CONSTRUCTION. ANL MAINTAINED THROUGHOUT THE DURATION OF<br>E TRACKING PADS MAY CHANGE AS VARIOUS PHASES OF CONSTRUCTION ARE COMPLETED.<br>ICKPILED FOR USE IN FINAL LANDSCAPING. ALL EARTH STOCKPILES SHALL HAVE<br>E. PILES SHALL BE TEMPORARILY SEEDED IF PILE IS TO REMAIN IN PLACE FOR MORE<br>E 134 CUBIC YARDS OF SEDIMENT STORAGE PER DISTURBED ACRE CONTRIBUTING TO<br>10 INSPECTION ZEQ. INFORMATER DISCHARGE FROM CONSTRUCTION ACTIVITIES<br>D INSPECTION PER ACRE. IF NECESSARY, REPLACE LOOSE HAVY ON SUPCES WITH<br>E. DINSPECTION REQUIREMENTS.<br>D AND MULCH DISTURBED AREAS WITH TEMPORARY MIX AS SOON AS PRACTICABLE (2<br>D) USING PERENNIAL RYEGRASS AT 40 LBS PER ACRE. MULCH ALL CUT AND FILL SLOPES<br>RATE OF 2 TONS PER ACRE. IF NECESSARY, REPLACE LOOSE HAVY ON SUPCES WITH<br>THE CLOTH. MODERATELY GRADED AREAS, ISLANDS, AND TEMPORARY CONSTRUCTION<br>ED WITH TACKIFIER.<br>NTROL MEASURES SHALL BE INSTALLED IN ACCORDANCE WITH DRAWINGS AND<br>PRIOR TO WORK IN ANY UPLAND AREAS.<br>RY SEDIMENT TRAPS MUST BE STOCKPILED ON UPHILL SIDE OF SILT FENCE.<br>ANUFACTURER'S INSTRUCTION, PARTICULARLY, BURY LOWER EDGE OF FABRIC INTO<br>FLEWINGPERS, MOUST BLASTRUCTION TO CONTROL WITH DRAWINGS AND<br>PRIOR TO WORK IN ANY UPLAND AREAS.<br>RY SEDIM                                     | <b>&amp; CASSIDY</b><br>SCALE: 1 <sup>*</sup><br>DATE: NOV<br>JOB No.::<br>JOB No.::<br>JOB No.::<br>JARET:<br>#1A<br>06416<br>06416<br>06416<br>06416<br>06416<br>06416<br>06416<br>06416<br>06416<br>06416<br>06416<br>06416   |
| S.<br>D BE SAVED BY FENCING AT THE DRIP LINE OR AS SHOWN WITH SNOW FENCE,<br>T FENCING. ANY LIMB TIMMING SHOULD BE DONE BEFORE CONSTRUCTION BEGINS IN<br>AINED AND REPAIRED DURING CONSTRUCTION. ALL CONSTRUCTION SHALL BE CONTAINED<br>CH SHALL BE MARKED WITH SILT FENCE, SAFETY FENCE, RIBBONS, OR OTHER MEANS<br>CITIVTY SHALL REMAIN ON THE UPHILL SIDE OF THE SILT FENCE UNLESS WORK IS<br>WHILL SIDE OF THE FENCE.<br>LLED AT START OF CONSTRUCTION AND MAINTAINED THROUGHOUT THE DURATION OF<br>E TRACKING PADS MAY CHANCE AS VARIOUS PHASES OF CONSTRUCTION ARE COMPLETED.<br>CKPILED FOR USE IN FINAL LANDSCAPING. ALL EARTH STOCKPILES SHALL HAVE<br>E. PILES SHALL BE TEMPORARILY SEEDED IF PILE IS TO REMAIN IN PLACE FOR MORE<br>E 134 CUBIC YARDS OF SEDIMENT STORAGE PER DISTURBED ACRE CONTRIBUTING TO<br>FOR ALL DISTURBANCE ON SITE.<br>SECTION 22A, 430B FOR STORMWATER DISCHARGE FROM CONSTRUCTION ACTIVITIES<br>) INSPECTION REQUIREMENTS.<br>D AND MULCH DISTURBED AREAS WITH TEMPORARY MIX AS SOON AS PRACTICABLE (2<br>) USING PEREINIAL RYCERASS AT 40 LBS PER ACRE. MULCH ALL CUT AND FILL SLOPES<br>RATE OF 2 TONS PER ACRE. IF NECESSARY, REPLACE LOOSE HAY ON SLOPES WITH<br>TE CLOTH. MODERATELY GRADED AREAS, ISLANDS, AND TEMPORARY CONSTRUCTION<br>ED WITH TACKIFIER.<br>RY SEDIMENT TRAPS MUST BE STOCKPILED ON UPHILL SIDE OF SILT FENCE.<br>ANUFACTURER'S INSTRUCTION, PARTICULARLY, BURY LOWER EDGE OF FABRIC INTO<br>FIRENWORCE SHALL BE INSTALLED IN ACCORDANCE WITH DRAWINGS AND<br>PRIOR TO WORK IN ANY UPLAND AREAS.<br>RY SEDIMENT TRAPS MUST BE STOCKPILED ON UPHILL SIDE OF SILT FENCE.<br>ANUFACTURER'S INSTRUCTION, PARTICULARLY, BURY LOWER EDGE OF FABRIC INTO<br>FI ENVIROPENCE, AMOCO SILT STOP OR EQUIVALENT TRAPS AND DEWAFERING PITS AS<br>AREOUS PALSES OF CONSTRUCTION, PARTICULARLY, BURY LOWER EDGE OF FABRIC INTO<br>FI ENVIROPENCE, AMOCO SILT STOP ON EQUIVALENT APPROVED BY SITE ENGINEER. FILTER<br>SR, PLUNKE POOLS, SEDIMENT BASINS, SEDIMENT TRAPS AND DEWATERING PITS AS<br>AREOUS PALSES OF CONSTRUCTION TO CONTROL RUNDOF UNTIL UPHILL AREAS ARE   | & CASSI<br>SURVEYORS<br>#1A<br>60)-721-7709  |
| Y SEDIMENT BASINS WILL REQUIRE REVIEW AND APPROVAL BY THE ENGINEER AND<br>ARGE TO A SEDIMENT CONTROL DEVICE SUCH AS TEMPORARY PITS, SEDIMENT BASINS<br>OVED LIMIT OF DISTURBANCE. DISCHARGE TO STORM SEWERS OR SURFACE WATERS FROM<br>R.<br>DETENTION PIPE SYSTEM OUTLET CONTROL ORIFICE UNTIL SITE IS STABILIZED AND<br>POSED TRENCHES WITH BOARDS AND SANDBAGS AT THE END OF EACH WORKING DAY<br>ITE ROADS ONE OR MORE TIMES A DAY (OR LESS FREQUENTLY IF TRACKING IS NOT<br>OTHER DUST CONTROL MEASURES TO BE USED AS NECESSARY INCLUDES WATERING<br>IUM CHLORIDE, AND COVERING LOADS ON DUMP TRUCKS.<br>SEDIMENT LEVELS IN THE SEDIMENT TRAPS DURING CONSTRUCTION AND CLEAN<br>' OR WHEN ONE FOOT OF SEDIMENT TRAPS DURING CONSTRUCTION AND CLEAN<br>SSARY. REMOVE ACCUMULATED SEDIMENT FROM BEHIND SILT FENCE WHEN LEVEL REACHES<br>ISPOSE OF SEDIMENT LEGALLY EITHER ON SITE IN NON-WETLANDS AREAS   | HALLISEY, PEARSON<br>CIVIL ENGINEERS & LAND<br>630 MAIN STREET, UNIT<br>CROMMELL, CONNECTICUT 0<br>PHONE: (860)-529-6812, FAX: (86   |
| JRARY SEDMENT CONTROL DEVICES IN EFFECTIVE CONDITION THROUGHOUT THE<br>ETON OF WORK SWEEP PARKING LOT AND REMOVE ALL TEMPORARY SEDMENT CONTROLS<br>ING AUTHORITY.<br>JSION AND SEDMENT CONTROL MEASURES IS:<br>ND SHALL BE COVERED WITH CALCIUM CHLORIDE OR WATER TRACK APPLICATIONS<br>EM.  | EROSION & SEDIMENT CONTROL NOTES<br>PREPARED FOR<br>CALITO DEVELOPMENT GROUP<br>PROPERTY LOCATED AT<br>WEST ROAD (RT. #83)<br>ELLINGTON, CONNECTICUT   |
|  |  |































| <b>BOTANICAL NAME</b>  | COMMON NAME        | SIZE     | SPACING       | QUANTITY |
|------------------------|--------------------|----------|---------------|----------|
| HERBACEOUS             |                    |          |               |          |
| Acorus americana       | Sweetflag          | 2" plugs | Min 2FT-0.C.  | 100      |
| ACORUS AMERICANA       | Swamp Milkweed     | 2" PLUGS | MIN. 2FT-0.C. | 100      |
| Caltha palustris       | Marsh Marigold     | 2" PLUGS | MIN. 2FT-0.C. | 100      |
| Carex Iurida           | Lurid Sedge        | 2" PLUGS | MIN. 2FT-0.C. | 100      |
| Carex stricta          | Tussock Sedge      | 2"PLUGS  | MIN. 2FT-O.C. | 100      |
| Eupatorium perfoliatum | Boneset            | 2"PLUGS  | MIN. 2FT-O.C. | 200      |
| Juncus effuses         | Soft Rush          | 2" PLUGS | MIN. 2FT-O.C. | 100      |
| lris versicolor        | Blue Flag Iris     | 2"PLUGS  | MIN. 2FT-O.C. | 200      |
| Lobelia siphilitica    | Great Blue Lobelia | 2"PLUGS  | MIN. 2FT-O.C. | 200      |
| Mimulus ringens        | Monkey-flower      | 2" PLUGS | MIN. 2FT-O.C. | 200      |

Note: Wetland plugs to be provided by New England Wetland Plants, Inc. (413-548-8000), or approved nursery. Substitutions based on availability are acceptable under the direction of a qualified wetland scientist.

PROPOSED WETLANDS MITIGATION AREA AREA = 4,500 sq. ft.

AREA TO BE PLANTED WITH NEW ENGLAND WETLAND PLANTS WETLAND PLANTS NEWENGLAND CONSERVATION/WILDLIFE SEED MIX • RATE OF 1,750 SF/LB





|   | //  | 5. <i>W.L</i> . 47   |
|---|---|--|
|   | ===   | S.W.L.   |
|   | 1   | $\underbrace{\begin{array}{ccccccccccccccccccccccccccccccccccc$  |
|   | $\frac{0.0  0.0  0.1}{0.1  0.1  0.1}$   | $\begin{array}{cccccccccccccccccccccccccccccccccccc$   |
| $\dot{0}.1$ $\dot{0}.0_{EX}$ , $\dot{N}.B.G.R.$ $\dot{0}.0$ $\dot{0}.0$ $\dot{0}.0$ $\dot{0}.0$ $\dot{0}.0$ $\dot{0}.0$ $\dot{0}.0$ $\dot{0}.0$ $\dot{0}.0$   | 0.0 	0.1 	0.1 	0.1 	0.1 	0.1  | $\begin{array}{cccccccccccccccccccccccccccccccccccc$   |
| 0.1 $0.1$ $0.1$ $0.1$ $0.0$ $0.0$ $0.0$ $0.0$ $0.0$ $0.0$ $0.0$ $0.0$ $0.0$ $0.0$ $0.0$ $0.0$ $0.0$ $0.0$ $0.0$ $0.0$ $0.0$ $0.1$   | $t_{0.1}$ $t_{0.2}$ $t_{0.2}$ $t_{0.3}$ $t_{0.3}$ $t_{0.3}$   | $\begin{array}{c} 98.87'  (ACCESS  EASE.) \\ 6  1.1  1.1  1.0  0.8  206 6 5 $  |
| $t_{0.3}$ $t_{0.3}$ $t_{0.3}$ $t_{0.3}$ $t_{0.2}$ $t_{0.1}$ $t_{0$  | $b_{0.2}  b_{0.2}^{\dagger}  b_{0.4}^{\dagger}  b_{0.5}^{\dagger}$  |  |
| $\begin{array}{cccccccccccccccccccccccccccccccccccc$  | $3  \begin{array}{c} 0.3  \begin{array}{c} 0.3 \\ 0.3 \end{array}  \begin{array}{c} 0.3 \\ 0.3 \end{array}  \begin{array}{c} 0.3 \\ 0.3 \\ 0.3 \\ 0.3 \end{array}  \begin{array}{c} 0.3 \\ 0.3 \\ 0.3 \\ 0.3 \end{array}  \begin{array}{c} 0.3 \\ 0.3 \\ 0.3 \\ 0.3 \end{array}  \begin{array}{c} 0.3 \\ 0.3 \\ 0.3 \\ 0.3 \\ 0.3 \end{array}  \begin{array}{c} 0.3 \\ 0.3 \\ 0.3 \\ 0.3 \\ 0.3 \end{array}  \begin{array}{c} 0.3 \\ 0.3 \\ 0.3 \\ 0.3 \\ 0.3 \\ 0.3 \end{array}  \begin{array}{c} 0.3 \\ 0.3$  | $\begin{array}{cccccccccccccccccccccccccccccccccccc$   |
| $\begin{array}{cccccccccccccccccccccccccccccccccccc$  | $\begin{array}{cccccccccccccccccccccccccccccccccccc$  | 1.4 $1.9$ $1.6$ $1.2$ $0.9$ $0.6$ $0.4$ $0.3$ $0.2$ $0.1$ $0.1$ $0.0$ $0.0$ $0.0$  |
| $\begin{array}{c} \begin{array}{c} \begin{array}{c} \begin{array}{c} \\ \\ \\ \\ \\ \end{array}\end{array} \\ \begin{array}{c} \\ \\ \\ \end{array} \\ \begin{array}{c} \\ \\ \\ \\ \end{array} \\ \begin{array}{c} \\ \\ \\ \end{array} \\ \begin{array}{c} \\ \\ \\ \end{array} \\ \begin{array}{c} \\ \\ \\ \\ \end{array} \\ \begin{array}{c} \\ \\ \\ \\ \end{array} \\ \begin{array}{c} \\ \\ \\ \end{array} \\ \begin{array}{c} \\ \\ \\ \end{array} \\ \end{array} \\ \begin{array}{c} \\ \\ \end{array} \\ \end{array} \\ \end{array} \\ \begin{array}{c} \\ \\ \end{array} \\ \end{array} \\ \end{array} \\ \begin{array}{c} \\ \\ \end{array} \\ \end{array} \\ \end{array} \\ \end{array} \\ \begin{array}{c} \\ \end{array} \\ $ | 5 1.1 <del>0.</del> 9 0.8 0.7 +   | 1.1 $1.3$ $1.2$ $1.1$ $1.8$ $1.6$ $1.4$ $1.6$ $1.2$ $1.1$ $1.0.0$ $0.0$ $0.0$ $0.0$  |
| $\begin{array}{cccccccccccccccccccccccccccccccccccc$  | .5 <sup>†</sup> .2 <sup>†</sup> 0.9 <sup>†</sup> 0.8 <sup>†</sup> 0.6<br><u>N 72°45'39" W</u>   | $\begin{array}{cccccccccccccccccccccccccccccccccccc$   |
| 1.7 1.8<br>1.3 1.2 1.2 1.1 1.0 0.9 $\pm 0.8$ 0.8 0.9 1.1 1.3 1.3 1.<br>WF#41  | $.2 + 1.0 = 5.00^{\circ}_{0.8} + 0.7 = 0.6$   | 1 29503 (ACCESS TEASE, ) 1 3 1 2 1 2 1 0.1 0.1 0.0 0.0 0.0   |
| $10^{-1}0.9^{-0.9}0.9^{-0.9}0.9^{-0.8}-0.7^{-0.02}$   |   | + $+$ $+$ $+$ $+$ $+$ $+$ $+$ $+$ $+$  |
|   |   |  |
|   |   |  |
| $2^{4}$ $1.3$ $1.3$ $0.9$ $0.4$ $0.4$ $0.3$ $0.2$ $0.1$ $0.1$ $0.1$ $0.0$ $0.0$   | 0.0 0.0 0.0 0.0 0.0 0.0 100   | $\begin{array}{cccccccccccccccccccccccccccccccccccc$   |
| 3 $1.6$ $1.8$ $1.3$ $0.6$ $0.5$ $0.3$ $WF#44$ $1$ $0.1$ $0.1$ $0.0$ $0.0$ $WF#44$   | $\begin{array}{cccccccccccccccccccccccccccccccccccc$  | $\begin{array}{cccccccccccccccccccccccccccccccccccc$   |
| 4 $1.9$ $2.4$ $2.3$ $1.3$ $0.6$ $0.3$ $0.2$   |   |  |
| $\begin{array}{cccccccccccccccccccccccccccccccccccc$  | <sup>+</sup> 0.0 <sup>+</sup> 0.0 <sup>+</sup> 0.0 <sup>+</sup> 0.0 <sup>+</sup> 0.0  | $\begin{array}{cccccccccccccccccccccccccccccccccccc$   |
| $1.0  \frac{1}{1.1}  \frac{1}{1.1}  \frac{1}{0.8}  \frac{1}{0.3}  \frac{1}{0.2}  \frac{1}{0.1}  \frac{1}{0.1}  \frac{1}{0.1}  \frac{1}{0.0}  \frac{1}{0.0} $  |   | $\begin{array}{cccccccccccccccccccccccccccccccccccc$   |
| $t_{0.8}$ $t_{0.8}$ $t_{0.8}$ $t_{0.5}$ $t_{0.1}$ $t_{0.1}$ $t_{0.1}$ $t_{0.1}$ $t_{0.1}$ $t_{0.1}$ $t_{0.1}$ $t_{0.1}$   |   | t to to to to $0.0$ $0.0$ $0.0$ $0.0$ $0.0$ $0.0$ $0.0$ $0.0$ $0.0$  |
| b.5 $b.5$   | $\dot{\phi}_{0,0}^{\dagger}$ $\dot{\phi}_{0,0}$ $\dot{\phi}_{0,0}$ $\dot{\phi}_{0,0}$ $\dot{\phi}_{0,0}$ $\dot{\phi}_{0,0}$   | $\begin{array}{cccccccccccccccccccccccccccccccccccc$   |
| $\begin{array}{cccccccccccccccccccccccccccccccccccc$  | $\begin{array}{c} & & \\ & & \\ & & \\ & 0 \\ & & \\$  | $\begin{array}{cccccccccccccccccccccccccccccccccccc$   |
| $t_{0,0}$ $t_{0$  | $\dot{a}_{0,0}$ $\dot{b}_{0,0}$ $\dot{b}_{0,0}$ $\dot{b}_{0,0}$ $\dot{b}_{0,0}$ $\dot{b}_{0,0}$ $\dot{b}_{0,0}$   | $\begin{array}{cccccccccccccccccccccccccccccccccccc$   |
|   | $10^{+0}$ $10^{+0}$ $10^{+0}$ $10^{-0}$ $10^{-0}$ $10^{-0}$   | 0.0    |
| $^{+}_{0.0}$ $\overset{-}_{0.0}$ $\overset{-}_{0.0}$ $\overset{-}_{0.0}$ $\overset{-}_{0.0}$ $\overset{-}_{0.0}$ $\overset{-}_{0.0}$ $\overset{-}_{0.0}$  |   | $a = \frac{1}{2}$  |
| $ \begin{array}{cccccccccccccccccccccccccccccccccccc$   | 0 <sup>+</sup> 0.0 | $b_{0.0}$ $b_{0$   |
| $t_{0}$ $t_{0$  |   | $t_{1}$ $t_{2}$ $t_{2$   |
| 0' UPLAND REVIEW AREA $0.0  0.0 $  | $\begin{array}{cccccccccccccccccccccccccccccccccccc$  | $\begin{array}{cccccccccccccccccccccccccccccccccccc$   |
| $\dot{0}_{.0}$   | $0.0  \stackrel{+}{0}  \stackrel{-}{0}  \stackrel{-}{0} $  | $\begin{array}{cccccccccccccccccccccccccccccccccccc$   |
| $\begin{array}{cccccccccccccccccccccccccccccccccccc$  | $t_{0}$ $t_{0$  | $\begin{array}{cccccccccccccccccccccccccccccccccccc$   |
| 0.0 $0.0$ $0.0$ $0.0$ $0.0$ $0.0$ $0.0$ $0.0$ $0.0$ $0.0$ $0.0$ $0.0$ $0.0$ $0.0$ $0.0$   |   | $t_{0,0}$ $t_{0$   |
| 5  0.0   | $t_{0}^{0}$ $t_{0,0}^{0}$ $t_{0,0}^{0}$ $t_{0,0}^{0}$ $t_{0,0}^{0}$ $t_{0,0}^{0}$ $t_{0,0}^{0}$ $t_{0,0}^{0}$ $t_{0,0}^{0}$   | $\dot{0}.0$ $\dot$   |
|   |   |  |
| $\begin{array}{cccccccccccccccccccccccccccccccccccc$  | \#&GE <sup>™</sup> \@IGHTS <sup>™</sup> 0 <sup>™</sup> C<br>WIG & JAMES J. (  | $\frac{DBERT}{DESSAY} \stackrel{0.0}{\longrightarrow} \stackrel{0.0}{$ |
| 0, 0, 0, 0, 0, 0, 0, 0, 0, 0, 0, 0, 0, 0  | uwogo 199, FG. 7  | 5  |
| $0.0$ $\dot{0}.0$   |   | $\dot{0}$  |
| $\begin{array}{cccccccccccccccccccccccccccccccccccc$  | $\dot{0}_{0}$ $\dot{0}_{0}$ $\dot{0}_{0}$ $\dot{0}_{0}$ $\dot{0}_{0}$ $\dot{0}_{0}$ $\dot{0}_{0}$   | $\dot{0}$ , $\dot{0}$  |
| $t_{0}$ $t_{0$  |   | $t$ , $t_{00}$ ,  |
| $t_{0.0}$ $t_{0$  |   | $\begin{array}{cccccccccccccccccccccccccccccccccccc$   |
| 0.0 $0.0$   | $\frac{1}{1}$ $\frac{1}$  | $\begin{array}{cccccccccccccccccccccccccccccccccccc$   |
| $\begin{array}{cccccccccccccccccccccccccccccccccccc$  | 0 <sup>†</sup> 0 <sup>†</sup> 0 <sup>†</sup> 0.0 <sup>†</sup> 0.0 <sup>†</sup> 0.0 <sup>†</sup> 0.0   | $\begin{array}{cccccccccccccccccccccccccccccccccccc$   |
| $\begin{array}{cccccccccccccccccccccccccccccccccccc$  |   | $\begin{array}{cccccccccccccccccccccccccccccccccccc$   |
|   |   | 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0 0.0  |

CT NAD 83

GRAPHIC SCALE ( IN FEET ) 1 inch = 30 ft.

COMMERCIAL OUTDOOR

area lights and floodlights. CONSTRUCTION -

foundation design.

OUTDOOR

Specifications

EPA:

Length:

Width:

Height H1:

Height H2:

DSX1 LED

Weight:

0.69 ft<sup>2</sup> (0.06 m<sup>2</sup>)

32.71" (83.1 cm)

14.26" (36.2 cm)

7.88" (20.0 cm)

2.73" (6.9 cm)

34 lbs (15.4 kg)

P1 P6 P2 P7

P3 P8

P4 P9

P101 P121

P111 P131

Rotated optics


P5

Shipped installed


PIR

PER

PER5



NO. 2066



# Ellington, CT Retail Shell

West Rd. (Rt 82) Ellington, CT


Prepared For

Calito DEVELOPMENT GROUP **Conceptual Elevations** 


Drawn by: DSG

BKA # 222115

|       | EXTERIOR F                      | INISH SCHE                       | EDULE                                  |
|-------|---------------------------------|----------------------------------|--|
| TAG   | MATERIAL/ MFG.                  | COLOR/ NO.                       | NOTES                                  |
| X1)   | CULTURED STONE<br>WAINSCOT      | COLOR: PALISADES                 | DEL-MAR<br>ANCIENT VILLA<br>LEDGESTONE |
| (X2)  | STANDARD METAL<br>PANEL         | COLOR: POLAR<br>WHITE            | FINISH BY PEMB                         |
| X2A)  | HARDIE BOARD                    | COLOR: ARCTIC<br>WHITE           | PRE-FINISHED                           |
| X2B   | HARDIE TRIM                     | COLOR: ARCTIC<br>WHITE           | PRE-FINISHED                           |
| ×2C)  | VERTICAL BATTON<br>HARDIE BOARD | COLOR: ARCTIC<br>WHITE           | PRE-FINISHED                           |
| X2D   | FINISHED PLWD                   | COLOR: LT BROWN<br>STAIN         | PRE-FINISHED<br>WOOD GRAIN             |
| (X3)  | STANDARD ENTRY<br>DOORS         | COLOR: DARK<br>BRONZE            | PRE-FINISHED                           |
| (X4)  | STANDARD METAL<br>ROOF PANEL    | COLOR:<br>GALVALUME              | FINISH BY PEMB                         |
| (X5)  | MTL GUTTERS,<br>DOWNSPOUTS      | COLOR: POLAR<br>WHITE            | FINISH BY PEMB                         |
| (X6)  | MTL GUTTERS,<br>DOWNSPOUTS      | COLOR: POLAR<br>WHITE            | FINISH BY PEMB                         |
| (X7)  | MTL COPING                      | COLOR: WHITE                     | FINISH BY PEMB                         |
| (X8)  | NOT USED                        | COLOR: N/A                       | N/A                                    |
| (X9)  | SPANDREL<br>STOREFRONT          | COLOR: DARK<br>BRONZE            | LT GREY FILM                           |
| ×10   | INS DOOR &<br>FRAME             | COLOR: TO<br>MATCH (X2)          | PAINTED                                |
| (X11) | MTL AWNING                      | COLOR: DARK<br>BRONZE            | FINISH BY PEMB                         |
| ×12   | NOT USED                        | N/A                              | N/A                                    |
| ×13   | ARCH ASPHALT<br>SHINGLES        | COLOR:<br>WEATHERED WOOD         | GAF TIMBERLINE                         |
| (X14) | WOOD TRELLIS                    | COLOR: STAINED<br>TO MATCH (X2D) | 6" X 6" WD POST<br>FEILD FABRIACTED    |



BKA Architects, Inc. Quincy + Tampa www.bkaarchitects.com



## PLANTING NOTES

- 1. BE AWARE OF ALL UNDERGROUND UTILITIES PRIOR TO ANY EXCAVATION OR PLANTING OPERATIONS. USE CARE TO PROTECT EXISTING UTILITIES FROM DAMAGE, CONTACT "CALL BEFORE YOU DIG" PRIOR TO EXCAVATION. 2. ALL PLANTINGS ARE TO BE INSTALLED BY A QUALIFIED LANDSCAPE CONTRACTOR.
- 3. THE CONTRACTOR SHALL BE REQUIRED TO CARRY WORKMEN'S COMPENSATION INSURANCE AND COMPREHENSIVE
- GENERAL LIABILITY INSURANCE. CERTIFICATES WILL BE REQUIRED PRIOR TO SIGNING CONTRACTS. 4. CONTRACTOR IS RESPONSIBLE FOR JOBSITE SAFETY. CONTRACTOR SHALL MAINTAIN A SAFE JOBSITE AT ALL TIMES. 5. CONTRACTOR SHALL BE FAMILIAR WITH THE SITE TO VERIFY ALL DIMENSIONS, GRADES AND EXISTING CONDITIONS. REPORT ANY DISCREPANCIES TO LANDSCAPE DESIGNER.
- . CONTRACTOR IS RESPONSIBLE FOR OBTAINING ALL PERMITS AND LICENSES REQUIRED FOR COMPLETING WORK. CONTRACTOR SHALL BE RESPONSIBLE FOR DISPOSAL OF ALL EXCAVATED SOIL, BRUSH AND DEBRIS OFF-SITE IN A SAFE
- AND LEGAL MANNER. 8. NOTIFY OWNER OR LANDSCAPE DESIGNER 72 HOURS MINIMUM IN ADVANCE OF STARTING PLANTING OPERATIONS.
- RECEIVE APPROVAL FOR LAYOUT OF ALL BED LINES AND MATERIAL LOCATIONS PRIOR TO INSTALLATION. . PROTECT EXISTING VEGETATION TO REMAIN FROM DAMAGE DURING CONSTRUCTION. IT IS THE INTENT OF THIS CONTRACT TO AVOID ANY DISTURBANCE TO EXISTING VEGETATION ON THE SITE OTHER THAN THOSE SPECIFICALLY DESIGNATED FOR REMOVAL. ADJUSTMENTS SHALL BE MADE IN THE FIELD AT THE DIRECTION OF THE LANDSCAPE DESIGNER.
- 10. CONTRACTOR IS RESPONSIBLE FOR COORDINATING ALL PLANTING, SEEDING AND TREE WORK WITH OTHER TRADES. RESPECT OTHER TRADES WORK AT ALL TIMES. 11. CONTRACTOR IS TO EXERCISE EXTREME CARE DURING THE COURSE OF DEMOLITION AND REMOVALS ANY DAMAGE TO
- EXISTING FACILITIES, UTILITIES OR TREES TO REMAIN SHALL BE THE SOLE RESPONSIBILITY OF THE CONTRACTOR TO REPLACE IN KIND. 12. CONTRACTOR IS RESPONSIBLE FOR RESTORING ALL AREAS DAMAGED TO PRE-EXISTING CONDITIONS AS A RESULT OF
- PLANTING OPERATIONS TO OWNERS AND/OR LANDSCAPE DESIGNERS APPROVAL. 13. VEGETATION TO BE REMOVED, NOT INDICATED ON PLAN, SHALL BE TAGGED IN FIELD BY LANDSCAPE DESIGNER. 14. THE LANDSCAPE DESIGNER RESERVES THE RIGHT TO REJECT INFERIOR PLANT MATERIALS AND SUBSTITUTIONS. THE LANDSCAPE DESIGNER IS WILLING TO MAKE TWO TRIPS TO SUPPLIERS TO TAG, REVIEW AND APPROVE MATERIALS.
- PREVIOUSLY UNAPPROVED MATERIALS MAY BE REJECTED AT THE SITE. MINIMALLY, ALL MATERIALS WILL CONFORM TO THE "AMERICAN STANDARD FOR NURSERY STOCK" (ANSI Z60.1 - 2004) OF THE AMERICAN ASSOCIATION OF NURSERYMEN. 15. ALL PLANT MATERIAL SHALL BE GUARANTEED BY THE CONTRACTOR TO BE IN GOOD, HEALTHY AND FLOURISHING CONDITION FOR A PERIOD OF ONE YEAR FROM THE DATE OF ACCEPTANCE. THE CONTRACTOR SHALL REPLACE, AS SOON AS WEATHER AND SEASONAL CONDITIONS PERMIT, ALL DEAD PLANTS AND ALL PLANTS NOT IN A VIGOROUS, THRIVING CONDITION. AS DETERMINED BY THE LANDSCAPE DESIGNER DURING, AND AT THE END OF THE GUARANTEE PERIOD. WARRANTY REPLACEMENT WILL BE PROVIDED AT NO COST TO THE OWNER AND INCLUDE MATERIALS AND LABOR. CONTRACTOR IS RESPONSIBLE FOR REPAIR OF ANY DAMAGE INCURRED DURING REPLACEMENT OF WARRANTY
- MATERIALS. 16. WHEN THERE IS A DISCREPANCY BETWEEN PLANT QUANTITIES SHOWN ON THE PLANT LIST & THE PLAN, USE THE QUANTITIES FROM THE PLAN.
- 17. PERENNIALS, GROUNDCOVERS & GRASSES TO BE FIELD LOCATED BY LANDSCAPE DESIGNER. COORDINATE TO NOTIFY LANDSCAPE DESIGNER AT LEAST 72 HOURS IN ADVANCE OF EXPECTED INSTALLATION DATE. ON THAT DATE ALL BEDS SHALL BE PREPARED & ALL PLANT MATERIAL SHALL BE ON SITE.
- 18. PROVIDE A MINIMUM 6" TOPSOIL FOR ALL DISTURBED AREAS. SUBMIT SAMPLE OF TOPSOIL AND SOIL TEST RESULTS FOR LANDSCAPE DESIGNER APPROVAL PRIOR TO DELIVERING TO SITE. 19. MULCH ALL BEDS SHOWN AS CONTINUOUS WITH A 3" MINIMUM OF DOUBLE SHREDDED CEDAR BARK MULCH. SAMPLE TO
- BE SUBMITTED TO LANDSCAPE DESIGNER FOR APPROVAL. 20. ALL PLANT MATERIALS TO BE SOURCED FROM LOCALLY GROWN GROWERS.

## PLANTING SCHEDULE

| KEY    | QTY      | BOTANICAL NAME                           | COMMON NAME                      | ROOT | SIZE            | COMMENTS              |
|--------|----------|--|----------------------------------|------|-----------------|-----------------------|
| TREES  |          |  |                                  | 1    |                 |                       |
| AR     | 3        | ACER RUBRUM 'RED SUNSET'                 | RED SUNSET RED MAPLE             | B&B  | 2 1/2" - 3" CAL | FULL, EXTRA HEAVY     |
| BN     | 7        | BETULA NIGRA 'HERITAGE'                  | HERITAGE RIVER BIRCH             | B&B  | 2 1/2" - 3" CAL | SINGLE STEM           |
| GB     | 5        | GINKO BILOBA 'PRINCETON SENTRY'          | PRINCETON SENTRY MAIDENHAIR TREE | B&B  | 2 1/2" - 3" CAL | FULL, EXTRA HEAVY     |
| QR     | 4        | QUERCUS RUBRA                            | RED OAK                          | B&B  | 2 1/2" - 3" CAL | FULL, EXTRA HEAVY     |
| UA     | 6        | ULMAS AMERICANA 'PRINCETON'              | PRINCETON ELM                    | B&B  | 2 1/2" - 3" CAL | FULL, EXTRA HEAVY     |
| UPLANI | SHRUBS   | 5  |                                  |      |                 |                       |
| ADW    | 15       | RHODODENDRON 'DELEWARE WHITE'            | DELEWARE WHITE AZALEA            | CONT | 30-36" HT       |                       |
| IG     | 10       | ILEX GLABRA 'SHAMROCK'                   | INKBERRY HOLLY 'SHAMROCK'        | CONT | 30-36" HT       | FULL, EXTRA HEAVY     |
| PO     | 10       | PHYSOCARPUS OPULIFOLIUS                  | COMMON NINEBARK                  | CONT | 30-36" HT       | FULL, EXTRA HEAVY     |
| PJM    | 10       | PJM RHODODENRON 'ELITE STAR'             | PJM RHODODENDRON 'ELITE STAR'    | CONT | 30-36" HT       | FULL, EXTRA HEAVY     |
| GRASSE | S / GROU | NDCOVER / PERENNIALS                     |                                  | 1    |                 |                       |
| JH     | 13       | JUNIPERUS HORIZONTALIS                   | HETZICOLUMNARIS CHINESE JUNIPER  | CONT | 3 GAL           | FULL, EXTRA HEAVY     |
| MG     | 14       | MISCANTHUS SINENSIS 'GRACILLIMUS'        | MAIDEN GRASS                     | CONT | 3 GAL           | FULL, EXTRA HEAVY     |
| PA     | 13       | PENNISETUM ALOPECUROIDES 'LITTLE BUNNY   | FOUNTAIN GRASS                   | CONT | 3 GAL           | FULL, EXTRA HEAVY     |
| WETLA  | ND TREES | S AND SHRUBS                             |                                  | 1000 |                 |                       |
| AM     | 3        | AMELANCHIER CANADENSIS                   | SHADBLOW SERVICEBERRY            | CONT | 6 HT            | FULL, EXTRA HEAVY     |
| CA     | 65       | CAREX STRICTA                            | TUSSOCK SEDGE                    | CONT | 1 GAL           | FULL, EXTRA HEAVY     |
| CL     | 5        | CLETHRA ALNIFOLIA                        | SWEET PEPPERBUSH                 | CONT | 36" HT          | FULL, EXTRA HEAVY     |
| IV     | 6        | ILEX VERTICILLATA                        | WINTERBERRY                      | CONT | 5 GAL           | FULL, EXTRA HEAVY     |
| VD     | 6        | VIBURNUM DENTATUM                        | ARROWWOOD VIBURNUM               | CONT | 5 GAL           | FULL, EXTRA HEAVY     |
| SEED M | IXES     |  |                                  | 1    |                 | and the second second |
| LAWN:  | PENNING  | TON SMART SEED SUN AND SHADE             |                                  |      |                 |                       |
|        | APPLICA  | TION RATE NEW LAWNS: 9 LB/1,000 S.F.     |                                  |      |                 |                       |
| NEW EN | GLAND F  | ROADSIDE MATRIX UPLAND MIX (NEW ENGLAN   | D WETLAND PLANTS, INC.)          |      |                 |                       |
|        | APPLICA  | ATION RATE: 1 LB/1,250 S.F.              |                                  |      |                 |                       |
| NEW EN | GLAND H  | EROSION CONTROL/RESTORATION MIX (NEW E   | NGLAND WETLAND PLANTS, INC.)     |      |                 |                       |
|        | APPLICA  | TION RATE NEW LAWNS: 9 LB/1,000 S.F.     |                                  |      |                 |                       |
| NEW EN | GLAND C  | CONSERVATION / WILDLIFE MIX (NEW ENGLANI | D WETLAND PLANTS, INC.)          |      |                 |                       |
|        | ADDITCA  | TION DATE, 1 LD/1 450 S E                |                                  |      |                 |                       |

APPLICATION RATE: 1 LB/1,450 S.F.

## WETLAND MITIGATION PLANTING SCHEDULE

| KEY                     | QTY     | <b>BOTANICAL NAME</b>       | COMMON NAME        | ROOT     | SPACING         | COMMENTS      |
|-------------------------|---------|-----------------------------|--------------------|----------|-----------------|---------------|
|                         | 50      | ACORUS AMERICANA            | SWEETFLAG          | 2" PLUGS | 2' O.C. MINIMUM | WETLAND PLANT |
| · · · · · · · · · · · · | 50      | ASCLEPIAS INCARNATA         | SWAMP MILKWEED     | 2" PLUGS | 2' O.C. MINIMUM | WETLAND PLANT |
|                         | 50      | CALTHA PALUSTRIS            | MARSH MARIGOLD     | 2" PLUGS | 2' O.C. MINIMUM | WETLAND PLANT |
|                         | 50      | CAREX LURIDA                | LURID SEDGE        | 2" PLUGS | 2' O.C. MINIMUM | WETLAND PLANT |
|                         | 50      | CAREX STRICTA               | TUSSOCK SEDGE      | 2" PLUGS | 2' O.C. MINIMUM | WETLAND PLANT |
|                         | 100     | EUPATORIUM PERFOLIATUM      | BONESET            | 2" PLUGS | 2' O.C. MINIMUM | WETLAND PLANT |
|                         | 50      | JUNCUS EFFUSES              | SOFT RUSH          | 2" PLUGS | 2' O.C. MINIMUM | WETLAND PLANT |
|                         | 100     | IRIS VERSICOLOR             | BLUE FLAG IRIS     | 2" PLUGS | 2' O.C. MINIMUM | WETLAND PLANT |
|                         | 100     | LOBELIA SIPHILITICA         | GREAT BLUE LOBELIA | 2" PLUGS | 2' O.C. MINIMUM | WETLAND PLANT |
|                         | 100     | MIMULUS RINGENS             | MONKEY-FLOWER      | 2" PLUGS | 2' O.C. MINIMUM | WETLAND PLANT |
| EED M                   | IXES    |                             |                    |          |                 |               |
| EW EN                   | GLAND C | CONSERVATION / WILDLIFE MIX |                    |          |                 |               |
|                         | APPLICA | TION RATE: 1 LB/1,750 S.F.  |                    |          |                 |               |

### PLANTING SOIL NOTES

- 1. ALL PLANTING MIXES SHALL BE PREPARED PRIOR TO DELIVERY TO SITE. 2. PLANTING MIX FOR TREES AND SHRUBS SHALL BE AS
- FOLLOWS: **3 PARTS SCREED TOPSOIL**
- 1 PART CLEAN WASHED COARSE SAND
- 1 PART PEAT HUMUS 5 LBS. SUPER PHOSPHATE PER CUBIC YARD OF MIX
- 3. MYCORRHIZAL INNCOULANT TO BE MYCOR TREE SAVER TRANSPLANT BY PLANT HEALTH CARE, INC. (1-800-421-9051) OR APPROVED EQUAL.
- 4. TERRASORB AVAILABLE FROM PLANT HEALTH CARE, INC. OR
- APPROVED EQUAL 5. SUBMIT CERTIFICATION OF PLANTING MIX FOR TREES AND
- SHRUBS FROM SOIL DISTRIBUTOR.
- 6. TOPSOIL MIX SHALL INCLUDE: **3 PARTS SCREENED TOPSOIL**
- 1 PART SAND

1 PART HUMUS 5 LBS. SUPER PHOSPHATE PER CU. YD. OF MIX


- 7. TOPSOIL:
- A. PROVIDE A NATURAL, FERTILE, FRIABLE, NATURAL LOAM SURFACE SOIL CAPABLE OF SUSTAINING VIGOROUS PLANT GROWTH. OF UNIFORM COMPOSITION THROUGHOUT AND WITHOUT ADMIXTURES OF SUBSOIL, AND FREE OF STONES, LUMPS, PLANTS, ROOTS, STICKS OR OTHER EXTRANEOUS MATTER.
- B. TOPSOIL SHALL CONTAIN NOT LESS THAN 4% NOR MORE THAN 20% ORGANIC MATTER AS DETERMINED BY THE WET COMBUSTION METHOD.
- C. MECHANICAL ANALYSIS

| REEN SIZE             | % BY WEIGHT PASSING    |
|-----------------------|------------------------|
| 1"                    | 100                    |
| 1/4"                  | 97 - 100               |
| NO. 200               | 20 - 65                |
| CTORS SHALL BE RESPON | NSIBLE FOR ALL TESTING |

- D. CONTRACTORS SHALL BE RESPONSIBLE FOR ALL TESTING AND ANALYSIS OF EXISTING AND IMPORTED SOILS. FURNISH A SOIL ANALYSIS MADE BY A QUALIFIED INDEPENDENT SOIL-TESTING AGENCY STATING PERCENTAGES OF ORGANIC MATTER, INORGANIC MATTER (SILT, CLAY, AND SAND), DELETERIOUS MATERIAL, PH, AND
- MINERAL AND PLANT-NUTRIENT CONTENT OF TOPSOIL. E. REPORT SUITABILITY OF TOPSOIL FOR LAWN AND SHRUB PLANTING GROWTH. RECOMMEND QUANTITIES OF NITROGEN, PHOSPHORUS, AND POTASH NUTRIENT AND ANY LIMESTONE, ALUMINUM SULFATE, OR OTHER SOIL
- AMENDMENTS TO BE ADDED TO PRODUCE A SATISFACTORY TOPSOIL.

# LEGEND

| <br> |  |
|------|--|
|      |  |



 $\times\!\!\!\times\!\!\!\times$ 

\* \*

.....

 $\nabla \nabla \nabla$ 

0505050

# PROPERTY LINE **RIGHT-OF-WAY LINE** ADJOINING LOT LINE LIMIT OF WETLANDS 100 YEAR FLOOD HAZARD AREA

#### OVERSTORY TREE

| SHRUBS & GROUNDCOVER                                |
|---|
| LAWN  |
| NEW ENGLAND ROADSIDE MATRIX<br>UPLAND MIX           |
| NEW ENGLAND EROSION<br>CONTROL/RESTORATION NO MOW M |
| NEW ENGLAND WETMIX                                  |
|   |

WETLAND MITIGATION PLANTINGS NEW ENGLAND CONSERVATION /

WILDLIFE MIX RIVER ROCK

#### GENERAL NOTES

- 1. ALL SITE WORK TO BE COMPLETED IN ACCORDANCE WITH ALL PERMITS, APPROVALS AND CONDITIONS OF APPROVALS ISSUED BY THE TOWN OF ELLINGTON, CONNECTICUT AND THE STATE OF CONNECTICUT FOR THIS PROJECT.
- 2. EXISTING SITE CONDITIONS AND BOUNDARY INFORMATION TAKEN FROM A PLAN TITLED "ZONING IMPROVEMENT LOCATION SURVEY-PROPOSED 175 WEST ROAD", SCALE 1"=40', PREPARED BY HALLSEY, PEARSON, AND CASSIDY.

| 1                 | 12/16/2024 I | Response To Comments                                      |  |
|-------------------|--------------|---|--|
| Rev. #:           |              | Description   |  |
| Graphic Scale     |              | Seconption  |  |
| 40                | 0            | 40 80   |  |
|                   |              |   |  |
| MC                | SOLLIENGIN   | FORD, CT   NORWOOD, MA<br>EERING.COM<br>F: (203) 880-9695 |  |
| Drawn By:         | JJS          | NUMBER OF CONVERSE  |  |
| Checked By:       | MFB          | E BLACK BURN  |  |
| Approved By:      | KMS          | * Mar B   |  |
| Project #:        | 24112401     | ANDSCAPE ACCOUNT  |  |
| Plan Date:        | 09/18/24     | Mary Blackburn, P.L.A.                                    |  |
| Scale:            | 1'' = 40'    | CT 1499   |  |
| Project:          | ח∩חח         | OCED  |  |
| _                 |              | OSED  |  |
| DEVELOPMENT       |              |   |  |
|                   |              | ROAD  |  |
| ELLINGTON, CT     |              |   |  |
| Sheet Title:      |              | Sheet #:  |  |
| I ANI             | )SCAPE       |   |  |
| LANDSCAPE<br>PLAN |              | 2.61  |  |
|                   |              |   |  |
|                   |              |   |  |



March 31, 2025

Town of Ellington Inland Wetlands Agency

Re: Resubdivision 20 Punkin Drive

Dear Agency,


At the request of the applicant, Philip & Michelle Bahler, I hereby request a positive referral from the Inland Wetland Agency to the Planning & Zoning Commission for the proposed Resubdivision Plan for Philip Bahler 20 Punkin Drive dated 3/25/2025.

The resubdivision plans proposed one new building lot and all proposed construction activities are located outside the wetlands and the 100' upland review area.

Sincerely,

Rachel Dearbyn

Rachel Dearborn L.S.



#### Town of Ellington Inland Wetlands and Watercourses Agency Application

Application #\_*IW202503* Date Submitted \_<u>4/15/2025</u>

| Notices associated with this application will be sent to the applicant unless otherwise requested.  | Notices associated with this application will be sent to the applicant unless otherwise requested.  |  |  |  |
|---|---|--|--|--|
| Owner's Information   | Applicant's Information (if different than owner)   |  |  |  |
| Name:Town of Ellington  | Name: (Same)  |  |  |  |
| Mailing<br>Address: 21 Main Street  | Mailing<br>Address:   |  |  |  |
| Ellington, CT 06029   |   |  |  |  |
| Email:  | Email:  |  |  |  |
| WHEN NOT REQUIRED BY LAW TO MAIL NOTICE BY USPS,<br>MAY NOTICES BE EMAILED TO YOU? Yes No<br>Primary Contact Phone #: 860-870-3140  | WHEN NOT REQUIRED BY LAW TO MAIL NOTICE BY USPS,<br>MAY NOTICES BE EMAILED TO YOU?  Yes No<br>Primary Contact Phone #:  |  |  |  |
| Secondary Contact Phone #: 860-870-3100   |   |  |  |  |
| Owner's<br>Signature: Date: 4/15/25   | Secondary Contact Phone #:<br>Applicant's<br>Signature: Date:   |  |  |  |
| By signing below I certify that all information submitted with this application is true<br>and accurate to the best of my knowledge, that I am aware of and understand<br>the application requirements and regulations, and acknowledge that the<br>application is to be considered complete only when all information and<br>documents required by the Agency have been submitted. Moreover, by signing<br>above I/we expressly provide written consent to the filing of the application and<br>access to the site by the Agency or its staff. | By signing below I certify that all information submitted with this application is true<br>and accurate to the best of my knowledge, that I am aware of and understand<br>the application requirements and regulations, and acknowledge that the<br>application is to be considered complete only when all information and<br>documents required by the Agency have been submitted. |  |  |  |
| Street Address: 79 Kibbe Road   | APR 15 2025   |  |  |  |
| Assessor's Parcel Number (APN): <u>142</u> <u>002</u>   | 0000 TOWN OF ELLINGTON<br>PLANNING DEPARTMENT   |  |  |  |
| Proposed upland review area affected in square feet:  | · • • • • • • • • • • • • • • • • • • •   |  |  |  |
| Proposed wetlands/watercourses affected in square feet  |   |  |  |  |
| Total area of wetlands/watercourses on parcel in square   |   |  |  |  |
| <b>Public Water:</b> Yes <b>✓</b> No <b>Public Sewer:</b> Yes <b>✓</b> No <b>application to North Central District Health Department (Enfield Office</b> )  | 0 <u>If not served by public water and sewer, applicant shall make</u>  |  |  |  |
| Is the project in a public water supply watershed area? Yes No<br>If YES, applicant is required to notify the Connecticut Water Company and Commissioner of Public Health by certified mail, return receipt<br>within 7 days of this application (Conn. Gen Stat. Sec 22a-42f). Copy of application, plans, and supporting documents must accompany<br>notice. Applicant can email the Commissioner of Public Health using their approved form. Proof of notice (return receipt and sent email)<br>must be provided to the Planning Department. |   |  |  |  |
| Describe the nature of proposed regulated activity, reque<br>nonregulated use, map or regulation amendment, or othe<br>See attached Application Checklist and Appendix D for guidance who   | r activity requiring review by the Agency or its Agent:   |  |  |  |
| See attached narrative and photos.  |   |  |  |  |
|   |   |  |  |  |
|   |   |  |  |  |
|   | · · · · · · · · · · · · · · · · · · ·   |  |  |  |
|   |   |  |  |  |

| Applicant shall provide certification in accordance with Wetlands Regulation, Section 7.4e, Application Requirements:   |               |
|---|---------------|
| Whether or not any portion of the property on which the regulated activity is proposed is located within 500 fe<br>adjoining town. Yes V No   | et of an      |
| Whether or not a significant portion of the traffic to the completed project will use streets within an adjoining to exit or enter the site. Yes VINO   | own to        |
| Whether or not a significant portion of the sewer or water drainage from the project will flow through and signi impact the sewer or water drainage system of an adjoining town. Yes Vo   | ficantly      |
| Whether water run-off from the improved site will impact streets or other municipal/private property within an a town. Yes V No   | adjoining     |
| FOR OFFICE USE ONLY<br>If YES to any of the above, the Agency shall, in accordance with CGS 8-7d(f) notify the clerk of any adjoining<br>municipality of the pendency of any application, petition, appeal, request or plan concerning any project on any sit<br>Notice of the pendency of such application shall be made by certified mail, return receipt requested, and shall be<br>within seven (7) days of the date of receipt of the application, petition, appeal, request or plan. (See Agency<br>requirements Section 8.4) | te.<br>mailed |
| Type of Project: (check one)  |               |
| Commercial/IndustrialResidentialMixed Use Timber Agricultura  | al            |
| X Other, explain: Municipal   |               |
| Type of Application: (check one)  |               |
| X Notification for Non-Regulated Use (Section 4.2)  |               |
| Notification of Permitted Use as of Right (Section 4.1)   |               |
| Administrative Permit (Section 6.4)   |               |
| Agency Permit (TWELVE COPIES REQUIRED)  |               |
| Permit Modification   |               |
| Permit Extension  |               |
| Regulation Amendment  |               |
| Map Amendment   |               |
| Appeal of Administrative Permit   |               |
| Application Submittals:   |               |
| Completed Application Form (Section 7.4a)   |               |
| Application Fee (Section 7.4b)  |               |
| Abutters List (Section 7.4c)  |               |
| Certification as to Adjacent Towns (See above)  |               |
| Certification as to Connecticut Water Company & Commissioner of Public Health (See above)   |               |
| Notification Narrative and Supporting Documentation (If applicable, Appendix D)   |               |
| Project Narrative and Supporting Documentation (Section 7.4g, 1-11 inclusive, as deemed appli   | cable)        |
| Project Site Plan - circle one: Administrative (Section 7.4h1) / Agency (Section 7.4h2)   | - /           |
| Supplemental Information (Section 7.5a-j, inclusive, as deemed applicable)  |               |

Town of ELLINGTON CONNECTICUT MECONIC SEAL SEAL STATE OF CONNECTICUT – COUNTY OF TOLLAND INCORPORATED 1786

TOWN OF ELLINGTON

Department of Public Works 21 MAIN STREET – PO BOX 187 ELLINGTON, CONNECTICUT 06029-0187

TEL 860-870-3140 FAX 860-870-3147 www.ellington-ct.gov

# Memo

To: John Colonese, Asst. Town Planner
From: Tom Modzelewski, Director of Public Works
cc: Lisa Houlihan, Town Planner
Lori Spielman, First Selectman
Matt Reed, Town Administrator
Date: 4-15-2025
Re: Kibbe Rd State Forest Access Road Improvements

Dear John,

The Department of Public Works has been instructed by the First Selectman to improve the accessibility and condition of the abandoned State Forest road at the North end of Kibbe Rd.

The prior owner hired a company to harvest the property for quality logs and in doing so the contractor placed logs all within the abandoned roadway. Additionally, after years of no maintenance, the old roadbed has washed out and become quite rutted.

It is our goal to establish a safe, passable roadway within the area of the previous road. Additionally, we plan to install a gravel parking area for users of the facility to safely park and enjoy what the area has to offer. Please see the attached depictions of said plan and follow up with any questions or concerns.

Respectfully,

Tom Modzelewski



### Town of Ellington Inland Wetlands and Watercourses Agency Application

Application #\_\_\_\_ Date Submitted \_

| Notices associated with this application will be sent to the applicant unless otherwise requested.  | Notices associated with this application will be sent to the applicant unless otherwise requested.  |  |  |  |
|---|---|--|--|--|
| Owner's Information   | Applicant's Information (if different than owner)   |  |  |  |
| Name: Grale Construction True   | Name: Gregery J. Gale   |  |  |  |
| Mailing<br>Address: 905 ds Mill Rd  | Mailing<br>Address: P.O. Box 317  |  |  |  |
| Ellington CT Obog   | Ellheten CT 06029   |  |  |  |
| Email: Greggale 1960 cgnall. com  | Email: Greggede Prodegnair.com  |  |  |  |
| WHEN NOT REQUIRED BY LAW TO MAIL NOTICE BY USPS,<br>MAY NOTICES BE EMAILED TO YOU? Yes No   | WHEN NOT REQUIRED BY LAW TO MAIL NOTICE BY USPS,<br>MAY NOTICES BE EMAILED TO YOU? Yes No   |  |  |  |
| Primary Contact Phone #:  | Primary Contact Phone #: 860-841-5300-Grey  |  |  |  |
| Secondary Contact Phone #:  | Secondary Contact Phone #: 860-819-5655-Jm  |  |  |  |
| Owner's<br>Signature: Arcony Ade Date: 4/0/25   | Applicant's Date:   |  |  |  |
| By signing below I certify that all information submitted with this application is true<br>and accurate to the best of my knowledge, that I am aware of and understand<br>the application requirements and regulations, and acknowledge that the<br>application is to be considered complete only when all information and<br>documents required by the Agency have been submitted. Moreover, by signing<br>above I/we expressly provide written consent to the filing of the application and   | By signing below I certify that all information submitted with this application is true<br>and accurate to the best of my knowledge, that I am aware of and understand<br>the application requirements and regulations, and acknowledge that the<br>application is to be considered complete only when all information and<br>documents required by the Agency have been submitted. |  |  |  |
| access to the site by the Agency or its staff.  |   |  |  |  |
| Street Address: <u>90 Sads Mill 82</u>  |   |  |  |  |
| Assessor's Parcel Number (APN): <u>09</u> - <u>002</u> -<br>Proposed upland review area affected in square feet: <u>2</u>   |   |  |  |  |
|   |   |  |  |  |
| Proposed wetlands/watercourses affected in square feet and linear feet (as applicable):<br>Total area of wetlands/watercourses on parcel in square feet or acres: _///  |   |  |  |  |
| Public Water: Yes X No Public Sewer: Yes X No <u>If not served by public water and sewer, applicant shall make</u><br>application to North Central District Health Department (Enfield Office) if required.   |   |  |  |  |
| Is the project in a public water supply watershed area? Yes No<br>If YES, applicant is required to notify the Connecticut Water Company and Commissioner of Public Health by certified mail, return receipt<br>within 7 days of this application (Conn. Gen Stat. Sec 22a-42f). Copy of application, plans, and supporting documents must accompany<br>notice. Applicant can email the Commissioner of Public Health using their approved form. Proof of notice (return receipt and sent email)<br>must be provided to the Planning Department. |   |  |  |  |
| Describe the nature of proposed regulated activity, request for acceptance of a permitted use as of right or a nonregulated use, map or regulation amendment, or other activity requiring review by the Agency or its Agent: <u>See attached Application Checklist and Appendix D for guidance when preparing application</u>   |   |  |  |  |
| See attached Application Checklist and Appendix D for guidance whe  | a preparing application   |  |  |  |
|   | activity requiring review by the Agency of its Agent.   |  |  |  |
|   | en preparing application  |  |  |  |
|   | en preparing application  |  |  |  |
|   | en preparing application  |  |  |  |

| Applicant shall provide certification in accordance with Wetlands Regulation, Section 7.4e, Application Requirements:  |  |  |  |  |
|--|--|--|--|--|
| Whether or not any portion of the property on which the regulated activity is proposed is located within 500 feet of an adjoining town.  |  |  |  |  |
| Whether or not a significant portion of the traffic to the completed project will use streets within an adjoining town to exit or enter the site. <b>Yes No</b>  |  |  |  |  |
| Whether or not a significant portion of the sewer or water drainage from the project will flow through and significantly impact the sewer or water drainage system of an adjoining town. 🗌 Yes 🔄 No  |  |  |  |  |
| Whether water run-off from the improved site will impact streets or other municipal/private property within an adjoining town.  Yes No   |  |  |  |  |
| FOR OFFICE USE ONLY<br>If YES to any of the above, the Agency shall, in accordance with CGS 8-7d(f) notify the clerk of any adjoining<br>municipality of the pendency of any application, petition, appeal, request or plan concerning any project on any site.<br>Notice of the pendency of such application shall be made by certified mail, return receipt requested, and shall be mailed<br>within seven (7) days of the date of receipt of the application, petition, appeal, request or plan. (See Agency<br>requirements Section 8.4) |  |  |  |  |
| Type of Project: (check one)   |  |  |  |  |
| Commercial/Industrial Residential Mixed Use Timber Agricultural  |  |  |  |  |
| Commercial/IndustrialResidentialMixed UseTimberAgricultural<br>X Other, explain: <u>Eacth</u> Excausiver   |  |  |  |  |
| Type of Application: (check one)   |  |  |  |  |
| Notification for Non-Regulated Use (Section 4.2)   |  |  |  |  |
|  |  |  |  |  |
| Notification of Permitted Use as of Right (Section 4.1)          Administrative Permit (Section 6.4)   |  |  |  |  |
| Agency Permit (TWELVE COPIES REQUIRED)   |  |  |  |  |
| Permit Modification  |  |  |  |  |
| Permit Extension   |  |  |  |  |
| Regulation Amendment   |  |  |  |  |
| Map Amendment  |  |  |  |  |
| Appeal of Administrative Permit  |  |  |  |  |
| Application Submittals:  |  |  |  |  |
| Completed Application Form (Section 7.4a)  |  |  |  |  |
| Application Fee (Section 7.4b)   |  |  |  |  |
| Abutters List (Section 7.4c)   |  |  |  |  |
| Certification as to Adjacent Towns (See above)   |  |  |  |  |
| Certification as to Connecticut Water Company & Commissioner of Public Health (See above)  |  |  |  |  |
| Notification Narrative and Supporting Documentation (If applicable, Appendix D)  |  |  |  |  |
| Project Narrative and Supporting Documentation (Section 7.4g, 1-11 inclusive, as deemed applicable)  |  |  |  |  |
| Project Site Plan - circle one: Administrative (Section 7.4h1) / Agency (Section 7.4h2)  |  |  |  |  |
| Supplemental Information (Section 7.5a-j, inclusive, as deemed applicable)   |  |  |  |  |
| 7/40   |  |  |  |  |

Rev. 7/18

PS PHASE 34.6± Acres N/F Rolling Meadows, LLC LEGEND: PROP. OUTLET STRUCTURE 

 PHASE LINE

 PHASE LINE

 EDGE OF WATER

 LIMIT OF WETLAND

 PROP. STORM SEWER

 EXISTING STORM SEWER

 EXISTING STORM SEWER

 ---258--- EXISTING CONTOUR

 ---258--- EXISTING CONTOUR

 256--- PROP. CONTOUR

 256x0
 EXISTING SPOT GRADE


 256.0
 PROP. SPOT GRADE

 LIMIT OF GRADING STAKE -0 PHASE LINE STAKE PHASE CORNER STAKE STAKED HAYBALES OR SILT FENCE EROSION & SEDIMENT CONTROL PLAN KEY PS PERMANENT SEEDING GSF GEOTEXTILE SILT FENCE RR RIPRAP OP OUTLET PROTECTION TS TEMPORARY SEEDING GRAPHIC SCALE

( IN FEET )


1 inch = 40 ft.

•



二、公司

• •



### GEOTEXTILE SILT FENCE (GSF)

#### SPECIFICATIONS <u>Materials</u>

, <del>-</del>

**.** 

÷. \_

\*

Geotextile fabric: shall be a pervious sheet of polypropylene, nylon, polyester, ethylene or similar filaments and shall be certified by the manufacturer or supplier as conforming to the requirements shown in Figure GSF-1 in the Connecticut Guidelines For Soil Erosion and Sediment Control latest edition. The geotextile shall be non-rotting, acid and alkali resistant and have sufficient strength and permeability operations. Filamanets in the geotextile shall be resistant to absorption. The filament network must be dimensionally stable and free of any chemical treatment or coating that will reduce its permeability. The geotextile shall also be free of any flaws or defects which will alter its physical

properties. Torn or punctured geotextiles shall not be used. Supporting posts: shall be at least 42 inches long made of either 1.5 inch square hardwood stakes or steel posts with projections for fastening the geotextile possessing a minimum strength of 0.5 pound per linear foot.

#### Placemen

For toe of slope: Locate 5-10 feet down gradient from the toe of slope, generally on the contour with maintenance and sediment removal requirements in mind. When the contour can not be followed install the fence such that perpendicular wings are created to break the velocity of water flowing along the fence. See Figure GSF-2 in the Connecticut Guidelines For Soil Erosion and Sediment Control for spacing requirements.

Swales: Locate "U" shape across swale such that the bottom of both ends of the fence are higher that the top of the lowest section of the fence.

Catch Basin in Swale on Slopes: Locate 2 "U" shapes across swale as above: one immediately up slope from the catch basin and the other immediately down slope from the catch basin.

Catch Basins in Depressions: Encircle catch basin.

Culvert Inlets: Locate in a "U" shape approximately 6 feet from the culvert in the direction of the incoming flow.

Culvert Outlets: Locate across the swale at least 6 feet from the culvert outlet.

#### Installatio

Trench excavation: Excavate a trench a minimum of 6 inches deep and 6 inches wide on the up slope side of the fence location. For slope and swale installations, extend the ends of the trench sufficiently up slope such that bottom end of the fence will be higher than the top of the lowest portion of the fence.

When the fence is not to be installed on the contour, excavate wing trenches spaces at the intervals given on Figure GSF-2 in the Connecticut Guidelines For Soil Erosion and Sediment Control latest edition.

When excavation is obstructed by an occasional stone or tree roots, provide a smooth transition between the trench bottom and the obstruction.

Support Posts: Drive support posts on the down slope side of the trench to a depth of at least 12 inches into original ground.

Never install support posts more than 10 feet apart. Install support posts closer than 10 feet apart when concentrated flows are anticipated or when steep contributing slopes and soil conditions are expected to generate larger volumes of sediment. For catch basins in hollows, drive posts at each corner of the catch basin. Whenever the geotextile filter fabric that is used exceeds the minimum material specifications contained in this measure, the spacing of the stakes shall be per manufacturer's recommendations.

Geotextile Filter Fabric: Staple or secure the geotextile to the support posts per manufacture's instruction such that at least 6 inches of geotextile lies within the trench, the height of the fence does not exceed 30 inches and the geotextile is taut between the posts. When the trench is obstructed by stones, tree roots, etc. allow the geotextile to lay over the obstruction such that the bottom of the geotextile points up slope.

In the absence of manufacture's instructions, space wire staples on wooden stakes at a maximum of 4 inches apart and alternate their position from parallel to the axis of the stake to perpendicular.

Do not staple the geotextile to living trees.

Provide reinforcement for the fence when it can be exposed to high winds.

When joints in the geotextile fabric are necessary, splice together only at at support posts, and securely seal.

Backfill & Compaction: Backfill the trench with tamped soil or aggregate over the geotextile. When the trench is obstructed by a stone, tree root, etc. make sure the bottom of the geotextile lies horizontal on the ground with the resulting flap on the up slope side of the geotextile and bury the flap with 6 inches of tamped soil, or aggregate.

#### MAINTENANCE

Inspect the silt fence at least once a week and within 24 hours of the end of a storm with rainfall amount of 0.5 inch or greater to determine maintenance needs. When used for dewatering operations, inspect frequently before, during and after pumping operations.

Remove the sediment deposits or, if room allows, install a secondary silt fence up slope of the existing fence when sediment deposits reach approximately one half the height of the existing fence.

Replace or repair the fence within 24 hours of observed failure. Failure of the fence has occurred when sediment fails to be retained by the fence because:

- (a) the fence has been overtopped, undercut or bypassed by runoff water, (b) the fence has been moved out of position (knocked
- over), or (c) the geotextile has decomposed or been damaged.

Maintain the fence until the contributing area is stabilized.

After the contributing area is stabilized determine if sediment

contained by the fence requires removal or regrading and stabilization. If the depth is greater than or equal to 6 inches, regrading or removal of the accumulated sediment is required. No removal or regrading is required if sediment depth is less than 6 inches.

Remove the fence by pulling up the support posts and cutting the geotextile at ground level. Regrade or remove sediment as needed, and stabilize disturbed soils.

#### MULCH FOR SEED (MS)

#### SPECIFICATIONS

Types of Mulches within this specification include, but are not limited to:

1. Hay: The dried stems and leafy parts of plants cut and harvested, such as alfalfa, clovers, other forage legumes and the finer stemmed, leafy grasses. The average stem length should not be less than 4 inches. Hay that can be windblown should be anchored to hold it in place.

2. Straw: Cut and dried stems of herbaceous plants, such as wheat, barley, cereal rye, or brome. The average stem length should not be less than 4 inches. Straw that can be windblown should be anchored to hold it in place.

#### 3. Cellulose Fiber: Fiber origin is either virgin wood,

post-industrial/pre-consumer wood or post consumer wood complying with materials specification (collectively referred to as "wood fiber"), newspaper, kraft paper, cardboard (collectively referred to as "paper fiber") or a combination of wood and paper fiber. Paper fiber, in particular, shall not contain boron. which inhibits seed germination. The cellulose fiber must be manufactured in such a manner that after the addition to and agitation in slurry tanks with water, the fibers in the slurry become uniformly suspended to form a homogeneous product. Subsequent to hydraulic spraying on the around, the mulch shall allow for the absorption and percolation of moisture and shall not form a tough crust such that it interferes with seed germination or growth. Generally applied with tackifier and fertilizer. Refer to manufacturer's specifications for application rates needed to attain 80%-95% coverage without interfering with seed germination or plant growth. Not recommended as a mulch for use when seeding occurs outside of the recommended seeding dates.

Tackifiers within this specification include, but are not limited to: Water soluble materials that cause mulch particles to adhere to one another, generally consisting of either a natural vegetable aum blended with gelling and hardening agents or a blend of hydrophilic polymers, resins, viscosifiers, sticking aids and gums. Good for areas intended to be mowed. Cellulose fiber mulch may be applied as a tackifier to other mulches, provided the application is sufficient to cause the other mulches to adhere to one another. Emulsified asphalts are specifically prohibited for use as tackifiers due to their potential for causing water pollution following its application.

Nettings within this specification include, but are not limited to: Prefabricated openwork fabrics made of cellulose cords, ropes, threads, or biodegradable synthetic material that is woven, knotted or molded in such a manner that it holds mulch in place until vegetation growth is sufficient to stabilize the soil. Generally used in areas where no mowing is planned.

#### Site Preparation

Grade according to plans and allow for the use of appropriate equipment for seedbed preparation, seeding, mulch application and mulch anchoring.

Timing: Applied immediately following seeding. Some cellulose fiber may be applied with seed to assist in marking where seed has been sprayed, but expect to apply a second application of cellulose fiber to meet the requirements of Mulch For Seed in the Connecticut Guidelines For Soil Erosion and Sediment Control latest edition.

Spreading: Mulch material shall be spread uniformly by hand or machine resulting in 80%-95% coverage of the disturbed soil

when seeding within the recommended seeding dates. Applications that are uneven can result in excessive mulch smothering the germinating seeds. For hay or straw anticipate an application rate of 2 tons per acre. For cellulose fiber follow manufacture's recommended application rates to provided 80%–95% coverage.

When seeding outside the recommended seeding dates, increase mulch application rate to provide between 95%-100% coverage of the disturbed soil. For hay or straw anticipate an application rate to 2.5 to 3 tons per acre.

When spreading hay mulch by hand, divide the area to be mulched into approximately 1,000 square feet and place 1.5-2 bales of hay in each section to facilitate uniform distribution.

For cellulose fiber mulch, expect several spray passes to attain adequate coverage, to eliminate shadowing, and to avoid slippage.

Anchoring: Expect the need for mulch anchoring along the shoulders of actively traveled roads, hill tops and long open slopes not protected by wind breaks.

When using netting, the most critical aspect is to ensure that the netting maintains substantial contact with the underlying mulch and the mulch, in turn, maintains continuos contact with the soil surface. Without such contact, the material is useless and erosion can be expected to occur.

#### MAINTENANCE

Inspect mulch for seed area at least once a week and within 24 hours of the end of a storm with a rainfall amount of 0.5 inch or greater until the grass has germinated to determine maintenance needs.

#### Where mulch has been moved or where soil erosion has occurred, determine the cause of the failure and repair as

needed.

#### PERMANENT SEEDING (PS)

#### SPECIFICATIONS

\_\_\_\_\_

Time Of Year

Seeding dates in Connecticut are normally April 1 through June 15 and August 15 through October 1. Spring seedings give the best results and spring seedings of all mixes with legumes is recommended. There are two exceptions to the above dates. The first exception is when seedings will be made in the areas of Connecticut known as the Coastal Slope and the Connecticut River Valley. The Coastal Slope includes the coastal towns of New London, Middlesex, New Haven, and Fairfield counties. In these areas, with the exception of crown vetch (when crown vetch is seeded in late summer, at least 35% of the seed should be hard seed (unscarified), the final fall seeding dates can be extended and additional 15 days. The second exception is frost crack or dormant seeding, the seed is applied during the time of year when no germination can be expected, normally November through February. Germination will take place when weather conditions improve, mulching is extremely important to protect the seed from wind and surface erosion and to provide erosion protection until the seeding becomes established.

#### **PERMANENT SEEDING (Continued)**

#### Site Preparation

Grade in accordance with the Land Gradina measure which is in the Connecticut Guidelines For Soil Erosion and Sediment Control latest edition.

Install all necessary surface water controls.

For areas to be mowed remove all surface stones 2 inches or larger. Remove all other debris such as wire, cable tree roots, pieces of concrete, clods, lumps, or other unsuitable material.

Seed Selection and Quantity Select a seed mixture appropriate to the intended use and soil conditions from Figure PS-2 and Figure PS-3 in the Connecticut Guidelines For Soil Erosion and Sediment Control latest edition or use mixture recommended by the NRCS.

#### Seedbed Preparation

Apply topsoil, if necessary, in accordance with the Topsoiling measure which is in the Connecticut Guidelines For Soil Erosion and Sediment Control latest edition

Apply ground limestone and fertilizer according to soil test recommendations (such as those offered by the University of Connecticut Soil Testing Laboratory or other reliable source).

Where soil testing is not feasible on small or variable sites, or where timing is critical, fertilizer may be applied at the rate of 300 pounds per acre or 7.5 pounds per 1,000 square feet of 10-10-10 or equivalent and limestone at 4 tons per acre or 200 pounds per 1,000 square feet.

Work lime and fertilizer into the soil to a depth of 3 to 4 inches with a disc or other suitable equipment.

Inspect seedbed just before seeding. If the soil is compacted, crusted or hardened, scarify the area prior to seeding.

#### Seed Application

Apply selected seed at rates provided in Figure PS-3 (in the Connecticut Guidelines For Soil Erosion and Sediment Control latest edition) uniformly by hand, cyclone seeder, drill, cultipacker type seeder or hydroseeder (slurry including seed, fertilizer). Normal seeding depth is from 0.25 to 0.5 inch. Increase seeding rates by 10% when hydroseeding or frost crack seeding. Seed warm season grasses during the spring period only.

<u>Mulching</u> See guidelines in the Mulch For Seed measures.

#### MAINTENANCE

Inspect temporary soil protection area at least once a week and within 24 hours of the end of a storm with a rainfall amount of 0.5 inch or areater during the first growing season.

Where seed has been moved or where soil erosion has occurred, determine the cause of the failure and repair as needed.

#### DUST CONTROL (DC)

#### SPECIFICATIONS

Mechanical Sweeping

Use mechanical sweeping on paved areas where dust and fine materials accumulate as a result of truck traffic, pavement saw cutting spillage, and wind or water deposition from adjacent disturbed areas. Sweep daily in heavily traveled areas.

Periodically moisten exposed soil surfaces on unpaved travelways to keep the travelway damp.

#### Non-Asphaltic Soil Tackifier

Non-asphaltic soil tackifier consists of an emulsified liquid soil stabilizer of organic, inorganic or mineral origin, including, but not limited to the following: modified resins, calcium chloride, complex surfactant copolymers or high grade latex acrylics. The solutions shall be non-asphaltic, non toxic to human, animal and plant life, non corrosive and nonflammable. Materials used shall meet local, state and federal guidelines for intended use. All materials are to be applied according to the manufacturer's recommendations and all safety guidelines shall be followed in storing, handling and applying materials.

#### MAINTENANCE

Repeat application of dust control measures when fugitive dust becomes evident

#### TEMPORARY SEEDING (TS)

#### **SPECIFICATIONS**

Site Preparation Install needed erosion control measures such as diversions. grade stabilization structures, sedimentation basins and grassed waterways in accordance with the approved plan.

Grade according to plans and allow for the use of appropriate equipment for seedbed preparation, seeding, mulch application

#### Seedbed Preparation

and mulch anchoring.

Loosen the soil to a depth of 3-4 inches with a slightly roughened surface. If the area has been recently loosened or disturbed, no further roughening is required. Soil preparation can be accomplished by tracking with a bulldozer, discing harrowing, raking or dragging with a section of chain link fence.

Apply ground limestone and fertilizer according to soil test recommendations (such as those offered by the University of Connecticut Soil Testing Laboratory or other reliable source).

If soil testing is not feasible on small or variable sites, or where timing is critical, fertilizer may be applied at the rate of 300 pounds per acre or 7.5 pounds per 1,000 square feet of 10-10-10 or equivalent.

Apply seed uniformly by hand, cyclone seeder, drill, cultipacker type seeder or hydroseeder at a minimum rate for the selected seed identified in Figure TS-2 in the Connecticut Guidelines For Soil Erosion and Sediment Control latest edition. Increase seeding rates by 10% when hydroseeding.

<u>Mulching</u> See guidelines in the Mulch For Seed measures.

#### MAINTENANCE

Inspect temporary seeding area at least once a week and within 24 hours of the end of a storm with a rainfall amount of 0.5 inch or greater for seed and mulch movement and rill erosion.


Where seed has been moved or where soil erosion has occurred. determine the cause of the failure and repair as needed.

## SOIL ERSOION & SEDIMENT CONTROL NOTES

1. All soil erosion and sediment control work shall be done in strict accordance with the Connecticut Guidelines For Soil Erosion and Sediment Control latest edition.

- 2. Any additional erosion/sediment control deemed necessary by the Engineer during construction, shall be installed by the developer. In addition, the developer shall be responsible for the repair/replacement and/or maintenance of all erosion control measures until all disturbed areas are stabilized to the satisfaction of the town staff.
- 3. All soil erosion and sediment control operations shall be in place prior to any grading operations and installation of proposed structures or utilities and shall be left in place until construction is completed and/or area is stabilized.
- 4. Unless already paved, all entrances to the project site are to be protected by construction entrance (CE) pads, conforming to the Connecticut Guidelines For Erosion and Sediment Control latest edition. Stone shall conform to Ct. D.O.T. Form 814A, latest edition, M.O1.O1 No. 4 stone. The CE pad is to be maintained at all times during the construction period.
- 5. In all areas, removal of trees, bushes and other vegetation as well as disturbance of the soil is to be kept to an absolute minimum while allowing proper development of the site. During construction, expose as small an area of soil as possible for as short a time as possible.
- 6. Topsoil is to be stripped and stockpiled in amounts necessary to complete finished grading of all exposed areas requiring topsoil. The stockpiled topsoil is to be located as designated on the plans and ringed with hay bale barrier or geotextile silt fence. The stockpiled topsoil shall be temporarily seeded if it is to remain more than 30 days. Topsoil shall not be placed while in a frozen or muddy condition, when the subgrade is excessively wet, or in a condition that may otherwise be detrimental to proper grading or proposed sodding or seeding.


7. There is to be no stockpiling of soil within a ten foot limit of adjoining properties. Any and all fill material is to be free of brush, rubbish, timber, logs vegetative matter and stumps in amounts that will be detrimental to constructing stable fills. Maximum side slopes of exposed surfaces of earth to be 3:1 or as otherwise specified by local authorities.



PLAN VIEW

## SOURCE: U.S. DEPARTMENT OF AGRICULTURE, SOIL CONSERVATION SERVICE, STORRS, CONNECTICUT SEDIMENTATION BARRIER (SILT FENCE) DETAIL


NOT TO SCALE





WRAP SIDES OF RISER PIPE OR EQUAL







TEE CONECTION

FL=202.00

18" MIN.





1 inch = 100 ft.

-----



STATE OF CONNECTICUT – COUNTY OF TOLLAND INCORPORATED 1786

TOWN OF ELLINGTON 55 MAIN STREET – PO BOX 187 ELLINGTON, CONNECTICUT 06029-0187 www.ellington-ct.gov

TEL. (860) 870-3120 TOWN PLANNER'S OFFICE FAX (860) 870-3122

#### INLAND WETLANDS AGENCY REGULAR MEETING MINUTES MONDAY, MARCH 17, 2025, 7:00 P.M.

#### IN PERSON ATTENDANCE: TOWN HALL ANNEX, 57 MAIN STREET REMOTE ATTENDANCE: ZOOM MEETING (ATTENDEES BELOW WERE IN PERSON UNLESS OTHERWISE NOTED)

- **PRESENT:** Chairman Jean Burns (via Zoom), Vice Chairman Katherine Heminway, Regular members Ken Braga, Landon Barlow (via Zoom, left meeting at 7:44 pm), and Alternate Subhra Roy
- **ABSENT:** Regular members Steve Hoffman, Hocine Baouche, and Jon Kaczmarek

#### STAFF

- **PRESENT:** John Colonese, Assistant Town Planner/Wetland Enforcement Officer and Barbra Galovich, Recording Clerk (via Zoom)
- I. CALL TO ORDER: Chairman Jean Burns called the Ellington Inland Wetlands Agency meeting to order at 7:00 pm.

Chairman Jean Burns introduced Subhra Roy as a new member of the commission. Subhra mentioned serving on the Zoning Board of Appeals for the past 4 years and is looking forward to serving on the Inland Wetland Agency.

II. PUBLIC COMMENTS (on non-agenda items): None

#### **III. PUBLIC HEARINGS:**

 IW202502 – Stephen D. Williams, owner/applicant request for a permit to conduct regulated activity to construct a single-family home and associated improvements at 37 Wendell Road, APN 168-019-0000.

**Time:** 7:04 pm **Seated:** Burns, Heminway, Braga, Barlow and Roy

Stephen Williams, 22 Rudnansky Lane, Tolland, CT, Mark Peterson, Gardner & Peterson Assoc, LLC, 178 Hartford Turnpike, Tolland, CT, George Logan, REMA Ecological Services, LLC, 43 Blue Ridge Drive, Vernon, CT, George and Michael Schober, Schober & Schober, PC, 139 Hazard Ave, Bldg. 2, Suite 7, Enfield, CT were present to represent the application.

Attorney George Schober submitted August 12, 2024, and September 23, 2024, Inland Wetland Agency meeting minutes, the Improvement Location Survey map last revision of 9-13-2024, and the denial letter dated October 1, 2024, for the record. Attorney Schober introduced Mark Peterson who will review the changes to the plan since the denial.

Mark Peterson explained the parcel is located on the corner of Wendell Road and Pine Street in a residential zone. Mark stated a topography and boundary survey has been completed, showing the wetlands delineations provided by George Logan, and existing drainage, which runs north to south on the parcel. Mark showed the proposed location of the house, the driveway, proposed well, sewer, and utilities on the map. The owner received well location approval from the North Central District Health Department (NCDHD) and will work with the Water Pollution Control Authority for the sewer installation. Mark showed the location of the proposed stockpile area, haybales, and silt fence, and the anti-tracking pad during the construction phase and noted the seeding schedule is on page 2 of the plan set. Mark stated there is zero disturbance to the wetlands, and 3,470 sf of disturbance is proposed within the 100' upland review area.

George Logan noted the field delineations were performed in 2024, and the wetland soil types are poorly drained. George showed the flagged wetland area and noted that functions and values are limited. George stated there is a 40-foot in length intermittent watercourse that crosses the southern corner of the site, originating at a culvert under Wendell Road and flowing to a culvert under Pine Street. George stated the silt fence and haybales are to be installed to protect the wetlands during construction for double protection. George stated the hydrology of the wetlands will be maintained and in his professional opinion the proposed activity does not have an adverse impact on the water quality.

Commissioner Braga asked about landscaping between the house and the flagged wetlands, Stephen Williams noted there will be grass seed planted within the area. Commissioner Heminway asked about applying wetlands seed, George Logan noted any exposed dirt would be grass seed. Commissioner Barlow asked if the any mitigation and removal of the Japanese Knotweed was part of this application and George responded that it was not.

David Fredericks, 13 Pine Street, asked if a basement would be part of the dwelling, stating there is ledge on the parcel. David explained there is ledge and blasting that has occurred within the neighborhood, and noted a gravity fed well upstream of the property. Mark Peterson noted there is a proposed well and the dwelling will have a crawl space rather than a basement with minimal excavation. Mark showed the proposed grading of the site. David asked again about the gravity fed well. George Logan stated if there is a gravity fed well upstream it would be offsite and would have no effect on 37 Wendell Road as the water will continue to flow as it does.

Maura Freckleton, 33 Pine Street, mentioned North Central District Health Department's plan approval for the well location approved on March 10, 2025. Maura's concern is the 75' radius from the proposed sewer to her well. Mark Peterson spoke with the North Central District Health Department (NCDHD) and verified the separation distances to the well are sufficient and noted the sewer pump will be in a sealed concrete pit. Chairman Burns stated that NCDHD approval has six conditions noted.

Dave Freckleton, 33 Pine Street asked about the well setback from the road. John Colonese explained that the NCDHD approval was present and questions regarding well setbacks should be directed to the health department. George Logan explained that the hydrology of the well is separate from the wetlands.

Maura Freckleton, 33 Pine Street, noted concerns regarding building setback requirements. John Colonese stated that should the wetlands permit be approved; the Zoning Board of Approvals will need to approve a variance for the proposed building setbacks that do not comply with regulations or prior variance.

Vice Chairman Heminway stated more support for approval of the application now that all activity on the site would be outside of the wetland delineations. John Colonese reviewed the possible conditions of approval with the agency and application. Vice Chairman Heminway requested that the haybales be extended along the proposed silt fence between the well and the wetlands. Chairman Burns requested the NCDHD approval to be added to the conditions.

# MOVED (BRAGA) SECONDED (HEMINWAY) AND PASSED UNANIMOUSLY TO MAKE DETERMINATION OF A NON-SIGNIFICANT ACTIVITY FOR IW202502.

Stephen Williams noted his parents purchased the parcel over 72 years ago and would like to do something with the property besides paying taxes.

**MOVED (BRAGA) SECONDED (HEWINWAY) AND PASSED UNANIMOUSLY TO CLOSE THE PUBLIC HEARING FOR IW202502** – Stephen D. Williams, owner/applicant request for a permit to conduct regulated activity to construct a single-family home and associated improvements at 37 Wendell Road, APN 168-019-0000.

**MOVE (HEMINWAY) SECONDED (BRAGA) AND PASSED UNANIMOUSLY TO APPROVE WITH CONDITIONS FOR IW202502** – Stephen D. Williams, owner/applicant request for a permit to conduct regulated activity to construct a single-family home and associated improvements at 37 Wendell Road, APN 168-019-0000.

#### Conditions of approval:

- 1. Haybales shall be extended to the west behind the proposed silt fence line.
- 2. Proposed silt fence and haybales shall be staked by a licensed land surveyor prior to activity.
- 3. Erosion control measures shall be installed then inspected by the wetland agent prior to construction of the site and remain operational until the site is stabilized.
- 4. A split-rail fence shall be installed prior to the issuance of a Certificate of Occupancy along the proposed haybale line as shown on the plan submitted with the application described as Improvement Location Survey Permit Plan dated 02-23-1996 revised through 02-01-2025 by Gardner & Peterson Associates LLC. Ellington Inland Wetlands placards shall be securely attached to the fence posts in three locations evenly spaced and facing the house.
- 5. North Central District Health Department well location plan approval dated March 10, 2025.

#### IV. OLD BUSINESS: None

#### V. NEW BUSINESS:

 MOVED (HEMINWAY) SECONDED (ROY) AND PASSED (BRAGA OPPOSED) TO ADD TO THE AGENDA A REQUEST FOR A MODIFICATION TO PERMIT IW202419 – Abdulsalam Alsaleh and Zak Smith, owner/ Calito Development Group, LLC, applicant, request for a permit to conduct regulated activity to construct a driveway crossing, parking lot, wetlands mitigation area, stormwater basin, and associated site improvements for a retail store on property to be subdivided on the west side of West Road across the street from 175 West Road. Property identified as Assessor Parcel Number 046-003-0002.

Jim Cassidy, PE, Hallisey, Pearson & Cassidy Engineering Associates, Inc., 630 Main Street, Cromwell, CT stated the Inland Wetland Agency granted a Wetlands permit on November 18, 2024. Since the approval, Jim has been working with the Connecticut Department of Transportation (CT DOT) for the last few months to obtain approval for the proposed site improvements. The CT DOT has concerns pertaining to the proposed detention basin along West Road and requested a revised plan to review. Jim shared the revised site plan, and the changes made to accommodate the CT DOT concerns. After a brief roundtable discussion, the Agency advised Jim Cassidy to attend the next meeting under New Business agenda item. MOVED (HEMINWAY) SECONDED (ROY) AND PASSED UNANIMOUSLY TO ADD UNDER NEW BUSINESS FOR MONDAY, APRIL 21, 2025, 7PM, TOWN HALL ANNEX, 57 MAIN STREET, ELLINGTON, AND ZOOM VIDEO CONFERENCING A REQUEST FOR A MODIFICATION TO PERMIT IW202419 – Abdulsalam Alsaleh and Zak Smith, owner/ Calito Development Group, LLC, applicant, request for a permit to conduct regulated activity to construct a driveway crossing, parking lot, wetlands mitigation area, stormwater basin, and associated site improvements for a retail store on property to be subdivided on the west side of West Road across the street from 175 West Road. Property identified as Assessor Parcel Number 046-003-0002.

#### VI. ADMINISTRATIVE BUSINESS:

1. Approval of February 10, 2025, Regular Meeting Minutes.

MOVED (BRAGA) SECONDED (HEMINWAY) (ROY - ABSTAINED) AND PASSED TO APPROVE FEBRUARY 10, 2025, REGULAR MEETING MINUTES AS WRITTEN.

2. Election of Officers

BY CONSENSUS, THE AGENCY TABLED ELECTION OF OFFICERS TO THE NEXT INLAND WETLAND AGENCY MEETING TO BE HELD ON MONDAY, APRIL 21, 2025, 7PM, TOWN HALL ANNEX, 57 MAIN STREET, ELLINGTON, AND ZOOM VIDEO CONFERENCING.

- 3. Correspondence/Discussion:
  - a. CT DEEP Municipal Inland Wetlands Agency Comprehensive Training Program.
  - b. North Central Conservation District Spring 2025 Plant & Seedling Sale.
  - c. Notice of Ellington Public Budget Presentations Community Voice Channel on March 20, 2025, Senior Center and Virtual Zoom Meeting on May 1, 2025, and Hall Memorial Library and Virtual Zoom Meeting on May 3, 2025.

#### VII. ADJOURNMENT:

# MOVED (BRAGA) SECONDED (HEMINWAY) TO ADJOURN THE MARCH 17, 2025, REGULAR MEETING OF THE INLAND WETLANDS AGENCY AT 8:03 PM.

Respectfully submitted,

Barbra Galovich, Recording Clerk