

ADDENDUM #1

To BID #25027

Playground Equipment Repairs and Surfacing Replacements Project

May 5, 2025

TO: ALL PROSPECTIVE BIDDERS
FROM: Travis Unified School District

RE: Addendum #1

This Addendum forms a part of the Contract Documents and modifies the original Bidding Documents as noted below.

Attachment A: Project Scope

Cambridge Elementary:

- c. Install new turf **TenCate, Diamond Pro fescue (1.875 inch pile)** surfacing, **or equivalent**, per manufacturer's specifications and must meet all fall height absorption criteria.
- d. ~~Remove existing shade sails and replace with metal cheer roof. Parts provided by the District.~~
- e. **Provide Alternate quote for:**
 - a. **Remove curbing on two sides.**
 - b. **Remove asphalt pathway along the West side of the play structure and replace with new AC, 2" thick. Subsurface shall be brought to make level with new turf with header boards on both sides.**

Center Elementary:

Upper Grade Playground Structure (B)

- c. Install new turf **TenCate, Diamond Pro fescue (1.875 inch pile)** surfacing, **or equivalent**, per manufacturer's specifications and must meet all fall height absorption criteria.

Upper Grade Playground Structure (C)

- c. Install new turf **TenCate, Diamond Pro fescue (1.875 inch pile)** surfacing, **or equivalent**, per manufacturer's specifications and must meet all fall height absorption criteria.