

**ADDENDUM #1**  
**To BID #25028**  
**TUSD Schools Painting Project**

May 20, 2025

TO: ALL PROSPECTIVE BIDDERS  
FROM: Travis Unified School District

**RE: Addendum #1**

*This Addendum forms a part of the Contract Documents and modifies the original Bidding Documents as noted below.*

**Notice to bidders:**

8. To bid on this Project, the Bidder is required to possess one or more of the following State of California contractors' license(s):

**A (General Engineering), B (General Contractor), or C-33 (Painting and Decorating Contractor).** The Bidder's license(s) must remain active and in good standing throughout the term of the Contract.

**NOTE: a Class A or B license is required for Cambridge Elementary.**

**Attachment A, Project Scope:**

**All School Locations:**

- ~~5. Primer and finish coat on stucco and wood shall be an elastomeric Paint or equivalent.~~
- ~~6. Body color of buildings shall be a low sheen paint.~~
- ~~7. Trim shall be a semi-gloss.~~

**4.1 Paint specifications shall be a Sherwin-Williams brand and as follows:**

**a. T1-11 Walls**

- **Primer - LXN C&M Primer WH, LX02W0050**
- **Topcoat – Duration Coating Exterior Latex Satin, K33W00251**

**b. Steel/Ferrous Metal for doors, door casings, and handrails**

- **Pro Industrial DTM Acrylic Semi-Gloss, B66W01151**

**c. Stucco/Wood**

- **Primer - LXN C&M Primer WH, LX02W0050**
- **Topcoat – Duration Coating Exterior Latex Satin, K33W00251**

**i. Wood Trim shall be in a semi-gloss finish**

**d. Wood classroom doors**

- **Waterbased Alkyd Urethane, B53W02053**

**4.2 All coats applied shall be back rolled.**

**7.1 The face of the doors and casings shall be painted only.**

**Cambridge Elementary School:**

2. Remove and replace T1-11 siding, Facia and trim boards on 5 lower sides (highlighted in picture below) and all upper sides of the main building, and remove and replace T1-11 on all upper sides. Dry rot facia on upper sides shall be replaced on a T&M basis, approved by the District.
6. Prep, scrape, and prime new and existing siding, skirting, overhangs, fascia trims, window and door trims, railings (around Bldg. B only), and gutters and down spouts for a smooth painting finish surface.

**9.1 Conduits and boxes shall be prepped and painted to match site color scheme.**

**Foxboro Elementary School:**

1. Pressure wash All building structures including overhead walkways, fences (excluding black wrought iron fence at the back of the school), block walls, and skylights.
3. Prep, scrape, and prime any new and existing siding, skirting, overhangs, fascia trims, window and door trims, fences (excluding black wrought iron fence at the back of the school), block walls, and gutters and down spouts for a smooth painting finish surface. Portables D1 through D8 will be primed and ready for paint after siding replacement. 6 portables will require prep, prime and paint.
6. All window/door trim (exterior only), railings, ramps, skylight trim shall be painted.

**Golden West Middle School:**

1. Pressure wash all building structures including overhangs, 8 alcoves and 3 courtyards in Bldg.'s A and B. Exclude Bldg. to be demoed. See photo reference below.
3. Apply one coat of primer to all buildings including excluding non-painted brick surfaces. Brick surfaces that were previously painted, will be primed and painted.
4. Apply two coats of finish color to body, trim, facia, gutters and down spouts. (Body color and trim colors to be determined by the District). Also includes 8 alcoves and 3 courtyards in Bldg.'s A and B. Exclude Bldg. to be demoed. See photo reference below.
6. Provide an alternate quote to prep and paint 4 connex boxes.



**ADDENDUM #1**  
**To BID #25028**  
**TUSD Schools Painting Project**

May 20, 2025

TO: ALL PROSPECTIVE BIDDERS  
FROM: Travis Unified School District

**RE: Addendum #1**

*This Addendum forms a part of the Contract Documents and modifies the original Bidding Documents as noted below.*

**Notice to bidders:**

8. To bid on this Project, the Bidder is required to possess one or more of the following State of California contractors' license(s):

**A (General Engineering), B (General Contractor), or C-33 (Painting and Decorating Contractor).** The Bidder's license(s) must remain active and in good standing throughout the term of the Contract.

**NOTE: a Class A or B license is required for Cambridge Elementary.**

**Attachment A, Project Scope:**

**All School Locations:**

- ~~5. Primer and finish coat on stucco and wood shall be an elastomeric Paint or equivalent.~~
- ~~6. Body color of buildings shall be a low sheen paint.~~
- ~~7. Trim shall be a semi-gloss.~~

**4.1 Paint specifications shall be a Sherwin-Williams brand and as follows:**

**a. T1-11 Walls**

- **Primer - LXN C&M Primer WH, LX02W0050**
- **Topcoat – Duration Coating Exterior Latex Satin, K33W00251**

**b. Steel/Ferrous Metal for doors, door casings, and handrails**

- **Pro Industrial DTM Acrylic Semi-Gloss, B66W01151**

**c. Stucco/Wood**

- **Primer - LXN C&M Primer WH, LX02W0050**
- **Topcoat – Duration Coating Exterior Latex Satin, K33W00251**

**i. Wood Trim shall be in a semi-gloss finish**

**d. Wood classroom doors**

- **Waterbased Alkyd Urethane, B53W02053**

**4.2 All coats applied shall be back rolled.**

**7.1 The face of the doors and casings shall be painted only.**

**Cambridge Elementary School:**

2. Remove and replace T1-11 siding, Facia and trim boards on 5 lower sides (highlighted in picture below) **and all upper sides of the main building, and remove and replace T1-11 on all upper sides. Dry rot facia on upper sides shall be replaced on a T&M basis, approved by the District.**
6. Prep, scrape, and prime new and existing siding, skirting, overhangs, fascia trims, window and door trims, **railings (around Bldg. B only)**, and gutters and down spouts for a smooth painting finish surface.

**9.1 Conduits and boxes shall be prepped and painted to match site color scheme.**

**Foxboro Elementary School:**

1. Pressure wash All building structures including overhead walkways, **fences (excluding black wrought iron fence at the back of the school), block walls**, and skylights.
3. Prep, scrape, and prime any new and existing siding, skirting, overhangs, fascia trims, window and door trims, **fences (excluding black wrought iron fence at the back of the school), block walls**, and gutters and down spouts for a smooth painting finish surface. Portables D1 through D8 will be primed and ready for paint after siding replacement. **6 portables will require prep, prime and paint.**
6. All window/door trim **(exterior only)**, railings, ramps, skylight trim shall be painted.

**Golden West Middle School:**

1. Pressure wash all building structures including overhangs, **8 alcoves and 3 courtyards in Bldg.'s A and B. Exclude Bldg. to be demoed. See photo reference below.**
3. Apply one coat of primer to all buildings ~~including~~ **excluding non-painted** brick surfaces. **Brick surfaces that were previously painted, will be primed and painted.**
4. Apply two coats of finish color to body, trim, facia, gutters and down spouts. (Body color and trim colors to be determined by the District). **Also includes 8 alcoves and 3 courtyards in Bldg.'s A and B. Exclude Bldg. to be demoed. See photo reference below.**
6. **Provide an alternate quote to prep and paint 4 connex boxes.**

