Video Intercom, Cabling and Installation
Project No 25.2
Exhibit A - Scope of Work

Objective: Install 1 network cable from nearest IDF to location at front of school. Install a 101Voice Intercom system at the front entrance.

Locations: 33 sites total

Burbank	222 Burbank St., 94541
East Avenue *	2424 East Ave., 94542
Eden Gardens	2184 Thayer Ave., 94545
Eldridge *	26825 Eldridge Ave., 94544
Fairview	23515 Maud Ave., 94541
Faith Ringgold (K-8)	1570 Ward St., 94541
Glassbrook	975 Schafer Rd., 94544
Harder	352 Harder Rd., 94544
Longwood	850 Longwood Ave., 94541
Lorin Eden	27790 Portsmouth Ave., 94545
Palma Ceia	27679 Melbourne Ave., 94545
Park *	411 Larchmont St., 94544
Ruus	28027 Dickens Ave., 94544
Schafer Park	26268 Flamingo Ave., 94544
Southgate	26601 Calaroga Ave., 94545
Stonebrae	28761 Hayward Blvd, 94542
Treeview	30565 Treeview St., 94544
Tyrrell	27000 Tyrrell Ave., 94544
Bret Harte	1047 E St., 94541
Cesar Chavez	27845 Whitman St., 94544
M.L. King Jr	26890 Holly Hill Ave., 94545
Ochoa	2121 Depot Rd., 94545
Winton	119 Winton Ave., 94544

Brenkwitz	22100 Princeton St (A) 94541
Hayward Adult School	22100 Princeton St (A) 94541
Hayward High	1633 East Ave., 94541
Mt. Eden	2300 Panama St., 94545
Tennyson	27035 Whitman St., 94544
HUB	4823 Soto Rd, 94544
District Office	24411 Amador St.
Maintenance Yard	24400 Amador St.
Helen Turner	23640 Reed Way
Performing Arts Center	2390 Panama St

Scope of work:

Cabling:

- 1 CAT6A cable shall be run from the nearest IDF to the front entrance location identified by the school site.
- All cabling shall either be above ceiling, in raceway, or in conduit.
- All exterior conduit shall be waterproof, sealed at all connection and penetration locations.
- Cabling shall adhere to district standards:
    - Panduit CAT6A
    - Panduit jacks and plugs
    - All work shall be done by a Panduit certified installer for warranty compliance
    - Follow all standards in Exhibit D HUSD network standards documentation
    - Adhere to Exhibit C HUSD network specifications
- Fluke test results shall be submitted and approved by HUSD

Video Intercom device

- 101Voice intercom is provided by HUSD
- Contractor shall install device at the front entrance location
- Ensure that all connections are waterproof
- Device mounting shall be done to protect against vandalism.
- Device shall be programmed using connection information provided by HUSD
- Final testing shall be done to ensure a video connection to at least 1 office phone.

Pre-Bid Conference & Job Walks

Please note: We will meet both days at the Hayward Unified School District's office, 24411 Amador St Hayward, Ca 94544 and attend sites as needed.

Day 1 **May 28, 2025 9:00 a.m.**	**Day 2** **May 29, 2025 9:00 a.m.**
DO / M&O Yard	Eden Gardens
Winton	Longwood
Burbank	Ochoa
Brenkwitz / HAS	Helen Turner
Bret Harte	Ochoa
East Ave	Helen Turner
Hayward HS	Harder
Stonebrae	Cesar Chavez
Fairview	Tennyson HS
Faith Ringgold	Mt. Eden HS
Park	PAC
Eldridge	ML King
Southgate	Palma Ceia
Schafer Park	Lorin Eden
Glassbrook	HUB
Tyrrell	