Marshall MS Beaumont ISD Snack Bar Replacement

Whenever product(s) and/or material(s) are referred by BISD in this solicitation by describing a proprietary product or by using the name of a manufacturer or brand name, the term “or equal” if not inserted shall be implied, as applicable.

Delivery & Installation:
Shall be coordinated with the Beaumont ISD Director of Child Nutrition, Mary Ellen Vivrett. Delivery and installation arrangements will be made after the Beaumont ISD Board of Trustees makes an award and the awarded vendor is notified.

ITEM # **1**
DESCRIPTION: **CUSTOM SERVING COUNTER**
QTY REQUIRED: **1**
MANUFACTURER: **COUNTERCRAFT (or equal)**
MODEL # **SCOL-192**

- One (1) CounterCraft (UL certified) fully enclosed base counter with enclosed shelving compartments at operator’s side.
- Custom stainless-steel rear apron for mounting equipment control panels (drop-in equipment).
- All equipment controls to be Touchscreen digital controls powered by Duke Sous Chef Technology. Controls to include Wi-Fi and Bluetooth Mesh connectivity. All compatible appliances controllable from the touchscreen and/or the Duke Mobile application.
  Counter Finishes:
- Countertop to be 14-gauge stainless-steel with #8 high polished edges, 2" turndown at all free sides.34" a.f.f at hot food and cashier, 32" a.f.f. everywhere else.
- Trayslide to be 2CM engineered stone (similar to Silestone) eased edge at all free sides, no turn down. 32" a.f.f.
- Counter front to have decorative 3form panels with LED backlighting. Panels to be flush and recessed in counter front with 1" s/s counter body revels between panels. Color to be confirmed by district.
  Counter Configuration:
- LED backlighting included.
- Counter to provide faux wall and proper receptacle for KEC provided milk cooler. KEC to provide approved factory cut sheet to CounterCraft for accommodations. Refer to drawings for location.
- Counter body to be constructed using fully welded 1.5" x 1.5" x 1/8" galvanized angle iron. All internal welds to be ground smooth and sprayed with silver enamel paint.
- All cut-outs to be completely framed below with angle iron to properly support drop-in equipment.
- Apply 1/2" sound deadening tape to top of angle iron frame between countertop.
- Counter body frame to be fully housed in #304 stainless-steel.
- All visible stainless to be fully re-grained for a consistent appearance. All stainless turn downs to be radius.
  Quotation for Marshall MS - Snack Bar - Beaumont ISD
  Item # Qty Price each Price Total Description
- Provide s/s perforated removable panels at condensers at operator's side.
- All rear shelving compartments to have coved corners.
- One (1) UL Listed load center compartments with wiring diagram.
- All counter electrical to be interconnected to load center.
- Electrical to be located in electrical flex conduit.
- All electrical wiring to be numbered at all junctions, per circuit.
  Included Equipment:
- One (1) each CounterCraft Food Guard, Model HFOVS-2 with LED lights only
- Three (3) each 2pan recessed HotFrost top and 1pan HotFrost Shelf, Duke model DE-RHF1-SL-HF01SL
- One (1) Cashier Stations with locking utility drawers. Below cashier station to be fully enclosed.

Marshall MS Beaumont ISD Snack Bar Replacement

- Counter to rest on 6" adjustable bullet feet and have a self-leveling s/s customer facing kick plate.
  ***EXCLUDES, Milk cooler ***

Guide Rails

- 1 5/8" O.D. tubular guide rails with 1 5/8" uprights set in sleeves set in concrete at maximum 48" on center
- Top of rails to be at 32" A.F.F. and shall be continuous. Intermediate legs stop at bottom of upper rail
- CounterCraft will core holes for posts.

ITEM # **2**
DESCRIPTION: **DISPLAY CASE, MILK**
QTY REQUIRED: **1**
MANUFACTURER: **RPI INDUSTRIES (or equal)**
MODEL # **SCAS36R-III MC PEC**

Modified Olympus III Air Screen Milk Case, 36" L x 91" H, self-contained top mounted refrigeration, top canopy LED light, (3) 3/8" tempered glass shelves with T5 LED lights, removable stainless steel deck, plexi rear interior panel, brushed stainless steel interior ends, roll-down locking security cover, heated Glass Vision end panels, lockable hinged rear see-through heated doors, adjustable stainless steel legs, 1/2 hp, cETLus, ETL-Sanitation, NSF

1 ea	NOTE: Some options may change electrical requirements
1 ea	NOTE: Minimum door clearance for this unit is 36"
1 ea	1 year parts & labor warranty
1 ea	Self-contained refrigeration, standard
1 ea	5 year compressor warranty (for self-contained units only)
1 ea	115v/60/1-ph, 12.9 amps, NEMA 5-20P, 8 ft cord
1 ea	Exterior Finish: Stainless steel with stainless steel air grill
1 ea	#4 Stainless steel
1 ea	Master on/off switch to be located on the operator side.
1 ea	Model EVAP PAN Modified to include: - Evap pan, condensate pump, and rear stainless steel chase. - The evap pan requires a separate 115V circuit (NEMA 5-15) in addition to the 115V circuit required for the case (NEMA 5-20).

ITEM # **3**
DESCRIPTION: **REACH-IN HEATED CABINET**
QTY REQUIRED: **1**
MANUFACTURER: **TRAULSEN (or equal)**
MODEL # **RHF232W-HHS**

Spec-Line Heated Cabinet, Reach-in, two-section, stainless steel exterior and interior, standard depth cabinet, half-height doors, with EZ-Clean Gaskets, with microprocessor controls, cETLus, ETL-Sanitation, ENERGY STAR®

1 ea	6-year parts & labor, standard. Visit www.traulsen.com for details
1 ea	208/115v/60/1-ph, 15.5 amps, standard
1 ea	Door hinging to be determined
26 ea	Universal tray slide - per pair
6 ea	Credit for standard coated shelf, deduct
1 st	Casters, 6" high (set of 4)
	M/F: Snack Bar

Marshall MS Beaumont ISD Snack Bar Replacement

ITEM # **4**
DESCRIPTION: **REACH-IN REFRIGERATOR**
QTY REQUIRED: **1**
MANUFACTURER: **TRAULSEN (or equal)**
MODEL # **RHT232WUT-HHS**

Spec-Line Refrigerator, Reach-in, two-section, 51.6 cu. ft., self-contained refrigeration, StayClear™ Condenser, variable speed compressor, stainless steel exterior and interior, standard depth, wide half-height door or doors with EZ-Clean Gaskets, (3) adjustable wire shelves per section, microprocessor controls, 6" adjustable stainless steel legs,R-290 Hydrocarbon refrigerant, 1/2 HP, cETLus, ETL-Sanitation, ENERGY STAR®

1 ea	6-year parts & labor and 7 year compressor, standard. Visit www.traulsen.com for details
1 ea	115v/60/1-ph, 8.2 amps, cord with NEMA 5-15P, standard
1 ea	Standard refrigerant, standard
1 ea	Door hinging to be determined
26 ea	Universal tray slide - per pair
6 ea	Credit for standard coated shelf, deduct
1 st	Casters, 6" high (set of 4)
	M/F: Snack Bar

ITEM # **5**
DESCRIPTION: **TURN KEY INSTALLATION**
QTY REQUIRED: **1**
MANUFACTURER: **PROKITCHEN INSTALLATIONS (or equal)**
MODEL # **INSTALLATION**

Full Turn Installation:
- Factory approved / authorized installation of serving line in compliance with local municipal code and guidelines.
- All work to be performed during normal business hours.
- Disconnect existing utilities from the serving line.
- Remove and dispose of existing serving line off site.
- Electrical modifications to accommodate new serving line load center.
- Receive, deliver and install new serving line per manufacture specifications.
- Start up and functional test new serving line and all equipment.
- Rep to perform operator training to Beaumont ISD staff