

BID # V24251169B – MADISON MIDDLE SCHOOL FUEL MANAGEMENT

ADDENDUM No. 1: *The following is issued to supplement or revise the Contract Documents. The revisions to the documents are described below. Unless specifically changed by this addendum, the remainder of the drawings, documents, specifications, and bid date/time shall remain in effect as originally issued.*

RFIs:

Q1: The project involves significant tree removal, but currently only a C-27 license is listed as a requirement. Could you please confirm whether a D-49 or C-49 classification will also be required to perform the tree work portion of the project?

A1: Yes

Q2: Will this work be registered with the DIR and require certified payroll records to be submitted to the state?

Q2: Yes

Additional information:

1. There is existing irrigation in the areas where work will be performed. Contractors are expected to avoid damaging the irrigation systems. If any damage occurs, it must be clearly marked and documented.
2. Contractors are not allowed to chip onto the current landscape or pile tailings onto existing plants. All mulch or wood chips must be applied to bare areas only, with a maximum depth of three inches. Any excess material must be removed from the site and disposed of properly.
3. Soil removed from the brow ditches may be placed alongside the existing ditch, but it must be graded out evenly to create a smooth surface. Piling soil along the ditch is not permitted.
4. Any damage to the concrete ditch must be repaired by the contractor.
5. Contractors will be responsible for the removal and repair of any fencing required to complete the project. If removal of fencing results in the campus being unsecured, temporary fencing must be provided and installed by the contractor for the duration of the project.