Scope of Work – Classroom

A. Classroom

1. Mechanical –
    a. Provide mobile eye wash station.
2. Electrical –
    a. Provide new LED lighting.
        i. 4000k, 70CRI min, and provide 50FC avg at desk level
        ii. Provide diming control.
    b. Provide new 120V, 20A duplex receptacles
    c. Provide load calculations for new equipment.

B. Garage

1. Architectural –
    a. Cap all hydraulic stations.
        i. Remove and dispose of oil.
        ii. Remove existing Tire stoppers in the garage. (? Confirm with Mark)
2. Electrical –
    a. Provide new LED lighting.
        i. 4000k, 70CRI min, and provide 50FC avg at floor level
        ii. Provide dimming control.
    b. Provide new 120V, 20A duplex receptacles
    c. Provide load calculations for new equipment.