



April 1, 2021

Joe Crelier, Director–Risk Management
Portland Public Schools
501 N Dixon Street
Portland, Oregon

Via email: jcrelier@pps.net

Regarding: COVID Response Indoor Air Quality Testing Report
Chapman K–5 School
1445 NW 26th Avenue
Portland, Oregon
PBS Project 25000.138

Dear Mr. Crelier:

On March 19, 2021, PBS Engineering and Environmental Inc. (PBS) performed indoor air quality testing in Chapman K–5 School located at the address above. These services were provided to Portland Public Schools (District) to measure air quality parameters before schools and district-owned buildings are opened again for reoccupancy.

As part of these indoor air quality testing services, PBS measured carbon monoxide (CO), carbon dioxide (CO₂), temperature in degrees Fahrenheit (°F), relative humidity (%RH), and airborne particulate (PM2.5 and PM10). Additionally, PBS reviewed and inventoried accessible components of the test rooms' heating, ventilation, and air conditioning (HVAC) systems

Based on PBS' findings, there is no indication that a significant or measurable indoor air quality concern exists in the building. The results of the testing and assessment indicates that indoor air quality in the building is good and that the building is acceptable for occupancy.

While PBS observed no measurable indoor air quality concerns in any of the rooms that were tested, PBS did not test every occupiable room in each building. This investigation has been performed in concert with a concerted effort on the part of the District to perform regular inspections and repair of all HVAC mechanical systems throughout the District. Additionally, it is the District's policy that rooms without adequate ventilation will not be utilized moving forward.

VENTILATION PARAMETERS AND AIRBORNE PARTICULATE MONITORING

PBS took spot measurements of ventilation parameters in approximately 20% of the classrooms, offices, and common areas in the building (or each building). The readings were compared to recommendations in the American Society of Heating, Refrigerating and Air-Conditioning Engineers (ASHRAE) Standard 62.1-2016, Ventilation for Acceptable Indoor Air Quality.

PBS used a TSI VelociCalc 9565 ventilation meter to measure temperature, %RH, CO, and CO₂. A TSI Aerotrak 9306-V2 optical particle counter was used to measure airborne particulate. The table below summarizes the results of the testing. Readings above or below the ASHRAE recommendations are shown in bold.

IAQ Testing Results

Room	CO	CO ₂	Temp. (°F)	%RH	PM2.5	PM10	HVAC
Outdoor Air (Pre)	0.5	468	63.1	36.6	0.031	0.008	N/A
Nurse Room	0.0	534	69.5	40.3	0.011	0.007	Operable Windows, Radiant Heat
Classroom 5	0.0	479	72.0	36.4	0.009	0.004	Operable Windows, Radiant Heat
Classroom 3	0.6	486	71.6	35.1	0.005	0.002	Supply and Return, Operable Windows, Radiant Heat
Kitchen	0.6	472	71.5	34.3	0.018	0.008	Suspended Heating Unit, Range Hoods
Gymnasium	0.0	478	71.5	37.2	0.015	0.007	Supply and Return, Operable Windows
Auditorium	0.0	472	73.1	35.7	0.010	0.005	Supply and Return, Operable Windows
Room 35	0.0	481	73.6	35.4	0.009	0.005	None Observed
Classroom 11	0.0	475	73.1	33.1	0.004	0.000	Supply and Return, Operable Windows, Radiant Heat
Classroom 8	0.4	461	72.5	34.1	0.007	0.002	Supply and Return, Operable Windows, Radiant Heat
Main Office	0.0	484	72.9	35.6	0.023	0.011	Supply and Return, Operable Windows, Radiant Heat
Classroom 13	0.1	469	72.3	31.5	0.015	0.005	Supply and Return, Operable Windows, Radiant Heat
Classroom 16	0.0	474	72.3	33.5	0.012	0.005	Supply and Return, Operable Windows, Radiant Heat
Library	0.0	455	73.1	31.7	0.009	0.002	Supply and Return, Operable Windows, Radiant Heat
Faculty Room	0.0	488	73.7	33.8	0.019	0.009	Supply and Return, Operable Windows, Radiant Heat

Room	CO	CO ₂	Temp. (°F)	%RH	PM2.5	PM10	HVAC
Classroom 20	0.7	460	72.5	31.8	0.009	0.001	Supply and Return, Operable Windows, Radiant Heat
Classroom 22	0.0	472	71.5	33.8	0.011	0.005	Supply and Return, Operable Windows, Radiant Heat
Classroom 24	0.0	475	72.3	33.1	0.009	0.002	Supply and Return, Operable Windows, Radiant Heat
Play Court West	0.0	459	72.2	34.4	0.008	0.004	Supply and Return, Operable Windows,
Play Court East	0.0	465	71.6	34.2	0.006	0.000	Supply and Return, Operable Windows,
Music Room	0.0	455	73.2	32.5	0.014	0.005	Supply and Return, Operable Windows, Radiant Heat
Outdoor Air (Post)	1.5	428	67.6	34.6	0.037	0.013	N/A
Outdoor Air (Pre)	1.2	444	62.5	33.5	0.039	0.011	N/A
Portable 25	0.0	438	68.3	36.1	0.003	0.002	Operable window, unit ventilator
Portable 26	0.0	442	68.1	39.3	0.004	0.001	Operable window, unit ventilator
Portable 27	0.0	502	68.4	42.1	0.002	0.001	Operable window, unit ventilator
Outdoor Air (Post)	1.2	440	58.1	43.4	0.041	0.013	N/A

CO and CO₂ are presented in parts per million (ppm)

°F: degrees Fahrenheit

%RH: relative humidity

PM: particulate matter

HVAC: visible heating, ventilation, and air conditioning components

CARBON MONOXIDE

CO is produced from the incomplete combustion of carbon-containing fuels, including gasoline, heating oil, and natural gas. CO encountered in a classroom or office environment would likely be the result of proximity to motor vehicles or a malfunctioning heating system exhaust. While ASHRAE recommends that CO levels indoors should not exceed 9 parts per million (ppm), any sustained measurable amount of CO should be investigated.

CARBON DIOXIDE

CO₂ is a normal constituent of exhaled breath and indoor concentrations depend on the number of occupants, duration of occupancy, and air exchanges in a given space. ASHRAE recommends maintaining indoor CO₂

concentrations at less than approximately 1,200 ppm. Given that the building had only limited occupancy during the testing, the reported concentrations are not reflective of conditions during full occupancy.

TEMPERATURE

ASHRAE recommends maintaining indoor temperatures between 68 and 76°F.

RELATIVE HUMIDITY

ASHRAE recommends maintaining relative humidity indoors below 60%. Relative humidity indoors is difficult to regulate and is largely reflective of outdoor conditions.

AIRBORNE PARTICULATE

PM2.5

Airborne particulate matter was measured to assess the effectiveness of the buildings ventilation filtration system. ASHRAE recommends that ambient airborne particulate matter concentrations, measured as PM2.5, should meet National Ambient Air Quality Standards (NAAQS) which for PM2.5 which is 0.035 milligrams per cubic meter of air (mg/m³) as measured and averaged over a period of 24 hours.

PM10

Airborne particulate matter was measured to assess the effectiveness of the buildings ventilation filtration system. ASHRAE recommends that airborne particulate matter concentrations, measured as PM10, should meet NAAQS which for PM10 which is 0.150 mg/m³ as measured and averaged over a period of 24 hours.

HVAC

The main building has radiant heat with a large fan unit for classrooms. The gymnasium, cafeteria, and auditorium each have their own fan unit. The portable has unit ventilators with mixed air.

RECOMMENDATIONS

PBS observed one room that had neither operable windows nor an obvious mechanical or gravity ventilation system. If this room does not have adequate ventilation (active or passive), PBS recommends that it not be used for staff or student activities. This room includes the following:

- Room 35


Until this room can be provided with an adequate form of ventilation, it should be secured and labeled with signage indicating that it is not to be used.

LIMITATIONS OF SCOPE

This study was limited to the tests and locations as indicated above. The site as a whole may have other environmental concerns that will not be characterized by this study. The findings and conclusions of this work are not scientific certainties but probabilities based on professional judgment concerning the significance of the data gathered during the course of this investigation. PBS is not able to represent conditions on the site or adjoining sites beyond those detected or observed by PBS.

PBS respectfully submits these results of our indoor air quality investigation. Please feel free to contact me at 503.313.9061 or wayne.sehman@pbsusa.com with any questions or comments.

Sincerely,

 Digitally signed
by Wayne
Sehman
Date: 2021.04.01
16:19:08 -07'00'

Wayne Sehman
Project Manager

WS:mo