



**VENTURA UNIFIED SCHOOL DISTRICT
VENTURA HIGH SCHOOL SOFTBALL SITE IMPROVEMENTS**

BID # E4-23

October 8th, 2024

ADDENDUM #03

NOTICE TO BIDDERS:

The following revisions and/or clarifications shall be made to the bidding requirements and contract documents. Revise and amend the documents for the above-named project in accordance with this addendum. The bid shall reflect these addendum changes and each bidder shall refer in their bid to this addendum.

All bidding requirements and contract documents shall apply to this addendum as originally indicated in the applicable portions of the contract documents, unless otherwise modified by this addendum.

Contractors shall acknowledge this addendum at the space provided on the Bid Proposal.

REVISIONS, CLARIFICATIONS, & RESPONSES TO PRE-BID RFI'S: Please see attached document for Pre-Bid RFI's questions and responses.

REVISIONS TO THE PLANS:

REVISIONS TO THE SPECIFICATIONS:

REVISED DOCUMENTS ATTACHED AT END OF ADDENDUM #03


Addendum: 1 Page

ENCLOSURES: 2 Pages

Total Number of Pages: 3 Pages

ADDENDUM NUMBER THREE

08 October 2024



E4-23 VENTURA HS SOFTBALL SITE IMPROVEMENTS

2 N Catalina St
Ventura, CA 93001

Issued By:
KRUGER BENSEN ZIEMER ARCHITECTS, INC.
199 Figueroa St, Ste 100A
Ventura, CA 93001

To all bidders submitting proposal(s) for the captioned project: this Addendum is hereby made part of the Contract Documents to the same extent as though it was originally included therein and takes precedence over the original documents and any previous addenda.

Acknowledge receipt of the Addendum on Form of Proposal

A. PRE-BID RFI'S

- Q3: *Refer Specification Section 32 8400/3.6/Item B – depth of sand backfill for all irrigation lines under paving is not provided. Please provide.*
- A3: Per Specifications, all piping installed under pavement shall be backfilled entirely with sand and compacted. As per landscape detail No. 1 'Irrigation Piping and Conduit Trench Section' on Sheet L-300 and Irrigation Legend on L-101, all sleeving and mainline piping shall have a 24" backfill cover measured from top of pipe to finish grade.
- a. All piping installed under paving shall be backfilled entirely with sand and compacted. That will be a depth of 24" over pipe, the diameter of pipe, and a 3" deep bedding layer under the mainline pipe.
 - b. Mainline piping installed in landscape areas will be installed 24" below finish grade. The mainline will receive a 3" thick bedding layer of sand. The rest of trench to be backfilled with site soil with no rocks greater than 1" in diameter.
- Q4: *Refer to the legend on Sheet L-101 – the size of the master valve is 2" size, however, the callout on plan indicates 3" size. Please confirm which one will take precedence.*
- A4: There is a typo on the Irrigation Legend. The master valve shall be 3" size, Superior normally open master valve, Model #3300-300.

B. PROJECT MANUAL

(NONE)

(continues next page)

C. DRAWINGS

(NONE)

D. ATTACHMENTS

(NONE)

END OF ADDENDUM NUMBER THREE