PROJECT MANUAL SPECIFICATIONS

PROJECT:

ENTRANCE SOFFIT REPLACEMENT

BARNARD ELEMENTARY SCHOOL – SOFFIT REPAIR - 22086E
3601 Forge Drive
Troy, MI 48083

BEMIS ELEMENTARY SCHOOL – SOFFIT REPAIR – 22087E
3751 Northfield Pkwy
Troy, MI 48084

HAMILTON ELEMENTARY SCHOOL – SOFFIT REPAIR – 22089E
5625 Northfield Pkwy
Troy, MI 48098

WASS ELEMENTARY SCHOOL – SOFFIT REPAIR – 22096E
2430 Willard
Troy, MI 48098

OWNER:

TROY SCHOOL DISTRICT
4400 Livernois Road
Troy, MI 48098

TMP PROJECT NO.: 22086E, 22087E, 22089E, 22096E
BID PACKAGE NO.: 01C

DATE: JULY 21, 2025

ISSUED FOR: CONSTRUCTION DOCUMENTS

ARCHITECT

TMP ARCHITECTURE, INC.
1191 West Square Lake Road
Bloomfield Hills, MI 48302-0374

PH 248-338-4561
Email info@tmp-architecture.com

Copyright (c) 2024 TMP Architecture, Inc.

CONSTRUCTION MANAGER

BARTON MALOW COMPANY
26500 American Drive
Southfield, MI 48034

PH 248-436-5000

ELECTRICAL CONSULTANT

PETER BASSO ASSOCIATES, INC
5145 Livernois Road, Suite 100
Troy, MI 48098

PH 248-879-5666
Email info@pbanet.com

Troy School District –Soffit Repair – Barnard, Bemis, Hamilton and Wass Elementary Schools – 22086E, 22087E, 22089E, 22096E

This Document has been prepared under the supervision of the Architect and/or Professional Engineer as indicated by their individual License Seals affixed hereon.

Professional License Seals

Seal	*Seal*	*Seal*
TMP Architecture, Inc. *Architect*	***Peter Basso Associates*** *Electrical Engineer*	

TABLE OF CONTENTS

PROCUREMENT AND CONTRACTING REQUIREMENTS GROUP

DIVISION 00 – PROCUREMENT AND CONTRACTING REQUIREMENTS

Section	Title	Issued
00 0101	Title Page	**CD**
00 0107	Professional Seals Page	**CD**
00 0110	Table of Contents	**CD**
00 0115	List of Drawings	**CD**
00 8200	Availability of Electronic Files	**CD**
00 8200.02	Electronic Files Release Form (Free)	**CD**

SPECIFICATIONS GROUP

GENERAL REQUIREMENTS SUBGROUP

DIVISION 01 - GENERAL REQUIREMENTS

Section	Title	Issued
01 0005	Related Requirements	**CD**
01 2300	Alternates	**CD**
01 2500	Substitution Procedures	**CD**
01 2500.01	TMP Substitution Request Form	**CD**
01 3000	Administrative Requirements	**CD**
01 3000.01	TMP Submittal and Sample Transmittal Form	**CD**
01 4000	Quality Requirements	**CD**
01 4100	Regulatory Requirements	**CD**
01 4216	Definitions	**CD**
01 4219	Reference Standards	**CD**
01 4533	Code-Required Special Inspections and Procedures	**CD**
01 6000	Product Requirements	**CD**
01 7000	Execution and Closeout Requirements	**CD**
01 7329	Cutting and Patching	**CD**
01 7800	Closeout Submittals	**CD**

FACILITY CONSTRUCTION SUBGROUP

DIVISION 02 – EXISTING CONDITIONS

Title	Issued	
02 4100	Demolition	**CD**

DIVISION 03 - CONCRETE

Not Used

DIVISION 04 - MASONRY

Not Used

DIVISION 05 - METALS

Not Used

DIVISION 06 – WOOD, PLASTICS, AND COMPOSITES

Section	Title	Issued
06 1000	Rough Carpentry	**CD**

DIVISION 07 - THERMAL AND MOISTURE PROTECTION

Section	Title	Issued
07 4213	Metal Wall Panels	**CD**
07 6200	Sheet Metal Flashing and Trim	**CD**
07 9200	Joint Sealants	**CD**

DIVISION 08 - OPENINGS

Not Used

DIVISION 09 - FINISHES

Section	Title	Issued
09 2216	Non-Structural Metal Framing	**CD**

DIVISION 10 - SPECIALTIES

Not Used

DIVISION 11 - EQUIPMENT

Not Used

DIVISION 12 - FURNISHINGS

Not Used

DIVISION 13 - SPECIAL CONSTRUCTION

Not Used

DIVISION 14 – CONVEYING EQUIPMENT

Not Used

FACILITY SERVICES SUBGROUP

DIVISION 20 – COMMON MECHANICAL REQUIREMENTS

Not Used

DIVISION 21 – FIRE SUPPRESSION

Not Used

DIVISION 22 - PLUMBING

Not Used

DIVISION 23 – HEATING VENTILATING AND AIR CONDITIONING (HVAC)

Not Used

DIVISION 25 – INTEGRATED AUTOMATION

Not Used

DIVISION 26 – ELECTRICAL

Section	Title	Issued
26 0010	Electrical General Requirements	**CD**
26 0519	Conductors and Cabling	**CD**
26 0526	Grounding and Bonding	**CD**
26 0529	Hangers and Supports for Electrical Systems	**CD**
26 0533	Raceways and Boxes	**CD**
26 0553	Electrical Identification	**CD**
26 5600	Exterior Lighting	**CD**

DIVISION 27 – COMMUNICATIONS

Not Used

DIVISION 28 – ELECTRONIC SAFETY AND SECURITY

Not Used

SITE AND INFRASTRUCTURE SUBGROUP

DIVISION 31 – EARTHWORK

Not Used

DIVISION 32 – EXTERIOR IMPROVEMENTS

Not Used

DIVISION 33 – UTILITIES

Not Used

END OF SECTION

SECTION 00 0115 - LIST OF DRAWINGS

LIST OF DRAWINGS

1.01 GENERAL

A. Drawings: Drawings consist of the Contract Drawings including drawings listed on the TITLE SHEET page of the separately bound drawing set titled Barnard Elementary School, Bemis Elementary School, Hamilton Elementary School, Wass Elementary School - Soffit Repair, dated July 14, 2025 and any subsequent Addenda and Contract modifications which may occur.

END OF SECTION

SECTION 00 0115 - LIST OF DRAWINGS

LIST OF DRAWINGS

1.01 GENERAL

A. Drawings: Drawings consist of the Contract Drawings including drawings listed on the TITLE SHEET page of the separately bound drawing set titled _____, dated _____ and any subsequent Addenda and Contract modifications which may occur.

END OF SECTION

SECTION 00 8200.02 - TMP ELECTRONIC FILES RELEASE FORM (FREE)

RE: AUTHORIZATION FORM FOR CAD FILE TRANSFERS
PROJECT NAME: BARNARD ELEMENTARY SCHOOL, BEMIS ELEMENTART SCHOOL, HAMILTON ELEMENTARY SCHOOL, WASS ELEMENTARY SCHOOL - SOFFIT REPAIR
TMP PROJECT NO. : 22086E, 22087E, 22089E, 22096E BID PACK NO. : 01C

Dear Sir/Madam:

Per your request, TMP Architecture, Inc. will electronically transmit requested CAD files upon receipt of an original signed copy of this form which states the conditions of agreement and the receipt of the required compensation fee.

1. By acceptance it is understood and agreed that the data and medium being supplied is to be used only for the project referenced.
2. It is further understood and agreed that the undersigned will hold TMP Architecture, Inc. and its Consultants harmless and indemnify TMP Architecture, Inc. and its Consultants from all claims, liabilities, losses, and so forth, including attorney's fees arising out of the use or misuse of the transferred files.
3. It is understood and agreed that the items transmitted are prepared from CAD files current at the time of preparation. All files are [AutoCAD version 2014 dwg files].
4. This information does not waive the need to verify and review current field conditions and the status of Addenda and/or Bulletin documentation.
5. As a record of information to be transmitted, TMP Architecture, Inc. will prepare a duplicate electronic back-up for its record.
6. Compensation for providing this material will be as follows: **$0.00 / No Charge**
7. A signed copy of this form must be provided before files will be released. Please remit to [Construction Manager] to be forwarded to the Project Manager at TMP Architecture, Inc. and allow five working days for processing.

REQUESTED DRAWINGS: _____
_____
_____

FIRM REQUESTING FILES:

Company: _____
Address: _____
Signed:_____Date: _____
Printed Name / Title: _____
Email: _____

TO BE COMPLETED BY TMP ARCHITECTURE, INC.

Released(signed by): _____TMP Architecture, Inc.
Printed Name/Title:_____ Date: _____

END OF SECTION

SECTION 00 8200 - AVAILABILITY OF ELECTRONIC FILES

AVAILABILITY OF ELECTRONIC FILES

1.01POLICY

A. As a service to Contractor, subcontractors, vendors, material suppliers and others needing electronic copies of Drawings, the Architect will provide CAD files electronically in accordance with the following policy:

1. By acceptance it is understood and agreed that the data and medium being supplied is to be used only for the project referenced.
2. It is further understood and agreed that the undersigned will hold TMP Architecture, Inc. and its Consultants harmless and indemnify TMP Architecture, Inc. and its Consultants from all claims, liabilities, losses, and so forth, including attorney's fees arising out of the use or misuse of the transferred files.
3. It is understood and agreed that the files transmitted are prepared from CAD files current at the time of preparation. All files are AutoCAD version 2014 dwg files.
4. This information does not waive the need to verify and review current field conditions and the status of Addenda and/or Bulletin documentation.
5. As a record of information to be transmitted, TMP Architecture, Inc. will prepare a duplicate electronic back-up for its record.
6. A signed copy of the Release Form must be provided before files will be released.

1.02 REQUEST PROCEDURE

A. To receive Drawing CAD files the Release Form must be completed in full and submitted to the Construction Manager to be forwarded to the Project Manager at TMP Architecture, Inc.

1. A signed copy of the Release Form must be submitted.
   a. Faxed or emailed copies will be accepted.
2. Upon remittance of the signed Release Form , allow five working days for processing.
3. Transmission of Drawings will be provided electronically .

1.03 RELEASE FORM

A. Release Form is located immediately after this Section. Refer to Section 00 8200.02 Electronic Files Release Form.

END OF SECTION

SECTION 01 0005 - RELATED REQUIREMENTS

PART 1 GENERAL

1.01 DIVISION 00 AND DIVISION 01

A. Unless otherwise noted, all provisions of sections and documents in Division 00 and Division 01, including, but not limited to, General Conditions and Supplementary Conditions, relate and apply to all sections and documents within Project Manual; including, but not limited to, sections and documents in Division 00 through Division 48.

1.02 DRAWINGS

A. Unless otherwise noted, Drawings relate and apply to all specification sections and documents within Project Manual; including, but not limited to, sections and documents in Division 00 through Division 48.

PART 2 PRODUCTS -- NOT USED

PART 3 EXECUTION -- NOT USED

END OF SECTION

SECTION 01 2300 - ALTERNATES

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Description of Alternates.

1.02 ACCEPTANCE OF ALTERNATES

A. Alternates quoted on Bid Forms will be reviewed and accepted or rejected at Owner's option. Accepted Alternates will be identified in the Owner-Contractor Agreement.

B. Coordinate related work and modify surrounding work to integrate the Work of each Alternate.

1.03 SCHEDULE OF ALTERNATES

A. Alternate 1 - Soffit Material

1. Base Bid: To provide and install the metal soffit using the Basis of Design: "Knotwood" by Aluminum Architectural Products - ALUMARCH; www.alumarch.com; PH 888-589-9771.
2. Alternate: To provide and install the metal soffit using the 6" wide Parallel AP plank style soffit in a sublimated wood grain pattern., as selected by the Architect.

PART 2 PRODUCTS - NOT USED

PART 3 EXECUTION - NOT USED

END OF SECTION

SECTION 01 2500.01 - TMP SUBSTITUTION REQUEST FORM

SUBSTITUTION REQUEST NUMBER: _____ DATE SUBMITTED: _____
TMP PROJECT NUMBER 22086E, 22087E, 22089E, 22096E PROJECT NAME: BARNARD ELEMENTARY SCHOOL, BEMIS ELEMENTARY SCHOOL, HAMILTON ELEMENMTARY SCHOOL, WASS ELEMENTARY SCHOOL - SOFFIT REPAIR.

SPECIFIED ITEM

SPECIFICATION TITLE:_____
SPECIFICATION SECTION_____SPECIFICATION ARTICLE/PARAGRAPH: _____
SPECIFIED PRODUCT / DESCRIPTION: _____
SPECIFIED MANUFACTURER: _____
SPECIFIED PRODUCT / MODEL: _____
REASON SPECIFIED ITEM CANNOT BE PROVIDED: _____
_____
_____

PROPOSED SUBSTITUTION

DESCRIPTION OF PROPOSED SUBSTITUTION: _____
_____
PROPOSED MANUFACTURER: _____
ADDRESS: _____
WEBSITE: _____
PRODUCT / MODEL: _____
YEARS PRODUCT/MODEL HAS BEEN MANUFACTURED: _____
DIFFERENCES BETWEEN PROPOSED SUBSTITUTION AND SPECIFIED ITEM: _____
_____
_____
_____
_____
WILL PROPOSED SUBSTITUTION AFFECT OTHER PARTS OF WORK? ☐ NO ☐ YES
IF YES, EXPLAIN HOW: _____
_____
_____
_____
HOW WILL SUBSTITUTION BENEFIT THE OWNER: ☐ COST SAVINGS ☐ TIME SAVINGS ☐ OTHER
PROVIDE SPECIFIC DETAILS: _____
_____
_____
_____

THE FOLLOWING INFORMATION IS REQUIRED; CHECK TO INDICATE INFORMATION IS ATTACHED. (REQUEST WILL BE REJECTED WITHOUT REQUIRED DATA)

32.01

A. ☐ List of references where proposed product has been installed; include address, owner, architect, and date installed.
B. ☐ Product data sheets.
C. ☐ Applicable certificates and test reports.

D. ☐ Comparative Data: Provide point-by-point, side-by-side comparison of specified product and proposed substitution addressing essential attributes specified.

INDICATE WHICH OF THE FOLLOWING VOLUNTARY INFORMATION IS ATTACHED, IF ANY:
☐ DRAWINGS.
☐ SAMPLES.
☐ OTHER ITEMS: _____

SIGNATURE

THE UNDERSIGNED CERTIFIES:

The proposed substitution meets or exceeds the quality level of the specified product, equipment, assembly, or system.
To provide the same warranty for the substitution as for the specified product.
Agrees to provide same or equivalent maintenance service and source of replacement parts, as applicable.
Agrees to coordinate installation and make changes to other work that may be required for the work to be complete, with no additional cost to Owner.
The proposed substitution will have no adverse effects on other work.
The proposed substitution will not affect project schedule.
Waives claims for additional costs or time extension that may subsequently become apparent.

CONTRACTOR / COMPANY: _____
SIGNED BY: _____PRINTED NAME: _____
TITLE: _____
ADDRESS: _____
EMAIL: _____ PHONE: _____

ARCHITECT'S RESPONSE

A. During bidding, Architect will approve substitution requests by issuing an Addendum. Substitutions not approved by addendum are rejected.
B. During construction, Architect will notify Contractor in writing (see below) of decision to accept or reject request, and incorporate the substitution into the project by Change Order, Construction Change Directive, Architectural Supplementary Instructions, or similar instruments as provided for in the Conditions of the Contract.

☐ SUBSTITUTION APPROVED - PROVIDE SUBMITTALS PER SECTION 01 3000 AND RESPECTIVE SECTION FOR WHICH SUBSTITUTION WAS MADE.
☐ SUBSTITUTION REJECTED - PROVIDE SPECIFIED MATERIALS.

SIGNED BY: _____PRINTED NAME: _____
ARCHITECT'S COMMENTS: _____
_____
_____

END OF SECTION

SECTION 01 2500 - SUBSTITUTION PROCEDURES

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Procedural requirements for proposed substitutions.

1.02 RELATED REQUIREMENTS

A. Section 01 2500.01 - TMP Substitution Request Form.

1.03 DEFINITIONS

A. Substitutions: Changes from Contract Documents requirements proposed by Contractor to materials, products, assemblies, and equipment.
   1. Substitutions for Cause: Proposed due to changed Project circumstances beyond Contractor's control.
   2. Substitutions for Convenience: Proposed due to possibility of offering substantial advantage to the Project.

B. Substitutions: Any proposed substitution to be evaluated by the Architect and accepted as stipulated below.

PART 2 PRODUCTS - NOT USED

PART 3 EXECUTION

3.01 GENERAL REQUIREMENTS

A. A Substitution Request for products, assemblies, materials, and equipment constitutes a representation that the submitter:
   1. Has investigated proposed product and determined that it meets or exceeds the quality level of the specified product, equipment, assembly, or system.
   2. Agrees to provide the same warranty for the substitution as for the specified product.
   3. Agrees to provide same or equivalent maintenance service and source of replacement parts, as applicable.
   4. Agrees to coordinate installation and make changes to other work that may be required for the work to be complete, with no additional cost to Owner.
   5. Waives claims for additional costs or time extension that may subsequently become apparent.

B. Document each request with complete data substantiating compliance of proposed substitution with Contract Documents. Burden of proof is on proposer.
   1. Note explicitly any non-compliant characteristics.

C. Content: Include information necessary for tracking the status of each Substitution Request, and information necessary to provide an actionable response.
   1. Forms included in the Project Manual are adequate for this purpose, and must be used.

D. Limit each request to a single proposed substitution item.
   1. Submit an electronic document, combining the request form with supporting data into single document.

3.02 SUBSTITUTION PROCEDURES DURING PROCUREMENT

A. Submittal Time Restrictions:

B. Substitution Request Form: TMP Substitution Request Form must be completed and provided at the beginning of each substitution request.
   1. Refer to Section 01 2500.01 - TMP Substitution Request Form.
   2. Submittals without a completed TMP Substitution Request Form will not be acknowledged, reviewed, or returned. Use only this form; other forms of submission are unacceptable.

C. Instructions to Bidders specifies time restrictions for submitting requests for substitutions during the bidding period.

3.03 SUBSTITUTION PROCEDURES DURING CONSTRUCTION

A. Substitution Request Form: TMP Substitution Request Form must be completed and provided at the beginning of each substitution request.
   1. Refer to Section 01 2500.01 - TMP Substitution Request Form.
   2. Submittals without a completed TMP Substitution Request Form will not be acknowledged, reviewed, or returned. Use only this form; other forms of submission are unacceptable.

B. Submit request for Substitution for Cause immediately upon discovery of need for substitution, but not later than 14 days prior to time required for review and approval by Architect, in order to stay on approved project schedule.

C. Submit request for Substitution for Convenience within 14 days of discovery of its potential advantage to the project, but not later than 14 days prior to time required for review and approval by Architect, in order to stay on approved project schedule.
   1. In addition to meeting general documentation requirements, document how the requested substitution benefits the Owner through cost savings, time savings, greater energy conservation, or in other specific ways.
   2. Document means of coordinating of substitution item with other portions of the work, including work by affected subcontractors.
   3. Bear the costs engendered by proposed substitution of:
      a. Owner's compensation to the Architect for any required redesign, time spent processing and evaluating the request.
      b. Other unanticipated project considerations.

D. Substitutions will not be considered under one or more of the following circumstances:
   1. When they are indicated or implied on shop drawing or product data submittals, without having received prior approval.
   2. Without a separate written request.

3.04 RESOLUTION

A. Architect may request additional information and documentation prior to rendering a decision. Provide this data in an expeditious manner.

B. Architect will notify Contractor in writing of decision to accept or reject request.
   1. During construction, Architect's decision following review of proposed substitution will be noted on the submitted form.
   2. During bidding, Architect will approve substitution requests by issuing an Addendum. Substitutions not approved by addendum are rejected.

3.05 ACCEPTANCE

A. Accepted substitutions change the work of the Project. They will be documented and incorporated into work of the project by Change Order, Construction Change Directive, Architectural Supplementary Instructions, or similar instruments provided for in the Conditions of the Contract.

3.06 CLOSEOUT ACTIVITIES

A. See Section 01 7800 - Closeout Submittals, for closeout submittals.

END OF SECTION

SUBMITTAL AND SAMPLE TRANSMITTAL FORM

01 3000.01

CONST. MANAGER / CONTRACTOR	PROJECT	TMP PROJECT NO.	DATE SUBMITTED	SUBMITTAL NO.
Name and Address:	Title:	22086E, 22087E, 22089E, 20096E		
	Barnard Elementary School Bemis Elementary School Hamilton Elementary School Wass Elementary School Entrance Soffit Replacement			
Email:	Location:	* ACTION CODES		Initial Submittal ☐ Resubmittal ☐
		R Reviewed – No Exceptions Taken RN Reviewed with Corrections Noted RR Revise and Resubmit X Not Approved – Resubmit NA No Action Taken – Not Reviewed		REVIEWED BY TMP ☐ Consultant ☐ Reviewer:
Phone:				

SPECIFICATION SECTION NO.	SUBCONTRACTOR / MANUFACTURER	ITEM DESCRIPTION	NO. OF SAMPLES	NO. OF SAMPLES RETURNED	ACTION CODE *	DATE REVIEWED	DATE RETURNED
Transmittal shall be for one specification section only; do not submit items from multiple sections under the same transmittal. Multi-section submittals will be returned; stamped "X - Not Approved - Resubmit"							

Submittal Stamps may be placed on subsequent blank page.

CONTRACTOR COMMENTS	ARCHITECT COMMENTS	The undersigned certifies that the above submitted items have been reviewed in detail and are correct and in strict conformance with the Contract Documents except as otherwise noted. NOTE: Approval of items submitted does not relieve Contractor from complying with all requirements of the Contract Documents.
		CONTRACTOR NAME
		SIGNATURE

This page intentionally left blank for Submittal Stamps

SECTION 01 3000 - ADMINISTRATIVE REQUIREMENTS

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Submittals for review, information, and project closeout.
B. Number of copies of submittals.
C. Requests for Interpretation (RFI) procedures.
D. Submittal procedures.

1.02 RELATED REQUIREMENTS

A. Section 01 3000.01 - TMP Submittal and Sample Transmittal Form.

1.03 REFERENCE STANDARDS

A. AIA G716 - Request for Information; 2004.
B. CSI/CSC Form 13.2A - Request for Information; Current Edition.

PART 2 PRODUCTS - NOT USED

PART 3 EXECUTION

3.01 REQUESTS FOR INTERPRETATION (RFI)

A. Definition: A request seeking one of the following:
   1. An interpretation, amplification, or clarification of some requirement of Contract Documents arising from inability to determine from them the exact material, process, or system to be installed; or when the elements of construction are required to occupy the same space (interference); or when an item of work is described differently at more than one place in Contract Documents.
   2. A resolution to an issue which has arisen due to field conditions and affects design intent.
B. Preparation: Prepare an RFI immediately upon discovery of a need for interpretation of Contract Documents. Failure to submit a RFI in a timely manner is not a legitimate cause for claiming additional costs or delays in execution of the work.
   1. Prepare a separate RFI for each specific item.
      a. Review, coordinate, and comment on requests originating with subcontractors and/or materials suppliers.
      b. Do not forward requests which solely require internal coordination between subcontractors.
   2. Prepare in a format and with content acceptable to Architect. Use one of the following:
      a. Use AIA G716 - Request for Information .
      b. Use CSI/CSC Form 13.2A - Request for Interpretation.
      c. Other format acceptable to Architect.
   3. Combine RFI and its attachments into a single electronic file. PDF format is preferred.
   4. Submit RFIs through Procore, email, or other approved method agreed to by the Architect and Owner.
      a. RFIs submitted via an internet-based submittal service are to send electronic documents to the Architect via email with a downloadable link.
C. Reason for the RFI: Prior to initiation of an RFI, carefully study all Contract Documents to confirm that information sufficient for their interpretation is definitely not included.
   1. Include in each request Contractor's signature attesting to good faith effort to determine from Contract Documents information requiring interpretation.
   2. Improper RFIs: Requests not prepared in conformance to requirements of this section, and/or missing key information required to render an actionable response. They will be returned without a response and may include an explanatory notation.
   3. Frivolous RFIs: Requests regarding information that is clearly indicated on, or reasonably inferable from, the Contract Documents, with no additional input required to clarify the question. They will be returned without a response and may include an explanatory notation.

a. The Owner reserves the right to assess the Contractor for the costs (on time-and-materials basis) incurred by the Architect, and any of its consultants, due to processing of such RFIs.

D. Content: Include identifiers necessary for tracking the status of each RFI, and information necessary to provide an actionable response.
1. Official Project name and number, and any additional required identifiers established in Contract Documents.
2. Discrete and consecutive RFI number, and descriptive subject/title.
3. Issue date, and requested reply date.
4. Reference to particular Contract Document(s) requiring additional information/interpretation. Identify pertinent drawing and detail number and/or specification section number, title, and paragraph(s).
5. Annotations: Field dimensions and/or description of conditions which have engendered the request.
6. Contractor's suggested resolution: A written and/or a graphic solution, to scale, is required in cases where clarification of coordination issues is involved, for example; routing, clearances, and/or specific locations of work shown diagrammatically in Contract Documents. If applicable, state the likely impact of the suggested resolution on Contract Time or the Contract Sum.

E. Attachments: Include sketches, coordination drawings, descriptions, photos, submittals, and other information necessary to substantiate the reason for the request.

F. RFI Log: Prepare and maintain a tabular log of RFIs for the duration of the project.
1. Indicate current status of every RFI. Update log promptly and on a regular basis.
2. Note dates of when each request is made, and when a response is received.
3. Identify and include improper or frivolous RFIs.

G. Review Time: Architect will respond and return RFIs to Contractor within seven calendar days of receipt. For the purpose of establishing the start of the mandated response period, RFIs received after 3:00 PM will be considered as having been received on the following regular working day.
1. Response period may be shortened or lengthened for specific items, subject to mutual agreement, and recorded in a timely manner in progress meeting minutes.

H. Responses: Content of answered RFIs will not constitute in any manner a directive or authorization to perform extra work or delay the project. If in Contractor's belief it is likely to lead to a change to Contract Sum or Contract Time, promptly issue a notice to this effect, and follow up with an appropriate Change Order request to Owner.
1. Response may include a request for additional information, in which case the original RFI will be deemed as having been answered, and an amended one is to be issued forthwith. Identify the amended RFI with an R suffix to the original number.
2. Do not extend applicability of a response to specific item to encompass other similar conditions, unless specifically so noted in the response.
3. Upon receipt of a response, promptly review and distribute it to all affected parties, and update the RFI Log.
4. Notify Architect within seven calendar days if an additional or corrected response is required by submitting an amended version of the original RFI, identified as specified above.

3.02 SUBMITTAL SCHEDULE

A. Submit to Architect for review a schedule for submittals in tabular format.
1. Submit at the same time as the preliminary schedule.
2. Coordinate with Contractor's construction schedule and schedule of values.
3. Format schedule to allow tracking of status of submittals throughout duration of construction.

4. Arrange information to include scheduled date for initial submittal, specification number and title, description of item of work covered, and role and name of subcontractor.
5. Account for time required for preparation, review, manufacturing, fabrication and delivery when establishing submittal delivery and review deadline dates.
   a. For assemblies, equipment, systems comprised of multiple components and/or requiring detailed coordination with other work, allow for additional time to make corrections or revisions to initial submittals, and time for their review.

3.03 SUBMITTALS FOR REVIEW

A. When the following are specified in individual sections, submit them for review:
   1. Product data.
   2. Shop drawings.
   3. Samples for selection.
   4. Samples for verification.
B. Submit to Architect for review for the limited purpose of checking for compliance with information given and the design concept expressed in Contract Documents.
C. Samples will be reviewed for aesthetic, color, or finish selection.
D. After review, provide copies and distribute in accordance with SUBMITTAL PROCEDURES article below and for record documents purposes described in Section 01 7800 - Closeout Submittals.

3.04 SUBMITTALS FOR INFORMATION

A. When the following are specified in individual sections, submit them for information:
   1. Design data.
   2. Certificates.
   3. Test reports.
   4. Inspection reports.
   5. Manufacturer's instructions.
   6. Manufacturer's field reports.
   7. Other types indicated.
B. Submit for Architect's knowledge as contract administrator or for Owner.

3.05 SUBMITTALS FOR PROJECT CLOSEOUT

A. Submit Correction Punch List for Substantial Completion.
B. Submit Final Correction Punch List for Substantial Completion.
C. When the following are specified in individual sections, submit them at project closeout in compliance with requirements of Section 01 7800 - Closeout Submittals:
   1. Project record documents.
   2. Operation and maintenance data.
   3. Warranties.
   4. Other types as indicated.
D. Submit for Owner's benefit during and after project completion.

3.06 NUMBER OF COPIES OF SUBMITTALS

A. Electronic Documents: Submit one electronic copy.
B. Samples: Submit the number specified in individual specification sections, but not less than 3; one (minimum) of which will be retained by Architect.
   1. After review, produce duplicates.
   2. Retained samples will not be returned to Contractor unless specifically so stated.

3.07 SUBMITTAL PROCEDURES

A. Transmittal Form: TMP Submittal and Sample Transmittal Form must be completed and provided at the beginning of each submittal.
   1. Refer to Section 01 3000.01 - TMP Submittal and Sample Transmittal Form.
   2. Submittals without a completed TMP Submittal and Sample Transmittal Form will not be acknowledged, reviewed, or returned.

B. Submittals shall be submitted in electronic form.
   1. Exceptions: Physical samples.
      a. Physical Samples must be accompanied by an electronic copy and a hard/physical copy of the completed TMP Submittal and Sample Transmittal Form.
C. Electronic Submittals: Comply with the following:
   1. Submittal process shall be through Procore, email, or other approved method agreed to by the Architect and Owner.
      a. Submittals via an internet-based submittal service are to send electronic documents to the Architect via email with a downloadable link.
   2. File Format: Portable Document Format (PDF).
   3. File Naming: File naming shall be in the following format:
      a. Specification section number, followed by a hyphen, and a consecutive number indicating sequential submittals for that section; followed by a general description of the submittal contents.
         1) Examples:
            (a) Section 07 9200; first submittal:
               (1) 07 9200-01 Joint Sealants
            (b) Section 07 9200; second submittal:
               (1) 07 9200-02 Joint Sealant Color
      b. Resubmittals. For revised resubmittals use original number and a sequential combination numerical and alphabetical suffix; hyphen followed by "R" and a two-digit consecutive number indicating sequential resubmittals for that particular submittal.
         1) Examples:
            (a) Section 07 9200; resubmittal of first submittal of section:
               (1) 07 9200-01-R01 Joint Sealants.
            (b) Section 07 9200; second resubmittal of first submittal of section:
               (1) 07 9200-01-R02 Joint Sealants
            (c) Section 07 9200; first resubmittal of second submittal of section:
               (1) 07 9200-02-R01 Joint Sealant Color
   4. Each Submittal shall be one file, complete with all attachments.
      a. Multi-file submittal will not be acknowledged, reviewed, or returned.
D. General Requirements:
   1. Use a single transmittal for related items.
      a. Each transmittal shall be for one specification section only; do not submit items for multiple sections under the same transmittal.
         1) Multi-section submittals will be acknowledged and returned; stamped "X - Not Approved - Resubmit".
   2. Submit separate packages of submittals for review and submittals for information, when included in the same specification section.
   3. Apply Contractor's stamp, signed or initialed certifying that review, approval, verification of products required, field dimensions, adjacent construction work, and coordination of information is in accordance with the requirements of the work and Contract Documents.
      a. Submittals from sources other than the Contractor, or without Contractor's stamp will not be acknowledged, reviewed, or returned.
   4. Deliver each submittal on date noted in submittal schedule, unless an earlier date has been agreed to by all affected parties, and is of the benefit to the project.
   5. Schedule submittals to expedite the Project, and coordinate submission of related items.
      a. For each submittal for review, allow 14 calendar days excluding delivery time to and from the Contractor.
      b. For sequential reviews involving Architect's consultants, Owner, or another affected party, allow an additional 7 calendardays.
   6. Identify variations from Contract Documents and product or system limitations that may be detrimental to successful performance of the completed work.
   7. When revised for resubmission, identify all changes made since previous submission.

8. Distribute reviewed submittals. Instruct parties to promptly report inability to comply with requirements.
9. Incomplete submittals will not be reviewed, unless they are partial submittals for distinct portion(s) of the work, and have received prior approval for their use.
10. Submittals not requested will be recognized and returned; stamped "NA - No Action Taken - Not Reviewed"

E. Product Data Procedures:
1. Submit only information required by individual specification sections.
2. Collect required information into a single submittal.
3. Submit concurrently with related shop drawing submittal.
4. Do not submit (Material) Safety Data Sheets for materials or products unless specifically called for in individual sections.

F. Shop Drawing Procedures:
1. Prepare accurate, drawn-to-scale, original shop drawing documentation by interpreting Contract Documents and coordinating related work.
2. Do not reproduce Contract Documents to create shop drawings.
3. Generic, non-project-specific information submitted as shop drawings do not meet the requirements for shop drawings.
4. Non-complying submittals will be acknowledged and returned; stamped "X - Not Approved - Resubmit".

G. Samples Procedures:
1. Transmit related items together as single package.
2. Identify each item to allow review for applicability in relation to shop drawings showing installation locations.
3. Submit actual physical samples.
4. Electronic submittals will not be accepted unless prior approval is received from the Architect. Electronic samples without prior approval will be acknowledged and returned; stamped "X - Not Approved - Resubmit."

3.08 SUBMITTAL REVIEW

A. General: Submittals that do not conform to the requirements of this section will not be acknowledged, reviewed, or returned.

B. Submittals for Review: Architect will review each submittal, and approve, or take other appropriate action.

C. Submittals for Information: Architect will acknowledge and may review. See below for actions to be taken.

D. Architect's actions will be reflected by marking each returned submittal using virtual stamp on electronic submittals.
1. Where more than one action has been indicated, each shall apply to that portion of the submittal for which the action is indicated.

E. Architect's review shall not indicate approval of dimensions, quantities or fabrication processes unless specific notations are made by the Architect regarding same.

F. Architect's and consultants' actions on items submitted for review:
1. Authorizing purchasing, fabrication, delivery, and installation:
a. "Reviewed - No Exceptions Taken", "Approved", or language with same legal meaning.
b. "Reviewed with Corrections Noted", "Approved as Noted, Resubmission not required", or language with same legal meaning.
1) At Contractor's option, submit corrected item, with review notations acknowledged and incorporated.
2. Not Authorizing fabrication, delivery, and installation:
a. "Revise and Resubmit", "Not Approved - Resubmit", or language with the same legal meaning.

1) Resubmit revised item, with review notations acknowledged and incorporated.

3. Not Authorizing manufacturer:
   a. Rejected - Resubmit, or language with the same legal meaning.

G. Architect's and consultants' actions on items submitted for information:
   1. Items for which no action was taken:
      a. "No Action Taken - Not Reviewed" or "Received" - to notify the Contractor that the submittal has been received for record only.

END OF SECTION

SECTION 01 4000 - QUALITY REQUIREMENTS

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Submittals.
B. Quality assurance.
C. References and standards.
D. Testing and inspection agencies and services.
E. Contractor's design-related professional design services.
F. Control of installation.
G. Mock-ups.
H. Tolerances.
I. Manufacturers' field services.
J. Defect Assessment.

1.02 REFERENCE STANDARDS

A. ASTM E329 - Standard Specification for Agencies Engaged in Construction Inspection, Testing, or Special Inspection; 2021.
B. ASTM E543 - Standard Specification for Agencies Performing Nondestructive Testing; 2021.
C. ASTM E699 - Standard Specification for Agencies Involved in Testing, Quality Assurance, and Evaluating of Manufactured Building Components; 2016.

1.03 DEFINITIONS

A. Contractor's Professional Design Services: Design of some aspect or portion of the project by party other than the design professional of record. Provide these services as part of the Contract for Construction.
    1. Design Services Types Required:
        a. Design-Related: Design services explicitly required to be performed by another design professional due to highly-technical and/or specialized nature of a portion of the project. Services primarily involve engineering analysis, calculations, and design, and are not intended to alter the aesthetic aspects of the design.
B. Design Data: Design-related, signed and sealed drawings, calculations, specifications, certifications, shop drawings and other submittals provided by Contractor, and prepared directly by, or under direct supervision of, appropriately licensed design professional.

1.04 CONTRACTOR'S DESIGN-RELATED PROFESSIONAL DESIGN SERVICES

A. Coordination: Contractor's professional design services are subject to requirements of project's Conditions for Construction Contract.
B. Base design on performance and/or design criteria indicated in individual specification sections.

1.05 SUBMITTALS

A. See Section 01 3000 - Administrative Requirements, for submittal procedures.
B. Design Data: Submit for Architect's knowledge as contract administrator for the limited purpose of assessing compliance with information given and the design concept expressed in the Contract Documents, or for Owner's information.
    1. Include a statement or certification attesting that design data complies with criteria indicated, such as building codes, loads, functional, and similar engineering requirements.
    2. Include signature and seal of design professional responsible for allocated design services on calculations and drawings.
C. Test Reports: After each test/inspection, promptly submit 1 copies of report to Architect and to Contractor.
    1. Include:
        a. Date issued.

b. Project title and number.
c. Name of inspector.
d. Date and time of sampling or inspection.
e. Identification of product and specifications section.
f. Location in the Project.
g. Type of test/inspection.
h. Date of test/inspection.
i. Results of test/inspection.
j. Compliance with Contract Documents.
k. When requested by Architect, provide interpretation of results.

2. Test report submittals are for Architect's knowledge as contract administrator for the limited purpose of assessing compliance with information given and the design concept expressed in the Contract Documents, or for Owner's information.

D. Certificates: When specified in individual specification sections, submit certification by the manufacturer and Contractor or installation/application subcontractor to Architect, in quantities specified for Product Data.
1. Indicate material or product complies with or exceeds specified requirements. Submit supporting reference data, affidavits, and certifications as appropriate.
2. Certificates may be recent or previous test results on material or product, but must be acceptable to Architect.

E. Manufacturer's Instructions: When specified in individual specification sections, submit printed instructions for delivery, storage, assembly, installation, start-up, adjusting, and finishing, for the Owner's information. Indicate special procedures, perimeter conditions requiring special attention, and special environmental criteria required for application or installation.

F. Manufacturer's Field Reports: Submit reports for Architect's benefit as contract administrator or for Owner.
1. Submit for information for the limited purpose of assessing compliance with information given and the design concept expressed in the Contract Documents.

1.06 QUALITY ASSURANCE

A. Testing Agency Qualifications:
1. Prior to start of Work, submit agency name, address, and telephone number, and names of full time specialist and responsible officer.

B. Designer Qualifications: Where professional engineering design services and design data submittals are specifically required of Contractor by Contract Documents, provide services of a Professional Engineer experienced in design of this type of work and licensed in the State in which the Project is located.

1.07 REFERENCES AND STANDARDS

A. Obtain copies of standards where required by product specification sections.

B. Maintain copy at project site during submittals, planning, and progress of the specific work, until Substantial Completion.

1.08 TESTING AND INSPECTION AGENCIES AND SERVICES

A. As indicated in individual specification sections, Owner or Contractor shall employ and pay for services of an independent testing agency to perform other specified testing.

B. Employment of agency in no way relieves Contractor of obligation to perform Work in accordance with requirements of Contract Documents.

C. Contractor Employed Agency:
1. Testing agency: Comply with requirements of ASTM E329, ASTM E543, and ASTM E699.
2. Inspection agency: Comply with requirements of ASTM E329.
3. Laboratory Staff: Maintain a full time specialist on staff to review services.

PART 2 PRODUCTS - NOT USED

PART 3 EXECUTION

3.01 CONTROL OF INSTALLATION

A. Monitor quality control over suppliers, manufacturers, products, services, site conditions, and workmanship, to produce work of specified quality.
B. Comply with manufacturers' instructions, including each step in sequence.
C. Should manufacturers' instructions conflict with Contract Documents, request clarification from Architect before proceeding.
D. Comply with specified standards as minimum quality for the work except where more stringent tolerances, codes, or specified requirements indicate higher standards or more precise workmanship.
E. Have work performed by persons qualified to produce required and specified quality.
F. Verify that field measurements are as indicated on shop drawings or as instructed by the manufacturer.
G. Secure products in place with positive anchorage devices designed and sized to withstand stresses, vibration, physical distortion, and disfigurement.

3.02 MOCK-UPS

A. Before installing portions of the Work where mock-ups are required, construct mock-ups in location and size indicated for each form of construction and finish required to comply with the following requirements, using materials indicated for the completed Work. The purpose of mock-up is to demonstrate the proposed range of aesthetic effects and workmanship.
B. Accepted mock-ups establish the standard of quality the Architect will use to judge the Work.
C. Integrated Exterior Mock-ups: Construct integrated exterior mock-up as indicated on drawings. Coordinate installation of exterior envelope materials and products as required in individual Specification Sections. Provide adequate supporting structure for mock-up materials as necessary.
D. Notify Architect 5 working days in advance of dates and times when mock-ups will be constructed.
E. Provide supervisory personnel who will oversee mock-up construction. Provide workers that will be employed during the construction at Project.
F. Tests shall be performed under provisions identified in this section and identified in the respective product specification sections.
G. Assemble and erect specified items with specified attachment and anchorage devices, flashings, seals, and finishes.
H. Obtain Architect's approval of mock-ups before starting work, fabrication, or construction.
    1. Make corrections as necessary until Architect's approval is issued.
I. Architect will use accepted mock-ups as a comparison standard for the remaining Work.
J. Where mock-up has been accepted by Architect and is specified in product specification sections to be removed, protect mock-up throughout construction, remove mock-up and clear area when directed to do so by Architect.

3.03 TOLERANCES

A. Monitor fabrication and installation tolerance control of products to produce acceptable Work. Do not permit tolerances to accumulate.
B. Comply with manufacturers' tolerances. Should manufacturers' tolerances conflict with Contract Documents, request clarification from Architect before proceeding.
C. Adjust products to appropriate dimensions; position before securing products in place.

3.04 TESTING AND INSPECTION

A. See individual specification sections for testing and inspection required.

B. Testing Agency Duties:
   1. Provide qualified personnel at site. Cooperate with Architect and Contractor in performance of services.
   2. Perform specified sampling and testing of products in accordance with specified standards.
   3. Ascertain compliance of materials and mixes with requirements of Contract Documents.
   4. Promptly notify Architect and Contractor of observed irregularities or non-compliance of Work or products.
   5. Perform additional tests and inspections required by Architect.
   6. Submit reports of all tests/inspections specified.

C. Limits on Testing/Inspection Agency Authority:
   1. Agency may not release, revoke, alter, or enlarge on requirements of Contract Documents.
   2. Agency may not approve or accept any portion of the Work.
   3. Agency may not assume any duties of Contractor.
   4. Agency has no authority to stop the Work.

D. Contractor Responsibilities:
   1. Deliver to agency at designated location, adequate samples of materials proposed to be used that require testing, along with proposed mix designs.
   2. Cooperate with laboratory personnel, and provide access to the Work.
   3. Provide incidental labor and facilities:
      a. To provide access to Work to be tested/inspected.
      b. To obtain and handle samples at the site or at source of Products to be tested/inspected.
      c. To facilitate tests/inspections.
      d. To provide storage and curing of test samples.
   4. Notify Architect and laboratory 48 hours prior to expected time for operations requiring testing/inspection services.
   5. Employ services of an independent qualified testing laboratory and pay for additional samples, tests, and inspections required by Contractor beyond specified requirements.
   6. Arrange with Owner's agency and pay for additional samples, tests, and inspections required by Contractor beyond specified requirements.

E. Re-testing required because of non-compliance with specified requirements shall be performed by the same agency on instructions by Architect.

F. Re-testing required because of non-compliance with specified requirements shall be paid for by Contractor.

3.05 MANUFACTURERS' FIELD SERVICES

A. When specified in individual specification sections, require material or product suppliers or manufacturers to provide qualified staff personnel to observe site conditions, conditions of surfaces and installation, quality of workmanship, start-up of equipment, test, adjust, and balance equipment as applicable, and to initiate instructions when necessary.

B. Report observations and site decisions or instructions given to applicators or installers that are supplemental or contrary to manufacturers' written instructions.

3.06 DEFECT ASSESSMENT

A. Replace Work or portions of the Work not complying with specified requirements.

B. If, in the opinion of Architect, it is not practical to remove and replace the work, Architect will direct an appropriate remedy or adjust payment.

END OF SECTION

SECTION 01 4100 - REGULATORY REQUIREMENTS

PART 1 GENERAL

1.01 SUMMARY OF REFERENCE STANDARDS

A. Regulatory requirements applicable to this project are the following:
   1. ASHRAE Std 90.1 I-P-2019 - Energy Standard for Buildings Except Low-Rise Residential Buildings; 2019, with Errata and Addenda (2021).
   2. Barrier Free Code: Comply with the following:
      a. Michigan Building Code; 2021.
      b. ICC A117.1 - Accessible and Usable Buildings and Facilities; 2017.
   3. School Fire Safety Rules: Michigan School Fire Safety Rules; 2016.
      a. Includes NFPA 101-2012 - Life Safety Code; 2012, plus amendments.
   4. Building Code: Michigan Building Code; 2021.
   5. Plumbing Code: Michigan Plumbing Code; 2021.
   6. Mechanical Code: Michigan Mechanical Code; 2021.
   7. Electrical Code: NFPA 70 - National Electric Code; 2023.
      a. Includes 2023 Michigan Construction Code - Part 8 Electrical Code Rules.
   8. Elevator Code: Comply with the following:
      a. ASME A17.1 - Safety Code for Elevators and Escalators; 2016.
      b. ASME A18.1- Safety Standard for Platform Lifts and Stairway Chairlifts; 2017.
      c. 2023 Michigan Elevator Safety Board General Rules.
   9. Boiler Code: Michigan Boiler Code.
      a. Includes the following:
         1) ASME Boiler and Pressure Vessel Codes; 2019.
         2) National Board Inspection Code; 2019.
         3) PA 407 Skilled Trades Regulation Act; 2016.
   10. Energy Code: Michigan Commercial Energy Code; 2021.
      a. Includes ASHRAE Std 90.1 I-P-2019 - Energy Standard for Buildings Except Low-Rise Residential Buildings; 2019.
   11. Existing Building Code: Michigan Rehabilitation Code; 2021.

B. Where specification sections reference more current standards or codes, comply with the more restrictive requirements unless notified in writing by Architect.

PART 2 PRODUCTS - NOT USED

PART 3 EXECUTION - NOT USED

END OF SECTION

SECTION 01 4216 - DEFINITIONS

PART 1 GENERAL

1.01 SUMMARY

A. This section supplements the definitions contained in the General Conditions.

B. Other definitions are included in individual specification sections.

1.02 DEFINITIONS

A. Furnish: To supply, deliver, unload, and inspect for damage.

B. Install: To unpack, assemble, erect, apply, place, finish, cure, protect, clean, start up, and make ready for use.

C. Product: Material, machinery, components, equipment, fixtures, and systems forming the work result. Not materials or equipment used for preparation, fabrication, conveying, or erection and not incorporated into the work result. Products may be new, never before used, or re-used materials or equipment.

D. Project Manual: The book-sized volume that includes the procurement requirements (if any), the contracting requirements, and the specifications.

E. Provide: To furnish and install.

F. Supply: Same as Furnish.

PART 2 PRODUCTS - NOT USED

PART 3 EXECUTION - NOT USED

END OF SECTION

SECTION 01 4219 - REFERENCE STANDARDS

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Requirements relating to referenced standards.

1.02 QUALITY ASSURANCE

A. For products or workmanship specified by reference to a document or documents not included in the Project Manual, also referred to as reference standards, comply with requirements of the standard, except when more rigid requirements are specified or are required by applicable codes.

B. Comply with the reference standard of date of issue specified in this section, except where a specific date is established by applicable code.

C. Should specified reference standards conflict with Contract Documents, request clarification from the Architect before proceeding.

D. Neither the contractual relationships, duties, or responsibilities of the parties in Contract nor those of the Architect shall be altered by Contract Documents by mention or inference otherwise in any reference document.

PART 2 PRODUCTS -- NOT USED

PART 3 EXECUTION -- NOT USED

END OF SECTION

SECTION 01 4533 - CODE-REQUIRED SPECIAL INSPECTIONS AND PROCEDURES

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Code-required special inspections.
B. Submittals.

1.02 ABBREVIATIONS AND ACRONYMS

A. AHJ: Authority having jurisdiction.
B. NIST: National Institute of Standards and Technology.

1.03 DEFINITIONS

A. Code or Building Code: Michigan Building Code; 2015, specifically Chapter 17 - Special Inspections and Tests.
B. Authority Having Jurisdiction (AHJ): Agency or individual officially empowered to enforce the building, fire and life safety code requirements of the permitting jurisdiction in which the Project is located.
C. Special Inspection:
   1. Special inspections are inspections and testing of materials, installation, fabrication, erection or placement of components and connections mandated by the AHJ that also require special expertise to ensure compliance with the approved Contract Documents and the referenced standards.
   2. Special inspections are separate from and independent of tests and inspections conducted by Owner or Contractor for the purposes of quality assurance and contract administration.

1.04 REFERENCE STANDARDS

A. ASTM E329 - Standard Specification for Agencies Engaged in Construction Inspection, Testing, or Special Inspection; 2021.

1.05 SUBMITTALS

A. See Section 01 3000 - Administrative Requirements, for submittal procedures.
B. Special Inspection Agency Qualifications: Prior to the start of work, the Special Inspection Agency is required to:
   1. Submit agency name, address, and telephone number, names of full time specialist and responsible officer.
   2. Submit copy of report of laboratory facilities inspection made by NIST Construction Materials Reference Laboratory during most recent inspection, with memorandum of remedies of any deficiencies reported by the inspection.
   3. Submit certification that Special Inspection Agency is acceptable to AHJ.
C. Special Inspection Reports: After each special inspection, Special Inspector is required to promptly submit at least two copies of report; one to Architect and one to the AHJ.
   1. Include:
      a. Date issued.
      b. Project title and number.
      c. Name of Special Inspector.
      d. Date and time of special inspection.
      e. Identification of product and specifications section.
      f. Location in the Project.
      g. Type of special inspection.
      h. Date of special inspection.
      i. Results of special inspection.
      j. Compliance with Contract Documents.
   2. Final Special Inspection Report: Document special inspections and correction of discrepancies prior to the start of the work.

D. Fabricator Special Inspection Reports: After each special inspection of fabricated items at the Fabricator's facility, Special Inspector is required to promptly submit at least two copies of report; one to Architect and one to AHJ.
   1. Include:
      a. Date issued.
      b. Project title and number.
      c. Name of Special Inspector.
      d. Date and time of special inspection.
      e. Identification of fabricated item and specification section.
      f. Location in the Project.
      g. Results of special inspection.
      h. Verification of fabrication and quality control procedures.
      i. Compliance with Contract Documents.
      j. Compliance with referenced standard(s).

E. Test Reports: After each test or inspection, promptly submit at least two copies of report; one to Architect and one to AHJ.
   1. Include:
      a. Date issued.
      b. Project title and number.
      c. Name of inspector.
      d. Date and time of sampling or inspection.
      e. Identification of product and specifications section.
      f. Location in the Project.
      g. Type of test or inspection.
      h. Date of test or inspection.
      i. Results of test or inspection.
      j. Compliance with Contract Documents.

1.06 SPECIAL INSPECTION AGENCY

A. Owner will employ services of a Special Inspection Agency to perform inspections and associated testing and sampling in accordance with ASTM E329 and required by the building code.

B. Employment of agency in no way relieves Contractor of obligation to perform work in accordance with requirements of Contract Documents.

1.07 QUALITY ASSURANCE

A. Special Inspection Agency Qualifications:
   1. Independent firm specializing in performing testing and inspections of the type specified in this section.

PART 2 PRODUCTS - NOT USED

PART 3 EXECUTION

3.01 SCHEDULE OF SPECIAL INSPECTIONS, GENERAL

A. Frequency of Special Inspections: Special Inspections are indicated as continuous or periodic.
   1. Continuous Special Inspection: Special Inspection Agency is required to be present in the area where the work is being performed and observe the work at all times the work is in progress.
   2. Periodic Special Inspection: Special Inspection Agency is required to be present in the area where work is being performed and observe the work part-time or intermittently and at the completion of the work.

3.02 SPECIAL INSPECTIONS

A. Special inspections and testing shall be for materials, installation, fabrication, erection or placement of components and connections as indicated on Drawings, but not less than that required by the building code.

END OF SECTION

SECTION 01 6000 - PRODUCT REQUIREMENTS

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Re-use of existing products.
B. Transportation, handling, storage and protection.
C. Product option requirements.
D. Substitution limitations.
E. Procedures for Owner-supplied products.
F. Maintenance materials, including extra materials, spare parts, tools, and software.

1.02 SUBMITTALS

A. Product Data Submittals: Submit manufacturer's standard published data. Mark each copy to identify applicable products, models, options, and other data. Supplement manufacturers' standard data to provide information specific to this Project.
B. Shop Drawing Submittals: Prepared specifically for this Project; indicate utility and electrical characteristics, utility connection requirements, and location of utility outlets for service for functional equipment and appliances.
C. Sample Submittals: Illustrate functional and aesthetic characteristics of the product, with integral parts and attachment devices. Coordinate sample submittals for interfacing work.
    1. For selection from standard finishes, submit samples of the full range of the manufacturer's standard colors, textures, and patterns.

PART 2 PRODUCTS

2.01 EXISTING PRODUCTS

A. Do not use materials and equipment removed from existing premises unless specifically required or permitted by Contract Documents.
B. Unforeseen historic items encountered remain the property of the Owner; notify Owner promptly upon discovery; protect, remove, handle, and store as directed by Owner.
C. Existing materials and equipment indicated to be removed, but not to be re-used, relocated, reinstalled, delivered to the Owner, or otherwise indicated as to remain the property of the Owner, become the property of the Contractor; remove from site.
D. Specific Products to be Reused: The reuse of certain materials and equipment already existing on the project site is required.
    1. Refer to Drawings and Section 02 4100 - Demolition.

2.02 NEW PRODUCTS

A. Provide new products unless specifically required or permitted by Contract Documents.

2.03 PRODUCT OPTIONS

A. Products Specified by Reference Standards or by Description Only: Use any product meeting those standards or description.
B. Products Specified by Naming One or More Manufacturers: Use a product of one of the manufacturers named and meeting specifications, no options or substitutions allowed.
C. Products Specified by Naming One or More Manufacturers with a Provision for Substitutions: Submit a request for substitution for any manufacturer not named.
D. Available Products: Products specified by naming one or more Manufacturers as an Available Product indicates that these Manufacturers' products may be provided but other comparable products and Manufacturers not named may also be provided without submitting a request for substitution.

2.04 MAINTENANCE MATERIALS

A. Furnish extra materials, spare parts, tools, and software of types and in quantities specified in individual specification sections.

B. Deliver and place in location as directed; obtain receipt prior to final payment.

PART 3 EXECUTION

3.01 SUBSTITUTION LIMITATIONS

A. See Section 01 2500 - Substitution Procedures.

3.02 OWNER-SUPPLIED PRODUCTS

A. Owner's Responsibilities:
   1. Arrange for and deliver Owner reviewed shop drawings, product data, and samples, to Contractor.
   2. Arrange and pay for product delivery to site.
   3. On delivery, inspect products jointly with Contractor.
   4. Submit claims for transportation damage and replace damaged, defective, or deficient items.
   5. Arrange for manufacturers' warranties, inspections, and service.

B. Contractor's Responsibilities:
   1. Review Owner reviewed shop drawings, product data, and samples.
   2. Receive and unload products at site; inspect for completeness or damage jointly with Owner.
   3. Handle, store, install and finish products.
   4. Repair or replace items damaged after receipt.

3.03 TRANSPORTATION AND HANDLING

A. Package products for shipment in manner to prevent damage; for equipment, package to avoid loss of factory calibration.

B. If special precautions are required, attach instructions prominently and legibly on outside of packaging.

C. Coordinate schedule of product delivery to designated prepared areas in order to minimize site storage time and potential damage to stored materials.

D. Transport and handle products in accordance with manufacturer's instructions.

E. Promptly inspect shipments to ensure that products comply with requirements, quantities are correct, and products are undamaged.

F. Provide equipment and personnel to handle products by methods to prevent soiling, disfigurement, or damage, and to minimize handling.

G. Arrange for the return of packing materials, such as wood pallets, where economically feasible.

3.04 STORAGE AND PROTECTION

A. Designate receiving/storage areas for incoming products so that they are delivered according to installation schedule and placed convenient to work area in order to minimize waste due to excessive materials handling and misapplication.

B. Store and protect products in accordance with manufacturers' instructions.

C. Store with seals and labels intact and legible.

D. Store sensitive products in weathertight, climate-controlled enclosures in an environment favorable to product.

E. For exterior storage of fabricated products, place on sloped supports above ground.

F. Provide off-site storage and protection when site does not permit on-site storage or protection.

G. Protect products from damage or deterioration due to construction operations, weather, precipitation, humidity, temperature, sunlight and ultraviolet light, dirt, dust, and other contaminants.

H. Comply with manufacturer's warranty conditions, if any.

I. Do not store products directly on the ground.

J. Cover products subject to deterioration with impervious sheet covering. Provide ventilation to prevent condensation and degradation of products.

K. Store loose granular materials on solid flat surfaces in a well-drained area. Prevent mixing with foreign matter.
L. Prevent contact with material that may cause corrosion, discoloration, or staining.
M. Provide equipment and personnel to store products by methods to prevent soiling, disfigurement, or damage.
N. Arrange storage of products to permit access for inspection. Periodically inspect to verify products are undamaged and are maintained in acceptable condition.

END OF SECTION

SECTION 01 7000 - EXECUTION AND CLOSEOUT REQUIREMENTS

PART 1 GENERAL

1.01SECTION INCLUDES

A. Examination, preparation, and general installation procedures.
B. Requirements for alterations work, including selective demolition.
C. Pre-installation meetings.
D. Cutting and patching.
E. Surveying for laying out the work.
F. Cleaning and protection.
G. Starting of systems and equipment.
H. Demonstration and instruction of Owner personnel.
I. Closeout procedures, including Contractor's Correction Punch List, except payment procedures.
J. General requirements for maintenance service.

1.02 REFERENCE STANDARDS

A. NFPA 241 - Standard for Safeguarding Construction, Alteration, and Demolition Operations; 2022, with Errata (2021).

1.03 SUBMITTALS

A. See Section 01 3000 - Administrative Requirements, for submittal procedures.
B. Cutting and Patching: Submit written request in advance of cutting or alteration that affects:
    1. Structural integrity of any element of Project.
    2. Integrity of weather exposed or moisture resistant element.
    3. Efficiency, maintenance, or safety of any operational element.
    4. Visual qualities of sight exposed elements.
    5. Work of Owner or separate Contractor.
    6. Include in request:
        a. Identification of Project.
        b. Location and description of affected work.
        c. Necessity for cutting or alteration.
        d. Description of proposed work and products to be used.
        e. Effect on work of Owner or separate Contractor.
C. Project Record Documents: Accurately record actual locations of capped and active utilities.
D. Warranties: For each affected material under warranty, submit written verification, signed by manufacturer of existing materials, stating that the Owner's full warranty will remain in effect after cutting and patching operations have been completed

1.04 QUALIFICATIONS

A. For surveying work, employ a land surveyor registered in the State in which the Project is located and acceptable to Architect. Submit evidence of surveyor's Errors and Omissions insurance coverage in the form of an Insurance Certificate. Employ only individual(s) trained and experienced in collecting and recording accurate data relevant to ongoing construction activities,

1.05 PROJECT CONDITIONS

A. Use of explosives is not permitted.
B. Grade site to drain. Maintain excavations free of water. Provide, operate, and maintain pumping equipment.
C. Protect site from puddling or running water. Provide water barriers as required to protect site from soil erosion.
D. Perform dewatering activities, as required, for the duration of the project.

E. Ventilate enclosed areas to assist cure of materials, to dissipate humidity, and to prevent accumulation of dust, fumes, vapors, or gases.
F. Dust Control: Execute work by methods to minimize raising dust from construction operations. Provide positive means to prevent air-borne dust from dispersing into atmosphere and over adjacent property.
   1. Provide dust-proof enclosures to prevent entry of dust generated outdoors.
   2. Provide dust-proof barriers between construction areas and areas continuing to be occupied by Owner.
G. Erosion and Sediment Control: Plan and execute work by methods to control surface drainage from cuts and fills, from borrow and waste disposal areas. Prevent erosion and sedimentation.
   1. Periodically inspect earthwork to detect evidence of erosion and sedimentation; promptly apply corrective measures.
H. Noise Control: Provide methods, means, and facilities to minimize noise produced by construction operations.
   1. Outdoors: Limit conduct of especially noisy exterior work to the hours of 8 am to 5 pm.
   2. Indoors: Limit conduct of especially noisy interior work to the hours of 6 pm to 7 am.
I. Pest and Rodent Control: Provide methods, means, and facilities to prevent pests and insects from damaging the work.
J. Pollution Control: Provide methods, means, and facilities to prevent contamination of soil, water, and atmosphere from discharge of noxious, toxic substances, and pollutants produced by construction operations. Comply with federal, state, and local regulations.

1.06 COORDINATION

A. Coordinate scheduling, submittals, and work of the various sections of the Project Manual to ensure efficient and orderly sequence of installation of interdependent construction elements, with provisions for accommodating items installed later.
B. Notify affected utility companies and comply with their requirements.
C. Verify that utility requirements and characteristics of new operating equipment are compatible with building utilities. Coordinate work of various sections having interdependent responsibilities for installing, connecting to, and placing in service, such equipment.
D. Coordinate space requirements, supports, and installation of mechanical and electrical work that are indicated diagrammatically on drawings. Follow routing indicated for pipes, ducts, and conduit, as closely as practicable; place runs parallel with lines of building. Utilize spaces efficiently to maximize accessibility for other installations, for maintenance, and for repairs.
E. In finished areas except as otherwise indicated, conceal pipes, ducts, and wiring within the construction. Coordinate locations of fixtures and outlets with finish elements.
F. Coordinate completion and clean-up of work of separate sections.
G. After Owner occupancy of premises, coordinate access to site for correction of defective work and work not in accordance with Contract Documents, to minimize disruption of Owner's activities.

1.07 WARRANTIES

A. Existing Warranties: Remove, replace, patch, and repair materials and surfaces cut or damaged during cutting and patching operations, by methods and with materials so as not to void existing warranties.

PART 2 PRODUCTS

2.01 PATCHING MATERIALS

A. New Materials: As specified in product sections; match existing products and work for patching and extending work.

B. Type and Quality of Existing Products: Determine by inspecting and testing products where necessary, referring to existing work as a standard.
C. Product Substitution: For any proposed change in materials, submit request for substitution described in Section 01 6000 - Product Requirements.

PART 3 EXECUTION

3.01 EXAMINATION

A. Verify that existing site conditions and substrate surfaces are acceptable for subsequent work. Start of work means acceptance of existing conditions.
B. Verify that existing substrate is capable of structural support or attachment of new work being applied or attached.
C. Examine and verify specific conditions described in individual specification sections.
D. Take field measurements before confirming product orders or beginning fabrication, to minimize waste due to over-ordering or misfabrication.
E. Verify that utility services are available, of the correct characteristics, and in the correct locations.
F. Prior to Cutting: Examine existing conditions prior to commencing work, including elements subject to damage or movement during cutting and patching. After uncovering existing work, assess conditions affecting performance of work. Beginning of cutting or patching means acceptance of existing conditions.

3.02 PREPARATION

A. Clean substrate surfaces prior to applying next material or substance.
B. Seal cracks or openings of substrate prior to applying next material or substance.
C. Apply manufacturer required or recommended substrate primer, sealer, or conditioner prior to applying any new material or substance in contact or bond.

3.03 PREINSTALLATION MEETINGS

A. When required in individual specification sections, convene a preinstallation meeting at the site prior to commencing work of the section.
B. Require attendance of parties directly affecting, or affected by, work of the specific section.
C. Notify Architect 5 calendar days in advance of meeting date.
D. Prepare agenda and preside at meeting:
    1. Review conditions of examination, preparation and installation procedures.
    2. Review coordination with related work.
E. Record minutes and distribute copies within two days after meeting to participants, with 1 copies to Architect, Owner, participants, and those affected by decisions made.

3.04 LAYING OUT THE WORK

A. Verify locations of survey control points prior to starting work.
B. Promptly notify Architect of any discrepancies discovered.
C. Contractor shall locate and protect survey control and reference points.
D. Protect survey control points prior to starting site work; preserve permanent reference points during construction.
E. Promptly report to Architect the loss or destruction of any reference point or relocation required because of changes in grades or other reasons.
F. Replace dislocated survey control points based on original survey control. Make no changes without prior written notice to Architect.
G. Utilize recognized engineering survey practices.
H. Establish elevations, lines and levels. Locate and lay out by instrumentation and similar appropriate means:

1. Site improvements including pavements; stakes for grading, fill and topsoil placement; utility locations, slopes, and invert elevations.
2. Grid or axis for structures.
3. Building foundation, column locations, ground floor elevations.
4. Controlling lines and levels required for mechanical and electrical trades.

I. Periodically verify layouts by same means.

J. Maintain a complete and accurate log of control and survey work as it progresses.

3.05 GENERAL INSTALLATION REQUIREMENTS

A. In addition to compliance with regulatory requirements, conduct construction operations in compliance with NFPA 241, including applicable recommendations in Appendix A.

B. Install products as specified in individual sections, in accordance with manufacturer's instructions and recommendations, and so as to avoid waste due to necessity for replacement.

C. Make vertical elements plumb and horizontal elements level, unless otherwise indicated.

D. Install equipment and fittings plumb and level, neatly aligned with adjacent vertical and horizontal lines, unless otherwise indicated.

E. Make consistent texture on surfaces, with seamless transitions, unless otherwise indicated.

F. Make neat transitions between different surfaces, maintaining texture and appearance.

3.06 ALTERATIONS

A. Drawings showing existing construction and utilities are based on casual field observation only.
1. Verify that construction and utility arrangements are as indicated.
2. Report discrepancies to Architect before disturbing existing installation.
3. Beginning of alterations work constitutes acceptance of existing conditions.

B. Keep areas in which alterations are being conducted separated from other areas that are still occupied.
1. Provide, erect, and maintain temporary dustproof partitions.

C. Maintain weatherproof exterior building enclosure except for interruptions required for replacement or modifications; take care to prevent water and humidity damage.
1. Where openings in exterior enclosure exist, provide construction to make exterior enclosure weatherproof.
2. Insulate existing ducts or pipes that are exposed to outdoor ambient temperatures by alterations work.

D. Remove existing work as indicated and as required to accomplish new work.
1. Remove items indicated on drawings.
2. Relocate items indicated on drawings.
3. Where new surface finishes are to be applied to existing work, perform removals, patch, and prepare existing surfaces as required to receive new finish; remove existing finish if necessary for successful application of new finish.
4. Where new surface finishes are not specified or indicated, patch holes and damaged surfaces to match adjacent finished surfaces as closely as possible.

E. Services (Including but not limited to HVAC, Plumbing, Fire Protection, Electrical, and Telecommunications): Remove, relocate, and extend existing systems to accommodate new construction.
1. Maintain existing active systems that are to remain in operation; maintain access to equipment and operational components; if necessary, modify installation to allow access or provide access panel.
2. Where existing systems or equipment are not active and Contract Documents require reactivation, put back into operational condition; repair supply, distribution, and equipment as required.
3. Where existing active systems serve occupied facilities but are to be replaced with new services, maintain existing systems in service until new systems are complete and ready for service.

a. Disable existing systems only to make switchovers and connections; minimize duration of outages.
b. Provide temporary connections as required to maintain existing systems in service.

4. Verify that abandoned services serve only abandoned facilities.
5. Remove abandoned pipe, ducts, conduits, and equipment , including those above accessible ceilings; remove back to source of supply where possible, otherwise cap stub and tag with identification; patch holes left by removal using materials specified for new construction.

F. Protect existing work to remain.
1. Prevent movement of structure; provide shoring and bracing if necessary.
2. Perform cutting to accomplish removals neatly and as specified for cutting new work.
3. Repair adjacent construction and finishes damaged during removal work.

G. Adapt existing work to fit new work: Make as neat and smooth transition as possible.
1. Where removal of partitions or walls results in adjacent spaces becoming one, rework floors, walls, and ceilings to a smooth plane without breaks, steps, or bulkheads.

H. Patching: Where the existing surface is not indicated to be refinished, patch to match the surface finish that existed prior to cutting. Where the surface is indicated to be refinished, patch so that the substrate is ready for the new finish.

I. Refinish existing surfaces as indicated:
1. Where rooms or spaces are indicated to be refinished, refinish all visible existing surfaces to remain to the specified condition for each material, with a neat transition to adjacent finishes.
2. If mechanical or electrical work is exposed accidentally during the work, re-cover and refinish to match.

J. Clean existing systems and equipment.

K. Remove demolition debris and abandoned items from alterations areas and dispose of off-site; do not burn or bury.

L. Do not begin new construction in alterations areas before demolition is complete.

M. Comply with all other applicable requirements of this section.

3.07 CUTTING AND PATCHING

A. Whenever possible, execute the work by methods that avoid cutting or patching.

B. See Alterations article above for additional requirements.

C. Perform whatever cutting and patching is necessary to:
1. Complete the work.
2. Fit products together to integrate with other work.
3. Provide openings for penetration of mechanical, electrical, and other services.
4. Match work that has been cut to adjacent work.
5. Repair areas adjacent to cuts to required condition.
6. Repair new work damaged by subsequent work.
7. Remove samples of installed work for testing when requested.
8. Remove and replace defective and non-complying work.

D. Execute work by methods that avoid damage to other work and that will provide appropriate surfaces to receive patching and finishing. In existing work, minimize damage and restore to original condition.

E. Employ skilled and experienced installer to perform cutting for weather exposed and moisture resistant elements, and sight exposed surfaces.

F. Cut rigid materials using masonry saw or core drill. Pneumatic tools not allowed without prior approval.

G. Restore work with new products in accordance with requirements of Contract Documents.

H. Fit work air tight to pipes, sleeves, ducts, conduit, and other penetrations through surfaces.

I. At penetrations of fire rated walls, partitions, ceiling, or floor construction, completely seal voids with fire rated material in accordance with Section 07 8400, to full thickness of the penetrated element.

J. Patching:
   1. Finish patched surfaces to match finish that existed prior to patching. On continuous surfaces, refinish to nearest intersection or natural break. For an assembly, refinish entire unit.
      a. This includes painted surfaces.
      b. Where the surface is indicated to be refinished, patch so that the substrate is ready for the new finish.
   2. Match color, texture, and appearance.
   3. Repair patched surfaces that are damaged, lifted, discolored, or showing other imperfections due to patching work. If defects are due to condition of substrate, repair substrate prior to repairing finish.

3.08 PROGRESS CLEANING

A. Maintain areas free of waste materials, debris, and rubbish. Maintain site in a clean and orderly condition.

B. Remove debris and rubbish from pipe chases, plenums, attics, crawl spaces, and other closed or remote spaces, prior to enclosing the space.

C. Broom and vacuum clean interior areas prior to start of surface finishing, and continue cleaning to eliminate dust.

D. Collect and remove waste materials, debris, and trash/rubbish from site periodically and dispose off-site; do not burn or bury.

3.09 PROTECTION OF INSTALLED WORK

A. Protect installed work from damage by construction operations.

B. Provide special protection where specified in individual specification sections.

C. Provide temporary and removable protection for installed products. Control activity in immediate work area to prevent damage.

D. Provide protective coverings at walls, projections, jambs, sills, and soffits of openings.

E. Protect finished floors, stairs, and other surfaces from traffic, dirt, wear, damage, or movement of heavy objects, by protecting with durable sheet materials.

F. Prohibit traffic or storage upon waterproofed or roofed surfaces. If traffic or activity is necessary, obtain recommendations for protection from waterproofing or roofing material manufacturer.

G. Remove protective coverings when no longer needed; reuse or recycle coverings if possible.

3.10 SYSTEM STARTUP

A. Coordinate schedule for start-up of various equipment and systems.

B. Notify Architectand Owner 7 calendar days prior to start-up of each item.

C. Verify that each piece of equipment or system has been checked for proper lubrication, drive rotation, belt tension, control sequence, and for conditions that may cause damage.

D. Verify tests, meter readings, and specified electrical characteristics agree with those required by the equipment or system manufacturer.

E. Verify that wiring and support components for equipment are complete and tested.

F. Execute start-up under supervision of applicable Contractor personnel and manufacturer's representative in accordance with manufacturers' instructions.

G. When specified in individual specification Sections, require manufacturer to provide authorized representative to be present at site to inspect, check, and approve equipment or system installation prior to start-up, and to supervise placing equipment or system in operation.

H. Submit a written report that equipment or system has been properly installed and is functioning correctly.

3.11 DEMONSTRATION AND INSTRUCTION

A. Demonstrate operation and maintenance of products to Owner's personnel two weeks prior to date of Substantial Completion.
B. Demonstrate start-up, operation, control, adjustment, trouble-shooting, servicing, maintenance, and shutdown of each item of equipment at agreed time, at equipment location.
C. For equipment or systems requiring seasonal operation, perform demonstration for other season within six months.
D. Provide a qualified person who is knowledgeable about the Project to perform demonstration and instruction of Owner's personnel.
E. Utilize operation and maintenance manuals as basis for instruction. Review contents of manual with Owner's personnel in detail to explain all aspects of operation and maintenance.
F. Prepare and insert additional data in operations and maintenance manuals when need for additional data becomes apparent during instruction.

3.12 ADJUSTING

A. Adjust operating products and equipment to ensure smooth and unhindered operation.

3.13 FINAL CLEANING

A. Use cleaning materials that are nonhazardous.
B. Clean interior and exterior glass, surfaces exposed to view; remove temporary labels, stains and foreign substances, polish transparent and glossy surfaces, vacuum carpeted and soft surfaces.
C. Remove all labels that are not permanent. Do not paint or otherwise cover fire test labels or nameplates on mechanical and electrical equipment.
D. Clean equipment and fixtures to a sanitary condition with cleaning materials appropriate to the surface and material being cleaned.
E. Clean filters of operating equipment.
F. Clean debris from roofs, gutters, downspouts, scuppers, overflow drains, area drains, and drainage systems.
G. Clean site; sweep paved areas, rake clean landscaped surfaces.
H. Remove waste, surplus materials, trash/rubbish, and construction facilities from the site; dispose of in legal manner; do not burn or bury.

3.14 CLOSEOUT PROCEDURES

A. Make submittals that are required by governing or other authorities.
B. Accompany Contractor on preliminary inspection to determine items to be listed for completion or correction in the Contractor's Correction Punch List for Contractor's Notice of Substantial Completion.
C. Notify Architect when work is considered ready for Architect's Substantial Completion inspection.

D. Submit written certification containing Contractor's Correction Punch List, that Contract Documents have been reviewed, work has been inspected, and that work is complete in accordance with Contract Documents and ready for Architect's Substantial Completion inspection.
E. Conduct Substantial Completion inspection and create Final Correction Punch List containing Architect's and Contractor's comprehensive list of items identified to be completed or corrected and submit to Architect.
F. Correct items of work listed in Final Correction Punch List and comply with requirements for access to Owner-occupied areas.
G. Notify Architect when work is considered finally complete and ready for Architect's Substantial Completion final inspection.
H. Complete items of work determined by Architect listed in executed Certificate of Substantial Completion.

3.15 MAINTENANCE

A. Provide service and maintenance of components indicated in specification sections.
B. Maintenance Period: As indicated in specification sections or, if not indicated, not less than one year from the Date of Substantial Completion or the length of the specified warranty, whichever is longer.
C. Examine system components at a frequency consistent with reliable operation. Clean, adjust, and lubricate as required.
D. Include systematic examination, adjustment, and lubrication of components. Repair or replace parts whenever required. Use parts produced by the manufacturer of the original component.
E. Maintenance service shall not be assigned or transferred to any agent or subcontractor without prior written consent of the Owner.

END OF SECTION

SECTION 01 7329 - CUTTING AND PATCHING

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Cutting and patching.

1.02 REFERENCE STANDARDS

A. NFPA 241 - Standard for Safeguarding Construction, Alteration, and Demolition Operations; 2013.

1.03 SUBMITTALS

A. See Section 01 3000 - Administrative Requirements, for submittal procedures.

B. Cutting and Patching: Submit written request in advance of cutting or alteration that affects:

1. Structural integrity of any element of Project.
2. Integrity of weather exposed or moisture resistant element.
3. Efficiency, maintenance, or safety of any operational element.
4. Visual qualities of sight exposed elements.
5. Work of Owner or separate Contractor.
6. Include in request:
   a. Location and description of affected work.
   b. Necessity for cutting or alteration.
   c. Description of proposed work and products to be used.
   d. Effect on work of Owner or separate Contractor.

C. Warranties: For each affected material under warranty, submit written verification, signed by manufacturer of existing materials, stating that the Owner's full warranty will remain in effect after cutting and patching operations have been completed.

1.04 WARRANTIES

A. Existing Warranties: Remove, replace, patch, and repair materials and surfaces cut or damaged during cutting and patching operations, by methods and with materials so as not to void existing warranties.

1. Materials that are still under warranty include, but are not limited to, the following:
   a. _____.
   b. _____.
   c. _____.

PART 2 PRODUCTS

2.01 PATCHING MATERIALS

A. New Materials: As specified in product sections; match existing products and work for patching and extending work.

B. Type and Quality of Existing Products: Determine by inspecting and testing products where necessary, referring to existing work as a standard.

C. Product Substitution: For any proposed change in materials, submit request for substitution described in Section 01 6000 - Product Requirements.

PART 3 EXECUTION

3.01 EXAMINATION

A. Prior to Cutting: Examine existing conditions prior to commencing work, including elements subject to damage or movement during cutting and patching. After uncovering existing work, assess conditions affecting performance of work. Beginning of cutting or patching means acceptance of existing conditions.

B. Prior to Patching: Before patching, verify compatibility and suitability of substrates, including compatibility with existing finishes or primers. Beginning of patching means acceptance of existing conditions.

3.02 PREPARATION

A. Clean substrate surfaces prior to applying next material or substance.
B. Seal cracks or openings of substrate prior to applying next material or substance.
C. Apply manufacturer required or recommended substrate primer, sealer, or conditioner prior to applying any new material or substance in contact or bond.
D. Protect existing work to remain.
    1. Prevent movement of structure; provide shoring and bracing if necessary.
    2. Perform cutting to accomplish removals neatly and as specified for cutting new work.
E. Existing Services: Where existing services are required to be removed, relocated, or abandoned, bypass such services before cutting to avoid interruption of services to occupied areas.

3.03 CUTTING AND PATCHING

A. Whenever possible, execute the work by methods that avoid cutting or patching.
B. Perform whatever cutting and patching is necessary to:
    1. Complete the work.
    2. Fit products together to integrate with other work.
    3. Provide openings for penetration of mechanical, electrical, and other services.
    4. Match work that has been cut to adjacent work.
    5. Repair areas adjacent to cuts to required condition.
    6. Repair new work damaged by subsequent work.
    7. Remove samples of installed work for testing when requested.
    8. Remove and replace defective and non-conforming work.
C. Execute work by methods that avoid damage to other work and that will provide appropriate surfaces to receive patching and finishing. In existing work, minimize damage and restore to original condition.
D. Employ skilled and experienced installer to perform cutting for weather exposed and moisture resistant elements, and sight exposed surfaces.
E. Cutting:
    1. In general, use hand or small power tools designed for sawing and grinding, not hammering and chopping. Cut holes and slots as small as possible, neatly to size required, and with minimum disturbance of adjacent surfaces.
    2. Cut rigid materials using masonry saw or core drill. Pneumatic tools not allowed without prior approval.
    3. Mechanical and Electrical Services: Cut off pipe or conduit in walls or partitions to be removed. Cap, valve, or plug and seal remaining portion of pipe or conduit to prevent entrance of moisture or other foreign matter after cutting.
F. Restore work with new products in accordance with requirements of Contract Documents.
G. Fit work air tight to pipes, sleeves, ducts, conduit, and other penetrations through surfaces.
H. At penetrations of fire rated walls, partitions, ceiling, or floor construction, completely seal voids with fire rated material in accordance with Section 07 8400 - Firestopping, to full thickness of the penetrated element.
I. Patching:
    1. Repair adjacent construction and finishes damaged during removal work and cutting work.
    2. Finish patched surfaces to match finish that existed prior to patching. On continuous surfaces, refinish to nearest intersection or natural break. For an assembly, refinish entire unit.
        a. This includes painted surfaces.
        b. Where the surface is indicated to be refinished, patch so that the substrate is ready for the new finish.
    3. Match color, texture, and appearance.

4. Repair patched surfaces that are damaged, lifted, discolored, or showing other imperfections due to patching work. If defects are due to condition of substrate, repair substrate prior to repairing finish.

END OF SECTION

SECTION 01 7800 - CLOSEOUT SUBMITTALS

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Project record documents.
B. Operation and maintenance data.
C. Warranties and bonds.

1.02 SUBMITTALS

A. Project Record Documents: Submit documents to Architect with claim for final Application for Payment.
B. Operation and Maintenance Data:
   1. Submit two copies of preliminary draft or proposed formats and outlines of contents before start of Work. Architect will review draft and return one copy with comments.
   2. For equipment, or component parts of equipment put into service during construction and operated by Owner, submit completed documents within ten days after acceptance.
   3. Submit one copy of completed documents 15 days prior to final inspection. This copy will be reviewed and returned after final inspection, with Architect comments. Revise content of all document sets as required prior to final submission.
   4. Submit two sets of revised final documents in final form within 10 days after final inspection.
C. Warranties and Bonds:
   1. For equipment or component parts of equipment put into service during construction with Owner's permission, submit documents within 10 days after acceptance.
   2. Make other submittals within 10 days after Date of Substantial Completion, prior to final Application for Payment.
   3. For items of Work for which acceptance is delayed beyond Date of Substantial Completion, submit within 10 days after acceptance, listing the date of acceptance as the beginning of the warranty period.

PART 2 PRODUCTS - NOT USED

PART 3 EXECUTION

3.01 PROJECT RECORD DOCUMENTS

A. General:
   1. Project Record Documents include:
      a. Complete set of Record Drawings.
      b. Complete set of Record Submittals.
      c. Complete set of Specifications.
   2. Project Record Documents shall be submitted in electronic form.
      a. File Format: Portable Document Format (PDF).
      b. Files shall be named and organized in a searchable, easy to understand, system.
   3. Ensure entries are complete and accurate, enabling future reference by Owner.
   4. Record information concurrent with construction progress.
B. Record Drawings: Record Drawings shall include the following:
   1. Complete set of Drawings.
      a. Indicate and record actual construction including, but not limited to, the following:
         1) Show all systems and assemblies as they exist at completion of the Work.
         2) Measured horizontal and vertical locations of underground utilities and appurtenances, referenced to permanent surface improvements.
         3) Measured locations of internal utilities and appurtenances concealed in construction, referenced to visible and accessible features of the Work.
         4) Field changes of dimension and detail.
         5) Details not on original Contract drawings.
   2. Addenda.
   3. Change Orders and other modifications to the Contract.

C. Record Submittals: Record Submittals shall include the following:
   1. Complete set of Submittals, including resubmittals.
   2. Shop Drawings shall indicate all field changes and other variations from the Submittal as originally reviewed by Architect.
D. Specifications: Specifications shall include the following:
   1. Complete Project Manual including all specifications, front end material, reports, and information available to bidders, as originally bid.
   2. Addenda.
   3. Change Orders and other modifications to the Contract.

3.02 OPERATION AND MAINTENANCE DATA

A. Source Data: For each product or system, list names, addresses and telephone numbers of Subcontractors and suppliers, including local source of supplies and replacement parts.
B. Product Data: Mark each sheet to clearly identify specific products and component parts, and data applicable to installation. Delete inapplicable information.
C. Drawings: Supplement product data to illustrate relations of component parts of equipment and systems, to show control and flow diagrams. Do not use Project Record Documents as maintenance drawings.
D. Typed Text: As required to supplement product data. Provide logical sequence of instructions for each procedure, incorporating manufacturer's instructions.

3.03 OPERATION AND MAINTENANCE DATA FOR MATERIALS AND FINISHES

A. For Each Product, Applied Material, and Finish:
   1. Product data, with catalog number, size, composition, and color and texture designations.
B. Instructions for Care and Maintenance: Manufacturer's recommendations for cleaning agents and methods, precautions against detrimental cleaning agents and methods, and recommended schedule for cleaning and maintenance.
C. Additional information as specified in individual product specification sections.
D. Where additional instructions are required, beyond the manufacturer's standard printed instructions, have instructions prepared by personnel experienced in the operation and maintenance of the specific products.

3.04 OPERATION AND MAINTENANCE DATA FOR EQUIPMENT AND SYSTEMS

A. For Each Item of Equipment and Each System:
   1. Description of unit or system, and component parts.
   2. Identify function, normal operating characteristics, and limiting conditions.
   3. Include performance curves, with engineering data and tests.
   4. Complete nomenclature and model number of replaceable parts.
B. Where additional instructions are required, beyond the manufacturer's standard printed instructions, have instructions prepared by personnel experienced in the operation and maintenance of the specific products.
C. Panelboard Circuit Directories: Provide electrical service characteristics, controls, and communications; typed.
D. Include color coded wiring diagrams as installed.
E. Operating Procedures: Include start-up, break-in, and routine normal operating instructions and sequences. Include regulation, control, stopping, shut-down, and emergency instructions. Include summer, winter, and any special operating instructions.
F. Maintenance Requirements: Include routine procedures and guide for preventative maintenance and trouble shooting; disassembly, repair, and reassembly instructions; and alignment, adjusting, balancing, and checking instructions.
G. Provide servicing and lubrication schedule, and list of lubricants required.
H. Include manufacturer's printed operation and maintenance instructions.

I. Include sequence of operation by controls manufacturer.
J. Provide original manufacturer's parts list, illustrations, assembly drawings, and diagrams required for maintenance.
K. Provide control diagrams by controls manufacturer as installed.
L. Provide charts of valve tag numbers, with location and function of each valve, keyed to flow and control diagrams.
M. Include test and balancing reports.
N. Additional Requirements: As specified in individual product specification sections.

3.05 ASSEMBLY OF OPERATION AND MAINTENANCE MANUALS

A. General:
   1. Operational and Maintenance Manuals include:
      a. Operational and maintenance data.
      b. Operational and maintenance data for materials and finishes.
      c. Operational and maintenance data for equipment and systems.
   2. Operational and Maintenance Manuals shall be submitted both in electronic form and as hard copy/durable manuals.
      a. Subject to Owner approval, hard copy/durable manuals may be omitted.
      b. Electronic File Format: Portable Document Format (PDF).
         1) Files shall be named and organized in a searchable, easy to understand, system similar to the descriptions for the hard copy/durable manuals
B. Assemble operation and maintenance data into durable manuals for Owner's personnel use, with data arranged in the same sequence as, and identified by, the specification sections.
C. Where systems involve more than one specification section, provide separate tabbed divider for each system.
D. Binders: Commercial quality, 8-1/2 by 11 inch three D side ring binders with durable plastic covers; 3 inch maximum ring size. When multiple binders are used, correlate data into related consistent groupings.
E. Cover: Identify each binder with typed or printed title OPERATION AND MAINTENANCE INSTRUCTIONS; identify title of Project; identify subject matter of contents.
F. Project Directory: Title and address of Project; names, addresses, and telephone numbers of Architect, Consultants, Contractor and subcontractors, with names of responsible parties.
G. Tables of Contents: List every item separated by a divider, using the same identification as on the divider tab; where multiple volumes are required, include all volumes Tables of Contents in each volume, with the current volume clearly identified.
H. Dividers: Provide tabbed dividers for each separate product and system; identify the contents on the divider tab; immediately following the divider tab include a description of product and major component parts of equipment.
I. Text: Manufacturer's printed data, or typewritten data on 20 pound paper.
J. Drawings: Provide with reinforced punched binder tab. Bind in with text; fold larger drawings to size of text pages.
K. Arrangement of Contents: Organize each volume in parts as follows:
   1. Project Directory.
   2. Table of Contents, of all volumes, and of this volume.
   3. Operation and Maintenance Data: Arranged by system, then by product category.
      a. Source data.
      b. Operation and maintenance data.
      c. Field quality control data.
      d. Photocopies of warranties and bonds.

3.06 WARRANTIES AND BONDS

A. Obtain warranties and bonds, executed in duplicate by responsible Subcontractors, suppliers, and manufacturers, within 10 days after completion of the applicable item of work. Except for items put into use with Owner's permission, leave date of beginning of time of warranty until Date of Substantial completion is determined.

B. Verify that documents are in proper form, contain full information, and are notarized.

C. Co-execute submittals when required.

D. Retain warranties and bonds until time specified for submittal.

E. Manual: Bind in commercial quality 8-1/2 by 11 inch three D side ring binders with durable plastic covers.

F. Cover: Identify each binder with typed or printed title WARRANTIES AND BONDS, with title of Project; name, address and telephone number of Contractor and equipment supplier; and name of responsible company principal.

G. Table of Contents: Neatly typed, in the sequence of the Table of Contents of the Project Manual, with each item identified with the number and title of the specification section in which specified, and the name of product or work item.

H. Separate each warranty or bond with index tab sheets keyed to the Table of Contents listing. Provide full information, using separate typed sheets as necessary. List Subcontractor, supplier, and manufacturer, with name, address, and telephone number of responsible principal.

END OF SECTION

SECTION 02 4100 - DEMOLITION

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Selective demolition of building elements for alteration purposes.
B. Removed and reinstalled items.

1.02 RELATED REQUIREMENTS

A. Section 04 2000 - Unit Masonry: Salvaging existing brick.
B. Section 31 2323 - Fill: Filling holes, pits, and excavations generated as a result of removal operations.

1.03 REFERENCE STANDARDS

A. NFPA 241 - Standard for Safeguarding Construction, Alteration, and Demolition Operations; 2022, with Errata (2021).

1.04 SUBMITTALS

A. See Section 01 3000 - Administrative Requirements, for submittal procedures.

1.05 QUALITY ASSURANCE

A. Demolition Firm Qualifications: Company specializing in the type of work required.
   1. Minimum of 5 years of documented experience.

PART 2 PRODUCTS - NOT USED

2.01 MATERIALS

PART 3 EXECUTION

3.01 SCOPE

A. Remove portions of existing building as indicated on Drawings including, but not limited to, the following:
   1. Remove other items indicated, for salvage and relocation.

3.02 GENERAL PROCEDURES AND PROJECT CONDITIONS

A. Comply with other requirements specified in Section 01 7000.
B. Comply with applicable codes and regulations for demolition operations and safety of adjacent structures and the public.
   1. Obtain required permits.
   2. Comply with applicable requirements of NFPA 241.
   3. Prior to start of demolition operations, perform an engineering survey of building condition to determine whether removing any element might result in structural deficiency or unplanned collapse of any portion of structure or adjacent structures.
   4. Use of explosives is not permitted.
   5. Take precautions to prevent catastrophic or uncontrolled collapse of structures to be removed; do not allow worker or public access within range of potential collapse of unstable structures.
   6. Provide, erect, and maintain temporary barriers and security devices.
   7. Conduct operations to minimize effects on and interference with adjacent structures and occupants.
   8. Do not close or obstruct roadways or sidewalks without permit.
   9. Conduct operations to minimize obstruction of public and private entrances and exits; do not obstruct required exits at any time; protect persons using entrances and exits from removal operations.
   10. Obtain written permission from owners of adjacent properties when demolition equipment will traverse, infringe upon or limit access to their property.
C. Do not begin removal until receipt of notification to proceed from Owner.
D. Do not begin removal until built elements to be salvaged or relocated have been removed.
E. Protect existing structures and other elements that are not to be removed.
   1. Provide bracing and shoring.

2. Prevent movement or settlement of adjacent structures.
3. Stop work immediately if adjacent structures appear to be in danger.

F. Minimize production of dust due to demolition operations; do not use water if that will result in ice, flooding, sedimentation of public waterways or storm sewers, or other pollution.

G. If hazardous materials are discovered during removal operations, stop work and notify Architect and Owner; hazardous materials include regulated asbestos containing materials, PCB's, and mercury.

H. Partial Removal of Paving and Curbs: Neatly saw cut at right angle to surface.

3.03 SELECTIVE DEMOLITION FOR ALTERATIONS

A. Drawings showing existing construction and utilities are based on casual field observation and existing record documents only.
1. Verify that construction and utility arrangements are as indicated.
2. Report discrepancies to Architect before disturbing existing installation.
3. Beginning of demolition work constitutes acceptance of existing conditions that would be apparent upon examination prior to starting demolition.

B. Separate areas in which demolition is being conducted from other areas that are still occupied.
1. Provide, erect, and maintain temporary dustproof partitions of construction as specified and/or indicated on Drawings .

C. Maintain weatherproof exterior building enclosure except for interruptions required for replacement or modifications; take care to prevent water and humidity damage.

D. Remove existing work as indicated and as required to accomplish new work.
1. Remove items indicated on Drawings.

E. Services (Including but not limited to HVAC and Electrical): Remove existing systems and equipment as indicated.
1. Maintain existing active systems that are to remain in operation; maintain access to equipment and operational components.
2. Where existing active systems serve occupied facilities but are to be replaced with new services, maintain existing systems in service until new systems are complete and ready for service.
3. Verify that abandoned services serve only abandoned facilities before removal.
4. Remove abandoned pipe, ducts, conduits, and equipment, including those above accessible ceilings; remove back to source of supply where possible, otherwise cap stub and tag with identification.

F. Protect existing work to remain.
1. Prevent movement of structure; provide shoring and bracing if necessary.
2. Perform cutting to accomplish removals neatly and as specified for cutting new work.
3. Repair adjacent construction and finishes damaged during removal work.
4. Patch as specified for patching new work.

3.04 SALVAGED ITEMS

A. Clean salvaged items.

B. Pack or crate items after cleaning. Identify contents of containers.

C. Store items in a secure area until delivery to Owner.

D. Transport items to Owner's storage area on-site.

E. Protect items from damage during transport and storage.

3.05 REMOVED AND REINSTALLED ITEMS

A. Clean and repair items to functional condition adequate for intended reuse.

B. Pack or crate items after cleaning and repairing. Identify contents of containers.

C. Protect items from damage during transport and storage.

D. Reinstall items in locations indicated. Comply with installation requirements for new materials and equipment. Provide connections, supports, and miscellaneous materials necessary to make item functional for use indicated.

3.06 EXISTING ITEMS TO REMAIN

A. Protect construction indicated to remain against damage and soiling during selective demolition. When permitted by Architect, items may be removed to a suitable, protected storage location during selective demolition and cleaned and reinstalled in their original locations after selective demolition operations are complete

3.07 DEBRIS AND WASTE REMOVAL

A. Remove debris, junk, and trash from site.
B. Leave site in clean condition, ready for subsequent work.
C. Clean up spillage and wind-blown debris from public and private lands.

END OF SECTION

SECTION 06 1000 - ROUGH CARPENTRY

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Nonstructural dimension lumber framing.
B. Preservative treated wood materials.
C. Fire retardant treated wood materials.
D. Miscellaneous framing and sheathing.
E. Concealed wood blocking, nailers, and supports.
F. Miscellaneous wood nailers, furring, and grounds.

1.02 REFERENCE STANDARDS

A. AWC (WFCM) - Wood Frame Construction Manual for One- and Two-Family Dwellings; 2024, with Errata.
B. ASTM C557 - Standard Specification for Adhesives for Fastening Gypsum Wallboard to Wood Framing; 2003 (Reapproved 2017).
C. ASTM D2898 - Standard Practice for Accelerated Weathering of Fire-Retardant-Treated Wood for Fire Testing; 2010 (Reapproved 2017).
D. ASTM D3498 - Standard Specification for Adhesives for Field-Gluing Wood Structural Panels (Plywood or Oriented Strand Board) to Wood Based Floor System Framing; 2019a.
E. ASTM E84 - Standard Test Method for Surface Burning Characteristics of Building Materials; 2023d.
F. AWPA U1 - Use Category System: User Specification for Treated Wood; 2023.
G. PS 20 - American Softwood Lumber Standard; 2021.

1.03 SUBMITTALS

A. See Section 01 3000 - Administrative Requirements for submittal procedures.
B. Product Data: Provide technical data on insulated sheathing, wood preservative materials, and application instructions.
C. Manufacturer's Certificate: Certify that wood products supplied for rough carpentry meet or exceed specified requirements.

1.04 DELIVERY, STORAGE, AND HANDLING

A. General: Cover wood products to protect against moisture. Support stacked products to prevent deformation and to allow air circulation.

PART 2 PRODUCTS

2.01 GENERAL REQUIREMENTS

A. Dimension Lumber: Comply with PS 20 and requirements of specified grading agencies.
    1. Species: Unless otherwise indicated, provide any species graded by the agency specified; if no grading agency is specified, provide lumber graded by any grading agency meeting the specified requirements.
    2. Grading Agency: Grading agency whose rules are approved by the Board of Review, American Lumber Standard Committee at www.alsc.org, and who provides grading service for the species and grade specified; provide lumber stamped with grade mark unless otherwise indicated.

2.02 DIMENSION LUMBER

A. Sizes: Nominal sizes as indicated on drawings, S4S.
B. Moisture Content: Kiln-dry or MC15.
C. Stud Framing (2 by 2 through 2 by 6):
    1. Species: Southern Pine.
    2. Grade: No. 2.
D. Stud Framing Framing (2 by 6 through 4 by 16):
    1. Species: Southern Pine.

2. Grade: No. 2.

E. Miscellaneous Framing, Blocking, Nailers, Grounds, and Furring:
1. Lumber: S4S, No. 2 or Standard Grade.
2. Boards: Grade No. 2.

2.03 ACCESSORIES

A. Fasteners and Anchors:
1. Metal and Finish: Stainless steel for high humidity and preservative-treated wood locations, unfinished steel elsewhere.
2. Drywall Screws: Bugle head, hardened steel, power driven type, length three times thickness of sheathing.
3. Anchors:
a. Toggle bolt type for anchorage to hollow masonry.
b. Expansion shield and lag bolt type for anchorage to solid masonry or concrete.
c. Bolt or ballistic fastener for anchorages to steel

B. Construction Adhesives: Adhesives complying with ASTM C557 or ASTM D3498.
1. Manufacturers:
a. Franklin International, Inc; Titebond GREENchoice Heavy Duty Construction Adhesive: www.titebond.com.
b. Liquid Nails, a brand of PPG Industries, Inc.; LN-903 Heavy Duty Construction Adhesive (Low VOC): www.liquidnails.com.
c. Substitutions: See Section 01 6000 - Product Requirements.

2.04 FACTORY WOOD TREATMENT

A. Treated Lumber and Plywood: Comply with requirements of AWPA U1 - Use Category System for wood treatments determined by use categories, expected service conditions, and specific applications.
1. Fire-Retardant Treated Wood: Mark each piece of wood with producer's stamp indicating compliance with specified requirements.
2. Preservative-Treated Wood: Provide lumber and plywood marked or stamped by an ALSC-accredited testing agency, certifying level and type of treatment in accordance with AWPA standards.

B. Fire Retardant Treatment:
1. Manufacturers:
a. Lonza Group: www.wolmanizedwood.com.
b. Hoover Treated Wood Products, Inc: www.frtw.com.
c. Koppers, Inc: www.koppersperformancechemicals.com.
d. Viance, LLC: www.treatedwood.com.
e. Substitutions: See Section 01 6000 - Product Requirements.
2. Exterior Type: AWPA U1, Category UCFB, Commodity Specification H, chemically treated and pressure impregnated; capable of providing a maximum flame spread index of 25 when tested in accordance with ASTM E84, with no evidence of significant combustion when test is extended for an additional 20 minutes both before and after accelerated weathering test performed in accordance with ASTM D2898.
a. Kiln dry wood after treatment to a maximum moisture content of 19 percent for lumber and 15 percent for plywood.
b. Treat lumber in locations as indicated

C. Preservative Treatment:
1. Manufacturers:
a. Lonza Group: www.wolmanizedwood.com.
b. Hoover Treated Wood Products, Inc: www.frtw.com.
c. Koppers Performance Chemicals, Inc: www.koppersperformancechemicals.com.
d. Viance, LLC: www.treatedwood.com.
e. Substitutions: See Section 01 6000 - Product Requirements.

2. Preservative Pressure Treatment of Lumber Above Grade: AWPA U1, Use Category UC3B, Commodity Specification A using waterborne preservative.
   a. Kiln dry lumber after treatment to maximum moisture content of 19 percent.
   b. Treat lumber exposed to weather.
   c. Treat lumber in contact with roofing, flashing, or waterproofing.
      1) At Contractor's option, roof nailers may be non-preservative treated.
   d. Treat lumber in contact with masonry or concrete.
   e. Treat lumber less than 18 inches above grade.
   f. Treat lumber in other locations as indicated.
3. Preservative Pressure Treatment of Plywood Above Grade: AWPA U1, Use Category UC2 and UC3B, Commodity Specification F using waterborne preservative.
   a. Kiln dry plywood after treatment to maximum moisture content of 19 percent.
   b. Treat plywood in contact with roofing, flashing, or waterproofing.
   c. Treat plywood in contact with masonry or concrete.
   d. Treat plywood less than 18 inches above grade.
   e. Treat plywood in other locations as indicated.
4. Preservative Pressure Treatment of Lumber in Contact with Soil: AWPA U1, Use Category UC4A, Commodity Specification A using waterborne preservative.
5. Preservative for Field Application to Cut Surfaces: As recommended by manufacturer of factory treatment chemicals for brush-application in the field.

PART 3 EXECUTION

3.01 PREPARATION

A. Install sill gasket under sill plate of framed walls bearing on foundations; puncture gasket cleanly to fit tightly around protruding anchor bolts.

3.02 INSTALLATION - GENERAL

A. Select material sizes to minimize waste.
B. Reuse scrap to the greatest extent possible; clearly separate scrap for use on site as accessory components, including: shims, bracing, and blocking.
C. Where treated wood is used on interior, provide temporary ventilation during and immediately after installation sufficient to remove indoor air contaminants.

3.03 FRAMING INSTALLATION

A. Set structural members level, plumb, and true to line. Discard pieces with defects that would lower required strength or result in unacceptable appearance of exposed members.
B. Make provisions for temporary construction loads, and provide temporary bracing sufficient to maintain structure in true alignment and safe condition until completion of erection and installation of permanent bracing.
C. Install structural members full length without splices.
D. Comply with member sizes, spacing, and configurations indicated, and fastener size and spacing indicated, but not less than required by applicable codes and AWC (WFCM) Wood Frame Construction Manual.
E. Install horizontal spanning members with crown edge up and not less than 3 inches of bearing at each end.
F. Construct double joist headers at floor and ceiling openings and under wall stud partitions that are parallel to floor joists; use metal joist hangers unless otherwise detailed.
G. Provide bridging at framing in excess of 8 feet span at mid-span and as detailed. Fit solid blocking at ends of members.
H. Frame wall openings with two or more studs at each jamb; support headers on cripple studs.

3.04 MISCELLANEOUS FRAMING

A. Install miscellaneous framing level, plumb, and true to line.

B. Comply with member sizes, spacing, and configurations indicated, and fastener size and spacing indicated, but not less than required by applicable codes and AWC (WFCM) Wood Frame Construction Manual.
C. Install horizontal spanning members with crown edge up and not less than 3 inches of bearing at each end.

3.05 BLOCKING, NAILERS, AND SUPPORTS

A. Provide framing and blocking members as indicated or as required to support finishes, fixtures, specialty items, and trim.
B. In walls, provide blocking attached to studs as backing and support for wall-mounted items, unless item can be securely fastened to two or more studs or other method of support is explicitly indicated.
C. Provide the following specific nonstructural framing and blocking:
    1. Cabinets and shelf supports.
    2. Wall brackets.
    3. Handrails.
    4. Grab bars.
    5. Towel and bath accessories.
    6. Other locations as indicated.

3.06 SITE APPLIED WOOD TREATMENT

A. Apply preservative treatment compatible with factory applied treatment at site-sawn cuts, complying with manufacturer's instructions.
B. Allow preservative to dry prior to erecting members.

3.07 TOLERANCES

A. Framing Members: 1/4 inch from true position, maximum.
B. Variation from Plane, Other than Floors: 1/4 inch in 10 feet maximum, and 1/4 inch in 30 feet maximum.

3.08 CLEANING

A. Do not leave wood, shavings, sawdust, etc. on the ground or buried in fill.
B. Prevent sawdust and wood shavings from entering the storm drainage system.

END OF SECTION

SECTION 07 4213 - METAL WALL PANELS

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Manufactured metal panels for soffits, with related flashings and accessory components.

1.02 REFERENCE STANDARDS

A. AAMA 2605 - Voluntary Specification, Performance Requirements and Test Procedures for Superior Performing Organic Coatings on Aluminum Extrusions and Panels (with Coil Coating Appendix); 2022.
B. ASTM B209 - Standard Specification for Aluminum and Aluminum-Alloy Sheet and Plate; 2014.
C. ASTM B209M - Standard Specification for Aluminum and Aluminum-Alloy Sheet and Plate (Metric); 2014.

1.03 SUBMITTALS

A. See Section 01 3000 - Administrative Requirements for submittal procedures.
B. Product Data: Manufacturer's data sheets on each product to be used.
C. Shop Drawings: Indicate dimensions, layout, joints, construction details, and methods of anchorage.
D. Samples: Submit three samples of soffit panel, 12 inch by 6 inch in size illustrating finish color, sheen, and texture.

1.04 QUALITY ASSURANCE

A. Manufacturer Qualifications: Company specializing in manufacturing the products specified in this section with minimum 5 years of documented experience.
B. Installer Qualifications: Company specializing in installing products of the type specified in this section with minimum 5 years of documented experience and approved by manufacturer.

1.05 MOCK-UP

A. Construct mock-up, 10 feet long by 10 feet wide; include panel and soffit system, attachments to building frame, associated vapor retarder and air seal materials, weep drainage system, sealants and seals, related insulation in mock-up.
B. Locate where directed by Architect.

1.06 DELIVERY, STORAGE, AND HANDLING

A. Protect panels from accelerated weathering by removing or venting plastic shipping sheet wrap.
B. Store prefinished material off the ground and protected from weather; prevent twisting, bending, or abrasion; provide ventilation; slope metal sheets to ensure proper drainage.
C. Prevent contact with materials that may cause discoloration or staining of products.

1.07 WARRANTY

A. See Section 01 7800 - Closeout Submittals for additional warranty requirements.
B. Correct defective work within a twenty year period after Date of Substantial Completion for degradation of panel finish, including color fading caused by exposure to weather.
C. Correct defective work within a five year period after Date of Substantial Completion, including defects in water tightness and integrity of seals for metal wall panels.

PART 2 PRODUCTS

2.01 MANUFACTURED METAL PANELS - GENERAL

A. Wall Panel System: Factory fabricated prefinished metal panel system, site assembled.
    1. Provide soffit panels.
    2. Design and size components to support assembly dead loads, and to withstand live loads caused by positive and negative wind pressure acting normal to plane of wall.
    3. Maximum Allowable Deflection of Panel: L/180 for length(L) of span.

4. Movement: Accommodate movement within system without damage to components or deterioration of seals, movement between system and perimeter components when subject to seasonal temperature cycling; dynamic loading and release of loads; and deflection of structural support framing.
5. Drainage: Provide positive drainage to exterior for moisture entering or condensation occurring within panel system.
6. Fabrication: Formed true to shape, accurate in size, square, and free from distortion or defects; pieces of longest practical lengths.
7. Corners: Factory-fabricated in one continuous piece with minimum 2 inch returns.

2.02 SOFFIT PANELS - CONCEALED FASTENERS

A. Flush Panels:
1. Profile: Flush flat.
2. Panel Coverage (Width): 6 inches.
3. Panel Depth: 3/8 inches - 5/8 inches.
4. Panel Reveal: None.
5. Material: Precoated extruded aluminum, 16 gage, 0.065 inch minimum thickness.
6. Side Laps: Manufacturers standard interlocking seam with flange for concealed screw fastening to sub-frame.
7. End Laps: Back-to-back extruded "J" Trim..
8. Fasteners: Concealed stainless steel screws, at intervals as indicated.
9. Panel Surface: Smooth.
10. Vented Planks: 6-inch-wide interlocking plank matching profile and finish and field planks with punched slots.
    a. Element Model No.: KECV150 Vented Cladding.
11. Provide for normal expansion and contraction. Indicate jointing on shop drawings.
12. Color: Woodgrain matching Manufacturer's "Eastern Mahogany".
    a. Pretreat Aluminum to AAMA 2604 Performance Standard
13. Basis-of-Design: Knotwood Wood Grain Extruded Aluminum Cladding, Trim and Accessories with aluminate bonded finish
    a. Substitutions: Not permitted.
14. Alternate No. 1: Panel Alternate:
    a. Parallel Architectural Products extruded cladding board:
        1) Regular Interlocking Plank: Profile: CB-6.
        2) Vented Interlocking Plank: Profile C-B6V
        3) Width: 6 inches. (152mm)
        4) Depth: 5/8 inches (16mm)
        5) Finish: Woodgrain - Selected from the manufacturer’s full range of 37 colors.
        6) Trim: Starter (C-STR) and termination (C-TTF) pieces.
        7) Provide trim elements matching details indicated and Basis of Design system.
        8) Provide for normal expansion and contraction of the soffit. Indicate jointing on shop drawings

2.03 MISCELLANEOUS

A. Internal and External Corners: Same material, thickness, and finish as wall panels and soffit panels; profile to suit system;shop cut and factory mitered to required angles.
B. Expansion Joints: Same material, thickness and finish as wall panels and soffit panels; manufacturer's standard type, of profile to suit system.
C. Trim, Closure Pieces, Caps, and Flashings: Same material, thickness and finish as wall panels and soffit panels; brake formed to required profiles.
D. Anchors: Stainless steel.

2.04 MATERIALS

A. Precoated Aluminum Sheet: ASTM B209 (ASTM B209M), 3105 alloy, O temper, smooth surface texture; continuous-coil-coated on exposed surfaces with specified finish coating and on panel back with specified panel back coating.
   1. Restricted to flashings as detailed.

B. Exstruded Aluminum

2.05 FINISHES

A. Fluoropolymer Coil Coating System: Manufacturer's standard multi-coat aluminum coil coating system complying with AAMA 2605, including at least 70 percent polyvinylidene fluoride (PVDF) resin, and at least 80 percent of coil coated aluminum surfaces having minimum total dry film thickness (DFT) of 0.9 mil, 0.0009 inch.
   1. Color: Custom color to match Architect's sample.

2.06 ACCESSORIES

A. Concealed Sealants: Non-curing butyl sealant or tape sealant.

B. Exposed Sealants: Refer to Section 07 9200 - Joint Sealants.

C. Fasteners: Manufacturer's standard type to suit application; with soft neoprene washers, steel, hot dip galvanized. Exposed fasteners same finish as panel system.

D. Field Touch-up Paint: As recommended by panel manufacturer.

E. Bituminous Paint: Asphalt base.

PART 3 EXECUTION

3.01 EXAMINATION

A. Verify that structural substrate is ready to receive panel system.

B. Verify that weather barrier has been installed over substrate completely and correctly.

3.02 INSTALLATION

A. Install panels on walls and soffits in accordance with manufacturer's instructions.

B. Protect surfaces in contact with cementitious materials and dissimilar metals with bituminous paint. Allow to dry prior to installation.

C. Fasten panels to structural supports; aligned, level, and plumb.

D. Lap panel ends minimum 2 inches.

E. Provide expansion and control joints where indicated.

3.03 TOLERANCES

A. Maximum Offset From True Alignment Between Adjacent Members Butting or In Line: 1/16 inch.

B. Maximum Variation from Plane or Location Indicated on Drawings: 1/8 inch.

3.04 CLEANING

A. Remove site cuttings from finish surfaces.

B. Remove protective material from wall panel surfaces.

C. Clean and wash prefinished surfaces with mild soap and water; rinse with clean water.

END OF SECTION

SECTION 07 6200 - SHEET METAL FLASHING AND TRIM

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Formed sheet metal items, including, but not limited to, the following:
   1. Flashings.
   2. Counterflashings.
   3. Other items as indicated on Drawings.

B. Manufactured reglets.

1.02 REFERENCE STANDARDS

A. AAMA 2605 - Voluntary Specification, Performance Requirements and Test Procedures for Superior Performing Organic Coatings on Aluminum Extrusions and Panels (with Coil Coating Appendix); 2022.

B. ASTM B32 - Standard Specification for Solder Metal; 2020.

C. ASTM C920 - Standard Specification for Elastomeric Joint Sealants; 2018.

D. FM DS 1-49 - FM Global Property Loss Prevention Data Sheet - Perimeter Flashing; 2016.

E. NRCA (RM) - The NRCA Roofing Manual; 2023.

F. SMACNA (ASMM) - Architectural Sheet Metal Manual; 2012.

1.03 ADMINISTRATIVE REQUIREMENTS

A. Preinstallation Meeting: Convene one week before starting work of this section.

1.04 SUBMITTALS

A. See Section 01 3000 - Administrative Requirements for submittal procedures.

B. Shop Drawings: Indicate material profile, jointing pattern, jointing details, fastening methods, flashings, terminations, and installation details.

C. Samples:
   1. For each material and finish, submit three samples 4 by 4 inch in size illustrating metal finish color.
   2. Reglets: Submit three samples, 4 inches long, full size, of each type and finish.

1.05 QUALITY ASSURANCE

A. Perform work in accordance with SMACNA (ASMM) requirements, except as otherwise indicated.

B. Fabricator and Installer Qualifications: Company specializing in sheet metal work with 5 years of documented experience.

1.06 MOCK-UP

A. Mockups: Build mockups to verify selections made under Sample submittals, to demonstrate aesthetic effects, and to set quality standards for materials and execution.
   1. Build mockup of typical wall flashing with counterflashing, approximately 10 feet long, including supporting construction cleats, seams, attachments and accessories.
   2. Locate where directed.
   3. Mock-up may remain as part of the Work.

1.07 DELIVERY, STORAGE, AND HANDLING

A. Stack material to prevent twisting, bending, and abrasion, and to provide ventilation. Slope metal sheets to ensure drainage.

B. Prevent contact with materials that could cause discoloration or staining.

PART 2 PRODUCTS

2.01 PERFORMANCE REQUIREMENTS

A. Perform work in accordance with SMACNA (ASMM) and NRCA (RM) requirements, unless more stringent requirements are indicated.

B. Sheet metal flashing and trim shall withstand wind loads, structural movement, thermally induced movement, and exposure to weather without failure due to defective manufacture, fabrication, installation, or other defects in construction.
C. Sheet metal flashing and trim shall not rattle, leak, or loosen, and shall remain watertight.
D. Fabricate cleats and attachment devices of sizes as recommended by cited sheet metal standards, and by Data Sheet FM DS 1-49: Perimeter Flashing, for application, but not less than thickness of metal being secured.
E. Coordination:
   1. Coordinate sheet metal flashing and trim layout and seams with sizes and locations of penetrations to be flashed, and joints and seams in adjacent materials.
   2. Coordinate sheet metal flashing and trim installation with adjoining roofing and wall materials, joints, and seams to provide leakproof, secure, and noncorrosive installation.

2.02 SHEET MATERIALS

A. Pre-Finished Aluminum: ASTM B209 (ASTM B209M); 20 gage, (0.032 inch) thick, minimum; plain finish shop pre-coated with fluoropolymer coating.
   1. Fluoropolymer Coating: High Performance Organic Finish, AAMA 2605; multiple coat, thermally cured fluoropolymer finish system.
   2. Color: Two or three-coat custom color to match Architect's sample.

2.03 FABRICATION

A. Form sections true to shape, accurate in size, square, and free from distortion or defects.
B. Form sheet metal flashing and trim to fit substrates without excessive oil canning, buckling, and tool marks; true to line, levels, and slopes.
C. Fabricate cleats of same material as sheet, interlocking with sheet.
D. Form pieces in longest possible lengths.
E. Hem exposed edges on underside 1/2 inch; miter and seam corners.
F. Form material with flat lock seams, except where otherwise indicated; at moving joints, use sealed lapped, bayonet-type or interlocking hooked seams.
G. Fabricate corners from one piece with minimum 18 inch long legs; seam for rigidity, seal with sealant.
H. Fabricate vertical faces with bottom edge formed outward 1/4 inch and hemmed to form drip.

2.04 ACCESSORIES

A. General: Provide all related materials, fasteners, hardware and accessories for a complete installation.
B. Fasteners: Same material and finish as flashing metal, with soft neoprene washers.
   1. Blind Fasteners: High-strength aluminum or stainless-steel rivets suitable for metal being fastened.
   2. Exposed Fasteners: Heads matching color of sheet metal using factory-applied coating.
C. Protective Backing Paint: Zinc molybdate alkyd.
D. Concealed Sealants: Non-curing butyl sealant.
E. Exposed Sealants: ASTM C920; elastomeric silicone sealant, with minimum movement capability as recommended by manufacturer for substrates to be sealed; color to match adjacent material.
F. Solder: ASTM B32; Sn96 type for stainless steel.

2.05 DRIP EDGES

A. Material: Pre-finished aluminum.
B. Provide L-shaped drip edges; extend horizontal leg 4 inches onto roof with vertical leg terminated with a 45 degree bent drip edge.
C. At Contractor's option, provide manufactured drip edges of type and profile required.

PART 3 EXECUTION

3.01 EXAMINATION

A. Verify roof openings, curbs, pipes, sleeves, ducts, and vents through roof are solidly set, reglets in place, and nailing strips located.
B. Verify roofing termination and base flashings are in place, sealed, and secure.

3.02 PREPARATION

A. Install starter and edge strips, and cleats before starting installation.
B. Install surface mounted reglets true to lines and levels, and seal top of reglets with sealant.
C. To prevent galvanic action or corrosion, back paint concealed metal surfaces with protective backing paint, minimum dry film thickness of 3 mil, where dissimilar metals contact each other, or where metal contacts pressure-treated wood or other corrosive substrates.

3.03 INSTALLATION - GENERAL

A. Install flashings and trim in accordance with SMACNA (ASMM) and NRCA (RM) requirements, unless more stringent methods are indicated.
B. Unless otherwise indicated, provide pre-finished aluminum flashings and trim in areas exposed to public view; at all other areas provide stainless steel flashings.
C. Insert flashings into reglets to form tight fit; secure in place with plastic wedges; seal flashings into reglets with sealant.
    1. Counterflashings shall lap base flashing 4 inches, minimum.
D. Secure flashings in place using concealed fasteners, and use exposed fasteners only where permitted.
E. Fit flashings tight in place; make corners square, surfaces true and straight in planes, and lines accurate to profiles.
F. Seal metal joints watertight.
G. For stainless steel, solder metal joints for full metal surface contact, and after soldering wash metal clean with neutralizing solution and rinse with water.
    1. Do not solder aluminum.

3.04 TOLERANCES

A. Sheet Metal Flashing and Trim Tolerances:
    1. Install to tolerance of 1/4 inch in 20 feet on slope and location lines indicated on Drawings.
    2. Install with 1/8 inch maximum offset of adjoining faces and of alignment of matching profiles.

3.05 CLEANING

A. On completion of sheet metal flashing and trim installation, remove unused materials and clean finished surfaces as recommended by sheet metal manufacturer. Maintain sheet metal flashing and trim in clean condition.
B. Replace sheet metal flashing and trim damaged or deteriorated beyond successful repair by finish touchup or similar minor repair procedures.

END OF SECTION

SECTION 07 9200 - JOINT SEALANTS

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Nonsag gunnable joint sealants.
B. Joint backings and accessories.

1.02 REFERENCE STANDARDS

A. ASTM C661 - Standard Test Method for Indentation Hardness of Elastomeric-Type Sealants by Means of a Durometer; 2015 (Reapproved 2022).
B. ASTM C794 - Standard Test Method for Adhesion-in-Peel of Elastomeric Joint Sealants; 2018 (Reapproved 2022).
C. ASTM C920 - Standard Specification for Elastomeric Joint Sealants; 2018.
D. ASTM C1087 - Standard Test Method for Determining Compatibility of Liquid-Applied Sealants with Accessories Used in Structural Glazing Systems; 2023.
E. ASTM C1193 - Standard Guide for Use of Joint Sealants; 2016 (Reapproved 2023).
F. ASTM C1248 - Standard Test Method for Staining of Porous Substrate by Joint Sealants; 2022.
G. ASTM C1330 - Standard Specification for Cylindrical Sealant Backing for Use with Cold Liquid-Applied Sealants; 2023.
H. ASTM C1521 - Standard Practice for Evaluating Adhesion of Installed Weatherproofing Sealant Joints; 2019 (Reapproved 2020).
I. ASTM D2240 - Standard Test Method for Rubber Property--Durometer Hardness; 2015 (Reapproved 2021).

1.03 SUBMITTALS

A. See Section 01 3000 - Administrative Requirements, for submittal procedures.
B. Product Data for Sealants: Submit manufacturer's technical data sheets for each product to be used, that includes the following.
    1. Physical characteristics, including movement capability, VOC content, hardness, cure time, and color availability.
    2. List of backing materials approved for use with the specific product.
    3. Substrates that product is known to satisfactorily adhere to and with which it is compatible.
    4. Substrates the product should not be used on.
    5. Substrates for which use of primer is required.
    6. Sample product warranty.
C. Product Data for Accessory Products: Submit manufacturer's technical data sheet for each product to be used, including physical characteristics, installation instructions, and recommended tools.
D. Color Cards for Selection: Where custom colors are not specified, submit manufacturer's color cards showing standard colors available for selection.
E. Samples for Verification: For each sealant color, submit at least three physical samples for color verification.
    1. Provide 1/2 inch wide joint sealant samples formed between two 4 inch long strips of material matching appearance of exposed surfaces adjacent to joint sealants.
F. Preconstruction Laboratory Test Reports: Submit at least four weeks prior to start of installation.
G. Field Quality Control Plan: Submit at least two weeks prior to start of installation.
H. Field Quality Control Log: Submit filled out log for each length or instance of sealant installed, within 10 days after completion of inspections/tests; include bagged test samples and photographic records, if any.

1.04 QUALITY ASSURANCE

A. Manufacturer Qualifications: Company specializing in manufacturing the products specified in this section with minimum 5 years documented experience.

B. Installer Qualifications: Company specializing in performing the work of this section and with at least 5 years of documented experience.

C. Preconstruction Laboratory Testing: Arrange for sealant manufacturer(s) to test each combination of sealant, substrate, backing, and accessories.
   1. Adhesion Testing: In accordance with ASTM C794.
   2. Compatibility Testing: In accordance with ASTM C1087.
   3. Stain Testing: In accordance with ASTM C1248; required only for stone substrates.
   4. Allow sufficient time for testing to avoid delaying the work.
   5. Deliver to manufacturer sufficient samples for testing.
   6. Report manufacturer's recommended corrective measures, if any, including primers or techniques not indicated in product data submittals.
   7. Testing is not required if sealant manufacturer provides data showing previous testing, not older than 24 months, that shows satisfactory adhesion, lack of staining, and compatibility.

D. Owner may employ an independent testing agency to perform the field quality control inspection and testing as referenced in PART 3 of this section and as follows, to prepare and submit the field quality control plan and log, and to provide recommendations of remedies in the case of failure.
   1. Contractor shall cooperate with testing agency and repair failures discovered.
   2. Otherwise, if Owner does not employ an independent testing agency, Contractor shall perform its own field quality control measures including the following:
      a. Field Quality Control Plan and Log.
      b. Field Adhesion Test Procedures.

E. Field Quality Control Plan:
   1. Visual inspection of entire length of sealant joints.
   2. Non-destructive field adhesion testing of sealant joints, except interior acrylic latex sealants.
      a. For each different sealant and substrate combination, allow for one test every 12 inches in the first 10 linear feet of joint and one test every 120 inches thereafter.
      b. If any failures occur in the first 10 linear feet, continue testing at 48 inch intervals at no extra cost to Owner.

F. Field Adhesion Test Procedures:
   1. Allow sealants to fully cure as recommended by manufacturer before testing.
   2. Have a copy of the test method document available during tests.
   3. Record the type of failure that occurred, other information required by test method, and the information required on the Field Quality Control Log.
   4. If any combination of sealant type and substrate does not show evidence of minimum adhesion or shows cohesion failure before minimum adhesion, report results to Architect.
   5. Non-Destructive Field Adhesion Test: Test for adhesion in accordance with ASTM C1521, using Nondestructive Spot Method.
      a. Record results on Field Quality Control Log.
      b. Repair failed portions of joints.

1.05 WARRANTY

A. See Section 01 7800 - Closeout Submittals, for additional warranty requirements.

B. Correct defective work within a five year period after Date of Substantial Completion.

C. Warranty: Include coverage for installed sealants and accessories that fail to achieve watertight seal , exhibit loss of adhesion or cohesion, or do not cure.

PART 2 PRODUCTS

2.01 JOINT SEALANT APPLICATIONS

A. Scope:
   1. Exterior Joints: Seal open joints, whether or not the joint is indicated on drawings, unless specifically indicated not to be sealed. Exterior joints to be sealed include, but are not limited to, the following items.
      a. Wall expansion and control joints.
      b. Joints between door, window, and other frames and adjacent construction.
      c. Joints between different exposed materials.
      d. Openings below ledge angles in masonry.
      e. Other joints as indicated.
   2. Do not seal the following types of joints.
      a. Intentional weepholes in masonry.
      b. Joints indicated to be treated with manufactured expansion joint cover or some other type of sealing device.
      c. Joints where sealant is specified to be provided by manufacturer of product to be sealed.
      d. Joints where installation of sealant is specified in another section.
      e. Joints between suspended panel ceilings/grid and walls.

B. Exterior Joints: Use non-sag non-staining silicone sealant, unless otherwise indicated.
   1. Control and Expansion Joints in Concrete Paving: Self-leveling silicone traffic-grade sealant.

2.02 NONSAG JOINT SEALANTS

A. Non-Staining Silicone Sealant: ASTM C920, Grade NS, Type S, Uses NT, A, G, M and O; not expected to withstand continuous water immersion or traffic.
   1. Movement Capability: Plus and minus 50 percent, minimum.
   2. Non-Staining To Porous Stone: Non-staining to light-colored natural stone when tested in accordance with ASTM C1248.
   3. Dirt Pick-Up: Reduced dirt pick-up compared to other silicone sealants.
   4. Hardness Range: Comply with one of the following:
      a. 15 to 35, Shore A, when tested in accordance with ASTM C661.
      b. 25 to 35, Shore A, when tested in accordance with ASTM D2240.
   5. Color: Custom color(s) to match Architect's sample(s).
   6. Cure Type: Single-component, neutral moisture curing.
   7. Service Temperature Range: Minus 40 to 250 degrees F.
   8. Products:
      a. Momentive Performance Materials, Inc./GE; SCS9000 SilPruf NB: www.siliconeforbuilding.com.
      b. Pecora Corporation; 890NST: www.pecora.com.
      c. Sika Corporation; Sikasil WS-295 FPS: www.usa.sika.com.
      d. Tremco, Inc.; Spectrem 3: www.tremcosealants.com.
      e. Dow Chemical Company; DOWSIL 790 Silicone Building Sealant: consumer.dow.com/en-us/industry/ind-building-construction.html/#sle.
      f. Substitutions: See Section 01 6000 - Product Requirements.

2.03 ACCESSORIES

A. Backer Rod: Cylindrical cellular foam rod with surface that sealant will not adhere to, compatible with specific sealant used, and recommended by backing and sealant manufacturers for specific application.
   1. Type for Joints Not Subject to Pedestrian or Vehicular Traffic: ASTM C1330; Type B - Bi-Cellular Polyethylene.
   2. Bi-Cellular: 25 to 33 percent larger in diameter than joint width.

B. Backing Tape: Self-adhesive polyethylene tape with surface that sealant will not adhere to and recommended by tape and sealant manufacturers for specific application.

C. Masking Tape: Self-adhesive, nonabsorbent, non-staining, removable without adhesive residue, and compatible with surfaces adjacent to joints and sealants.
D. Primers: Type recommended by sealant manufacturer to suit application; non-staining.

PART 3 EXECUTION

3.01 EXAMINATION

A. Verify that joints are ready to receive work.
B. Verify that backing materials are compatible with sealants.
C. Verify that backer rods are of the correct size.

3.02 PREPARATION

A. Remove loose materials and foreign matter that could impair adhesion of sealant.
B. Clean joints, and prime as necessary, in accordance with manufacturer's instructions.
C. Perform preparation in accordance with manufacturer's instructions and ASTM C1193.
D. Mask elements and surfaces adjacent to joints from damage and disfigurement due to sealant work; be aware that sealant drips and smears may not be completely removable.

3.03 INSTALLATION

A. Perform work in accordance with sealant manufacturer's requirements for preparation of surfaces and material installation instructions.
B. Perform installation in accordance with ASTM C1193.
C. Measure joint dimensions and size joint backers to achieve width-to-depth ratio, neck dimension, and surface bond area as recommended by manufacturer.
D. Install bond breaker backing tape where backer rod cannot be used.
E. Install sealant free of air pockets, foreign embedded matter, ridges, and sags, and without getting sealant on adjacent surfaces.
F. Do not install sealant when ambient temperature is outside manufacturer's recommended temperature range, or will be outside that range during the entire curing period, unless manufacturer's approval is obtained and instructions are followed.
G. Nonsag Sealants: Tool surface concave, unless otherwise indicated; remove masking tape immediately after tooling sealant surface.
H. Concrete Floor Joint Filler: After full cure, shave joint filler flush with top of concrete slab.
I. Installation of Two-Stage Joints at Precast Architectural Concrete Units:
    1. Joint system consists of two back-to-back sealant joints at each precast architectural concrete unit joint with a weep at the bottom of the unit joint per Precast/Prestressed Concrete Institute (PCI) recommendations and as follows:
        a. Inner (Secondary) Seal: Inner secondary backer rod and sealant joint is installed a minimum of 2 to 2-1/2 inches beyond the exposed face of the precast architectural concrete panels within the panel joint itself.
        b. Exterior (Primary) Seal: Following the installation of the secondary joint, the outer primary backer rod and sealant joint is installed at the face of the precast architectural concrete panels with a weep at the bottom of the joint. Leave open continuous air space between the primary backer rod and inner secondary seal.
        c. Install 3/8 inch minimum weep openings in the exterior seal to allow water penetrating the exterior seal and contained by the inner seal to exit the cavity between joint seals.
            1) Do not install weeps below finish grades.
        d. Near the junction of horizontal and vertical joints, the inner seal must turn out to the plane of the exterior seal at regular intervals to force water out of the joint.

3.04 FIELD QUALITY CONTROL

A. Owner may employ an independent testing agency to perform field quality control inspection and testing as specified in PART 1 under QUALITY ASSURANCE article.

B. Non-Destructive Adhesion Testing: If there are any failures in first 100 linear feet, notify Architect immediately.
C. Remove and replace failed portions of sealants using same materials and procedures as indicated for original installation.

END OF SECTION 07 9200

This page intentionally left blank

SECTION 09 2216 - NON-STRUCTURAL METAL FRAMING

PART 1 GENERAL

1.01 SECTION INCLUDES

A. Suspension systems for exterior soffits.
B. Framing accessories.

1.02 REFERENCE STANDARDS

A. ASTM A641/A641M - Standard Specification for Zinc-Coated (Galvanized) Carbon Steel Wire; 2019.
B. ASTM A653/A653M - Standard Specification for Steel Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy-Coated (Galvannealed) by the Hot-Dip Process; 2023.
C. ASTM C645 - Standard Specification for Nonstructural Steel Framing Members; 2018.
D. ASTM C754 - Standard Specification for Installation of Steel Framing Members to Receive Screw-Attached Gypsum Panel Products; 2020.
E. ASTM C840 - Standard Specification for Application and Finishing of Gypsum Board; 2023.
F. ASTM C955 - Standard Specification for Cold-Formed Steel Structural Framing Members; 2018, with Editorial Revision.
G. ASTM D3575 - Standard Test Methods for Flexible Cellular Materials Made From Olefin Polymers.
H. ASTM E119 - Standard Test Methods for Fire Tests of Building Construction and Materials; 2022.
I. GA-216 - Application and Finishing of Gypsum Panel Products; 2024.
J. GA-600 - Fire Resistance and Sound Control Design Manual; 2024.
K. UL (FRD) - Fire Resistance Directory; Current Edition.

1.03 SUBMITTALS

A. See Section 01 3000 - Administrative Requirements for submittal procedures.
B. Shop Drawings:
   1. Indicate component details, control joints, stud layout, framed openings, acoustic details, type and location of fasteners, and accessories.
   2. Describe method for securing studs to tracks, splicing, and for blocking and reinforcement of framing connections.
   3. Coordinate with Section 09 2900
C. Product Data: Provide data describing framing member materials and finish, product criteria, load charts, and limitations.
D. Manufacturer's Qualification Statement.
E. Installer's Qualification Statement.

1.04 QUALITY ASSURANCE

A. Manufacturer Qualifications: Company specializing in performing work of type specified and with at least five years of documented experience.
B. Installer Qualifications: Company specializing in performing the work of this section with minimum five years documented experience and approved by manufacturer.

PART 2 PRODUCTS

2.01 MANUFACTURERS

A. Metal Framing, Shaft Wall Framing, Connectors, and Accessories:
   1. ClarkDietrich Building Systems: www.clarkdietrich.com.
   2. Jaimes Industries Inc.: www.jaimesind.com.
   3. MarinoWARE: www.marinoware.com.
   4. MBA Building Supplies, Inc.: www.mbastuds.com.
   5. State Building Products; www.statebp.com.
   6. The Steel Network, Inc: www.SteelNetwork.com.

7. Telling Industries; www.buildstrong.com.
8. Substitutions: See Section 01 6000 - Product Requirements.

2.02 PERFORMANCE REQUIREMENTS

A. Provide completed assemblies complying with ASTM C840 and GA-216.

B. Fire-Rated Assemblies: For fire-resistance-rated assemblies that incorporate non-load-bearing steel framing, provide materials and construction identical to those tested in assembly indicated, according to ASTM E119 and as follows:
   1. Provide construction equivalent to one of the following:
      a. UL Assembly Numbers: Provide construction equivalent to that listed for the particular assembly in the current UL (FRD).
      b. Gypsum Association File Numbers: Provide construction complying with requirements of GA-600 for the particular assembly.

C. Horizontal Deflection: For wall assemblies, limit maximum deflection of wall framing to L/240 at 5 psf .
   1. Exception: Limit deflection of walls to receive hard tile surfaces to L/360 at 5 psf.

D. Protective Coatings: Equivalent (EQ) coatings are not acceptable; products shall be hot-dip galvanized as indicated.

E. Embossed (equivalent thickness) steel framing products are not acceptable; unless products are in steel thicknesses indicated.

2.03 FRAMING MATERIALS

A. Non-Loadbearing Framing System Components: ASTM C645; galvanized sheet steel, of size and properties necessary to comply with ASTM C754 for the spacing indicated.
   1. Protective Coating: ASTM A653/A653M, G60, hot-dip galvanized.
   2. Minimum Metal Thickness: 0.030 inch (20 gage).
   3. Framing Depths: As indicated.
   4. Profiles:
      a. Studs: C shaped with flat or formed webs.
      b. Ceiling Channels: C shaped.
      c. Furring: Hat-shaped sections, minimum depth of 7/8 inch.

2.04 FRAMING ACCESSORIES

A. Bridging and Bracing Members: Of same material as studs; thickness to suit purpose; complying with applicable requirements of ASTM C754.
   1. Steel, 0.0538-inch (1.37mm) minimum base-metal thickness, with a minimum 1/2-inch (13mm) wide flanges.
      a. Basis-of-Design Product: Subject to compliance with requirements, provide ClarkDietrich Systems Spazzer 9200 Bridge and Spacing Bar, or equivalent.

B. Backing Plates: 0.064 inch thick (16 gage), galvanized.

C. Wood Blocking: Refer to Section 06 1000 - Rough Carpentry.

D. Anchorage Devices: Powder actuated or Drilled expansion bolts.

E. Acoustic Sealant: As specified in Section 09 2900 - Gypsum Board.

F. Isolation Strip: Foam gasket, ASTM D3575, closed-cell vinyl foam strips, 1/8 inch thick, in width to suit steel stud size.
   1. Manufacturer:
      a. Williams; Everlastic EVA 200; www.williamsproducts.net.
      b. Substitutions: See Section 01 6000 - Product Requirements.

2.05 SHAFT WALL FRAMING MATERIALS

2.06 SUSPENSION SYSTEMS

A. Carrying Channels: ASTM C955; cold-rolled galvanized steel sheet U-channel.
   1. Protective Coating: ASTM A653/A653M, G60, hot-dip galvanized.
   2. Minimum Metal Thickness: 0.064 inch (16 gage).

3. Depth: 2 inches unless otherwise indicated.

B. Furring Channels:
1. Hat-Shaped, Rigid Furring Channels: As specified in "Framing Materials" above.
2. Resilient Furring Channels: As specified in "Framing Materials" above.

C. Tie Wire: ASTM A641/A641M, Class 1 zinc coating, soft temper, 0.062-inch (16 gage) diameter or double strand of 0.048-inch (18 gage) diameter wire.

D. Wire Hangers: ASTM A641/A641M, Class 1 zinc coating, soft temper, 0.16 inch (8 gage) diameter.

2.07 FABRICATION

A. Fabricate assemblies of framed sections to sizes and profiles required.

B. Fit, reinforce, and brace framing members to suit design requirements.

PART 3 EXECUTION

3.01 EXAMINATION

A. Verify existing conditions before starting work.

3.02 INSTALLATION OF STUD FRAMING

A. Comply with requirements of ASTM C754.

B. Install suspension systems and related accessories and components in accordance with manufacturer's instructions.

C. Secure studs to tracks using fastener method. Do not weld.
1. Secure studs to top and bottom runner tracks at both inside and outside flanges.

D. Stud splicing is not permissible.

E. Fabricate corners using a minimum of three studs.

F. Brace stud framing system rigid.

G. Coordinate installation of bucks, anchors, and blocking with electrical, mechanical, and other work to be placed within or behind stud framing.

H. Blocking/Backing: Use metal backing plate, wood blocking, or supplementary framing secured to studs. Provide blocking/backing for support of equipment services, plumbing fixtures, toilet partitions, wall cabinets, toilet accessories, hardware, and similar construction.

I. Furring: Install at spacing and locations shown on drawings. Lap splices a minimum of 6 inches.

J. Do not bridge building control and expansion joints. Frame both sides of joints independently.
1. Install Horzontal stiffeners in stud system, spaced (vertical distance) not more than 4'-6" o.c.

K. General requirements and locations of control joints in metal-framed gypsum board construction:
1. General: Comply with requirements of ASTM C840, and as noted below:
a. Control joints shall be constructed with manufactured control joint trim, or field fabricated from materials as specified.
b. Control joints will be installed where a partition, wall, or ceiling traverses and construction joint (expansion, or building control element) in the base building structure.
c. Control joints will be installed where a wall or partition extends in an uninterrupted straight plane exceeding 30 linear feet. Door and/or window frames that extend full height of partitions will be considered equivalent to control joint construction.
d. Control joints in interior ceilings, bulkheads, fasciae and soffits will be installed so that linear dimensions between control joints do not exceed 30 linear feet and total area between control joints does not exceed 900 square feet. Control joints will be installed to isolate wings of “L”, “U: and “T” shaped ceiling and soffit areas.
e. A control joint will be installed where ceiling, bulkhead, fascia and soffit framing members change direction.

f. Provide appropriate backing material, fire-safing insulation, and sealant for control joints installed in acoustical or fire-rated construction, as required to maintain fire-rating and/or acoustical separation.

L. Where studs are installed directly against exterior masonry walls, install isolation strip between studs and exterior wall.

3.03 CEILING AND SOFFIT FRAMING

A. Comply with requirements of ASTM C754.

B. Install furring after work above ceiling or soffit is complete. Coordinate the location of hangers with other work.

C. Install furring independent of walls, columns, and above-ceiling work.

D. Securely fix carrying channels to existing red iron angles with mechanical fasteners to prevent turning or twisting and to transmit full load to hangers.

E. Laterally brace suspension system.

3.04 TOLERANCES

A. Maximum Variation From True Position: 1/8 inch in 10 feet.

B. Maximum Variation From Plumb: 1/8 inch in 10 feet.

C. Maximum variation From Level: 1/8 inch in 10 feet.

END OF SECTION

SECTION 26 0010 - ELECTRICAL GENERAL REQUIREMENTS

PART 1 GENERAL 1
1.01 RELATED DOCUMENTS 1
1.02 SUMMARY 1
1.03 REFERENCES 1
1.04 QUALITY ASSURANCE 2
1.05 CODES, PERMITS AND FEES 2
1.06 DRAWINGS 3
1.07 MATERIAL AND EQUIPMENT MANUFACTURERS 3
1.08 INSPECTION OF SITE 3
1.09 ITEMS REQUIRING PRIOR APPROVAL 3
1.10 SHOP DRAWINGS/SUBMITTALS 4
1.11 COORDINATION DRAWINGS 4
1.12 OPERATION AND MAINTENANCE INSTRUCTIONAL MANUALS 4
1.13 RECORD DRAWINGS 5
1.14 WARRANTY 5
1.15 USE OF EQUIPMENT 5
1.16 COORDINATION 5

PART 2 PRODUCTS (NOT APPLICABLE) 6

PART 3 EXECUTION 6
3.01 COMMON REQUIREMENTS FOR ELECTRICAL INSTALLATION 6
3.02 DEMOLITION WORK 6
3.03 INSTALLATION OF EQUIPMENT 7
3.04 WORK IN EXISTING BUILDINGS 7
3.05 TEMPORARY SERVICES 7
3.06 DISPOSAL 7
3.07 CHASES AND RECESSES 8
3.08 CUTTING, PATCHING AND DAMAGE TO OTHER WORK 8
3.09 EQUIPMENT CONNECTIONS 8
3.10 CLEANING 8
3.11 PROTECTION AND HANDLING OF EQUIPMENT AND MATERIALS 8
3.12 EXTRA WORK 8
3.13 DRAWINGS AND MEASUREMENTS 8

PART 1 GENERAL

1.01 RELATED DOCUMENTS

A. Drawings and General Provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification sections, apply to work of this section.

1.02 SUMMARY

A. This Section includes electrical general administrative and procedural requirements. The following requirements are included in this Section to supplement the requirements specified in Division 1 Specification Sections.

1.03 REFERENCES

A. All materials shall be new. The electrical and physical properties of all materials, and the design, performance characteristics, and methods of construction of all items of equipment, shall be in accordance with the latest issue of the various, applicable Standard Specifications of the following recognized authorities:

1. ANSI - American National Standards Institute; www.ansi.org.
2. ASTM - ASTM International; www.astm.org.

3. CSI - Construction Specifications Institute (The); www.csiresources.org.
4. ICEA - Insulated Cable Engineers Association, Inc.; www.icea.net.
5. IEEE - Institute of Electrical and Electronics Engineers, Inc. (The); www.ieee.org.
6. NEC - National Electrical Code
7. NECA - National Electrical Contractors Association; www.necanet.org.
   a. NECA 1-2000, “Practices for Good Workmanship in Electrical Contracting (ANSI).”
8. NEMA - National Electrical Manufacturers Association; www.nema.org.
9. NETA - InterNational Electrical Testing Association; www.netaworld.org.
10. UL - Underwriters Laboratories Inc.; www.ul.com.

1.04 QUALITY ASSURANCE

A. Scope of Work: Furnish all labor, material, equipment, technical supervision, and incidental services required to complete, test, and leave ready for operation the electrical systems as specified in the Division 26 Sections and as indicated on Drawings.
   1. Contract Documents are complementary, and what is required by one shall be as binding as if required by all. In the event of inconsistencies or disagreements within the Construction Documents bids shall be based on the most expensive combination of quality and quantity of the work indicated.
   2. The Contractor understands that the work herein described shall be complete in every detail.

B. Ordinances and Codes: Perform all Work in accordance with applicable Federal, State, and local ordinances and regulations, the Rules and Regulations of NFPA, NECA, and UL, unless otherwise indicated.
   1. Notify the Architect/Engineer if revisions to the Drawings or Specifications are required to conform to applicable ordinances, codes, or regulations. Identify the cost associated with these revisions in the bid.

C. Source Limitations: All equipment of the same or similar systems shall be by the same manufacturer.

D. Tests and Inspections: Perform all tests required by state, city, county, and/or other agencies having jurisdiction. Provide all materials, equipment, etc., and labor required for tests.

E. Performance Requirements: Perform all work in a first class and workmanlike manner, in accordance with the latest accepted standards and practices for the trades involved.

F. Sequence and Schedule: Avoid interference with the work of other trades. Remove and relocate any work which in the opinion of the Owner’s Representatives causes interference.

1.05 CODES, PERMITS AND FEES

A. Unless otherwise indicated, all required permits, licenses, inspections, approvals, and fees for electrical work shall be secured and paid for by the Contractor. All work shall conform to all applicable codes, rules, and regulations.

B. Comply with rules of local utility companies. Coordinate with the utility company supplying service to the installation and determine all devices including, but not limited to, all current and potential transformers, meter boxes, C.T. cabinets, and meters which will be required and include the cost of all such items and all utilities costs in proposal.

C. All work shall be executed in accordance with the rules and regulations outlined in local and state codes. Prepare any detailed Drawings or diagrams which may be required by the governing authorities. Where the Drawings and/or Specifications indicate materials or construction that exceed code requirements, the Drawings and/or Specifications shall govern.

1.06 DRAWINGS

A. The Drawings show the location and general arrangement of equipment, electrical systems, and related items. They shall be followed as closely as elements of the construction will permit.

B. Examine the Drawings of other trades and verify the conditions governing the work on the job site. Arrange work accordingly, providing such fittings, conduit, junction boxes, and accessories as may be required to meet such conditions.

C. Deviations from the Drawings, apart from minor changes in routing and other such incidental changes that do not affect the functioning or serviceability of the systems, shall not be made without the written approval of the Architect/Engineer.

D. The architectural and structural Drawings take precedence in all matters pertaining to the building structure, mechanical Drawings in all matters pertaining to mechanical trades, and electrical Drawings in all matters pertaining to electrical trades. Where there are conflicts or differences between the Drawings for the various trades, report such conflicts or differences to the Architect/Engineer for resolution.

E. Drawings are not intended to be scaled for rough-in or to serve as shop drawings. Take all field measurements required to complete the Work.

1.07 MATERIAL AND EQUIPMENT MANUFACTURERS

A. All items of equipment shall be furnished complete with all accessories normally supplied with the catalog items listed and all other accessories necessary for a complete and satisfactory operating system. All equipment and materials shall be new, be standard products of manufacturers regularly engaged in the production of electrical equipment and be of the manufacturer's latest design.

B. If an approved manufacturer is other than the manufacturer used as the basis for design, the equipment or product provided shall be equal in size, quality, durability, appearance, capacity, and efficiency through all ranges of operation, shall conform with arrangements and space limitations of the equipment shown on the plans and/or specified, shall be compatible with the other components of the system and shall comply with the requirements for Items Requiring Prior Approval specified in this section of the Specifications. All costs to make these items of equipment comply with these requirements including, but not limited to, electrical work, and building alterations shall be included in the original Bid. Similar equipment shall be by one manufacturer.

C. Where existing equipment is modified to include new switches, circuit breakers, metering, or other components, the new components shall be by the original equipment manufacturer and shall be listed for installation in the existing equipment. Where original equipment manufacturer components are not available, third-party aftermarket components shall be listed for the application and submitted to the engineer for approval. Reconditioned or salvaged components shall not be used unless specifically indicated on the drawings.

1.08 INSPECTION OF SITE

A. Visit the site, examine, and verify the conditions under which the Work must be conducted before submitting Proposal. The submitting of a Proposal implies that the Contractor has visited the site and understands the conditions under which the Work must be conducted. No additional charges will be allowed because of failure to make this examination or to include all materials and labor to complete the Work.

1.09 ITEMS REQUIRING PRIOR APPROVAL

A. Bids shall be based upon manufactured equipment specified. All items that the Contractor proposes to use in the Work that are not specifically named in the Contract Documents must be submitted for review prior to bids. Such items must be submitted in compliance with Division 1 specifications. Requests for prior approval must be accompanied by complete catalog information, including but not limited to, model, size, accessories, complete electrical information,

and performance data in the form given in the equipment schedule on the drawings at stated design conditions. Where items are referred to by symbolic designations on the drawings, all requests for prior approval shall bear the same designations.

1. Equipment to be considered for prior approval shall be equal in quality, durability, appearance, capacity, and efficiency through all ranges of operation, shall fulfill the requirements of equipment arrangement and space limitations of the equipment shown on the plans and/or specified and shall be compatible with the other components of the system.
2. All costs incurred to make equipment comply with other requirements, including providing maintenance, clearance, electrical, replacement of other components, and building alterations shall be included in the original bid.

B. Voluntary alternates may be submitted for consideration, with listed addition or deduction to the bid.

1.10 SHOP DRAWINGS/SUBMITTALS

A. Submit project-specific submittals for review in compliance with Division 1.

B. All shop Drawings shall be submitted in groupings of similar and/or related items (lighting fixtures, switchgear, etc.). Incomplete submittal groupings will be returned unchecked.

C. If deviations (not substitutions) from the Contract Documents are deemed necessary by the Contractor, the details of such deviations, the reason for the deviation, and the resulting changes shall be included with the submittal for approval.

D. Submit for approval shop drawings for electrical systems or equipment indicated in other sections of electrical specs. Where items are referred to by symbolic designation on the Drawings and Specifications, all submittals shall bear the same designation (light fixtures).

1.11 COORDINATION DRAWINGS

A. Submit project specific coordination drawings for review in compliance with Division 1 Specification Sections.

1.12 OPERATION AND MAINTENANCE INSTRUCTIONAL MANUALS

A. Submit project specific Operation and Maintenance Instructional Manuals for review in compliance with Division 01 Specification Sections.

B. Provide complete operation and maintenance instructional manuals covering all electrical equipment herein specified, together with parts lists. Maintenance and operating instructional manuals shall be job specific to this project. Generic manuals are not acceptable. Manual shall be provided on electronic media. All literature shall be combined in one document and shall be properly bookmarked with all applicable sections. Maintenance and operating instructional manuals shall be provided when construction is approximately 75% complete.

C. The operating and maintenance instructions shall include a brief, general description for all electrical systems including, but not limited to:

1. Routine maintenance procedures.
2. Trouble-shooting procedures.
3. Contractor's telephone numbers for warranty repair service.
4. Submittals.
5. Recommended spare parts list.
6. Names and telephone numbers of major material suppliers and subcontractors.
7. System schematic drawings on 8-1/2" x 11" sheets.

1.13 RECORD DRAWINGS

A. Submit record drawings in compliance with Division 01.

B. Contractor shall submit to the Architect/Engineer, record drawings on electronic media which have been neatly marked to represent as-built conditions for all new electrical work. Modifications to original drawings shall be marked with a contrasting color so the marks are readily apparent.

C. The Contractor shall keep accurate note of all deviations from the construction documents and discrepancies in the underground concealed conditions and other items of construction on field drawings as they occur. The marked up field documents shall be available for review by the Architect, Engineer, and Owner at their request during construction.

1.14 WARRANTY

A. Warranty: Comply with the requirements in Division 01 Specification Sections. Contractor shall warranty that the electrical installation is free from defects and agrees to replace or repair, to the Owner’s satisfaction, any part of this electrical installation which becomes defective within a period of one year (unless specified otherwise in other Division 26 sections) from the date of substantial completion following final acceptance, provided that such failure is due to defects in the equipment, material, workmanship, or failure to follow the contract documents.

B. Contractor shall be responsible for any temporary services including equipment and installation required to maintain operation as a result of any equipment failure or defect during warranty period.

C. File with the Owner all warranties from the equipment manufacturers including the operating conditions and performance capacities they are based on.

1.15 USE OF EQUIPMENT

A. The use of any equipment, or any part thereof for purposes other than testing even with the Owner's consent, shall not be construed to be an acceptance of the work on the part of the Owner, nor be construed to obligate the Owner in any way to accept improper work or defective materials.

B. Do not use Owner's lamps for temporary lighting except as allowed and directed by the Owner. Equip lighting fixtures with new lamps when the project is turned over to the Owner.

1.16 COORDINATION

A. Coordinate arrangement, mounting, and support of electrical equipment:

1. To allow maximum possible headroom unless specific mounting heights that reduce headroom are indicated.
2. To provide for ease of disconnecting the equipment with minimum interference to other installations.
3. To allow right of way for piping and conduit installed at required slope.
4. To ensure that connecting raceways, cables, wireways, cable trays, and busways will be clear of obstructions; and to maintain the working and access space of other equipment.

B. Coordinate installation of required supporting devices and set sleeves in cast-in-place concrete, masonry walls, and other structural components as they are constructed.

C. Coordinate location of access panels and doors for electrical items that are behind finished surfaces or otherwise concealed. Access doors and panels are specified in Division 8 Section "Access Doors and Frames."

D. Coordinate electrical testing of electrical, mechanical, and architectural items, so equipment and systems that are functionally interdependent are tested to demonstrate successful interoperability.

PART 2 PRODUCTS (NOT APPLICABLE)

PART 3 EXECUTION

3.01 COMMON REQUIREMENTS FOR ELECTRICAL INSTALLATION

A. Comply with NECA 1.

B. Measure indicated mounting heights to bottom of unit for suspended items and to center of unit for wall-mounting items.

C. Headroom Maintenance: If mounting heights or other location criteria are not indicated, arrange, and install components and equipment to provide maximum possible headroom consistent with these requirements.

D. Equipment: Install to facilitate service, maintenance, and repair or replacement of components of both electrical equipment and other nearby installations. Connect in such a way as to facilitate future disconnecting with minimum interference with other items in the vicinity.

E. Right of Way: Give to raceways and piping systems installed at a required slope.

3.02 DEMOLITION WORK

A. All demolition of existing electrical equipment and materials will be done by this Contractor unless otherwise indicated. Include all items related to the existing systems that are being removed such as, but not limited to, electrical equipment, cabinets, devices, lighting fixtures, conduit, fittings, boxes, wiring, and supports. No abandoned components of the electrical systems indicated to be removed shall remain.

1. Where electrically powered equipment is included in the demolition scope of other trades, disconnect electrical wiring connections and remove circuit wiring complete.

B. In general, demolition work is indicated on the Drawings. However, the Contractor shall visit the job site to determine the full extent and character of this work.

C. Unless specifically noted otherwise, removed materials shall not be reused in the work.

1. Materials indicated to be salvaged shall be carefully removed, stored, and protected from damage.

2. Salvaged materials intended to be re-used shall be thoroughly cleaned, refurbished if necessary, and determined to be fully functional prior to placing back into service.

3. Salvaged materials of value that are not to be reused shall remain the property of the Owner unless such ownership is waived. Items that the Owner has waived ownership shall become the property of the Contractor, who shall remove and legally dispose of same, away from the premises.

D. Where equipment or fixtures are removed, outlet boxes that remain recessed in walls shall be properly blanked off, and conduits capped. After alterations are complete, the entire installation shall present a "finished" look, as approved by the Architect/Engineer. The original function of the present electrical systems remaining in service shall not be changed unless specifically indicated as part of the project scope.

E. Reroute signal wires, lighting, and power wiring as required to maintain services that are to remain and/or unaffected by the renovations. Where walls and ceilings are to be removed as shown on the Drawings, the conduit is to be cut off by the Electrical Trades so that the abandoned conduit in these walls and ceilings may be removed with the walls and ceilings by the Architectural Trades. All dead-end conduit runs shall be plugged at the remaining line outlet boxes or the panels.

F. Where new walls and/or floors are installed which interfere with existing outlets, devices, etc., the Electrical Trades shall adjust, extend and reconnect such items as required to maintain continuity of same.

G. All electrical work in altered and unaltered areas shall be run concealed wherever possible. Use of surface raceway or exposed conduits will be permitted only where specifically indicated on the drawings or approved by the Architect/Engineer.

H. Existing lighting shall be reused where indicated on plans. Reused fixtures shall be detergent cleaned, re-lamped, and reconditioned suitable for satisfactory operation and appearance.

3.03 INSTALLATION OF EQUIPMENT

A. Install all equipment in strict accordance with all directions and recommendations furnished by the manufacturer. Where such directions conflict with the Drawings and Specifications, report such conflicts to the Architect/Engineer for resolution.

B. Device Location:

1. Allow for wiring devices, control devices, and fire alarm devices to be relocated within a 10’ radius to accommodate final coordination with furnishings and other finish elements. Devices relocated prior to installation shall be done without additional cost to the project.

3.04 WORK IN EXISTING BUILDINGS

A. The Owner will provide access to existing buildings as required. Access requirements to occupied buildings shall be identified on the project schedule. The Contractor, once Work is started in the existing building, shall complete same without interruption to return work areas as soon as possible to Owner.

B. Adequately protect and preserve all existing and newly installed Work. Promptly repair any damage to same at Contractor's expense.

C. Consult with the Owner’s Representative as to the methods of carrying on the Work so as not to interfere with the Owner's operation any more than necessary. Accordingly, all service lines shall be kept in operation as long as possible and the services shall only be interrupted at such time as will be designated by the Owner's Representative.

3.05 TEMPORARY SERVICES

A. Provide and remove upon completion of the project, following the general conditions and as described in Division 01, a complete temporary electrical and telephone service during construction.

3.06 DISPOSAL

A. Fluorescent Lamps

1. Fluorescent lamps are known to contain mercury and are classified as hazardous material. All fluorescent lamps shall be assumed to contain mercury unless tested and confirmed otherwise with a toxicity characteristic leaching procedure (TCLP).

2. Hazardous materials (fluorescent lamps), shall be sent to a lamp recycling facility. The materials shall be properly packaged with labels that meet the Department of Transportation Regulations and stored in a secure location before transportation.

3. The Contractor shall identify the costs of the lamp disposal process including, but not limited to, the lamp packaging, storage, transportation, disposal, and any profile fees.

4. Upon completion of the project, provide documentation to verify that the lamps have been properly disposed of in accordance with all local, state, and federal guidelines.

B. Ballasts

1. Lighting ballasts manufactured prior to 1979 have been known to contain polychlorinated biphenyls (PCBs). Unless specifically noted on the ballast as containing "No PCBs," the ballast shall be assumed to contain components with PCB materials.

2. Hazardous materials (ballasts with PCBs), shall be disposed of at a hazardous waste incineration facility, or at a recycling facility in accordance with the Code of Federal Regulations as administered by the EPA in regards to this issue. The ballasts shall be packaged/stored in fifty-five gallon steel drums with labels that meet the Department of Transportation Regulations.
3. The Contractor shall identify the costs of the ballast disposal process including, but not limited to, the packaging, storage, transportation, disposal, and any profile fees.
4. Provide at completion of the project documentation (manifests) to verify that the ballasts have properly been disposed of in accordance with all local, state, and federal guidelines.

3.07 CHASES AND RECESSES

A. Provided by the architectural trades, but the Contractor shall be responsible for their accurate location and size.

3.08 CUTTING, PATCHING AND DAMAGE TO OTHER WORK

A. Refer to General Conditions for requirements.

B. All cutting, patching, and repair work shall be performed by the Contractor through approved, qualified subcontractors. Contractor shall include full cost of same in bid.

3.09 EQUIPMENT CONNECTIONS

A. Make connections to equipment and other items included in the work in accordance with the approved shop Drawings and rough-in measurements furnished by the manufacturers of the particular equipment furnished. All additional connections not shown on the Drawings, but called out by the equipment manufacturer's shop Drawings shall be provided.

3.10 CLEANING

A. All debris shall be removed daily as required to maintain the work area in a neat, orderly condition.

B. Final cleanup shall include, but not be limited to, washing of fixture lenses or louvers, switchboards, substations, motor control centers, panels, etc. Fixture reflectors and lenses or louvers shall be left with no water marks or cleaning streaks.

3.11 PROTECTION AND HANDLING OF EQUIPMENT AND MATERIALS

A. Equipment and materials shall be protected from theft, injury, or damage.

B. Protect conduit openings with temporary plugs or caps.

C. Provide adequate storage for all equipment and materials delivered to the job site. Location of the space will be designated by the Owner's representative or Architect/Engineer. Equipment set in place in unprotected areas must be provided with temporary protection.

3.12 EXTRA WORK

A. For additional electrical work which may be proposed or requested, furnish an itemized cost breakdown of material and labor required to complete the work. Proceed only after receiving a written authorization.

3.13 DRAWINGS AND MEASUREMENTS

A. The Drawings are not intended to be scaled for rough-in measurements nor to serve as Shop Drawings. Field measurements necessary for ordering materials and fitting the installation to the building construction and arrangement are the Contractor’s responsibility. The Contractor shall check latest Architectural Drawings and locate light switches from same where door swings are different from Electrical Drawings.

END OF SECTION

SECTION 26 0519 - CONDUCTORS AND CABLES

PART 1 GENERAL 1
1.01 RELATED DOCUMENTS 1
1.02 SUMMARY 1
1.03 ACTION SUBMITTALS 1
1.04 INFORMATIONAL SUBMITTALS 1
1.05 QUALITY ASSURANCE 1
PART 2 PRODUCTS 1
2.01 COPPER BUILDING WIRE 1
2.02 METAL-CLAD CABLE, TYPE MC 2
2.03 CONNECTORS AND SPLICES 3
PART 3 EXECUTION 3
3.01 CONDUCTOR MATERIAL APPLICATIONS 3
3.02 CONDUCTOR INSULATION AND MULTICONDUCTOR CABLE APPLICATIONS AND WIRING METHODS 3
3.03 INSTALLATION OF CONDUCTORS AND CABLES 3
3.04 CONNECTIONS 3
3.05 IDENTIFICATION 4
3.06 SLEEVE AND SLEEVE-SEAL INSTALLATION FOR ELECTRICAL PENETRATIONS 4
3.07 FIRESTOPPING 4

PART 1 GENERAL

1.01 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.02 SUMMARY

A. Section includes:

1. Building wires and cables rated 600V and less.
2. Connectors, splices, and terminations rated 600 V and less.

1.03 ACTION SUBMITTALS

A. Submit letter of compliance (intent) for copper building wire.

1.04 INFORMATIONAL SUBMITTALS

A. Field Quality-Control Test Reports.

1.05 QUALITY ASSURANCE

A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, Article 100, by a testing agency acceptable to authorities having jurisdiction, and marked for intended use.

B. Comply with NFPA 70.

PART 2 PRODUCTS

2.01 COPPER BUILDING WIRE

A. Description: Flexible, insulated and uninsulated, drawn copper current-carrying conductor with an overall insulation layer or jacket, or both, rated 600 V or less.

B. Standards:

1. Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and use.

2. Conductor and Cable Marking: Comply with wire and cable marking according to UL's "Wire and Cable Marking and Application Guide."

C. Conductors: Copper, complying with ASTM B 3 for bare annealed copper and with ASTM B 8 for stranded conductors.

D. Conductor Insulation:

1. Type THHN/THWN-2: Comply with UL 83.
2. Type XHHW-2: Comply with UL 44.

2.02 METAL-CLAD CABLE, TYPE MC

A. Description: A factory assembly of one or more current-carrying insulated conductors in an overall metallic sheath.

B. Manufacturers:

1. AFC Cable Systems
2. Alpha Wire Company
3. American Bare Conductor
4. Belden
5. Encore
6. General Cable
7. Okonite
8. Service Wire Co.
9. Southwire Company

C. Standards:

1. Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and use.
2. Comply with UL 1569.
3. Conductor and Cable Marking: Comply with wire and cable marking according to UL's "Wire and Cable Marking and Application Guide."

D. Circuits:

1. Single circuit and multi-circuit with color-coded conductors for branch circuit distribution.
2. Power-Limited Fire-Alarm Circuits: Comply with UL 1424.

E. Conductors:

1. Copper, complying with ASTM B 3 for bare annealed copper and with ASTM B 8 for stranded conductors.

F. Ground Conductor: Insulated. Ground conductor sized as indicated on drawings (reduced ground conductor is not acceptable).

G. Conductor Insulation:

1. Type TFN/THHN/THWN-2: Comply with UL 83.
2. Type XHHW-2: Comply with UL 44.

H. Armor: Aluminum, interlocked.

I. Jacket: PVC applied over armor.

2.03 CONNECTORS AND SPLICES

A. Description: Factory-fabricated connectors and splices of size, ampacity rating, material, type, and class for application and service indicated.

PART 3 EXECUTION

3.01 CONDUCTOR MATERIAL APPLICATIONS

A. Refer to application schedule on the drawings

B. Feeders and Branch Circuits: Solid or stranded for No. 12 AWG and smaller; stranded for No. 10 AWG and larger.

C. Each feeder shall be of the same conductor and insulation material (phase, neutral, and parallel).

D. Use conductor not smaller than 14 AWG for 120V control circuits.

3.02 CONDUCTOR INSULATION AND MULTICONDUCTOR CABLE APPLICATIONS AND WIRING METHODS

A. Refer to application schedule on the drawings

3.03 INSTALLATION OF CONDUCTORS AND CABLES

A. Conceal cables in finished walls, ceilings, and floors, unless otherwise indicated.

B. Complete raceway installation between conductor and cable termination points according to Section 26 0533 "Raceways and Boxes for Electrical Systems" prior to pulling conductors and cables.

C. Use manufacturer-approved pulling compound or lubricant where necessary; compound used must not deteriorate conductor or insulation. Do not exceed manufacturer's recommended maximum pulling tensions and sidewall pressure values.

D. Use pulling means, including fish tape, cable, rope, and basket-weave wire/cable grips, that will not damage cables or raceway.

E. Install exposed cables parallel and perpendicular to surfaces of exposed structural members, and follow surface contours where possible.

F. Support cables according to Division 26 Section "Hangers and Supports for Electrical Systems."

G. Neatly train and lace wiring inside boxes, equipment, and panelboards.

H. Provide a separate neutral conductor for each circuit unless multi-wire branch circuits are specifically indicated on the drawings.

I. Electrical Contractor shall be responsible for de-rating of conductors as required by N.E.C. when more than three current carrying conductors are installed in a single raceway or cable. Neutral conductors shall be considered current carrying conductors.

J. Type MC cable shall be supported and secured at intervals not exceeding 4'-0" in new construction.

K. Where AC/MC cable is permitted by the specifications, AC/MC cable shall not be bundled.

L. Between support, hangers and termination no more than 3" deflection from the bottom of the cable to a horizontal line between the support/hanger or termination.

M. Do not route conductors across roof without prior approval from engineer.

N. Install and terminate power cable for variable frequency- controlled motors according to cable manufacturer’s recommendations.

3.04 CONNECTIONS

A. Tighten electrical connectors and terminals according to manufacturer's published torque-tightening values. If manufacturer's torque values are not indicated, use those specified in UL 486A.

B. Make splices and taps that are compatible with conductor material and that possess equivalent or better mechanical strength and insulation ratings than un-spliced conductors.

C. Clean conductor surfaces before installing lugs and connectors.

D. Make splices, taps, and terminations to carry full ampacity of conductors with no perceptible temperature rise.

E. Use solderless pressure connectors with insulating covers for copper conductor splices and taps, 8 AWG and larger.

F. Use Sta-Kon connectors to terminate stranded conductors #10 AWG and smaller to screw terminals.

G. Use insulated spring wire connectors with plastic caps (wire nuts) for copper conductor splices and taps, 10 AWG and smaller. Push-in style connectors are not permitted.

H. Provide lugs suitable for bussing and conductor material used.

I. Use appropriately sized compression pin adapters to make terminations at equipment where equipment lugs cannot accommodate conductors that are oversized for voltage drop or similar conditions.

3.05 IDENTIFICATION

A. Identify and color-code conductors and cables according to Section 26 0553 "Identification for Electrical Systems."

B. Identify each spare conductor at each end with identity number and location of other end of conductor, and identify as spare conductor.

3.06 SLEEVE AND SLEEVE-SEAL INSTALLATION FOR ELECTRICAL PENETRATIONS

A. Install sleeves and sleeve seals at penetrations of exterior floor and wall assemblies. Comply with requirements in Section 26 0533 "Raceways and Boxes."

3.07 FIRESTOPPING

A. Apply firestopping to electrical penetrations of fire-rated floor and wall assemblies to restore original fire-resistance rating of assembly according to Division 07 Section "Penetration Firestopping”.

END OF SECTION

SECTION 26 0526 - GROUNDING AND BONDING

PART 1 GENERAL 1
1.01 RELATED DOCUMENTS 1
1.02 SUMMARY 1
1.03 REFERENCES 1
1.04 ACTION SUBMITTALS 2
1.05 CLOSEOUT SUBMITTALS 2
1.06 QUALITY ASSURANCE 2
PART 2 PRODUCTS 2
2.01 MANUFACTURERS 2
2.02 GROUNDING CONDUCTORS 2
2.03 CONNECTOR PRODUCTS 2
PART 3 EXECUTION 3
3.01 EQUIPMENT GROUNDING 3
3.02 CONNECTIONS 3
3.03 INSTALLATION 4

PART 1 GENERAL

1.01 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.02 SUMMARY

A. This Section includes grounding of electrical systems and equipment. Grounding requirements specified in this Section may be supplemented by special requirements of systems described in other Sections.

B. Related Sections include the following:

1. Division 26 Section “Electrical General Requirements”.
2. Division 26 Section “Conductors and Cables”.

1.03 REFERENCES

A. ASTM B 3: Specification for Soft or Annealed Copper Wire.

B. ASTM B 8: Specification for Concentric-Lay-Stranded Copper Conductors, Hard, Medium-Hard or Soft.

C. IEEE 81: Guide for Measuring Earth Resistivity, Ground Impedance, and Earth Surface Potentials of a Ground System.

D. IEEE 142: Grounding of Industrial and Commercial Power Systems.

E. IEEE C2: National Electrical Safety Code.

F. NETA MTS – 2001: Maintenance Testing Specifications.

G. NFPA 70: National Electrical Code.

H. NFPA 70B: Recommended Practice for Electrical Equipment Maintenance.

I. TIA/EIA 607: Commercial Building Grounding and Bonding Requirements Standard.

J. UL 467: Grounding and Bonding Equipment.

K. UL 486 A: Wire Connectors and Soldering Lugs for Use with Copper Conductors.

L. UL 486B: Wire Connectors for Use with Aluminum Conductors.

1.04 ACTION SUBMITTALS

A. Submit letter of compliance (intent) for grounding and bonding equipment.

1.05 CLOSEOUT SUBMITTALS

A. Project Record Documents

1. Submit under provisions of Division 26 “Electrical General Requirements”.

1.06 QUALITY ASSURANCE

A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, Article 100, by a testing agency acceptable to authorities having jurisdiction, and marked for intended use.

1. Comply with UL 467.

PART 2 PRODUCTS

2.01 MANUFACTURERS

A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

1. Grounding Conductors and Cables:
    a. Refer to Division 26 Section “Conductors and Cables”.
2. Mechanical Connectors:
    a. American Electric-Blackburn.
    b. Burndy.
    c. Chance/Hubbell.
3. Exothermic Connections:
    a. Cadweld.
4. Compression-type Connectors:
    a. Burndy HyGround
    b. Blackburn EZ Ground.
    c. Panduit.

2.02 GROUNDING CONDUCTORS

A. For insulated conductors, comply with Division 26 Section "Conductors and Cables."

B. Equipment Grounding Conductors: Insulated with green-colored insulation.

C. Copper Bonding Conductors: As follows:

1. Bonding Conductor: Stranded copper conductor; size per the NEC.
2. Bonding Jumper: Bare copper tape, braided bare copper conductors, terminated with copper ferrules; size per the NEC.
3. Tinned Bonding Jumper: Tinned-copper tape, braided copper conductors, terminated with copper ferrules; size per the NEC.

2.03 CONNECTOR PRODUCTS

A. Comply with IEEE 837 and UL 467; listed for use for specific types, sizes, and combinations of conductors and connected items.

B. Bolted Connectors: Bolted-pressure-type connectors, or compression type.

C. Welded Connectors: Exothermic-welded type, in kit form, and selected for the specific application per manufacturer's written instructions.

D. Compression-Type Connectors: Pure, wrought copper, per ASTM B187.

PART 3 EXECUTION

3.01 EQUIPMENT GROUNDING

A. Comply with NFPA 70, Article 250, for types, sizes, and quantities of equipment grounding conductors, unless specific types, larger sizes, or more conductors than required by NFPA 70 are indicated.

B. In raceways, use insulated equipment grounding conductors. Install equipment grounding conductors in all feeders and circuits. Terminate each end on suitable lugs, bus or bushing.

1. Where existing branch circuits are using conduit as equipment grounding conductor and are extended, provide grounding bushing on existing conduit and provide new equipment grounding conductor with new branch circuit.

C. Install equipment grounding conductors in all feeders and circuits. Terminate each end on suitable lugs, bus or bushing.

D. Nonmetallic Raceways: Install an equipment grounding conductor in nonmetallic raceways unless they are designated for telephone or data cables.

E. Verify specific equipment grounding requirements with the manufacturer’s recommendations.

3.02 CONNECTIONS

A. General: Make connections so galvanic action or electrolysis possibility is minimized. Select connectors, connection hardware, conductors, and connection methods so metals in direct contact will be galvanically compatible.

1. Use electroplated or hot-tin-coated materials to ensure high conductivity and to make contact points closer to order of galvanic series.

2. Make connections with clean, bare metal at points of contact.

3. Make aluminum-to-steel connections with stainless-steel separators and mechanical clamps.

4. Make aluminum-to-galvanized steel connections with tin-plated copper jumpers and mechanical clamps.

5. Coat and seal connections having dissimilar metals with inert material to prevent future penetration of moisture to contact surfaces.

B. Exothermic-Welded Connections: Use for connections to structural steel and for underground connections, except those at test wells. Comply with manufacturer's written instructions. Welds that are puffed up or that show convex surfaces indicating improper cleaning are not acceptable.

C. Equipment Grounding Conductor Terminations

1. Use solderless pressure connectors with insulating covers for copper conductor splices and taps, 8 AWG and larger.

2. Use insulated spring wire connectors with plastic caps for copper conductor splices and taps, 10 AWG and smaller.

D. Noncontact Metal Raceway Terminations: If metallic raceways terminate at metal housings without mechanical and electrical connection to housing, terminate each conduit with a grounding bushing. Connect grounding bushings with a bare grounding conductor to grounding bus or terminal in housing. Bond electrically noncontinuous conduits at entrances and exits with grounding bushings and bare grounding conductors, unless otherwise indicated.

E. Tighten screws and bolts for grounding and bonding connectors and terminals according to manufacturer's published torque-tightening values. If manufacturer's torque values are not indicated, use those specified in UL 486A.

F. Compression-Type Connections: Use hydraulic compression tools to provide correct circumferential pressure for compression connectors. Connections shall be non-reversible. Use tools and dies recommended by connector manufacturer. Provide embossing die code or other standard method to make a visible indication that a connector has been adequately compressed on grounding conductor.

G. Moisture Protection: If insulated grounding conductors are connected to ground rods or grounding buses, insulate entire area of connection and seal against moisture penetration of insulation and cable.

3.03 INSTALLATION

A. Grounding Conductors: Route along shortest and straightest paths possible, unless otherwise indicated. Avoid obstructing access or placing conductors where they may be subjected to strain, impact, or damage. Install in conduit where routed above grade.

B. Bonding Straps and Jumpers: Install so vibration by equipment mounted on vibration isolation hangers and supports is not transmitted to rigidly mounted equipment. Use exothermic-welded connectors or non-reversing compression-type connectors for outdoor locations, unless a disconnect-type connection is required; then, use a bolted clamp. Bond straps directly to the basic structure taking care not to penetrate any adjacent parts. Install straps only in locations accessible for maintenance.

C. Bond interior metal piping systems, including any portions of metal piping systems separated by non-metal piping, and metal air ducts to equipment grounding conductors of associated pumps, fans, blowers, electric heaters, and air cleaners. Use braided-type bonding straps.

D. Equipment Grounding: Provide a permanent and continuous bonding of conductor enclosures, equipment frames, power distribution equipment ground busses, cable trays, metallic raceways, and other non-current carrying metallic parts of the electrical system.

E. Bond together metal building elements not attached to grounded structure; bond to ground.

F. Provide a flexible braid bonding jumper at each set of columns at expansion joints.

END OF SECTION

SECTION 26 0529 - HANGERS AND SUPPORTS FOR ELECTRICAL SYSTEMS

PART 1 GENERAL 1
1.01 RELATED DOCUMENTS 1
1.02 SUMMARY 1
1.03 DEFINITIONS 1
1.04 PERFORMANCE REQUIREMENTS 1
1.05 ACTION SUBMITTALS 1
1.06 QUALITY ASSURANCE 1
PART 2 PRODUCTS 2
2.01 SUPPORT, ANCHORAGE, AND ATTACHMENT COMPONENTS 2
PART 3 EXECUTION 3
3.01 APPLICATION 3
3.02 SUPPORT INSTALLATION 3
3.03 PAINTING 4

PART 1 GENERAL

1.01 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.02 SUMMARY

A. This Section includes the following:

1. Hangers and supports for electrical equipment and systems.

1.03 DEFINITIONS

A. EMT: Electrical metallic tubing.

B. IMC: Intermediate metal conduit.

C. RMC: Rigid metal conduit.

1.04 PERFORMANCE REQUIREMENTS

A. Delegated Design: Design supports for multiple raceways, including comprehensive engineering analysis by a qualified professional engineer, using performance requirements and design criteria indicated.

B. Design supports for multiple raceways capable of supporting combined weight of supported systems and its contents.

C. Design equipment supports capable of supporting combined operating weight of supported equipment and connected systems and components.

D. Rated Strength: Adequate in tension, shear, and pullout force to resist maximum loads calculated or imposed for this Project, with a minimum structural safety factor of five times the applied force.

1.05 ACTION SUBMITTALS

A. Product Data: For the following:

1. Steel slotted support systems.

1.06 QUALITY ASSURANCE

A. Comply with NFPA 70.

PART 2 PRODUCTS

2.01 SUPPORT, ANCHORAGE, AND ATTACHMENT COMPONENTS

A. Steel Slotted Support Systems: Comply with MFMA-4, factory-fabricated components for field assembly.

1. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
    a. Allied Tube & Conduit; a part of Atkore International..
    b. B-Line, by Eaton..
    c. GS Metals Corp.
    d. Pentair Electrical & Fastening Solutions.
    e. Thomas & Betts Corporation.
    f. Unistrut; a part of Atkore International.
    g. Wesanco, Inc.
2. Metallic Coatings: Hot-dip galvanized after fabrication and applied according to MFMA-4.
3. Channel Dimensions: Selected for applicable load criteria.

B. Raceway and Cable Supports: As described in NECA 1 and NECA 101.

C. Conduit and Cable Support Devices: Steel hangers, clamps, and associated fittings, designed for types and sizes of raceway or cable to be supported.

D. Support for Conductors in Vertical Conduit: Factory-fabricated assembly consisting of threaded body and insulating wedging plug or plugs for non-armored electrical conductors or cables in riser conduits. Plugs shall have number, size, and shape of conductor gripping pieces as required to suit individual conductors or cables supported. Body shall be malleable iron.

E. Mounting, Anchoring, and Attachment Components: Items for fastening electrical items or their supports to building surfaces include the following:

1. Powder-Actuated Fasteners: Threaded-steel stud, for use in hardened portland cement concrete, steel, or wood, with tension, shear, and pullout capacities appropriate for supported loads and building materials where used.
    a. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
        1) Hilti Inc.
        2) ITW Ramset/Red Head; a division of Illinois Tool Works, Inc.
        3) MKT Fastening, LLC.
        4) Simpson Strong-Tie Co., Inc.; Masterset Fastening Systems Unit.
2. Mechanical-Expansion Anchors: Insert-wedge-type, zinc-coated steel, for use in hardened portland cement concrete with tension, shear, and pullout capacities appropriate for supported loads and building materials in which used.
    a. Manufacturers: Subject to compliance with requirements, provide products by one of the following:
        1) B-Line by Eaton.
        2) Empire Tool and Manufacturing Co., Inc.
        3) Hilti Inc.

4) ITW Ramset/Red Head; a division of Illinois Tool Works, Inc.

5) MKT Fastening, LLC.

3. Concrete Inserts: Steel or malleable-iron, slotted support system units similar to MSS Type 18; complying with MFMA-4 or MSS SP-58.

4. Clamps for Attachment to Steel Structural Elements: MSS SP-58, type suitable for attached structural element.

5. Through Bolts: Structural type, hex head, and high strength. Comply with ASTM A 325.

6. Toggle Bolts: All-steel springhead type.

7. Hanger Rods: Threaded steel.

PART 3 EXECUTION

3.01 APPLICATION

A. Comply with NECA 1 and NECA 101 for application of hangers and supports for electrical equipment and systems except if requirements in this Section are stricter.

B. Maximum Support Spacing and Minimum Hanger Rod Size for Raceway: Space supports for EMT, IMC, and RMC as required by NFPA 70. Minimum rod size shall be 1/4 inch in diameter.

C. Multiple Raceways or Cables: Install trapeze-type supports fabricated with steel slotted support system, sized so capacity can be increased by at least 25 percent in future without exceeding specified design load limits.

1. Secure raceways and cables to these supports with:

a. Two-bolt conduit clamps

b. Single-bolt conduit clamps

c. Single-bolt conduit clamps using spring friction action for retention in support channel.

D. Spring-steel clamps designed for supporting single conduits without bolts may be used for 1-1/2-inch and smaller raceways serving branch circuits and communication systems above suspended ceilings and for fastening raceways to trapeze supports.

E. Support single runs of MC cable using spring-steel clamps from suspended ceiling hangers, hanger wire or building structure at intervals not to exceed three feet. Do not support MC cable from ceiling grid.

3.02 SUPPORT INSTALLATION

A. Comply with NECA 1 and NECA 101 for installation requirements except as specified in this Article.

B. Raceway Support Methods: In addition to methods described in NECA 1, EMT may be supported by openings through structure members, as permitted in NFPA 70.

C. Strength of Support Assemblies: Where not indicated, select sizes of components so strength will be adequate to carry present and future static loads within specified loading limits. Minimum static design load used for strength determination shall be weight of supported components plus 200 lb.

D. Mounting and Anchorage of Surface-Mounted Equipment and Components: Anchor and fasten electrical items and their supports to building structural elements by the following methods unless otherwise indicated by code:

1. To Wood: Fasten with lag screws or through bolts.

2. To New Concrete: Bolt to concrete inserts.

3. To Masonry: Approved toggle-type bolts on hollow masonry units and expansion anchor fasteners on solid masonry units.
4. To Existing Concrete: Expansion anchor fasteners.
5. Instead of expansion anchors, powder-actuated driven threaded studs provided with lock washers and nuts may be used in existing standard-weight concrete 4 inches thick or greater. Do not use for anchorage to lightweight-aggregate concrete or for slabs less than 4 inches thick.
6. To Steel:
    a. Welded threaded studs complying with AWS D1.1/D1.1M, with lock washers and nuts.
    b. Beam clamps (MSS Type 19, 21, 23, 25, or 27) complying with MSS SP-69
    c. Spring-tension clamps.
7. To Light Steel: Sheet metal screws.
8. Items Mounted on Hollow Walls and Nonstructural Building Surfaces: Mount cabinets, panelboards, disconnect switches, control enclosures, pull and junction boxes, transformers, and other devices on slotted-channel support systems attached to substrate.

E. Slotted support systems applications:
1. Indoor dry and damp Locations: Galvanized Steel
2. Outdoors and interior wet locations: Galvanized Steel

F. Drill holes for expansion anchors in concrete at locations and to depths that avoid reinforcing bars.

G. Do not fasten supports to floor decks, roof decks, pipes, ducts, mechanical equipment, or conduit.

H. Obtain permission from Architect/Engineer before using powder-actuated anchors.

I. Obtain permission from Architect/Engineer before drilling or cutting structural members.

J. Fabricate supports from structural steel or steel channel. Rigidly weld members or use hexagon head bolts to present neat appearance with adequate strength and rigidity. Use spring lock washers under all nuts.

K. The Contractor shall replace all supports and channels that sag, twist, and/or show signs of not providing proper structural support, to the equipment, it is intended for, as determined by the Owner and Architect/Engineer. All costs associated with replacing supports and steel channels shall be incurred by the Contractor.

3.03 PAINTING

A. Touchup: Comply with requirements in Division 09 painting Sections for cleaning and touchup painting of field welds, bolted connections, and abraded areas of shop paint on miscellaneous metal.

B. Galvanized Surfaces: Clean welds, bolted connections, and abraded areas and apply galvanizing-repair paint to comply with ASTM A 780.

END OF SECTION

SECTION 26 0533 - RACEWAYS AND BOXES

PART 1 GENERAL 1
1.01 RELATED DOCUMENTS 1
1.02 SUMMARY 1
1.03 DEFINITIONS 1
1.04 ACTION SUBMITTALS 1
1.05 QUALITY ASSURANCE 2
1.06 COORDINATION 2
PART 2 PRODUCTS 2
2.01 METAL CONDUIT AND TUBING 2
2.02 NONMETALLIC CONDUIT AND TUBING 2
2.03 BOXES, ENCLOSURES, AND CABINETS 3
2.04 SLEEVES FOR RACEWAYS 3
2.05 GROUT 3
PART 3 EXECUTION 3
3.01 RACEWAY APPLICATION 3
3.02 INSTALLATION 4
3.03 SLEEVE INSTALLATION FOR ELECTRICAL AND COMMUNICATIONS PENETRATIONS 5
3.04 FIRESTOPPING 6
3.05 PROTECTION 6
3.06 CLEANING 6

PART 1 GENERAL

1.01 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.02 SUMMARY

A. This Section includes raceways, fittings, boxes, enclosures, and cabinets for electrical wiring.

B. Related Sections include the following:

1. Division 07 Section, “Penetration Firestopping” for firestopping materials and installation at penetrations through walls, ceilings, and other fire-rated elements.
2. Division 26 “Hangers and Supports for Electrical Systems” for concrete bases.

1.03 DEFINITIONS

A. EMT: Electrical metallic tubing.

B. ENT: Electrical nonmetallic tubing.

C. FMC: Flexible metal conduit.

D. IMC: Intermediate metal conduit.

E. LFMC: Liquidtight flexible metal conduit.

F. RNC: Rigid nonmetallic conduit.

G. PVC: Polyvinyl Chloride.

1.04 ACTION SUBMITTALS

A. Product Data: For surface raceways, wireways and fittings, floor boxes, hinged-cover enclosures, and cabinets.

1.05 QUALITY ASSURANCE

A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, Article 100, by a testing agency acceptable to authorities having jurisdiction, and marked for intended use.

B. Comply with NFPA 70.

1.06 COORDINATION

A. Coordinate layout and installation of raceways, boxes, enclosures, cabinets, and suspension system with other construction that penetrates ceilings or is supported by them, including light fixtures.

PART 2 PRODUCTS

2.01 METAL CONDUIT AND TUBING

A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

1. AFC Cable Systems, Inc.
2. Alflex Inc.
3. Allied Tube Triangle Century.
4. Anamet Electrical, Inc.; Anaconda Metal Hose.
5. International Metal Hose.
6. Electri-Flex Co
7. Grinnell Co./Tyco International; Allied Tube and Conduit Div.
8. LTV Steel Tubular Products Company – Manhattan/CDT/Cole-Flex.
9. Maverick.
10. O-Z Gedney; unit of General Signal.
11. Wheatland.

B. Rigid Steel Conduit: ANSI C80.1.

C. IMC: ANSI C80.6.

D. PVC-Coated Steel Conduit: PVC-coated IMC.

1. Comply with NEMA RN 1.
2. Coating Thickness: 0.040 inch, minimum.

E. EMT: ANSI C80.3.

F. FMC: Aluminum.

G. Fittings for Conduit (Including all Types and Flexible and Liquidtight), EMT, and Cable: NEMA FB 1; listed for type and size raceway with which used, and for application and environment in which installed.

1. Fittings for EMT: Steel, set-screw type.
2. Coating for Fittings for PVC-Coated Conduit: Minimum thickness, 0.040 inch, with overlapping sleeves protecting threaded joints.

2.02 NONMETALLIC CONDUIT AND TUBING

A. Manufacturers: Subject to compliance with requirements, provide products by one of the following:

1. American International.

2. Anamet Electrical, Inc.; Anaconda Metal Hose.
3. Arnco Corp.
4. Cantex Inc.
5. Certainteed Corp.; Pipe and Plastics Group.
6. Condux International.
7. ElecSys, Inc.
8. Electri-Flex Co.
9. Integral.
10. Kor-Kap.
11. Lamson and Sessions: Carlon Electrical Products.
12. Manhattan/CDT/Cole-Flex.
13. RACO; Division of Hubbell, Inc.
14. Scepter.
15. Spiralduct, Inc./AFC Cable Systems, Inc.
16. Thomas & Betts Corporation.

B. ENT: NEMA TC 13.

C. RNC: NEMA TC 2, Schedule 40 and Schedule 80 PVC.

D. ENT and RNC Fittings: NEMA TC 3; match to conduit or tubing type and material.

E. LFNC: UL 1660.

2.03 BOXES, ENCLOSURES, AND CABINETS

A. Sheet Metal Outlet and Device Boxes: NEMA OS 1. Shall be used within walls or ceiling.

B. Cast-Metal Outlet and Device Boxes: NEMA FB 1, Type FD, with gasketed cover. Shall be used in all exposed, non-recessed, locations.

C. Small Sheet Metal Pull and Junction Boxes: NEMA OS 1.

2.04 SLEEVES FOR RACEWAYS

A. Steel Pipe Sleeves: ASTM A 53/A 53M, Type E, Grade B, Schedule 40, galvanized steel, plain ends.

B. Cast-Iron Pipe Sleeves: Cast or fabricated "wall pipe," equivalent to ductile-iron pressure pipe, with plain ends and integral waterstop, unless otherwise indicated.

C. Coordinate sleeve selection and application with selection and application of firestopping specified in Division 7 Section "Through-Penetration Firestop Systems."

2.05 GROUT

A. Nonmetallic, Shrinkage-Resistant Grout: ASTM C 1107, factory-packaged, nonmetallic aggregate grout, noncorrosive, nonstaining, mixed with water to consistency suitable for application and a 30-minute working time.

PART 3 EXECUTION

3.01 RACEWAY APPLICATION

A. Provide raceways in interior and exterior locations in accordance with the “Raceway Application Matrix” included on the drawings.

B. Boxes and Enclosures, Exterior Aboveground: NEMA 250, Type 3R.

C. Boxes and Enclosures: NEMA 250, Type 1, except use NEMA 250, Type 4, nonmetallic in damp or wet locations.

D. Minimum Raceway Size: 3/4-inch trade size.

E. Raceway Fittings: Compatible with raceways and suitable for use and location.

1. Rigid and Intermediate Steel Conduit: Use threaded rigid steel conduit fittings, unless otherwise indicated.

2. PVC Externally Coated, Rigid Steel Conduits: Use only fittings listed for use with that material. Patch and seal all joints, nicks, and scrapes in PVC coating after installing conduits and fittings. Use sealant recommended by fitting manufacturer.

3. EMT: Use setscrew, cast-metal fittings. Comply with NEMA FB 2.10.

4. Flexible Conduit: Use only fittings listed for use with flexible conduit. Comply with NEMA FB 2.20.

F. Do not install nonmetallic conduit where ambient temperature exceeds 120 deg F.

3.02 INSTALLATION

A. Comply with NECA 1 and NECA 101 for installation requirements except where requirements on Drawings or in this article are stricter. Comply with NECA 102 for aluminum conduits. Comply with NFPA 70 limitations for types of raceways allowed in specific occupancies and number of floors.

B. Keep raceways at least 6 inches away from parallel runs of flues and steam or hot-water pipes. Install horizontal raceway runs above water and steam piping.

C. Complete raceway installation before starting conductor installation.

D. Support raceways as specified in Division 26 Section "Hangers and Supports for Electrical Systems."

E. Install temporary closures to prevent foreign matter from entering raceways.

F. Protect stub-ups from damage where conduits rise through floor slabs. Arrange so curved portions of bends are not visible above the finished slab.

G. Make bends and offsets so ID is not reduced. Keep legs of bends in the same plane and keep straight legs of offsets parallel, unless otherwise indicated.

H. Install no more than the equivalent of four 90-degree bends in any conduit run except for control wiring conduits, for which fewer bends are allowed. Support within 12 inches of changes in direction.

I. Conceal conduit and EMT within finished walls, ceilings, and floors, unless otherwise indicated.

1. Install concealed raceways with a minimum of bends in the shortest practical distance, considering type of building construction and obstructions, unless otherwise indicated.

J. Support conduit within 12 inches of enclosures to which attached.

K. Install exposed raceways parallel or at right angles to nearby surfaces or structural members and follow surface contours as much as possible.

1. Run parallel or banked raceways together on common supports.

2. Make parallel bends in parallel or banked runs. Use factory elbows only where elbows can be installed parallel; otherwise, provide field bends for parallel raceways.

L. Raceway Terminations at Locations Subject to Moisture or Vibration: Use insulating bushings to protect conductors, including conductors smaller than No. 4 AWG.

M. Terminate threaded conduits into threaded hubs or with locknuts on inside and outside of boxes or cabinets. Install bushings on conduits up to 1-1/4-inch trade size and insulated throat metal bushings on 1-1/2-inch trade size and larger conduits terminated with locknuts. Install insulated throat metal grounding bushings on service conduits.

N. Install raceways square to the enclosure and terminate at enclosures with locknuts. Install locknuts hand tight plus 1/4 turn more.

O. Do not rely on locknuts to penetrate nonconductive coatings on enclosures. Remove coatings in the locknut area prior to assembling conduit to enclosure to assure a continuous ground path.

P. Cut conduit perpendicular to the length. For conduits 2-inch trade size and larger, use roll cutter or a guide to make cut straight and perpendicular to the length.

Q. Threaded Conduit Joints, Exposed to Wet, Damp, Corrosive, or Outdoor Conditions: Apply listed compound to threads of raceway and fittings before making up joints. Follow compound manufacturer's written instructions.

R. Where raceways are terminated with threaded hubs, screw raceways or fittings tightly into hub so end bears against wire protection shoulder. Where chase nipples are used, align raceways so coupling is square to box; tighten chase nipple so no threads are exposed.

S. Install pull wires in empty raceways. Use polypropylene or monofilament plastic line with not less than 200-lb tensile strength. Leave at least 12 inches of slack at each end of pull wire.

T. Provide pull string and 25% spare capacity in every branch circuit conduit.

U. Flexible Conduit Connections: Comply with NEMA RV3. Use maximum of 72 inches of flexible conduit for recessed and semirecessed lighting fixtures; for equipment subject to vibration, noise transmission, or movement; and for all motors. Use LFMC in damp or wet locations. Install separate ground conductor across flexible connections.

V. Recessed Boxes in Masonry Walls: Saw-cut opening for box in center of cell of masonry block, and install box flush with surface of wall.

W. Horizontally separate boxes mounted on opposite sides of walls so they are not in the same vertical channel.

X. Locate boxes so that cover or plate will not span different building finishes.

Y. Support boxes of three gangs or more from more than one side by spanning two framing members or mounting on brackets specifically designed for the purpose.

Z. Fasten junction and pull boxes to or support from building structure. Do not support boxes by conduits.

AA. Do not route feeders across roof.

BB. Provide a pull box (a handhole for outdoor applications) for each conduit run that exceeds 250 feet. Provide two pull boxes (handholes for outdoor applications) for runs that exceed 500 feet.

CC. Route conduits in finished areas with exposed ceilings at underside of structural deck or as high as possible.

3.03 SLEEVE INSTALLATION FOR ELECTRICAL AND COMMUNICATIONS PENETRATIONS

A. Coordinate sleeve selection and application with selection and application of firestopping specified in Division 07 Section "Through-Penetration Firestop Systems."

B. Concrete Slabs and Walls: Install sleeves for penetrations unless core-drilled holes or formed openings are used. Install sleeves during erection of slabs and walls.

C. Fire-Rated Assemblies: Install sleeves for penetrations of fire-rated floor and wall assemblies unless openings compatible with firestop system used are fabricated during construction of floor or wall.

D. Cut sleeves to length for mounting flush with both surfaces of walls.

E. Size pipe sleeves to provide 1/4-inch annular clear space between sleeve and raceway unless sleeve seal is to be installed.

F. Seal space outside of sleeves with grout for penetrations of concrete and masonry and with approved joint compound for gypsum board assemblies.

G. Interior Penetrations of Non-Fire-Rated Walls and Floors: Seal annular space between sleeve and raceway, using joint sealant appropriate for size, depth, and location of joint. Refer to Division 7 Section "Joint Sealants" for materials and installation.

H. Fire-Rated-Assembly Penetrations: Maintain indicated fire rating of walls, partitions, ceilings, and floors at raceway penetrations. Install sleeves and seal with firestop materials. Comply with Division 7 Section "Through-Penetration Firestop Systems."

3.04 FIRESTOPPING

A. Apply firestopping to electrical penetrations of fire-rated floor and wall assemblies to restore original fire-resistance rating of assembly. Firestopping materials and installation requirements are specified in Division 07 Section "Through-Penetration Firestop Systems."

3.05 PROTECTION

A. Provide final protection and maintain conditions that ensure coatings, finishes, and cabinets are without damage or deterioration at time of Substantial Completion.

1. Repair damage to galvanized finishes with zinc-rich paint recommended by manufacturer.

2. Repair damage to PVC or paint finishes with matching touchup coating recommended by manufacturer.

3.06 CLEANING

A. After completing installation of exposed, factory-finished raceways and boxes, inspect exposed finishes and repair damaged finishes.

END OF SECTION

SECTION 26 0553 - ELECTRICAL IDENTIFICATION

PART 1 GENERAL 1
1.01 RELATED DOCUMENTS 1
1.02 SUMMARY 1
1.03 ACTION SUBMITTALS 1
1.04 QUALITY ASSURANCE 1
1.05 COORDINATION 1
PART 2 PRODUCTS 1
2.01 CONDUCTOR, COMMUNICATION AND CONTROL CABLE IDENTIFICATION MATERIALS 2
2.02 EQUIPMENT IDENTIFICATION LABELS 2
2.03 MISCELLANEOUS IDENTIFICATION PRODUCTS 2
PART 3 EXECUTION 2
3.01 APPLICATION 2
3.02 INSTALLATION 3

PART 1 GENERAL

1.01 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 1 Specification Sections, apply to this Section.

1.02 SUMMARY

A. This Section includes the following:

1. Identification for raceway and metal-clad cable.
2. Identification for conductors and communication and control cable.
3. Equipment identification labels.
4. Miscellaneous identification products.

1.03 ACTION SUBMITTALS

A. Product Data: For each type of product.

B. Identification Schedule: For each piece of electrical equipment and electrical system components to be index of nomenclature for electrical equipment and system components used in identification signs and labels. Use same designations indicated on Drawings.

1.04 QUALITY ASSURANCE

A. Comply with NFPA 70.

B. Comply with 29 CFR 1910.145.

1.05 COORDINATION

A. Coordinate identification names, abbreviations, colors, and other features with requirements in the Contract Documents, Shop Drawings, manufacturer's wiring diagrams, and the Operation and Maintenance Manual, and with those required by codes, standards, and 29 CFR 1910.145. Use consistent designations throughout Project.

B. Coordinate installation of identifying devices with completion of covering and painting of surfaces where devices are to be applied.

C. Coordinate installation of identifying devices with location of access panels and doors.

D. Install identifying devices before installing acoustical ceilings and similar concealment.

PART 2 PRODUCTS

2.01 CONDUCTOR, COMMUNICATION AND CONTROL CABLE IDENTIFICATION MATERIALS

A. Color-Coding Conductor Tape: Colored, self-adhesive vinyl tape not less than 3 mils thick by 1 to 2 inches wide.

B. Marker Tapes: Vinyl or vinyl-cloth, self-adhesive wraparound type, with circuit identification legend machine printed by thermal transfer or equivalent process.

2.02 EQUIPMENT IDENTIFICATION LABELS

A. Engraved, Laminated Acrylic or Melamine Label: Punched or drilled for screw mounting. Black letters on a white background. Minimum letter height shall be 3/8 inch.

B. Outdoor Equipment Stenciled Legend: In nonfading, waterproof, black ink or paint. Minimum letter height shall be 1 inch.

2.03 MISCELLANEOUS IDENTIFICATION PRODUCTS

A. Cable Ties: Fungus-inert, self-extinguishing, 1-piece, self-locking, Type 6/6 nylon cable ties.

1. Minimum Width: 3/16 inch.
2. Tensile Strength: 50 lb, minimum.
3. Temperature Range: Minus 40 to plus 185 deg F.
4. Color: Black, except where used for color-coding.

B. Paint: Paint materials and application requirements are specified in Division 9 painting Sections.

C. Fasteners for Labels and Signs: Self-tapping, stainless-steel screws or stainless-steel machine screws with nuts and flat and lock washers.

PART 3 EXECUTION

3.01 APPLICATION

A. Branch-Circuit Conductor Identification: Where there are conductors for more than three branch circuits in same junction or pull box, use marker tape. Identify each ungrounded conductor according to source and circuit number as indicated on Drawings. Identify control circuits by control wire number as indicated on shop drawings.

B. Branch-Circuit Conductor Identification: Mark junction box covers in indelible ink with the panel and breaker numbers of other circuits contained within.

C. Conductor Identification: Locate at each conductor at panelboard gutters, pull boxes, outlet and junction boxes, and each load connection or termination point.

D. Equipment Identification Labels: On each unit of equipment, install unique designation label that is consistent with wiring diagrams, schedules, and Operation and Maintenance Manual. Apply labels to disconnect switches and protection equipment, central or master units, control panels, control stations, terminal cabinets, and racks of each system. Systems include power, lighting, control, communication, signal, monitoring, and alarm systems unless equipment is provided with its own identification.

1. Labeling Instructions:
    a. Indoor Equipment: Engraved, laminated acrylic or melamine label mechanically secured.
    b. Elevated Components: Increase sizes of labels and letters to those appropriate for viewing from the floor.
2. Equipment to Be Labeled: If included on project. All items may not be on project.
    a. Panelboards, electrical cabinets, and enclosures.
    b. Access doors and panels for concealed electrical items.

c. Electrical switchgear and switchboards.

d. Transformers.

e. Disconnect switches.

f. Contactors.

3.02 INSTALLATION

A. Verify identity of each item before installing identification products.

B. Location:

1. Install identification materials and devices at locations for most convenient viewing without interference with operation and maintenance of equipment.

C. Apply identification devices to surfaces after completing finish work.

D. Self-Adhesive Identification Products: Clean surfaces before application, using materials and methods recommended by manufacturer of identification device.

E. Attach nonadhesive signs and plastic labels with screws and auxiliary hardware appropriate to the location and substrate.

F. Label information arrangement for 3 lines of text.

1. Line one shall describe the panel or equipment. Line one example: “DP-XX,” RP-XX,” “T-XX,” “EF-XX,” etc.

2. Line two shall describe the first disconnecting means feeding this panel or equipment. Line two example: “Fed from DP-XX,” “Fed from RP-XX,” etc.

3. Line three indicates that location of the disconnecting means as identified in line two. Line three example: “First Floor Elect. Rm #XXX.”

4. Line four shall include “Via T-XX” when panel or equipment is fed from a transformer.

G. Examples:

RP-1A FED FROM DP-1A ELECTRICAL ROOM A100 VIA T-1A	EF-1 FED FROM MCC-1A MECHANICAL ROOM F101	LP-1A LOCATED IN ELECTRICAL ROOM A100

H. Degrease and clean surface to receive nameplates.

I. Install nameplate and labels parallel to equipment lines.

J. Secure nameplate to equipment front using screws.

END OF SECTION

SECTION 26 5600 – EXTERIOR LIGHTING

PART 1 GENERAL 1
1.01 RELATED DOCUMENTS 1
1.02 SUMMARY 1
1.03 DEFINITIONS 1
1.04 ACTION SUBMITTALS 1
1.05 CLOSEOUT SUBMITTALS 2
1.06 MAINTENANCE MATERIAL SUBMITTALS 2
1.07 QUALITY ASSURANCE 2
1.08 DELIVERY, STORAGE, AND HANDLING 3
1.09 WARRANTY 3
PART 2 PRODUCTS 3
2.01 LUMINAIRES (LIGHTING FIXTURES) 3
2.02 LUMINAIRE REQUIREMENTS 3
2.03 MATERIALS 3
2.04 METAL FINISHES 4
2.05 LUMINAIRE FIXTURE SUPPORT COMPONENTS 4
PART 3 EXECUTION 4
3.01 EXAMINATION 4
3.02 TEMPORARY LIGHTING 4
3.03 INSTALLATION 4
3.04 CONNECTIONS 5
3.05 IDENTIFICATION 5
3.06 FIELD QUALITY CONTROL 5
3.07 CLEANING 5

PART 1 GENERAL

1.01 RELATED DOCUMENTS

A. Drawings and general provisions of the Contract, including General and Supplementary Conditions and Division 01 Specification Sections, apply to this Section.

1.02 SUMMARY

A. Section Includes:

1. Interior solid-state luminaires that use LED technology.
2. Lighting fixture supports.

1.03 DEFINITIONS

A. CCT: Correlated color temperature.

B. CRI: Color Rendering Index.

C. Fixture: See "Luminaire."

D. IP: International Protection or Ingress Protection Rating.

E. Lamp: LED and substrate as a replaceable assembly.

F. LED: Light-emitting diode.

G. Lumen: Measured output of lamp and luminaire, or both.

H. Luminaire: Complete lighting unit, including lamp, reflector, and housing.

1.04 ACTION SUBMITTALS

A. Product Data: For each type of product.

1. Arrange in order of luminaire designation.
2. Include data on features, accessories, and finishes.
3. Include physical description and dimensions of luminaires.
4. Include emergency lighting units, including batteries and chargers.
5. Include life, output (lumens, CCT, and CRI), and energy efficiency data.
6. Photometric data and adjustment factors based on laboratory tests, complying with IESNA Lighting Measurements Testing and Calculation Guides, of each lighting fixture type. The adjustment factors shall be for lamps and accessories identical to those indicated for the lighting fixture as applied in this Project per IES LM-79 and IES LM-80.
    a. Manufacturers' Certified Data: Photometric data certified by manufacturer's laboratory with a current accreditation under the National Voluntary Laboratory Accreditation Program for Energy Efficient Lighting Products or certified by a qualified independent testing agency.

B. Shop Drawings: For nonstandard or custom luminaires.
1. Include plans, elevations, sections, and mounting and attachment details.
2. Include details of luminaire assemblies. Indicate dimensions, weights, loads, required clearances, method of field assembly, components, and location and size of each field connection.
3. Include diagrams for power, signal, and control wiring.

1.05 CLOSEOUT SUBMITTALS

A. Operation and Maintenance Data: For luminaires and lighting systems to include in operation and maintenance manuals.
1. Provide a list of all lamp types used on Project; use ANSI and manufacturers' codes.

1.06 MAINTENANCE MATERIAL SUBMITTALS

A. Furnish extra materials that match products installed and that are packaged with protective covering for storage and identified with labels describing contents.
1. Lamps: 5% attic stock of each type and rating installed. Furnish at least one of each type.
2. LED Drivers: 5% attic stock of each type and rating installed. Furnish at least one of each type.
3. Diffusers and Lenses: 1% attic stock of each type and rating installed. Furnish at least one of each type.

1.07 QUALITY ASSURANCE

A. Luminaire Photometric Data Testing Laboratory Qualifications: Luminaire manufacturer's laboratory that is accredited under the NVLAP for Energy Efficient Lighting Products.

B. Provide luminaires from a single manufacturer for each luminaire type.

C. Each luminaire type shall be binned within a three-step MacAdam Ellipse to ensure color consistency among luminaires.

D. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, Article 100, by a testing agency acceptable to authorities having jurisdiction, and marked for intended use.

E. Comply with:
1. NFPA 70 - National Electrical Code.

2. NECA/IESNA 500-1998 – Recommended Practice for Installing Indoor Commercial Lighting Systems.
3. NECA/IESNA 502-1999 – Recommended Practice for Installing Industrial Lighting Systems.
4. Code of Federal Regulations (47 CFR 37342).
5. Michigan Department of Community Industry Services requirements that all lamps shall be protected from breakage. Exposed lamps are not acceptable.

F. NFPA 101 Compliance: Comply with visibility and luminance requirements for exit signs.

1.08 DELIVERY, STORAGE, AND HANDLING

A. Protect finishes of exposed surfaces by applying a strippable, temporary protective covering before shipping.

1.09 WARRANTY

A. Warranty: Manufacturer and Installer agree to repair or replace components of luminaires that fail in materials or workmanship within specified warranty period.

B. Warranty Period: Five year(s) or manufacturer's standard warranty length (whichever is longer) from date of Substantial Completion.

PART 2 PRODUCTS

2.01 LUMINAIRES (LIGHTING FIXTURES)

A. Provide Luminaires as included in Luminaire schedule shown on drawings.

B. Acceptable alternate manufacturers are indicated on the luminaire schedule. Alternate manufacturer products shall be equal in all respects including materials, finishes, photometric performance and energy performance and shall include all options, features, and accessories identified.

2.02 LUMINAIRE REQUIREMENTS

A. Electrical Components, Devices, and Accessories: Listed and labeled as defined in NFPA 70, by a qualified testing agency, and marked for intended location and application.

B. Unless otherwise specified in Luminaire product data, provide products with an IES LM-80 rated lamp life of 70,000 hours.

C. Driver

1. Provided as an integrated component of the luminaire or as an external component of an assembly of luminaries.
2. Nominal Input Voltage: All drivers shall be rated for use on either 120V or 277V systems.

2.03 MATERIALS

A. Metal Parts:

1. Free of burrs and sharp corners and edges.
2. Sheet metal components shall be steel unless otherwise indicated.
3. Form and support to prevent warping and sagging.

B. Doors, Frames, and Other Internal Access: Smooth operating, free of light leakage under operating conditions, and designed to permit relamping without use of tools. Designed to prevent doors, frames, lenses, diffusers, and other components from falling accidentally during relamping and when secured in operating position.

C. Diffusers and Globes:

1. Acrylic Diffusers: One hundred percent virgin acrylic plastic, with high resistance to yellowing and other changes due to aging, exposure to heat, and UV radiation.
2. Lens Thickness: At least 0.125 inch minimum unless otherwise indicated.

D. Factory-Applied Labels: Comply with UL 1598 Locate labels where they will be readily visible to service personnel, but not seen from normal viewing angles when lamps are in place.

1. Label shall include the following lamp characteristics:
   a. "USE ONLY" and include specific lamp type.
   b. Lamp diameter, shape, size, wattage, and coating.
   c. CCT and CRI for all luminaires.

2.04 METAL FINISHES

A. Variations in finishes are unacceptable in the same piece. Variations in finishes of adjoining components are acceptable if they are within the range of approved Samples and if they can be and are assembled or installed to minimize contrast.

2.05 LUMINAIRE FIXTURE SUPPORT COMPONENTS

A. Comply with requirements in Section 26 0529 "Hangers and Supports for Electrical Systems" for channel and angle iron supports and nonmetallic channel and angle supports.

B. Wires: Unless otherwise specified in Luminaire product data, provide products with a minimum ASTM A 641/A 641 M, Class 3, soft temper, zinc-coated steel, 12 gage.

PART 3 eXECUTION

3.01 EXAMINATION

A. Examine substrates, areas, and conditions, with Installer present, for compliance with requirements for installation tolerances and other conditions affecting performance of the Work.

B. Examine roughing-in for luminaire to verify actual locations of luminaire and electrical connections before fixture installation. Proceed with installation only after unsatisfactory conditions have been corrected.

3.02 TEMPORARY LIGHTING

A. Do not use permanent luminaires for temporary lighting.

3.03 INSTALLATION

A. Install in accordance with manufacturer’s instructions and N.E.C.A./I.E.S.N.A. 500-2006 and 502-2006.

B. Locate ceiling luminaires as indicated on reflected ceiling plan.

C. Support luminaires independent of ceiling framing. Support recessed grid luminaries from two opposite corners directly to structure. Wire or rod shall have breaking strength of the weight of fixture at a safety factor of 3.

D. Install recessed luminaires to permit removal from below.

E. Install recessed luminaires using accessories and firestopping materials to meet regulatory requirements for fire rating.

F. Install luminaires level, plumb, and square with ceilings and walls unless otherwise indicated.

G. Install fixture with no gaps between adjacent fixtures or between fixtures and surrounding surfaces. Trims of fixtures shall be properly and uniformly aligned.

H. Supports:

1. Sized and rated for luminaire weight.
2. Able to maintain luminaire position after cleaning and relamping.
3. Provide support for luminaire without causing deflection of ceiling or wall.
4. Luminaire mounting devices shall be capable of supporting a horizontal force of 100 percent of luminaire weight and vertical force of 400 percent of luminaire weight.

I. Flush-Mounted Luminaire Support:

1. Secured to outlet box.
2. Attached to ceiling structural members at four points equally spaced around circumference of luminaire.
3. Trim ring flush with finished surface.

J. Comply with requirements in Section 26 0519 "Conductors and Cables" for wiring connections.

K. Fixtures shall have their exterior labels removed and shall be thoroughly cleaned.

L. Locate the remote test/monitor modules identically so that they are visible and they form a straight line when viewed from the end of the corridor or room. Where a suspended ceiling exists, center the modules in adjacent ceiling tiles.

3.04 CONNECTIONS

A. Tighten electrical connectors and terminals according to manufacturer's published torque-tightening values. If manufacturer's torque values are not indicated, use those specified in UL 486A and UL 486B.

B. Make wiring connections to branch circuit using building wire with insulation suitable for temperature conditions within luminaire.

C. Bond products and metal accessories to branch circuit equipment grounding conductor.

D. Connect luminaires to branch circuit outlet boxes provided under Division 26 Section "Raceways and Boxes" using 1/2" flexible conduit.

3.05 IDENTIFICATION

A. Identify system components, wiring, cabling, and terminals. Comply with requirements for identification specified in Section 26 0553 "Identification for Electrical Systems."

3.06 FIELD QUALITY CONTROL

A. Perform the following tests and inspections:

1. Operational Test: After installing luminaires, switches, and accessories, and after electrical circuitry has been energized, test units to confirm proper operation.
2. Test for Emergency Lighting: Interrupt power supply to demonstrate proper operation. Verify transfer from normal power to battery power and retransfer to normal.

B. Luminaire will be considered defective if it does not pass operation tests and inspections.

C. Prepare test and inspection reports.

D. A visual inspection shall be performed to verify cleanliness and alignment of the fixtures, misalignment and light leaks shall be corrected, and rattles due to ventilation system vibration shall be eliminated.

3.07 CLEANING

A. Clean electrical parts to remove conductive and deleterious materials.

B. Remove dirt and debris from enclosures and lenses.

C. Clean photometric control surfaces as recommended by manufacturer.

D. Clean finishes and touch up damage.

END OF SECTION