

MATERIAL INVENTORY ASBESTOS SAMPLES

CLIENT: Santa Monica Malibu Unified School District
PROJECT NO: SMSD-19-8865
PROJECT NAME: SMASH/John Muir Bldg 600

Page 1 of 3

Material	Sample No.	Asbestos Content	Sample Location	Material Location	Approx. Qty.	Friable	Damage
Drywall mud	612-1	None Detected	600 northeast	Rooms 600, 602, 605, 610, 612, 615, restrooms, Computer Lab, main entry (walls only)	4,000 SF	No	Yes
Drywall mud	612-2	None Detected	610 southeast				
Drywall mud	612-3	None Detected	Main entry, south west				
Drywall mud	612-4	None Detected	615 northwest				
Drywall mud	612-5	None Detected	610 southwest	Note: Damage at base of the walls in Room 600, 602, Computer Lab, 605, main entry, water damage crew removed baseboard damaging the drywall with mud behind it			
Drywall	612-6	None Detected	600 south center				
Drywall	612-7	None Detected	605 north center				
Composite drywall mud	612-8	None Detected	600 northeast				
6" blue cove base with glue	612-9	None Detected	610 southwest				
6" blue cove base with glue	612-10	None Detected	Computer Lab, east center	Janitor's closet	10 LF	No	No
6" blue cove base with glue	612-11	None Detected	615 southwest				
4" pink cove base with glue	612-12	None Detected	Janitor's closet north center				
4" pink cove base with glue	612-13	None Detected	Janitor's closet southwest				
4" pink cove base with glue	612-14	None Detected	Janitor's closet southeast	Rooms 600, 602, 605, 610, 612, 615, Computer Lab	5,000 LF	No	No
Yellow adhesive for blue carpet	612-15	None Detected	600 center				
Yellow adhesive for blue carpet	612-16	None Detected	605 center				
Yellow adhesive for blue carpet	612-17	None Detected	615 center				

**MATERIAL INVENTORY
ASBESTOS SAMPLES**

CLIENT: Santa Monica Malibu Unified School District
PROJECT NO: SMSD-19-8865
PROJECT NAME: SMASH/John Muir Bldg 600

Page 2 of 3

Material	Sample No.	Asbestos Content	Sample Location	Material Location	Approx. Qty.	Friable	Damage
12"x12" blue speckled floor tile with yellow glue	612-18	None Detected	Main entry, northwest	Rooms 600, 605, main entry, 615	900 SF	No	No
12"x12" blue speckled floor tile with yellow glue	612-19	None Detected	600 north center				
12"x12" blue speckled floor tile with yellow glue	612-20	None Detected	605 north east				
12"x12" pink floor tile with yellow glue	612-21	None Detected	Main entry northwest	Rooms 600, 605, main entry, 615 (under 12" blue floor tile)	900 SF	No	No
12"x12" pink floor tile with yellow glue	612-22	None Detected	600 north center				
12"x12" pink floor tile with yellow glue	612-23	None Detected	605 north east				

Note: Only floors, baseboards and walls were to be tested. No ceramic. Client directed bulk sampling per SMMUSD rep Elizabeth Villalobos.

MATERIAL INVENTORY
LEAD PAINT CHIP SAMPLES

Page 3 of 3

CLIENT: Santa Monica Malibu Unified School District
PROJECT NO: SMSD-19-8865
PROJECT NAME: SMASH/John Muir Bldg 600

Component	Sample No.	Substrate	Paint Color	Sample Location	Material Location	Results (PPM)	Damage	Approx. Damage Qty.
Wall	PC -1	Drywall	Pink	Room 600 north center	Building 600 throughout	<46	No	
Door	PC -2	Wood	Orange	Room 605 north east		<47	No	
Door case	PC -3	Metal	Orange	Room 605 north east		<46	No	

Note: Client directed sampling only walls and doors are to be tested. No ceramic was tested per SMMUSD rep Elizabeth Villalobos.



1508 East 33rd Street
Signal Hill, CA 90755
Toll: 888-207-2022
Tel: 562-206-2770
Fax: 562-206-2773

Alta Environmental
3777 Long Beach Blvd.
Long Beach CA 90807
Attn.: David Schack

Report Number 1935935

Project Number

Project Name SMASH-Bldg 600

Location

PO Number

WO Number

Date Received 06/12/2019

Date Analyzed 06/12/2019

Date Reported 06/12/2019

Date Sampled 06/12/2019

Sampled By F.R.

Total Samples 35

Method of Analysis 40 CFR Part 763 Appendix E to Subpart E, EPA Method 600/M4-82-020; updated method 600 R-93/116
Determination of Asbestos in Bulk Building Materials.

Test Report

Laboratory ID Sample No.	Sample Location Description	Layer No. Layer %	Non-Asbestos Components	(%)	Asbestos Type	(%)
1935935-001 612-1	Bldg 600 Drywall Mud, Cream, Homogeneous	LAYER 1 100%	Perlite Calcium Carbonate Binder/Filler	5% 85% 10%	None Detected	
Asbestos Present: No		Total % Non-Asbestos:		100.0%	Total %Asbestos:	No Asbestos Detected
1935935-002 612-2	Bldg 600 Drywall Mud, Cream, Homogeneous	LAYER 1 100%	Perlite Calcium Carbonate Binder/Filler	5% 85% 10%	None Detected	
Asbestos Present: No		Total % Non-Asbestos:		100.0%	Total %Asbestos:	No Asbestos Detected
1935935-003 612-3	Bldg 600 Drywall Mud, Cream, Homogeneous	LAYER 1 100%	Perlite Calcium Carbonate Binder/Filler	5% 85% 10%	None Detected	
Asbestos Present: No		Total % Non-Asbestos:		100.0%	Total %Asbestos:	No Asbestos Detected
1935935-004 612-4	Bldg 600 Drywall Mud, Cream, Homogeneous	LAYER 1 100%	Perlite Calcium Carbonate Binder/Filler	5% 85% 10%	None Detected	
Asbestos Present: No		Total % Non-Asbestos:		100.0%	Total %Asbestos:	No Asbestos Detected
1935935-005 612-5	Bldg 600 Drywall Mud, Cream, Homogeneous	LAYER 1 100%	Perlite Calcium Carbonate Binder/Filler	5% 85% 10%	None Detected	
Asbestos Present: No		Total % Non-Asbestos:		100.0%	Total %Asbestos:	No Asbestos Detected



1508 East 33rd Street
Signal Hill, CA 90755
Toll: 888-207-2022
Tel: 562-206-2770
Fax: 562-206-2773

Alta Environmental
3777 Long Beach Blvd.
Long Beach CA 90807
Attn.: David Schack

Report Number 1935935

Project Number

Project Name SMASH-Bldg 600

Location

PO Number

WO Number

Date Received 06/12/2019

Date Analyzed 06/12/2019

Date Reported 06/12/2019

Date Sampled 06/12/2019

Sampled By F.R.

Total Samples 35

Method of Analysis 40 CFR Part 763 Appendix E to Subpart E, EPA Method 600/M4-82-020; updated method 600 R-93/116
Determination of Asbestos in Bulk Building Materials.

Test Report

Laboratory ID Sample No.	Sample Location Description	Layer No. Layer %	Non-Asbestos Components	(%)	Asbestos Type	(%)
1935935-006 612-6	Bldg 600 Drywall, White/ Brown, Non-homogeneous	LAYER 1 100%	Cellulose Fiber Fibrous Glass Gypsum/Filler	10% <1 90%	None Detected	
Asbestos Present: No		Total % Non-Asbestos:		100.0%	Total %Asbestos:	No Asbestos Detected
1935935-007 612-7	Bldg 600 Drywall, White/ Brown, Non-homogeneous	LAYER 1 100%	Cellulose Fiber Fibrous Glass Gypsum/Filler	10% <1 90%	None Detected	
Asbestos Present: No		Total % Non-Asbestos:		100.0%	Total %Asbestos:	No Asbestos Detected
1935935-008 612-8	Bldg 600 Composite Drywall w/ Mud, White/Brown/Cream, Non-homogeneous	LAYER 1 100%	Cellulose Fiber Fibrous Glass Calcium Carbonate	5% <1 20%	None Detected	
Asbestos Present: No		Total % Non-Asbestos:		100.0%	Total %Asbestos:	No Asbestos Detected
1935935-009 612-9A	Bldg 600 6" Cove Base, Blue, Homogeneous	LAYER 1 100%	Vinyl Binder/ Filler	100%	None Detected	
Asbestos Present: No		Total % Non-Asbestos:		100.0%	Total %Asbestos:	No Asbestos Detected
1935935-010 612-9B	Bldg 600 Glue, Cream, Homogeneous	LAYER 1 100%	Organic Binders/Filler	100%	None Detected	
Asbestos Present: No		Total % Non-Asbestos:		100.0%	Total %Asbestos:	No Asbestos Detected
1935935-011 612-10A	Bldg 600 6" Cove Base, Blue, Homogeneous	LAYER 1 100%	Vinyl Binder/ Filler	100%	None Detected	
Asbestos Present: No		Total % Non-Asbestos:		100.0%	Total %Asbestos:	No Asbestos Detected



1508 East 33rd Street
Signal Hill, CA 90755
Toll: 888-207-2022
Tel: 562-206-2770
Fax: 562-206-2773

Alta Environmental
3777 Long Beach Blvd.
Long Beach CA 90807
Attn.: David Schack

Report Number 1935935

Date Received 06/12/2019

Date Analyzed 06/12/2019

Date Reported 06/12/2019

Method of Analysis 40 CFR Part 763 Appendix E to Subpart E, EPA Method 600/M4-82-020; updated method 600 R-93/116
Determination of Asbestos in Bulk Building Materials.

Project Number

Project Name SMASH-Bldg 600

Location

PO Number

WO Number

Date Sampled 06/12/2019

Sampled By F.R.

Total Samples 35

Test Report

Laboratory ID Sample No.	Sample Location Description	Layer No. Layer %	Non-Asbestos Components	(%)	Asbestos Type	(%)
1935935-012 612-10B	Bldg 600 Glue, Cream, Homogeneous	LAYER 1 100%	Organic Binders/Filler	100%	None Detected	
Asbestos Present: No		Total % Non-Asbestos:		100.0%	Total %Asbestos:	No Asbestos Detected
1935935-013 612-11A	Bldg 600 6" Cove Base, Blue, Homogeneous	LAYER 1 100%	Vinyl Binder/ Filler	100%	None Detected	
Asbestos Present: No		Total % Non-Asbestos:		100.0%	Total %Asbestos:	No Asbestos Detected
1935935-014 612-11B	Bldg 600 Glue, Cream, Homogeneous	LAYER 1 100%	Organic Binders/Filler	100%	None Detected	
Asbestos Present: No		Total % Non-Asbestos:		100.0%	Total %Asbestos:	No Asbestos Detected
1935935-015 612-12A	Bldg 600 4" Cove Base, Pink (Brown), Homogeneous	LAYER 1 100%	Calcium Carbonate Vinyl Binder	25% 75%	None Detected	
Asbestos Present: No		Total % Non-Asbestos:		100.0%	Total %Asbestos:	No Asbestos Detected
1935935-016 612-12B	Bldg 600 Glue, White, Homogeneous	LAYER 1 100%	Organic Binders/Filler	100%	None Detected	
Asbestos Present: No		Total % Non-Asbestos:		100.0%	Total %Asbestos:	No Asbestos Detected
1935935-017 612-13A	Bldg 600 4" Cove Base, Pink (Brown), Homogeneous	LAYER 1 100%	Calcium Carbonate Vinyl Binder	25% 75%	None Detected	
Asbestos Present: No		Total % Non-Asbestos:		100.0%	Total %Asbestos:	No Asbestos Detected



1508 East 33rd Street
Signal Hill, CA 90755
Toll: 888-207-2022
Tel: 562-206-2770
Fax: 562-206-2773

Alta Environmental
3777 Long Beach Blvd.
Long Beach CA 90807
Attn.: David Schack

Report Number 1935935

Project Number

Project Name SMASH-Bldg 600

Location

PO Number

WO Number

Date Received 06/12/2019

Date Analyzed 06/12/2019

Date Reported 06/12/2019

Date Sampled 06/12/2019

Sampled By F.R.

Total Samples 35

Method of Analysis 40 CFR Part 763 Appendix E to Subpart E, EPA Method 600/M4-82-020; updated method 600 R-93/116
Determination of Asbestos in Bulk Building Materials.

Test Report

Laboratory ID Sample No.	Sample Location Description	Layer No. Layer %	Non-Asbestos Components	(%)	Asbestos Type	(%)
1935935-018 612-13B	Bldg 600 Glue, White, Homogeneous	LAYER 1 100%	Organic Binders/Filler	100%	None Detected	
Asbestos Present: No		Total % Non-Asbestos:		100.0%	Total %Asbestos:	No Asbestos Detected
1935935-019 612-14A	Bldg 600 4" Cove Base, Pink (Brown), Homogeneous	LAYER 1 100%	Calcium Carbonate Vinyl Binder	25% 75%	None Detected	
Asbestos Present: No		Total % Non-Asbestos:		100.0%	Total %Asbestos:	No Asbestos Detected
1935935-020 612-14B	Bldg 600 Glue, White, Homogeneous	LAYER 1 100%	Organic Binders/Filler	100%	None Detected	
Asbestos Present: No		Total % Non-Asbestos:		100.0%	Total %Asbestos:	No Asbestos Detected
1935935-021 612-15	Bldg 600 Adhesive for blue carpet, Yellow, Homogeneous	LAYER 1 100%	Organic Binders/Filler	100%	None Detected	
Asbestos Present: No		Total % Non-Asbestos:		100.0%	Total %Asbestos:	No Asbestos Detected
1935935-022 612-16	Bldg 600 Adhesive for blue carpet, Yellow, Homogeneous	LAYER 1 100%	Organic Binders/Filler	100%	None Detected	
Asbestos Present: No		Total % Non-Asbestos:		100.0%	Total %Asbestos:	No Asbestos Detected
1935935-023 612-17	Bldg 600 Adhesive for blue carpet, Yellow, Homogeneous	LAYER 1 100%	Organic Binders/Filler	100%	None Detected	
Asbestos Present: No		Total % Non-Asbestos:		100.0%	Total %Asbestos:	No Asbestos Detected



1508 East 33rd Street
Signal Hill, CA 90755
Toll: 888-207-2022
Tel: 562-206-2770
Fax: 562-206-2773

Alta Environmental
3777 Long Beach Blvd.
Long Beach CA 90807
Attn.: David Schack

Report Number 1935935

Project Number

Project Name SMASH-Bldg 600

Location

PO Number

WO Number

Date Received 06/12/2019

Date Analyzed 06/12/2019

Date Reported 06/12/2019

Date Sampled 06/12/2019

Sampled By F.R.

Total Samples 35

Method of Analysis 40 CFR Part 763 Appendix E to Subpart E, EPA Method 600/M4-82-020; updated method 600 R-93/116
Determination of Asbestos in Bulk Building Materials.

Test Report

Laboratory ID Sample No.	Sample Location Description	Layer No. Layer %	Non-Asbestos Components	(%)	Asbestos Type	(%)
1935935-024 612-18A	Bldg 600 12"x12" Floor Tile, Blue, Homogeneous	LAYER 1 100%	Calcium Carbonate Vinyl Binder	60% 40%	None Detected	
Asbestos Present: No		Total % Non-Asbestos:		100.0%	Total %Asbestos:	No Asbestos Detected
1935935-025 612-18B	Bldg 600 Glue, Yellow, Homogeneous	LAYER 1 100%	Organic Binders	100%	None Detected	
Asbestos Present: No		Total % Non-Asbestos:		100.0%	Total %Asbestos:	No Asbestos Detected
1935935-026 612-19A	Bldg 600 12"x12" Floor Tile, Blue, Homogeneous	LAYER 1 100%	Calcium Carbonate Vinyl Binder	60% 40%	None Detected	
Asbestos Present: No		Total % Non-Asbestos:		100.0%	Total %Asbestos:	No Asbestos Detected
1935935-027 612-19B	Bldg 600 Glue, Yellow, Homogeneous	LAYER 1 100%	Organic Binders	100%	None Detected	
Asbestos Present: No		Total % Non-Asbestos:		100.0%	Total %Asbestos:	No Asbestos Detected
1935935-028 612-20A	Bldg 600 12"x12" Floor Tile, Blue, Homogeneous	LAYER 1 100%	Calcium Carbonate Vinyl Binder	60% 40%	None Detected	
Asbestos Present: No		Total % Non-Asbestos:		100.0%	Total %Asbestos:	No Asbestos Detected
1935935-029 612-20B	Bldg 600 Glue, Yellow (Orange), Homogeneous	LAYER 1 100%	Organic Binders	100%	None Detected	
Asbestos Present: No		Total % Non-Asbestos:		100.0%	Total %Asbestos:	No Asbestos Detected



1508 East 33rd Street
Signal Hill, CA 90755
Toll: 888-207-2022
Tel: 562-206-2770
Fax: 562-206-2773

Alta Environmental
3777 Long Beach Blvd.
Long Beach CA 90807
Attn.: David Schack

Report Number 1935935

Project Number

Project Name SMASH-Bldg 600

Location

PO Number

WO Number

Date Received 06/12/2019

Date Analyzed 06/12/2019

Date Reported 06/12/2019

Date Sampled 06/12/2019

Sampled By F.R.

Total Samples 35

Method of Analysis 40 CFR Part 763 Appendix E to Subpart E, EPA Method 600/M4-82-020; updated method 600 R-93/116
Determination of Asbestos in Bulk Building Materials.

Test Report

Laboratory ID Sample No.	Sample Location Description	Layer No. Layer %	Non-Asbestos Components	(%)	Asbestos Type	(%)
1935935-030 612-21A	Bldg 600 12"x12" Floor Tile, Pink, Homogeneous	LAYER 1 100%	Quartz Calcium Carbonate Vinyl Binder	5% 50% 45%	None Detected	
Asbestos Present: No		Total % Non-Asbestos:		100.0%	Total %Asbestos:	No Asbestos Detected
1935935-031 612-21B	Bldg 600 Glue, Yellow, Homogeneous	LAYER 1 100%	Organic Binders	100%	None Detected	
Asbestos Present: No		Total % Non-Asbestos:		100.0%	Total %Asbestos:	No Asbestos Detected
1935935-032 612-22A	Bldg 600 12"x12" Floor Tile, Pink, Homogeneous	LAYER 1 100%	Quartz Calcium Carbonate Vinyl Binder	5% 50% 45%	None Detected	
Asbestos Present: No		Total % Non-Asbestos:		100.0%	Total %Asbestos:	No Asbestos Detected
1935935-033 612-22B	Bldg 600 Glue, Yellow, Homogeneous	LAYER 1 100%	Organic Binders	100%	None Detected	
Asbestos Present: No		Total % Non-Asbestos:		100.0%	Total %Asbestos:	No Asbestos Detected
1935935-034 612-23A	Bldg 600 12"x12" Floor Tile, Pink, Homogeneous	LAYER 1 100%	Quartz Calcium Carbonate Vinyl Binder	5% 50% 45%	None Detected	
Asbestos Present: No		Total % Non-Asbestos:		100.0%	Total %Asbestos:	No Asbestos Detected
1935935-035 612-23B	Bldg 600 Glue, Yellow, Homogeneous	LAYER 1 100%	Organic Binders	100%	None Detected	
Asbestos Present: No		Total % Non-Asbestos:		100.0%	Total %Asbestos:	No Asbestos Detected



1508 East 33rd Street
Signal Hill, CA 90755
Toll: 888-207-2022
Tel: 562-206-2770
Fax: 562-206-2773

Alta Environmental
3777 Long Beach Blvd.
Long Beach CA 90807
Attn.: David Schack

Report Number 1935935

Date Received 06/12/2019

Date Analyzed 06/12/2019

Date Reported 06/12/2019

Project Number

Project Name SMASH-Bldg 600

Location

PO Number

WO Number

Date Sampled 06/12/2019

Sampled By F.R.

Total Samples 35

Method of Analysis 40 CFR Part 763 Appendix E to Subpart E, EPA Method 600/M4-82-020; updated method 600 R-93/116
Determination of Asbestos in Bulk Building Materials.

Test Report

Laboratory ID Sample No.	Sample Location Description	Layer No. Layer %	Non-Asbestos Components (%)	Asbestos Type (%)
-----------------------------	--------------------------------	----------------------	--------------------------------	----------------------

Method Detection Limit: Less than one percent (<1%). Asbestos content has been determined using calibrated visual estimation (CVES). Samples tested were received in acceptable condition unless otherwise stated. Test report relates only to items tested. Non-homogeneous samples containing discrete and separable layers are analyzed and reported separately; composite results may be reported upon customer's request. Non-homogeneous samples with inseparable layers are analyzed and reported as composite samples. Due to the limitations of Polarized Light Microscopy, samples reported as None Detected or with low asbestos concentrations may not be reliable and further analysis such as TEM is recommended to confirm PLM results. This report shall not be reproduced except in full without the written approval of this laboratory. This report may not be used by the customer to claim product certification, endorsement, or approval by NIST/NVLAP or any agency of the government. Samples shall be disposed according to local, state and federal laws, 30 days after results are reported unless otherwise instructed.

CA-ELAP #2823

Analyst - Cristina Tabatt

Approved Signatory Cristina E. Tabatt



NVLAP Lab Code 500044-0



1508 East 33rd Street
Signal Hill, CA 90755
Tel (562) 206-2770
Fax (562) 206-2773

Alta Environmental
3777 Long Beach Boulevard
Long Beach, CA 90807
Attention: D. Schack

Project Number:
Project Name: SMASH - Bldg 600
Location:

Report Number: 1935936

Date Received: 6/12/2019
Date Analyzed: 6/12/2019
Date Reported: 6/12/2019

Date Sampled: 6/12/2019
Sampled By: F.R.
Total Samples: 3

Analytical Method: EPA 7420/3050
Reporting Limit: 5.0 µg Pb

Lead (Pb) in Paint by Flame AAS

Lab ID Client ID	Location/Description	Sample Weight (g)	Lead Concentration ppm (mg/kg)
1935936-001 PC-1	Wall Drywall Pink - Bldg 600	0.1095	< 46
1935936-002 PC-2	Door Wood Orange - Bldg 600	0.1069	< 47
1935936-003 PC-3	Door Case Metal Orange - Bldg 600	0.1090	< 46

Samples tested were received in acceptable condition unless otherwise stated. Test report relates only to items tested. This report shall not be reproduced without the written approval of this laboratory. The client shall be solely responsible for interpreting analytical results. Samples have not been blank corrected. Samples shall be disposed according to local, state and federal laws, 30 days after reporting results.

CA ELAP Cert #2823

Approved Signatory- Cristina E. Tabatt

CHAIN OF CUSTODY

1508 E. 33rd Street
Signal Hill, CA 90755
562-206-2770 Tel
562-206-2773 Fax
services@AQenvlabs.com

(Lab) Order No. PLM: 1935935 / pb: 1935935

CUSTOMER INFORMATION		Turnaround Time	Shipped By	Report Send Via:
Company	Alta Environmental	Same Day ☒	Fedex ☐	Web ☐
Address	3777 Long Beach Blvd	1 Day ☐	UPS ☐	Email ☒
City/State/Zip	Long Beach Ca	2 Day ☐	USPS ☐	Fax ☐
Contact	D. Schack	3 Day ☐	Drop Off ☒	Verbal ☐
Office Phone		5 Day ☐	Drop Box ☐	Mail ☐
Cell		Weekend ☐	Other ☐	Pick up ☐
Fax		Special Instructions: * - Paint dips only		
Email				

PROJECT INFORMATION	
Project Name: SMASH - Bldg 600	PO Number:
Project Number:	Work Order No.:
Location:	Sampled By: F.R.

PLM	PCM	MOLD	LEAD (Pb)
PLM EPA 600/M4-82-020 ☒	NIOSH 7400A ☐	Spore Trap ☐	Air ☐ TTLC ☐
PLM 400 Pt. Count (<0.25%) ☐	NIOSH 7400B ☐	Tape Lift ☐	Paint ☒
PLM 1000 Pt. Count (<0.1%) ☐	w/ TWA ☐	Bulk Sample ☐	Wipe ☐
		Swab ☐	Soil ☐

SAMPLE ID	SAMPLE TYPE	LOCATION	Date Sampled	Start Time	Stop Time	Avg Flow Rate	Volume (L)
PC-1	wall Drywall Pink	Bldg 600	6/12/19				
-2	Door Wood Orange						
-3	Door Core Metal Orange						
612-1	Drywall Mud						
2							
3							
4							
5							
6	Drywall						
7							

Relinquished By: Fabian Funches	Received By: P. J. Abbott
Date/Time: 6-12-19 0900	Date/Time: 06/12/19, 09:00
Relinquished By:	Received By:
Date/Time:	Date/Time:



CHAIN OF CUSTODY

1508 E. 33rd Street
Signal Hill, CA 90755
562-206-2770 Tel
562-206-2773 Fax
services@AQenvlabs.com

Company:

Alfa

Project Number:

Project Name:

SMASH - Bldg 600

(Lab) Order No.

PLM: 1935935

Pb: 1935936

SAMPLE ID	SAMPLE TYPE	LOCATION	Date Sampled	Start Time Stop Time	Avg Flow Rate	Volume (L)
612-8	Composite - Direct v/ dead	Bldg 600	6-12-19			
9	6" Blue Lumber w/ Blue					
10						
11	J					
12	4" Pink Lumber w/ blue					
13	J					
14	J					
15	Yellow adhesive for Blue Lumber					
16	J					
17	J					
18	12"x12" Blue floor tile w/ Yellow Blue					
19	J					
20	J					
21	12"x12" Pink floor					
22	tile w/ Yellow Blue					
23	J					

Relinquished By: *Alfonso Raul Garcia*

Received By: *M. Abbott*

Date/Time: 6-12-19 0900

Date/Time: 06/12/19, 19:00

Relinquished By:

Received By:

Date/Time:

Date/Time: