



REQUEST FOR PROPOSAL – Timberlane Regional School District

Timberlane Regional High School Fence Replacement 2025

SAU 106 (Timberlane Regional School District “TRSD” or “the district”) requests sealed proposals to remove and dispose of perimeter fencing, as outlined in the attached specification document. All sealed proposals must be submitted by Friday, June 13, 2025, at 9:00 AM, with the bid opening on June 13 at 1:00 PM.

The company shall submit a statement with the proposal, indicating school experience, along with the names of the school districts previously and/or currently served, the involved dates, and the scope of services performed.

Proposals must remain valid for 96 hours after the opening.

The SAU may conduct an investigation as necessary to determine the company's capacity to execute the work. Upon request, the company must provide the SAU with all relevant information and data needed for this purpose. The Superintendent retains the authority to accept or reject any proposals, or any individual item(s) within them, waive any informalities in the procurement process, and cancel, either partially or entirely, the request for proposals. The Superintendent will award the contract in a manner deemed to be in the School District's best interests. The School District reserves the right to select the proposal that most effectively meets the District's requirements as determined by the Superintendent. Although price will be a significant factor in the evaluation, the Superintendent retains the right to select a vendor even if it does not submit the lowest cost proposal.

Each proposer must clearly express any deviation from the conditions and specifications in the appropriate space on the proposal form. Unless stated by the proposer and accepted by the districts, all conditions and specifications apply.

Any fraudulent or inaccurate statements or willful concealment of relevant information by the Proposer are grounds for rejecting that proposal and terminating any subsequent contract. The Proposer may not withdraw proposals after the proposal opening.

The successful proposer, known as the contractor, shall be ready to enter into a written contract with the school district following the District's written acceptance of the proposal. Work is to be completed at a mutually agreeable time.

Once the district has evaluated project costs, final decisions on quantities and any limits to the scope of work shall be noted in the agreement/contract.

All contractors or companies submitting proposals must provide the labor, materials, tools, and equipment necessary to complete the task and anything else reasonably implied to complete this contract promptly and satisfactorily.

All proposals must be submitted in a sealed envelope marked “RFP-TRHS Perimeter Fencing” and addressed to Justin Krieger, Superintendent, Timberlane Regional School District, 30 Greenough Road, Plaistow, NH 03865, no later than Friday, June 13, 2025, at 9:00 am. **The bid opening will be on June 13 at 1:00 PM.**

Please direct all questions to:

Frank Janvrin, Director of Facilities, frank.janvrin@timberlane.net

SAU 106 – 30 Greenough Road, Plaistow, NH 03865 (603) 382-6119



TRHS Perimeter Fencing Scope

Area 1

- Remove and dispose of 858 feet of existing chain link.
- Approximately 858 feet of commercial-grade, all-black vinyl chain link fence.
- 3" SS40 terms and gate posts, 2 ½" lines, 1 5/8" top rail.
- 2X8 #2 grade permafused chain link mesh.
- All posts are set in concrete footings.
- (1) 6' X 12' double swing gate.
- (1) 6' X 10' single swing gate.
- Add 858 feet of bottom rail.

Area 2

- Remove and dispose of 1024 feet of existing chain link.
- Post cut off below ground level.
- Approximately 1024' of commercial-grade, all-black vinyl chain link fence.
- 3" SS40 terminal and gate posts, 2 ½" line posts, 1 5/8" top rail.
- 2X8 #2 grade permafused chain link mesh.
- All posts are set in concrete footings.
- (1) Walk-through section.
- No gates.
- Add 1024 feet of bottom rail.

Area 3

- Remove and dispose of 427 feet of existing chain link.
- Post cut off below ground level.
- Approximately 427 feet of commercial-grade, all-black vinyl chain link fence.
- 3" SS40 terms and gate posts, 2 ½" lines, and 1 5/8" top rail.
- 2X8 #2 grade permafused chain link mesh.
- All posts are set in concrete footings.
- (1) 6'X12' double swing gate.
- (1) walk-through section.
- Add 427 feet of bottom rail.



NH School Administrative Unit 106 | Timberlane Regional School District

30 Greenough Road, Plaistow, NH 03865 Voice: (603) 382-6119 Fax: (603) 382-3334

 Timberlane.net

 @TimberlaneRegional

 @TimberlaneRSD

 @TimberlaneRSD

Proposal Submittal

Sealed proposals are due on Friday, June 13, 2025, at 9:00 AM, with the bid opening on June 13 at 1:00 PM at the SAU 106 office Building at 30 Greenough Road, Plaistow, NH 03865

COMPANY PROFILE and REQUIRED SUBMITTALS

Please provide the following information about your business. This form is necessary for submitting your proposal. You may attach extra sheets or documents as needed.

1. DUNS Number or Federal Tax ID # _____
2. Size of Company: Total number of employees _____
Total number of service employees _____
3. Number of years in business _____
4. Number of years under current management _____
5. Office locations (service, retail, other) _____
6. Please provide the website address: _____

List three references for which your company performed similar scope and size work. Include the company or agency name, contact name, telephone number, and email address.

- 1) _____

- 2) _____

- 3) _____

(Company Name)

(Print Name)

(Authorized Signature & Title)

(Date)



NH School Administrative Unit 106 | Timberlane Regional School District

30 Greenough Road, Plaistow, NH 03865 Voice: (603) 382-6119 Fax: (603) 382-3334

 Timberlane.net

 [@TimberlaneRegional](https://www.facebook.com/TimberlaneRegional)

 [@TimberlaneRSD](https://www.instagram.com/TimberlaneRSD)

 [@TimberlaneRSD](https://twitter.com/TimberlaneRSD)