

SECTION 27 00 00**COMMUNICATIONS BASIC REQUIREMENTS****PART 1 - GENERAL****1.01 SUMMARY**

- A. This Section specifies the common administration basic requirements and common methods for all low voltage systems installation work included under Division 27 and 28 (and other Divisions). Where those requirements differ from the requirements of this section, the more stringent shall govern.

1.02 STANDARDS, REGULATIONS, AND CODES REFERENCES

- A. The following Standards, Regulations and Codes apply to work specified in the Contract Documents.
1. Applicable State and Local Codes.
 2. California Building Code and California Electrical Code, Current Editions.
 3. BICSI TDMM (Telecommunications Distribution Methods Manual), 11th Edition 2006.
 4. ANSI/TIA/EIA-568-B.1. Commercial Building Telecommunications Cabling Standard,
 5. ANSI/TIA/EIA-568-B.1-2. Commercial Building Telecommunications Cabling Standard, Part 1: General Requirements, Addendum 2, Grounding and Bonding Specifications for Screened Balanced Twisted-Pair Horizontal Cabling.
 6. ANSI/TIA/EIA-568-B.1-3. Commercial Building Telecommunications Cabling Standard.
 7. ANSI/TIA/EIA-568-B.1-4. Commercial Building Telecommunications Cabling Standard, Part 1: General Requirements, Addendum 4, Recognition of Category 6 and Category Cat 6A and 50 nm Laser-Optimized 50/125 um Multimode Optical Fiber Cabling.
 8. ANSI/TIA/EIA-568-B.1-2. Commercial Building Telecommunications Cabling Standard, Part 2: Balanced Twisted-Pair Cabling Components.
 9. ANSI/TIA/EIA-568-B.2-1. Commercial Building Telecommunications Cabling Standard, Part 2: Balanced Twisted-Pair Cabling Components, Addendum 1, Transmission Performance Specifications for 4-Pair 100 Ohm Category 6 Cabling.
 10. ANSI/TIA/EIA-568-B.2-10 (draft 2.0). Commercial Building Telecommunications Cabling Standard, Part 2: Balanced Twisted-Pair Cabling Components, Addendum 10, Transmission Performance Specifications for 4-Pair 100 Ohm Augmented Category 6 Cabling.
 11. ANSI/TIA/EIA-568-B3.3 Optical Fiber Cabling Components Standard.
 12. TIA-569-B. Commercial Building Standard for Telecommunications Pathways and Spaces.
 13. ANSI/TIA/EIA-606-A. Administration Standard for Commercial Telecommunications Infrastructure.
 14. ANSI/TIA/EIA-607-A. Commercial Building Grounding (Earthing) and Bonding Requirements for Telecommunications.

15. TIA/EIA TSB-67 Transmission Performance Specifications for Field Testing of Unshielded Twisted-Pair Cabling Systems.

16. TIA/EIA TSB-72 Centralized Optical Fiber Cabling Guidelines.

1.03 DEFINITIONS

A. The following is a list of abbreviations generally used in Divisions 27 & 28:

1. ADA - Americans with Disabilities Act
2. AHJ - Authority Having Jurisdiction
3. ANSI - American National Standards Institute
4. APWA - American Public Works Association
5. ASTM - American Society for Testing and Materials
6. CBC - California Building Code
7. CEC - California Electrical Code
8. CFC - California Fire Code
9. FCC - Federal Communications Commission
10. HVAC - Heating, Ventilating and Air Conditioning
11. IEC - International Electro-technical Commission
12. IEEE - Institute of Electrical and Electronics Engineers.
13. IETA - International Electrical Testing Association
14. FM - FM Global
15. NEMA - National Electrical Manufacturers Association
16. NFPA - National Fire Protection Association
17. OSHA - Occupational Safety and Health Administration
18. UL - Underwriters Laboratories Inc.

B. Provide: To furnish and install, complete and ready for the intended use.

C. Furnish: Supply and deliver to the project site, ready for unpacking, assembly, and installation.

D. Install: Includes unloading, unpacking, assembling, erecting, installing, applying, finishing, protecting, cleaning, and similar operations at the project site to complete items of work furnished by others.

E. Following is a list of commonly used terms:

1. Active Equipment: Electronic equipment used to develop various WAN and LAN services.
2. Backbone: Collective term sometimes used to describe the campus and vertical distribution subsystem facilities and media interconnecting service entrances, communications rooms, and communications cabinets.
3. Bonding: Permanent joining of metallic parts to form an electrically conductive path which will assure electrical continuity and the capacity to safely conduct currents likely to be imposed on it.
4. Cabinet: Wall-mounted modular enclosure designed to house and protect electronic equipment.

5. Cable Tray: Vertical or horizontal open supports, usually made of aluminum or steel, that are fastened to a building ceiling or wall. Cables are laid in and fastened to the trays. A cable tray is not a raceway.
6. Campus: Grounds and buildings of a multi-building premises environment.
7. Channel: The end-to-end transmission path between two points at which application specific equipment is connected; may include one or more links, cross-connect jumper and/or patch cords, and work area station cords. Does not include connections to active equipment.
8. Cross-Connect: Equipment used to terminate and tie together communications circuits.
9. Cross-Connect Jumper: A cluster of twisted-pair conductors without connectors used to establish a circuit by linking two cross-connect termination points.
10. Fiber Optic Distribution Unit (FDU): Cabinet with terminating equipment used to develop fiber optic cross-connect facilities. Also known as LIU.
11. Grounding: a conducting connection to earth, or to some conducting body that serves in place of earth.
12. Hinged Cover Enclosure: Wall-mounted box with a hinged cover that is used to house and protect electrical devices.
13. Horizontal: Pathway facilities and media connecting the MDF or IDF to Telecommunications Outlets.
14. Intermediate Distribution Frame (IDF): Data networking equipment rack and/or location that serves an individual area, floor or building. Downstream from the MDF.
15. Jack: Receptacle used in conjunction with a plug to make electrical contact between communications circuits, e.g., eight-position/eight-contact modular jacks.
16. Link: A transmission path between two points, not including terminal equipment, work area cables, and equipment cables; one continuous section of conductors or fiber, including the connecting hardware at each end.
17. Local Area Network (LAN): Data transmission facility connecting several communicating devices, typically Ethernet and the network is limited to a single campus.
18. Main Distribution Frame (MDF): Initial (main) data network equipment rack and/or location. Only one MDF occurs per site and may serve many downstream IDFs.
19. Media: The type of cable (e.g., twisted-pair, coaxial, or fiber optic) used to provide signal transmission paths.
20. Minimum Point of Entry (MPOE): The location where the service provider hands off connection and responsibility for service to on-premise customer owned equipment.
21. Modular plug: An eight-position, eight-conductor end-of-wire electrical connector used with Category rated cable.
22. Passive Equipment: Non-electronic hardware and apparatus, e.g., equipment racks, cable trays, electrical protection, wiring blocks, FDUs, etc.
23. Patch Cord: A length of copper or fiber cable with connectors on both ends used to join communications circuits at MDF/IDF and end stations.
24. Patch Panel: System of terminal blocks or connectors used with patch cords that facilitate the administration of cross-connect fields.

- 25. Pathway: Facility for the placement of communications cable. A pathway facility can be composed of several components including conduit, wireway, cable tray, surface raceway, underfloor systems, raised floor, ceiling support wires, etc.
- 26. Protectors: Electrical protection devices used to limit foreign voltages on metallic communications circuits.
- 27. Raceway: An enclosed channel designed expressly for holding wires or cables; may either conductive metal or insulating plastic. The term includes conduit, tubing, wireway, underfloor raceway, and surface raceway; does not include cable tray.
- 28. Rack: An open or enclosed structure, typically made of aluminum or steel, used to mount equipment; usually referred to as an equipment rack. Maybe freestanding and floor mounted or a wall mounted cabinet. Industry standard 19" width spacing.
- 29. Wiring Block: Punch down terminating equipment used to develop twisted pair cross-connect facilities.

1.04 PRODUCT AVAILABILITY

- A. Products with long lead times are to be brought to the attention of the project manager.

1.05 PRODUCT SUBMITTALS

- A. See Division 01 Submittals for more requirements

1.06 SUBSTITUTION LIMITATIONS

- A. Equivalent product(s) may be considered for substitution for those products specified, however, the equivalent product(s) must be approved, and show demonstrated and documented equivalence to the product(s) specified. Documentation includes, but is not limited to, product samples, data sheets, and actual test data. The request for product substitution, and supporting documentation, must be submitted to the Project Manager/Designer in writing.
- B. See Division 01 Substitutions for more requirements

1.07 QUALITY ASSURANCE

- A. The Contractor is to conform to requirements of the latest adopted version of the CEC with amendments by local AHJs.
- B. The Contractor is to conform to the latest adopted version of the CBC with amendments by local AHJs.
- C. The Contractor is to obtain and pay for electrical permits, plan review, and inspections from local AHJs.

- D. The Contractor is to furnish products listed by UL or other testing firm acceptable to AHJ.
- E. The Contractor is to conform to requirements of the Service Providers (i.e., electric, telephone, broadband and cable television).
- F. Contractor Qualifications:
 - 1. The Contractor shall have a minimum of five years' experience in the design, installation, testing, and maintenance of low-voltage systems.
 - 2. The Contractor shall maintain a local service facility which stocks spare devices and/or components for servicing systems.
 - 3. The Contractor shall have performed successful installation and maintenance of at least three projects similar in scope and size. The Contractor must be able to provide project references for these three projects, including scope of Work, project type, owner/user contact name and telephone number.
 - 4. For sections requiring installation personnel to be certified by the manufacturer, the Contractor selected for this project shall provide current certificates for all technicians working on the project.
 - 5. The Contractor shall hold and maintain a valid California C-7 or C-10 State Contractors License, and can exhibit validity upon request.
 - 6. The Contractor shall provide a list of test equipment proposed for use in verifying the installed integrity of copper and fiber optic cable systems used.
 - 7. The Contractor shall provide the resume for the contractor's Project Manager and on-site Installation Supervisor who will be assigned to this project.
 - 8. The Contractor shall provide a list of technical product training attended by the contractor's personnel that will install the specified manufacturer system.
 - 9. The Contractor shall provide a list of Sub-Contractor(s) who will assist the Contractor in the performance of this work.

1.08 SEQUENCING AND SCHEDULING

- A. For the proper execution of the work, the Contractor shall cooperate with other trades and contracts as needed.
- B. To avoid installation conflicts, the Contractor shall thoroughly examine the complete set of Contract Documents, and resolve conflicts with Project Manager/Designer prior to installation.
- C. Prior to installation of communications cable to equipment requiring connections, examine the manufacturer's shop drawings, wiring diagrams, product data, and installation instructions. Verify that the electrical characteristics detailed in the Contract Documents are consistent with the electrical characteristics of the actual equipment being installed. When

inconsistencies do occur, the Contractor shall request clarification from Project Manager/Designer.

1.09 SHOP DRAWINGS

- A. Shop Drawings: When required by individual Specification Sections, the Contractor shall provide shop drawings which include physical characteristics, electrical characteristics, device layout plans, point-to-point wiring diagrams for all connections, and the like. Refer to individual Specification Sections for additional requirements for the shop drawings.

1.10 WARRANTY

- A. The Contractor shall provide an extended manufacturer's warranty on the Backbone and Horizontal Communications systems as specified in other sections of Division 27.

1.11 CLOSE OUT DOCUMENTS

- A. The Contractor shall provide final coordination drawings, with as-built information added, which are to be submitted as record drawings at completion of project.
- B. Record Drawings:
 - 1. Show changes and deviations from the Construction Drawings (including Addendums and change order documents).
 - 2. Show exact routes of pathway facilities and service entrance conduits.
 - 3. Show the exact location of racks, cabinets, mounting frames and the like.
- C. Operation and Maintenance Documentation: Provide copies of certificates of code authority acceptance, product data, guarantees, warranties, installation guides, maintenance guides and the like.
- D. Inspection and/or testing: Submit testing reports for testing that was performed.

PART 2 PRODUCTS

2.01 MANUFACTURERS

- A. Provide like items from one manufacturer, such as wire/cable, jacks, modular plugs, patch panels, equipment connection cords, wall plates, and the like. See individual sections for detailed information.

2.02 MATERIALS

- A. Provide new electrical materials of the type and quality detailed, listed by UL, bearing their label wherever standards have been established. Indicated brand names and catalog numbers are used to establish standards of performance and quality.
- B. Provide material and equipment that is acceptable to AHJ as suitable for the use indicated. For example, provide plenum rated cable in ceilings that are utilized as air return plenums.
- C. Include special features, finishes, accessories, and other requirements as described in the Contract Documents regardless of the item's listed catalog number.
- D. Provide incidentals not specifically mentioned herein or noted on Drawings, but needed to complete the system, in a safe and satisfactory working condition.

PART 3 - EXECUTION**3.01 EXAMINATION****A. Construction Documents:**

1. Drawings are diagrammatic with symbols representing communications equipment, outlets, accessories, and wiring.
2. Examine the entire set of Drawings to avoid conflicts with other systems. Determine the exact route and installation of communications wiring and equipment with conditions of construction.

3.02 INSTALLATION

- A. Install communications equipment completely as directed by manufacturer's installation instructions. Obtain installation instructions from manufacturer prior to rough-in of the communications equipment, and examine the instructions thoroughly. When requirements of the installation instructions conflict with the Contract Documents, request clarification from Project Manager/Designer prior to proceeding with the installation.
- B. Do not install communications equipment in obvious passages, doorways, scuttles, or crawl spaces, which would impede or block the passage's intended usage.
- C. Do not install communications equipment in locations where it would obviously be subject to damage during normal use.

3.03 FIELD QUALITY CONTROL

- A. Tests: Conduct tests of equipment and systems to demonstrate compliance with requirements specified in Division 27 & 28. Refer to individual Specification Sections for required tests. Testing documentation is to be included in Closeout Documents.

3.04 CLEANING

- A. Remove all dirt and debris caused by the execution of the work.
- B. Leave the entire communications system installed under this Contract in a clean, dust-free, and proper working order.
- C. Vacuum and clean interiors of new and modified electrical signal and communication equipment enclosures.

END OF SECTION

SECTION 27 21 00

DATA COMMUNICATIONS NETWORK EQUIPMENT

PART I - GENERAL

1.01 SUMMARY

- A. This section specifies equipment, accessories, materials, installation, configuration, and testing requirements for a complete and operable data network system. The system shall provide reliable and high-performance data communication throughout the site.

1.02 SCOPE

- A. The work will include but not be limited to the following objectives:
1. Provide, coordinate, and install all required equipment, licenses, and accessories as outlined in the design documents for a complete and operable system.
 2. Labor and Materials: The Contractor shall provide and pay for all labor, supervision, materials, accessories, components, equipment, tools, utilities, construction equipment and machinery, transportation, and other facilities and services necessary for the proper execution, operation, and completion of a turn-key system to the District.
 3. Data Communications Network Equipment: Includes, but is not limited to:
 - a. Routers
 - b. Firewalls
 - c. Networking Switches
 - d. Wireless Access Points
 - e. Licenses
 - f. Uninterruptible Power Supplies (UPS)
 4. Data Switches to be programmed by the District. The Contractor shall coordinate, deliver and pickup Data Switches from the District.

1.03 RELATED REQUIREMENTS

- A. Division 01 - General Requirements
- B. Section 27 00 00 - Communications
- C. Section 27 05 00 - Common Work Results for Communication Systems.
- D. Section 27 10 00 - Structured Cabling

1.04 QUALIFICATIONS

- A. Contractor shall be located within 50 miles or less from the project site to support 2-hour response time.
- B. Five years' experience installing data network equipment and systems.

1.05 SYSTEM REQUIREMENTS

- A. Any new installations or existing system modifications shall seamlessly integrate into the site's existing data network infrastructure.

1.06 CONTRACTOR "SHOP DRAWINGS" DESIGN REQUIREMENTS

- A. See section 27 00 00 for requirements.

1.07 SUBMITTALS

- A. See section 27 00 00 for requirements.

1.08 WARRANTY

- A. Refer to Division 01 Warranty section.
- B. See section 27 00 00 for additional requirements.

1.09 CLOSEOUT DOCUMENTS

- A. See section 27 00 00 for requirements.

PART 2 - PRODUCTS**2.01 GENERAL**

- A. See Appendix A at the end of this document for pre-approved materials.
- B. All products shall be new, unused and without blemishes and shall be of manufacturer's current and standard production.
- C. Drawings and Specifications indicate major system components, and may not show every component, connector, module, or accessory that may be required to support the operation specified. Contractor shall provide all components needed for complete and satisfactory installation/operation.

D. Product Availability

1. Contractor, prior to submitting a proposal, shall determine product availability and delivery time, and shall include such considerations into his proposed Contract Time.
2. Subject to compliance with these specifications, products and systems included in this section are to be installed as specified by the manufacturer of the system or engineer approved equal.

2.02 EQUIPMENT

- A. The District's preferred manufacturer for:
1. Routers - Cisco
 2. Firewalls - Cisco
 3. Networking Switches – Cisco
 4. Wireless Access Points - Cisco
 5. UPS – N1C
- B. Substitutions require proof of equivalence and approval by District and/or its representative.
- C. All equipment shall be provided with Licenses as required for seamless integration with the District's network infrastructure.

PART 3 - EXECUTION**3.01 ACCEPTABLE INSTALLERS**

- A. The equipment shall only be installed by Contractors who are qualified to install and maintain the system.
- B. The Contractor (or subcontractor listed at time of bid) must have at least five (5) years' experience installing data network equipment before the Bid Opening Date.

3.02 EXAMINATION

- A. The Contractor shall be required to visit the installation site(s) prior to bidding for the job. The Contractor acknowledges that the failure to visit the site(s) will not relieve the Contractor of the responsibility for observing and considering those conditions which a Contractor would have observed and considered during a site visit, estimating properly the difficulty and cost of successfully performing the Work or proceeding to perform the Work without additional cost to District.
- B. The Contractor shall report any discrepancies between the Specifications, Drawings, and Site Examination prior to the Bid Opening Date.

3.03 PREPARATION

- A. The Contractor shall verify materials are readily available prior to submitting product submittals and notify the Project Manager of long lead time items.
- B. The Contractor shall order all required parts and equipment only after receipt of approved product submittals from the Project Manager.
- C. The Contractor shall coordinate with the District's Technology Services department for needed IP addresses at least 4 weeks prior to configuration/installation.

3.04 SHOP DRAWINGS

- A. The Contractor shall create "Shop Drawings" per section 27 00 00.

3.05 WORKMANSHIP

- A. Quality workmanship is a high priority for the District and the Contractor shall be held to a high-level of professional workmanship.
- B. The District's Project or Construction Manager will have the authority to reject Work which does not conform to the Drawings and Specifications.

- C. Comply with the highest industry standards, except when specified requirements indicate more rigid standards or more precise workmanship.
- D. Perform Work with persons experienced and qualified to produce workmanship specified.
- E. Maintain quality control over suppliers and Subcontractors.

3.06 PATHWAY AND EQUIPMENT INSTALLATION

- A. Install all conduit and pathway per design documents. Refer to 27 05 00 for additional information/requirements.
- B. Install all Cat6A cable per design documents. Refer to 27 15 00 for additional information/requirements.
- C. Equipment to be installed per manufacturer's instructions.
- D. Devices requiring PoE power shall be connected to a PoE switch in the MDF/IDF data rack – verify with Technology Services for available PoE power.

3.07 EQUIPMENT COMMISSIONING/CONFIGURATION

- A. See 27 10 00, 3.10 COMMISSIONING PREPARATION
 - 1. 4 weeks prior to system turn up:
 - a. All jacks in patch panels are to be completely installed.
 - b. A worksheet is to be prepared by the Contractor indicating which switch port is assigned to what system (i.e. general data, intercom, AP, etc.) and the worksheet to be attached to the data switch.
 - c. Data switches are to be delivered to the District by the Contractor and coordinated with the District's Network Engineer.
- B. The Contractor shall pick up the equipment from the District.
- C. The Contractor shall install the equipment and patch in all connections.
- D. All equipment to be fully configured and tested for functionality by the Contractor prior to District acceptance testing.

3.08 FIELD QUALITY CONTROL AND TESTING

- A. Upon reaching substantial completion, perform a complete test and inspection of the system. If found to be installed and operating properly, notify the District of readiness to perform the formal Test & Inspection of the complete system by the District or its representative. Make all adjustments/changes required from District/representative review.

- B. Submit the Record Drawings (as-builts) to District for review prior to inspection.
- C. During the formal Test & Inspection (Commissioning) of the system and have personnel available with tools and equipment to inspect wiring, devices, and system operation.
- D. If corrections are needed, the Contractor will be provided with a Punch-List of all discrepancies. Perform the needed corrections in a timely fashion.
- E. Notify the District when ready to perform a re-inspection of the installation.

3.10 AS-BUILT DRAWINGS

- A. See section 27 00 00 for requirements.

APPENDIX A – Pre-Approved Materials

DESCRIPTION	MFG	PART NUMBER
Network Switch (48G/4SFP+) (New Install)	Cisco	OFCI
AP Mount (right angle)	Oberon	1006-COAP9136
UPS (IDF) (2000 VA)	N1C	N1C.L1500
UPS (MDF) 2000VA	N1C	N1C.LR2000 w/ N1C.L4850EBM2U
1U Rack Mount Monitor	Tripp Lite	B021-SWHD-K

END OF APPENDIX A

END OF SECTION

SECTION 27 51 23.50

EDUCATIONAL INTERCOM SYSTEMS

PART I - GENERAL**1.01 SUMMARY**

- A. This section specifies equipment, accessories, materials, wire, installation, configuration, and testing requirements for a complete and operable Intercom/Public Address/Bell system. This system shall provide the ability to bi-directionally communicate with an individual room, broadcast to defined speaker zone(s) and ring bell tones on a predefined schedule. For sites that utilize the small message board, this section will supplant the use of section 27 53 13 Clock Systems.

1.02 SCOPE

- A. The work will include but not be limited to the following objectives:
 - 1. Labor and Materials: The Contractor shall provide and pay for all labor, supervision, materials, accessories, components, equipment, tools, transportation, and other facilities and services necessary for the proper installation of a turn-key Assistive Listening system to the District.
 - 2. The contractor will coordinate with the District in writing for any needed information (i.e. IP addresses, etc.) 10 business days prior to the date the information is needed.
- B. The District has standardized on Rauland Telecenter U equipment and the installing Contractor shall be Rauland Telecenter authorized.
- C. For existing construction – provide and install all components and accessories to modify the existing system while maintaining code compliance and to seamlessly integrate the new components into the existing campus' system. Prior to beginning any work, the Contractor is responsible for identifying any existing system errors or faults and bring these issues to the attention of the District Project Manager.
- D. The Contractor shall be responsible for programming the Rauland Telecenter Intercom System.
- E. The Contractor shall coordinate with site staff for Bell schedule programming requirements.
- F. The Contractor shall review the proposed final system programming, functionality and expectations with the project manager, Architect/Engineer/Designer and District prior to final programming.

- G. After completion of the installation and pretest of the system a satisfactory final test of the entire system shall be made in the presence of the inspector of record (IOR) and District or the District's representative.
- H. The Contractor shall adjust any speaker levels to the appropriate level as determined in system testing.
- I. Existing systems shall remain operable until the new system is accepted and approved by the District or the District's representative.
- J. The Contractor is responsible for user/operator training (maximum 2 hours).
- K. The Contractor shall complete all required project closeout documentation in a timely fashion.

1.03 RELATED REQUIREMENTS

- A. Division 01 – General Requirements
- B. Section 27 00 00 - Communications
- C. Section 27 05 00 – Common Work Results for Communication Systems.
- E. Section 27 10 00 – Structured Cabling

1.04 REFERENCES

- A. See section 27 00 00 for requirements.

1.05 DEFINITIONS

- A. See section 27 00 00 for requirements.

1.06 SYSTEM REQUIREMENTS

- A. Any new installations or existing system modifications shall seamlessly integrate into the site's existing intercom system when applicable.

1.07 SUBMITTALS

- A. See section 27 00 00 for requirements.

1.08 CONTRACTOR "SHOP DRAWINGS" DESIGN REQUIREMENTS

- A. See section 27 00 00 for requirements.
- B. Shop drawings are required for this section.

1.09 QUALIFICATIONS

- B. The Contractor shall be located within 50 miles or less from the project site to support 2-hour response time.
- B. Five (5) years' experience installing Rauland Telecenter equipment.
- C. The contractor shall possess a California a C7 or C10 license.
- D. The Contractor or Subcontractor shall be Rauland Telecenter authorized to provide and install equipment with 5 years documented experience.

1.10 CERTIFICATIONS

- A. Installers shall be manufacturer certified..

1.11 WORKMANSHIP

- A. Quality workmanship is a high priority for the District and the Contractor shall be held to a high-level of professional workmanship.
- B. The District's Project or Construction Manager will have the authority to reject Work which does not conform to the Drawings and Specifications.
- C. Comply with highest industry standards, except when specified requirements indicate more rigid standards or more precise workmanship.
- D. Perform Work with persons experienced and qualified to produce workmanship specified.
- E. Maintain quality control over suppliers and Subcontractors.
- F. Contractor shall be responsible for scheduling Subcontractors in a timely fashion.

1.12 WARRANTY

- A. Refer to Division 01 Warranty section.
- B. See section 27 00 00 for additional requirements.

1.13 CLOSEOUT DOCUMENTS

- A. See section 27 00 00 for requirements.

PART 2 – PRODUCTS**2.01 GENERAL**

- A. The approved manufacturers for the project are:
 - 1. Control unit and related accessories: Rauland Telecenter U
 - 2. Speakers: See Appendix A for different installation types
 - 3. Wire, cable, and accessories: See Appendix A.
- B. All products shall be new, unused and without blemishes and shall be of manufacturer's current and standard production.
- C. Drawings and Specifications indicate major system components, and may not show every component, connector, module, or accessory that may be required to support the operation specified. The Contractor shall provide all components needed for complete and satisfactory installation and operation.
- D. Product Availability
 - 1. The Contractor, prior to submitting a proposal, shall determine product availability and delivery time, and shall include such considerations into his proposed Contract Time.
 - 2. Subject to compliance with these specifications, products and systems included in this section are to be installed as specified by the manufacturer of the system or engineer approved equal.

2.02 EQUIPMENT

- A. See Appendix A at the end of this document for pre-approved materials.
- B. Substitutions require proof of equivalence and prior approval by District and/or its representative before ordering.
- C. Main system components:
 - 1. Rauland Telecenter U IP Campus Controller and software
 - 2. Rauland Telecenter U Auxilliary Input/Output Module
 - 4. Rauland Telecenter U IP Classroom Module
 - 5. Rauland Telecenter U Administrative Console
 - 6. Rauland Telecenter U Program Line Input Module

PART 3 - EXECUTION**3.01 ACCEPTABLE INSTALLERS**

- A. The equipment shall only be installed by Contractors who are qualified and certified by the manufacturer to install and maintain the system.
- B. The Contractor (or subcontractor listed at time of bid) must have at least five (5) years' experience installing educational intercom equipment before the Bid Opening Date.

3.02 EXAMINATION

- A. The Contractor shall be required to visit the installation site(s) prior to bidding the job. The Contractor acknowledges that the failure to visit the site(s) will not relieve the Contractor of the responsibility for observing and considering those conditions which a Contractor would have observed and considered during a site visit, estimating properly the difficulty and cost of successfully performing the Work or proceeding to perform the Work without additional cost to District.
- B. The Contractor shall report any discrepancies between the Specifications, Drawings, and Site Examination prior to the Bid Opening Date.

3.03 PREPARATION

- A. The Contractor shall verify materials are readily available prior to submitting product submittals and notify the District's Project Manager of long lead time items.
- B. The Contractor shall order all required parts and equipment only after receipt of approved product submittals from the District's Project Manager.
- C. Submit and receive approval for shop drawings prior to work commencement.

3.04 PATHWAY INSTALLATION

- A. See Division 26 and Section 27 05 00 for requirements and more information.
- B. Existing Construction:
 - 1. Refer to design documents.
 - 2. Surface raceway and components shall be Wiremold 2300.

3.05 EQUIPMENT INSTALLATION

- A. Equipment to be wired and installed per manufacturer's instructions.

- B. The Contractor shall coordinate with the District's IT Department if connecting to their network. The Contractor shall provide a spreadsheet of all device MAC addresses indexed by device location to the District IT department to facilitate programming of reserved IP addresses for each device.
- C. Installation shall be in accordance with applicable codes (i.e. NEC, NFPA 72) local and state codes, as shown on the drawings, and as recommended by the major equipment manufacturer.
- D. Perform all Work as indicated in the Drawings and Specifications.
- E. All low voltage cables shall be kept away from power circuits.
- F. Contractor shall provide programming and configuration of the Educational Intercom system for full functionality.
- G. Contractor shall maintain a complete, up-to-date backup of the system configuration. Backup shall be maintained throughout the programming period until final Acceptance by District. Submit back-ups to District upon Final Acceptance.

3.06 LABELING/SCHEDULES

- A. All labels are to be machine generated black letters on white adhesive label stock that is appropriate for the installation environment (interior/exterior).
- B. Label all standard speaker cables with port ID.
- C. Label all speakers with speaker ID.
- D. Label all IP speakers with MDF/IDF, patch panel and jack numbers.

3.09 CONFIGURATION

- A. All equipment to be fully configured and tested for functionality prior to testing.

3.10 FIELD QUALITY CONTROL AND TESTING

- A. Upon reaching substantial completion, perform a complete test and inspection of the system. If found to be installed and operating properly, notify District of your readiness to perform the formal Test & Inspection of the complete system.
- B. Submit the Record Drawings (as-builts) to District for review prior to inspection.

- C. During the formal Test & Inspection (Commissioning) of the system the Contractor shall have personnel available with tools and equipment to inspect wiring, devices, and system operation.
- D. If corrections are needed, the Contractor will be provided with a Punch-List of all discrepancies. Perform the needed corrections in a timely fashion.
- E. Notify the District when ready to perform a re-inspection of the installation.
- F. District or its representative to provide final sign-off for acceptance.

3.11 AS-BUILT DRAWINGS

- A. See section 27 00 00 for requirements.
- B. As-built riser diagram showing all access control components for site.

3.12 TRAINING

- A. For new systems provide 8-hrs end-user training.
- B. For existing system upgrades provide 2-hrs end-user training.

APPENDIX A – Pre-Approved Materials

DESCRIPTION	MFG	PART NUMBER
IP Campus Controller and software/licenses	Rauland Telecenter U	TCC2000
Administrative Console	Rauland Telecenter U	TCC2045
Auxiliary Input/Output Module	Rauland Telecenter U	TCC2033
Universal Rack Mounting Kit	Rauland Telecenter U	TCC2099
Program Line Input Module	Rauland Telecenter U	TCC2055
Zone Page Amplifier	Rauland Telecenter U	TCC3022 w/ TCC3022PS
IP Classroom Module	Rauland Telecenter U	TCC2011B
8-Ohm 8" Speaker assembly surface (retrofit)	Rauland	- Speaker USO880 - Baffle ACC1003 - Backbox ACC1112 - Add: IP Classroom module
Clock/Speaker surface combo (standard classroom/office retrofit)	Rauland	- Baffle w/ Speaker ACC3011S - Backbox ACC3011SBB - Message Board TCC3011S Add: IP Classroom module
Large Message Board	Rauland American Time	- Message Board TCC3012L - Cover G2055OF-28
Exterior Speaker (retrofit)	Rauland Lowell Rauland FSR	Backbox: ACC1113 Baffle: ACC1012 Speaker: 8C10MRB Interior Backbox SMWB-4G-WHT - Add: IP Classroom Module (single speaker up to 2W) Add: Wire breakout 603101 (when IP module used)
Clock/Speaker surface combo (Lowell backbox retrofit)	Rauland Lowell	- Speaker USO880 - Message Board TCC3011S - Baffle C100-5526 - Add: IP Classroom module

END OF APPENDIX
END OF SECTION

SECTION 28 20 00

VIDEO SURVEILLANCE

PART I - GENERAL**1.01 SUMMARY**

- A. This section specifies software, equipment, accessories, wire, materials, installation, configuration, and testing requirements for a complete and operable Video Surveillance system. The system shall provide electronic recording/playback and monitoring of digital cameras installed at the site.

1.02 SCOPE

- A. The work will include but not be limited to the following objectives:
 - 1. Labor and Materials: The Contractor shall provide and pay for all labor, supervision, materials, accessories, wire, components, equipment, tools, transportation, and other facilities and services necessary for the proper installation of a turn-key Video Surveillance system to District.
- A. The CCTV system shall have the following minimum requirements.
 - 1. Cameras
 - a. Weather resistant IP67 or greater (exterior only)
 - b. Network/IP based
 - c. PoE powered
 - d. 5MP or 4K resolution
 - e. H.265 video compression
 - f. Day/night with IR illumination
 - g. Motion detection
 - h. ONVIF
 - 2. Network Video Recorder
 - a. Network/IP based
 - b. H.265 video compression
 - c. RAID 5 or greater
 - d. Record on motion detection
 - e. 30+ day recording
 - C. Software
 - a. PC and Mobile viewing
 - b. View live and recorded video
 - c. Search
 - d. Save video to MP4 format
 - e. Notifications

1.03 RELATED REQUIREMENTS

- A. Division 01 - General Requirements
- B. Section 27 00 00 - Communications
- C. Section 27 05 00 - Common Work Results for Communication Systems.
- C. Section 27 10 00 - Structured Cabling

1.04 QUALIFICATIONS

- A. Contractor shall be located within 50 miles or less from the project site to support 2-hour response time.
- B. Five years' experience installing Video Surveillance equipment systems.

1.05 SYSTEM REQUIREMENTS

- A. Any new installations or existing system modifications shall seamlessly integrate into the site's existing Video Surveillance system.

1.06 CONTRACTOR "SHOP DRAWINGS" DESIGN REQUIREMENTS

- A. See section 27 00 00 for requirements.
- B. Shop drawings are required for this section

1.07 SUBMITTALS

- A. See section 27 00 00 for requirements.

1.08 WARRANTY

- A. Refer to Division 01 Warranty section.
- B. See section 27 00 00 for additional requirements.

1.09 CLOSEOUT DOCUMENTS

- A. See section 27 00 00 for requirements.

PART 2 - PRODUCTS**2.01 GENERAL**

- A. See Appendix A at the end of this document for pre-approved materials.
- B. All products shall be new, unused and without blemishes and shall be of manufacturer's current and standard production.
- C. Drawings and Specifications indicate major system components, and may not show every component, connector, module, or accessory that may be required to support the operation specified. Contractor shall provide all components needed for complete and satisfactory installation/operation.
- D. Product Availability
 - 1. Contractor, prior to submitting a proposal, shall determine product availability and delivery time, and shall include such considerations into his proposed Contract Time.
 - 2. Subject to compliance with these specifications, products and systems included in this section are to be installed as specified by the manufacturer of the system or engineer approved equal.

2.02 EQUIPMENT

- A. The District's preferred manufacturer for CCTV equipment is i-Pro (formally Panasonic) for cameras and network video recorders (NVR).
- B. The District's preferred manufacturer for video intercom is Avigilon.
- C. Substitutions require proof of equivalence and approval by District and/or its representative.
- D. All exterior cameras to be IP67 rated or better.

PART 3 - EXECUTION**3.01 ACCEPTABLE INSTALLERS**

- A. The equipment shall only be installed by Contractors who are qualified to install and maintain the system.
- B. The Contractor (or subcontractor listed at time of bid) must have at least five (5) years' experience installing Video Surveillance equipment before the Bid Opening Date.

3.02 EXAMINATION

- A. The Contractor shall be required to visit the installation site(s) prior to job bidding. The Contractor acknowledges that the failure to visit the site(s) will not relieve the Contractor of the responsibility for observing and considering those conditions which a Contractor would have observed and considered during a site visit, estimating properly the difficulty and cost of successfully performing the Work or proceeding to perform the Work without additional cost to District.
- B. The Contractor shall report any discrepancies between the Specifications, Drawings, and Site Examination prior to the Bid Opening Date.

3.03 PREPARATION

- A. The Contractor shall verify materials are readily available prior to submitting product submittals and notify the Project Manager of long lead time items.
- B. The Contractor shall order all required parts and equipment only after receipt of approved product submittals from the Project Manager.
- C. The Contractor shall coordinate with the District's Technology Services department for needed IP addresses at least 2 weeks prior to configuration/installation.

3.04 SHOP DRAWINGS

- A. The Contractor shall create "Shop Drawings" per section 27 00 00.

3.05 WORKMANSHIP

- A. Quality workmanship is a high priority for the District and the Contractor shall be held to a high-level of professional workmanship.
- B. The District's Project or Construction Manager will have the authority to reject Work which does not conform to the Drawings and Specifications.

- C. Comply with highest industry standards, except when specified requirements indicate more rigid standards or more precise workmanship.
- D. Perform Work with persons experienced and qualified to produce workmanship specified.
- E. Maintain quality control over suppliers and Subcontractors.

3.06 PATHWAY AND EQUIPMENT INSTALLATION

- A. Install all conduit and pathway per design documents. Refer to 27 05 00 for additional information/requirements.
- B. Install all Cat6A cables per design documents. Refer to Section 27 10 00 for additional information/requirements.
- B. Equipment to be installed per manufacturer's instructions.
- C. Devices requiring PoE power shall be connected to a PoE switch in the MDF/IDF data rack – verify for adequate PoE power capacity.

3.07 CONFIGURATION

- A. Program cameras and/or NVR with network IP address using the following scheme.
Note: x=site octet, contact District Electronics shop for site information.
 - 1. Cameras: 10.x.253.101 = Camera 1, 10.x.253.102 = Camera 2...
 - 2. NVR: 10.x.253.5
 - 3. POE Switch: 10.x.253.10 = 1st switch, 10.x.253.11 = 2nd switch...
 - 4. Gateway: 10.x.0.1
 - 5. Subnet Mask: 255.255.0.0
- B. All equipment to be fully configured and tested for functionality prior to District acceptance testing.

3.08 CAMERA VIEW

- A. Adjust view aim, zoom and focus camera to show intended view from design documents.

3.09 FIELD QUALITY CONTROL AND TESTING

- A. Upon completion of network programming and initial view setting, notify District of your readiness to perform the formal camera view review with District or its representative. Make all adjustments required from District review.
- B. Submit the Record Drawings (as-builts) to District for review prior to inspection.

- C. During the formal Test & Inspection (Commissioning) of the system, Contractor to have personnel available with tools and equipment to inspect wiring, devices, and system operation.
- D. If corrections are needed, the Contractor will be provided with a Punch-List of all discrepancies. Perform the needed corrections in a timely fashion.
- E. Notify the District when ready to perform a re-inspection of the installation.

3.10 AS-BUILT DRAWINGS

- A. See section 27 00 00 for requirements.

APPENDIX A – Pre-Approved Materials**VIDEO SURVEILLANCE:**

DESCRIPTION	MFG.	PART NUMBER
Network Dome Camera, Outdoor, Vandal Resistant, 5MP	i-PRO	WV-S25500-V3L
Wall Mount Bracket for Dome Camera (Outdoor)	i-PRO	WV-QJB501-W
Ceiling Mount Bracket for Dome Camera (Outdoor)	i-PRO	WV-QJB504-W
Sunshade for Dome Camera (Outdoor)	i-PRO	WV-QSR505-W
Smoked Dome Cover for Dome Camera (Outdoor)	i-PRO	WV-CW7SN
Pole Mount Bracket for Cameras	i-PRO	WV-QPL500-W
Corner Mount Bracket for Cameras	i-PRO	WV-QCN500-W

END OF APPENDIX A
END OF SECTION