## Bid Category 04-26-01: Site Electrical

A. INCLUDES

Except for those items (if any) specifically noted to be excluded as defined below, the work of this bid category shall include all of the work and contract requirements according to Division 1 complete, including all bid requirements, Contract Documents; General and Supplemental Conditions, and General Requirements. Should any conflict exist between this written scope of work and the scope of work inferred by the Division 1 General Requirements or the technical specifications listed below, the work required by this bid category description shall govern. Work of this bid category specifically includes the work of the technical specification sections listed below, in their entirety, unless otherwise noted within this work category description:

**Specification Sections**

All Specifications

B. SPECIFICALLY INCLUDES

1. All work shown on drawings and included in specifications. Note this is the only bid category for this bid package, all associated work shall be included.

C. CLARIFICATIONS

1. Include all work listed as Installing Contractor Responsibilities in specification 26 5668 1.01. Note the section G labeled ALTERNATE Show Light and or Color Luminaires is base bid to this category and should be included.
2. Include 6% use tax for the Musco lighting package.
3. Note minimum 10' depth requirement for boring underneath football field and track. Confirm location of all bleacher footings prior to boring.
4. Schedule is based on electrical panel not being available prior to spring sports season starting. If materials are available for work to be completed prior to March 1 please advise construction manager. Alternate manufacturers may be considered for schedule purposes.
5. Include restoration of site at bore pits and any trenches, including cold patch asphalt in pathways. Include rolling back and reinstalling chain link fencing behind home side bleacher light poles to allow equipment access as necessary.

D. EXCLUDED

1. Purchase of the Musco lighting fixtures and items listed under Musco Responsibilities in 26 5668 1.01 B.

E. ALLOWANCES

1. Include a $25,000 allowance for temporary fencing and other work as directed by the construction manager.

F. REQUESTED ALTERNATES

1. Alternate 1 – Provide cost to trench in conduit and wiring as shown to light poles around perimeter of track in lieu of directional boring.

END OF SECTION