Quote

Date: October 3, 2025
Exp. Date: November 3, 2025

Project: Dexter High School – Al Ritt Stadium
Dexter, MI
Musco Project Number: 237119

Sourcewell
Master Project: 199030, **Contract Number:** 041123-MSL, **Expiration:** 06/16/2027
Category: Sports lighting with related supplies and services

All purchase orders should note the following:
Sourcewell Purchase – Contract Number: 041123-MSL

Quotation Price – Materials Only Delivered to Job Site

TLC for LED™ Sports Lighting w/ Control-Link® Control & Monitoring $328,374.00
ADDER #1: Show-Light® Special Effects ..... (+) $5,000.00
ADDER #2: TLC-RGBW & TLC-RGB-U Luminaires ..... (+) $20,000.00
- ***Requires Show-Light® Special Effects to Operate***

Sales tax, bonding, labor, installation, and unloading of the equipment are not included.
Quote is confidential. Pricing and lead times are effective for 30 days only.

Light-Structure System™ with Total Light Control – TLC for LED™ technology

Guaranteed Lighting Performance

- Guaranteed light levels and uniformities as noted below
  - **Football Field w/ Track (360'x160'):** 50FC, 2:1
- BallTracker® technology – targeted light, optimizing visibility of the ball in play with no glare in the players typical line-of-sight

System Description

- Factory aimed and assembled luminaries, including BallTracker® luminaires
- ***ADDER #2:*** Factory aimed and assembled TLC-RGBW and TLC-RGB-U luminaires
- Galvanized steel poles
- Pre-cast concrete bases with integrated lightning grounding
- Pole length factory assembled wire harnesses
- Factory wired and tested remote electrical component enclosures
- UL listed assemblies
- Corrosion protection

Control Systems and Services

- Control-Link® control and monitoring system to provide remote on/off and dimming (high/medium/low) control and performance monitoring with 24/7 customer support

ADDER #1: Show-Light® Entertainment System with Control-Link® Control and Monitoring

- Control-Link® control and monitoring system to provide remote on/off and dimming (high/medium/low/blackout) control and performance monitoring with 24/7 customer support
- Touchscreen(s) for onsite control of lighting effects
- Up to 30 lighting scenes
- 4 standard and 2 optional lighting effects
- 4 minutes of light show programming set to customer supplied and licensed music
- Scene programming must be requested within 90 days of commissioning, Effect and Show programming must be requested within 12 months of commissioning

Operation and Warranty Services

- Product assurance and warranty program that covers materials and onsite labor, eliminating 100% of your maintenance costs for 25 years
- Support from Musco's Lighting Services Team – over 170 Team members dedicated to operating and maintaining your lighting system – plus a network of 1800+ contractors
- Warranty starts the date of shipment

2016, 2025 Musco Sports Lighting, LLC • M-2168-enUS-17

Payment Terms

Final payment terms are subject to approval by Musco credit department. Final payment shall not be withheld by Buyer on account of delays beyond the control of Musco.

Email or fax a copy of the Purchase Order to Musco Sports Lighting, LLC:

Musco Sports Lighting, LLC
Attn: Musco Contracts
Fax: 800-734-6402
Email: musco.contracts@musco.com

All Purchase orders should note the following:
Sourcewell Purchase – Contract Number: 041123-MSL

Delivery Timing

8 - 12 weeks for delivery of materials to the job site from the time of order, submittal approval, and confirmation of order details including voltage, phase, and pole/luminaire locations.

Notes

Quote is based on following conditions:

- Shipment of entire project together to one location.
- 480 Volt, 3 phase electrical system requirement.
- Structural code and wind speed = 2021 IBC, 110 mi/h, Exposure C, Importance Factor 1.0.
- Due to the built-in custom light control per luminaire, pole or luminaire locations need to be confirmed prior to production. Changes to pole or luminaire locations after the product is sent to production could result in additional charges.
- Standard soil conditions – rock, bottomless, wet, or unsuitable soil may require additional engineering, special installation methods and additional cost.

Thank you for considering Musco for your lighting needs. Please contact me with any questions or if you need additional details.

Will McIntosh
Sales Representative
Musco Sports Lighting, LLC
Phone: (641) 670-0665
E-mail: will.mcintosh@musco.com

2016, 2025 Musco Sports Lighting, LLC • M-2168-enUS-17