



**Francis Howell R-III School District**  
**Request for Proposal**  
**Replacement of Interior and Exterior Doors and Frames**  
**Addendum II December 9, 2025 - Clarifications and Changes**  
**Pertaining to the RFP**  
**Responses due December 12, 2025, 11:00 a.m. CDT**

The following changes are being made to the Replacement of Interior and Exterior Doors and Frames RFP dated and issued November 12, 2025 by Francis Howell School District.

### **Section 3.0 - Scope of Work**

#### **Original scope:**

- **Francis Howell Middle (FHM)**

Door Openings to be Replaced:

- Doors 2, 19, and 20: Replace with glass doors (like for like).
- Doors 7 and 10: Replace with 3" x 33" view light doors.
- Doors 3, 4, 5, 6, 8, 9, 12, 13, 14, 15, 16, and 17: Replace with solid doors (no glass).

Scope:

- Remove existing interior and exterior hollow metal doors and frames.
- Install new Fiberglass Reinforced Plastic (FRP) doors and aluminum frames with all required new hardware.
- FRP finish, hardware, and sightlines to match the main entrance.
- Ensure proper door alignment, secure fastening, weather sealing, and smooth operation.

#### **Revised scope:**

- **Francis Howell Middle (FHM)**

Door Openings to be Replaced:

- Doors 2 and 20: Replace with glass doors (like for like).
- Doors 7, 10, and 19: Replace with 3" x 33" view light doors.
- Doors 3, 4, 5, 6, 8, 9, 12, 13, 14, 15, 16, and 17: Replace with solid doors (no glass).

Scope:

- Remove existing interior and exterior hollow metal doors and frames.
- Reuse existing steel frames on interior vestibule doors for entrances 4, 7, and 10.
- Install new Fiberglass Reinforced Plastic (FRP) doors and aluminum frames with all required new hardware.
- FRP finish, hardware, and sightlines to match the main entrance.
- Ensure proper door alignment, secure fastening, weather sealing, and smooth operation.

- Use 1" insulated glass on exterior and interior vestibule doors