



The School District of Haverford Township

Addendum #2

Questions & Answers

Erate 470 # 260007539

Total Port counts per area

Office\Cafeteria - 102 Red, 47 Blue, 44 Yellow, 32 Black

Gym\Auditorium - 15 Red, 6 Blue, 10 Yellow, 10 Black

Basement - 43 Red, 6 Yellow, 8 Blue, 5 Green

Bidder Q&A

1. **Is there a specification for manufacture of cabling and components?**
 - a. on page 17 of the RFP states "The District prefers utilizing solutions from Belden, Panduit, or Commscope or equivalent when possible"
2. **Facility lift available for gymnasium cabling. Also, will the District cover the gym floor? Please confirm on both?**
 - a. The facility lift is available. The Contractor will be responsible for any damages to the lift and floor while using the lift. Lauan flooring will be required to be on the gym floor to keep the lifts wheels from touching the gym floor.
3. **All demolition cabling to be removed from jack to patch panel. Please confirm.**
 - a. Correct, for each line installed, you will demo a line from the jack to the panel
4. **The RFP that is currently on the USAC Website (attached) is showing 32 Drops in the Basement. During the meeting, you had indicated that there is a revised drawing showing the correct number of Drops?**
 - a. The RFP [here](#) should match the one on USAC's site. as mentioned during the walkthrough, that was a last minute adjustment to remove the additional 32 drops from what was a computer lab. They can be excluded from all bids.
5. **During the walkthrough yesterday, it was discovered that there was an AP Missing in the Auditorium.**
 - a. Correct, 1 additional AP in the rear of the Auditorium
6. **Do you have floor plans like the attached photos that were hanging in the Maintenance Office?**

Robert Anderson, Director of Technology

The Oakmont School Central Administration & Early Childhood Education Center

50 East Eagle Road, Havertown, PA 19083

Phone: 610-853-5900 Ext.: 7215 | Email: randerson@haverfordsd.net



The School District of Haverford Township

- a. I'm not sure which drawings you're referring to, the drawings in the end of the RFP cover all of the parts of the building involved in the project. We can supply a larger set of drawings to the awarded vendor.
- 7. We are to supply 48P unloaded Patch Panels, correct?**
- a. Correct
- 8. Cable is CAT6A Plenum Rated, Blue, correct?**
- a. Yes CAT6A Plenum Rate, Blue in color.
- 9. We are supplying color coated jacks at the station end and the patch panel to match the intended use (Red – Work Station, Blue – Voice, Yellow – AP, Black – Security), correct?**
- a. Correct, color code is mentioned on the maps. Yellow for APs, Black for security, Blue for voice, Workstations are 2 red, 1 Blue, and remaining data jacks are red.
- 10. We are reusing the existing face plates, are they Standard Keystone Jack Compatible? What brand/model of Jack is currently being used in the faceplates?**
- a. Correct, Standard Keystone Jack Compatible. We have several different brand/model jacks we are currently using.
- 11. Work Hours are M-F 7 AM - 3 PM. Would we be able to work until 6 PM?**
- a. Yes we are very flexible with the work hours as long as Monday thru Friday.
- 12. We are to use Surface Mounted Boxes for Security and AP's, correct? Where you are calling out (2) Drops, can we use a 2P Surface Mounted box?**
- a. Correct, and yes, a 2P surface mount box is fine
- 13. Will you be sending a copy of the sign in sheet?**
- a. Yes

Deadline and Bid Opening	January 15, 2026 @ 10:30AM
Solicitor review & negotiation of language re solicitor	January 24, 2026
Submission of final contract signed by Vendor	January 28, 2026
Board Discussion	February 5, 2026
Board Approval	February 19, 2026
Installation can begin	July 1, 2026

Robert Anderson, Director of Technology

The Oakmont School Central Administration & Early Childhood Education Center

50 East Eagle Road, Havertown, PA 19083

Phone: 610-853-5900 Ext.: 7215 | Email: randerson@haverfordsd.net