



The Identification Specialists

Analysis Report
prepared for
Boggs Environmental Consultants, Inc

Report Date: 11/24/2025

Project Name: WCPS - Williamsport High School

Project #: MD25066

SanAir ID#: 25079339



NVLAP LAB CODE 200870-0

10501 Trade Court, North Chesterfield, Virginia 23236
888.895.1177 | 804.897.1177 | fax: 804.897.0070 | LabReports@SanAir.com | SanAir.com



SanAir ID Number

25079339

FINAL REPORT

11/24/2025 4:33:42 PM

Name: Boggs Environmental Consultants, Inc
Address: 200 West Main Street
Middletown, MD 21769
Phone: 301-694-5687

Project Number: MD25066
P.O. Number: MD25066
Project Name: WCPS - Williamsport High School
Collected Date: 11/21/2025
Received Date: 11/24/2025 10:00:00 AM

Dear Josh Faircloth,

We at SanAir would like to thank you for the work you recently submitted. The 5 sample(s) were received on Monday, November 24, 2025 via FedEx. The final report(s) is enclosed for the following sample(s): WHS-112125-1, WHS-112125-2, WHS-112125-3, WHS-112125-4, WHS-112125-5.

These results only pertain to this job and should not be used in the interpretation of any other job. This report is only complete in its entirety. Refer to the listing below of the pages included in a complete final report.

Sincerely,

A handwritten signature in black ink that reads "Sandra Sobrino".

Sandra Sobrino
Asbestos & Materials Laboratory Manager
SanAir Technologies Laboratory

Final Report Includes:

- Cover Letter
- Analysis Pages
- Disclaimers and Additional Information

Sample conditions:

- 5 samples in Good condition.



SanAir ID Number
25079339
FINAL REPORT
11/24/2025 4:33:42 PM

Name: Boggs Environmental Consultants, Inc
Address: 200 West Main Street
Middletown, MD 21769
Phone: 301-694-5687

Project Number: MD25066
P.O. Number: MD25066
Project Name: WCPS - Williamsport High School
Collected Date: 11/21/2025
Received Date: 11/24/2025 10:00:00 AM

Analyst: Hayes, Dillon

Asbestos Air TEM AHERA, 40 CFR Part 763 Subpart E

Sample	Volume (Liters)	Area Analyzed	Non Asb	Asbestos Type(s)	# Structures		Analytical Sensitivity (S/cc)	Reporting Limits	Asbestos Concentration	
					$\geq 0.5\mu$	$< 5 \geq 5\mu$		LCL - UCL (S/cc)	(S/mm ²)	(S/cc)
25079339-001 WHS-112125- 1 WA #2: Interior: Room #166 Center	1235	0.0650 mm ²	1	None Detected			0.0048		<15.00	<0.0048
25079339-002 WHS-112125- 2 WA #2: Interior: Room #158 Center	1235	0.0650 mm ²	0	None Detected			0.0048		<15.00	<0.0048
25079339-003 WHS-112125- 3 WA #2: Interior: Room #148 Center	1235	0.0650 mm ²	0	None Detected			0.0048		<15.00	<0.0048
25079339-004 WHS-112125- 4 WA #2: Interior: Room #145 Center	1235	0.0650 mm ²	0	None Detected			0.0048		<15.00	<0.0048
25079339-005 WHS-112125- 5 WA #2: Interior: Room #141 Center	1235	0.0650 mm ²	0	None Detected			0.0048		<15.00	<0.0048

Analyst: *Dillon Hayes*

Approved Signatory:

Sandra Sobiering

Analysis Date: 11/24/2025

Date: 11/24/2025



SanAir ID Number
25079339
FINAL REPORT
11/24/2025 4:33:42 PM

Name: Boggs Environmental Consultants, Inc
Address: 200 West Main Street
Middletown, MD 21769
Phone: 301-694-5687

Project Number: MD25066
P.O. Number: MD25066
Project Name: WCPS - Williamsport High School
Collected Date: 11/21/2025
Received Date: 11/24/2025 10:00:00 AM

Asbestos Air TEM AHERA, 40 CFR Part 763 Subpart E Worksheet


SanAir Sample ID: 25079339-001

Grid Box ID: 25-622

Grid Orientation

Client Sample ID: WHS-112125-1

G.O.A.: 0.013 mm sq.



Instrument ID: Hitachi TEM Scope #1

No. G.O. Analyzed: 5

Magnification: 20 K

Analyst: Hayes, Dillon

AV: 100Kv

Date: 11/24/2025

Grid ID	G.O. ID	Structure Number	ED Observation			Sketch	Length		Width	Structure Type	EDX Fiber Type	SAED Film ID	QC
			Non Asbestos	Chrysotile	Amphibole		≥ 0.5um < 5um	≥ 5um					
c10	i1	NSD									None		
c10	i3	1	N								Non-Asbestos	0	
c10	i5	NSD									None		
d6	c2	NSD									None		
d6	c4	NSD									None		
25079339-001		Total:	1	0	0	Count:	0	0					



Name: Boggs Environmental Consultants, Inc
Address: 200 West Main Street
Middletown, MD 21769
Phone: 301-694-5687

Project Number: MD25066
P.O. Number: MD25066
Project Name: WCPS - Williamsport High School
Collected Date: 11/21/2025
Received Date: 11/24/2025 10:00:00 AM

Asbestos Air TEM AHERA, 40 CFR Part 763 Subpart E Worksheet

SanAir Sample ID: 25079339-002
Client Sample ID: WHS-112125-2
Instrument ID: Hitachi TEM Scope #1
Magnification: 20 K
AV: 100Kv

Grid Box ID: 25-622
G.O.A.: 0.013 mm sq.
No. G.O. Analyzed: 5
Analyst: Hayes, Dillon
Date: 11/24/2025

Grid Orientation
F

Grid ID	G.O. ID	Structure Number	ED Observation			Sketch	Length		Width	Structure Type	EDX Fiber Type	SAED Film ID	QC
			Non Asbestos	Chrysotile	Amphibole		≥ 0.5um < 5um	≥ 5um					
d7	h3	NSD									None		
d7	h5	NSD									None		
d7	h7	NSD									None		
d8	i2	NSD									None		
d8	i4	NSD									None		
25079339-002		Total:	0	0	0	Count:	0	0					



SanAir ID Number
25079339
FINAL REPORT
11/24/2025 4:33:42 PM

Name: Boggs Environmental Consultants, Inc
Address: 200 West Main Street
Middletown, MD 21769
Phone: 301-694-5687

Project Number: MD25066
P.O. Number: MD25066
Project Name: WCPS - Williamsport High School
Collected Date: 11/21/2025
Received Date: 11/24/2025 10:00:00 AM

Asbestos Air TEM AHERA, 40 CFR Part 763 Subpart E Worksheet


SanAir Sample ID: 25079339-003

Grid Box ID: 25-622

Grid Orientation

Client Sample ID: WHS-112125-3

G.O.A.: 0.013 mm sq.



Instrument ID: Hitachi TEM Scope #1

No. G.O. Analyzed: 5

Magnification: 20 K

Analyst: Hayes, Dillon

AV: 100Kv

Date: 11/24/2025

Grid ID	G.O. ID	Structure Number	ED Observation			Sketch	Length		Width	Structure Type	EDX Fiber Type	SAED Film ID	QC
			Non Asbestos	Chrysotile	Amphibole		≥ 0.5um < 5um	≥ 5um					
d10	b6	NSD									None		
d10	b8	NSD									None		
d9	e5	NSD									None		
d9	e7	NSD									None		
d9	e9	NSD									None		
25079339-003		Total:	0	0	0	Count:	0	0					



SanAir ID Number
25079339
FINAL REPORT
11/24/2025 4:33:42 PM

Name: Boggs Environmental Consultants, Inc
Address: 200 West Main Street
Middletown, MD 21769
Phone: 301-694-5687

Project Number: MD25066
P.O. Number: MD25066
Project Name: WCPS - Williamsport High School
Collected Date: 11/21/2025
Received Date: 11/24/2025 10:00:00 AM

Asbestos Air TEM AHERA, 40 CFR Part 763 Subpart E Worksheet


SanAir Sample ID: 25079339-004

Grid Box ID: 25-622

Grid Orientation

Client Sample ID: WHS-112125-4

G.O.A.: 0.013 mm sq.



Instrument ID: Hitachi TEM Scope #1

No. G.O. Analyzed: 5

Magnification: 20 K

Analyst: Hayes, Dillon

AV: 100Kv

Date: 11/24/2025

Grid ID	G.O. ID	Structure Number	ED Observation			Sketch	Length		Width	Structure Type	EDX Fiber Type	SAED Film ID	QC
			Non Asbestos	Chrysotile	Amphibole		≥ 0.5um < 5um	≥ 5um					
e6	g2	NSD									None		
e6	g4	NSD									None		
e6	g6	NSD									None		
e7	j10	NSD									None		
e7	j8	NSD									None		
25079339-004		Total:	0	0	0	Count:	0	0					



Name: Boggs Environmental Consultants, Inc
Address: 200 West Main Street
Middletown, MD 21769
Phone: 301-694-5687

Project Number: MD25066
P.O. Number: MD25066
Project Name: WCPS - Williamsport High School
Collected Date: 11/21/2025
Received Date: 11/24/2025 10:00:00 AM

Asbestos Air TEM AHERA, 40 CFR Part 763 Subpart E Worksheet


SanAir Sample ID: 25079339-005

Grid Box ID: 25-622

Grid Orientation

Client Sample ID: WHS-112125-5

G.O.A.: 0.013 mm sq.



Instrument ID: Hitachi TEM Scope #1

No. G.O. Analyzed: 5

Magnification: 20 K

Analyst: Hayes, Dillon

AV: 100Kv

Date: 11/24/2025

Grid ID	G.O. ID	Structure Number	ED Observation			Sketch	Length		Width	Structure Type	EDX Fiber Type	SAED Film ID	QC
			Non Asbestos	Chrysotile	Amphibole		≥ 0.5um < 5um	≥ 5um					
e8	h10	NSD									None		
e8	h7	NSD									None		
e8	j6	NSD									None		
e9	f10	NSD									None		
e9	f8	NSD									None		
25079339-005		Total:	0	0	0	Count:	0	0					

Disclaimer

U.S. EPA's "Interim Transmission Electron Microscopy Analytical Methods – Mandatory and Nonmandatory-and Mandatory Section to Determine Completion of Response Actions" as found 40 CFR, Part 763, Subpart E, Appendix A.

This report is the sole property of the client named on the SanAir Technologies Laboratory chain-of-custody (COC). Results in the report are confidential information intended only for the use by the customer listed on the COC. Neither results nor reports will be discussed with or released to any third party without our client's written permission. The final report shall not be reproduced except in full without written approval of the laboratory to assure that parts of the report are not taken out of context. The information provided in this report applies only to the samples submitted and is relevant only for the date, time, and location of sampling. The accuracy of the results is dependent upon the client's sampling procedure and information provided to the laboratory by the client. SanAir assumes no responsibility for the sampling procedure and will provide evaluation reports based solely on the sample(s) in the condition in which they arrived at the laboratory and information provided by the client on the COC, such as: project number, project name, collection dates, po number, special instructions, samples collected by, sample numbers, sample identifications, sample type, selected analysis type, flow rate, total volume or area, and start stop times that may affect the validity of the results in this report. Samples were received in good condition unless otherwise noted. SanAir assumes no responsibility or liability for the manner in which the results are used or interpreted. This report does not constitute and shall not be used to claim product certification, approval, or endorsement by NVLAP, NIST, or any other U.S. governmental agencies and may not be certified by every local, state, and federal regulatory agencies. Clearance test for AHERA samples from abatement projects requires a minimum of five samples inside the work site, five samples outside the work site, and three blanks. Samples are held for a period of 60 days. 95% Confidence levels are reported using the upper and lower concentrations limits.

Laboratory Relative Standard Deviation: 0.3

Analyst RSD: D. Hayes 0.3, J. Tallert 0.3, S. Sobrino 0.3

1876 b Alternative Accuracy and Precision:

D. Hayes: 100%, J. Tallert: 100%, S. Sobrino: 100%

Asbestos Certifications:

National Voluntary Laboratory Accreditation Program (NVLAP) Lab Code 200870-0

City of Philadelphia Department of Public Health Air Management Services, Certification#ALL-460

Commonwealth of Pennsylvania Department of Environmental Protection Number 68-05397

California State Environmental Laboratory Accreditation Program Certificate Number 2915

Colorado Department of Public Health and Environment Registration Number AL-23143

Connecticut Department of Public Health Environmental Laboratory Registration Number PH-0105

Massachusetts Department of Labor Standards Asbestos Analytical Services Lic Number: AA000222

State of Maine Department of Environmental Protection License Number: LB-0075, LA-0084

New Jersey Department of Environmental Protection VA-014

New York State Department of Health Laboratory ID: 11983

State of Rhode Island Department of Health Certification No.: PCM00126, PLM00126, TEM00126

Texas Department of State Health Services License Number: 300440

Virginia Department of Professional and Occupational Regulation Number: 3333000323

State of Washington Department of Ecology Laboratory ID: C989

State of Hawaii Department of Health L-23-005

State of West Virginia Bureau for Public Health Analytical Laboratory Number: LT000616

Vermont Department of Health License Number: Asb-Co-An-000006

Louisiana Department of Environmental Quality AI Number 212253, Certificate #05088

Revision Date: 1/25/2024

TEM AHERA AIR SAMPLING LOG

Date: 11/21/2025

BEC Staff: Josh Faircloth & Derrick Klein

Project #: MD25066

Abatement Contractor: Retro Environmental

Flow Rate Calibration (Rotameter, Dwyer Precision, Other): Dry Cal

Calibration Test Performed (Technician/Date): Josh Faircloth 11/21/2025

SAMPLE INFORMATION

Project Location: Williamsport High School - Lower Level

5 S Clifton Drive, Williamsport, MD 21795

Project Manager: Richard Robinson & Derrick Klein

Abatement Contractor License #: M21-24-107

Sample Number	Sample Location	Sample Description	Flow Rate Liters Per Minute			Sampling Period			Total Volume (L)
			Pre	Post	Average	Begin	End	Total Minutes	
WHS-112125-1	WA #2: Interior: Room #166 Center	TEM INTERIOR	9.5	9.5	9.5	940	1150	130	1,235
WHS-112125-2	WA #2: Interior: Room #158 Center	TEM INTERIOR	9.5	9.5	9.5	941	1151	130	1,235
WHS-112125-3	WA #2: Interior: Room #148 Center	TEM INTERIOR	9.5	9.5	9.5	942	1152	130	1,235
WHS-112125-4	WA #2: Interior: Room #145 Center	TEM INTERIOR	9.5	9.5	9.5	943	1153	130	1,235
WHS-112125-5	WA #2: Interior: Room #141 Center	TEM INTERIOR	9.5	9.5	9.5	944	1154	130	1,235
WHS-112125-6	WA #2: Exterior: Room #157 South	TEM EXTERIOR	9.5	9.5	9.5	955	1205	130	1,235
WHS-112125-7	WA #2: Exterior: Room #158 West	TEM EXTERIOR	9.5	9.5	9.5	956	1206	130	1,235
WHS-112125-8	WA #2: Exterior: Room #172 West	TEM EXTERIOR	9.5	9.5	9.5	957	1207	130	1,235
WHS-112125-9	WA #2: Exterior: Room #169 West	TEM EXTERIOR	9.5	9.5	9.5	958	1208	130	1,235
WHS-112125-10	WA #2: Exterior: Room #197 West	TEM EXTERIOR	9.5	9.5	9.5	959	1209	130	1,235
WHS-112125-11	Field Blank Interior	QA/QC	x	x	x	x	x	x	x
WHS-112125-12	Field Blank Exterior	QA/QC	x	x	x	x	x	x	x
WHS-112125-13	Box Lot Media Blank	QA/QC	x	x	x	x	x	x	x

COMMENTS: TEM AHERA FINAL AIR CLEARANCE COLLECTED UTILIZING "AGGRESSIVE" SAMPLING TECHNIQUES WITH LEAF BLOWERS & BOX FANS

BEC Staff Signature

Date: 11/21/25



The Identification Specialists

Analysis Report
prepared for
Boggs Environmental Consultants, Inc

Report Date: 11/14/2025

Project Name: WCPS - Williamsport High School

Project #: MD25066

SanAir ID#: 25077193



NVLAP LAB CODE 200870-0

10501 Trade Court, North Chesterfield, Virginia 23236
888.895.1177 | 804.897.1177 | fax: 804.897.0070 | LabReports@SanAir.com | SanAir.com



SanAir ID Number

25077193

FINAL REPORT

11/14/2025 3:52:30 PM

Name: Boggs Environmental Consultants, Inc
Address: 200 West Main Street
Middletown, MD 21769
Phone: 301-694-5687

Project Number: MD25066
P.O. Number: MD25066
Project Name: WCPS - Williamsport High School
Collected Date: 11/13/2025
Received Date: 11/14/2025 11:30:00 AM

Dear Josh Faircloth,

We at SanAir would like to thank you for the work you recently submitted. The 5 sample(s) were received on Friday, November 14, 2025 via FedEx. The final report(s) is enclosed for the following sample(s): WHS-111325-1, WHS-111325-2, WHS-111325-3, WHS-111325-4, WHS-111325-5.

These results only pertain to this job and should not be used in the interpretation of any other job. This report is only complete in its entirety. Refer to the listing below of the pages included in a complete final report.

Sincerely,

A handwritten signature in black ink that reads "Sandra Sobrino".

Sandra Sobrino
Asbestos & Materials Laboratory Manager
SanAir Technologies Laboratory

Final Report Includes:

- Cover Letter
- Analysis Pages
- Disclaimers and Additional Information

Sample conditions:

- 5 samples in Good condition.



SanAir ID Number
25077193
FINAL REPORT
11/14/2025 3:52:30 PM

Name: Boggs Environmental Consultants, Inc
Address: 200 West Main Street
Middletown, MD 21769
Phone: 301-694-5687

Project Number: MD25066
P.O. Number: MD25066
Project Name: WCPS - Williamsport High School
Collected Date: 11/13/2025
Received Date: 11/14/2025 11:30:00 AM

Analyst: Hayes, Dillon

Asbestos Air TEM AHERA, 40 CFR Part 763 Subpart E

Sample	Volume (Liters)	Area Analyzed	Non Asb	Asbestos Type(s)	# Structures ≥ 0.5μ < 5 ≥ 5μ	Analytical Sensitivity (S/cc)	Reporting	Asbestos Concentration (S/mm ²) (S/cc)
							Limits LCL - UCL (S/cc)	
25077193-001 WHS-111325-1 WA #2B: Interior: Room #145 Center	1235	0.0650 mm ²	0	None Detected		0.0048		<15.00 <0.0048
25077193-002 WHS-111325-2 WA #2B: Interior: Room #139 Center	1235	0.0650 mm ²	0	None Detected		0.0048		<15.00 <0.0048
25077193-003 WHS-111325-3 WA #2B: Interior: Room #144 Center	1235	0.0650 mm ²	0	None Detected		0.0048		<15.00 <0.0048
25077193-004 WHS-111325-4 WA #2B: Interior: Room #143 Center	1235	0.0650 mm ²	0	None Detected		0.0048		<15.00 <0.0048
25077193-005 WHS-111325-5 WA #2B: Interior: Room #141 Center	1235	0.0650 mm ²	0	None Detected		0.0048		<15.00 <0.0048

Analyst: *Dillon Hayes*

Approved Signatory: *Sandra Sobiering*

Analysis Date: 11/14/2025

Date: 11/14/2025



SanAir ID Number
25077193
FINAL REPORT
11/14/2025 3:52:30 PM

Name: Boggs Environmental Consultants, Inc
Address: 200 West Main Street
Middletown, MD 21769
Phone: 301-694-5687

Project Number: MD25066
P.O. Number: MD25066
Project Name: WCPS - Williamsport High School
Collected Date: 11/13/2025
Received Date: 11/14/2025 11:30:00 AM

Asbestos Air TEM AHERA, 40 CFR Part 763 Subpart E Worksheet


SanAir Sample ID: 25077193-001

Grid Box ID: 25-612

Grid Orientation

Client Sample ID: WHS-111325-1

G.O.A.: 0.013 mm sq.



Instrument ID: Hitachi TEM Scope #1

No. G.O. Analyzed: 5

Magnification: 20 K

Analyst: Hayes, Dillon

AV: 100Kv

Date: 11/14/2025

Grid ID	G.O. ID	Structure Number	ED Observation			Sketch	Length		Width	Structure Type	EDX Fiber Type	SAED Film ID	QC
			Non Asbestos	Chrysotile	Amphibole		≥ 0.5um < 5um	≥ 5um					
d1	c4	NSD									None		
d1	c6	NSD									None		
d1	e2	NSD									None		
d2	g7	NSD									None		
d2	g9	NSD									None		
25077193-001		Total:	0	0	0	Count:	0	0					



Name: Boggs Environmental Consultants, Inc
Address: 200 West Main Street
Middletown, MD 21769
Phone: 301-694-5687

Project Number: MD25066
P.O. Number: MD25066
Project Name: WCPS - Williamsport High School
Collected Date: 11/13/2025
Received Date: 11/14/2025 11:30:00 AM

Asbestos Air TEM AHERA, 40 CFR Part 763 Subpart E Worksheet

SanAir Sample ID: 25077193-002
Client Sample ID: WHS-111325-2
Instrument ID: Hitachi TEM Scope #1
Magnification: 20 K
AV: 100Kv

Grid Box ID: 25-612
G.O.A.: 0.013 mm sq.
No. G.O. Analyzed: 5
Analyst: Hayes, Dillon
Date: 11/14/2025

Grid Orientation
F

Grid ID	G.O. ID	Structure Number	ED Observation			Sketch	Length		Width	Structure Type	EDX Fiber Type	SAED Film ID	QC
			Non Asbestos	Chrysotile	Amphibole		≥ 0.5um < 5um	≥ 5um					
d3	f1	NSD									None		
d3	f3	NSD									None		
d3	f5	NSD									None		
d4	g5	NSD									None		
d4	g7	NSD									None		
25077193-002		Total:	0	0	0	Count:	0	0					



SanAir ID Number
25077193
FINAL REPORT
11/14/2025 3:52:30 PM

Name: Boggs Environmental Consultants, Inc
Address: 200 West Main Street
Middletown, MD 21769
Phone: 301-694-5687

Project Number: MD25066
P.O. Number: MD25066
Project Name: WCPS - Williamsport High School
Collected Date: 11/13/2025
Received Date: 11/14/2025 11:30:00 AM

Asbestos Air TEM AHERA, 40 CFR Part 763 Subpart E Worksheet


SanAir Sample ID: 25077193-003

Grid Box ID: 25-612

Grid Orientation

Client Sample ID: WHS-111325-3

G.O.A.: 0.013 mm sq.



Instrument ID: Hitachi TEM Scope #1

No. G.O. Analyzed: 5

Magnification: 20 K

Analyst: Hayes, Dillon

AV: 100Kv

Date: 11/14/2025

Grid ID	G.O. ID	Structure Number	ED Observation			Sketch	Length		Width	Structure Type	EDX Fiber Type	SAED Film ID	QC
			Non Asbestos	Chrysotile	Amphibole		≥ 0.5um < 5um	≥ 5um					
d5	b1	NSD									None		
d5	b3	NSD									None		
d5	b5	NSD									None		
e1	a2	NSD									None		
e1	a4	NSD									None		
25077193-003		Total:	0	0	0	Count:	0	0					



Name: Boggs Environmental Consultants, Inc
Address: 200 West Main Street
Middletown, MD 21769
Phone: 301-694-5687

Project Number: MD25066
P.O. Number: MD25066
Project Name: WCPS - Williamsport High School
Collected Date: 11/13/2025
Received Date: 11/14/2025 11:30:00 AM

Asbestos Air TEM AHERA, 40 CFR Part 763 Subpart E Worksheet

SanAir Sample ID: 25077193-004
Client Sample ID: WHS-111325-4
Instrument ID: Hitachi TEM Scope #1
Magnification: 20 K
AV: 100Kv

Grid Box ID: 25-612
G.O.A.: 0.013 mm sq.
No. G.O. Analyzed: 5
Analyst: Hayes, Dillon
Date: 11/14/2025

Grid Orientation
F

Grid ID	G.O. ID	Structure Number	ED Observation			Sketch	Length		Width	Structure Type	EDX Fiber Type	SAED Film ID	QC
			Non Asbestos	Chrysotile	Amphibole		≥ 0.5um < 5um	≥ 5um					
e2	i1	NSD									None		
e2	i3	NSD									None		
e2	j5	NSD									None		
e3	i6	NSD									None		
e3	i8	NSD									None		
25077193-004		Total:	0	0	0	Count:	0	0					



Name: Boggs Environmental Consultants, Inc
Address: 200 West Main Street
Middletown, MD 21769
Phone: 301-694-5687

Project Number: MD25066
P.O. Number: MD25066
Project Name: WCPS - Williamsport High School
Collected Date: 11/13/2025
Received Date: 11/14/2025 11:30:00 AM

Asbestos Air TEM AHERA, 40 CFR Part 763 Subpart E Worksheet


SanAir Sample ID: 25077193-005

Grid Box ID: 25-612

Grid Orientation

Client Sample ID: WHS-111325-5

G.O.A.: 0.013 mm sq.



Instrument ID: Hitachi TEM Scope #1

No. G.O. Analyzed: 5

Magnification: 20 K

Analyst: Hayes, Dillon

AV: 100Kv

Date: 11/14/2025

Grid ID	G.O. ID	Structure Number	ED Observation			Sketch	Length		Width	Structure Type	EDX Fiber Type	SAED Film ID	QC
			Non Asbestos	Chrysotile	Amphibole		≥ 0.5um < 5um	≥ 5um					
e4	a2	NSD									None		
e4	a4	NSD									None		
e4	a6	NSD									None		
e5	g4	NSD									None		
e5	g6	NSD									None		
25077193-005		Total:	0	0	0	Count:	0	0					

Disclaimer

U.S. EPA's "Interim Transmission Electron Microscopy Analytical Methods – Mandatory and Nonmandatory-and Mandatory Section to Determine Completion of Response Actions" as found 40 CFR, Part 763, Subpart E, Appendix A.

This report is the sole property of the client named on the SanAir Technologies Laboratory chain-of-custody (COC). Results in the report are confidential information intended only for the use by the customer listed on the COC. Neither results nor reports will be discussed with or released to any third party without our client's written permission. The final report shall not be reproduced except in full without written approval of the laboratory to assure that parts of the report are not taken out of context. The information provided in this report applies only to the samples submitted and is relevant only for the date, time, and location of sampling. The accuracy of the results is dependent upon the client's sampling procedure and information provided to the laboratory by the client. SanAir assumes no responsibility for the sampling procedure and will provide evaluation reports based solely on the sample(s) in the condition in which they arrived at the laboratory and information provided by the client on the COC, such as: project number, project name, collection dates, po number, special instructions, samples collected by, sample numbers, sample identifications, sample type, selected analysis type, flow rate, total volume or area, and start stop times that may affect the validity of the results in this report. Samples were received in good condition unless otherwise noted. SanAir assumes no responsibility or liability for the manner in which the results are used or interpreted. This report does not constitute and shall not be used to claim product certification, approval, or endorsement by NVLAP, NIST, or any other U.S. governmental agencies and may not be certified by every local, state, and federal regulatory agencies. Clearance test for AHERA samples from abatement projects requires a minimum of five samples inside the work site, five samples outside the work site, and three blanks. Samples are held for a period of 60 days. 95% Confidence levels are reported using the upper and lower concentrations limits.

Laboratory Relative Standard Deviation: 0.3

Analyst RSD: D. Hayes 0.3, J. Tallert 0.3, S. Sobrino 0.3

1876 b Alternative Accuracy and Precision:

D. Hayes: 100%, J. Tallert: 100%, S. Sobrino: 100%

Asbestos Certifications:

National Voluntary Laboratory Accreditation Program (NVLAP) Lab Code 200870-0

City of Philadelphia Department of Public Health Air Management Services, Certification#ALL-460

Commonwealth of Pennsylvania Department of Environmental Protection Number 68-05397

California State Environmental Laboratory Accreditation Program Certificate Number 2915

Colorado Department of Public Health and Environment Registration Number AL-23143

Connecticut Department of Public Health Environmental Laboratory Registration Number PH-0105

Massachusetts Department of Labor Standards Asbestos Analytical Services Lic Number: AA000222

State of Maine Department of Environmental Protection License Number: LB-0075, LA-0084

New Jersey Department of Environmental Protection VA-014

New York State Department of Health Laboratory ID: 11983

State of Rhode Island Department of Health Certification No.: PCM00126, PLM00126, TEM00126

Texas Department of State Health Services License Number: 300440

Virginia Department of Professional and Occupational Regulation Number: 3333000323

State of Washington Department of Ecology Laboratory ID: C989

State of Hawaii Department of Health L-23-005

State of West Virginia Bureau for Public Health Analytical Laboratory Number: LT000616

Vermont Department of Health License Number: Asb-Co-An-000006

Louisiana Department of Environmental Quality AI Number 212253, Certificate #05088

Revision Date: 1/25/2024



1551 Oakbridge Drive Suite B
Powhatan, VA 23139
804-897-1177 / 888-895-1177
Fax 804-897-0070
www.sanair.com

Asbestos Chain of Custody

SanAir ID Number

25077193

Company: Boggs Environmental Consultants		Project #: MD25066	Collected by: Josh Faircloth
Address: 200 West Main Street		Project Name: WCPS - Williamsport High School	Phone #: 509-205-8863
City, St., Zip: Middletown, MD 21769		Date Collected: 11/13/2025	Fax #: 301-694-9799
State of Collection: MD	Account#: 2845	P.O. Number: MD25066	Email: staff@boggsenvironmental.com

Bulk			Air			Soil/Vermiculite		
ABB	PLM EPA 600/R-93/116	☐	ABA	PCM NIOSH 7400	☐	ABSE	PLM EPA 600/R-93/116 (Qual.)	☐
	Positive Stop ☐		ABA-2	OSHA w/ TWA*	☐	ABSP	PLM CARB 435 (LOD <1%)	☐
ABEPA	PLM EPA 400 Point Count	☐	ABTEM	TEM AHERA	☒	ABSP1	PLM CARB 435 (LOD 0.25%)	☐
ABB1K	PLM EPA 1000 Point Count	☐	ABATN	TEM NIOSH 7402	☐	ABSP2	PLM CARB 435 (LOD 0.1%)	☐
ABBEN	PLM EPA NOB	☐	ABT2	TEM Level II	☐			
ABBCH	TEM Chatfield	☐						
ABBTM	TEM EPA NOB	☐						

Water			New York ELAP			Dust		
ABHE	EPA 100.2	☐	PLM NY	PLM EPA 600/M4-82-020	☐	ABWA	TEM Wipe ASTM D-6480	☐
			ABEPA2	NY ELAP 198.1	☐	ABDMV	TEM Microvac ASTM D-5755	☐
			ABENY	NY ELAP 198.6 PLM NOB	☐			
			ABBNY	NY ELAP 198.4 TEM NOB	☐	Matrix	Other	☐

Turn Around Times	3 HR (4 HR TEM) ☐	6 HR (8HR TEM) ☒	12 HR ☐	24 HR ☐
	2 Days ☐	3 Days ☐	4 Days ☐	5 Days ☐

Special Instructions

Sample #	Sample Identification/Location	Volume or Area	Sample Type	Flow Rate*	Time* Start - Stop
	Please See Attached BEC Logsheet				
	Please Analyze Interior Samples Only				

Relinquished by: <i>[Signature]</i>	Date: 11/13/25	Time: 1645	Received by: <i>[Signature]</i>	Date: 11/14/25	Time: 11:30 AM
-------------------------------------	-----------------------	-------------------	---------------------------------	-----------------------	-----------------------

Unless scheduled, the turn around time for all samples received after 3 pm EST Friday will begin at 8 am Monday morning. Weekend or Holiday work must be scheduled ahead of time and is charged for rush turn around time. Work with standard turn around time sent Priority Overnight and Billed to Recipient will be charged a \$10 shipping fee.

25077193

TEM AHRA AIR SAMPLING LOG

 Date: 11/13/2025

 BEC Staff: Josh Faircloth & Derrick Klein

 Project #: MD25066

 Abatement Contractor Retro Environmental

 Flow Rate Calibration (Rotameter, Dwyer Precision, Other): Dry Cal

 Calibration Test Performed (Technician/Date): Josh Faircloth 11/13/2025

SAMPLE INFORMATION

Sample Number	Sample Location	Sample Description	Flow Rate Liters Per Minute			Sampling Period			Total Volume (L)
			Pre	Post	Average	Begin	End	Total Minutes	
WHS-111325-1	WA #2B: Interior: Room #145 Center	TEM INTERIOR	9.5	9.5	9.5	1130	1340	130	1,235
WHS-111325-2	WA #2B: Interior: Room #139 Center	TEM INTERIOR	9.5	9.5	9.5	1131	1341	130	1,235
WHS-111325-3	WA #2B: Interior: Room #144 Center	TEM INTERIOR	9.5	9.5	9.5	1132	1342	130	1,235
WHS-111325-4	WA #2B: Interior: Room #143 Center	TEM INTERIOR	9.5	9.5	9.5	1133	1343	130	1,235
WHS-111325-5	WA #2B: Interior: Room #141 Center	TEM INTERIOR	9.5	9.5	9.5	1134	1344	130	1,235
WHS-111325-6	WA #2B: Exterior: Room #145 Northeast	TEM EXTERIOR	9.5	9.5	9.5	1142	1352	130	1,235
WHS-111325-7	WA #2B: Exterior: Room #145 Northwest	TEM EXTERIOR	9.5	9.5	9.5	1143	1353	130	1,235
WHS-111325-8	WA #2B: Exterior: Room #143 Northeast	TEM EXTERIOR	9.5	9.5	9.5	1144	1354	130	1,235
WHS-111325-9	WA #2B: Exterior: Room #141 Northwest	TEM EXTERIOR	9.5	9.5	9.5	1145	1355	130	1,235
WHS-111325-10	WA #2B: Exterior: Room 141 Northeast	TEM EXTERIOR	9.5	9.5	9.5	1146	1356	130	1,235
WHS-111325-11	Field Blank Interior	QA/QC	X	X	X	X	X	X	X
WHS-111325-12	Field Blank Exterior	QA/QC	X	X	X	X	X	X	X
WHS-111325-13	Box Lot Media Blank	QA/QC	X	X	X	X	X	X	X

COMMENTS: TEM AHRA FINAL AIR CLEARANCE COLLECTED UTILIZING "AGGRESSIVE" SAMPLING TECHNIQUES WITH A LEAF BLOWERS & BOX FANS

BEC Staff Signature

Date

ENVIRONMENTAL SCIENCE, ENGINEERING & INDUSTRIAL HYGIENE SERVICES

11:30AM