ADDENDUM NO. 1

Date:	March 22, 2024
Issued By:	Jordan & Bain Landscape Architects, Inc. 459 North Ventura Avenue; Ventura, CA 93001 (805) 642-3641 Phone; (805) 653-7874 Fax
Project:	Portola Elementary School Fencing Project
Issued To:	Ventura Unified School District For Distribution to all bidders of record

---

Notice: Acknowledge receipt of this addendum by enclosing one signed copy with your bid documents. Failure to do so may subject bidder to disqualification. This addendum consists of one (1) page and the following enclosures. This addendum forms a part of the bid documents. It modifies them as follows:

A. Modification to swinging gate fence panels
   1. Sheet L4.3 – Construction Details – Detail #4 – Gate No. 3 (Outside View) – Add a second decorative rail on both swing gates, 2" x 2" x 14 ga size, to match fence panels designed used on this project.

   2. Sheet L4.4 – Construction Details – Detail #6 – Gate No. 11 – Add a second decorative rail on both swing gates, 2" x 2" x 14 ga size, to match fence panels designed used on this project.

   3. Sheet L4.5 – Construction Details – Detail #1 – Gate No. 12 – Add a second decorative rail on both swing gates, 2" x 2" x 14 ga size, to match fence panels designed used on this project.

B. VUSD Mandatory Work Schedule

   1. VUSD shall be teaching summer school programs at Portola Elementary School starting from July 1st and ending July 26th. The students and teachers will be on campus from 8am until 12:30pm, Monday through Friday. The students and teachers will be confined to entering the exiting the campus through the main entrance only during the construction, which is identified on the plan as Gate No. 9. The work shall begin on campus two weeks prior to the children and staff arriving on campus. VUSD has requested that the concrete and fence demo work with replacement concrete and new fence posts be installed at the main entrance (Gate 9) prior to the start of summer school. Temporary gate access will need to be established for easy entrance and exit into the campus at this location. Also, the tree removal with related sidewalk replacement must also be completed within this same two weeks prior to the start of summer school beginning.

End of Addendum No. 1