



Hendry County School District

ADDENDUM 1

IMPORTANT DOCUMENT –

Central Elementary & Country Oaks Elementary Re-cabling Project for Hendry County School

ADDENDUM DATE: JANUARY 27, 2026

INFORMATION TECHNOLOGY RELATED DOCUMENTS- Revision of Scope and Q&A

Purpose of Addendum

This addendum updates the original fiber optic cabling scope to reflect a change in material requirements. During project review, it was determined that the originally specified armored fiber optic cable will be replaced with outdoor-rated fiber optic cable or equivalent, based on site conditions and installation needs.

Scope Revision

1. Cable Type Adjustment

The project will now utilize outdoor-rated fiber optic cable (or equivalent) in place of armored fiber. Cable must meet or exceed the performance specifications of the originally proposed armored fiber at 10Gbs. Cable must be suitable for exterior pathways, environmental exposure, and conduit-based installation.

2. Installation Requirements

Outdoor-rated fiber must be installed in accordance with district standards and industry best practices. Pathways, conduit, and pull boxes remain unchanged unless otherwise noted. Vendor must ensure proper protection, strain relief, and termination consistent with the new cable type.

1. Can you please provide the reference form that is required as per Responsive Requirements? Or, will you accept a form of our own making?

a. We will accept a reference form of your own making.

2. Are these to be bid as (1) Job with Pricing Breakdown per School? Or (2) Separate Jobs by Each school?

a. 1 Job and pricing breakdown per school

3. Is there a bid bond required?

a. No

4. Is OS2 Armored Fiber 100% required? Asking because for example at Country Oaks ES there are (8) portables in a row that need conduit back to the MDF - (8) 12-Strand Armored Fibers will never be able to pull in a conduit - We would have to have multiple conduits to make this happen, increasing the price significantly. I would suggest maybe that the portable be a regular 12-Strand Indoor / Outdoor non-armored

a. Thank you for bringing this to our attention, an addendum will be issued for meeting these requirements.

5. In both Schools they are asking for a 2-Post Rack, with Vertical and Horizontal Wire Management, is the Vertical 4" or 6" and are the Horizontal 1U or 2U

a. Vertical is 6" and Horizontal will be 2U

6. I haven't looked at the schools yet, but if they are block walls inside the classrooms – I am assuming Wire Mold will need to be used, is this correct?

a. This is correct. Wire mold will need to be used for block/brick walls inside classrooms.

7. Do you have a preference for the make and model of the network racks?

a. We do not have a preference for the make and model of the network racks.

PLEASE ACKNOWLEDGE RECEIPT OF THIS ADDENDUM AND RETURN IT WITH YOUR SUBMITTAL. FAILURE TO SIGN AND RETURN WITH YOUR SUBMITTAL COULD RESULT IN REJECTION OF YOUR PROPOSAL.

SIGNATURE

PRINT OR TYPE NAME

COMPANY NAME

EMAIL ADDRESS