



5 May 2025

Dylan Laflam
Facilities Director
Lamoille North Supervisory Union
736 VT RTE 15 West
Hyde Park, VT 05655

Re: Radon Measurement – Lamoille North Supervisory Union Schools, Vermont
K-D Project No. 00073-003

Dear Mr. Laflam:

At your request, K-D Associates, Inc. conducted radon testing in the Lamoille North School District facilities including Eden Elementary School, Waterville Elementary School, Cambridge Elementary School, Johnson Elementary School, Lamoille Union Middle and High School, Green Mountain Technical and Career Center, and Hyde Park Elementary. The testing was conducted in accordance with the ANSI/AARST Protocol for Conducting Measurements of Radon and Radon Decay Products in Schools and Large Buildings. The measurements were collected using short-term devices and were analysed by EPA Method 402-R-92-004. Laboratory analysis results are attached. The samples were collected between April 21 and 24, 2025. The results can be found on the attached laboratory analysis report.

Measurements in a number of areas exceeded the EPA's Action Limit of 4.0 pCi/L including:

Eden Elementary School, Room 1	10.0 pCi/L
Eden Elementary School, Room 5	5.3 pCi/L
Eden Elementary School, Room 6	7.6 pCi/L
Eden Elementary School, Pre-K	7.2 pCi/L
Eden Elementary School, Special Ed office	6.0 pCi/L
Cambridge Elementary School, Guidance	4.3 pCi/L

All other measurements were below the EPA's Action Limit of 4.0 pCi/L. Measurements throughout the Eden Elementary School were above the detectable level. You should consider applying any mitigation efforts to the entire school. Measurements can vary with time of year, weather conditions, operation of the heating and ventilation system, and occupancy of the building. Please do not hesitate to call if you have any questions.

Sincerely,

John P. Madigan

Radon test result report for:**CAMBRIDGE**

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
12051544	100	2025-04-21 @ 11:00 am	2025-04-24 @ 7:00 am	< 0.3	2025-04-29
12051519	101	2025-04-21 @ 11:00 am	2025-04-24 @ 7:00 am	0.6 ± 0.4	2025-04-29
12051537	102	2025-04-21 @ 11:00 am	2025-04-24 @ 7:00 am	< 0.3	2025-04-29
12051536	103	2025-04-21 @ 11:00 am	2025-04-24 @ 7:00 am	0.7 ± 0.4	2025-04-29
12051535	104	2025-04-21 @ 11:00 am	2025-04-24 @ 7:00 am	0.9 ± 0.4	2025-04-29
12051517	201	2025-04-21 @ 11:00 am	2025-04-24 @ 7:00 am	< 0.3	2025-04-29
12051503	201	2025-04-21 @ 11:00 am	2025-04-24 @ 7:00 am	< 0.3	2025-04-29
12051514	203	2025-04-21 @ 11:00 am	2025-04-24 @ 7:00 am	< 0.3	2025-04-29
12051502	204	2025-04-21 @ 11:00 am	2025-04-24 @ 7:00 am	< 0.3	2025-04-29
12051506	207	2025-04-21 @ 11:00 am	2025-04-24 @ 7:00 am	< 0.3	2025-04-29
12051507	208	2025-04-21 @ 11:00 am	2025-04-24 @ 7:00 am	< 0.3	2025-04-29
12051509	209	2025-04-21 @ 11:00 am	2025-04-24 @ 7:00 am	< 0.3	2025-04-29
12051511	210	2025-04-21 @ 11:00 am	2025-04-24 @ 7:00 am	< 0.3	2025-04-29
12051518	211	2025-04-21 @ 11:00 am	2025-04-24 @ 7:00 am	< 0.3	2025-04-29
12051521	21ST CENTURY	2025-04-21 @ 11:00 am	2025-04-24 @ 7:00 am	0.6 ± 0.4	2025-04-29
12051530	ADMIN ASSISTANT	2025-04-21 @ 11:00 am	2025-04-24 @ 7:00 am	1.1 ± 0.4	2025-04-29
12051510	CAFETERIA	2025-04-21 @ 11:00 am	2025-04-24 @ 7:00 am	0.6 ± 0.4	2025-04-29
12051538	CLINICIAN	2025-04-21 @ 11:00 am	2025-04-24 @ 7:00 am	1.3 ± 0.4	2025-04-29
12051529	CONFERENCE RM. 2	2025-04-21 @ 11:00 am	2025-04-24 @ 7:00 am	3.7 ± 0.6	2025-04-29
12051526	GUIDANCE	2025-04-21 @ 11:00 am	2025-04-24 @ 7:00 am	4.3 ± 0.6	2025-04-29
12051543	GYM	2025-04-21 @ 11:00 am	2025-04-24 @ 7:00 am	< 0.3	2025-04-29
12051505	KITCHEN	2025-04-21 @ 11:00 am	2025-04-24 @ 7:00 am	0.9 ± 0.4	2025-04-29
12051512	LEARNING COORDINATOR	2025-04-21 @ 11:00 am	2025-04-24 @ 7:00 am	< 0.3	2025-04-29
12051513	LIBRARY	2025-04-21 @ 11:00 am	2025-04-24 @ 7:00 am	< 0.3	2025-04-29
12051532	MAIN OFFICE	2025-04-21 @ 11:00 am	2025-04-24 @ 7:00 am	0.8 ± 0.4	2025-04-29
12051501	NURSE	2025-04-21 @ 11:00 am	2025-04-24 @ 7:00 am	2.9 ± 0.5	2025-04-29
12051531	PRINCIPAL	2025-04-21 @ 11:00 am	2025-04-24 @ 7:00 am	2.0 ± 0.5	2025-04-29
11946798	RESOURCE RM. 1	2025-04-21 @ 11:00 am	2025-04-24 @ 7:00 am	2.1 ± 0.4	2025-04-29
11987059	STAFF ROOM	2025-04-21 @ 10:00 am	2025-04-24 @ 7:00 am	< 0.3	2025-04-29
12051504	STUDENT SUPPORT	2025-04-21 @ 11:00 am	2025-04-24 @ 7:00 am	< 0.3	2025-04-29
12051520	TECH OFFICE	2025-04-21 @ 11:00 am	2025-04-24 @ 7:00 am	< 0.3	2025-04-29

Radon test result report for:**HYDE PARK**

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
11946652	/1	2025-04-21 @ 10:00 am	2025-04-24 @ 10:00 am	< 0.3	2025-04-29
11946667	103	2025-04-21 @ 10:00 am	2025-04-24 @ 10:00 am	< 0.3	2025-04-29
11946679	104	2025-04-21 @ 10:00 am	2025-04-24 @ 10:00 am	< 0.3	2025-04-29
11947095	105	2025-04-21 @ 10:00 am	2025-04-24 @ 10:00 am	< 0.3	2025-04-29
11946653	106	2025-04-21 @ 10:00 am	2025-04-24 @ 10:00 am	< 0.3	2025-04-29
11946601	108	2025-04-21 @ 10:00 am	2025-04-24 @ 10:00 am	< 0.3	2025-04-29
11987399	109	2025-04-21 @ 10:00 am	2025-04-24 @ 10:00 am	< 0.3	2025-04-29
11947077	111	2025-04-21 @ 10:00 am	2025-04-24 @ 10:00 am	< 0.3	2025-04-29
11946659	116	2025-04-21 @ 10:00 am	2025-04-24 @ 10:00 am	< 0.3	2025-04-29
11946674	118	2025-04-21 @ 10:00 am	2025-04-24 @ 10:00 am	0.7 ± 0.4	2025-04-29
11946685	120	2025-04-21 @ 10:00 am	2025-04-24 @ 10:00 am	< 0.3	2025-04-29
11946681	121	2025-04-21 @ 10:00 am	2025-04-24 @ 10:00 am	0.9 ± 0.4	2025-04-29
11946680	13	2025-04-21 @ 10:00 am	2025-04-24 @ 10:00 am	< 0.3	2025-04-29
11946670	14	2025-04-21 @ 10:00 am	2025-04-24 @ 10:00 am	< 0.3	2025-04-29
11947075	15	2025-04-21 @ 10:00 am	2025-04-24 @ 10:00 am	< 0.3	2025-04-29
11946639	202	2025-04-21 @ 10:00 am	2025-04-24 @ 10:00 am	< 0.3	2025-04-29
11946654	203	2025-04-21 @ 10:00 am	2025-04-24 @ 10:00 am	< 0.3	2025-04-29
11946656	205	2025-04-21 @ 10:00 am	2025-04-24 @ 10:00 am	< 0.3	2025-04-29
11947020	212	2025-04-21 @ 10:00 am	2025-04-24 @ 10:00 am	< 0.3	2025-04-29
11946686	215	2025-04-21 @ 10:00 am	2025-04-24 @ 10:00 am	< 0.3	2025-04-29
11946662	216	2025-04-21 @ 10:00 am	2025-04-24 @ 10:00 am	0.8 ± 0.4	2025-04-29
11946672	217	2025-04-21 @ 10:00 am	2025-04-24 @ 10:00 am	< 0.3	2025-04-29
11946668	218	2025-04-21 @ 10:00 am	2025-04-24 @ 10:00 am	< 0.3	2025-04-29
11946644	219	2025-04-21 @ 10:00 am	2025-04-24 @ 10:00 am	< 0.3	2025-04-29
11947094	22	2025-04-21 @ 10:00 am	2025-04-24 @ 10:00 am	0.7 ± 0.4	2025-04-29
11946642	GYM	2025-04-21 @ 10:00 am	2025-04-24 @ 10:00 am	< 0.3	2025-04-29
11946682	KITCHEN	2025-04-21 @ 10:00 am	2025-04-24 @ 10:00 am	0.5 ± 0.4	2025-04-29

Radon test result report for:**JOHNSON**

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
11946648	101	2025-04-21 @ 12:00 pm	2025-04-24 @ 9:00 am	< 0.3	2025-04-29
11947078	102	2025-04-21 @ 12:00 pm	2025-04-24 @ 9:00 am	1.6 ± 0.4	2025-04-29
11947090	103	2025-04-21 @ 12:00 pm	2025-04-24 @ 9:00 am	< 0.3	2025-04-29
11946657	107	2025-04-21 @ 12:00 pm	2025-04-24 @ 9:00 am	< 0.3	2025-04-29
11946658	201	2025-04-21 @ 11:00 am	2025-04-24 @ 9:00 am	< 0.3	2025-04-29
11946646	202	2025-04-21 @ 11:00 am	2025-04-24 @ 9:00 am	< 0.3	2025-04-29
11947098	203A	2025-04-21 @ 11:00 am	2025-04-24 @ 9:00 am	< 0.3	2025-04-29
11946655	203B	2025-04-21 @ 12:00 pm	2025-04-24 @ 9:00 am	< 0.3	2025-04-29
11946665	204	2025-04-21 @ 12:00 pm	2025-04-24 @ 9:00 am	< 0.3	2025-04-29
11946673	205	2025-04-21 @ 12:00 pm	2025-04-24 @ 9:00 am	< 0.3	2025-04-29
11946651	206	2025-04-21 @ 12:00 pm	2025-04-24 @ 9:00 am	< 0.3	2025-04-29
11946649	207	2025-04-21 @ 12:00 pm	2025-04-24 @ 9:00 am	< 0.3	2025-04-29
11946677	209	2025-04-21 @ 11:00 am	2025-04-24 @ 9:00 am	1.0 ± 0.4	2025-04-29
11946640	210	2025-04-21 @ 11:00 am	2025-04-24 @ 9:00 am	0.9 ± 0.4	2025-04-29
11947091	211	2025-04-21 @ 11:00 am	2025-04-24 @ 9:00 am	1.7 ± 0.5	2025-04-29
11946664	212	2025-04-21 @ 11:00 am	2025-04-24 @ 9:00 am	0.6 ± 0.4	2025-04-29
11946684	213	2025-04-21 @ 11:00 am	2025-04-24 @ 9:00 am	0.7 ± 0.4	2025-04-29
11946678	214	2025-04-21 @ 11:00 am	2025-04-24 @ 9:00 am	0.6 ± 0.4	2025-04-29
11946671	215	2025-04-21 @ 11:00 am	2025-04-24 @ 9:00 am	1.2 ± 0.4	2025-04-29
11946661	216	2025-04-21 @ 11:00 am	2025-04-24 @ 9:00 am	0.7 ± 0.4	2025-04-29
11946663	217	2025-04-21 @ 11:00 am	2025-04-24 @ 9:00 am	< 0.3	2025-04-29
11947096	218	2025-04-21 @ 11:00 am	2025-04-24 @ 9:00 am	0.9 ± 0.4	2025-04-29
11947089	301	2025-04-21 @ 12:00 pm	2025-04-24 @ 9:00 am	< 0.3	2025-04-29
11947063	302	2025-04-21 @ 12:00 pm	2025-04-24 @ 9:00 am	< 0.3	2025-04-29
11947087	303	2025-04-21 @ 12:00 pm	2025-04-24 @ 9:00 am	< 0.3	2025-04-29
11946797	304	2025-04-21 @ 12:00 pm	2025-04-24 @ 9:00 am	< 0.3	2025-04-29
11946800	305	2025-04-21 @ 12:00 pm	2025-04-24 @ 9:00 am	< 0.3	2025-04-29
11946899	306	2025-04-21 @ 12:00 pm	2025-04-24 @ 9:00 am	< 0.3	2025-04-29
11946645	307	2025-04-21 @ 12:00 pm	2025-04-24 @ 9:00 am	< 0.3	2025-04-29
11947067	308	2025-04-21 @ 12:00 pm	2025-04-24 @ 9:00 am	< 0.3	2025-04-29
11946643	309	2025-04-21 @ 12:00 pm	2025-04-24 @ 9:00 am	< 0.3	2025-04-29
11946893	310	2025-04-21 @ 12:00 pm	2025-04-24 @ 9:00 am	< 0.3	2025-04-29
11947008	311	2025-04-21 @ 12:00 pm	2025-04-24 @ 9:00 am	< 0.3	2025-04-29
11947086	CAFETERIA	2025-04-21 @ 12:00 pm	2025-04-24 @ 9:00 am	< 0.3	2025-04-29
11946650	KITCHEN	2025-04-21 @ 12:00 pm	2025-04-24 @ 9:00 am	0.6 ± 0.4	2025-04-29

Radon test result report for:

GMTCC

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
12051523	CEC	2025-04-21 @ 9:00 am	2025-04-24 @ 8:00 am	< 0.3	2025-04-29
11946615	HT12	2025-04-21 @ 9:00 am	2025-04-24 @ 8:00 am	< 0.3	2025-04-29
11987058	HT2	2025-04-21 @ 9:00 am	2025-04-24 @ 8:00 am	< 0.3	2025-04-29
11987020	HT4	2025-04-21 @ 9:00 am	2025-04-24 @ 8:00 am	< 0.3	2025-04-29
11987041	HT6	2025-04-21 @ 9:00 am	2025-04-24 @ 8:00 am	< 0.3	2025-04-29
11987043	T11	2025-04-21 @ 9:00 am	2025-04-24 @ 8:00 am	< 0.3	2025-04-29
11987062	T12	2025-04-21 @ 9:00 am	2025-04-24 @ 8:00 am	< 0.3	2025-04-29
12051524	T12B	2025-04-21 @ 9:00 am	2025-04-24 @ 8:00 am	< 0.3	2025-04-29
11987039	T14	2025-04-21 @ 9:00 am	2025-04-24 @ 8:00 am	< 0.3	2025-04-29
11987094	T16	2025-04-21 @ 9:00 am	2025-04-24 @ 8:00 am	< 0.3	2025-04-29
11987044	T17	2025-04-21 @ 9:00 am	2025-04-24 @ 8:00 am	< 0.3	2025-04-29
11987007	T18	2025-04-21 @ 9:00 am	2025-04-24 @ 8:00 am	< 0.3	2025-04-29
11987005	T20	2025-04-21 @ 9:00 am	2025-04-24 @ 8:00 am	< 0.3	2025-04-29
11946629	T21	2025-04-21 @ 9:00 am	2025-04-24 @ 8:00 am	< 0.3	2025-04-29
11987045	T22	2025-04-21 @ 9:00 am	2025-04-24 @ 8:00 am	< 0.3	2025-04-29
11987040	T23	2025-04-21 @ 9:00 am	2025-04-24 @ 8:00 am	< 0.3	2025-04-29
11946604	T24	2025-04-21 @ 9:00 am	2025-04-24 @ 8:00 am	< 0.3	2025-04-29
11987073	T27	2025-04-21 @ 9:00 am	2025-04-24 @ 8:00 am	0.6 ± 0.4	2025-04-29
11947059	T28	2025-04-21 @ 9:00 am	2025-04-24 @ 8:00 am	< 0.3	2025-04-29
12051516	T29	2025-04-21 @ 9:00 am	2025-04-24 @ 8:00 am	< 0.3	2025-04-29
12051508	T30	2025-04-21 @ 9:00 am	2025-04-24 @ 8:00 am	< 0.3	2025-04-29
12051515	T36	2025-04-21 @ 9:00 am	2025-04-24 @ 8:00 am	< 0.3	2025-04-29
11987067	T6B	2025-04-21 @ 9:00 am	2025-04-24 @ 8:00 am	0.5 ± 0.4	2025-04-29
11987071	T6C	2025-04-21 @ 9:00 am	2025-04-24 @ 8:00 am	< 0.3	2025-04-29
11987080	T6D	2025-04-21 @ 9:00 am	2025-04-24 @ 8:00 am	< 0.3	2025-04-29
11987069	T6E	2025-04-21 @ 9:00 am	2025-04-24 @ 8:00 am	< 0.3	2025-04-29
11947072	T6F	2025-04-21 @ 9:00 am	2025-04-24 @ 8:00 am	< 0.3	2025-04-29
11946635	T7	2025-04-21 @ 9:00 am	2025-04-24 @ 8:00 am	< 0.3	2025-04-29

Radon test result report for:**LUHS**

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
11987018	A101	2025-04-21 @ 11:00 am	2025-04-24 @ 9:00 am	< 0.3	2025-04-29
11946607	A102A	2025-04-21 @ 11:00 am	2025-04-24 @ 9:00 am	0.6 ± 0.4	2025-04-29
11947068	A103	2025-04-21 @ 11:00 am	2025-04-24 @ 9:00 am	< 0.3	2025-04-29
11987038	A104	2025-04-21 @ 11:00 am	2025-04-24 @ 9:00 am	< 0.3	2025-04-29
11987081	A203	2025-04-21 @ 11:00 am	2025-04-24 @ 10:00 am	< 0.3	2025-04-29
11987088	A206	2025-04-21 @ 11:00 am	2025-04-24 @ 10:00 am	< 0.3	2025-04-29
11987050	A215	2025-04-21 @ 11:00 am	2025-04-24 @ 10:00 am	< 0.3	2025-04-29
11946638	ADMIN ASSISTANT	2025-04-21 @ 11:00 am	2025-04-24 @ 9:00 am	< 0.3	2025-04-29
11987013	ART	2025-04-21 @ 11:00 am	2025-04-24 @ 9:00 am	< 0.3	2025-04-29
11987026	ART 1	2025-04-21 @ 11:00 am	2025-04-24 @ 9:00 am	< 0.3	2025-04-29
11987028	ART 2	2025-04-21 @ 11:00 am	2025-04-24 @ 9:00 am	< 0.3	2025-04-29
11987024	AUDITORIUM	2025-04-21 @ 11:00 am	2025-04-24 @ 9:00 am	< 0.3	2025-04-29
11987063	B102	2025-04-21 @ 10:00 am	2025-04-24 @ 9:00 am	< 0.3	2025-04-29
11987089	B103	2025-04-21 @ 10:00 am	2025-04-24 @ 9:00 am	< 0.3	2025-04-29
11946625	B104	2025-04-21 @ 10:00 am	2025-04-24 @ 9:00 am	< 0.3	2025-04-29
11987002	B105	2025-04-21 @ 11:00 am	2025-04-24 @ 9:00 am	< 0.3	2025-04-29
11987083	B106	2025-04-21 @ 10:00 am	2025-04-24 @ 9:00 am	< 0.3	2025-04-29
11946637	B107	2025-04-21 @ 11:00 am	2025-04-24 @ 9:00 am	< 0.3	2025-04-29
11987068	B108	2025-04-21 @ 10:00 am	2025-04-24 @ 9:00 am	< 0.3	2025-04-29
11987049	B109	2025-04-21 @ 11:00 am	2025-04-24 @ 9:00 am	< 0.3	2025-04-29
11987042	B111	2025-04-21 @ 11:00 am	2025-04-24 @ 9:00 am	< 0.3	2025-04-29
11987095	B112	2025-04-21 @ 10:00 am	2025-04-24 @ 9:00 am	< 0.3	2025-04-29
11987032	B113	2025-04-21 @ 11:00 am	2025-04-24 @ 9:00 am	< 0.3	2025-04-29
11987070	B115	2025-04-21 @ 11:00 am	2025-04-24 @ 9:00 am	< 0.3	2025-04-29
11987036	B206	2025-04-21 @ 11:00 am	2025-04-24 @ 10:00 am	< 0.3	2025-04-29
11987035	B215	2025-04-21 @ 11:00 am	2025-04-24 @ 10:00 am	< 0.3	2025-04-29
11987052	BAND ROOM	2025-04-21 @ 11:00 am	2025-04-24 @ 9:00 am	< 0.3	2025-04-29
12051522	BRAGGINS	2025-04-21 @ 11:00 am	2025-04-24 @ 9:00 am	< 0.3	2025-04-29
11987015	BUSINESS LAB	2025-04-21 @ 11:00 am	2025-04-24 @ 9:00 am	< 0.3	2025-04-29
11987030	CAFETERIA	2025-04-21 @ 9:00 am	2025-04-24 @ 9:00 am	< 0.3	2025-04-29
11946610	CREIGHTON	2025-04-21 @ 11:00 am	2025-04-24 @ 9:00 am	< 0.3	2025-04-29
11987061	FACS	2025-04-21 @ 11:00 am	2025-04-24 @ 9:00 am	< 0.3	2025-04-29
11987022	FACS	2025-04-21 @ 11:00 am	2025-04-24 @ 9:00 am	< 0.3	2025-04-29
11987029	GUIDANCE 1	2025-04-21 @ 11:00 am	2025-04-24 @ 9:00 am	< 0.3	2025-04-29
11987090	GUIDANCE 2	2025-04-21 @ 11:00 am	2025-04-24 @ 9:00 am	< 0.3	2025-04-29
11987055	GUIDANCE 3	2025-04-21 @ 11:00 am	2025-04-24 @ 9:00 am	< 0.3	2025-04-29
11987048	GUIDANCE 4	2025-04-21 @ 11:00 am	2025-04-24 @ 9:00 am	< 0.3	2025-04-29

Radon test result report for:**LUHS**

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
11946603	GUIDANCE 5	2025-04-21 @ 11:00 am	2025-04-24 @ 9:00 am	< 0.3	2025-04-29
11987010	GUIDANCE 6	2025-04-21 @ 11:00 am	2025-04-24 @ 9:00 am	< 0.3	2025-04-29
11987011	GYM	2025-04-21 @ 10:00 am	2025-04-24 @ 9:00 am	< 0.3	2025-04-29
11987027	KITCHEN	2025-04-21 @ 10:00 am	2025-04-24 @ 9:00 am	< 0.3	2025-04-29
11987057	L100	2025-04-21 @ 10:00 am	2025-04-24 @ 9:00 am	< 0.3	2025-04-29
11987033	L101	2025-04-21 @ 10:00 am	2025-04-24 @ 9:00 am	< 0.3	2025-04-29
11987096	LIBRARY	2025-04-21 @ 11:00 am	2025-04-24 @ 9:00 am	< 0.3	2025-04-29
11987086	M203	2025-04-21 @ 11:00 am	2025-04-24 @ 10:00 am	< 0.3	2025-04-29
11987051	M209	2025-04-21 @ 11:00 am	2025-04-24 @ 10:00 am	< 0.3	2025-04-29
11946630	MORIN	2025-04-21 @ 11:00 am	2025-04-24 @ 9:00 am	< 0.3	2025-04-29
11987021	MULTIMEDIA	2025-04-21 @ 11:00 am	2025-04-24 @ 9:00 am	< 0.3	2025-04-29
11987075	MULTIPURPOSE	2025-04-21 @ 11:00 am	2025-04-24 @ 10:00 am	< 0.3	2025-04-29
11987001	NURSE	2025-04-21 @ 11:00 am	2025-04-24 @ 9:00 am	< 0.3	2025-04-29
11987019	OFFICE 1	2025-04-21 @ 10:00 am	2025-04-24 @ 9:00 am	< 0.3	2025-04-29
11987037	OFFICE 1	2025-04-21 @ 11:00 am	2025-04-24 @ 10:00 am	< 0.3	2025-04-29
11987025	OFFICE 5	2025-04-21 @ 11:00 am	2025-04-24 @ 9:00 am	< 0.3	2025-04-29
11987064	REGISTRAR	2025-04-21 @ 11:00 am	2025-04-24 @ 9:00 am	< 0.3	2025-04-29
11987060	TEC ED	2025-04-21 @ 11:00 am	2025-04-24 @ 9:00 am	< 0.3	2025-04-29
11987014	TECHNOLOGY LAB	2025-04-21 @ 11:00 am	2025-04-24 @ 9:00 am	< 0.3	2025-04-29
11946606	THERAPY	2025-04-21 @ 10:00 am	2025-04-24 @ 9:00 am	< 0.3	2025-04-29
11987092	VOCAL MUSIC	2025-04-21 @ 11:00 am	2025-04-24 @ 9:00 am	< 0.3	2025-04-29

April 29, 2025

**** LABORATORY ANALYSIS REPORT ****

Radon test result report for:

LUML

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
11987066	OFFICE 2	2025-04-21 @ 11:00 am	2025-04-24 @ 10:00 am	< 0.3	2025-04-29
11987085	OFFICE 3	2025-04-21 @ 11:00 am	2025-04-24 @ 10:00 am	< 0.3	2025-04-29
11987054	OFFICE 4	2025-04-21 @ 11:00 am	2025-04-24 @ 10:00 am	< 0.3	2025-04-29
11987087	PLANNING RM	2025-04-21 @ 11:00 am	2025-04-24 @ 10:00 am	< 0.3	2025-04-29

Air Chek 1936 Butler Bridge Rd, Mills River, NC 28759-3892 Phone: (828) 684-0893 Fax: (828) 684-8498

April 29, 2025

**** LABORATORY ANALYSIS REPORT ****

Radon test result report for:

LUMS

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
11987072	B205	2025-04-21 @ 11:00 am	2025-04-24 @ 10:00 am	< 0.3	2025-04-29

Air Chek 1936 Butler Bridge Rd, Mills River, NC 28759-3892 Phone: (828) 684-0893 Fax: (828) 684-8498

Radon test result report for:
ECS

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
11947097	1	2025-04-21 @ 1:00 pm	2025-04-24 @ 1:00 pm	10.0 ± 0.8	2025-04-29
11987372	1ST	2025-04-21 @ 1:00 pm	2025-04-24 @ 1:00 pm	2.6 ± 0.5	2025-04-29
11987375	2	2025-04-21 @ 1:00 pm	2025-04-24 @ 1:00 pm	3.1 ± 0.5	2025-04-29
11946636	226	2025-04-21 @ 1:00 pm	2025-04-24 @ 1:00 pm	0.6 ± 0.4	2025-04-29
11947076	22A	2025-04-21 @ 1:00 pm	2025-04-24 @ 1:00 pm	< 0.3	2025-04-29
11987381	22B	2025-04-21 @ 1:00 pm	2025-04-24 @ 1:00 pm	0.6 ± 0.4	2025-04-29
11947084	22C	2025-04-21 @ 1:00 pm	2025-04-24 @ 1:00 pm	3.7 ± 0.5	2025-04-29
11947058	22E	2025-04-21 @ 1:00 pm	2025-04-24 @ 1:00 pm	1.1 ± 0.4	2025-04-29
11946762	22F	2025-04-21 @ 1:00 pm	2025-04-24 @ 1:00 pm	< 0.3	2025-04-29
11946896	2ND	2025-04-21 @ 1:00 pm	2025-04-24 @ 1:00 pm	2.4 ± 0.5	2025-04-29
11947081	3RD	2025-04-21 @ 1:00 pm	2025-04-24 @ 1:00 pm	3.5 ± 0.5	2025-04-29
11946894	3RD	2025-04-21 @ 1:00 pm	2025-04-24 @ 1:00 pm	2.7 ± 0.5	2025-04-29
11947061	5	2025-04-21 @ 1:00 pm	2025-04-24 @ 1:00 pm	5.3 ± 0.6	2025-04-29
11987382	5TH	2025-04-21 @ 1:00 pm	2025-04-24 @ 1:00 pm	2.2 ± 0.4	2025-04-29
11987374	6	2025-04-21 @ 1:00 pm	2025-04-24 @ 1:00 pm	7.6 ± 0.7	2025-04-29
11947062	6TH	2025-04-21 @ 1:00 pm	2025-04-24 @ 1:00 pm	3.8 ± 0.5	2025-04-29
11946898	GYM	2025-04-21 @ 1:00 pm	2025-04-24 @ 1:00 pm	1.8 ± 0.4	2025-04-29
11947083	KINDERGARTEN	2025-04-21 @ 1:00 pm	2025-04-24 @ 1:00 pm	3.8 ± 0.5	2025-04-29
11946900	KITCHEN	2025-04-21 @ 1:00 pm	2025-04-24 @ 1:00 pm	1.0 ± 0.4	2025-04-29
11947051	LIBRARY	2025-04-21 @ 1:00 pm	2025-04-24 @ 1:00 pm	3.5 ± 0.5	2025-04-29
11947055	MUSIC	2025-04-21 @ 1:00 pm	2025-04-24 @ 1:00 pm	< 0.3	2025-04-29
11947093	PLANNING ROOM	2025-04-21 @ 1:00 pm	2025-04-24 @ 1:00 pm	3.6 ± 0.5	2025-04-29
11946799	PRE-K	2025-04-21 @ 1:00 pm	2025-04-24 @ 1:00 pm	7.2 ± 0.6	2025-04-29
11946891	SPED OFFICE	2025-04-21 @ 1:00 pm	2025-04-24 @ 1:00 pm	6.0 ± 0.6	2025-04-29

April 29, 2025

**** LABORATORY ANALYSIS REPORT ****

Radon test result report for:
WES

Kit #	Room Id	Started	Ended	pCi/L	Analyzed
11947085	1	2025-04-21 @ 12:00 pm	2025-04-24 @ 8:00 am	0.8 ± 0.4	2025-04-29
11947082	15	2025-04-21 @ 12:00 pm	2025-04-24 @ 8:00 am	< 0.3	2025-04-29
11946669	16	2025-04-21 @ 12:00 pm	2025-04-24 @ 8:00 am	0.8 ± 0.4	2025-04-29
11947060	17	2025-04-21 @ 12:00 pm	2025-04-24 @ 8:00 am	< 0.3	2025-04-29
11987016	2	2025-04-21 @ 12:00 pm	2025-04-24 @ 8:00 am	< 0.3	2025-04-29
11987065	3	2025-04-21 @ 12:00 pm	2025-04-24 @ 8:00 am	< 0.3	2025-04-29
11947092	4	2025-04-21 @ 12:00 pm	2025-04-24 @ 8:00 am	< 0.3	2025-04-29
11987023	5	2025-04-21 @ 12:00 pm	2025-04-24 @ 8:00 am	0.6 ± 0.4	2025-04-29
11987046	6	2025-04-21 @ 12:00 pm	2025-04-24 @ 8:00 am	< 0.3	2025-04-29
11947088	7	2025-04-21 @ 12:00 pm	2025-04-24 @ 8:00 am	< 0.3	2025-04-29
11946647	8	2025-04-21 @ 12:00 pm	2025-04-24 @ 8:00 am	< 0.3	2025-04-29
11946641	9	2025-04-21 @ 12:00 pm	2025-04-24 @ 8:00 am	< 0.3	2025-04-29
11947065	GYM	2025-04-21 @ 12:00 pm	2025-04-24 @ 8:00 am	< 0.3	2025-04-29
11946660	KITCHEN	2025-04-21 @ 12:00 pm	2025-04-24 @ 8:00 am	0.6 ± 0.4	2025-04-29