

**ADDENDUM NO. 1**


February 2, 2026

Project: Beaumont ISD Stadium Score Board

Prepared by: Salas O'Brien Engineers  
10930 W. Sam Houston Parkway N., Suite 900  
Houston, Texas 77064

SOBE Project No.: 2550-02337

Prepared For: Prospective Proposers

**PART A: NOTICE TO PROPOSERS**

1. Receipt of this Addendum shall be acknowledged on the Proposal Form. Failure to do so may subject Proposers to disqualification. Each Proposer shall make necessary adjustments and submit his proposal with full knowledge of all modifications, clarifications, and supplemental data included therein.
2. This Addendum forms part of the Contract Documents and shall be incorporated integrally therewith. Where provisions of the following supplemental data differ from those of previously issued documents, this Addendum shall govern.
3. The following Contract Documents have been issued to date delineating the Work (Project). Contract Documents dated: January 6, 2026
4. This Addendum consists of 3 typewritten pages and no page of attachments for a total of 3 pages.

**PART B: CHANGES TO PRIOR ADDENDUM**

1. None

**PART C: CHANGES TO THE PROJECT MANUAL**

1. None

**PART D: CHANGES TO THE DRAWINGS**

1. None

**PART E: RE-ISSUED DRAWING SHEET (30"X42")**

1. None

**PART F: NEW DRAWINGS SHEETS (30"X42")**

1. None

**PART G: QUESTIONS/CLARIFICATIONS****Comments from preproposal Meeting:**

1. **Procurement Method**  
Is this project being administered through a cooperative purchasing agreement (CO-OP)? If so, please specify which cooperative applies.

**RESPONSE:** CSP only

2. **Clock Systems**  
Should the existing locker-room clocks be reallocated as part of this project, or should new clocks be included in our proposal?

**RESPONSE:** Yes, new clocks installed at existing locations four total.

Are delay-of-game clocks required as part of the project scope?

**RESPONSE:** Yes, replace clocks at existing location.

3. **Video and Replay Systems**

Should our proposal include any cameras and/or a four-channel replay capability?

**RESPONSE:** Yes, include at least 3 cameras and 4 channel replay system.

4. **Audio System**

Is a new audio system included within the project scope, or should it be excluded from our proposal?

**RESPONSE:** Yes, a new audio system is to be included.

5. **Audible Signaling**, should a horn be included as part of the proposed system?

**RESPONSE:** Yes, horn should be provided

6. Are bids to include all necessary electrical and fiber upgrades? The CSP doc on page 11 says *“Removal/replacement of current scoreboard and electrical upgrades to support new board”* but Project specs on page 115 say *“All power distribution from the disconnect to the sign to be provided by the owner. The Contractor is responsible for all power distribution inside the LED”* and on page 108 *“Any necessary signal/control conduit and cable raceways for cable runs to and from display components will be provided by others. All fiber to be provided by the Contractor.”*

**RESPONSE:** All electrical work is shown in the contract documents and to be provided. Reference Sheets: E01, E1.0, E2.0, All power distribution is to be provided in this contract. Electrical. All power distribution from the disconnect to the sign to be provided by THIS CONTRACTOR. The Contractor is responsible for all power distribution inside the LED display as required.

7. Our original bid, prior to the release of the CSP, included: Delay of Game Clocks, Sound System, Backlit Truss above the display with speaker mesh, (4) cameras (3 wireless and 1 wired). I did not see those items listed in any of the documents. Are any of those listed items to be provided in the bid?

**RESPONSE:** Yes, all video and audio equipment, and game clocks are to be provided as per original proposal.

8. We originally provided a bid on the Natatorium LED display. I just want to confirm that is not part of the scope. If it is not, is there a plan to release another CSP for that project?

**RESPONSE:** The Natatorium is not part of this CSP scope.

**CLARIFICATIONS**

1. Game Clocks TO BE RELACED AT EXISTING LOCATION
  - A. Clocks
    1. 4” red digit – 8”x1’-3”x3.25” or similar (Qty: 5)

**PART H. ATTACHMENTS**

1. None

**END OF ADDENDUM 1**