

BID ADDENDUM NO. 2

OWNER: EDGEMONT UNION FREE SCHOOL DISTRICT

PROJECT NAME: SEELY PLACE ES & GREENVILLE ES,
INTERIOR RENOVATIONS & SITE IMPROVEMENTS

This Addendum is hereby included in and made a part of the Contract Documents, dated January 14, 2026 whether or not attached thereto.

All requirements of the original project specifications and drawings shall remain in force except as amended by this addendum.

DATE: February 3, 2026

This addendum consists of three (3) pages plus new specification section 33 4213 Ductile Iron Sanitary Sewer Pipe, Sketch SK-1 and revised drawings GVES C100, GVES C101, GVES C102, GVES C103 and new drawing GVES C504.

THE FOLLOWING ARE MODIFICATIONS, CLARIFICATIONS, DELETIONS OR ADDITIONS TO THE SPECIFICATIONS:

01 1000 – SUMMARY OF CONTRACTS

01 1000-10, 1.19 C REVISE height of fence from 8' to 6'.

33 4213 – PIPE CULVERTS

33 4213-4 2.1 B2 **DELETE** in its entirety.

THE FOLLOWING ARE MODIFICATIONS, CLARIFICATIONS, DELETIONS OR ADDITIONS TO THE DRAWINGS:

DRAWING G-1 – GENERAL INFORMATION SHEET

ADD Drawing GVES C504 to Contract #5 Site Constructionnote “Utility trench excavation/backfill for the HVAC underground piping by Site GC, piping by M-Contractor”.

DRAWING SPES C103 – GRADING AND UTILITY PLAN

ADD note “Utility trench excavation/backfill for the HVAC underground piping by Site GC, piping by M-Contractor”.

DRAWING SPES C502 – TYPICAL SECTIONS AND DETAILS

Detail 7 **REVISE** note “6” Sch. 80 steel pipe filled with concrete – see note 2 for bollard cover details” to read “Traffic Guard, stainless fixed post – Model RFP6660RS, 304 stainless steel, #4 brushed finish, 6.525” outside diameter”.

Detail 8 **REVISE** thicnes of pad from 6” to 8”.

DRAWING GVES C102 – SITE LAYOUT AND MATERIALS AND PLANTING PLAN

REVISE note “Provide New Water Fountain With Bottle Filler – See Specs” to read “Provide New Water Fountain With Bottle Filler – See Specs and the following notes:

1. All work shall comply with applicable plumbing codes, manufacturer installation requirements, and Owner’s standards.

2. Connect the fountain and bottle filler to the existing water service, including any required valves, fittings, or adapters.
3. Verify proper water supply, pressure and flow.
4. Test the fountain and bottle filler to ensure proper operation.
5. Coordinate any required shutdowns or connections with the Owner's Representative and/or utility company.
6. Provide all labor, materials, and equipment necessary to install the fountain and bottle filler."

DRAWING GVES C101 – DEMOLITION AND EROSION AND SEDIMENTATION CONTROL PLAN

REVISE note" Portion of Existing Storm Pipe To Be Abandoned In Place" to read "Portion of Existing Storm Pipe To remain in place".

DRAWING GVES C501 – SITE CONSTRUCTION DETAILS - 1

Detail 9 **REVISE** detail as per Sketch SK-1 attached to this addendum.

DRAWING SPES A110 – CLASSROOM PLANS & INTERIOR ELEVATIONS

Material Storage 107.2 **ADD** 16 shelf standards, 4 feet long and four (4) shelves @ 20 l.f. similar to detail 10/A525.

DRAWING SPES M100 – MECHANICAL PLANS

Mechanical General Notes **ADD** "18. RTU-1 shall be furnished with a factory 24" tall roof curb, to be installed at time of roof replacement. If manufacturer does not offer 24" tall curb option, furnish custom curb by Cambridgeport." Detail 1, **REVISE** all references to "Aquatherm PP-R" to "Clima Allpro preinsulated piping by Niron, SDR11 or approved equal. Joints shall be made via heat fusion."

DRAWING GVES A110 – PARTIAL FIRST FLOOR PLANS & INTERIOR ELEVATIONS

Material Storage A1.2 **ADD** 16 shelf standards, 4 feet long and four (4) shelves @ 20 l.f. similar to detail 10/A525.

END OF BID ADDENDUM NO. 2

The following attachments are being provided for informational purposes:

Bidder RFI Responses (In the event of a discrepancy between these responses and the contract documents, the contract documents shall prevail unless modified by addendum.)

Bid RFI-#010 dated 1/28/2026 (2 pages).
Bid RFI-#011 dated 1/28/2026 (2 pages).
Bid RFI-#012 dated 1/28/2026 (2 pages).
Bid RFI-#013 dated 1/29/2026 (2 pages).
Bid RFI-#014 dated 1/29/2026 (2 pages).
Bid RFI-#015 dated 1/29/2026 (2 pages).
Bid RFI-#016 dated 1/29/2026 (2 pages).
Bid RFI-#017 dated 2/2/2026 (2 pages).
Bid RFI-#018 dated 2/2/2026 (2 pages).
Bid RFI-#019 dated 2/2/2026 (2 pages).
Bid RFI-#020 dated 2/2/2026 (2 pages).
Bid RFI-#021 dated 1/30/2026 (2 pages).
Bid RFI-#022 dated 2/2/2026 (2 pages).
Bid RFI-#023 dated 1/28/2026 (2 pages).
Bid RFI-#024 dated 1/30/2026 (2 pages).
Bid RFI-#025 dated 2/2/2026 (2 pages).
Bid RFI-#026 dated 2/2/2026 (2 pages).
Bid RFI-#027 dated 2/2/2026 (2 pages).
Bid RFI-#028 dated 2/2/2026 (2 pages).

Bid RFI-#029 dated 2/2/2026 (2 pages).
Bid RFI-#030 dated 2/2/2026 (2 pages).
Bid RFI-#031 dated 2/2/2026 (2 pages).
Bid RFI-#032 dated 2/2/2026 (2 pages).
Bid RFI-#033 dated 2/2/2026 (2 pages).
Bid RFI-#034 dated 2/2/2026 (2 pages).
Bid RFI-#035 dated 2/2/2026 (2 pages).
Bid RFI-#036 dated 2/2/2026 (2 pages).
Bid RFI-#037 dated 2/2/2026 (2 pages).
Bid RFI-#038 dated 2/2/2026 (2 pages).
Bid RFI-#039 dated 2/2/2026 (2 pages).
Bid RFI-#040 dated 2/2/2026 (2 pages).
Bid RFI-#041 dated 2/2/2026 (2 pages).