

RFP Addendum No. 02

DATE ISSUED: February 18, 2026
TO: Invited Bidders
FROM OWNER'S REPRESENTATIVE: Collin Frink
Plante Moran Realpoint
3000 Town Center, Suite 100
Southfield, MI 48075
ON BEHALF OF CLIENT: Livonia Public Schools (LPS)
SUBJECT: Addendum for Central Office Paving Phase 3

DESCRIPTION OF CHANGES

- Item 1: The Bid Due date and opening has been changed to February 24, 2026 at 12pm
- Item 2: Question and Answer Log (2 Pages)

Livonia Public Schools 2026 Paving Program – Q/A

Question 1

Q: Is everything full depth replacement including the stone or is it a mill and cap with base repairs TBD.

A: Base bid includes a partial-depth mill and overlay for all asphalt pavement areas as indicated on the project plans. Base bid shall also include the Milled Surface Patching Allowances as indicated on the project plans and Specification Section 01 2100. There are multiple alternates for alternative repairs as indicated in Specification Section 01 2300 Alternates.

Question 2

Q: The plan shows a lot of bumper blocks but there is nothing called out for them. I assume you want to salvage and re-use?

A: The typical demolition note on the Demolition Plans calls to remove and dispose of the parking blocks, and the typical detail callout on the Site Engineering Plans calls to install new parking blocks per Detail PB.

Question 3

Q: What is the difference in the bid pack between “remove and replace” and “reconstruct”? I assume remove and replace is asphalt only and the other means the stone as well, please confirm.

A: That assumption is correct. As noted on the Bid Form under the Alternate Bids pricing section. Refer to Specification Section 01 2300 for detailed information on alternates.

Question 4

Q: The prebid minutes reference all remaining or unused permit funds are to be returned to the owner. I don't see where there is a permit allowance in the project. How are permits being handled (and will the city even get around to issuing one)?

A: We do not anticipate any permits being required with how we are structuring the plans and bids.

Question 5

Q: The meeting minutes state we are to replace box outs and perform drainage structure repairs to catch basins and as shown or as needed. The plans show all collars to remain

and be protected. If the box outs are to remain and be protected, we can't replace them nor can we perform the drainage structure repairs. How should this be addressed?

A: Most box outs were recently replaced or repaired. The plan is to protect and leave in place. Replace or repair if needed after review with the engineer and district based on unit pricing provided.