

Hoover Middle School Portable Classroom Updates

BID # 2025-9

- Project Advertising: February 19, 2026 and February 26, 2026
- Mandatory Job Walk: March 4 at 10:00 a.m.
- Bids Due: Wednesday, March 25, 2026 at 2:00 p.m.
- Projected Award Date: April 14, 2026

SCOPE OF WORK

Room 30

- Refinish Ramp – *SEE PROJECT SPECIFICATION*
- Replace Roof – *SEE PROJECT SPECIFICATIONS*
- Replace / Paint Dry Rot Panel Boards (Exterior)
- New Carpet / baseboard
- New Ceiling Tiles
- New Lights
- New Tackboard
- New Window Coverings
- Floor leveling / Float
- New Whiteboard
- Electrical / Data / Audio-Video Connections (*Will be detailed at job walk*)

Room 31

- Refinish Ramp – *SEE PROJECT SPECIFICATION*
- New Whiteboard
- New Window Coverings
- New Ceiling Tiles
- New Lights
- New Carpet / baseboard
- Paint Tackboard
- Electrical / Data / Audio-Video Connections (*Will be detailed at job walk*)

Room 32

- Refinish Ramp – *SEE PROJECT SPECIFICATION*
- New Whiteboard
- New Window Coverings
- New Tackboard (East, West, and South Walls only)
- Floor Leveling / Float
- New Carpet / baseboard

Room 33

- Refinish Ramp – *SEE PROJECT SPECIFICATION*
- New Window Coverings
- New Ceiling Tiles
- New Lights
- New Carpet / baseboard
- Electrical / Data / Audio-Video Connections (*Will be detailed at job walk*)

Add Alternates:

- (1) Reroof Room 31
- (2) Reroof Room 32
- (3) Reroof Room 33

PROJECT SPECIFICATIONS

- Refinish Ramp - Marine Grade Plywood Anti-Slip Epoxy
- Whiteboards – 16' x 5' with full-length pen shelf (magnetic)
 - [Link to Markerboard with 1" map rail](#) **Must be equivalent to this style**
- Carpet Tiles – Tarkett Aftermath II (Tapestry 23512)
- Lights – Lithonia Lighting LED C Panel CPX-2x4-ALO80SWW7
- Window Coverings – Hunter Douglas Roller & Screen Shades AGO – Agora 0% 832-Hadrian Wall
- Tackboard – Chatfield Clarke – Belair Misty Grey (8.5' floor to ceiling)
- Roofing Info: *SEE SUMMARY OF WORK AND PROJECT DRAWINGS*