21 Griffin Rd. North
Windsor, CT 06095
T 860.298.9692
TRCcompanies.com

February 13, 2026

Mr. Angelus Papageorge
Director of Operations
Fairfield Public Schools
501 Kings Highway East, Suite 210
Fairfield, CT 06825

Via email: apapageorge@fairfieldschools.org

**Re: Radon Re-Evaluation – December 2025/January 2026**
**Fairfield Public Schools**
TRC Project Number: 685659

Dear Mr. Papageorge:

TRC Environmental Corporation (TRC) conducted radon in air testing for Fairfield Public Schools as required under the Connecticut Indoor Air Quality in Schools Act (CGS 10-220(d)).

Fairfield Public Schools is composed of the following seventeen (17) school buildings:

1. Burr Elementary School
2. Dwight Elementary School
3. Holland Hill Elementary School
4. Jennings Elementary School
5. McKinley Elementary School
6. Mill Hill Elementary School
7. North Stratfield Elementary School
8. Osborne Hill Elementary School
9. Riverfield Elementary School
10. Roger Sherman Elementary School
11. Stratfield Elementary School
12. Fairfield Woods Middle School
13. Roger Ludlowe Middle School
14. Tomlinson Middle School
15. Fairfield Ludlowe High School
16. Fairfield Warde High School
17. Walter Fitzgerald Campus

For reference purposes, the following four (4) school buildings have active radon mitigation systems in place:

- Riverfield Elementary School – Room CC-29 Gym Office, Rooms 30, 32, and 34
- Fairfield Ludlowe High School – Computer Room 30
- Mill Hill Elementary School – Room 124 and Room 126 (Resource Rooms 1 and 2)
- Tomlinson Middle School – Room 171 Custodial Office and Room 173

Fairfield Public Schools was last evaluated for radon during the 2022 testing season. In addition, Riverfield Elementary School, Fairfield Ludlowe High School, Mill Hill Elementary School, and Tomlinson Middle School were evaluated for radon in February of 2025 to satisfy the mid-cycle testing requirement.

This radon testing event was conducted to satisfy the three-year testing requirement. Mid-cycle evaluations (every 1-2 years) are required for schools with active mitigation systems in place.

***Radon Testing***

On December 16-18, 2025, TRC representatives Julia Grounds, Hugh Crundwell, and Carmen Jacko, performed radon re-evaluation testing to satisfy the three-year testing requirement.

As recommended by the USEPA and the CTDPH, air re-testing in all subject facilities was conducted in 10% of the prior tested rooms as well as in rooms where any prior testing had indicated radon levels near or above the EPA/CTDPH Action Level of 4.0 pCi/L.

Testing was conducted under "closed building conditions" during the weekday period of the colder months of the year and with the buildings occupied and the HVAC systems operating normally. Air testing was conducted using short-term (2-day), 4" open faced, activated charcoal (AC) adsorption canisters in accordance with the CTDPH guidance documents *Radon Testing in Connecticut Schools, November 2005* and *Radon Re-evaluation in Public Schools Circular Letter, November 2010*, as well as USEPA guidance documents *Radon Measurement in Schools, July 1993*, *Indoor Radon and Radon Decay Product Measurement Device Protocols, July 1992* and ANSI/AARST *Protocol for Conducting Measurements of Radon and Radon Decay Products in Schools and Large Buildings, 2014*.

Sample collection, placement and retrieval were conducted under the direction of TRC personnel certified as Residential Measurement Providers (RMP) (#103081RT) by the American Association of Radon Scientists and Technologists (AARST) National Radon Proficiency Program (NRPP) and accredited under the CTDPH Radon Testing in Connecticut Schools training program. All air samples were then returned to TRC's AARST NRPP certified Analytical Laboratory (#102266AL) for analysis utilizing a gamma scintillation spectroscopy system.

The results of this radon re-evaluation were acceptable and below the EPA/CTDPH Action Level of 4.0 pCi/L, with the exception of Room 127 (5.0 pCi/L) at Fairfield Ludlowe High School. On January 12-14, 2026, TRC representative Cole Bova conducted re-testing in Room 127 as well as adjacent rooms at Fairfield Ludlowe High School. Re-test results in Room 127 (6.9 and 6.1 piC/L) were confirmed to be above the EPA/CTDPH Action Level.

Since airborne radon concentrations above the USEPA Action Level of 4.0 pCi/L were identified in Room 127 at Fairfield Ludlowe High School, the installation of a radon mitigation system is required along with follow-up re-testing to verify the effectiveness of the radon mitigation system.

Per CTDPH requirements, all school buildings will require re-evaluation every 3 years. In addition, rooms with active radon mitigation systems in place (Riverfield Elementary School, Fairfield Ludlowe High School, Mill Hill Elementary School, and Tomlinson Middle School) will require a mid-cycle evaluation every 1-2 years to verify the effectiveness of the radon mitigation systems.

Refer to *Attachment A* for the RMP and lab certifications.

Refer to *Attachment B* for the radon laboratory analytical reports.

Refer to *Attachment C* for the CTDPH Radon Re-Evaluation Report Forms.

Thank you for the opportunity to be of service to Fairfield Public Schools. If you have any questions or require additional information, please contact me at 860-937-4370 or via e-mail at emarques@trccompanies.com

Sincerely,

**TRC**



Eduardo Miguel Marques
Project Manager
Safety & Industrial Hygiene



Gregory Kaczynski
Senior Project Manager
Safety & Industrial Hygiene



Kathleen Williamson
NRPP Radon Measurement Professional
(#103081RT)

# Attachment A

# Radon Laboratory Accreditations

# Kathleen Williamson

## TRC Environmental Corporation

Has satisfactorily fulfilled the requirements set forth by the
National Radon Proficiency Program and is therefore certified as a:

## Analytical Laboratory

NRPP ID 102266-AL
Issued On: 2018-03-06  Expires: 2026-03-31

Valid for specific activities or measurement devices, which can be verified with NRPP. State and local agencies may have additional requirements.




In witness Whereof,
I have subscribed my name as a
Representative of NRPP

Ashley Falco
Chair, Certification Council

# THE NATIONAL RADON SAFETY BOARD

Certified Radon Professionals

Certifies that

## *TRC Environmental Corporation*

*21 Griffin Road North Windsor, CT 06095*

Has Successfully Met The Established & Published Requirements for Accreditation
by The National Radon Safety Board as an

# Accredited Radon Laboratory

**23ARL006**

Certification Number

**12/30/2027**

Expiration Date

National Radon Safety Board
NRSB
Certified Radon Professionals

National Radon Safety Board
NRSB
Certified Radon Professionals

*This certificate is the property of The National Radon Safety Board*

# Attachment B

# Radon Laboratory Analytical Reports

Industrial Hygiene Laboratory
21 Griffin Road North
Windsor, CT 06095
(860) 298-6308

# RADON ANALYSIS REPORT

CLIENT: Fairfield Public Schools

Site: Tomlinson Middle School, 200 Unquowa Road, Fairfield, CT
Project #: 685659.0000.0000
Lab #: 68685
Date Received: 12/19/2025
Date Analyzed: 12/19/2025

| Room# / Name | Canister # | Start Date | Start Time | Stop Date | Stop Time | Result (pCi/L) |
|---|---|---|---|---|---|---|
| Rm 171 | 130F | 12/16/2025 | 10:40 | 12/18/2025 | 11:03 | 2.1 |
| Rm 171 (duplicate) | 358D | 12/16/2025 | 10:40 | 12/18/2025 | 11:03 | 2.1 |
| Rm 173 | 318D | 12/16/2025 | 10:41 | 12/18/2025 | 11:04 | 1.1 |
| Rm 173 (field blank) | 185D | 12/16/2025 | 10:41 | 12/18/2025 | 11:04 | ND< 0.5 |
| Rm 166 | 435C | 12/16/2025 | 10:42 | 12/18/2025 | 11:08 | 1.0 |
| Rm 157 | 276D | 12/16/2025 | 10:46 | 12/18/2025 | 11:10 | 1.3 |
| Rm 032 | 62F | 12/16/2025 | 10:48 | 12/18/2025 | 11:12 | 0.8 |
| Rm 013 | 338D | 12/16/2025 | 10:50 | 12/18/2025 | 11:14 | 2.1 |
| Rm 018 | 339C | 12/16/2025 | 10:52 | 12/18/2025 | 11:16 | 1.9 |
| Rm 001 | 58F | 12/16/2025 | 10:53 | 12/18/2025 | 11:18 | 1.0 |

Results relate only to samples tested, as received by the laboratory.

The counting uncertainty is +/-0.2 pCi/L

This laboratory utilizes gamma scintillation spectroscopy to analyze activated charcoal (AC) canisters following USEPA Indoor Radon and Radon Decay Product Measurement Device Protocols, July 1992. The United States Environmental Protection Agency has set a CONTINUOUS EXPOSURE Action Level of 4 pCi/l as a guidance level at which further testing and/or remedial actions are indicated. Consult your testing laboratory or State Health Department for further information

Analyzed by _____
Kathleen Williamson, Laboratory Manager

Reviewed by _____
Kathleen Williamson, Laboratory Manager
or other approved signatory

Date Issued: 12/22/2025

# DEVICE PLACEMENT LOG

Project: Fairfield PS TOMLINSON MIDDLE SCHOOL
Client:
Site: 200 Unquowa Rd, Fairfield
Project #: 685659

Lab #: 68685
Relinquished by: Hugh Crundwell
Received by: 12/19/25 KW 0930

| Room# / Name | Location | Sample ID # | Canister # | Start Date | Start Time | Stop Date | Stop Time | Date Analyzed | Time Analyzed | Initial Wt | Final Wt | Gross Counts | Result (pCi/L) |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Rm 171 | On top of fridge | 1 | 130F | 12/16/2025 | 10:40 | 12/18/2025 | 11:03 | 12/19/2025 | 10:07 | 159.4 | 160.3 | 2829 | 2.1 |
| Rm 171 (duplicate) | On top of fridge | 2 | 358D | 12/16/2025 | 10:40 | 12/18/2025 | 11:03 | 12/19/2025 | 10:18 | 160.8 | 161.9 | 2721 | 2.1 |
| Rm 173 | On top of cabinet | 3 | 318D | 12/16/2025 | 10:41 | 12/18/2025 | 11:04 | 12/19/2025 | 10:28 | 160.3 | 161.1 | 1999 | 1.1 |
| Rm 173 (field blank) | On top of shelf | 4 | 185D | 12/16/2025 | 10:41 | 12/18/2025 | 11:04 | 12/19/2025 | 10:39 | 163.7 | 164.3 | 1147 | 0.1 |
| Rm 166 | On top of shelf | 5 | 435C | 12/16/2025 | 10:42 | 12/18/2025 | 11:08 | 12/19/2025 | 10:49 | 163 | 164.1 | 1892 | 1.0 |
| Rm 157 | On top of table | 6 | 276D | 12/16/2025 | 10:46 | 12/18/2025 | 11:10 | 12/19/2025 | 10:59 | 160.1 | 161.4 | 2078 | 1.3 |
| Rm 032 | On top of cabinet | 7 | 62F | 12/16/2025 | 10:48 | 12/18/2025 | 11:12 | 12/19/2025 | 11:10 | 159.6 | 160.5 | 1717 | 0.8 |
| Rm 013 | On top of cabinet | 8 | 338D | 12/16/2025 | 10:50 | 12/18/2025 | 11:14 | 12/19/2025 | 11:21 | 160.4 | 161.5 | 2745 | 2.1 |
| Rm 018 | On top of cabinet | 9 | 339C | 12/16/2025 | 10:52 | 12/18/2025 | 11:16 | 12/19/2025 | 11:31 | 164.3 | 165.1 | 2602 | 1.9 |
| Rm 001 | On top of cabinets | 10 | 58F | 12/16/2025 | 10:53 | 12/18/2025 | 11:18 | 12/19/2025 | 11:42 | 159.3 | 160.5 | 1826 | 1.0 |

# DEVICE PLACEMENT LOG

Project: Fairfield PS TOMLINSON MIDDLE SCHOOL
Client:
Site: 200 Unquowa Rd, Fairfield
Project #: 685659

Lab #: 68685
Relinquished by: Hugh Crundwell
Received by: 12/19/25 KW 0930

| Room# / Name | Location | Sample ID # | Canister # | Start Date | Start Time | Stop Date | Stop Time | Date Analyzed | Time Analyzed | Initial Wt | Final Wt | Gross Counts | Result (pCi/L) |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Rm 171 | On top of fridge | 1 | 130F | 12/16/2025 | 10:40 | 12/18/2025 | 11:03 | | | | | | #N/A |
| Rm 171 (duplicate) | On top of fridge | 2 | 358D | 12/16/2025 | 10:40 | 12/18/2025 | 11:03 | | | | | | #N/A |
| Rm 173 | On top of cabinet | 3 | 318D | 12/16/2025 | 10:41 | 12/18/2025 | 11:04 | | | | | | #N/A |
| Rm 173 (field blank) | On top of shelf | 4 | 185D | 12/16/2025 | 10:41 | 12/18/2025 | 11:04 | | | | | | #N/A |
| Rm 166 | On top of shelf | 5 | 435C | 12/16/2025 | 10:42 | 12/18/2025 | 11:08 | | | | | | #N/A |
| Rm 157 | On top of table | 6 | 276D | 12/16/2025 | 10:46 | 12/18/2025 | 11:10 | | | | | | #N/A |
| Rm 032 | On top of cabinet | 7 | 62F | 12/16/2025 | 10:48 | 12/18/2025 | 11:12 | | | | | | #N/A |
| Rm 013 | On top of cabinet | 8 | 338D | 12/16/2025 | 10:50 | 12/18/2025 | 11:14 | | | | | | #N/A |
| Rm 018 | On top of cabinet | 9 | 339C | 12/16/2025 | 10:52 | 12/18/2025 | 11:16 | | | | | | #N/A |
| Rm 001 | On top of cabinets | 10 | 58F | 12/16/2025 | 10:53 | 12/18/2025 | 11:18 | | | | | | #N/A |

Industrial Hygiene Laboratory
21 Griffin Road North
Windsor, CT 06095
(860) 298-6308

# RADON ANALYSIS REPORT

CLIENT: Fairfield Public Schools

Site: Roger Sherman Elementary School, 250 Fern Street, Fairfield, CT
Project #: 685659.0000.0000
Lab #: 68686
Date Received: 12/19/2025
Date Analyzed: 12/19/2025

| Room# / Name | Canister # | Start Date | Start Time | Stop Date | Stop Time | Result (pCi/L) |
|---|---|---|---|---|---|---|
| Main Office | 111F | 12/16/2025 | 11:17 | 12/18/2025 | 11:40 | 1.0 |
| Main Office (duplicate) | 245D | 12/16/2025 | 11:17 | 12/18/2025 | 11:40 | 0.9 |
| Room 1 | 248D | 12/16/2025 | 11:19 | 12/18/2025 | 11:42 | 0.9 |
| Room 1 (field blank) | 125F | 12/16/2025 | 11:19 | 12/18/2025 | 11:42 | ND< 0.5 |
| Room 6 | 422C | 12/16/2025 | 11:21 | 12/18/2025 | 11:50 | 1.5 |
| Rm 10 | 3147 | 12/16/2025 | 11:22 | 12/18/2025 | 11:54 | 2.1 |

Results relate only to samples tested, as received by the laboratory.

The counting uncertainty is +/-0.2 pCi/L

This laboratory utilizes gamma scintillation spectroscopy to analyze activated charcoal (AC) canisters following USEPA Indoor Radon and Radon Decay Product Measurement Device Protocols, July 1992. The United States Environmental Protection Agency has set a CONTINUOUS EXPOSURE Action Level of 4 pCi/l as a guidance level at which further testing and/or remedial actions are indicated. Consult your testing laboratory or State Health Department for further information

Analyzed by _____
Kathleen Williamson, Laboratory Manager

Reviewed by _____
Kathleen Williamson, Laboratory Manager
or other approved signatory

Date Issued: 12/22/2025

# DEVICE PLACEMENT LOG

Project: Fairfield PS Roger Sherman Elementary School
Client:
Site: 250 Fern St Fairfield CT
Project #: 685659

Lab #: 68686
Relinquished by: Hugh Crundwell
Received by: 12/19/25 KW 0930

| Room# / Name | Location | Sample ID # | Canister # | Start Date | Start Time | Stop Date | Stop Time | Date Analyzed | Time Analyzed | Initial Wt | Final Wt | Gross Counts | Result (pCi/L) |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Main Office | On top of cabinet | 1 | 111F | 12/16/2025 | 11:17 | 12/18/2025 | 11:40 | 12/19/2025 | 11:52 | 159.8 | 160.5 | 1860 | 1.0 |
| Main Office (duplicate) | On top of cabinet | 2 | 245D | 12/16/2025 | 11:17 | 12/18/2025 | 11:40 | 12/19/2025 | 12:03 | 161 | 161.8 | 1807 | 0.9 |
| Room 1 | On top of cabinet | 3 | 248D | 12/16/2025 | 11:19 | 12/18/2025 | 11:42 | 12/19/2025 | 12:14 | 160.7 | 161.7 | 1771 | 0.9 |
| Room 1 (field blank) | On top of cabinet | 4 | 125F | 12/16/2025 | 11:19 | 12/18/2025 | 11:42 | 12/19/2025 | 12:24 | 160.5 | 161 | 1159 | 0.1 |
| Room 6 | On top of cabinet | 5 | 422C | 12/16/2025 | 11:21 | 12/18/2025 | 11:50 | 12/19/2025 | 12:35 | 162.2 | 163.4 | 2241 | 1.5 |
| Rm 10 | On top of cabinet | 6 | 3147 | 12/16/2025 | 11:22 | 12/18/2025 | 11:54 | 12/19/2025 | 12:45 | 157.2 | 158.9 | 2623 | 2.1 |

# DEVICE PLACEMENT LOG

Project: Fairfield PS Roger Sherman Elementary School
Client:
Site: 250 Fern St Fairfield CT
Project #: 685659

Lab #: 68686
Relinquished by: Hugh Crundwell
Received by: 12/19/25 KW 0930

| Room# / Name | Location | Sample ID # | Canister # | Start Date | Start Time | Stop Date | Stop Time | Date Analyzed | Time Analyzed | Initial Wt | Final Wt | Gross Counts | Result (pCi/L) |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Main Office | On top of cabinet | 1 | 111F | 12/16/2025 | 11:17 | 12/18/2025 | 11:40 | | | | | | #N/A |
| Main Office (duplicate) | On top of cabinet | 2 | 245D | 12/16/2025 | 11:17 | 12/18/2025 | 11:40 | | | | | | #N/A |
| Room 1 | On top of cabinet | 3 | 248D | 12/16/2025 | 11:19 | 12/18/2025 | 11:42 | | | | | | #N/A |
| Room 1 (field blank) | On top of cabinet | 4 | 125F | 12/16/2025 | 11:19 | 12/18/2025 | 11:42 | | | | | | #N/A |
| Room 6 | On top of cabinet | 5 | 422C | 12/16/2025 | 11:21 | 12/18/2025 | 11:50 | | | | | | #N/A |
| Rm 10 | On top of cabinet | 6 | 3147 | 12/16/2025 | 11:22 | 12/18/2025 | 11:54 | | | | | | #N/A |

Industrial Hygiene Laboratory
21 Griffin Road North
Windsor, CT 06095
(860) 298-6308

# RADON ANALYSIS REPORT

CLIENT: Fairfield Public Schools

Site: Jennings Elementary School, 31 Palm Drive, Fairfield, CT
Project #: 685659.0000.0000
Lab #: 68687
Date Received: 12/19/2025
Date Analyzed: 12/19/2025

| Room# / Name | Canister # | Start Date | Start Time | Stop Date | Stop Time | Result (pCi/L) |
|---|---|---|---|---|---|---|
| Rm 3 | 149F | 12/16/2025 | 10:19 | 12/18/2025 | 12:50 | 0.7 |
| Rm 3 (duplicate) | 198B | 12/16/2025 | 10:21 | 12/18/2025 | 12:52 | 0.9 |
| Rm 6 | 22F | 12/16/2025 | 10:25 | 12/18/2025 | 12:53 | 0.7 |
| Rm 6 (field blank) | 270D | 12/16/2025 | 10:26 | 12/18/2025 | 12:55 | ND< 0.5 |
| Rm 13 | 189C | 12/16/2025 | 10:31 | 12/18/2025 | 12:56 | 1.3 |
| Rm 20 | 330D | 12/16/2025 | 10:36 | 12/18/2025 | 12:58 | 0.5 |

Results relate only to samples tested, as received by the laboratory.

The counting uncertainty is +/-0.2 pCi/L

This laboratory utilizes gamma scintillation spectroscopy to analyze activated charcoal (AC) canisters following USEPA Indoor Radon and Radon Decay Product Measurement Device Protocols, July 1992. The United States Environmental Protection Agency has set a CONTINUOUS EXPOSURE Action Level of 4 pCi/l as a guidance level at which further testing and/or remedial actions are indicated. Consult your testing laboratory or State Health Department for further information

Analyzed by _____
Kathleen Williamson, Laboratory Manager

Reviewed by _____
Kathleen Williamson, Laboratory Manager
or other approved signatory

Date Issued: 12/22/2025

# DEVICE PLACEMENT LOG

Project: Fairfield PS RadonJennings Elementary School
Client:
Site: 31 Palm Drive, Fairfield, CONNECTICUT 06825
Project #: 685659

Lab #: 68687
Relinquished by: Hugh Crundwell
Received by: 12/19/25 KW 0930

| Room# / Name | Location | Sample ID # | Canister # | Start Date | Start Time | Stop Date | Stop Time | Date Analyzed | Time Analyzed | Initial Wt | Final Wt | Gross Counts | Result (pCi/L) |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 3 | Locker area at entrance | 1 | 149F | 12/16/2025 | 10:19 | 12/18/2025 | 12:50 | 12/19/2025 | 12:56 | 159.9 | 160.8 | 1686 | 0.7 |
| 3 (duplicate) | Lover area at entrance | 2 | 198B | 12/16/2025 | 10:21 | 12/18/2025 | 12:52 | 12/19/2025 | 13:06 | 162.7 | 164 | 1779 | 0.9 |
| 6 | Ledge at front of room | 3 | 22F | 12/16/2025 | 10:25 | 12/18/2025 | 12:53 | 12/19/2025 | 13:16 | 159.4 | 160.4 | 1652 | 0.7 |
| 6 (field blank) | Ledge at front of room | 4 | 270D | 12/16/2025 | 10:26 | 12/18/2025 | 12:55 | 12/19/2025 | 13:27 | 160.2 | 160.7 | 1119 | 0.1 |
| 13 | Ledge at entrance | 5 | 189C | 12/16/2025 | 10:31 | 12/18/2025 | 12:56 | 12/19/2025 | 13:37 | 161 | 161.7 | 2182 | 1.3 |
| 20 | Cabinet | 6 | 330D | 12/16/2025 | 10:36 | 12/18/2025 | 12:58 | 12/19/2025 | 13:48 | 161.4 | 162.3 | 1491 | 0.5 |

# DEVICE PLACEMENT LOG

Project: Fairfield PS RadonJennings Elementary School
Client:
Site: 31 Palm Drive, Fairfield, CONNECTICUT 06825
Project #: 685659

Lab #: 68687
Relinquished by: Hugh Crundwell
Received by: 12/19/25 KW 0930

| Room# / Name | Location | Sample ID # | Canister # | Start Date | Start Time | Stop Date | Stop Time | Date Analyzed | Time Analyzed | Initial Wt | Final Wt | Gross Counts | Result (pCi/L) |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 3 | Locker area at entrance | 1 | 149F | 12/16/2025 | 10:19 | 12/18/2025 | 12:50 | | | | | | #N/A |
| 3 (duplicate) | Lover area at entrance | 2 | 198B | 12/16/2025 | 10:21 | 12/18/2025 | 12:52 | | | | | | #N/A |
| 6 | Ledge at front of room | 3 | 22F | 12/16/2025 | 10:25 | 12/18/2025 | 12:53 | | | | | | #N/A |
| 6 (field blank) | Ledge at front of room | 4 | 270D | 12/16/2025 | 10:26 | 12/18/2025 | 12:55 | | | | | | #N/A |
| 13 | Ledge at entrance | 5 | 189C | 12/16/2025 | 10:31 | 12/18/2025 | 12:56 | | | | | | #N/A |
| 20 | Cabinet | 6 | 330D | 12/16/2025 | 10:36 | 12/18/2025 | 12:58 | | | | | | #N/A |

Industrial Hygiene Laboratory
21 Griffin Road North
Windsor, CT 06095
(860) 298-6308

# RADON ANALYSIS REPORT

CLIENT: Fairfield Public Schools


Site: Ludlowe Middle School, 689 Unquowa Road, Fairfield, CT
Project #: 685659.0000.0000
Lab #: 68688
Date Received: 12/19/2025
Date Analyzed: 12/19/2025


| Room# / Name | Canister # | Start Date | Start Time | Stop Date | Stop Time | Result (pCi/L) |
|---|---|---|---|---|---|---|
| Rm 156 | 465C | 12/16/2025 | 10:15 | 12/18/2025 | 10:43 | 1.4 |
| Rm 156 (duplicate) | 1867 | 12/16/2025 | 10:15 | 12/18/2025 | 10:43 | 1.4 |
| Rm 140 | 156F | 12/16/2025 | 10:17 | 12/18/2025 | 10:46 | 1.0 |
| Rm 140 (field blank) | 391D | 12/16/2025 | 10:17 | 12/18/2025 | 10:47 | ND< 0.5 |
| Rm 182 | 234C | 12/16/2025 | 10:20 | 12/18/2025 | 10:50 | 1.0 |

Results relate only to samples tested, as received by the laboratory.

The counting uncertainty is +/-0.2 pCi/L

This laboratory utilizes gamma scintillation spectroscopy to analyze activated charcoal (AC) canisters following USEPA Indoor Radon and Radon Decay Product Measurement Device Protocols, July 1992. The United States Environmental Protection Agency has set a CONTINUOUS EXPOSURE Action Level of 4 pCi/l as a guidance level at which further testing and/or remedial actions are indicated. Consult your testing laboratory or State Health Department for further information

Analyzed by 
Kathleen Williamson, Laboratory Manager

Reviewed by 
Kathleen Williamson, Laboratory Manager
or other approved signatory

Date Issued: 12/22/2025

# DEVICE PLACEMENT LOG

Project: FAIRFIELD LUDLOWE MIDDLE SCHOOL
Client:
Site: 689 Unquowa Rd Fairfield
Project #: 685659

Lab #: 68688
Relinquished by: Hugh Crundwell
Received by: 12/19/25 0900 KW

| Room# / Name | Location | Sample ID # | Canister # | Start Date | Start Time | Stop Date | Stop Time | Date Analyzed | Time Analyzed | Initial Wt | Final Wt | Gross Counts | Result (pCi/L) |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Rm 156 | On shelf | 1 | 465C | 12/16/2025 | 10:15 | 12/18/2025 | 10:43 | 12/19/2025 | 9:46 | 163.6 | 164.6 | 2220 | 1.4 |
| Rm 156 (duplicate) | On shelf | 2 | 1867 | 12/16/2025 | 10:15 | 12/18/2025 | 10:43 | 12/19/2025 | 9:57 | 154.1 | 155.4 | 2149 | 1.4 |
| Rm 140 | On top of cabinet | 3 | 156F | 12/16/2025 | 10:17 | 12/18/2025 | 10:46 | 12/19/2025 | 9:15 | 159.2 | 160.2 | 1891 | 1.0 |
| Rm 140 (field blank) | On top of cabinet | 4 | 391D | 12/16/2025 | 10:17 | 12/18/2025 | 10:47 | 12/19/2025 | 9:25 | 160.6 | 161.4 | 1152 | 0.1 |
| Rm 182 | On top of shelf | 5 | 234C | 12/16/2025 | 10:20 | 12/18/2025 | 10:50 | 12/19/2025 | 9:36 | 163.1 | 163.8 | 1940 | 1.0 |

# DEVICE PLACEMENT LOG

Project: FAIRFIELD LUDLOWE MIDDLE SCHOOL
Client:
Site: 689 Unquowa Rd Fairfield
Project #: 685659

Lab #: 68688
Relinquished by: Hugh Crundwell
Received by: 12/19/25 0900 KW

| Room# / Name | Location | Sample ID # | Canister # | Start Date | Start Time | Stop Date | Stop Time | Date Analyzed | Time Analyzed | Initial Wt | Final Wt | Gross Counts | Result (pCi/L) |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Rm 156 | On shelf | 1 | 465C | 12/16/2025 | 10:15 | 12/18/2025 | 10:43 | | | | | | #N/A |
| Rm 156 (duplicate) | On shelf | 2 | 1867 | 12/16/2025 | 10:15 | 12/18/2025 | 10:43 | | | | | | #N/A |
| Rm 140 | On top of cabinet | 3 | 156F | 12/16/2025 | 10:17 | 12/18/2025 | 10:46 | | | | | | #N/A |
| Rm 140 (field blank) | On top of cabinet | 4 | 391D | 12/16/2025 | 10:17 | 12/18/2025 | 10:47 | | | | | | #N/A |
| Rm 182 | On top of shelf | 5 | 234C | 12/16/2025 | 10:20 | 12/18/2025 | 10:50 | | | | | | #N/A |

Industrial Hygiene Laboratory
21 Griffin Road North
Windsor, CT 06095
(860) 298-6308

# RADON ANALYSIS REPORT

CLIENT: Fairfield Public Schools

Site: Ludlowe High School, 785 Unquowa Road, Fairfield, CT
Project #: 685659.0000.0000
Lab #: 68689
Date Received: 12/19/2025
Date Analyzed: 12/19/2025

| Room# / Name | Canister # | Start Date | Start Time | Stop Date | Stop Time | Result (pCi/L) |
|---|---|---|---|---|---|---|
| Computer Room 30 | 55C | 12/16/2025 | 9:43 | 12/18/2025 | 10:20 | 2.5 |
| Computer Room 30 (duplicate) | 196F | 12/16/2025 | 9:43 | 12/18/2025 | 10:20 | 2.4 |
| Art Room 06 | 356C | 12/16/2025 | 9:47 | 12/18/2025 | 10:24 | 1.1 |
| Art Room 06 (field blank) | 238D | 12/16/2025 | 9:47 | 12/18/2025 | 10:24 | ND< 0.5 |
| CAD room 31 | 492C | 12/16/2025 | 9:45 | 12/18/2025 | 10:22 | 2.1 |
| Room 15 Graphics Lab | 26F | 12/16/2025 | 9:48 | 12/18/2025 | 10:25 | 1.2 |
| Band Room 107 | 27D | 12/16/2025 | 9:50 | 12/18/2025 | 10:27 | 1.0 |
| Rm 121 Orchestra | 142F | 12/16/2025 | 9:52 | 12/18/2025 | 10:29 | 0.7 |
| Rm 123 Athletic Director | 138D | 12/16/2025 | 9:54 | 12/18/2025 | 10:31 | 2.1 |
| Room 127 | 5F | 12/16/2025 | 9:56 | 12/18/2025 | 10:33 | 5.0 |
| Rm 130 Faculty Lounge | 311D | 12/16/2025 | 9:59 | 12/18/2025 | 10:36 | 0.6 |

Results relate only to samples tested, as received by the laboratory.

The counting uncertainty is +/-0.2 pCi/L

This laboratory utilizes gamma scintillation spectroscopy to analyze activated charcoal (AC) canisters following USEPA Indoor Radon and Radon Decay Product Measurement Device Protocols, July 1992. The United States Environmental Protection Agency has set a CONTINUOUS EXPOSURE Action Level of 4 pCi/l as a guidance level at which further testing and/or remedial actions are indicated. Consult your testing laboratory or State Health Department for further information

Analyzed by _____
Kathleen Williamson, Laboratory Manager

Reviewed by _____
Kathleen Williamson, Laboratory Manager
or other approved signatory

Date Issued: 12/22/2025

# DEVICE PLACEMENT LOG

Project: Fairfield PS FAIRFIELD LUDLOWE HIGH SCHOOL
Client:
Site: 785 Unquowa Rd Fairfield
Project #: 685659

Lab #: 68689
Relinquished by: Hugh Crundwell
Received by: 12/19/25 0930 KW

| Room# / Name | Location | Sample ID # | Canister # | Start Date | Start Time | Stop Date | Stop Time | Date Analyzed | Time Analyzed | Initial Wt | Final Wt | Gross Counts | Result (pCi/L) |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Computer Room 30 | On top of cabinet | 1 | 55C | 12/16/2025 | 9:43 | 12/18/2025 | 10:20 | 12/19/2025 | 14:20 | 162.8 | 163.6 | 3124 | 2.5 |
| Computer Room 30 (duplicate) | On top of cabinet | 2 | 196F | 12/16/2025 | 9:43 | 12/18/2025 | 10:20 | 12/19/2025 | 14:30 | 159.4 | 160.1 | 3059 | 2.4 |
| Art Room 06 | On top of cabinet | 3 | 356C | 12/16/2025 | 9:47 | 12/18/2025 | 10:24 | 12/19/2025 | 14:41 | 163.9 | 164.8 | 1929 | 1.1 |
| Art Room 06 (field blank) | On top of cabinet | 4 | 238D | 12/16/2025 | 9:47 | 12/18/2025 | 10:24 | 12/19/2025 | 14:51 | 160.8 | 161.5 | 1133 | 0.1 |
| CAD room 31 | On top of cabinet | 5 | 492C | 12/16/2025 | 9:45 | 12/18/2025 | 10:22 | 12/19/2025 | 15:02 | 163.9 | 164.8 | 2702 | 2.1 |
| Room 15 Graphics Lab | On top of cabinet | 6 | 26F | 12/16/2025 | 9:48 | 12/18/2025 | 10:25 | 12/19/2025 | 15:13 | 159.3 | 160.4 | 1949 | 1.2 |
| Band Room 107 | On top of cabinet | 7 | 27D | 12/16/2025 | 9:50 | 12/18/2025 | 10:27 | 12/19/2025 | 15:24 | 164.2 | 165.1 | 1818 | 1.0 |
| Rm 121 Orchestra | On top of cabinet | 8 | 142F | 12/16/2025 | 9:52 | 12/18/2025 | 10:29 | 12/19/2025 | 15:35 | 159.3 | 160.2 | 1587 | 0.7 |
| Rm 123 Athletic Director | On shelf | 9 | 138D | 12/16/2025 | 9:54 | 12/18/2025 | 10:31 | 12/19/2025 | 15:46 | 163.4 | 164.2 | 2738 | 2.1 |
| Room 127 | On top of cabinet | 10 | 5F | 12/16/2025 | 9:56 | 12/18/2025 | 10:33 | 12/19/2025 | 15:57 | 159.4 | 160.1 | 5135 | 5.0 |
| Rm 130 Faculty Lounge | On top of cabinet | 11 | 311D | 12/16/2025 | 9:59 | 12/18/2025 | 10:36 | 12/19/2025 | 16:08 | 160.4 | 161.1 | 1580 | 0.6 |

# DEVICE PLACEMENT LOG

Project: Fairfield PS FAIRFIELD LUDLOWE HIGH SCHOOL
Client:
Site: 785 Unquowa Rd Fairfield
Project #: 685659

Lab #: 68689
Relinquished by: Hugh Crundwell
Received by: 12/19/25 0930 KW

| Room# / Name | Location | Sample ID # | Canister # | Start Date | Start Time | Stop Date | Stop Time | Date Analyzed | Time Analyzed | Initial Wt | Final Wt | Gross Counts | Result (pCi/L) |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Computer Room 30 | On top of cabinet | 1 | 55C | 12/16/2025 | 9:43 | 12/18/2025 | 10:20 | | | | | | #N/A |
| Computer Room 30 (duplicate) | On top of cabinet | 2 | 196F | 12/16/2025 | 9:43 | 12/18/2025 | 10:20 | | | | | | #N/A |
| Art Room 06 | On top of cabinet | 3 | 356C | 12/16/2025 | 9:47 | 12/18/2025 | 10:24 | | | | | | #N/A |
| Art Room 06 (field blank) | On top of cabinet | 4 | 238D | 12/16/2025 | 9:47 | 12/18/2025 | 10:24 | | | | | | #N/A |
| CAD room 31 | On top of cabinet | 5 | 492C | 12/16/2025 | 9:45 | 12/18/2025 | 10:22 | | | | | | #N/A |
| Room 15 Graphics Lab | On top of cabinet | 6 | 26F | 12/16/2025 | 9:48 | 12/18/2025 | 10:25 | | | | | | #N/A |
| Band Room 107 | On top of cabinet | 7 | 27D | 12/16/2025 | 9:50 | 12/18/2025 | 10:27 | | | | | | #N/A |
| Rm 121 Orchestra | On top of cabinet | 8 | 142F | 12/16/2025 | 9:52 | 12/18/2025 | 10:29 | | | | | | #N/A |
| Rm 123 Athletic Director | On shelf | 9 | 138D | 12/16/2025 | 9:54 | 12/18/2025 | 10:31 | | | | | | #N/A |
| Room 127 | On top of cabinet | 10 | 5F | 12/16/2025 | 9:56 | 12/18/2025 | 10:33 | | | | | | #N/A |
| Rm 130 Faculty Lounge | On top of cabinet | 11 | 311D | 12/16/2025 | 9:59 | 12/18/2025 | 10:36 | | | | | | #N/A |

Industrial Hygiene Laboratory
21 Griffin Road North
Windsor, CT 06095
(860) 298-6308

# RADON ANALYSIS REPORT

CLIENT: Fairfield Public Schools

Site: Fairfield Woods Middle School, 1115 Fairfield Woods Road, Fairfield, CT
Project #: 685659.0000.0000
Lab #: 68690
Date Received: 12/19/2025
Date Analyzed: 12/20/2025

| Room# / Name | Canister # | Start Date | Start Time | Stop Date | Stop Time | Result (pCi/L) |
|---|---|---|---|---|---|---|
| Main Office | 126D | 12/16/2025 | 10:57 | 12/18/2025 | 13:10 | 0.7 |
| Main Office (field blank) | 316D | 12/16/2025 | 10:58 | 12/18/2025 | 13:10 | ND< 0.5 |
| Team Room | 355C | 12/16/2025 | 11:03 | 12/18/2025 | 13:12 | 0.6 |
| Team Room (duplicate) | 279D | 12/16/2025 | 11:04 | 12/18/2025 | 13:12 | 0.5 |
| A152 | 313D | 12/16/2025 | 11:08 | 12/18/2025 | 13:14 | 0.8 |
| 142A | 140D | 12/16/2025 | 11:13 | 12/18/2025 | 13:17 | 1.1 |
| C158 | 1462 | 12/16/2025 | 11:18 | 12/18/2025 | 13:19 | ND< 0.5 |
| B118 | 2054 | 12/16/2025 | 11:24 | 12/18/2025 | 13:20 | 0.6 |
| A159A | 116F | 12/16/2025 | 11:26 | 12/18/2025 | 13:25 | 1.0 |

Results relate only to samples tested, as received by the laboratory.

The counting uncertainty is +/-0.2 pCi/L

This laboratory utilizes gamma scintillation spectroscopy to analyze activated charcoal (AC) canisters following USEPA Indoor Radon and Radon Decay Product Measurement Device Protocols, July 1992. The United States Environmental Protection Agency has set a CONTINUOUS EXPOSURE Action Level of 4 pCi/l as a guidance level at which further testing and/or remedial actions are indicated. Consult your testing laboratory or State Health Department for further information

Analyzed by _____
Kathleen Williamson, Laboratory Manager

Reviewed by _____
Kathleen Williamson, Laboratory Manager
or other approved signatory

Date Issued: 12/22/2025

# DEVICE PLACEMENT LOG

Project: Fairfield PS RadonFairfield Woods Middle School
Client:
Site: 1115 Fairfield Woods Road, Fairfield , CONNECTICUT
Project #: 685659

Lab #: 68690
Relinquished by: Hugh Crundwell
Received by: 12/19/25 0930 KW

| Room# / Name | Location | Sample ID # | Canister # | Start Date | Start Time | Stop Date | Stop Time | Date Analyzed | Time Analyzed | Initial Wt | Final Wt | Gross Counts | Result (pCi/L) |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Main Office | Book Shelf | 1 | 126D | 12/16/2025 | 10:57 | 12/18/2025 | 13:10 | 12/20/2025 | 7:46 | 163.4 | 164.1 | 1521 | 0.7 |
| Main Office (field blank) | Book Self | 2 | 316D | 12/16/2025 | 10:58 | 12/18/2025 | 13:10 | 12/20/2025 | 7:56 | 161.6 | 162 | 1048 | 0.1 |
| Team Room | Back Table | 3 | 355C | 12/16/2025 | 11:03 | 12/18/2025 | 13:12 | 12/20/2025 | 8:07 | 164.2 | 165.2 | 1425 | 0.6 |
| Team Room (duplicate) | Back Table | 4 | 279D | 12/16/2025 | 11:04 | 12/18/2025 | 13:12 | 12/20/2025 | 8:17 | 160.5 | 161.7 | 1355 | 0.5 |
| A152 | Table | 5 | 313D | 12/16/2025 | 11:08 | 12/18/2025 | 13:14 | 12/20/2025 | 8:28 | 160.9 | 161.8 | 1579 | 0.8 |
| 142A | Refrigerator | 6 | 140D | 12/16/2025 | 11:13 | 12/18/2025 | 13:17 | 12/20/2025 | 8:38 | 162.9 | 164 | 1827 | 1.1 |
| C158 | Book Shelf at Entrance | 7 | 1462 | 12/16/2025 | 11:18 | 12/18/2025 | 13:19 | 12/20/2025 | 8:48 | 161.5 | 162.4 | 1310 | 0.4 |
| B118 | Shelf | 8 | 2054 | 12/16/2025 | 11:24 | 12/18/2025 | 13:20 | 12/20/2025 | 8:59 | 157.6 | 158.5 | 1416 | 0.6 |
| A159A | Cabinet | 9 | 116F | 12/16/2025 | 11:26 | 12/18/2025 | 13:25 | 12/20/2025 | 9:09 | 159.4 | 160.4 | 1725 | 1.0 |

# DEVICE PLACEMENT LOG

Project: Fairfield PS RadonFairfield Woods Middle School
Client:
Site: 1115 Fairfield Woods Road, Fairfield , CONNECTICUT
Project #: 685659

Lab #: 68690
Relinquished by: Hugh Crundwell
Received by: 12/19/25 0930 KW

| Room# / Name | Location | Sample ID # | Canister # | Start Date | Start Time | Stop Date | Stop Time | Date Analyzed | Time Analyzed | Initial Wt | Final Wt | Gross Counts | Result (pCi/L) |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Main Office | Book Shelf | 7 | 126D | 12/16/2025 | 10:57 | 12/18/2025 | 13:10 | | | | | | #N/A |
| Main Office (field blank) | Book Self | 8 | 316D | 12/16/2025 | 10:58 | 12/18/2025 | 13:10 | | | | | | #N/A |
| Team Room | Back Table | 9 | 355C | 12/16/2025 | 11:03 | 12/18/2025 | 13:12 | | | | | | #N/A |
| Team Room (duplicate) | Back Table | 10 | 279D | 12/16/2025 | 11:04 | 12/18/2025 | 13:12 | | | | | | #N/A |
| A152 | Table | 11 | 313D | 12/16/2025 | 11:08 | 12/18/2025 | 13:14 | | | | | | #N/A |
| 142A | Refrigerator | 12 | 140D | 12/16/2025 | 11:13 | 12/18/2025 | 13:17 | | | | | | #N/A |
| C158 | Book Shelf at Entrance | 13 | 1462 | 12/16/2025 | 11:18 | 12/18/2025 | 13:19 | | | | | | #N/A |
| B118 | Shelf | 14 | 2054 | 12/16/2025 | 11:24 | 12/18/2025 | 13:20 | | | | | | #N/A |
| A159A | Cabinet | 15 | 116F | 12/16/2025 | 11:26 | 12/18/2025 | 13:25 | | | | | | #N/A |

Industrial Hygiene Laboratory
21 Griffin Road North
Windsor, CT 06095
(860) 298-6308

# RADON ANALYSIS REPORT

CLIENT: Fairfield Public Schools

Site: Riverfield Elementary School, 1625 Mill Plain Road, Fairfield, CT
Project #: 685659.0000.0000
Lab #: 68691
Date Received: 12/19/2025
Date Analyzed: 12/20/2025

| Room# / Name | Canister # | Start Date | Start Time | Stop Date | Stop Time | Result (pCi/L) |
|---|---|---|---|---|---|---|
| Gym Office | 355B | 12/16/2025 | 9:10 | 12/18/2025 | 9:36 | 1.5 |
| Gym Office (duplicate) | 15F | 12/16/2025 | 9:10 | 12/18/2025 | 9:36 | 1.6 |
| CC-29 | 59F | 12/16/2025 | 9:12 | 12/18/2025 | 9:38 | 1.0 |
| CC-29 (field blank) | 230 | 12/16/2025 | 9:12 | 12/18/2025 | 9:38 | ND< 0.5 |
| Class 30 | 127D | 12/16/2025 | 9:14 | 12/18/2025 | 9:40 | 1.1 |
| Class 32 | 141D | 12/16/2025 | 9:15 | 12/18/2025 | 9:55 | 1.2 |
| Class 34 | 274D | 12/16/2025 | 9:16 | 12/18/2025 | 9:47 | 1.2 |
| Rm Faculty Lounge | 2114 | 12/16/2025 | 9:18 | 12/18/2025 | 9:49 | 2.9 |
| Class 2 Language Arts | 3253 | 12/16/2025 | 9:20 | 12/18/2025 | 9:50 | 2.8 |
| Class 15 | 120F | 12/16/2025 | 9:22 | 12/18/2025 | 9:54 | 1.2 |
| Main Office | 371D | 12/16/2025 | 9:26 | 12/18/2025 | 9:56 | 2.8 |

Results relate only to samples tested, as received by the laboratory.

The counting uncertainty is +/-0.2 pCi/L

This laboratory utilizes gamma scintillation spectroscopy to analyze activated charcoal (AC) canisters following USEPA Indoor Radon and Radon Decay Product Measurement Device Protocols, July 1992. The United States Environmental Protection Agency has set a CONTINUOUS EXPOSURE Action Level of 4 pCi/l as a guidance level at which further testing and/or remedial actions are indicated. Consult your testing laboratory or State Health Department for further information

Analyzed by _____
Kathleen Williamson, Laboratory Manager

Reviewed by _____
Kathleen Williamson, Laboratory Manager
or other approved signatory

Date Issued: 12/22/2025

# DEVICE PLACEMENT LOG

Project: FAIRFIELD PS-RIVERFIELD ELEMENTARY SCHOOL
Client:
Site: 1625 Mill Plain Rd, Fairfield
Project #: 685659

Lab #: 68691
Relinquished by: Hugh Crundwell
Received by: 12/19/25 0930 KW

| Room# / Name | Location | Sample ID # | Canister # | Start Date | Start Time | Stop Date | Stop Time | Date Analyzed | Time Analyzed | Initial Wt | Final Wt | Gross Counts | Result (pCi/L) |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Gym Office | On top of shelf | 1 | 355B | 12/16/2025 | 9:10 | 12/18/2025 | 9:36 | 12/20/2025 | 9:20 | 163 | 163.8 | 2060 | 1.5 |
| Gym Office (duplicate) | On top of shelf | 2 | 15F | 12/16/2025 | 9:10 | 12/18/2025 | 9:36 | 12/20/2025 | 9:30 | 159.4 | 160.4 | 2099 | 1.6 |
| CC-29 | On top of cabinet | 3 | 59F | 12/16/2025 | 9:12 | 12/18/2025 | 9:38 | 12/20/2025 | 9:41 | 159.5 | 160.2 | 1724 | 1.0 |
| CC-29 (field blank) | On top of cabinet | 4 | 230 | 12/16/2025 | 9:12 | 12/18/2025 | 9:38 | 12/20/2025 | 9:51 | 160.4 | 161.2 | 1027 | 0.0 |
| Class 30 | On top of cabinet | 5 | 127D | 12/16/2025 | 9:14 | 12/18/2025 | 9:40 | 12/20/2025 | 10:02 | 164 | 164.4 | 1801 | 1.1 |
| Class 32 | On top of cabinet | 6 | 141D | 12/16/2025 | 9:15 | 12/18/2025 | 9:55 | 12/20/2025 | 10:12 | 163.1 | 163.9 | 1820 | 1.2 |
| Class 34 | On top of cabinet | 7 | 274D | 12/16/2025 | 9:16 | 12/18/2025 | 9:47 | 12/20/2025 | 10:22 | 160.5 | 161.2 | 1887 | 1.2 |
| Rm Faculty Lounge | On top of cabinet | 8 | 2114 | 12/16/2025 | 9:18 | 12/18/2025 | 9:49 | 12/20/2025 | 10:33 | 155.3 | 157.3 | 2720 | 2.9 |
| Class 2 Language Arts | On top of cabinet | 9 | 3253 | 12/16/2025 | 9:20 | 12/18/2025 | 9:50 | 12/20/2025 | 10:43 | 160.4 | 161.5 | 2927 | 2.8 |
| Class 15 | On top of cabinet | 10 | 120F | 12/16/2025 | 9:22 | 12/18/2025 | 9:54 | 12/20/2025 | 10:53 | 159.6 | 160.3 | 1888 | 1.2 |
| Main Office | On top of cabinet | 11 | 371D | 12/16/2025 | 9:26 | 12/18/2025 | 9:56 | 12/20/2025 | 11:04 | 160.8 | 161.6 | 2985 | 2.8 |

# DEVICE PLACEMENT LOG

Project: FAIRFIELD PS-RIVERFIELD ELEMENTARY SCHOOL
Client:
Site: 1625 Mill Plain Rd, Fairfield
Project #: 685659

Lab #: 68691
Relinquished by: Hugh Crundwell
Received by: 12/19/25 0930 KW

| Room# / Name | Location | Sample ID # | Canister # | Start Date | Start Time | Stop Date | Stop Time | Date Analyzed | Time Analyzed | Initial Wt | Final Wt | Gross Counts | Result (pCi/L) |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Gym Office | On top of shelf | 1 | 355B | 12/16/2025 | 9:10 | 12/18/2025 | 9:36 | | | | | | #N/A |
| Gym Office (duplicate) | On top of shelf | 2 | 15F | 12/16/2025 | 9:10 | 12/18/2025 | 9:36 | | | | | | #N/A |
| CC-29 | On top of cabinet | 3 | 59F | 12/16/2025 | 9:12 | 12/18/2025 | 9:38 | | | | | | #N/A |
| CC-29 (field blank) | On top of cabinet | 4 | 230 | 12/16/2025 | 9:12 | 12/18/2025 | 9:38 | | | | | | #N/A |
| Class 30 | On top of cabinet | 5 | 127D | 12/16/2025 | 9:14 | 12/18/2025 | 9:40 | | | | | | #N/A |
| Class 32 | On top of cabinet | 6 | 141D | 12/16/2025 | 9:15 | 12/18/2025 | 9:55 | | | | | | #N/A |
| Class 34 | On top of cabinet | 7 | 274D | 12/16/2025 | 9:16 | 12/18/2025 | 9:47 | | | | | | #N/A |
| Rm Faculty Lounge | On top of cabinet | 8 | 2114 | 12/16/2025 | 9:18 | 12/18/2025 | 9:49 | | | | | | #N/A |
| Class 2 Language Arts | On top of cabinet | 9 | 3253 | 12/16/2025 | 9:20 | 12/18/2025 | 9:50 | | | | | | #N/A |
| Class 15 | On top of cabinet | 10 | 120F | 12/16/2025 | 9:22 | 12/18/2025 | 9:54 | | | | | | #N/A |
| Main Office | On top of cabinet | 11 | 371D | 12/16/2025 | 9:26 | 12/18/2025 | 9:56 | | | | | | #N/A |

Industrial Hygiene Laboratory
21 Griffin Road North
Windsor, CT 06095
(860) 298-6308

# RADON ANALYSIS REPORT

CLIENT: Fairfield Public Schools

Site: Mill Hill Elementary School, 6935 Mill Hill Terrace, Southport, CT
Project #: 685659.0000.0000
Lab #: 68692
Date Received: 12/19/2025
Date Analyzed: 12/20/2025

| Room# / Name | Canister # | Start Date | Start Time | Stop Date | Stop Time | Result (pCi/L) |
|---|---|---|---|---|---|---|
| Room 124 | 188F | 12/16/2025 | 11:44 | 12/18/2025 | 12:12 | 0.6 |
| Room 124 (duplicate) | 309C | 12/16/2025 | 11:44 | 12/18/2025 | 12:12 | 0.7 |
| Room 126 | 187F | 12/16/2025 | 11:46 | 12/18/2025 | 12:14 | 0.6 |
| Rm 126 (field blank) | 60F | 12/16/2025 | 11:46 | 12/18/2025 | 12:14 | ND< 0.5 |
| Faculty Work Room (copy room) | 205D | 12/16/2025 | 11:50 | 12/18/2025 | 12:16 | ND< 0.5 |
| MC 142A | 189F | 12/16/2025 | 11:52 | 12/18/2025 | 12:15 | 0.5 |
| Staff Lounge | 2055 | 12/16/2025 | 11:53 | 12/18/2025 | 12:17 | 0.5 |
| Rm 100A | 25F | 12/16/2025 | 11:54 | 12/18/2025 | 12:19 | ND< 0.5 |
| Nurses Office | 351D | 12/16/2025 | 11:55 | 12/18/2025 | 12:21 | 0.5 |
| Main Office | 175F | 12/16/2025 | 11:56 | 12/18/2025 | 12:23 | 0.5 |

Results relate only to samples tested, as received by the laboratory.

The counting uncertainty is +/-0.2 pCi/L

This laboratory utilizes gamma scintillation spectroscopy to analyze activated charcoal (AC) canisters following USEPA Indoor Radon and Radon Decay Product Measurement Device Protocols, July 1992. The United States Environmental Protection Agency has set a CONTINUOUS EXPOSURE Action Level of 4 pCi/l as a guidance level at which further testing and/or remedial actions are indicated. Consult your testing laboratory or State Health Department for further information

Analyzed by _____
Kathleen Williamson, Laboratory Manager

Reviewed by _____
Kathleen Williamson, Laboratory Manager
or other approved signatory

Date Issued: 12/22/2025

# DEVICE PLACEMENT LOG

Project: Fairfield PS MILL HILL ELEMENTARY SCHOOL
Client:
Site: 635 Mill Hill Terr, Southport CT
Project #: 685659

Lab #: 68692
Relinquished by: Hugh Crundwell
Received by: 12/19/25 0930 KW

| Room# / Name | Location | Sample ID # | Canister # | Start Date | Start Time | Stop Date | Stop Time | Date Analyzed | Time Analyzed | Initial Wt | Final Wt | Gross Counts | Result (pCi/L) |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Room 124 | On top of cabinet | 1 | 188F | 12/16/2025 | 11:44 | 12/18/2025 | 12:12 | 12/20/2025 | 11:14 | 160 | 161.2 | 1434 | 0.6 |
| Room 124 (duplicate) | On top of cabinet | 2 | 309C | 12/16/2025 | 11:44 | 12/18/2025 | 12:12 | 12/20/2025 | 11:25 | 164.3 | 165.4 | 1505 | 0.7 |
| Room 126 | On top of cabinet | 3 | 187F | 12/16/2025 | 11:46 | 12/18/2025 | 12:14 | 12/20/2025 | 11:35 | 160.9 | 161.8 | 1427 | 0.6 |
| Rm 126 (field blank) | On top of cabinet | 4 | 60F | 12/16/2025 | 11:46 | 12/18/2025 | 12:14 | 12/20/2025 | 11:46 | 159.2 | 159.9 | 1038 | 0.1 |
| Faculty Work Room (copy room) | On top of cabinet | 5 | 205D | 12/16/2025 | 11:50 | 12/18/2025 | 12:16 | 12/20/2025 | 11:56 | 160.9 | 161.9 | 1305 | 0.4 |
| MC 142A | On top of cabinet | 6 | 189F | 12/16/2025 | 11:52 | 12/18/2025 | 12:15 | 12/20/2025 | 12:07 | 159.3 | 160.3 | 1315 | 0.5 |
| Staff Lounge | On top of cabinet | 7 | 2055 | 12/16/2025 | 11:53 | 12/18/2025 | 12:17 | 12/20/2025 | 12:17 | 157.5 | 158.7 | 1301 | 0.5 |
| Rm 100A | On top of cabinet | 8 | 25F | 12/16/2025 | 11:54 | 12/18/2025 | 12:19 | 12/20/2025 | 12:27 | 159.1 | 160.2 | 1272 | 0.4 |
| Nurses Office | On top of cabinet | 9 | 351D | 12/16/2025 | 11:55 | 12/18/2025 | 12:21 | 12/20/2025 | 12:38 | 160.5 | 161.5 | 1343 | 0.5 |
| Main Offie | On top of cabinet | 10 | 175F | 12/16/2025 | 11:56 | 12/18/2025 | 12:23 | 12/20/2025 | 12:48 | 159 | 159.9 | 1343 | 0.5 |

# DEVICE PLACEMENT LOG

Project: Fairfield PS MILL HILL ELEMENTARY SCHOOL
Client:
Site: 635 Mill Hill Terr, Southport CT
Project #: 685659

Lab #: 68692
Relinquished by: Hugh Crundwell
Received by: 12/1925 0930 KW

| Room# / Name | Location | Sample ID # | Canister # | Start Date | Start Time | Stop Date | Stop Time | Date Analyzed | Time Analyzed | Initial Wt | Final Wt | Gross Counts | Result (pCi/L) |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Room 124 | On top of cabinet | 1 | 188F | 12/16/2025 | 11:44 | 12/18/2025 | 12:12 | | | | | | #N/A |
| Room 124 (duplicate) | On top of cabinet | 2 | 309C | 12/16/2025 | 11:44 | 12/18/2025 | 12:12 | | | | | | #N/A |
| Room 126 | On top of cabinet | 3 | 187F | 12/16/2025 | 11:46 | 12/18/2025 | 12:14 | | | | | | #N/A |
| Rm 126 (field blank) | On top of cabinet | 4 | 60F | 12/16/2025 | 11:46 | 12/18/2025 | 12:14 | | | | | | #N/A |
| Faculty Work Room (copy room) | On top of cabinet | 5 | 205D | 12/16/2025 | 11:50 | 12/18/2025 | 12:16 | | | | | | #N/A |
| MC 142A | On top of cabinet | 6 | 189F | 12/16/2025 | 11:52 | 12/18/2025 | 12:15 | | | | | | #N/A |
| Staff Lounge | On top of cabinet | 7 | 2055 | 12/16/2025 | 11:53 | 12/18/2025 | 12:17 | | | | | | #N/A |
| Rm 100A | On top of cabinet | 8 | 25F | 12/16/2025 | 11:54 | 12/18/2025 | 12:19 | | | | | | #N/A |
| Nurses Office | On top of cabinet | 9 | 351D | 12/16/2025 | 11:55 | 12/18/2025 | 12:21 | | | | | | #N/A |
| Main Offie | On top of cabinet | 10 | 175F | 12/16/2025 | 11:56 | 12/18/2025 | 12:23 | | | | | | #N/A |

Industrial Hygiene Laboratory
21 Griffin Road North
Windsor, CT 06095
(860) 298-6308

# RADON ANALYSIS REPORT

CLIENT: Fairfield Public Schools

Site: McKinley Elementary School, 60 Thompson St, Fairfield, CT
Project #: 685659.0000.0000
Lab #: 68694
Date Received: 12/19/2025
Date Analyzed: 12/21/2025

| Room# / Name | Canister # | Start Date | Start Time | Stop Date | Stop Time | Result (pCi/L) |
|---|---|---|---|---|---|---|
| 130 | 216D | 12/16/2025 | 14:51 | 12/18/2025 | 15:18 | 0.5 |
| 130 (field blank) | 3068 | 12/16/2025 | 14:52 | 12/18/2025 | 15:19 | ND< 0.5 |
| 130 (duplicate) | 481C | 12/16/2025 | 14:52 | 12/18/2025 | 15:19 | ND< 0.5 |
| 145 | 9D | 12/16/2025 | 14:55 | 12/18/2025 | 15:22 | ND< 0.5 |
| 174 | 437C | 12/16/2025 | 14:58 | 12/18/2025 | 15:23 | 0.5 |

Results relate only to samples tested, as received by the laboratory.

The counting uncertainty is +/-0.2 pCi/L

This laboratory utilizes gamma scintillation spectroscopy to analyze activated charcoal (AC) canisters following USEPA Indoor Radon and Radon Decay Product Measurement Device Protocols, July 1992. The United States Environmental Protection Agency has set a CONTINUOUS EXPOSURE Action Level of 4 pCi/l as a guidance level at which further testing and/or remedial actions are indicated. Consult your testing laboratory or State Health Department for further information

Analyzed by _____
Kathleen Williamson, Laboratory Manager

Reviewed by _____
Kathleen Williamson, Laboratory Manager
or other approved signatory

Date Issued: 12/22/2025

# DEVICE PLACEMENT LOG

Project: McKinley Elementary School
Client:
Site: 60 Thompson St, Fairfield, CT
Project #: 685659

Lab #: 68694
Relinquished by: Julia Grounds
Received by: 12/19/25 1400 KW

| Room# / Name | Location | Sample ID # | Canister # | Start Date | Start Time | Stop Date | Stop Time | Date Analyzed | Time Analyzed | Initial Wt | Final Wt | Gross Counts | Result (pCi/L) |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 130 | Behind kindness sign | 1 | 216D | 12/16/2025 | 14:51 | 12/18/2025 | 15:18 | | | | | | #N/A |
| 130 (field blank) | Behind kindness sign | 2 | 3068 | 12/16/2025 | 14:52 | 12/18/2025 | 15:19 | | | | | | #N/A |
| 130 (duplicate) | Behind kindness sign | 3 | 481C | 12/16/2025 | 14:52 | 12/18/2025 | 15:19 | | | | | | #N/A |
| 145 | Behind printer | 4 | 9D | 12/16/2025 | 14:55 | 12/18/2025 | 15:22 | | | | | | #N/A |
| 174 | Bookcase | 5 | 437C | 12/16/2025 | 14:58 | 12/18/2025 | 15:23 | | | | | | #N/A |

# DEVICE PLACEMENT LOG

Project: McKinley Elementary School
Client:
Site: 60 Thompson St, Fairfield, CT
Project #: 685659

Lab #: 68694
Relinquished by: Julia Grounds
Received by: 12/19/25 1400 KW

| Room# / Name | Location | Sample ID # | Canister # | Start Date | Start Time | Stop Date | Stop Time | Date Analyzed | Time Analyzed | Initial Wt | Final Wt | Gross Counts | Result (pCi/L) |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 130 | Behind kindness sign | 1 | 216D | 12/16/2025 | 14:51 | 12/18/2025 | 15:18 | 12/21/2025 | 10:48 | 161 | 162.1 | 1329 | 0.5 |
| 130 (field blank) | Behind kindness sign | 2 | 3068 | 12/16/2025 | 14:52 | 12/18/2025 | 15:19 | 12/21/2025 | 11:00 | 161.6 | 162 | 1104 | 0.1 |
| 130 (duplicate) | Behind kindness sign | 3 | 481C | 12/16/2025 | 14:52 | 12/18/2025 | 15:19 | 12/21/2025 | 11:11 | 164.3 | 165.2 | 1235 | 0.4 |
| 145 | Behind printer | 4 | 9D | 12/16/2025 | 14:55 | 12/18/2025 | 15:22 | 12/21/2025 | 11:22 | 165 | 165.8 | 1269 | 0.4 |
| 174 | Bookcase | 5 | 437C | 12/16/2025 | 14:58 | 12/18/2025 | 15:23 | 12/21/2025 | 11:33 | 164.2 | 165.2 | 1286 | 0.5 |

Industrial Hygiene Laboratory
21 Griffin Road North
Windsor, CT 06095
(860) 298-6308

# RADON ANALYSIS REPORT

CLIENT: Fairfield Public Schools

Site: Warde High School, 755 Melville Avenue, Fairfield, CT
Project #: 685659.0000.0000
Lab #: 68695
Date Received: 12/19/2025
Date Analyzed: 12/22/2025

| Room# / Name | Canister # | Start Date | Start Time | Stop Date | Stop Time | Result (pCi/L) |
|---|---|---|---|---|---|---|
| A6 | 90F | 12/16/2025 | 10:10 | 12/18/2025 | 11:07 | 0.5 |
| A6 (field blank) | 55F | 12/16/2025 | 10:11 | 12/18/2025 | 11:07 | ND< 0.5 |
| A6 (duplicate) | 131F | 12/16/2025 | 10:13 | 12/18/2025 | 11:08 | 0.5 |
| P26 | 138F | 12/16/2025 | 10:18 | 12/18/2025 | 11:10 | 0.7 |
| P33 | 143F | 12/16/2025 | 10:23 | 12/18/2025 | 11:12 | 0.9 |
| P6 | 431C | 12/16/2025 | 10:27 | 12/18/2025 | 11:14 | 0.6 |
| P12 | 300D | 12/16/2025 | 10:31 | 12/18/2025 | 11:15 | ND< 0.5 |
| Girls locker room | 3281 | 12/16/2025 | 10:38 | 12/18/2025 | 11:19 | 0.7 |
| M2 | 246D | 12/16/2025 | 10:44 | 12/18/2025 | 11:21 | 0.9 |

| Room# / Name | Canister # | Start Date | Start Time | Stop Date | Stop Time | Result (pCi/L) |
|---|---|---|---|---|---|---|
| Library | 134F | 12/16/2025 | 10:52 | 12/18/2025 | 11:24 | 0.8 |
| Library (duplicate) | 81F | 12/16/2025 | 10:53 | 12/18/2025 | 11:24 | 0.8 |
| Library | 41F | 12/16/2025 | 10:56 | 12/18/2025 | 11:26 | 0.9 |
| T36 | 4F | 12/16/2025 | 11:00 | 12/18/2025 | 11:28 | ND< 0.5 |
| F4 | 399D | 12/16/2025 | 11:04 | 12/18/2025 | 11:31 | 1.5 |
| F13 | 359C | 12/16/2025 | 11:07 | 12/18/2025 | 11:33 | 0.5 |
| T16 | 281D | 12/16/2025 | 11:11 | 12/18/2025 | 11:36 | ND< 0.5 |
| T11 | 145F | 12/16/2025 | 11:14 | 12/18/2025 | 11:37 | ND< 0.5 |
| T4 | 397D | 12/16/2025 | 11:19 | 12/18/2025 | 11:39 | ND< 0.5 |
| T30 | 76C | 12/16/2025 | 11:23 | 12/18/2025 | 11:41 | 0.7 |

Results relate only to samples tested, as received by the laboratory.

The counting uncertainty is +/-0.2 pCi/L

This laboratory utilizes gamma scintillation spectroscopy to analyze activated charcoal (AC) canisters following USEPA Indoor Radon and Radon Decay Product Measurement Device Protocols, July 1992. The United States Environmental Protection Agency has set a CONTINUOUS EXPOSURE Action Level of 4 pCi/l as a guidance level at which further testing and/or remedial actions are indicated. Consult your testing laboratory or State Health Department for further information

Analyzed by Aaliyah Walker

Aaliyah Walker, Laboratory Analyst

Reviewed by Najaat Bhuiyan

Kathleen Williamson, Laboratory Manager
or other approved signatory

Date Issued: 12/22/2025

# DEVICE PLACEMENT LOG

Project: Fairfield Warde High School
Client:
Site: 755 Melville Ave, Fairfield, CT
Project #: 685659

Lab #: 68695
Relinquished by: Julia Grounds
Received by: 12/19/25 1400 KW

| Room# / Name | Location | Sample ID # | Canister # | Start Date | Start Time | Stop Date | Stop Time | Date Analyzed | Time Analyzed | Initial Wt | Final Wt | Gross Counts | Result (pCi/L) |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| A6 | In side room | 01 | 90F | 12/16/2025 | 10:10 | 12/18/2025 | 11:07 | 12/22/2025 | 8:55 | 158.9 | 159.8 | 1206 | 0.5 |
| A6 (field blank) | In side room | 02 B | 55F | 12/16/2025 | 10:11 | 12/18/2025 | 11:07 | 12/22/2025 | 9:06 | 159.4 | 160.1 | 1054 | 0.2 |
| A6 (duplicate) | In side room | 03 D | 131F | 12/16/2025 | 10:13 | 12/18/2025 | 11:08 | 12/22/2025 | 9:17 | 160.1 | 160.6 | 1244 | 0.5 |
| P26 | On top of back blue bookshelf | 04 | 138F | 12/16/2025 | 10:18 | 12/18/2025 | 11:10 | 12/22/2025 | 9:29 | 159.3 | 160.1 | 1315 | 0.7 |
| P33 | Bookshelf by door | 05 | 143F | 12/16/2025 | 10:23 | 12/18/2025 | 11:12 | 12/22/2025 | 9:40 | 159.2 | 160.4 | 1415 | 0.9 |
| P6 | Back bookshelf | 06 | 431C | 12/16/2025 | 10:27 | 12/18/2025 | 11:14 | 12/22/2025 | 9:50 | 164.8 | 165.5 | 1272 | 0.6 |
| P12 | Filing cabinets | 07 | 300D | 12/16/2025 | 10:31 | 12/18/2025 | 11:15 | 12/22/2025 | 10:01 | 162.1 | 162.9 | 1185 | 0.4 |
| Girls locker room | On top of partition wall | 08 | 3281 | 12/16/2025 | 10:38 | 12/18/2025 | 11:19 | 12/22/2025 | 10:11 | 161.3 | 162.1 | 1327 | 0.7 |
| M2 | By trophies | 09 | 246D | 12/16/2025 | 10:44 | 12/18/2025 | 11:21 | 12/22/2025 | 10:22 | 160.5 | 161.6 | 1398 | 0.9 |
| Library | Behind librarian desk | 10 | 134F | 12/16/2025 | 10:52 | 12/18/2025 | 11:24 | 12/22/2025 | 10:32 | 160.4 | 161.3 | 1344 | 0.8 |
| Library (duplicate) | Behind librarian desk | 11 D | 81F | 12/16/2025 | 10:53 | 12/18/2025 | 11:24 | 12/22/2025 | 10:43 | 159.4 | 160.1 | 1350 | 0.8 |
| Library | Back wall top of bookshelves | 12 | 41F | 12/16/2025 | 10:56 | 12/18/2025 | 11:26 | 12/22/2025 | 10:54 | 159.2 | 160.1 | 1407 | 0.9 |
| T36 | On top of cabinets | 13 | 4F | 12/16/2025 | 11:00 | 12/18/2025 | 11:28 | 12/22/2025 | 11:04 | 160.3 | 161.4 | 1139 | 0.4 |
| F4 | Shelves by teacher desk | 14 | 399D | 12/16/2025 | 11:04 | 12/18/2025 | 11:31 | 12/22/2025 | 11:15 | 160.7 | 161.9 | 1675 | 1.5 |
| F13 | On top of back bookshelf | 15 | 359C | 12/16/2025 | 11:07 | 12/18/2025 | 11:33 | 12/22/2025 | 11:25 | 164.4 | 165.2 | 1222 | 0.5 |
| T16 | Front of room on top of shelves | 16 | 281D | 12/16/2025 | 11:11 | 12/18/2025 | 11:36 | 12/22/2025 | 11:36 | 160.9 | 161.4 | 1153 | 0.4 |
| T11 | Front bookshelf | 17 | 145F | 12/16/2025 | 11:14 | 12/18/2025 | 11:37 | 12/22/2025 | 11:46 | 159.8 | 160.9 | 1168 | 0.4 |
| T4 | Bookshelf | 18 | 397D | 12/16/2025 | 11:19 | 12/18/2025 | 11:39 | 12/22/2025 | 11:57 | 160.8 | 161.7 | 1161 | 0.4 |

# DEVICE PLACEMENT LOG

Project: Fairfield Warde High School
Client:
Site: 755 Melville Ave, Fairfield, CT
Project #: 685659

Lab #: 68695
Relinquished by: Julia Grounds
Received by: 12/19/25 1400 KW

| Room# / Name | Location | Sample ID # | Canister # | Start Date | Start Time | Stop Date | Stop Time | Date Analyzed | Time Analyzed | Initial Wt | Final Wt | Gross Counts | Result (pCi/L) |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| T30 | Back filing cabinet | 19 | 76C | 12/16/2025 | 11:23 | 12/18/2025 | 11:41 | 12/22/2025 | 12:08 | 159.5 | 160.5 | 1290 | 0.7 |

# DEVICE PLACEMENT LOG

Project: Fairfield Warde High School
Client:
Site: 755 Melville Ave, Fairfield, CT
Project #: 685659

Lab #: 68695
Relinquished by: Julia Grounds
Received by: 12/19/25 1400 KW

| Room# / Name | Location | Sample ID # | Canister # | Start Date | Start Time | Stop Date | Stop Time | Date Analyzed | Time Analyzed | Initial Wt | Final Wt | Gross Counts | Result (pCi/L) |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| A6 | In side room | 01 | 90F | 12/16/2025 | 10:10 | 12/18/2025 | 11:07 | | | | | | #N/A |
| A6 (field blank) | In side room | 02 B | 55F | 12/16/2025 | 10:11 | 12/18/2025 | 11:07 | | | | | | #N/A |
| A6 (duplicate) | In side room | 03 D | 131F | 12/16/2025 | 10:13 | 12/18/2025 | 11:08 | | | | | | #N/A |
| P26 | On top of back blue bookshelf | 04 | 138F | 12/16/2025 | 10:18 | 12/18/2025 | 11:10 | | | | | | #N/A |
| P33 | Bookshelf by door | 05 | 143F | 12/16/2025 | 10:23 | 12/18/2025 | 11:12 | | | | | | #N/A |
| P6 | Back bookshelf | 06 | 431C | 12/16/2025 | 10:27 | 12/18/2025 | 11:14 | | | | | | #N/A |
| P12 | Filing cabinets | 07 | 300D | 12/16/2025 | 10:31 | 12/18/2025 | 11:15 | | | | | | #N/A |
| Girls locker room | On top of partition wall | 08 | 3281 | 12/16/2025 | 10:38 | 12/18/2025 | 11:19 | | | | | | #N/A |
| M2 | By trophies | 09 | 246D | 12/16/2025 | 10:44 | 12/18/2025 | 11:21 | | | | | | #N/A |
| Library | Behind librarian desk | 10 | 134F | 12/16/2025 | 10:52 | 12/18/2025 | 11:24 | | | | | | #N/A |
| Library (duplicate) | Behind librarian desk | 11 D | 81F | 12/16/2025 | 10:53 | 12/18/2025 | 11:24 | | | | | | #N/A |
| Library | Back wall top of bookshelves | 12 | 41F | 12/16/2025 | 10:56 | 12/18/2025 | 11:26 | | | | | | #N/A |
| T36 | On top of cabinets | 13 | 4F | 12/16/2025 | 11:00 | 12/18/2025 | 11:28 | | | | | | #N/A |
| F4 | Shelves by teacher desk | 14 | 399D | 12/16/2025 | 11:04 | 12/18/2025 | 11:31 | | | | | | #N/A |
| F13 | On top of back bookshelf | 15 | 359C | 12/16/2025 | 11:07 | 12/18/2025 | 11:33 | | | | | | #N/A |
| T16 | Front of room on top of shelves | 16 | 281D | 12/16/2025 | 11:11 | 12/18/2025 | 11:36 | | | | | | #N/A |
| T11 | Front bookshelf | 17 | 145F | 12/16/2025 | 11:14 | 12/18/2025 | 11:37 | | | | | | #N/A |
| T4 | Bookshelf | 18 | 397D | 12/16/2025 | 11:19 | 12/18/2025 | 11:39 | | | | | | #N/A |

# DEVICE PLACEMENT LOG

Project: Fairfield Warde High School
Client:
Site: 755 Melville Ave, Fairfield, CT
Project #: 685659

Lab #: 68695
Relinquished by: Julia Grounds
Received by: 12/19/25 1400 KW

| Room# / Name | Location | Sample ID # | Canister # | Start Date | Start Time | Stop Date | Stop Time | Date Analyzed | Time Analyzed | Initial Wt | Final Wt | Gross Counts | Result (pCi/L) |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| T30 | Back filing cabinet | 19 | 76C | 12/16/2025 | 11:23 | 12/18/2025 | 11:41 | | | | | | #N/A |

Industrial Hygiene Laboratory
21 Griffin Road North
Windsor, CT 06095
(860) 298-6308

# RADON ANALYSIS REPORT

CLIENT: Fairfield Public Schools

Site: Walter Fitzerald Campus, 309 Barbary Road, Fairfield, CT
Project #: 685659.0000.0000
Lab #: 68696
Date Received: 12/19/2025
Date Analyzed: 12/21/2025

| Room# / Name | Canister # | Start Date | Start Time | Stop Date | Stop Time | Result (pCi/L) |
|---|---|---|---|---|---|---|
| 18 | 87F | 12/16/2025 | 13:17 | 12/18/2025 | 15:47 | 1.2 |
| 18 (duplicate) | 154F | 12/16/2025 | 13:18 | 12/18/2025 | 15:48 | 1.1 |
| 11 | 36F | 12/16/2025 | 13:21 | 12/18/2025 | 15:49 | 0.6 |
| 11 (field blank) | 95B | 12/16/2025 | 13:22 | 12/18/2025 | 15:49 | ND< 0.5 |
| 5 | 107F | 12/16/2025 | 13:24 | 12/18/2025 | 15:51 | 0.9 |

Results relate only to samples tested, as received by the laboratory.

The counting uncertainty is +/-0.2 pCi/L

This laboratory utilizes gamma scintillation spectroscopy to analyze activated charcoal (AC) canisters following USEPA Indoor Radon and Radon Decay Product Measurement Device Protocols, July 1992. The United States Environmental Protection Agency has set a CONTINUOUS EXPOSURE Action Level of 4 pCi/l as a guidance level at which further testing and/or remedial actions are indicated. Consult your testing laboratory or State Health Department for further information

Analyzed by _____
Kathleen Williamson, Laboratory Manager

Reviewed by _____
Kathleen Williamson, Laboratory Manager
or other approved signatory

Date Issued: 12/22/2025

# DEVICE PLACEMENT LOG

Project: Fairfield PS RadonWalter Fitzgerald Campus
Client:
Site: 309 Barbary Road, Fairfield , CONNECTICUT
Project #: 685659

Lab #: 68696
Relinquished by: Julia Grounds
Received by: 12/19/25 1400 KW

| Room# / Name | Location | Sample ID # | Canister # | Start Date | Start Time | Stop Date | Stop Time | Date Analyzed | Time Analyzed | Initial Wt | Final Wt | Gross Counts | Result (pCi/L) |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 18 | Shelf | 1 | 87F | 12/16/2025 | 13:17 | 12/18/2025 | 15:47 | | | | | | #N/A |
| 18 (duplicate) | Shep | 2 | 154F | 12/16/2025 | 13:18 | 12/18/2025 | 15:48 | | | | | | #N/A |
| 11 | Desk | 3 | 36F | 12/16/2025 | 13:21 | 12/18/2025 | 15:49 | | | | | | #N/A |
| 11 (field blank) | Desk | 4 | 95B | 12/16/2025 | 13:22 | 12/18/2025 | 15:49 | | | | | | #N/A |
| 5 | Shelf | 5 | 107F | 12/16/2025 | 13:24 | 12/18/2025 | 15:51 | | | | | | #N/A |

# DEVICE PLACEMENT LOG

Project: Fairfield PS RadonWalter Fitzgerald Campus
Client:
Site: 309 Barbary Road, Fairfield , CONNECTICUT
Project #: 685659

Lab #: 68696
Relinquished by: Julia Grounds
Received by: 12/19/25 1400 KW

| Room# / Name | Location | Sample ID # | Canister # | Start Date | Start Time | Stop Date | Stop Time | Date Analyzed | Time Analyzed | Initial Wt | Final Wt | Gross Counts | Result (pCi/L) |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 18 | Shelf | 1 | 87F | 12/16/2025 | 13:17 | 12/18/2025 | 15:47 | 12/21/2025 | 11:44 | 160 | 160.8 | 1761 | 1.2 |
| 18 (duplicate) | Shep | 2 | 154F | 12/16/2025 | 13:18 | 12/18/2025 | 15:48 | 12/21/2025 | 11:58 | 159.6 | 160.5 | 1663 | 1.1 |
| 11 | Desk | 3 | 36F | 12/16/2025 | 13:21 | 12/18/2025 | 15:49 | 12/21/2025 | 12:09 | 159.6 | 160.6 | 1384 | 0.6 |
| 11 (field blank) | Desk | 4 | 95B | 12/16/2025 | 13:22 | 12/18/2025 | 15:49 | 12/21/2025 | 12:23 | 153.1 | 153.6 | 1063 | 0.1 |
| 5 | Shelf | 5 | 107F | 12/16/2025 | 13:24 | 12/18/2025 | 15:51 | 12/21/2025 | 12:34 | 159.4 | 160.4 | 1531 | 0.9 |

Industrial Hygiene Laboratory
21 Griffin Road North
Windsor, CT 06095
(860) 298-6308

# RADON ANALYSIS REPORT

CLIENT: Fairfield Public Schools

Site: Osborn Hill Elementary School, 760 Stillson Rd, Fairfield, CT
Project #: 685659.0000.0000
Lab #: 68697
Date Received: 12/19/2025
Date Analyzed: 12/21/2025

| Room# / Name | Canister # | Start Date | Start Time | Stop Date | Stop Time | Result (pCi/L) |
|---|---|---|---|---|---|---|
| 6 | 166D | 12/16/2025 | 14:05 | 12/18/2025 | 14:50 | 1.1 |
| 6 (field blank) | 235A | 12/16/2025 | 14:06 | 12/18/2025 | 14:50 | ND< 0.5 |
| 6 (duplicate) | 97F | 12/16/2025 | 14:06 | 12/18/2025 | 14:50 | 1.0 |
| 10 | 466C | 12/16/2025 | 14:10 | 12/18/2025 | 14:53 | 1.2 |
| A3 | 109F | 12/16/2025 | 14:14 | 12/18/2025 | 14:55 | ND< 0.5 |
| 12 | 45B | 12/16/2025 | 14:18 | 12/18/2025 | 14:57 | 1.0 |
| 18 | 283D | 12/16/2025 | 14:20 | 12/18/2025 | 14:59 | 0.9 |

Results relate only to samples tested, as received by the laboratory.

The counting uncertainty is +/-0.2 pCi/L

This laboratory utilizes gamma scintillation spectroscopy to analyze activated charcoal (AC) canisters following USEPA Indoor Radon and Radon Decay Product Measurement Device Protocols, July 1992. The United States Environmental Protection Agency has set a CONTINUOUS EXPOSURE Action Level of 4 pCi/l as a guidance level at which further testing and/or remedial actions are indicated. Consult your testing laboratory or State Health Department for further information

Analyzed by _____
Kathleen Williamson, Laboratory Manager

Reviewed by _____
Kathleen Williamson, Laboratory Manager
or other approved signatory

Date Issued: 12/22/2025

# DEVICE PLACEMENT LOG

Project: Osborn Hill Elementary School
Client:
Site: 760 Stillson Rd, Fairfield, CT
Project #: 685659

Lab #: 68697
Relinquished by: Julia Grounds
Received by: 12/19/25 1400 KW

| Room# / Name | Location | Sample ID # | Canister # | Start Date | Start Time | Stop Date | Stop Time | Date Analyzed | Time Analyzed | Initial Wt | Final Wt | Gross Counts | Result (pCi/L) |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 6 | Math unit 7 box | 1 | 166D | 12/16/2025 | 14:05 | 12/18/2025 | 14:50 | | | | | | |
| 6 (field blank) | Math unit 7 box | 2 B | 235A | 12/16/2025 | 14:06 | 12/18/2025 | 14:50 | | | | | | |
| 6 (duplicate) | Math unit 7 box | 3 D | 97F | 12/16/2025 | 14:06 | 12/18/2025 | 14:50 | | | | | | |
| 10 | By door | 4 | 466C | 12/16/2025 | 14:10 | 12/18/2025 | 14:53 | | | | | | |
| A3 | By teachers desk | 5 | 109F | 12/16/2025 | 14:14 | 12/18/2025 | 14:55 | | | | | | |
| 12 | Above cabinet by door | 6 | 45B | 12/16/2025 | 14:18 | 12/18/2025 | 14:57 | | | | | | |
| 18 | Above sink | 7 | 283D | 12/16/2025 | 14:20 | 12/18/2025 | 14:59 | | | | | | |

# DEVICE PLACEMENT LOG

Project: Osborn Hill Elementary School
Client:
Site: 760 Stillson Rd, Fairfield, CT
Project #: 685659

Lab #: 68697
Relinquished by: Julia Grounds
Received by: 12/19/25 1400 KW

| Room# / Name | Location | Sample ID # | Canister # | Start Date | Start Time | Stop Date | Stop Time | Date Analyzed | Time Analyzed | Initial Wt | Final Wt | Gross Counts | Result (pCi/L) |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 6 | Math unit 7 box | 1 | 166D | 12/16/2025 | 14:05 | 12/18/2025 | 14:50 | 12/21/2025 | 12:46 | 163.1 | 164.1 | 1649 | 1.1 |
| 6 (field blank) | Math unit 7 box | 2 B | 235A | 12/16/2025 | 14:06 | 12/18/2025 | 14:50 | 12/21/2025 | 12:57 | 156.2 | 156.5 | 1070 | 0.1 |
| 6 (duplicate) | Math unit 7 box | 3 D | 97F | 12/16/2025 | 14:06 | 12/18/2025 | 14:50 | 12/21/2025 | 13:08 | 159.4 | 160.5 | 1585 | 1.0 |
| 10 | By door | 4 | 466C | 12/16/2025 | 14:10 | 12/18/2025 | 14:53 | 12/21/2025 | 13:19 | 164.1 | 165.2 | 1689 | 1.2 |
| A3 | By teachers desk | 5 | 109F | 12/16/2025 | 14:14 | 12/18/2025 | 14:55 | 12/21/2025 | 13:30 | 159.9 | 161.2 | 1239 | 0.4 |
| 12 | Above cabinet by door | 6 | 45B | 12/16/2025 | 14:18 | 12/18/2025 | 14:57 | 12/21/2025 | 13:44 | 164.1 | 165.6 | 1561 | 1.0 |
| 18 | Above sink | 7 | 283D | 12/16/2025 | 14:20 | 12/18/2025 | 14:59 | 12/21/2025 | 13:55 | 161.2 | 162.2 | 1527 | 0.9 |

Industrial Hygiene Laboratory
21 Griffin Road North
Windsor, CT 06095
(860) 298-6308

# RADON ANALYSIS REPORT

CLIENT: Fairfield Public Schools

Site: North Stratfield Elementary School, 190 Putting Green Road, Fairfield, CT
Project #: 685659.0000.0000
Lab #: 68698
Date Received: 12/19/2025
Date Analyzed: 12/22/2025

| Room# / Name | Canister # | Start Date | Start Time | Stop Date | Stop Time | Result (pCi/L) |
|---|---|---|---|---|---|---|
| 20 | 18F | 12/16/2025 | 12:03 | 12/18/2025 | 12:14 | 0.6 |
| 20 (field blank) | 23F | 12/16/2025 | 12:04 | 12/18/2025 | 12:14 | ND< 0.5 |
| 20 (duplicate) | 178C | 12/16/2025 | 12:05 | 12/18/2025 | 12:14 | 0.5 |
| 25 | 235D | 12/16/2025 | 12:10 | 12/18/2025 | 12:16 | 0.6 |
| 31 Reading | 491C | 12/16/2025 | 12:13 | 12/18/2025 | 12:18 | 0.5 |
| 4 Kindergarten | 57F | 12/16/2025 | 12:16 | 12/18/2025 | 12:19 | ND< 0.5 |
| 7 | 123F | 12/16/2025 | 12:19 | 12/18/2025 | 12:21 | ND< 0.5 |

Results relate only to samples tested, as received by the laboratory.

The counting uncertainty is +/-0.2 pCi/L

This laboratory utilizes gamma scintillation spectroscopy to analyze activated charcoal (AC) canisters following USEPA Indoor Radon and Radon Decay Product Measurement Device Protocols, July 1992. The United States Environmental Protection Agency has set a CONTINUOUS EXPOSURE Action Level of 4 pCi/l as a guidance level at which further testing and/or remedial actions are indicated. Consult your testing laboratory or State Health Department for further information

Analyzed by _____
Aaliyah Walker, Laboratory Analyst

Reviewed by _____
Kathleen Williamson, Laboratory Manager
or other approved signatory

Date Issued: 12/22/2025

# DEVICE PLACEMENT LOG

Project: North Stratfield Elementary School
Client:
Site: 190 Putting Green Road, Fairfield, CT
Project #: 685659

Lab #: 68698
Relinquished by: Julia Grounds
Received by: 12/19/25 1400 KW

| Room# / Name | Location | Sample ID # | Canister # | Start Date | Start Time | Stop Date | Stop Time | Date Analyzed | Time Analyzed | Initial Wt | Final Wt | Gross Counts | Result (pCi/L) |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 20 | Hallway Window sill | 1 | 18F | 12/16/2025 | 12:03 | 12/18/2025 | 12:14 | 12/22/2025 | 7:38 | 159.2 | 160.3 | 1275 | 0.6 |
| 20 (field blank) | Hallway window sill | 2 B | 23F | 12/16/2025 | 12:04 | 12/18/2025 | 12:14 | 12/22/2025 | 7:50 | 160.3 | 160.6 | 1064 | 0.2 |
| 20 (duplicate) | Hallway window sill | 3 D | 178C | 12/16/2025 | 12:05 | 12/18/2025 | 12:14 | 12/22/2025 | 8:01 | 161.2 | 162.3 | 1223 | 0.5 |
| 25 | By door | 4 | 235D | 12/16/2025 | 12:10 | 12/18/2025 | 12:16 | 12/22/2025 | 8:11 | 161 | 162.3 | 1257 | 0.6 |
| 31 Reading | Bookshelf wall | 5 | 491C | 12/16/2025 | 12:13 | 12/18/2025 | 12:18 | 12/22/2025 | 8:22 | 164.2 | 164.9 | 1200 | 0.5 |
| 4 Kindergarten | Partition wall | 6 | 57F | 12/16/2025 | 12:16 | 12/18/2025 | 12:19 | 12/22/2025 | 8:33 | 159.6 | 160.5 | 1167 | 0.4 |
| 7 | On top of bookshelf in back of room | 7 | 123F | 12/16/2025 | 12:19 | 12/18/2025 | 12:21 | 12/22/2025 | 8:44 | 159.6 | 160.6 | 1183 | 0.4 |

# DEVICE PLACEMENT LOG

Project: North Stratfield Elementary School
Client:
Site: 190 Putting Green Road, Fairfield, CT
Project #: 685659

Lab #: 68698
Relinquished by: Julia Grounds
Received by: 12/19/25 1400 KW

| Room# / Name | Location | Sample ID # | Canister # | Start Date | Start Time | Stop Date | Stop Time | Date Analyzed | Time Analyzed | Initial Wt | Final Wt | Gross Counts | Result (pCi/L) |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 20 | Hallway Window sill | 1 | 18F | 12/16/2025 | 12:03 | 12/18/2025 | 12:14 | | | | | | #N/A |
| 20 (field blank) | Hallway window sill | 2 B | 23F | 12/16/2025 | 12:04 | 12/18/2025 | 12:14 | | | | | | #N/A |
| 20 (duplicate) | Hallway window sill | 3 D | 178C | 12/16/2025 | 12:05 | 12/18/2025 | 12:14 | | | | | | #N/A |
| 25 | By door | 4 | 235D | 12/16/2025 | 12:10 | 12/18/2025 | 12:16 | | | | | | #N/A |
| 31 Reading | Bookshelf wall | 5 | 491C | 12/16/2025 | 12:13 | 12/18/2025 | 12:18 | | | | | | #N/A |
| 4 Kindergarten | Partition wall | 6 | 57F | 12/16/2025 | 12:16 | 12/18/2025 | 12:19 | | | | | | #N/A |
| 7 | On top of bookshelf in back of room | 7 | 123F | 12/16/2025 | 12:19 | 12/18/2025 | 12:21 | | | | | | #N/A |

Industrial Hygiene Laboratory
21 Griffin Road North
Windsor, CT 06095
(860) 298-6308

# RADON ANALYSIS REPORT

CLIENT: Fairfield Public Schools

Site: Holland Hill Elementary School, 105 Meadowcroft Road, Fairfield, CT
Project #: 685659.0000.0000
Lab #: 68699
Date Received: 12/19/2025
Date Analyzed: 12/22/2025

| Room# / Name | Canister # | Start Date | Start Time | Stop Date | Stop Time | Result (pCi/L) |
|---|---|---|---|---|---|---|
| 5 | 46F | 12/16/2025 | 13:29 | 12/18/2025 | 14:30 | ND< 0.5 |
| 5 (field blank) | 250D | 12/16/2025 | 13:30 | 12/18/2025 | 14:30 | ND< 0.5 |
| 5 (duplicate) | 212D | 12/16/2025 | 13:31 | 12/18/2025 | 14:30 | ND< 0.5 |
| 12 | 19F | 12/16/2025 | 13:33 | 12/18/2025 | 14:32 | ND< 0.5 |
| 20 | 484C | 12/16/2025 | 13:36 | 12/18/2025 | 14:34 | 0.6 |
| 141 | 89D | 12/16/2025 | 13:38 | 12/18/2025 | 14:36 | 0.8 |

Results relate only to samples tested, as received by the laboratory.

The counting uncertainty is +/-0.2 pCi/L

This laboratory utilizes gamma scintillation spectroscopy to analyze activated charcoal (AC) canisters following USEPA Indoor Radon and Radon Decay Product Measurement Device Protocols, July 1992. The United States Environmental Protection Agency has set a CONTINUOUS EXPOSURE Action Level of 4 pCi/l as a guidance level at which further testing and/or remedial actions are indicated. Consult your testing laboratory or State Health Department for further information

Analyzed by _____
Aaliyah Walker, Laboratory Analyst

Reviewed by _____
Kathleen Williamson, Laboratory Manager
or other approved signatory

Date Issued: 12/22/2025

# DEVICE PLACEMENT LOG

Project: Holland Hill Elementary School
Client:
Site: 105 Meadowcroft Rd, Fairfield, CT
Project #: 685659

Lab #: 68699
Relinquished by: Julia Grounds
Received by: 12/19/25 1400 KW

| Room# / Name | Location | Sample ID # | Canister # | Start Date | Start Time | Stop Date | Stop Time | Date Analyzed | Time Analyzed | Initial Wt | Final Wt | Gross Counts | Result (pCi/L) |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 5 | By door | 1 | 46F | 12/16/2025 | 13:29 | 12/18/2025 | 14:30 | 12/22/2025 | 6:21 | 159.3 | 160.3 | 1162 | 0.4 |
| 5 (field blank) | By door | 2 | 250D | 12/16/2025 | 13:30 | 12/18/2025 | 14:30 | 12/22/2025 | 6:44 | 160.8 | 161.1 | 1079 | 0.2 |
| 5 (duplicate) | By door | 3 | 212D | 12/16/2025 | 13:31 | 12/18/2025 | 14:30 | 12/22/2025 | 6:55 | 160.8 | 161.9 | 1148 | 0.4 |
| 12 | By door | 4 | 19F | 12/16/2025 | 13:33 | 12/18/2025 | 14:32 | 12/22/2025 | 7:05 | 160 | 161 | 1192 | 0.4 |
| 20 | By door | 5 | 484C | 12/16/2025 | 13:36 | 12/18/2025 | 14:34 | 12/22/2025 | 7:16 | 163.9 | 164.8 | 1264 | 0.6 |
| 141 | Back filing cabinet | 6 | 89D | 12/16/2025 | 13:38 | 12/18/2025 | 14:36 | 12/22/2025 | 7:27 | 163.7 | 164.9 | 1353 | 0.8 |

# DEVICE PLACEMENT LOG

Project: Holland Hill Elementary School
Client:
Site: 105 Meadowcroft Rd, Fairfield, CT
Project #: 685659

Lab #: 68699
Relinquished by: Julia Grounds
Received by: 12/19/25 1400 KW

| Room# / Name | Location | Sample ID # | Canister # | Start Date | Start Time | Stop Date | Stop Time | Date Analyzed | Time Analyzed | Initial Wt | Final Wt | Gross Counts | Result (pCi/L) |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 5 | By door | 1 | 46F | 12/16/2025 | 13:29 | 12/18/2025 | 14:30 | | | | | | #N/A |
| 5 (field blank) | By door | 2 | 250D | 12/16/2025 | 13:30 | 12/18/2025 | 14:30 | | | | | | #N/A |
| 5 (duplicate) | By door | 3 | 212D | 12/16/2025 | 13:31 | 12/18/2025 | 14:30 | | | | | | #N/A |
| 12 | By door | 4 | 19F | 12/16/2025 | 13:33 | 12/18/2025 | 14:32 | | | | | | #N/A |
| 20 | By door | 5 | 484C | 12/16/2025 | 13:36 | 12/18/2025 | 14:34 | | | | | | #N/A |
| 141 | Back filing cabinet | 6 | 89D | 12/16/2025 | 13:38 | 12/18/2025 | 14:36 | | | | | | #N/A |

Industrial Hygiene Laboratory
21 Griffin Road North
Windsor, CT 06095
(860) 298-6308

# RADON ANALYSIS REPORT

CLIENT: Fairfield Public Schools

Site: Burr Elementary School, 196 Burr Street, Fairfield, CT
Project #: 685659.0000.0000
Lab #: 68700
Date Received: 12/19/2025
Date Analyzed: 12/22/2025

| Room# / Name | Canister # | Start Date | Start Time | Stop Date | Stop Time | Result (pCi/L) |
|---|---|---|---|---|---|---|
| 149 | 176F | 12/16/2025 | 12:39 | 12/18/2025 | 13:27 | 1.5 |
| 149 (duplicate) | 154C | 12/16/2025 | 12:40 | 12/18/2025 | 13:27 | 1.5 |
| Nurse's Office 165 | 193F | 12/16/2025 | 12:43 | 12/18/2025 | 13:29 | 1.1 |
| Nurse's Office (field blank) | 137F | 12/16/2025 | 12:44 | 12/18/2025 | 13:30 | ND< 0.5 |
| 106 | 161F | 12/16/2025 | 12:48 | 12/18/2025 | 13:32 | 1.1 |
| 116 | 94B | 12/16/2025 | 12:53 | 12/18/2025 | 13:33 | 0.9 |

Results relate only to samples tested, as received by the laboratory.

The counting uncertainty is +/-0.2 pCi/L

This laboratory utilizes gamma scintillation spectroscopy to analyze activated charcoal (AC) canisters following USEPA Indoor Radon and Radon Decay Product Measurement Device Protocols, July 1992. The United States Environmental Protection Agency has set a CONTINUOUS EXPOSURE Action Level of 4 pCi/l as a guidance level at which further testing and/or remedial actions are indicated. Consult your testing laboratory or State Health Department for further information

Analyzed by _____
Aaliyah Walker, Laboratory Analyst

Reviewed by _____
Kathleen Williamson, Laboratory Manager
or other approved signatory

Date Issued: 12/22/2025

# DEVICE PLACEMENT LOG

Project: Burr Elementary SchoolFairfield PS Radon
Client:
Site: 196 Burr Street, Fairfield , CONNECTICUT
Project #: 695659

Lab #: 68700
Relinquished by: Julia Grounds
Received by: 12/19/25 KW 1400

| Room# / Name | Location | Sample ID # | Canister # | Start Date | Start Time | Stop Date | Stop Time | Date Analyzed | Time Analyzed | Initial Wt | Final Wt | Gross Counts | Result (pCi/L) |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 149 | Mini Refrigerator | 1 | 176F | 12/16/2025 | 12:39 | 12/18/2025 | 13:27 | 12/22/2025 | 5:16 | 159.6 | 160.9 | 1732 | 1.5 |
| 149 (duplicate) | Mini Refrigerator | 2 | 154C | 12/16/2025 | 12:40 | 12/18/2025 | 13:27 | 12/22/2025 | 5:27 | 162.6 | 163.7 | 1720 | 1.5 |
| Nurse's Office 165 | Cabinet | 3 | 193F | 12/16/2025 | 12:43 | 12/18/2025 | 13:29 | 12/22/2025 | 5:37 | 159.5 | 160.4 | 1523 | 1.1 |
| Nurse's Pffice (field blank) | Cabinet | 4 | 137F | 12/16/2025 | 12:44 | 12/18/2025 | 13:30 | 12/22/2025 | 5:48 | 160.6 | 161 | 1036 | 0.1 |
| 106 | Shelf at Entrance | 5 | 161F | 12/16/2025 | 12:48 | 12/18/2025 | 13:32 | 12/22/2025 | 5:59 | 159.7 | 160.6 | 1543 | 1.1 |
| 116 | Ledge at Entrance | 6 | 94B | 12/16/2025 | 12:53 | 12/18/2025 | 13:33 | 12/22/2025 | 6:10 | 162.7 | 163.8 | 1434 | 0.9 |

# DEVICE PLACEMENT LOG

Project: Burr Elementary SchoolFairfield PS Radon
Client:
Site: 196 Burr Street, Fairfield , CONNECTICUT
Project #: 695659

Lab #: 68700
Relinquished by: Julia Grounds
Received by: 12/19/25 KW 1400

| Room# / Name | Location | Sample ID # | Canister # | Start Date | Start Time | Stop Date | Stop Time | Date Analyzed | Time Analyzed | Initial Wt | Final Wt | Gross Counts | Result (pCi/L) |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 149 | Mini Refrigerator | 1 | 176F | 12/16/2025 | 12:39 | 12/18/2025 | 13:27 | | | | | | #N/A |
| 149 (duplicate) | Mini Refrigerator | 2 | 154C | 12/16/2025 | 12:40 | 12/18/2025 | 13:27 | | | | | | #N/A |
| Nurse's Office 165 | Cabinet | 3 | 193F | 12/16/2025 | 12:43 | 12/18/2025 | 13:29 | | | | | | #N/A |
| Nurse's Pffice (field blank) | Cabinet | 4 | 137F | 12/16/2025 | 12:44 | 12/18/2025 | 13:30 | | | | | | #N/A |
| 106 | Shelf at Entrance | 5 | 161F | 12/16/2025 | 12:48 | 12/18/2025 | 13:32 | | | | | | #N/A |
| 116 | Ledge at Entrance | 6 | 94B | 12/16/2025 | 12:53 | 12/18/2025 | 13:33 | | | | | | #N/A |

Industrial Hygiene Laboratory
21 Griffin Road North
Windsor, CT 06095
(860) 298-6308

# RADON ANALYSIS REPORT

CLIENT: Fairfield Public Schools

Site: Timothy Dwight Elementary School, 1600 Redding Road, Fairfield , CT
Project #: 685659.0000.0000
Lab #: 68701
Date Received: 12/19/2025
Date Analyzed: 12/21/2025

| Room# / Name | Canister # | Start Date | Start Time | Stop Date | Stop Time | Result (pCi/L) |
|---|---|---|---|---|---|---|
| 1 | 467C | 12/16/2025 | 11:58 | 12/18/2025 | 12:53 | 0.7 |
| 1 (field blank) | 41B | 12/16/2025 | 11:58 | 12/18/2025 | 12:53 | ND< 0.5 |
| 11 | 38 F | 12/16/2025 | 12:02 | 12/18/2025 | 12:56 | 1.0 |
| 11 (duplicate) | 211D | 12/16/2025 | 12:03 | 12/18/2025 | 12:56 | 0.9 |
| Faculty Lounge | 208D | 12/16/2025 | 12:07 | 12/18/2025 | 13:00 | 1.1 |
| 15 | 83D | 12/16/2025 | 12:10 | 12/18/2025 | 13:03 | 0.7 |

Results relate only to samples tested, as received by the laboratory.

The counting uncertainty is +/-0.2 pCi/L

This laboratory utilizes gamma scintillation spectroscopy to analyze activated charcoal (AC) canisters following USEPA Indoor Radon and Radon Decay Product Measurement Device Protocols, July 1992. The United States Environmental Protection Agency has set a CONTINUOUS EXPOSURE Action Level of 4 pCi/l as a guidance level at which further testing and/or remedial actions are indicated. Consult your testing laboratory or State Health Department for further information

Analyzed by _____
Kathleen Williamson, Laboratory Manager

Reviewed by _____
Kathleen Williamson, Laboratory Manager
or other approved signatory

Date Issued: 12/22/2025

# DEVICE PLACEMENT LOG

Project: Fairfield PS RadonTimothy Dwight Elementary School
Client:
Site: 1600 Redding Road, Fairfield , CONNECTICUT
Project #: 685659

Lab #: 68701
Relinquished by: Julia Grounds
Received by: 12/19/25 1400 KW

| Room# / Name | Location | Sample ID # | Canister # | Start Date | Start Time | Stop Date | Stop Time | Date Analyzed | Time Analyzed | Initial Wt | Final Wt | Gross Counts | Result (pCi/L) |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 1 | Book shelf | 16 | 467C | 12/16/2025 | 11:58 | 12/18/2025 | 12:53 | | | | | | #N/A |
| 1 (field blank) | Book shelf | 17 | 41B | 12/16/2025 | 11:58 | 12/18/2025 | 12:53 | | | | | | #N/A |
| 11 | Book shelf | 18 | 38 F | 12/16/2025 | 12:02 | 12/18/2025 | 12:56 | | | | | | #N/A |
| 11 (duplicate) | Book shelf | 19 | 211D | 12/16/2025 | 12:03 | 12/18/2025 | 12:56 | | | | | | #N/A |
| Faculty Lounge | Shelf | 20 | 208D | 12/16/2025 | 12:07 | 12/18/2025 | 13:00 | | | | | | #N/A |
| 15 | Shelf | 21 | 83D | 12/16/2025 | 12:10 | 12/18/2025 | 13:03 | | | | | | #N/A |

# DEVICE PLACEMENT LOG

Project: Fairfield PS RadonTimothy Dwight Elementary School
Client:
Site: 1600 Redding Road, Fairfield , CONNECTICUT
Project #: 685659

Lab #: 68701
Relinquished by: Julia Grounds
Received by: 12/19/25 1400 KW

| Room# / Name | Location | Sample ID # | Canister # | Start Date | Start Time | Stop Date | Stop Time | Date Analyzed | Time Analyzed | Initial Wt | Final Wt | Gross Counts | Result (pCi/L) |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| 1 | Book shelf | 16 | 467C | 12/16/2025 | 11:58 | 12/18/2025 | 12:53 | 12/21/2025 | 9:39 | 163.7 | 164.7 | 1427 | 0.7 |
| 1 (field blank) | Book shelf | 17 | 41B | 12/16/2025 | 11:58 | 12/18/2025 | 12:53 | 12/21/2025 | 9:51 | 160.8 | 161.3 | 1066 | 0.1 |
| 11 | Book shelf | 18 | 38 F | 12/16/2025 | 12:02 | 12/18/2025 | 12:56 | 12/21/2025 | 10:03 | 159.5 | 160.3 | 1592 | 1.0 |
| 11 (duplicate) | Book shelf | 19 | 211D | 12/16/2025 | 12:03 | 12/18/2025 | 12:56 | 12/21/2025 | 10:14 | 160.6 | 161.6 | 1537 | 0.9 |
| Faculty Lounge | Shelf | 20 | 208D | 12/16/2025 | 12:07 | 12/18/2025 | 13:00 | 12/21/2025 | 10:25 | 160.9 | 161.7 | 1682 | 1.1 |
| 15 | Shelf | 21 | 83D | 12/16/2025 | 12:10 | 12/18/2025 | 13:03 | 12/21/2025 | 10:36 | 163.8 | 164.6 | 1439 | 0.7 |

Industrial Hygiene Laboratory
21 Griffin Road North
Windsor, CT 06095
(860) 298-6308

# RADON ANALYSIS REPORT

CLIENT: Fairfield Public Schools

Site: Stratfield Elementary School, 1407 Melville Avenue, Fairfield, CT
Project #: 685659.0000.0000
Lab #: 68702
Date Received: 12/19/2025
Date Analyzed: 12/20/2025

| Room# / Name | Canister # | Start Date | Start Time | Stop Date | Stop Time | Result (pCi/L) |
|---|---|---|---|---|---|---|
| Media center 100A | 256C | 12/16/2025 | 12:48 | 12/18/2025 | 14:02 | 0.6 |
| Media center 100A (field blank) | 190F | 12/16/2025 | 12:49 | 12/18/2025 | 14:02 | ND< 0.5 |
| Media center 100A (duplicate) | 380B | 12/16/2025 | 12:50 | 12/18/2025 | 14:02 | 0.6 |
| Media center 100A | 85F | 12/16/2025 | 12:51 | 12/18/2025 | 14:04 | ND< 0.5 |
| Music 103 | 3058 | 12/16/2025 | 12:55 | 12/18/2025 | 14:06 | 0.5 |

Results relate only to samples tested, as received by the laboratory.

The counting uncertainty is +/-0.2 pCi/L

This laboratory utilizes gamma scintillation spectroscopy to analyze activated charcoal (AC) canisters following USEPA Indoor Radon and Radon Decay Product Measurement Device Protocols, July 1992. The United States Environmental Protection Agency has set a CONTINUOUS EXPOSURE Action Level of 4 pCi/l as a guidance level at which further testing and/or remedial actions are indicated. Consult your testing laboratory or State Health Department for further information

Analyzed by _____
Kathleen Williamson, Laboratory Manager

Reviewed by _____
Kathleen Williamson, Laboratory Manager
or other approved signatory

Date Issued: 12/22/2025

# DEVICE PLACEMENT LOG

Project: Stratfield Elementary School
Client:
Site: 1407 Melville Ave, Fairfield, CT
Project #: 685659

Lab #: 68702
Relinquished by: Julia Grounds
Received by: 12/19/25 1400 KW

| Room# / Name | Location | Sample ID # | Canister # | Start Date | Start Time | Stop Date | Stop Time | Date Analyzed | Time Analyzed | Initial Wt | Final Wt | Gross Counts | Result (pCi/L) |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Media center 100A | Bookshelf by desk | 01 | 256C | 12/16/2025 | 12:48 | 12/18/2025 | 14:02 | 12/20/2025 | 12:59 | 162.5 | 163.3 | 1421 | 0.6 |
| Media center 100A (field blank) | Bookshelf by desk | 2 B | 190F | 12/16/2025 | 12:49 | 12/18/2025 | 14:02 | 12/20/2025 | 13:09 | 159.6 | 159.9 | 1062 | 0.1 |
| Media center 100A (duplicate) | Bookshelf by desk | 3 D | 380B | 12/16/2025 | 12:50 | 12/18/2025 | 14:02 | 12/20/2025 | 13:19 | 162 | 163 | 1392 | 0.6 |
| Media center 100A | By librarian desk | 4 | 85F | 12/16/2025 | 12:51 | 12/18/2025 | 14:04 | 12/20/2025 | 13:30 | 159.3 | 160.2 | 1286 | 0.4 |
| Music 103 | Back corner cabinet | 5 | 3058 | 12/16/2025 | 12:55 | 12/18/2025 | 14:06 | 12/20/2025 | 13:40 | 157.4 | 158.8 | 1328 | 0.5 |

# DEVICE PLACEMENT LOG

Project: Stratfield Elementary School
Client:
Site: 1407 Melville Ave, Fairfield, CT
Project #: 685659

Lab #: 68702
Relinquished by: Julia Grounds
Received by: 12/19/25 1400 KW

| Room# / Name | Location | Sample ID # | Canister # | Start Date | Start Time | Stop Date | Stop Time | Date Analyzed | Time Analyzed | Initial Wt | Final Wt | Gross Counts | Result (pCi/L) |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Media center 100A | Bookshelf by desk | 01 | 256C | 12/16/2025 | 12:48 | 12/18/2025 | 14:02 | | | | | | #N/A |
| Media center 100A (field blank) | Bookshelf by desk | 2 B | 190F | 12/16/2025 | 12:49 | 12/18/2025 | 14:02 | | | | | | #N/A |
| Media center 100A (duplicate) | Bookshelf by desk | 3 D | 380B | 12/16/2025 | 12:50 | 12/18/2025 | 14:02 | | | | | | #N/A |
| Media center 100A | By librarian desk | 4 | 85F | 12/16/2025 | 12:51 | 12/18/2025 | 14:04 | | | | | | #N/A |
| Music 103 | Back corner cabinet | 5 | 3058 | 12/16/2025 | 12:55 | 12/18/2025 | 14:06 | | | | | | #N/A |

Industrial Hygiene Laboratory
21 Griffin Road North
Windsor, CT 06095
(860) 298-6308

# RADON ANALYSIS REPORT

CLIENT: Fairfield Public Schools


Site: Ludlowe High School, 785 Unquowa Road, Fairfield, CT
Project #: 685659.0000.0000
Lab #: 68806
Date Received: 01/14/2026
Date Analyzed: 01/14/2026


| Room# / Name | Canister # | Start Date | Start Time | Stop Date | Stop Time | Result (pCi/L) |
|---|---|---|---|---|---|---|
| Room 127 | 25-138 | 1/12/2026 | 9:16 | 1/14/2026 | 9:29 | 6.9 |
| Room 127- Duplicate | 75D | 1/12/2026 | 9:16 | 1/14/2026 | 9:29 | 6.1 |
| Room 127B | 343D | 1/12/2026 | 9:18 | 1/14/2026 | 9:30 | 2.1 |
| Room 126 | 25-31 | 1/12/2026 | 9:21 | 1/14/2026 | 9:33 | 1.0 |
| Room 126- Field Blank | 25-135 | 1/12/2026 | 9:22 | 1/14/2026 | 9:33 | ND< 0.5 |
| Room 125 | 25-132 | 1/12/2026 | 9:24 | 1/14/2026 | 9:35 | 1.1 |
| Room 129 | 239C | 1/12/2026 | 9:28 | 1/14/2026 | 9:35 | 2.4 |

Results relate only to samples tested, as received by the laboratory.

The counting uncertainty is +/-0.2 pCi/L

This laboratory utilizes gamma scintillation spectroscopy to analyze activated charcoal (AC) canisters following USEPA Indoor Radon and Radon Decay Product Measurement Device Protocols, July 1992. The United States Environmental Protection Agency has set a CONTINUOUS EXPOSURE Action Level of 4 pCi/l as a guidance level at which further testing and/or remedial actions are indicated. Consult your testing laboratory or State Health Department for further information

Analyzed by 
Kathleen Williamson, Laboratory Manager

Reviewed by 
Kathleen Williamson, Laboratory Manager
or other approved signatory

Date Issued: 01/14/2026

# DEVICE PLACEMENT LOG

Project:
Client: Fairfield Public Schools
Site: Ludlowe High School
Project #: 685659.0000.0000

Radon Log #: 68806
Relinquished by:
Received by: KW 11/14/26 1130

| Room# / Name | Location | Sample ID # | Canister # | Start Date | Start Time | Stop Date | Stop Time | Date Analyzed | Time Analyzed | Initial Wt | Final Wt | Gross Counts | Result (pCi/L) |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Room 127 | | 1 | 25-138 | 1/12/2026 | 9:16 | 1/14/2026 | 9:29 | 1/14/2026 | 13:30 | 169.4 | 170.2 | 7396 | 6.9 |
| Room 127- Duplicate | | 2 | 75D | 1/12/2026 | 9:16 | 1/14/2026 | 9:29 | 1/14/2026 | 13:41 | 163.8 | 164.6 | 6671 | 6.1 |
| Room 127B | | 3 | 343D | 1/12/2026 | 9:18 | 1/14/2026 | 9:30 | 1/14/2026 | 13:51 | 161 | 162 | 2970 | 2.1 |
| Room 126 | | 4 | 25-31 | 1/12/2026 | 9:21 | 1/14/2026 | 9:33 | 1/14/2026 | 14:01 | 169.7 | 170.4 | 2005 | 1.0 |
| Room 126- Field Blank | | 5 | 25-135 | 1/12/2026 | 9:22 | 1/14/2026 | 9:33 | 1/14/2026 | 14:12 | 169.4 | 169.5 | 1083 | 0.0 |
| Room 125 | | 6 | 25-132 | 1/12/2026 | 9:24 | 1/14/2026 | 9:35 | 1/14/2026 | 14:23 | 169.9 | 170.6 | 2037 | 1.1 |
| Room 129 | | 7 | 239C | 1/12/2026 | 9:28 | 1/14/2026 | 9:35 | 1/14/2026 | 14:33 | 160.7 | 161.5 | 3260 | 2.4 |

# DEVICE PLACEMENT LOG

Project: Fairfield Public Schools- Fairfield Ludlowe High School Re-Eval
Client: Fairfield Public Schools
Site: Fairfield, CT
Project #: 000685659

Lab #: 68806
Relinquished by:
Received by:

| Room# / Name | Location | Sample ID # | Canister # | Start Date | Start Time | Stop Date | Stop Time | Date Analyzed | Time Analyzed | Initial Wt | Final Wt | Gross Counts | Result (pCi/L) |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| Room 127 | On top of cabinet | 01 | 25-138 | 1/12/2026 | 9:16 | 1/14/2026 | 9:29 | | | | | | #N/A |
| Room 127 (duplicate) | On top of cabinet | 02 | 75D | 1/12/2026 | 9:16 | 1/14/2026 | 9:29 | | | | | | #N/A |
| Room 127B | On table | 03 | 343D | 1/12/2026 | 9:18 | 1/14/2026 | 9:30 | | | | | | #N/A |
| Room 126 | On top of cabinet | 04 | 25-31 | 1/12/2026 | 9:21 | 1/14/2026 | 9:33 | | | | | | #N/A |
| Room 126 (field blank) | On top of cabinet | 05 | 25-135 | 1/12/2026 | 9:22 | 1/14/2026 | 9:33 | | | | | | #N/A |
| Room 125 | On top of cabinet | 06 | 25-132 | 1/12/2026 | 9:24 | 1/14/2026 | 9:35 | | | | | | #N/A |
| Room 129 | On table | 07 | 239C | 1/12/2026 | 9:28 | 1/14/2026 | 9:35 | | | | | | #N/A |

# Attachment C

# CTDPH Radon Re-evaluation Report Forms

.

# STATE OF CONNECTICUT

DEPARTMENT OF PUBLIC HEALTH
RADON PROGRAM
SCHOOL RADON **RE-EVALUATION** REPORT FORM

July 2023

The following form must be submitted to the Connecticut Department of Public Health Radon Program within ten (10) business days of providing a final written report of radon measurement activities to school personnel.
**Do not send test results or other documents.**
Submit this signed form by **email** to the Radon Program at:
DPH.RadonReports@ct.gov

**Name of School:** Walter Fitzgerald Campus

**Address:**
(Street, town, zip code)
309 Barberry Road
Southport, CT 06890

**Measurement Company:** TRC Environmental Corporation

*Please provide the following summary information:*

**Dates of Testing:**
(Deployment/retrieval dates. Include confirmatory testing dates, if applicable.) December 16-18, 2025

**Total # of Rooms Tested:** 3

**Total # of Rooms Requiring Re-Testing:** 0

**Total # of Rooms Where Average Results Were at or above 4.0 pCi/L:** 0

Radon measurement activities were carried out in accordance with United States Environmental Protection Agency protocols and the Connecticut Department of Public Health Radon Program's *School Radon Testing Guidance* at the location described above.

| Kathleen Williamson/103081RT | Kathleen Williamson Digitally signed by Kathleen Williamson Date: 2026.01.19 10:27:29 -05'00' | |
|---|---|---|
| Measurement Professional / NRPP/NRSB # | Signature | Date |
| Angelus Papageorge/Executive Director of Operations | | 2/12/26 |
| School Designee / Title | Signature | Date |

*Phone: (860) 509-7300*
*Telephone Device for the Deaf (860) 509-7191*
*410 Capitol Avenue - MS # 12-RAD*
*P.O. Box 340308, Hartford, CT 06134*
*An Equal Opportunity Employer*

# STATE OF CONNECTICUT

DEPARTMENT OF PUBLIC HEALTH
RADON PROGRAM
SCHOOL RADON **RE-EVALUATION** REPORT FORM

July 2023

The following form must be submitted to the Connecticut Department of Public Health Radon Program within ten (10) business days of providing a final written report of radon measurement activities to school personnel.
**Do not send test results or other documents.**
Submit this signed form by **email** to the Radon Program at:
DPH.RadonReports@ct.gov

**Name of School:** Riverfield Elementary School

**Address:**
(Street, town, zip code)
1625 Mill Plain Road
Fairfield, CT 06824

**Measurement Company:** TRC Environmental Corporation

*Please provide the following summary information:*

**Dates of Testing:**
(Deployment/retrieval dates. Include confirmatory testing dates, if applicable.) December 16-18, 2025

**Total # of Rooms Tested:** 9

**Total # of Rooms Requiring Re-Testing:** 0

**Total # of Rooms Where Average Results Were at or above 4.0 pCi/L:** 0

Radon measurement activities were carried out in accordance with United States Environmental Protection Agency protocols and the Connecticut Department of Public Health Radon Program's *School Radon Testing Guidance* at the location described above.

| | | |
|---|---|---|
| Kathleen Williamson/103081RT | Kathleen Williamson Digitally signed by Kathleen Williamson Date: 2026.01.19 10:25:24 -05'00' | |
| Measurement Professional / NRPP/NRSB # | Signature | Date |
| Angelus Papageorge/Executive Director of Operations | | 2/12/26 |
| School Designee / Title | Signature | Date |

*Phone: (860) 509-7300*
*Telephone Device for the Deaf (860) 509-7191*
*410 Capitol Avenue - MS # 12-RAD*
*P.O. Box 340308, Hartford, CT 06134*
*An Equal Opportunity Employer*

# STATE OF CONNECTICUT

DEPARTMENT OF PUBLIC HEALTH
RADON PROGRAM
SCHOOL RADON **RE-EVALUATION** REPORT FORM

July 2023

The following form must be submitted to the Connecticut Department of Public Health Radon Program within ten (10) business days of providing a final written report of radon measurement activities to school personnel.
**Do not send test results or other documents.**
Submit this signed form by **email** to the Radon Program at:
DPH.RadonReports@ct.gov

**Name of School:** Roger Sherman Elementary School

**Address:**
(Street, town, zip code) 250 Fern Street
Fairfield, CT 06824

**Measurement Company:** TRC Environmental Corporation

*Please provide the following summary information:*

**Dates of Testing:**
(Deployment/retrieval dates. Include confirmatory testing dates, if applicable.) December 16-18, 2025

**Total # of Rooms Tested:** 4

**Total # of Rooms Requiring Re-Testing:** 0

**Total # of Rooms Where Average Results Were at or above 4.0 pCi/L:** 0

Radon measurement activities were carried out in accordance with United States Environmental Protection Agency protocols and the Connecticut Department of Public Health Radon Program's *School Radon Testing Guidance* at the location described above.

| | | |
|---|---|---|
| Kathleen Williamson/103081RT | Kathleen Williamson Digitally signed by Kathleen Williamson Date: 2026.01.19 10:26:05 -05'00' | |
| Measurement Professional / NRPP/NRSB # | Signature | Date |
| Angelus Papageorge/Executive Director of Operations | | 2/12/26 |
| School Designee / Title | Signature | Date |

*Phone: (860) 509-7300*
*Telephone Device for the Deaf (860) 509-7191*
*410 Capitol Avenue - MS # 12-RAD*
*P.O. Box 340308, Hartford, CT 06134*
*An Equal Opportunity Employer*

# STATE OF CONNECTICUT

DEPARTMENT OF PUBLIC HEALTH
RADON PROGRAM
SCHOOL RADON **RE-EVALUATION** REPORT FORM

July 2023

The following form must be submitted to the Connecticut Department of Public Health Radon Program within ten (10) business days of providing a final written report of radon measurement activities to school personnel.
**Do not send test results or other documents.**
Submit this signed form by **email** to the Radon Program at:
DPH.RadonReports@ct.gov

**Name of School:** Stratfield Elementary School

**Address:**
(Street, town, zip code)
1407 Melville Avenue
Fairfield, CT 06825

**Measurement Company:** TRC Environmental Corporation

*Please provide the following summary information:*

**Dates of Testing:**
(Deployment/retrieval dates. Include confirmatory testing dates, if applicable.) December 16-18, 2025

**Total # of Rooms Tested:** 3

**Total # of Rooms Requiring Re-Testing:** 0

**Total # of Rooms Where Average Results Were at or above 4.0 pCi/L:** 0

Radon measurement activities were carried out in accordance with United States Environmental Protection Agency protocols and the Connecticut Department of Public Health Radon Program's *School Radon Testing Guidance* at the location described above.

| | | |
|---|---|---|
| Kathleen Williamson/103081RT | Kathleen Williamson Digitally signed by Kathleen Williamson Date: 2026.01.19 10:26:30 -05'00' | |
| Measurement Professional / NRPP/NRSB # | Signature | Date |
| Angelus Papageorge/Exectutive Director of Operations | | 2/12/26 |
| School Designee / Title | Signature | Date |

*Phone: (860) 509-7300*
*Telephone Device for the Deaf (860) 509-7191*
*410 Capitol Avenue - MS # 12-RAD*
*P.O. Box 340308, Hartford, CT 06134*
*An Equal Opportunity Employer*

# STATE OF CONNECTICUT

DEPARTMENT OF PUBLIC HEALTH
RADON PROGRAM
SCHOOL RADON **RE-EVALUATION** REPORT FORM

July 2023

The following form must be submitted to the Connecticut Department of Public Health Radon Program within ten (10) business days of providing a final written report of radon measurement activities to school personnel.
**Do not send test results or other documents.**
Submit this signed form by **email** to the Radon Program at:
DPH.RadonReports@ct.gov

**Name of School:** Tomlinson Middle School

**Address:**
(Street, town, zip code) 689 Unqouwa Road
Fairfield, CT 06824

**Measurement Company:** TRC Environmental Corporation

*Please provide the following summary information:*

**Dates of Testing:**
(Deployment/retrieval dates. Include confirmatory testing dates, if applicable.) December 16-18, 2025

**Total # of Rooms Tested:** 8

**Total # of Rooms Requiring Re-Testing:** 0

**Total # of Rooms Where Average Results Were at or above 4.0 pCi/L:** 0

Radon measurement activities were carried out in accordance with United States Environmental Protection Agency protocols and the Connecticut Department of Public Health Radon Program's *School Radon Testing Guidance* at the location described above.

| | | |
|---|---|---|
| Kathleen Williamson/103081RT | Kathleen Williamson Digitally signed by Kathleen Williamson Date: 2026.01.19 10:27:06 -05'00' | |
| Measurement Professional / NRPP/NRSB # | Signature | Date |
| Angelus Papageorge/Executive Director of Operations | | 2/12/26 |
| School Designee / Title | Signature | Date |

*Phone: (860) 509-7300*
*Telephone Device for the Deaf (860) 509-7191*
*410 Capitol Avenue - MS # 12-RAD*
*P.O. Box 340308, Hartford, CT 06134*
*An Equal Opportunity Employer*

# STATE OF CONNECTICUT

DEPARTMENT OF PUBLIC HEALTH
RADON PROGRAM
SCHOOL RADON **RE-EVALUATION** REPORT FORM

July 2023

The following form must be submitted to the Connecticut Department of Public Health Radon Program within ten (10) business days of providing a final written report of radon measurement activities to school personnel.
**Do not send test results or other documents.**
Submit this signed form by **email** to the Radon Program at:
DPH.RadonReports@ct.gov

**Name of School:** Osborn Hill Elementary School

**Address:**
(Street, town, zip code)
760 Stillson Road
Fairfield, CT 06824

**Measurement Company:** TRC Environmental Corporation

*Please provide the following summary information:*

**Dates of Testing:**
(Deployment/retrieval dates. Include confirmatory testing dates, if applicable.) December 16-18, 2025

**Total # of Rooms Tested:** 5

**Total # of Rooms Requiring Re-Testing:** 0

**Total # of Rooms Where Average Results Were at or above 4.0 pCi/L:** 0

Radon measurement activities were carried out in accordance with United States Environmental Protection Agency protocols and the Connecticut Department of Public Health Radon Program's *School Radon Testing Guidance* at the location described above.

| Kathleen Williamson/103081RT | Kathleen Williamson Digitally signed by Kathleen Williamson Date: 2026.01.19 10:36:16 -05'00' | |
|---|---|---|
| Measurement Professional / NRPP/NRSB # | Signature | Date |
| Angelus Papageorge/Executive Director of Operations | | 2/12/26 |
| School Designee / Title | Signature | Date |

*Phone: (860) 509-7300*
*Telephone Device for the Deaf (860) 509-7191*
*410 Capitol Avenue - MS # 12-RAD*
*P.O. Box 340308, Hartford, CT 06134*
*An Equal Opportunity Employer*

# STATE OF CONNECTICUT

DEPARTMENT OF PUBLIC HEALTH
RADON PROGRAM
SCHOOL RADON **RE-EVALUATION** REPORT FORM

July 2023

The following form must be submitted to the Connecticut Department of Public Health Radon Program within ten (10) business days of providing a final written report of radon measurement activities to school personnel.
**Do not send test results or other documents.**
Submit this signed form by **email** to the Radon Program at:
DPH.RadonReports@ct.gov

**Name of School:** North Stratfield Elementary School

**Address:**
(Street, town, zip code) 190 Putting Green Road
Fairfield, CT 06825

**Measurement Company:** TRC Environmental Corporation

*Please provide the following summary information:*

**Dates of Testing:**
(Deployment/retrieval dates. Include confirmatory testing dates, if applicable.) December 16-18, 2025

**Total # of Rooms Tested:** 5

**Total # of Rooms Requiring Re-Testing:** 0

**Total # of Rooms Where Average Results Were at or above 4.0 pCi/L:** 0

Radon measurement activities were carried out in accordance with United States Environmental Protection Agency protocols and the Connecticut Department of Public Health Radon Program's *School Radon Testing Guidance* at the location described above.

| | | |
|---|---|---|
| Kathleen Williamson/103081RT | Kathleen Williamson Digitally signed by Kathleen Williamson Date: 2026.01.19 10:35:47 -05'00' | |
| Measurement Professional / NRPP/NRSB # | Signature | Date |
| Angelus Papageorge/Executive Director of Operations | | 2/12/26 |
| School Designee / Title | Signature | Date |

*Phone: (860) 509-7300*
*Telephone Device for the Deaf (860) 509-7191*
*410 Capitol Avenue - MS # 12-RAD*
*P.O. Box 340308, Hartford, CT 06134*
*An Equal Opportunity Employer*

# STATE OF CONNECTICUT

DEPARTMENT OF PUBLIC HEALTH
RADON PROGRAM
SCHOOL RADON **RE-EVALUATION** REPORT FORM

July 2023

The following form must be submitted to the Connecticut Department of Public Health Radon Program within ten (10) business days of providing a final written report of radon measurement activities to school personnel.
**Do not send test results or other documents.**
Submit this signed form by **email** to the Radon Program at:
DPH.RadonReports@ct.gov

**Name of School:** Mill Hill Elementary School

**Address:**
(Street, town, zip code)
635 Mill Hill Terrace
Southport, CT 06890

**Measurement Company:** TRC Environmental Corporation

*Please provide the following summary information:*

**Dates of Testing:**
(Deployment/retrieval dates. Include confirmatory testing dates, if applicable.) December 16-18, 2025

**Total # of Rooms Tested:** 8

**Total # of Rooms Requiring Re-Testing:** 0

**Total # of Rooms Where Average Results Were at or above 4.0 pCi/L:** 0

Radon measurement activities were carried out in accordance with United States Environmental Protection Agency protocols and the Connecticut Department of Public Health Radon Program's *School Radon Testing Guidance* at the location described above.

| Kathleen Williamson/103081RT | Kathleen Williamson Digitally signed by Kathleen Williamson Date: 2026.01.19 10:35:15 -05'00' | |
|---|---|---|
| Measurement Professional / NRPP/NRSB # | Signature | Date |
| Angelus Papageorge/Executive Director of Operations | | 2/12/26 |
| School Designee / Title | Signature | Date |

*Phone: (860) 509-7300*
*Telephone Device for the Deaf (860) 509-7191*
*410 Capitol Avenue - MS # 12-RAD*
*P.O. Box 340308, Hartford, CT 06134*
*An Equal Opportunity Employer*

# STATE OF CONNECTICUT

DEPARTMENT OF PUBLIC HEALTH
RADON PROGRAM
SCHOOL RADON **RE-EVALUATION** REPORT FORM

July 2023

The following form must be submitted to the Connecticut Department of Public Health Radon Program within ten (10) business days of providing a final written report of radon measurement activities to school personnel.
**Do not send test results or other documents.**
Submit this signed form by **email** to the Radon Program at:
DPH.RadonReports@ct.gov

**Name of School:** McKinley Elementary School

**Address:**
(Street, town, zip code)
60 Thompson Street
Fairfield, CT 06825

**Measurement Company:** TRC Environmental Corporation

*Please provide the following summary information:*

**Dates of Testing:**
(Deployment/retrieval dates. Include confirmatory testing dates, if applicable.) December 16-18, 2025

**Total # of Rooms Tested:** 3

**Total # of Rooms Requiring Re-Testing:** 0

**Total # of Rooms Where Average Results Were at or above 4.0 pCi/L:** 0

Radon measurement activities were carried out in accordance with United States Environmental Protection Agency protocols and the Connecticut Department of Public Health Radon Program's *School Radon Testing Guidance* at the location described above.

| Kathleen Williamson/103081RT | Kathleen Williamson Digitally signed by Kathleen Williamson Date: 2026.01.19 10:34:47 -05'00' | |
|---|---|---|
| Measurement Professional / NRPP/NRSB # | Signature | Date |
| Angelus Papageorge/Executive Director of Operations | | 2/12/26 |
| School Designee / Title | Signature | Date |

*Phone: (860) 509-7300*
*Telephone Device for the Deaf (860) 509-7191*
*410 Capitol Avenue - MS # 12-RAD*
*P.O. Box 340308, Hartford, CT 06134*
*An Equal Opportunity Employer*

# STATE OF CONNECTICUT

DEPARTMENT OF PUBLIC HEALTH
RADON PROGRAM
SCHOOL RADON **RE-EVALUATION** REPORT FORM

July 2023

The following form must be submitted to the Connecticut Department of Public Health Radon Program within ten (10) business days of providing a final written report of radon measurement activities to school personnel.
**Do not send test results or other documents.**
Submit this signed form by **email** to the Radon Program at:
DPH.RadonReports@ct.gov

**Name of School:** Fairfield Ludlowe Middle School

**Address:**
(Street, town, zip code)
689 Unquowa Road
Fairfield, CT 06824

**Measurement Company:** TRC Environmental Corporation

*Please provide the following summary information:*

**Dates of Testing:**
(Deployment/retrieval dates. Include confirmatory testing dates, if applicable.) December 16-18, 2025

**Total # of Rooms Tested:** 3

**Total # of Rooms Requiring Re-Testing:** 0

**Total # of Rooms Where Average Results Were at or above 4.0 pCi/L:** 0

Radon measurement activities were carried out in accordance with United States Environmental Protection Agency protocols and the Connecticut Department of Public Health Radon Program's *School Radon Testing Guidance* at the location described above.

| | | |
|---|---|---|
| Kathleen Williamson/103081RT | Kathleen Williamson Digitally signed by Kathleen Williamson Date: 2026.01.19 10:29:30 -05'00' | |
| Measurement Professional / NRPP/NRSB # | Signature | Date |
| Angelus Papageorge/Executive Director of Operations | | 2/12/26 |
| School Designee / Title | Signature | Date |

*Phone: (860) 509-7300*
*Telephone Device for the Deaf (860) 509-7191*
*410 Capitol Avenue - MS # 12-RAD*
*P.O. Box 340308, Hartford, CT 06134*
*An Equal Opportunity Employer*

# STATE OF CONNECTICUT

DEPARTMENT OF PUBLIC HEALTH
RADON PROGRAM
SCHOOL RADON **RE-EVALUATION** REPORT FORM

July 2023

The following form must be submitted to the Connecticut Department of Public Health Radon Program within ten (10) business days of providing a final written report of radon measurement activities to school personnel.
**Do not send test results or other documents.**
Submit this signed form by **email** to the Radon Program at:
DPH.RadonReports@ct.gov

**Name of School:** Fairfield Warde High School

**Address:**
(Street, town, zip code) 755 Melville Avenue
Fairfield, CT 06825

**Measurement Company:** TRC Environmental Corporation

*Please provide the following summary information:*

**Dates of Testing:**
(Deployment/retrieval dates. Include confirmatory testing dates, if applicable.) December 16-18, 2025

**Total # of Rooms Tested:** 16

**Total # of Rooms Requiring Re-Testing:** 0

**Total # of Rooms Where Average Results Were at or above 4.0 pCi/L:** 0

Radon measurement activities were carried out in accordance with United States Environmental Protection Agency protocols and the Connecticut Department of Public Health Radon Program's *School Radon Testing Guidance* at the location described above.

| Kathleen Williamson/103081RT | Kathleen Williamson Digitally signed by Kathleen Williamson Date: 2026.01.19 10:29:51 -05'00' | |
|---|---|---|
| Measurement Professional / NRPP/NRSB # | Signature | Date |
| Angelus Papageorge/Executive Director of Operations | | 2/12/26 |
| School Designee / Title | Signature | Date |

*Phone: (860) 509-7300*
*Telephone Device for the Deaf (860) 509-7191*
*410 Capitol Avenue - MS # 12-RAD*
*P.O. Box 340308, Hartford, CT 06134*
*An Equal Opportunity Employer*

# STATE OF CONNECTICUT

DEPARTMENT OF PUBLIC HEALTH
RADON PROGRAM
SCHOOL RADON **RE-EVALUATION** REPORT FORM

July 2023

The following form must be submitted to the Connecticut Department of Public Health Radon Program within ten (10) business days of providing a final written report of radon measurement activities to school personnel.
**Do not send test results or other documents.**
Submit this signed form by **email** to the Radon Program at:
DPH.RadonReports@ct.gov

**Name of School:** Holland Hill Elementary School

**Address:**
(Street, town, zip code)
105 Meadowcroft Road
Fairfield, CT 06824

**Measurement Company:** TRC Environmental Corporation

*Please provide the following summary information:*

**Dates of Testing:**
(Deployment/retrieval dates. Include confirmatory testing dates, if applicable.) December 16-18, 2025

**Total # of Rooms Tested:** 4

**Total # of Rooms Requiring Re-Testing:** 0

**Total # of Rooms Where Average Results Were at or above 4.0 pCi/L:** 0

Radon measurement activities were carried out in accordance with United States Environmental Protection Agency protocols and the Connecticut Department of Public Health Radon Program's *School Radon Testing Guidance* at the location described above.

| Kathleen Williamson/103081RT | Kathleen Williamson Digitally signed by Kathleen Williamson Date: 2026.01.19 10:30:09 -05'00' | |
|---|---|---|
| Measurement Professional / NRPP/NRSB # | Signature | Date |
| Angelus Papageorge/Executive Director of Operations | | 2/12/26 |
| School Designee / Title | Signature | Date |

*Phone: (860) 509-7300*
*Telephone Device for the Deaf (860) 509-7191*
*410 Capitol Avenue - MS # 12-RAD*
*P.O. Box 340308, Hartford, CT 06134*
*An Equal Opportunity Employer*

# STATE OF CONNECTICUT

DEPARTMENT OF PUBLIC HEALTH
RADON PROGRAM
SCHOOL RADON **RE-EVALUATION** REPORT FORM

July 2023

The following form must be submitted to the Connecticut Department of Public Health Radon Program within ten (10) business days of providing a final written report of radon measurement activities to school personnel.
**Do not send test results or other documents.**
Submit this signed form by **email** to the Radon Program at:
DPH.RadonReports@ct.gov

**Name of School:** Jennings Elementary School

**Address:**
(Street, town, zip code)
31 Palm Drive
Fairfield, CT 06825

**Measurement Company:** TRC Environmental Corporation

*Please provide the following summary information:*

**Dates of Testing:**
(Deployment/retrieval dates. Include confirmatory testing dates, if applicable.) December 16-18, 2025

**Total # of Rooms Tested:** 4

**Total # of Rooms Requiring Re-Testing:** 0

**Total # of Rooms Where Average Results Were at or above 4.0 pCi/L:** 0

Radon measurement activities were carried out in accordance with United States Environmental Protection Agency protocols and the Connecticut Department of Public Health Radon Program's *School Radon Testing Guidance* at the location described above.

| Kathleen Williamson/103081RT | Kathleen Williamson Digitally signed by Kathleen Williamson Date: 2026.01.19 10:30:28 -05'00' | |
|---|---|---|
| Measurement Professional / NRPP/NRSB # | Signature | Date |
| Angelus Papageorge/Executive Director of Operations | | 2/12/26 |
| School Designee / Title | Signature | Date |

*Phone: (860) 509-7300*
*Telephone Device for the Deaf (860) 509-7191*
*410 Capitol Avenue - MS # 12-RAD*
*P.O. Box 340308, Hartford, CT 06134*
*An Equal Opportunity Employer*

# STATE OF CONNECTICUT

DEPARTMENT OF PUBLIC HEALTH
RADON PROGRAM
SCHOOL RADON **RE-EVALUATION** REPORT FORM

July 2023

The following form must be submitted to the Connecticut Department of Public Health Radon Program within ten (10) business days of providing a final written report of radon measurement activities to school personnel.
**Do not send test results or other documents.**
Submit this signed form by **email** to the Radon Program at:
DPH.RadonReports@ct.gov

**Name of School:** Fairfield Ludlowe High School

**Address:**
(Street, town, zip code)
785 Unquowa Road
Fairfield, CT 06824

**Measurement Company:** TRC Environmental Corporation

*Please provide the following summary information:*

**Dates of Testing:**
(Deployment/retrieval dates. Include confirmatory testing dates, if applicable.) December 16-18, 2025, January 12-14, 2026

**Total # of Rooms Tested:** 13

**Total # of Rooms Requiring Re-Testing:** 1

**Total # of Rooms Where Average Results Were at or above 4.0 pCi/L:** 1

Radon measurement activities were carried out in accordance with United States Environmental Protection Agency protocols and the Connecticut Department of Public Health Radon Program's *School Radon Testing Guidance* at the location described above.

| Kathleen Williamson/103081RT | Kathleen Williamson Digitally signed by Kathleen Williamson Date: 2026.01.19 10:29:12 -05'00' | |
|---|---|---|
| Measurement Professional / NRPP/NRSB # | Signature | Date |
| Angelus Papageorge/Executive Director of Operations | | 2/12/26 |
| School Designee / Title | Signature | Date |

*Phone: (860) 509-7300*
*Telephone Device for the Deaf (860) 509-7191*
*410 Capitol Avenue - MS # 12-RAD*
*P.O. Box 340308, Hartford, CT 06134*
*An Equal Opportunity Employer*

# STATE OF CONNECTICUT

DEPARTMENT OF PUBLIC HEALTH
RADON PROGRAM
SCHOOL RADON **RE-EVALUATION** REPORT FORM

July 2023

The following form must be submitted to the Connecticut Department of Public Health Radon Program within ten (10) business days of providing a final written report of radon measurement activities to school personnel.
**Do not send test results or other documents.**
Submit this signed form by **email** to the Radon Program at:
DPH.RadonReports@ct.gov

**Name of School:** Fairfield Woods Middle School

**Address:**
(Street, town, zip code) 1115 Fairfield Woods Road
Fairfield, CT 06825

**Measurement Company:** TRC Environmental Corporation

*Please provide the following summary information:*

**Dates of Testing:**
(Deployment/retrieval dates. Include confirmatory testing dates, if applicable.) December 16-18, 2025

**Total # of Rooms Tested:** 7

**Total # of Rooms Requiring Re-Testing:** 0

**Total # of Rooms Where Average Results Were at or above 4.0 pCi/L:** 0

Radon measurement activities were carried out in accordance with United States Environmental Protection Agency protocols and the Connecticut Department of Public Health Radon Program's *School Radon Testing Guidance* at the location described above.

| Kathleen Williamson/103081RT | Kathleen Williamson Digitally signed by Kathleen Williamson Date: 2026.01.19 10:28:51 -05'00' | |
|---|---|---|
| Measurement Professional / NRPP/NRSB # | Signature | Date |
| Angelus Papageorge/Executive Director of Operations | | 2/12/26 |
| School Designee / Title | Signature | Date |

*Phone: (860) 509-7300*
*Telephone Device for the Deaf (860) 509-7191*
*410 Capitol Avenue - MS # 12-RAD*
*P.O. Box 340308, Hartford, CT 06134*
*An Equal Opportunity Employer*

# STATE OF CONNECTICUT

DEPARTMENT OF PUBLIC HEALTH
RADON PROGRAM
SCHOOL RADON **RE-EVALUATION** REPORT FORM

July 2023

The following form must be submitted to the Connecticut Department of Public Health Radon Program within ten (10) business days of providing a final written report of radon measurement activities to school personnel.
**Do not send test results or other documents.**
Submit this signed form by **email** to the Radon Program at:
DPH.RadonReports@ct.gov

**Name of School:** Dwight Elementary School

**Address:**
(Street, town, zip code)
1600 Redding Road
Fairfield, CT 06824

**Measurement Company:** TRC Environmental Corporation

*Please provide the following summary information:*

**Dates of Testing:**
(Deployment/retrieval dates. Include confirmatory testing dates, if applicable.) December 16-18, 2025

**Total # of Rooms Tested:** 4

**Total # of Rooms Requiring Re-Testing:** 0

**Total # of Rooms Where Average Results Were at or above 4.0 pCi/L:** 0

Radon measurement activities were carried out in accordance with United States Environmental Protection Agency protocols and the Connecticut Department of Public Health Radon Program's *School Radon Testing Guidance* at the location described above.

| Kathleen Williamson/103081RT | Kathleen Williamson Digitally signed by Kathleen Williamson Date: 2026.01.19 10:28:30 -05'00' | |
|---|---|---|
| Measurement Professional / NRPP/NRSB # | Signature | Date |
| Angelus Papageorge/Executive Director of Operations | | 2/12/26 |
| School Designee / Title | Signature | Date |

*Phone: (860) 509-7300*
*Telephone Device for the Deaf (860) 509-7191*
*410 Capitol Avenue - MS # 12-RAD*
*P.O. Box 340308, Hartford, CT 06134*
*An Equal Opportunity Employer*

# STATE OF CONNECTICUT

DEPARTMENT OF PUBLIC HEALTH
RADON PROGRAM
SCHOOL RADON **RE-EVALUATION** REPORT FORM

July 2023

The following form must be submitted to the Connecticut Department of Public Health Radon Program within ten (10) business days of providing a final written report of radon measurement activities to school personnel.
**Do not send test results or other documents.**
Submit this signed form by **email** to the Radon Program at:
DPH.RadonReports@ct.gov

**Name of School:** Burr Elementary School

**Address:**
(Street, town, zip code)
1960 Burr Street
Fairfield, CT 06824

**Measurement Company:** TRC Environmental Corporation

*Please provide the following summary information:*

**Dates of Testing:**
(Deployment/retrieval dates. Include confirmatory testing dates, if applicable.) December 16-18, 2025

**Total # of Rooms Tested:** 4

**Total # of Rooms Requiring Re-Testing:** 0

**Total # of Rooms Where Average Results Were at or above 4.0 pCi/L:** 0

Radon measurement activities were carried out in accordance with United States Environmental Protection Agency protocols and the Connecticut Department of Public Health Radon Program's *School Radon Testing Guidance* at the location described above.

| | | |
|---|---|---|
| Kathleen Williamson/103081RT | Kathleen Williamson Digitally signed by Kathleen Williamson Date: 2026.01.19 10:28:00 -05'00' | |
| Measurement Professional / NRPP/NRSB # | Signature | Date |
| Angelus Papageorge/Executive Director of Operations | | 2/12/26 |
| School Designee / Title | Signature | Date |

*Phone: (860) 509-7300*
*Telephone Device for the Deaf (860) 509-7191*
*410 Capitol Avenue - MS # 12-RAD*
*P.O. Box 340308, Hartford, CT 06134*
*An Equal Opportunity Employer*