

Measure C Bond Office

February 9, 2026

To: All Bidders

From: Sandra Lovaas, Measure C Bond Manager
Pleasant Valley School District

Subject: Addendum 1, **Bid FB-26-03, Parking Lot Pavement and ADA Pathway Replacement Project, Las Posas Elementary School**

This addendum is hereby made a part of the Contract Documents for **Bid FB-26-03, Parking Lot Pavement and ADA Pathway Replacement Project, Las Posas Elementary School** to the same extent as though it was originally included therein and takes precedence over the original documents.

Receipt of this addendum should be acknowledged on the Bid Form.

- 1) Provides a revised Section 32 93 33, Shrub Planting
Revision changes quantity of 5-gallon shrubs being provided by the District for planting by the Contractor. Quantity changes from forty-eight (48) to a quantity of sixty (60) shrubs being provided for planting

Enclosure: Section 32 93 33 (addendum 1)



Pleasant Valley School District

600 Temple Avenue • Camarillo, CA 93010 • (805) 389-2100 (Office) • www.pleasantvalleysd.org
PVSD prepares 21st century learners who are responsible members of our global society.

SECTION 32 93 33
SHRUB PLANTING

Addendum1

PART 1 GENERAL

1.01 SECTION INCLUDES

- A. This section includes general requirements for the installation of the shrub planting and the espalier plants.
- B. The District shall purchase and deliver to the site (60) 5-gallon shrubs. The Contractor shall lay out the shrubs in their location and when approved by the District, shall install the shrub planting.

1.02 RELATED SECTIONS

Section 32 84 23 – Irrigation Systems
Section 32 93 30 – Sod Lawn Planting
Section 32 93 43 – Tree Planting

1.03 SUBMITTALS

Furnish material invoices indicating the quantities of fertilizers, soil amendments, mulch, and all materials required to complete the Work. Material invoices must be approved by the Landscape Architect prior to incorporating soil amendments. Certificates shall be prepared by the supplier or distributor and shall indicate the quantities and qualities of materials used.

1.04 PROTECTION

Contractor shall check or locate existing structures, electric cables or conduits, utility lines and other existing features or conditions above or below ground level that might be damaged as a result of the operation. Questions or conflicts arising out of such examination prior to or during operation shall be immediately directed to the attention of the District for necessary action or decisions before resuming operation. Contractor shall be responsible for repair or replacement at no cost to the District for features or conditions damaged through failure to comply with the above procedures.

1.05 ALTERNATES

Alternates will not be permitted, except where indicated, and as approved by the Landscape Architect.

PART 2 PRODUCTS

2.01 MATERIALS – LANDSCAPE

- A. (60) 5-gallon shrubs shall be purchased and delivered to site by PVSD for Contractor to position and plant.
- B. Soil amendments: organic soil amendment shall be Agromin “Agromend,” or equal.
- C. Backfill material shall be:
 - 1. $\frac{1}{3}$ organic soil amendment
 - 2. $\frac{2}{3}$ existing site soil.
 - 3. Commercial Fertilizer (15-15-15), 1 lb./cu. yd.
 - 4. Iron, Zinc, Manganese, 1 oz. /cu. yd.
- D. Soil preparation materials per 1,000 square feet:
 - 1. Three cubic yards of organic soil amendment
 - 2. Commercial Fertilizer (15-15-15), eight pounds
- E. Mulch shall be Agromin “Garden Mulch” or equal.
- F. Pre-Emergent herbicide – product ‘Dimension’.
- G. Redwood header shall be 2” x 4” nominal size, staked into place with redwood stakes and wood screws.

PART 3 EXECUTION

3.01 SITE CONDITION

No plant materials shall be planted until all operations in conjunction with the installation of the irrigation system have been approved by the District and the Landscape Architect. Final grades shall be established, and the planting areas shall be properly prepared and graded.

3.02 GROUND PREPARATION – ALL AREAS

- A. After the site clearance and preparation has been approved by the District, planted areas shall be thoroughly cultivated to a depth of six inches to reduce any compaction caused by the Work. Protect existing tree roots.
- B. Stones or rocks over 1” in size, construction refuse, and other deleterious material shall be removed from the site, safely and legally.
- C. Apply soil preparation materials to all planting areas and thoroughly incorporate into the top six inches of soil.
- D. Wet soil thoroughly and allow to settle. Repeat this compaction procedure until soil is stable enough to permit aeration and drainage for plant material.

- E. Finish grade all planting areas to a smooth, uniform surface ready for planting. Finish grade shall be one inch below finish grade of adjacent paved surfaces unless otherwise noted on Drawings.

3.03 PLANTING – SHRUBS

- A. Shrub planting shall comply with details on drawings.
- B. Make necessary adjustments and excavate pits of square outline and vertical sides for all plants. Scarify sides and bottoms of all plant pits. Set trees vertical.
- C. At all times, protect roots and rootball of plants from drying.
- D. If directed by the Landscape Architect, the Contractor shall prune plants in accordance with standard horticultural practice.

3.04 PRE-EMERGENT HERBICIDE

Broadcast pre-emergent herbicide product 'Dimension' over surface of exposed soil in shrub planters at rate per Manufacturer's specifications. Herbicide shall be applied prior to wood mulch installation.

3.05 MULCH

Install three-inch layer of mulch throughout shrub areas without groundcover. Finish grade shrub areas to a smooth uniform surface to receive mulch. Keep mulch away from tree and shrub crown. Dress mulch areas to present a clean uniform appearance when complete.

END OF SECTION 32 93 33