SAN BENITO CONSOLIDATED INDPENDENT SCHOOL
DISTRICT CSP-0326-FERF, FORCE ENTRY RESISTANT FILM
MARCH 3, 2026

ADDENDUM NO. 2

The campus listing indicates a total of **6,308.39 square feet** CSP-0326-FERF_1, while the proposal form references **7,000 SF** CSP-0326-FERF_1.

Question1

Please confirm the final square footage to be used for pricing and contract award. Will payment be based on actual verified field measurements?

The final square footage will be used for pricing. Payment will be based on the square footage requested.

The specification references 9.5 mil film but does not specify required anchoring methodology CSP-0326-FERF_1.

Question 2

Is a structural silicone (wet glaze) attachment system required for forced-entry performance or is film-only installation acceptable?

Please include structural silicone attachment system.

The bid references manufacturer brand "or owner approved equal" CSP-0326-FERF_1 but does not specify warranty expectations.

Question 3

Does the District require a manufacturer-backed warranty, installer warranty, or both? What minimum term is required (e.g., 10-year, 15-year)?

The district does not require a manufacturer warranty, but please state the warranty period as part of your proposal.

Per RFP, contractor must coordinate with district operations CSP-0326-FERF_1.

Question 4

Are installations required outside instructional hours (after school, weekends, summer only), or will daytime work be permitted?

Daytime work will be permitted

The bid references "Force Entry Resistant Film" CSP-0326-FERF_1 but does not define performance criteria.

Question 5

Does the District require compliance with any specific forced-entry testing protocol (e.g., impact cycling, ASTM forced-entry standards, or other criteria)? If so, please specify the required standard.

The district is complying with requirements made by the State of Texas as per TEA guidelines for school facilities.