

ATTACHMENT E

SCOPE OF WORK

Required Submittals-In addition to information requested elsewhere in this solicitation, Offerors should submit the following information for purposes of evaluation:

1. A photocopy of your contractor's license
2. The successful Offeror shall provide satisfactory evidence of all required insurance coverage and licenses PRIOR TO PERFORMANCE

General Specifications:

1. The Contractor must have a detailed understanding of positive drainage in all areas of work with forms & backfill. Must be familiar with ADA code requirements for ramps, sidewalks; be able to read construction plans and layout work in accordance with plans or written or verbal directions of DD2 Facilities personnel.
2. The Contractor must furnish a comprehensive, written "Not To Exceed" estimate prior to beginning each projects. If estimate exceeds budget, or appears to be against it's best interests, the District reserves the right to bid out the work in question.
3. The District expects a high standard of quality & quantity of work. Contractor must have full understanding of the work requested for each project. If any work deemed unacceptable by the District, the Contractor will replace at no additional cost to DD2.
4. Contractor must supply all hand tools, supplies, materials, and labor required to complete all projects.
5. The Contractor shall furnish necessary on site supervision at all times.
6. The Contractor is responsible for underground utility locating prior to commencement.
7. Contractor responsible for all site, pedestrian and vehicular traffic safety and control (All Projects).
8. The Contractor must follow all OSHA safety requirements.
9. The Contractor must complete work in a timely manner and with minimum of supervision from DD2 staff
10. The Contractor must maintain a neat and safe work site during & after work hours.
11. All debris, spoils, and trash collection, hauling, and disposal is the responsibility of the Contractor, including coordination of waste receptacles onsite, if necessary.

ATTACHMENT E

Detailed Specifications:

1. Any work not covered by unit pricing will be billed based on hourly rates.
2. Concrete will generally be 3,000 psi for most projects undertaken with this contract with lime, fiber, or other additives, as requested by the District.
3. Other materials (masonry, precast concrete, etc.) must be submitted to the District for approval prior to ordering.
4. Concrete finish: A smooth, hard, dense surface is desired, floating should be followed by steel troweling. Troweling should not be done on a surface that has not been floated; only bull floating is not an adequate finish procedure. A light broomed finish is desired, the concrete should be sufficiently hard to retain the scoring impression.
5. All 6" X 18" curb to be standard SCDOT curb profile.
6. No free hand forming of curb and gutter. All curb and gutter require front, face, and rear forms.
7. Contractor responsible for site dressing after remove and replace projects (included in unit pricing - if unit pricing applies). Site dressing for new projects will be optional but based on hourly rates if requested by The District.
8. Control joints (sawed) are required (Flatwork @ 10' maximum all directions. Curb and gutter @ 10' maximum) Fiber joint expansion material required at 60' maximum – Sawed joints and fiber joints Included in unit pricing.
9. #4 rebar dowels @ 2' on center inserted 4" minimum into adjacent existing concrete required for patches or repairs (Included in unit pricing – if unit pricing applies).
10. Contractor responsible for all concrete cleanout/cleanup to include receptacle which complies with EPA NPDES regulations (All Projects).
11. Contractor to be available to respond to District requests for estimate within 48 hours.

ATTACHMENT E

12. This contract will commonly entail (but is not limited to):
- a) Flatwork
 - b) Curb and gutter
 - c) ADA ramps
 - d) Storm water infrastructure (above and below grade)
 - e) Light bases
 - f) Monumental sign bases (brick or concrete)
 - g) Catch basins
 - h) Retaining walls
 - i) Stairs and/or handrails
 - j) Utility duct banks
 - k) Miscellaneous grading
 - l) Miscellaneous excavating
 - m) Brick and block
 - n) Rock walls
 - o) Pavers
 - p) Detectable warning pavers

APPENDICES TO SCOPE OF WORK

Attachment D - [Bidding Schedule](#)

All offerors must complete Attachment D - Bidding Schedule, which may be found under the “Attachments” link on the District’s Solicitation Page. The Bidding Schedule is an Excel spreadsheet and must be downloaded, completed, printed and submitted with your sealed bid. Failure to do so will result in rejection of offer.