



## ADDENDUM #4

7 April 2026

TO: All Bidders

RE: Maize USD 266 – Bus Storage Building

Project #: 5537.50

*This Addendum is hereby made part of the Contract Documents to the same extent as though it were originally included therein. Refer to "Bid Form" for acknowledgment of Addenda.*

*All Contractors, Subcontractors and suppliers are reminded that they shall be familiar with all Addenda items (as well as all parts of the Construction Documents) so as to understand the extent of their work and its interrelation with other trades.*

### **Architectural:**

#### **Item AD4-A01 Specification Section 13 34 19 – Metal Building Systems:**

ADDITION: 2.05 – Exterior wall panels should be:

- Nominal thickness: 24 ga. coated thickness, with smooth surface,
- Exterior Finish: Fluoropolymer two-coat system (PVDF),
- Colors: As selected by Architect from Manufacturer's standard colors and will match the existing buildings on site. Beige exterior walls and Colonial Red (burgundy) for trim/gutters/downspouts and roof.

**By: Gary Holler**  
**Schaefer Architecture**

