

Facilities Services Department

ADDENDUM #2

Issued 4-13-26

Bid Date 4-16-26 @ 2:00 pm

Fremont Elementary School Re-Roofing Project 2026-1

This addendum to the bid package (contract documents) issued on the above date sets forth changes and amendments to the previously published description of work for this project. Questions regarding the following listed changes should be directed to Merced City School District, Steven Whitaker swhitaker@mcsd.k12.ca.us (209) 385-6332.

Item #1 – Modify Addendum 1 Section 01 11 00 Summary of Work, 1.3, D, # 37 to read.

Install Pyramic acrylic coating in one coat at 1 - 1.5 gal per square over all roof areas shown as "repair areas" and marked in blue highlight on the addendum 1 site map. The repairs made will require a base coat of 1 gallon per square and the balance of the roof areas will be completed in one coat at 1 - 1.5 gallons per square. Back roll for complete adhesion, coverage, and mil thickness. Additional coats may be required for proper coverage.

Questions & Answers:

1. Q: Will building 6 be getting polyiso flute fill like building 7?

A: The addendum scope of work only specifies building 7 to received flute fill insulation. Building 6 will follow the scope of work with roof removal and replacement.

2. Q: Building 1 has many existing rubber/foam blocks with metal caps on them. Are those also being removed and replaced with rubber dura blocks?

A: See item 16 and item 17 in addendum 1.

3. Q: Add.#1 SOW #26 - Will a plumbing or HVAC subcontractor be required by the district to complete this portion of work?

A: No the roofing contractor shall utilize means and methods to protect the building and HVAC work from damage. Item 26 in addendum 1 is to provide a possible means to prevent damage however it is the roofing contractor's responsibility

4. Q: Can you provide a map showing the locations of the new gutters as well as a downspout layout?

A: Item #21 in the addendum summary of work states to install gutters and downspouts at all eve locations. Downspouts will be needed in each gutter section and placement will be addressed during a site walk with the district.

End of addendum 2

Addendum must be signed, dated and returned with bid to confirm receipt and acknowledgment

Signed_____

Date_____

Print Name_____