Flushing Community Schools
Stormwater Management Program Plan

Municipal Separate Storm Sewer System (MS4)
National Pollutant Discharge Elimination System (NPDES)
Stormwater Discharge Permit

PERMIT NO. In-Process

Prepared By:

Arch Environmental Group, Inc.
37720 Interchange Drive
Farmington Hills, Michigan 48335

Development Date: May 17, 2025
Revision Date: February 10, 2025
Revision Date: May 27, 2025

Table of Contents

1.0 Introduction 1

1.1 Regulated Area 1

1.2 Outfalls & Discharge Points/ Receiving Waters 2

1.3 Enforcement Response Procedures 3

2.0 Stormwater Management Program Plan (SWMP) Minimum Control Measures 4

2.1 Public Involvement/Participation Program (PPP) 5

2.1.1 Public Involvement/Participation Program Objectives 5
2.1.2 Public Involvement & Participation Procedure 5
2.1.3 Public Involvement & Participation Assessment 5
2.1.4 Public Involvement & Participation Program (PPP) BMP Table 6

2.2 Public Education Program (PEP) 8

2.2.1 Public Education Program Objectives 8
2.2.2 Public Education Program Procedure 8
2.2.3 Public Education Program BMP Table 9
2.2.4 Public Education Program Effectiveness 15

2.3 Illicit Discharge Elimination Program (IDEP) 15

2.3.1 Illicit Discharge Elimination Program (IDEP) Program Objectives 15
2.3.2 Facility Site Storm Sewer System Maps and Lists 15
2.3.3 Illicit Discharge Identification & Investigation Procedure – Field Observations 16
2.3.4 Illicit Discharge Identification & Investigation Procedure – Field Screening & Source Investigation 16
2.3.5 Illicit Discharge/Connection Elimination Procedure 17
2.3.6 Illicit Discharge Regulatory Mechanism/Policy 18
2.3.7 Illicit Discharge Elimination Training 20
2.3.8 Illicit Discharge Elimination Program Effectiveness 20
2.3.9 Illicit Discharge Elimination Program – BMP Table 22
2.3.10 Polluting Materials Emergency and Spill Response Policy and Procedures 25

2.4 Construction Site Stormwater Runoff Control Program 26

2.4.1 Construction Site Stormwater Management Program Objectives 26
2.4.2 Construction Notification Procedure 26
2.4.3 Part 91 Permit 27
2.4.4 Permit by Rule Compliance 27
2.4.5 Construction Site Stormwater Management-BMP Table 29

2.5 Post Construction Stormwater Controls for New Developments & Redevelopments 31

2.5.1 Post Construction Stormwater Management Program Objectives 31
2.5.2 Post-Construction Policy and Procedure 31
2.5.3 Water Quality Treatment Standard 32
2.5.4 Channel Protection Performance Standard 33

2.5.5 Site-Specific Requirements 33
2.5.6 Site Plan Review 34
2.5.7 Long-Term Operation & Maintenance of Stormwater Controls 35
2.5.8 Post Construction Stormwater Management-BMP Table 36

2.6 Pollution Prevention & Good Housekeeping Program 38
2.6.1 Pollution Prevention & Good Housekeeping Program Objectives 38
2.6.2 Structural Control Inventory & Schedule Table 38
2.6.3 Facility Assessment & Prioritization 38
2.6.4 Storm Sewer Structure Controls Inspection & Maintenance Policy & Procedure 39
2.6.5 Structural BMP Operation & Maintenance Waste Disposal Procedures 40
2.6.6 Pollution Prevention/Good Housekeeping – Municipal Operations & Maintenance Activities 41
2.6.7 Street Sweeping Procedure, Prioritization & Schedule 44
2.6.8 Managing Vegetated Properties 45
2.6.9 Contractor Requirements & Oversight 45
2.6.10 Pollution Prevention/Good House Keeping Training 46
2.6.11 Pollution Prevention/Good Housekeeping –BMP Table 47

3.0 Training 52

3.1 Training Table 53

4.0 Total Maximum Daily Load (TMDL) Restrictions 54

4.1 What are TMDLs 54

4.2 Statewide E. coli TMDL 54

4.3 TMDL Implementation – Monitoring Plan 55
4.3.1 Sampling 55
4.3.2 Prioritized TMDL Best Management Practices 56
4.3.3 TMDL - BMP Table **Error! Bookmark not defined.**

Appendices

Appendix A Outfall/Discharge Point Receiving Water Table & Site Stormwater Structure Maps
Appendix B Enforcement Policies and Tracking Forms
Appendix C SEMCOG Poster & Illicit Discharge Poster
Appendix D Inspection Field Worksheets
Appendix E Property Structural Controls Inventory, Inspection, & Maintenance Schedule
Appendix F Contractor Oversight & Employee Training Documentation
Appendix G TMDL Sample Location Table

Stormwater Management Program Plan

1.0 Introduction

Flushing Community Schools is a public school district based in Flushing, Michigan that owns or operates a regulated Municipal Separate Storm Sewer System (MS4). This Stormwater Management Plan (SWMP) has been developed to retain authorization to discharge stormwater to surface waters and reduce the discharge of pollutants from the MS4 to the Maximum Extent Practicable and protect water quality. Flushing Community Schools will implement and enforce this SWMP to the Maximum Extent Practicable.

This Stormwater Management Plan commits to actions throughout the permit cycle. This SWMP includes measurable goals for Best Management Practices (BMP), focusing on the six minimum measures. Measurable goals describe the actions Flushing Community Schools will take to implement each BMP and allow Flushing Community Schools to evaluate progress toward meeting key objectives outlined in the following sections.

Flushing Community Schools owns and operates thirteen (13) public properties within the boundaries of the "Flint Urbanized Area". All Flushing Community Schools properties are within the urbanized area based off of the 2010 Census data, and the facilities include:


1. Bus Garage & Maintenance - 4335 N Seymour Rd, Flushing, MI 48433
2. Central Elementary School-Football Field Complex - 525 Coutant St, Flushing, MI 48433
3. Central Office - 522 N McKinley Rd, Flushing, MI 48433
4. Early Childhood Center - 409 Chamberlain St, Flushing, MI 48433
5. Elms Elementary School - 6125 Elms Rd, Flushing, MI 48433
6. Flushing High School - 5039 Deland Rd, Flushing, MI 48433
7. Flushing Middle School - 8100 Carpenter Rd, Flushing, MI 48433
8. Seymour Elementary School-Soccer Fields Complex - 3088 N Seymour Rd, Flushing, MI 48433
9. Springview Elementary School - 1233 Springview Dr, Flushing, MI 48433
10. Flushing RVA, 230 Oak Street, Flushing, MI 48433
11. Vacant Property, Morrish Road, Flushing
12. Vacant Property, North Mckinley Road, Flushing
13. Vacant Property, Nichols Road, Flushing

1.1 Regulated Area

A map identifying the urbanized area within the Flushing Community Schools urbanized area as defined by the 2010 Census is provided below in Map 1.

Development Date: May 17, 2025
Revision Date: February 10, 2025
Revision Date: May 27, 2025

Map 1 – District Jurisdictional Boundary Map – Urbanized Area[1]



1.2 Outfalls & Discharge Points/ Receiving Waters


The permit authorizes the discharge of stormwater from municipal separate stormwater drainage systems to waters of the state from all existing outfalls or points of discharge.

Flushing Community Schools has identified outfalls that discharge directly into surface waters of the state and discharge points that discharge into other MS4 drainage systems. The Flushing Community Schools drainage system discharges directly or indirectly into the Flint River Watershed as detailed in Map 2 below.

Flushing Community Schools has completed site specific storm sewer system maps which identify outfall and discharge point locations, discharge point source identification numbers, and receiving waters. A receiving water table and site-specific storm sewer system maps are provided in Appendix A. Any changes to the Flushing Community Schools storm sewer system will be reflected on the storm sewer system maps and reported provided to the EGLE during progress reporting. The district watershed boundary map is provided below in the map listed as "Map 2".

[1] Urbanized area boundary based on U.S. Census Bureau 2010 Urban Area Reference Maps.

Map 2 – District Watershed Map[2]



1.3 Enforcement Response Procedures

The Flushing Community Schools properties are regulated as an MS4 under the NPDES Permit program. Environmental compliance staff members from Flushing Community Schools have the authority to inspect and monitor stormwater-related activities on campus and require full compliance with all stormwater permit requirements. Enforcement of Flushing Community Schools policies, procedures, and best management practices (BMPs) outlined in this SWMP is the responsibility of the Stormwater Program Manager or their designee. Any questions regarding this policy and procedure will be directed to the Stormwater Program Manager.

[2] Watershed boundaries based on Environmental Protection Agency MiWaters Mapper National Hydrography Dataset Mapper 12-Digit Watersheds.

The primary role of the Superintendent or their designee is to ensure that the ERP is followed in a timely and consistent manner and track compliance issues and schedules. To achieve compliance, the following steps may be conducted:

1. Reviews reported violation.
2. Contact business or non-district individual responsible for the violation.
3. Ensures that compliance actions taken are consistent and timely.
4. Tracks instances of noncompliance.
5. Review compliance reports and schedules to ensure that appropriate enforcement actions are taken, and compliance goals are met.
6. Conduct follow-up inspection(s) to verify the violation has been corrected.
7. Legal action may be pursued for the most serious violations including where the response to previous enforcement actions is inadequate.

The tracking of instances of noncompliance includes the following information:

- Name
- Date
- Location of Violation (address, cross streets, etc.,)
- Business/Agency/Organization (as appropriate)
- Description of Violation
- Description of Enforcement Response
- Date Violation was Resolved

Information shall be placed into the Districts Noncompliance Enforcement Tracking Sheet.

This procedure will be reviewed on an annual basis by the Stormwater Manager for any updates. A copy of the SW Illicit Discharge Regulatory Policy is included with and an example of the Municipal Separate Storm Sewer System Noncompliance Enforcement Tracking Sheet in Appendix B.

2.0 Stormwater Management Program Plan (SWMP) Minimum Control Measures

This SWMP has been developed to describe the Best Management Practices (BMPs) Flushing Community Schools will implement to meet the six minimum control measures and water quality requirements. The six minimum control measures include:

- **Public Participation/Involvement Program (PPP)**
  To share components of the SWMP and encourage participation in its review and implementation.
- **Public Education Program (PEP)**
  To promote, publicize, and facilitate education for the purpose of encouraging the public to reduce the discharge of pollutants to stormwater to the maximum extent practicable.
- **Illicit Discharge Elimination Program (IDEP)**
  To detect and eliminate illicit connections and discharges to the MS4.
- **Construction Stormwater Runoff Control Program**

To augment Part 91 rules dealing with soil erosion, offsite sedimentation, and other construction-related wastes.

- **Post-Construction Stormwater Runoff Program**
  To address post-construction stormwater runoff from projects that disturb one acre or more, including projects less than one acre that are part of a larger common plan of development that would disturb one acre or more.
- **Pollution Prevention/Good Housekeeping Program**
  To minimize pollutant runoff to the maximum extent practicable from municipal operations that discharge stormwater to the surface waters of the state.

Each BMP includes a measurable goal, implementation schedule, and measure of assessment.

2.1 Public Involvement/Participation Program (PPP)

Engaging and empowering the public in the effort to reduce the impacts of stormwater runoff is a key element of the public involvement/participation program.

2.1.1 Public Involvement/Participation Program Objectives

1. Process for making the Stormwater Management Plan available for public inspection and comment.
2. Process for inviting public involvement and participation in the implementation of SWMP best management practices and periodic review of the SWMP.

2.1.2 Public Involvement & Participation Procedure

1. As required, the approved Stormwater Management Program (SWMP) will be made available to the public via the district website throughout the permit cycle.
2. The stormwater webpages will include contact information for public comments.
3. The public will be notified through announcements or newsletters that a copy of the SWMP is available on the district stormwater webpage.
4. A public survey has been developed and placed on the Flushing Community Schools stormwater webpage in an effort to provide input into stormwater implementation.
5. A link to a stormwater blog “Cleanwater Chronicles” has been added to the Flushing Community Schools stormwater webpage. The stormwater blog explains water quality issues and promotes opportunities for public involvement.
6. Cooperation with local watershed protection groups.

2.1.3 Public Involvement & Participation Assessment

1. Flushing Community Schools will review the public involvement & participation BMPs as part of annual SWMP review to determine level of district involvement and identify areas of improvement.

2.1.4 Public Involvement & Participation Program (PPP) BMP Table

BMP	Implementation of BMP	Timeframe	Measurable Goal	Measure of Assessment	Responsible Party
BMP #2.1.4.1 Public Notice of SWMP	Make SWMP available for public review through stormwater webpage.	Annually Throughout Permit Cycle	Public notice published in annual district wide newsletter announcing the availability of the SWMP for review, including contact information for comments.	Verify SWMP available on stormwater webpage, and track changes webpage posting of SWMP.	Flushing Community Schools
	Notification in annual district newsletter, website, or school posting to publicize updated SWMP and locations for review.			Keep copies of official SWMP posting notifications.	
	Contact information will be available on the stormwater webpages to forward comments regarding the SWMP.			Compile and track comments from the public.	
BMP #2.1.4.2 Stormwater Blog	Post link to stormwater blog on district website.	Ongoing Throughout Permit Cycle	A link to a stormwater blog established and maintained on the district stormwater webpage to assist in distributing information and updating the public on the watershed and activities.	Copies of monthly stormwater blog postings for reporting period.	Flushing Community Schools
BMP #2.1.4.3 Stormwater Education Program Survey	Post survey on district website.	Ongoing Throughout Permit Cycle	Survey posted on the stormwater webpages and link maintained throughout the permit term to assess community knowledge and provide input into stormwater implementation.	Results of completed surveys.	Flushing Community Schools

BMP	Implementation of BMP	Timeframe	Measurable Goal	Measure of Assessment	Responsible Party
BMP #2.1.4.4 Participation Activities	Engage in environmental education activities.	Ongoing Throughout Permit Cycle	Increase in public participation in environmental activities and outreach events. Participation activities include water quality issues, stormwater management initiatives, home toxics, recycling, compost, and disposal.	Reports of participation.	Flushing Community Schools
BMP #2.1.4.5 Public Involvement & Participation Program Assessment	Evaluate the effectiveness of the public involvement program.	Annually Throughout Permit Cycle	Complete as part of annual SWMP review to determine level of district involvement and identify areas of improvement. Program activities may be adjusted based on the results of the assessment.	Copies of annual SWMP review noting any areas of needed improvement.	Flushing Community Schools

2.2 Public Education Program (PEP)

Flushing Community Schools' "Public Education Program (PEP)" is designed to promote, publicize, and facilitate education for the purpose of encouraging the public to reduce the discharge of pollutants into the Flushing Community Schools separate storm sewer system.

The term "Public" as referred in to in this program is defined to include all persons who could potentially affect the quality of stormwater discharges from Flushing Community Schools properties including but not limited to Flushing Community Schools faculty, staff, contractors, and students of Flushing Community Schools, as well as area residents, visitors, public employees, local businesses, industries, construction contractors and property developers. This PEP will include a variety of mechanisms and venues to provide watershed awareness and pollution prevention education throughout the Flushing Community Schools jurisdiction.

2.2.1 Public Education Program Objectives

1. Responsibility and stewardship in their watershed.
2. Inform and educate the public about the connection of the MS4 to area waterbodies and the potential impacts discharges could have on surface waters of the state.
3. Educate the public on illicit discharges and promote public reporting of illicit discharges and improper disposal of materials into the MS4.
4. Promote preferred cleaning materials and procedures for car, pavement, and power washing.
5. Inform and educate the public on the proper application and disposal of pesticides, herbicides, and fertilizers.
6. Promote proper disposal practices for grass clippings, leaf litter, and animal wastes that may enter the MS4.
7. Identify and promote the availability, location, and requirements of facilities for collection or disposal of household hazardous wastes, travel trailer sanitary wastes, chemicals, yard wastes, and motor vehicle fluids.
8. Inform and educate the public on proper septic system care and maintenance, and how to recognize system failure.
9. Promote methods for managing riparian lands to protect water quality.
10. Provide training for staff.

2.2.2 Public Education Program Procedure

Flushing Community Schools is targeting all community wide issues as high priority. No prioritization will be needed, as educational activities to ensure that all community wide issues are reached to the public. It is anticipated that during this permit a combination of educational approaches will be used to convey the individual components of the PEP. Educational mechanisms will include tracking of watershed specific education topics in various science curriculums, cooperation with the distribution or posting of community newsletters and other watershed partner literature, and event notices. Flushing Community Schools has developed and implemented a comprehensive "Stormwater Management" webpage on the district's website. Additionally, program posters, are strategically placed throughout school facilities. Copies of SEMCOG posters are provided in Appendix C.

2.2.3 Public Education Program BMP Table

BMP Topic	Description of BMP	Timeframe	Measurable Goal & Key Messages	Measure of Assessment	Target Audience	Responsible Party
BMP #2.2.3.1 Promote public responsibility and stewardship in watershed.	Watershed website. Watershed specific website hosted by district, featuring watershed map, description of watershed, and links to watershed groups.	Ongoing Throughout Permit Cycle	Supply watershed information and promote watershed membership information. Educate the public on local water body health.	Update webpages as necessary. Confirm posting & track webpage reviews. Provide watershed membership information.	Students, faculty, and community	Flushing Community Schools
	Place SEMCOG "7 Simple Steps to Clean Water" information on stormwater webpages.		SEMCOG "7 Simple Steps to Clean Water" information and links.	Update webpages as necessary. Confirm posting & track webpage reviews.		
			Communicate with faculty regarding the resources available to reach the student audience.	Documentation of communication with faculty.		
	Publicize environmental related events through email, newsletters, or social media.	Ongoing Throughout Permit Cycle	Promote public awareness on environmental issues and increase district environmental participation.	Date, time location and name of event attended.	Students, faculty and community	
				Maintain copies of email notices (watershed announcement) of educational materials provided to district staff.		

Development Date: May 17, 2025
Revision Date: February 10, 2025
Revision Date: May 27, 2025

BMP Topic	Description of BMP	Timeframe	Measurable Goal & Key Messages	Measure of Assessment	Target Audience	Responsible Party
BMP #2.2.3.2 Educate the public about the connection of the MS4 to the area waterbodies and the potential impacts discharges could have on surface waters of the state.	Posting of the training video "When it Rains, it Drains…The Stormwater Question" on the district webpage.	Ongoing Throughout Permit Cycle	Educate the public on local water bodies, water quality issues, and impacts of discharges on surface waters through visual media.	Update webpages as necessary. Confirm posting & track webpage reviews.	Students, faculty, and community	Flushing Community Schools
	Include information and links to USEPA and EGLE Stormwater information on district stormwater webpage.		Provide resources to water quality issues and impacts of discharges on surface waters.	Update webpages as necessary. Confirm posting of links & track webpage reviews.		
	SEMCOG posters placed strategically throughout the district.		Maintain three (3) various SEMCOG posters at each facility. Strategic locations include Main Office, Lounge, and Receiving Area (if available).	Annual review of postings. Number of posters placed throughout district.		
	General Stormwater Awareness Training	Ongoing Throughout Permit Cycle	Encourage teachers, administrative and support staff to watch the General Awareness Stormwater Video "When it Rains it Drains".	Copy of sign in sheets and Agenda (if available).	Faculty	
			Post stormwater training video on stormwater webpage.	Update webpages as necessary. Confirm posting & track webpage reviews.	Students, faculty, and community	

Development Date: May 17, 2025
Revision Date: February 10, 2025
Revision Date: May 27, 2025

BMP Topic	Description of BMP	Timeframe	Measurable Goal & Key Messages	Measure of Assessment	Target Audience	Responsible Party
BMP #2.2.3.3 Educate the Public on Illicit Discharges and promote public reporting of illicit discharges and improper disposal of materials into the MS4.	Publicize 24-hour environmental hot-line phone numbers and instructions for reporting spills, illicit discharges, or connections.	Ongoing Throughout Permit Cycle	Track # of calls received on hotline per year. All calls to be addressed and record outcome of calls. Goal of an overall decrease in number of illicit discharges in improper disposal of materials into MS4s.	Number of calls to the Stormwater Manager.	Students, faculty, and community	Flushing Community Schools
			Place 24-hour environmental hot-line posters throughout the district.	Promotion/ publicizing efforts; number of posters placed throughout district.		
	Pollutants & Illicit Discharges webpage; featuring information regarding sources of pollution, how pollutants cause damage, illicit discharges. How to Report/Hotline Numbers poster; describing illicit discharges and how to report illicit discharges.		Maintain illicit discharge webpage.	Update webpages as necessary. Confirm posting & track webpage reviews.		
			Place "How to spot illicit discharge/ How to Report-Hotline Numbers" posters placed in Receiving Rooms at each district facility. Goal is to have one poster at each facility.	Annual review of postings. Number of posters placed throughout district.		
	SEMCOG posters placed strategically throughout the district.		Goal to maintain three (3) various SEMCOG posters at each facility. Strategic locations include Main Office, Lounge, and Receiving Area (if available).	Annual review of postings. Number of posters placed throughout district.		
	The district implements an active storm drain labeling/ marking program.	Update as needed Throughout Permit Cycle	Visually making a connection of storm drains to local waterways and the impacts of dumping pollutants into these drains, increase number of staff, students and visitors who can identify the connection. Mark all drains on pervious surfaces.	Annual inventory of stenciled basins.		

BMP Topic	Description of BMP	Timeframe	Measurable Goal & Key Messages	Measure of Assessment	Target Audience	Responsible Party
BMP #2.2.3.4 Promote preferred cleaning materials and procedures for car, pavement, and power washing.	SEMCOG posters placed strategically throughout the district.	Ongoing Throughout Permit Cycle	Goal to maintain three (3) various SEMCOG posters at each facility. Strategic locations include Main Office, Lounge, and Receiving Area (if available).	Annual review of postings. Number of posters placed throughout district.	Students, faculty, and community	Flushing Community Schools
	Discontinue practice of allowing school or other private groups from holding car wash fund raising project on school property.	Annually Throughout Permit Cycle	Send reminder email notice to all school Principals, Athletic Directors regarding the policy.	Copy of annual notice.	Faculty & students	
BMP #2.2.3.5 Inform and educate the public on proper application and disposal of pesticides, herbicides, and fertilizers.	Maintain a district "Good Housekeeping" informational page on stormwater management webpages.	Ongoing Throughout Permit Cycle	Address the environmental (including water quality) and resulting from improper handling and disposal of pesticides, herbicides, and fertilizers.	Update webpages as necessary. Confirm posting & track webpage reviews.	Students, faculty, and community	Flushing Community Schools
	SEMCOG posters placed strategically throughout the district.		Goal to maintain three (3) various SEMCOG posters at each facility. Strategic locations include Main Office, Lounge, and Receiving Area (if available).	Annual review of postings. Number of posters placed throughout district.		

BMP Topic	Description of BMP	Timeframe	Measurable Goal & Key Messages	Measure of Assessment	Target Audience	Responsible Party
BMP #2.2.3.6 **Promote proper disposal practices for grass clippings, leaf litter, and animal wastes that may enter into the MS4.**	SEMCOG posters placed strategically throughout the district.	Ongoing Throughout Permit Cycle	Goal to maintain three (3) various SEMCOG posters at each facility. Strategic locations include Main Office, Lounge, and Receiving Area (if available).	Annual review of postings. Number of posters placed throughout district.	Students, faculty, and community	Flushing Community Schools
BMP #2.2.3.7 **Identify and promote the availability, location, and requirements of facilities for collection and disposal of household hazardous wastes, travel trailer wastes, chemicals, and motor vehicle fluids.**	Maintain a district "Household Hazardous Waste" informational page on stormwater management webpages.	Ongoing Throughout Permit Cycle	Address the environmental (including water quality) and public health effects resulting from improper handling and disposal of household hazardous waste, reduce the use of home toxics, keep citizens informed about the choices and responsibilities associated with purchasing, handling, and disposing of toxic substances. Increase the number of residents using the program to dispose of home toxics.	Update webpages as necessary. Confirm posting & track webpage reviews.	Students, faculty, and community	Flushing Community Schools
BMP #2.2.3.8 **Inform and educate the public on proper septic system care and maintenance, and how to recognize system failure.**	Maintain a district "Sewer Overflows and Septic Systems" informational page on stormwater management webpages.	Ongoing Throughout Permit Cycle	Educate why sewer overflows and septic systems are pollution issues. Promote proper and consistent maintenance of septic systems.	Update webpages as necessary. Confirm posting & track webpage reviews.	Students, faculty, and community	Flushing Community Schools

BMP Topic	Description of BMP	Timeframe	Measurable Goal & Key Messages	Measure of Assessment	Target Audience	Responsible Party
BMP #2.2.3.9 Promote methods for managing riparian lands to protect water quality.	Maintain a district "Riparian Zone Management" informational page on stormwater management webpages.	Ongoing Throughout Permit Cycle	Educate on why riparian zones are important, what riparian zona management is (river friendly lawn care, riparian buffer zones, stream bank stabilization, woody debris management, river maintenance). Increase number of riparian landowners who implement BMPs.	Update webpages as necessary. Confirm posting & track webpage reviews.	Students, faculty, and community	Flushing Community Schools
	Encourage teachers and students to participate in stream bank monitoring programs.		Increase awareness, inspire people to take actions that lead to better river protection at home and in their communities.	Report on schools that participated in monitoring programs.	Students and faculty	
	Include guidance and links on Stormwater webpage on native vegetation.	Ongoing Throughout Permit Cycle	Maintain a district "Native, Non-Native, & Invasive Species" and "Why Use Native Plants?" informational page on stormwater management webpages. Increase the use of native plants and encourage the use of gardens at school facilities.	Update webpages as necessary. Confirm posting & track webpage reviews.	Students, faculty, and community	Flushing Community Schools
BMP #2.2.3.10 Stormwater Education Program Effectiveness Survey	Post survey on district website	Annually Throughout Permit Cycle	A survey has been posted on the stormwater webpages and will be posted throughout the permit term to ascertain behavioral changes.	Annual results of survey.	Students, faculty, and community	Flushing Community Schools
BMP #2.2.3.11 Public Education Program Effectiveness Assessment	Summary of annual public education activities for the "Public Education" component to evaluate the effectiveness.	Annually Throughout Permit Cycle	Determine if the public education best management practices have been implemented and identify areas of improvement.	Annual SWMP review. Summary of public education activities. Survey results review.	Students, faculty, and community	Flushing Community Schools

2.2.4 Public Education Program Effectiveness

The effectiveness of the public education program will be evaluated based on progress made towards meeting the BMP objectives described above.

The District has implemented a "Watershed Awareness Survey" to be used as an evaluation. The purpose of these surveys is to provide an assessment of public understanding of issues in the watershed related to pollution from stormwater runoff. Results would be used to guide Flushing Community Schools in identifying opportunities for enhancement of the PEP. Additionally, Flushing Community Schools will conduct an annual review of the public education best management practices to determine if they have been implemented and identify areas of improvement.

2.3 Illicit Discharge Elimination Program (IDEP)

The following Flushing Community Schools Illicit Discharge Elimination Program is designed to identify, locate, prohibit, and effectively eliminate illicit discharges, including discharges of sanitary wastewaters, to the permitted separate stormwater drainage systems.

2.3.1 Illicit Discharge Elimination Program (IDEP) Program Objectives

1. Establish authority to investigate, inspect and monitor suspected illicit discharges.
2. Maintain maps of the MS4, points of discharge, and outfalls.
3. Prohibit non-stormwater discharge into the MS4.
4. Provide regular training to staff.
5. Instruct contractors to prevent dumping into the MS4.
6. Conduct routine dry weather screening.
7. Conduct source investigations if the source of an illicit discharge/connection is not identified by field screening.
8. Illicit discharge identification and elimination program performance & effectiveness.

2.3.2 Facility Site Storm Sewer System Maps and Lists

Flushing Community Schools and consultants completed storm sewer system mapping at each of the owner operated properties identified in Section 1.0 of this Stormwater Management Plan. Storm sewer system maps include detailed information of the storm sewer system, including the locations of outfalls, points of discharge, and waters of the State that receive the discharges. The maps include a unique identification number for each storm sewer location identified on the map. Latitude and longitude are also noted for outfall and points of discharge location. Storm sewer system information will be maintained and updated and reported in Progress Reports.

Outfalls are discharge points where stormwater is discharged directly to surface waters of the state. Surface waters of the state include streams, lakes, ponds, county drains, and wetlands. Outfalls can be pipes, ditches, or even sheet flow from the facility. Some facilities will have an outfall where they can manually control the discharge.

Points of Discharge are discharge points where stormwater is discharged to a municipal or private separate storm sewer system. The visual assessment will be conducted as close to the point of discharge as possible before the storm water enters the municipal or private separate storm sewer system. Points of discharge include on-site catch basins and trench drains, in-street catch basins, and conveyances to roadside ditches.

Copies of the current facility storm sewer system maps are available at the Bus Garage and Maintenance building. Additionally, copies of the storm sewer system maps and a list of the outfalls and points of discharge are provided in Appendix A.

2.3.3 Illicit Discharge Identification & Investigation Procedure – Field Observations

Flushing Community Schools will conduct field observations for 100% of all outfalls and points of discharge locations during dry weather or more expeditiously if Flushing Community Schools becomes aware of a non-stormwater discharge. Outfalls and points of discharge will be inspected by personnel trained to recognize all signs of possible illicit discharges. Dry weather screening will occur at once per permit cycle. Flushing Community Schools will conduct DWS once during this 5-year permit cycle. Preferably, each outfall and points of discharge will be inspected and evaluated following a period of at least 48-72 hours of dry weather.

The field observations will focus on visual inspection for the following:

- Outfall/point of discharge number
- Date/name of inspector
- Date of last rainfall
- Presence or absence of flow
- Presence or absence of standing water
- Water clarity and color
- Presence of oil sheen, trash and or other floatable materials
- Presence of bacterial sheen or slimes
- Excessive vegetative growth
- Odor
- Suds
- Presence of oil

❖ These characteristics are documented even if no flow is observed at the time of the inspection.

All field observations are detailed on a "Screening Inspection Log". A copy of the Screening Inspection Log is provided in Appendix D.

During field observations, in instances where the storm sewer outfalls and points of discharge is submerged or is connected to another enclosed sewer, the inspector will observe the nearest upstream storm sewer location or access point. Additionally, if dry weather flow is observed and it is obvious that an illicit discharge is present and the source of the discharge is obvious, Flushing Community Schools will document the observations and the source and follow-up with applicable parties. Once a potential discharge is indicated at an outfall or point of discharge, additional inspection, field screening and source investigation activities are conducted.

2.3.4 Illicit Discharge Identification & Investigation Procedure – Field Screening & Source Investigation

At the time of the outfall or discharge point inspection, if dry weather flow is observed and the source is not obvious, the inspector who identified the discharge shall immediately conduct an upstream source investigation to determine the origin of the flow. The initial investigation will include visual and olfactory observations upstream from the outfall/point of discharge. If necessary, relevant indicator field screening or dye tracing will be conducted.

If the origin of the flow is not identified during the visual upstream investigation, a grab sample is collected within 24 hours from the discharge for indicator field screening analysis. Indicator field screening is a secondary tool utilized to help determine the source of dry weather flow when there are no obvious indicators such as very high turbidity, strong odors, or visible discharge. The determination of which field screening parameters to use to determine dry weather flow may be determined based on the site conditions, visual observations, and olfactory observations.

Additional grab samples may be collected and delivered for external laboratory analysis, if additional test parameters are needed for the source investigation. The laboratory analysis parameters for grab samples will be determined based on the suspected source of the flow during the source investigation.

Field screening and laboratory analysis parameters may include the following with the associated action level[3]:

- **pH** (Action Level: <6.5 or >9.0)
- **E. coli** (Action Level: >1,000 CFU)
- **Surfactants** (Action Level: >0.5 mg/l)
- **Ammonia** (Action Level: >1.0 mg/l)

Once the source has been isolated down to a specific site location through field investigation, field screening, and/or laboratory analysis, the work for source confirmation will begin. Additional fieldwork, building evaluation, and/or dye testing may be necessary to confirm the source of the flow. Continued source investigations will be conducted, if needed, within 14 days of the original observed dry weather flow.

2.3.5 Illicit Discharge/Connection Elimination Procedure

Illicit discharges and connections are identified through reporting, routine storm sewer system inspections and dry weather screening inspections. A "How to Spot Illicit Discharges" poster along with a "How to Report/Hotline Numbers" posters are placed in the receiving/custodial areas in each facility to report concerns. Flushing Community Schools goal is to evaluate all potential unauthorized or suspected illicit discharge to the municipal separate storm sewer system (MS4) and perform any necessary notifications and reporting to the applicable agencies (i.e., EGLE, local drain commission, etc.) within the required time period(s).

Flushing Community Schools will evaluate and conduct the following actions regarding reported or observed illicit discharges/illegal dumping spills into the storm drainage system.

- Suspected discharges will be investigated within 24 hours. The Flushing Community Schools will ensure enforcement actions within 7 days.
- Conduct source investigations, including applicable field screening to trace the origin of the materials within 14 days of the reported/observed illicit discharge.
    - Flushing Community Schools will follow existing spill response procedures outlined in Section 2.3.10, under Spill Response, Policy & Procedures, if required.
- Once the source has been isolated down to a specific site location, the work will become source confirmation.

[3] Action levels were determined based on the EGLE Municipal Separate Storm Sewer System (MS4) Program – Dry-Weather Screening: A Guide for Permittees

- If the responsible party is identified, educate the party on the impacts of their actions, explain the stormwater requirements, and provide information regarding Best Management Practices.
- Evidence of illicit discharges traced to other MS4 jurisdictions will be provided to the responsible MS4 operator along with any collected data to assist that MS4 operator in completing their investigations to correct the illicit discharge or connection.
- Flushing Community Schools will cooperate with the MS4 operator in determining the source or type of illicit discharge and/or connection and will follow-up to ensure that appropriate action has been completed by the MS4 operator to eliminate the discharge.
- Continue inspection and follow-up activities until the illicit discharge activity has ceased.
- Document all activities utilizing the Illicit Discharge/Illegal Dumping Reporting form.

A copy of the Illicit Discharge/Illegal Dumping Reporting form is located in Appendix B.

Once an illicit discharge has been confirmed from a Flushing Community Schools facility, the discharge will be corrected using the most expedient method possible based on the type and configuration of the discharge or connections. Other illicit discharges or releases of polluting materials will be corrected through administrative measures including employee training, placement of signs or markings, policy revisions, or any other steps necessary to eliminate the continued release of polluting materials to the MS4.

Within 60 days of a confirmed illicit connection from a Flushing Community Schools facility, Flushing Community Schools will take steps to fix or eliminate the illicit connection. These steps include a review of corrective methods to be used to repair or eliminate the connection, determine the length of time the repair or elimination will take to complete, the cost of the elimination, the pollution potential and consider how the removal of the illicit connection will be confirmed. Corrective methods include capping, closing, or re-routing illicit connections to the sanitary sewer or other collection systems.

2.3.6 Illicit Discharge Regulatory Mechanism/Policy

The district developed a “Stormwater Management – Illicit Discharge Regulatory Policy”. This illicit discharge regulatory policy was developed as a regulatory policy for prevention of pollution from storm water runoff and to protect the quality of the waters of the State of Michigan through the regulation of non-stormwater discharges to the municipal separate storm sewer system (MS4) to the maximum extent practicable as required by federal and state law. This regulatory mechanism establishes methods for controlling the introduction of pollutants into the MS4 in order to comply with the requirements of the National Pollutant Discharge Elimination System (NPDES) permit through the Michigan Department of Environment, Great Lakes, and Energy (EGLE). The objectives of the regulatory mechanism are:

Department of Environment, Great Lakes, and Energy (EGLE). The objectives of the regulatory mechanism are:

1. To regulate the contribution of pollutants to the MS4 by stormwater discharges by any user.
2. To prohibit illicit connections and discharges into the MS4.
3. To establish authority to investigate, inspect, and monitor suspected illicit discharges.

Flushing Community Schools has a board policy resolution to direct compliance with these requirements. The Flushing Community Schools updated School Board Resolution was passed in June 2023. A copy of the passed School Board Policy is provided in Appendix B.

The Stormwater Program Manager or designee will be provided full access to all the district facilities and properties owned and operated by the district as required to inspect, investigate, and monitor suspected or confirmed illicit discharges or connections to the MS4.

The district stormwater webpage includes information on how to notify the district if a discharge is witnessed taking place. Finally, the "Stormwater Management – Illicit Discharge Regulatory Policy" will be emailed to district staff members and/or posted on the district stormwater webpage. The "Stormwater Management – Illicit Discharge Regulatory Policy" is available in Appendix B.

Illicit Discharge means any discharge to, or seepage into the separate stormwater drainage system that is not composed entirely of stormwater or uncontaminated groundwater except discharges pursuant to an NPDES permit. Illicit discharges include but are not limited to the following:

- Dumping of motor vehicle fluids
- Improper disposal of household hazardous wastes
- Grass clippings
- Leaf litter
- Pet & other animal wastes
- Unauthorized discharges of sewage
- Industrial wastes
- Restaurant wastes
- Vehicle & equipment wash waters
- Any non-stormwater waste

All activities are documented utilizing the Illicit Discharge/Illegal Dumping Reporting form.

Illicit Connection means a physical connection to the MS4 separate stormwater system that primarily conveys non-stormwater discharges other than uncontaminated groundwater into the MS4 separate storm sewer system; or a physical connection not authorized or permitted by the local authority, where a local authority requires authorization or a permit for physical connections.

Flushing Community Schools' policy is to eliminate all illicit connections or discharges from their facilities and restrict the discharge of polluting substances to the separate storm sewer system. The process to achieve these goals will consist of the inspection and screening of all storm sewer systems and elimination of any improper connection from any Flushing Community Schools facility to any waterway or the municipally owned separate storm sewer system (MS4).

<u>Prohibitions of Illicit Discharges</u>

1. Prohibition of Illicit Discharges:
    a. Flushing Community Schools prohibits the discharge of non-stormwater discharges into the storm drain system, including but not limited to pollutants or waters containing any pollutants.
2. The following discharges are NOT prohibited:
    a. This policy excludes prohibitions from the discharge or flows from firefighting activities to the Flushing Community Schools MS4. Discharge or flows from firefighting activities will be addressed only if they are identified as significant sources of pollutants to surface waters of the state.

b. The following activities are not prohibited under this policy unless they are determined to be significant sources of pollutants to surface waters of the state:
    - Water line flushing and discharges from potable water sources.
    - Landscape irrigation runoff, lawn water runoff, and irrigation waters.
    - Diverted stream flows and flows from riparian habitats and wetlands.
    - Rising groundwater and springs.
    - Uncontaminated groundwater infiltration and seepage.
    - Uncontaminated pumped groundwater, except groundwater cleanups specifically authorized by NPDES permits.
    - Foundation drains, water from crawl space pumps, footing drains, and basement sump pumps.
    - Air conditioning condensation.
    - Waters from noncommercial car washing (runoff from family home).
    - Street wash water.
    - Dechlorinated swimming pool water from single, two, or three family residences. (A swimming pool operated by the permittee shall not be discharged to a separate storm sewer or to surface waters of the state without NPDES permit authorization from EGLE.)

Identifying a discharge or flow as a significant contributor is completed on a case-by-case basis and is dependent on many factors, including the type of pollutant, amount discharged, and impacts to surface waters of the state.

Prohibition of Illicit Connections

1. Improper connections in violation of this regulatory mechanism must be disconnected and redirected.
2. Illicit discharge and connections will be eliminated.
3. The construction, use, maintenance, or continued existence of illicit connections to the storm drain system is prohibited by Flushing Community Schools. This prohibition expressly includes, without limitation, illicit connections made in the past, regardless of whether the connection was permissible under law or practices applicable or prevailing at the time of connection.

2.3.7 Illicit Discharge Elimination Training

A training program is an important component of an effective IDEP. Training is required for all employees whose job responsibilities involve illicit discharge related activities, or indicate a potential to cause, witness, or report an illicit discharge or connection. Training is discussed in detail in Section 3.0 of this SWMP.

2.3.8 Illicit Discharge Elimination Program Effectiveness

Flushing Community Schools is required to track implementation of the illicit discharge elimination program stormwater management items and evaluate its effectiveness. Documentation of these items includes documents of actions taken to eliminate illicit discharges. The following are examples of the types of performance measures and effectiveness measures that may be used to evaluate the effectiveness of the IDEP program. The following information will be reviewed annually, and will be used to focus and modify activities to maximize environmental benefits of the plan:

- Verify the distribution of public education posters.
- Number of outfalls/discharge points screened.

- Number of illicit connections found.
- Number of illicit connections eliminated.
- Number and type of discharges that are investigated.
- Actions conducted to follow-up discharges that are identified or reported.
- Number of scheduled clean-outs and routine maintenance work conducted.

The District shall evaluate:

1. Evaluate the number of illicit discharges and determine if discharges have decreased throughout the permit cycle.
2. Evaluate if the number of reported potential discharges has increased due to improved awareness.
3. Evaluate dry weather screening monitoring data to measure changes in water quality.

2.3.9 Illicit Discharge Elimination Program – BMP Table

BMP	Description of BMP	Timeframe	Measurable Goal	Measure of Assessment	Responsible Party
BMP #2.3.9.1 Facility Storm Sewer System Maps	Provide an up-to-date storm sewer system map. The maps shall identify the storm sewer system, location of outfalls and points of discharge, and names and locations of the surface waters of the state receive the discharge.	Maps Completed in 2023 Updates Ongoing as Needed throughout Permit Cycle Within 30 days of new outfalls, discharge points, structures, and conveyances.	100% of facilities mapped, and 100% of storm sewer system updates mapped.	Bus Garage and Maintenance, 4335 N Seymour Rd, Flushing, MI 48433	Flushing Community Schools
				Update facility map with sewer system updates. Maintain maps for progress report submittal.	Flushing Community Schools
BMP#2.3.9.2 Enforcement	Written policy to enforce elimination of illicit discharges into MS4 owned by the Permittee.	Illicit Discharge Regulatory Policy Developed and Board Resolution Passed June 2023	Illicit Discharge Regulatory Policy developed, and Board Policy Resolution reviewed and approved by the school board.	Copy of the Illicit Discharge Regulatory Policy and Approved Board Resolution	Flushing Community Schools
				Copy of policy available on the district stormwater webpage or emailed to staff.	
BMP #2.3.9.3 Dry Weather Screening	Dry Weather Screening conducted once per permit cycle. Dry weather screening will be conducted by personnel trained to recognize all signs of possible illicit discharges.	DWS Scheduled to be completed once during the permit cycle	100% of outfalls and point of discharges inspected and evaluated following a period of 48-72 hours of dry weather. Outfalls/points of discharges re-inspected if necessary.	Maintain dry weather screening inspection logs/reports.	Flushing Community Schools

BMP	Description of BMP	Timeframe	Measurable Goal	Measure of Assessment	Responsible Party
BMP #2.3.9.4 Illicit Discharge Reporting	Eliminate illicit discharges and connections through reporting, routine storm sewer system inspections and dry weather screening inspections.	Ongoing Throughout Permit Cycle	Place "How to spot illicit discharge/ How to Report-Hotline Numbers" posters placed in Receiving Rooms at each Flushing Community Schools facility. Goal is to have one poster at each facility.	Annually verify number of posters in place throughout the district.	Flushing Community Schools
			Advertise reporting hotline on district webpage.	Track number of calls and document calls onto Illicit Discharge/Illegal Dumping Reporting form. (Appendix B).	
BMP #2.3.9.5 Unauthorized Discharge/ Illicit Discharge Complaint Response	The district will immediately evaluate any potential unauthorized or suspected illicit discharge to the municipal separate storm sewer system (MS4) and perform any necessary notifications and reporting to the applicable agencies (i.e., EGLE, local drain commission, etc.) within the required time period(s). This procedure is outlined in Section 2.3.10 Polluting Materials Emergency and Spill Response Policy & Procedures.	Suspected discharges will be investigated within 24 hours. The Flushing Community Schools will ensure enforcement actions within 7 days.	100% of unauthorized or suspected illicit discharges evaluated (field observation, field screening, and source investigation) and eliminated.	Documentation of relevant field observations, field screening or source investigations.	Flushing Community Schools
		Within 14 days of reported suspected discharge.			
BMP #2.3.9.6 Illicit Connections	Reroute, repair, or disconnect any illicit connections.	Within 60 days of identified illicit connection	Take steps to eliminate 100% of identified illicit connections.	Work order, receipt or report detailing the illicit connection correction activities.	Flushing Community Schools
BMP #2.3.9.7 Illicit Discharge Elimination Training	Train staff on the identification and reporting of illicit discharges or improper connections and the cleanup/notification procedures for spills of polluting materials.	Once per permit cycle or during the 1st year of employment Throughout Permit Cycle	Goal of providing illicit discharge elimination training to all maintenance, transportation, custodial and skilled trade staff who work for Flushing Community Schools. **[All Stormwater Training is outlined in Section 3.0 Training]**	Copy of sign in sheets and Agenda (if available).	Flushing Community Schools

BMP	Description of BMP	Timeframe	Measurable Goal	Measure of Assessment	Responsible Party
BMP #2.3.9.8 Notice of Intent to Discharge Tracer Dyes	Maintain approval from the EGLE for authorization to discharge tracer dyes in surface waters per General Rule 97 to conduct source investigations.	As needed Throughout Permit Cycle	EGLE approval to discharge tracer dyes.	Documentation of EGLE approval.	Flushing Community Schools
BMP #2.3.9.9 IDEP program Performance & Effectiveness	Review performance measures to evaluate the effectiveness of the IDEP program. Items include posting of IDEP public education posters, number of outfalls/discharge points screened, number of illicit connections found, number of illicit connections eliminated, number and type of violations investigated, and number of scheduled clean-outs and routine maintenance work conducted.	Annually Throughout Permit Cycle	Annual review of SWMP IDEP program performed. Evaluate reduced illicit discharges, increase reporting, and evaluate dry weather screening data.	Maintain copy of SWMP annual review and evaluation information for progress reporting.	Flushing Community Schools

2.3.10 Polluting Materials Emergency and Spill Response Policy and Procedures

Purpose

This policy and associated procedures have been developed to define appropriate and safe response procedures for spill or accidental releases of hazardous materials or substances at all Flushing Community Schools' facilities.

Policy

Only trained and authorized personnel are permitted to respond to hazardous materials incidents! Employees must be trained in the safe use of chemicals or chemical management prior to working in a lab or cleaning up minor spills. The Stormwater Program Manager will immediately report any release of any polluting materials from the MS4 to surface waters or groundwater of the state, unless a determination is made that the release is not in excess of the threshold reporting quantities in the Part 5 Rules and comply with all Federal, State, and local regulatory requirements for the management and reporting of all hazardous materials and/or waste releases.

If it is determined that the release poses a threat to the safety or the environment outside the facility or in excess of the threshold reporting quantities, the Stormwater Program Manager will report the release immediately or within 24 hours of knowledge of the release to:

- The EGLE Lansing District Office at (517) 284-6651 during regular working hours.
- The 24-hour Michigan Pollution Emergency Alerting System (PEAS) at 1-800-292-4706 after working hours.

Any release of oil (includes gasoline, diesel fuel, used oil and mineral spirits) to navigable waters or adjoining shorelines will be reported to the immediately or within 24 hours of knowledge of the release to:

1. The 24-hour National Response Center (NRC) at 1-800-424-8802

The Stormwater Program Manager will maintain responsibility for monitoring any changes in regulatory requirements regarding hazardous materials and waste spills or accidental releases. This policy will be revised as necessary based upon any changes in the regulatory requirements or internal experiences. All hazardous materials spills or releases will be thoroughly investigated by the Stormwater Program Manager.

Emergency Spill Response Procedures

Each facility having the potential for the release of a hazardous material or substance shall have trained and knowledgeable staff members to respond and/or implement spill response procedures for that facility. Spill containment materials such as absorbent pigs, pads, booms, diking materials, storm drain covers, etc. are to be stored and maintained at all facilities for use by trained employees in the event of a spill or accidental release.

The following general guidelines are to be implemented as applicable in managing spills and accidental releases:

1. **Minor Spill or Leak**

- Attempt to contain the spill.
- Wear proper Personal Protective Equipment (PPE) while cleaning up the spill/leak.
- Notify supervisor and call Stormwater Program Manager at (810) 955-8682.

2. **Major Spill or Leak**

- Call the Stormwater Program Manager immediately at (810) 955-8682.
- Do not attempt to clean up the spill yourself.
- Provide clean-up/rescue personnel with appropriate Safety Data Sheets (SDS) and other important information.

Refer to sections **2.3.4 Illicit Discharge Identification & Investigation Procedure – Field Screening & Source Investigation** and **2.3.5 Illicit Discharge/Connection Elimination Procedure** for implementation timeframes.

This guidance has been developed in anticipation of potential releases of hazardous materials and substances. The procedures outlined in this guidance will only be implemented by those people who have received sufficient training and are competent in the handling of the released material.

As appropriate, illicit discharges or releases of polluting materials will be corrected through administrative measures including employee training, placement of signs or markings, policy revisions, or any other steps necessary to eliminate the continued release of polluting materials to the MS4. The district will conduct follow-up inspections and sampling as needed to ensure that appropriate action has been completed.

2.4 Construction Site Stormwater Runoff Control Program

Flushing Community Schools' goal is to establish procedures for construction stormwater runoff control to meet minimum measure requirements to maximum extent practicable.

Construction refers to actions that result in a disturbance of the land, including clearing, grading, excavating, and other similar activities.

Construction-related activities are activities that support the construction project such as stockpiles, borrow areas, concrete truck washouts, fueling areas, material storage areas and equipment storage areas.

2.4.1 Construction Site Stormwater Management Program Objectives

A. Process for notifying the Part 91 Agency appropriate staff when soil or sediment is discharged to the MS4 from a construction activity.
    - The procedure shall allow for the receipt and consideration of complaints or other information submitted by the public or identified internally as it relates to construction stormwater runoff control.
B. Procedure for when to notify the EGLE when soil, sediment, or other pollutants are discharged to the MS4.
    - Other pollutants include pesticides, petroleum derivatives, construction chemicals, and solid wastes that may become mobilized when land surfaces are disturbed.
C. Procedure for ensuring that construction activity one acre or greater in total land disturbance obtains a Part 91 Permit.

2.4.2 Construction Notification Procedure

The EGLE certified construction stormwater operator inspector conducting site inspections will normally detect any soil or sediment entering the MS4.

In the event an inspector identified a discharge during an inspection:

1. The inspector shall document all details of the soil erosion and sedimentation control deficiency and report to the Flushing Community Schools Stormwater Manager.
2. The Flushing Community Schools Stormwater Manager (or designee) is responsible for assessing any suspected or confirmed discharge and notifying the appropriate agency.
3. Flushing Community Schools will notify the local Part 91 agency and EGLE when significant runoff of soil, sediment, or other pollutants such as pesticides, petroleum derivatives, construction chemicals, or solid wastes from the construction site discharges to the MS4 or surface waters of the state within 24 hours of discovery or as otherwise required by the issuing agency.

In the event of a public complaint:

Flushing Community Schools will track the receipt of complaints submitted by the public or noted by staff during regular course of business of soil, sediment, or other pollutants such as pesticides, petroleum derivatives, construction chemicals, and solid wastes are being discharged into the MS4.

The tracking will include:

- Name of person providing the complaint.
- Location (address or nearest cross street).
- Description of follow up (e.g., date referred to the Part 91 enforcing agency).

Flushing Community Schools will notify the Part 91 Agency, when soil, sediment, and other pollutants such as pesticides, petroleum derivatives, construction chemicals, and solid wastes are discharged into MS4.

Flushing Community Schools ensures that construction activity one acre of greater in total earth disturbance with the potential to discharge to the MS4 does obtain a Part 91 Permit and State of Michigan Permit by Rule.

2.4.3 Part 91 Permit

Flushing Community Schools will ensure that any construction activity that result in a land disturbance meeting the following criteria:

- Greater than or equal to one (1) acre, or
- Disturb less than one (1) acre that is part of a common plan of development or sale.

Will obtain a Part 91 Permit through the site plan review process with the appropriate county or municipal permitting agency.

2.4.4 Permit by Rule Compliance

Flushing Community Schools shall comply with the State of Michigan Permit by Rule (Rule 323.2190) for stormwater discharge from construction activity. Sites disturbing one (1) to five (5) acres with a point source discharge to the waters of the state receive automatic storm water coverage upon securing a SESC permit from the appropriate Part 91 recognized County Enforcing Agency, Municipal Enforcing Agency, or Authorized Public Agency (APA) under the authority of Part 91.

1. Construction sites with at least one (1) acre but less than five (5) acres of soil disturbance with a surface water discharge, must obtain a county or municipal SESC permit, and are required to follow the provisions of the Permit by Rule, but do not need to notify the EGLE of the construction activity.
2. Construction sites disturbing over five (5) acres with a point source discharge to the waters of the state must obtain a county or municipal SESC permit and submit a Notice of Coverage (NOC) and other pertinent documents and the appropriate fee to the EGLE.

Requirements of Permit by Rule include, but are not limited to:

- Weekly site inspections conducted by a Certified Construction Stormwater Operator.
- Inspection within 24 hours of a precipitation event that results in a discharge from the site by a Certified Construction Stormwater Operator.

2.4.5 Construction Site Stormwater Management-BMP Table

BMP	Description of BMP	Timeframe	Measurable Goal	Measure of Assessment	Responsible Party
BMP #2.4.5.1 Notification of Deposit during Inspection	Flushing Community Schools will notify the local part 91 agencies or EGLE when runoff from the construction site discharges significant pollutants to the MS4 or surface waters of the state within 24 hours of discovery or as otherwise required by the issuing agency. The Flushing Community Schools Stormwater Manager (or designee) is responsible for assessing any suspected or confirmed discharge and notifying the appropriate agency. (Refer to section 2.4.2)	As necessary Throughout Permit Cycle	100% discharges identified and appropriate agencies notified. Control of potential system failure.	Documentation of Construction Stormwater Operator site inspection.	Flushing Community Schools
	Track complaints submitted by the public or noted by staff during regular course of business of soil, sediment, or other pollutants such as pesticides, petroleum derivatives, construction chemicals, and solid wastes are being discharged into the MS4.			Documentation of public complaint (Name of person providing the complaint, location [address or nearest cross street] description of follow up [e.g., date referred to the Part 91 enforcing agency]).	Flushing Community Schools
BMP #2.4.5.2 Part 91 Permit	Flushing Community Schools will ensure that any construction activity that result in a land disturbance greater than or equal to one (1) acre or disturb less than one (1) acre that is part of a common plan of development or sale will obtain a Part 91 Permit through the site plan review process.	As necessary Throughout Permit Cycle	100% of permits obtained.	Copy of permit and associated soil erosion and sedimentation control plans.	Flushing Community Schools

BMP	Description of BMP	Timeframe	Measurable Goal	Measure of Assessment	Responsible Party
BMP #2.4.5.3 Permit by Rule	Construction sites between (1) acre but and five (5) acres of soil disturbance follow the provisions of the Permit by Rule, but do not need to notify the EGLE of the construction activity.	As necessary Throughout Permit Cycle	Goal of 100% of weekly and precipitation event inspection completed by certified Construction Stormwater Operator.	Copy of inspections.	Flushing Community Schools
	Construction sites disturbing over five (5) acres with a point source discharge to the waters of the state must follow provisions of the Permit by Rule and submit a Notice of Coverage (NOC) and other pertinent documents and the appropriate fee to the EGLE.		100% NOC obtained.	Copy of NOC	Flushing Community Schools

2.5 Post Construction Stormwater Controls for New Developments & Redevelopments

Post-construction storm water runoff is the storm water that would flow from a project site to the Municipal Separate Storm Sewer System (MS4) after completion of a development or redevelopment project (not during the project).

A post-construction stormwater runoff program compliance assistance document is available via the internet at https://www.michigan.gov/documents/deq/wrd-storm-MS4-ComplianceAssistance_470350_7.pdf.

2.5.1 Post Construction Stormwater Management Program Objectives

The post-construction stormwater run-off controls are necessary to maintain or restore stable hydrology in receiving waters by limiting surface runoff rates and volumes and reducing pollutant loadings from sites that undergo development or significant redevelopment.

Projects that change the existing footprint (e.g., increase impervious surface) or offer new opportunities for storm water control (e.g., reconstruction to the subbase layer with a change in underdrainage) are considered redevelopment projects.

The objects of this program and associated procedures are to:

- Develop and implement regulatory mechanisms to address post-construction stormwater runoff for new development and redevelopment projects, including preventing or minimizing water quality impacts.
- Develop and implement regulatory mechanisms for projects that disturb one or more acre, including projects less than an acre that are part of a larger common plan of development or sale and discharge into the applicants MS4.
- Ensure post construction controls to minimize water quality impacts by following water quality treatment standards.
- Require that BMPs be designed on a site-specific basis to reduce post-development total suspended solids loading.
- Procedure to meet water quality treatment and channel protection standards of new development or redevelopment projects.
- Address “hot spots”.
- Require adequate long-term O&M of BMPs by ordinance or other regulatory means.

2.5.2 Post-Construction Policy and Procedure

The district has developed a “Stormwater Management - Post-Construction Policy & Procedure” to direct compliance with these requirements. The “Stormwater Management - Post-Construction Policy & Procedure” is located in Appendix B.

Development and redevelopment projects on district properties are regulated under and must comply with the Flushing Community Schools individual NPDES permit for stormwater discharges, as issued by the Michigan Department of Environment, Great Lakes and Energy (EGLE). The Stormwater Management Post-Construction Policy & Procedure has been developed to provide guidance regarding responsibilities and actions to meet the NPDES permit conditions for development and redevelopment projects on Flushing Community Schools properties.

The post-construction plan for stormwater management on regulated sites **must** include:

- A minimum treatment volume standard to address water quality impacts.
- Channel protection criteria to address resource impairment resulting from flow volumes and rates.
- Review sites with known soil and/or groundwater contamination, including potential "hot spots" and evaluate the use of infiltration BMPs to meet water quality treatment and channel protection criteria to ensure that infiltration BMPs do not exacerbate existing conditions. Hot spots include areas with the potential for significant pollutant loading such as vehicle service and maintenance facilities, vehicle equipment cleaning facilities, fleet storage areas for buses, and outdoor liquid container storage.
- Drawings showing the location of stormwater control measures and the storm system.
- Details on the proposed stormwater control measures.
- Operation & Maintenance (O&M) requirements.
- Supporting information:

    - Calculations used for designing all components of the stormwater management systems.
    - Total suspended Solids (TSS) design removal rates and supporting manufacturer documentation, if applicable.
    - Geotechnical report including soil boring and infiltration test data.

The project team [Architecture, Engineering & Construction, Other Project Manager, Project Developer and/or Contractors] shall develop the post-construction plan for stormwater management in accordance with this guideline and the NPDES permit.

Flushing Community Schools has developed and passed a board resolution in June 2023, to direct compliance with these requirements. In addition to the board policy resolution, the following sections identify specific actions to be taken by Flushing Community Schools to ensure compliance with the applicable standards. A copy of the signed Flushing Community Schools School Board Policy Resolution is provided in Appendix B.

The Stormwater Program Manager or designee will administer and enforce the stormwater management program, including maintaining procedures, guidance, information, etc. to aid district staff and contractors in complying with the post-construction requirements for stormwater management.

2.5.3 Water Quality Treatment Standard

Flushing Community Schools' goal is to include water quality treatment volume standards for each new construction or redevelopment project where the area of development or redevelopment exceeds one (1) acre. One or more of the following treatment standards will be included as part:

1) Treat the first one inch of runoff from the entire site, or
2) Treat the runoff generated from ninety percent (90%) of all runoff-producing storms for the project site.

The source of the rainfall data for the water quality treatment standard of requiring the treatment of the runoff generated from the ninety percent (90%) of all runoff-producing storms is:

- The EGLE memo dated March 24, 2006, which is available via the internet at http://www.michigan.gov/documents/deq/wrd-hsu-ninety-percent_557709_7.pdf

Treatment methods shall be designed on a site-specific basis to achieve the following:

1. A minimum of eighty percent (80%) removal of total suspended solids (TSS), as compared with uncontrolled runoff, or
2. Discharge concentrations of TSS not to exceed 80 milligrams per liter (80mg/L).

A minimum treatment volume standard is not required where site conditions are such that TSS concentrations in storm water discharges will not exceed 80mg/L.

Treatment methods shall be designed on a site-specific basis to reduce the discharge of sedimentation or TSS from the site. Such methods may include:

1. Standpipe filters in storm water detention basins
2. Sediment filter tanks
3. Catch basin sumps
4. Aqua-Swirls®
5. Treatment trains
6. Rain Gardens
7. Pervious pavement systems

2.5.4 Channel Protection Performance Standard

Flushing Community Schools understands that channel protection criteria are necessary to maintain post-development stormwater runoff volumes and peak flow rates at or below existing levels for all storms up to the 2-year, 24-hour event. “Existing Levels” means the runoff volume and peak flow rate for the last land use prior to the planned new development or redevelopment. More restrictive channel protection criteria may be utilized on a case-by-case basis, as appropriate.

Rainfall Data
The rainfall data for calculating runoff volume and peak flow rate shall be the Rainfall Frequency Atlas of the Midwest, 1992 [National Oceanic & Atmospheric Administration (NOAA) - Huff & Angel].

2.5.5 Site-Specific Requirements

Because each site has its’ own special circumstances and conditions, the following BMPs will be considered as appropriate according to site conditions:

- Reduce runoff from the site to greatest extent possible (provide holding basins, divert water through grassed swales).
- Prevent spills and discharges.
- Control waste such as building materials, concrete washout, chemicals, litter, and sanitary waste.
- Phasing will be considered to limit amount of exposed soils.
- Interim soils stabilization methods are to be considered (temporary seeding, mulching etc.).
- Buffer preservation (avoid exposing soils to property limits).
- Inspection staff will be trained in the proper maintenance and operation of Soil Erosion and Silt Prevention measures.

Construction plans will be reviewed for sites with known soil and/or groundwater contamination, including potential “hot spots” and evaluate the use of infiltration BMPs to meet water quality treatment and channel protection criteria to ensure that infiltration BMPs do not exacerbate existing conditions. Hot spots include areas with the potential for

significant pollutant loading such as vehicle service and maintenance facilities, vehicle equipment cleaning facilities, fleet storage areas for buses, and outdoor liquid container storage.

Additional water quality standards or pretreatment measures may be required in addition to those included in the water quality criteria in order to remove potential pollutant loadings from entering either groundwater of surface water systems.

Pretreatment measures include:

Stormwater Hot Spots	Minimum Pre-Treatment Options
Vehicle service and maintenance facilities	1. Oil/Water Separators/Hydrodynamic Devices 2. Use of Drip Pans and/or Dry Sweep Material under Vehicles/Equipment 3. Use of Absorbent Devices to Reduce Liquid Releases 4. Spill Prevention Response Program
Fleet storage areas for buses	BMPs that are part of a Stormwater Pollution Prevention Plan (SWPPP)
Vehicle Fueling Stations	1. Oil/Water Separators/Hydrodynamic Devices 2. Water Quality Inserts for Inlets 3. Spill Prevention Response Program
Vehicle equipment cleaning facilities	BMPs that are part of a Stormwater Pollution Prevention Plan (SWPPP)
Outdoor liquid container storage	Spill Prevention Response Program

2.5.6 Site Plan Review

This policy is to establish a requirement to submit a site plan for review as required by the EGLE NPDES Stormwater Discharge Permit and ensure that water quality objectives, erosion and sediment control requirements, and BMP maintenance are considered to the maximum extent practicable.

Flushing Community Schools shall evaluate proposed construction activities to determine:

- If the activity meets the criteria of a development or redevelopment project with an earth disturbance greater than or equal to 1 acre, or part of a common plan of development resulting in a development or redevelopment activity greater than or equal to 1 acre in size.
- Does the development or redevelopment project discharge to waters of the state, or to a county, city, or township MS4.

If the development or redevelopment project discharges directly to waters of the state, Flushing Community Schools shall comply with the post-construction standards outlined in this SWMP.

If the development or redevelopment project discharges to a regulated county, city, or township MS4, Flushing Community Schools shall submit the site plan for review and approval. Site plan approval by the county, city, or township of an equivalent post-construction standard ensures acceptable compliance with the Flushing Community

Schools NPDES MS4 Stormwater Discharge Permit. Flushing Community Schools shall obtain and maintain a copy of the site plan approval document.

If the development or redevelopment project discharges to a county, city, or township MS4 that is not regulated or requires site plan review, Flushing Community Schools shall comply with the post-construction standards outlined in this SWMP.

2.5.7 Long-Term Operation & Maintenance of Stormwater Controls

Ongoing operation and maintenance of the stormwater BMPs is a critical component of the Stormwater Management Plan. All structural and vegetative stormwater control measures installed as a requirement under this section of the permit shall include guidance for maintaining maximum design performance through long-term operation and maintenance.

- Update and revise the stormwater structural controls on facility site diagrams as identified during scheduled inspections or within 30 days following the completion of a new facility or reconstruction/redevelopment site project.
- Follow long-term guidance for inspection and operation to maintain maximum design performance.
- Stormwater runoff facilities shall be maintained in good condition, in accordance with the approved storm water plan.

Trained staff or certified contractors will conduct routine inspection of all identified structural controls and complete maintenance, repair, or replacement, as necessary.

2.5.8 Post Construction Stormwater Management-BMP Table

BMP	Description of BMP	Timeframe	Measurable Goal	Measure of Assessment	Responsible Party
BMP #2.5.8.1 Regulatory Mechanism	Develop and implement regulatory mechanisms to address post-construction stormwater runoff for new development and redevelopment projects, including preventing or minimizing water quality impact. Develop and implement regulatory mechanisms for projects that disturb one or more acre, including projects less than an acre that are part of a larger common plan of development or sale and discharge into the applicants MS4.	Post-Construction Policy & Procedure Developed and Board Resolution Passed in June 2023	Post-Construction Policy & Procedure developed, and Board Resolution reviewed and approved by the school board.	Copy of the Post-Construction Policy and Procedure and the Approved Board Resolution	Flushing Community Schools
BMP #2.5.8.2 Post Construction Standards	Ensure post-construction channel protection standards and water quality treatment standards are met.	As necessary Throughout Permit Cycle	All development or redevelopment projects meet water quality and channel protection standards outlined in the districts SWMP or meet an equivalent post-construction standard for the township, city, or county.	Copy of calculations.	Flushing Community Schools
BMP #2.5.8.3 Site Specific	Flushing Community Schools will review construction plans for sites with known soil and/or groundwater contamination, including potential “hot spots” and evaluate the use of infiltration BMPs to meet water quality treatment and channel protection criteria.	As necessary Throughout Permit Cycle	Reduce or eliminate discharge of pollutants during construction on contaminated sites.	Documentation of additional stormwater controls.	Flushing Community Schools

BMP	Description of BMP	Timeframe	Measurable Goal	Measure of Assessment	Responsible Party
BMP #2.5.8.4 Site Plan Review	Prepare and submit a written application, including site plan for construction of storm water management systems for all new construction or redevelopment projects where the area of development or redevelopment exceeds one (1) acre.	As necessary Throughout Permit Cycle	If the development or redevelopment project discharges to a regulated county, city, or township MS4, the district shall submit the site plan for review and approval. Site plan approval by the county, city, or township of an equivalent post-construction standard ensures acceptable compliance with the districts NPDES MS4 Stormwater Discharge Permit.	Obtain and maintain a copy of the site plan approval document and copy of calculations.	Flushing Community Schools
			If the development or redevelopment project discharges directly to waters of the state, the district shall comply with the post-construction standards outlined in this SWMP. If the development or redevelopment project discharges to a county, city, or township MS4 that is not regulated or requires site plan review, Flushing Community Schools shall comply with the post-construction standards outlined in this SWMP.	Copy of calculations.	Flushing Community Schools
BMP #2.5.8.5 Long-Term Operation & Maintenance of Stormwater Controls	All structural and vegetative stormwater control measures installed as a requirement under this section of the permit shall include guidance for maintaining maximum design performance through long-term operation and maintenance.	Within 30 days of the completion of a new facility or reconstruction/redevelopment site project. Throughout Permit Cycle	Follow long-term guidance for inspection and operation to maintain maximum design performance. Stormwater runoff facilities shall be maintained in good condition, in accordance with the approved storm water plan.	All storm sewer site maps updated. Maintain all inspection, maintenance, and repair reports conducted by staff or contractors.	Flushing Community Schools

2.6 Pollution Prevention & Good Housekeeping Program

Develop, implement, and ensure compliance through a program of operation & maintenance of BMPs, with the ultimate goal of preventing or reducing pollutant runoff to the maximum extent practicable from operation that discharge stormwater to surface waters of the state.

2.6.1 Pollution Prevention & Good Housekeeping Program Objectives

a. Maintain an up-to-date inventory of owned facilities and stormwater structural controls.
b. Procedure for updating and revising inventory of stormwater structural controls.
c. Procedure for assessing each facility for the potential to discharge pollutants.
d. Develop an SOP (SWPPP) for all facilities with a high potential for pollutant runoff.
e. Procedure identifying BMPs currently implemented or to be implemented to prevent or reduce pollutant runoff at each facility with medium and lower potential to discharge.
f. Procedure for prioritizing of catch basins/manholes for maintenance and cleaning.
g. Schedule for routine catch basin/manhole inspection, maintenance, and cleaning.
h. Provide the geographic location of stormwater structures.
i. Procedure for dewatering, storage and disposal of materials extracted from storm sewer cleaning.
j. Procedure for inspecting and maintaining storm water controls.
k. Procedure for new structural controls to be designed and implemented in accordance with post-construction stormwater runoff control performance standards.
l. Best management practices for operation and maintenance activities.
m. Procedure for street sweeping.
n. Procedure for pesticide application.
o. Training.
p. Contractor requirements and oversight.

It is the ultimate goal of Flushing Community Schools to prevent and reduce pollutant/contaminant runoff from Flushing Community Schools facilities to the maximum extent practicable. All BMPs are implemented at all low, medium, and high priority facilities.

2.6.2 Structural Control Inventory & Schedule Table

No prioritization will be needed, as all structures are to be inspected and maintained equally. All structural controls will have routine inspection, maintenance schedules, and long-term procedures which adequately control, to the maximum extent practicable, pollution removal and control. Structural control effectiveness will be determined based on the results of these inspections and repaired, upgraded, or replaced as indicated.

The structural Control Inventory and Schedule Table for each property are in Appendix E.

2.6.3 Facility Assessment & Prioritization

Flushing Community Schools has identified all applicant owned facilities with a discharge of stormwater to surface waters of the state, and during mapping of each facility, inventoried the number of stormwater structural controls (i.e., catch basins, detention basins, etc.) at each site. Each location was assessed to determine high, medium, and low potential to discharge pollutants to surface waters of the state.

Flushing Community Schools considered the following when assessing each facility:

- Absence of any factors,
- Presence of urban pollutants stored at the site (i.e., sediment, nutrients, metals, hydrocarbons, pesticides, fertilizers, herbicides, chlorides, trash, bacteria, or other site-specific pollutants,
- Identification of improperly stored materials,
- Potential for polluting activities to be conducted outside (i.e., vehicle washing),
- Proximity to water bodies,
- Poor housekeeping practices,
- Discharge of pollutants of concern to impaired waters.

For facilities that have a high potential to discharge pollutants to surface waters of the state, a Stormwater Pollution Prevention Plan (SWPPP) and/or Pollution Incident Prevention Plan (PIPP) for salt storage facilities will continue to be implemented.

BMPs currently implemented by Flushing Community Schools at facilities with medium and lower potential for the discharge of pollutants to surface waters of the state include:

1. Good housekeeping practices,
2. Employee training,
3. Routine visual inspections,
4. Spill prevention and response.

This inventory will be updated as facilities and structural stormwater controls are added, removed, or no longer owned or operated by the applicant following routine inspections or following new construction or redevelopment projects. Priority level assessments will be revised within 30 days following the completion of a new facility or reconstruction/redevelopment.

2.6.4 Storm Sewer Structure Controls Inspection & Maintenance Policy & Procedure

1. Develop a schedule for inspecting and maintaining catch basins and stormwater controls at each facility, for the reduction of pollutant runoff. A schedule is included in Appendix E.
2. Visually inspect all stormwater controls identified on facility maps. Inspection includes:
    a. Structural integrity of the structure.
        - Areas of significant cracking or sinkholes.
    b. Sediment build-up.
        - Areas with high amounts of build-up sediment. A build-up of accumulated solid material that is greater than or equal to the one-third guideline established by the EPA or between 30 and 40% of the total sump depth, as established by the EGLE[4].
    c. Color, odor, sheen, and flow.
    d. Overall functionality and presence of erosion.
    e. Pond evaluation.
3. Note inspection information on the inspection form. A copy of the inspection form “Structural BMP Table” is located in Appendix D.
4. When inspecting stormwater controls, review the site for non-structural BMPs currently implemented to prevent or reduce pollutant runoff at each facility. BMPs include:

[4] Michigan Department of Environment, Great Lakes, and Energy (EGLE) Catch Basin/Street Sweeping Management

a. Review of "No Dumping" stencils at storm drains.
b. Review of catch basins/manholes cleaned.
c. Dumpster good housekeeping practices.
d. Garden, green space and signage inventories.
e. "SEMCOG" poster placement at facilities.
f. Illicit discharge reporting numbers poster placement at facilities.
g. "How to spot illicit discharge/ How to Report-Hotline Numbers" poster placement at facilities.
h. Spill kit availability at facilities.

5. Following the inspection, the stormwater controls will be prioritized for cleaning and maintenance in a timely manner. Prioritize locations based on the following:
    - Drainage structures that are designated as consistently generating the highest volumes of trash and/or debris.
    - Areas with high amounts of build-up sediment. Refer to number 2 (b) above.
    - Areas of significant erosion.
    - Areas of significant cracking or sinkholes.
6. Once the inspection is complete, the stormwater manager or designated person will review the report and determine if a work order or other item is needed to work with relevant departments or contractors to fix any problems.
7. If an illicit discharge is suspected, follow the procedure outlined in Section 2.3 Illicit Discharge Elimination Program.
8. Retain inspection forms for each stormwater structural control inspected.
9. Retain documentation regarding the scheduling or completion of the repair/maintenance if completed.
10. Debris and maintenance waste removed as part of the maintenance and/or repairs shall be disposed of in accordance with the Structural BMP Operation & Maintenance Waste Disposal procedures.

Furthermore, staff members conducting maintenance and grounds activities are provided IDEP and pollution prevention/good housekeeping training. All structural controls will have routine inspection, maintenance schedules, and long-term procedures which adequately control, to the maximum extent practicable, pollution removal and control. Structural control effectiveness will be determined based on the results of these inspections and repaired, upgraded, or replaced as indicated. This procedure will be reviewed on an annual basis and updated as needed or 30 days following the implementation of a new stormwater structural control.

2.6.5 Structural BMP Operation & Maintenance Waste Disposal Procedures

Waste materials generated from operation, maintenance, and cleaning activities associated with storm sewer systems have typically been discharged back into the storm sewer system. This type of discharge is unauthorized per Part 31, Water Resources Protection (Part 31) of the Natural Resources and Environmental Protection Act, 1994 PA 451, as amended (NREPA) and is therefore illegal. The combined solid and liquid waste stream (solid/liquid waste) from cleaning storm sewer systems is legally defined as "Liquid Industrial By-products" pursuant to Part 121, Liquid Industrial By-products (Part 121) of NREPA.

Flushing Community Schools will ensure that all waste materials generated during operation and maintenance of structural stormwater controls are properly characterized, transported, and disposed as required under State of Michigan PA 451 Part 111 (hazardous wastes), Part 121 (liquid industrial by-products), and Part 115 (solid wastes). At a minimum, the following procedures will be implemented for waste generated from cleaning or maintaining storm sewer structural controls.

Waste Disposal Methods for Non-Contaminated Materials

Non-contaminated waste materials generated during cleaning or maintenance of storm sewer structures will be properly disposed using one of the following methods:

1. Have the waste transported to drying beds to separate the solid/liquid waste. This is usually performed at a publicly owned treatment plant or at a privately-owned permitted facility where the liquid portion of the waste stream is separated from the solids and treated.
2. Request permission from the local wastewater treatment plant operator to discharge the combined solid/liquid waste into the sanitary system. Most treatment plants will require pre-treatment prior to discharge. All applicable local ordinance provisions must be followed.
3. When conducting catch basin maintenance activities where the above options are not available, the following methods can be used as long as there are no discharges to surface waters during dry weather conditions:
    - Conduct visual inspection to ensure the water in the sump has not been contaminated. If necessary, collect a grab sample of the water and look for signs of contamination such as visible sheen, discoloration, obvious odor, etc. If there is any doubt of the quality of the water, it will be collected into a vacuum truck and treated as Liquid Industrial By-Products under Part 121 or Part 115 of PA 451 (NREPA).
    - Using a sump pump, or any other pumping mechanism, remove the majority of water in the sump of the basin without disturbing the solid material below. Do not use pumps connected to the vacuum truck's holding tank.
    - The clear water may then be directly discharged to one of the following:
        - Sanitary system (with prior approval from local sewer authority).
        - Curb and gutter.
        - Back into the storm sewer system if it is contained within the system during dry weather condition to ensure no discharge into surface water.
        - Applied to the ground adjacent to the catch basin (evenly distributed at a maximum rate of 250 gallons/acre/year).
    - The remaining liquid/solid in the sump will be collected with a vacuum truck and disposed of off-site in accordance with MI P.A. 451 Parts 115 or 121.

Flushing Community Schools does not currently own or operate storm sewer cleaning or transportation equipment. If Flushing Community Schools contracts with a private contractor to transport liquids generated from cleaning of catch basins or other structures, that contractor must be registered and permitted as a Uniform Liquid Industrial By-Product Hauler under the provisions of HMTA.

Waste Disposal Methods for Contaminated Materials

Waste materials generated during operation and maintenance of storm sewer systems found or suspected to be contaminated with pollutants or hazardous substances will be characterized, packaged, marked, labeled, stored, transported, and disposed as a liquid industrial by-product under Part 121 or Part 115 of PA 451 (NREPA).

2.6.6 Pollution Prevention/Good Housekeeping – Municipal Operations & Maintenance Activities

Flushing Community Schools recognizes the importance of reducing pollutant runoff from maintenance activities. The following procedure will include an assessment of the potential activities for the potential to discharge pollutants. The assessment shall identify the pollutants that could be discharged from the applicable operation and maintenance activity and the BMPs implemented or to be implemented to prevent or reduce pollutant runoff.

PROCEDURE

Applicable operations and maintenance activities include parking lot and sidewalk maintenance, cold weather operations, vehicle washing, maintenance of vehicles, land disturbance, landscape, and unpaved parking lot maintenance. Bridge maintenance and right-of-way maintenance do not apply to Flushing Community Schools.

Roadways/Parking Lots

Maintenance: Pothole, sidewalk, curb, and gutter repair.

Possible Pollutants: Fuel, oil, sediment, concrete.

BMPs to address Pollutants:

1. Contractors and in-house staff contracted to complete these jobs are informed of stormwater management practices to reduce pollution in stormwater.
2. Avoid mixing excess amounts of fresh concrete or cement.
3. Never dispose of washout into the street, storm drains, ditches, or creeks.
4. Stencil storm drains to prevent disposal of wash water.
5. Schedule patching, resurfacing and surface sealing during dry weather.
6. If it rains unexpectedly, take appropriate action to prevent pollution of stormwater runoff (e.g., divert runoff around work areas, cover materials).
7. Maintain pollution prevention/good housekeeping practices, which is to remove stockpiles (asphalt materials, sand, etc.) by the end of the day to a covered location. Alternatively, cover the piles if they cannot be moved.

Process for updating assessment: Contractor or project is assessed on an ongoing basis, and problems are addressed when found.

Cold Weather Operations

Maintenance: Plowing, sanding, deicing, snow pile disposal.

Possible Pollutants: Sodium, magnesium, calcium, potassium, chloride, turbidity.

BMPs to address Pollutants:

1. Keep all deicing material covered or in waterproof containers.
2. Prevent deicer drainage to storm sewers.
3. Mechanical removal of as much snow or ice as possible prior to applying deicing chemicals.
4. Proper salt storage management.
5. Maintain application equipment per manufacturer's recommendations.

Process for updating assessment: BMPs will be assessed for effectiveness within 30 days following their addition or removal.

Vehicle Washing

Maintenance: Washing of buses, staff vehicles and maintenance equipment.

Possible Pollutants: Petroleum based wastes, metals, and nutrients.

BMPs to address Pollutants:

1. All vehicle washing and maintenance is to be performed indoors where drains connecting to the sanitary system can receive all waste. The district does not have an interior bus wash on site.
2. Alternatively, vehicle washing can be performed at a commercial auto wash facility.
3. Alternatively, rinse grass from lawn care equipment on permeable (grassed) areas.
4. School car wash fundraising events will not be permitted on school grounds.

Process for updating assessment: BMPs will be assessed for effectiveness within 30 days following their addition or removal.

Vehicle Maintenance

Possible Pollutants: Petroleum based wastes, metals, and nutrients.

BMPs to address Pollutants:

1. All vehicle or equipment maintenance will take place inside or away from storm drains where drains connecting to the sanitary system can receive all waste.
2. Any floor drains suspected of draining to the stormwater system will be dye traced as needed.
3. Recycle used motor oil, diesel oil, other vehicle fluids, and vehicle parts whenever possible.

Process for updating assessment: BMPs will be assessed for effectiveness within 30 days following their addition or removal.

Landscaping

Possible Pollutants: Wood chips, sediment, sand, and compost.

BMPs to address Pollutants:

1. Place temporary stockpiled material away from storm drains, and berm or cover stockpiles to prevent material releases into the storm drain. Alternatively, place stockpiles on permeable (grassed) areas.
2. Proper Storage, handling, and use of pesticides, herbicides, and fertilizers.

Process for updating assessment: BMPs will be assessed for effectiveness within 30 days following their addition or removal.

Land Disturbance

Possible Pollutants: Sediment runoff.

BMPs to address Pollutants:

1. Plan land clearing so soil is not exposed for long periods of time.
2. Place temporary stockpiled material away from storm drains, and berm or cover stockpiles to prevent material releases into the storm drain.
3. Protect against sediment flowing into drains.
4. Install sediment barriers.

Process for updating assessment: BMPs will be assessed for effectiveness within 30 days following their addition or removal.

Unpaved Roads & Parking Areas

Possible Pollutants: Sediment runoff.

BMPs to address Pollutants:

1. Protect against sediment flowing into drains.
2. Install sediment barriers.
3. Maintain unpaved roads and parking lots to reduce dust, raveling, potholes, and depressions.

Process for updating assessment: BMPs will be assessed for effectiveness within 30 days following their addition or removal.

ASSESSMENT

Pollution prevention inspections ensure that these BMPs are carried out properly. Any issues identified during the inspections will be reviewed and addressed by the Stormwater Manager.

2.6.7 Street Sweeping Procedure, Prioritization & Schedule

PRIORITIZATION

The EGLE Stormwater Discharge Permit requires a procedure for prioritizing owned streets, parking lots, and other impervious infrastructure for street sweeping based on the potential to discharge pollutants. Flushing Community Schools evaluated each facility for the presence of the following factors:

- Potential for polluting activities to be conducted outside
- Proximity to water bodies
- Traffic volume
- Land use
- Absence of any factors

PROCEDURE

Flushing Community Schools does not own or operate sweeping equipment. However, Flushing Community Schools will be proactive and undertake the following activities to reduce the potential to discharge pollutants to surface waters of the state from parking lots and other impervious infrastructures.

1. Conduct seasonal efforts to remove leaves.
2. Inspect parking lot and street areas.
3. Conduct hand sweeping of debris to prevent accumulated wastes in the spring and the fall.
4. Waste disposal areas will be kept free of litter and debris.
5. Analyze sediment, removed from an inlet cleaning if it is suspected of being contaminated with a hazardous material, prior to disposal. Sediment or materials determined to be hazardous waste will be disposed of in accordance with the Structural BMP Operation & Maintenance Waste Disposal procedures.
6. Contract out street cleaning when appropriate.

This prioritization will be updated as facilities and structural stormwater controls are added, removed, or no longer owned or operated by the applicant following routine inspections, or as traffic volume, land use or sediment and trash accumulation increases.

PRIORITIZATION LEVELS & SCHEDULE

All low, medium, and high prioritized parking lots and streets are inspected on the same schedule in an effort to reduce pollutants.

Facility Name	Priority Level of Potential Discharge* (High, Med, Low)	Street Sweeping Schedule
Bus Garage & Maintenance	High	Monthly Inspections, Hand Sweep as Needed
Central Elementary School / Football Field Complex	Low	Hand Sweeping, Spring and Fall

Facility Name	Priority Level of Potential Discharge* (High, Med, Low)	Street Sweeping Schedule
Central Office	Low	Hand Sweeping, Spring and Fall
Early Childhood Center	Low	Hand Sweeping, Spring and Fall
Elms Elementary School	Low	Hand Sweeping, Spring and Fall
Flushing High School	Medium	Hand Sweeping, Spring and Fall
Flushing Middle School	Medium	Hand Sweeping, Spring and Fall
Seymour Elementary School / Soccer Field Complex	Low	Hand Sweeping, Spring and Fall
Springview Elementary School	Low	Hand Sweeping, Spring and Fall

*If required, following inspections indicating higher traffic volume, land use or sediment and trash accumulation at all low, medium, and high prioritized parking lots and streets, the District shall contract a commercial street sweeping company.

DISPOSAL

If a commercial street sweeper is contracted to clean a parking lot and street areas for Flushing Community Schools, the street sweeping activities are subject to the solid waste requirements. Solid waste must be managed under Part 115 requirements. Dispose of the solid waste in a licensed landfill. The contractor hired to do the street sweeping is responsible for proper disposal of the waste material. The contracted sweeping will not be completed when streets are wet, so dewatering of the collected debris will not be required.

2.6.8 Managing Vegetated Properties

Flushing Community Schools has established this policy to prevent or reduce pollutant runoff from vegetated land:

1. Flushing Community Schools requires all contracted personnel who participate in the application of pesticides, to will be trained and licensed by the State of Michigan under the Commercial Pesticide Application Certification Program for relevant categories as applicable, to prevent or reduce pollutant runoff from vegetated land.
2. Whenever practicable, an integrated pest management technique will be implemented.

2.6.9 Contractor Requirements & Oversight

Flushing Community Schools requires contractors to comply with pollution prevention and good housekeeping BMPs. Flushing Community Schools will perform the following activities for applicable contractors and projects to

comply with all pollution prevention and good housekeeping BMPs as appropriate and comply with pollution as well as provide oversight to ensure compliance:

- Contractor Notification
- Contractor Training
- Pre-project Meeting/Review
- Periodic Inspections

Prior to conducting work, contractors shall be provided a "Stormwater Contractor Oversight Record" form. This will allow the district to review stormwater compliance with contractors hired to perform municipal operation and maintenance activities and to obtain signatures. The "Stormwater Contractor Oversight Record" form is located in Appendix F.

2.6.10 Pollution Prevention/Good House Keeping Training

A training program is an important component to effective pollution prevention. Training is required for all employees whose job responsibilities involve municipal or maintenance activities. Training is discussed in detail in Section 3.0 of this SWMP.

2.6.11 Pollution Prevention/Good Housekeeping –BMP Table

BMP	Description of BMP	Timeframe	Measurable Goal	Measure of Assessment	Responsible Party
BMP #2.6.11.1 Structural Control Inventory	Provide an up-to-date inventory of the number of stormwater structural controls for each facility's (i.e., catch basins, detention ponds). Update facilities potential to discharge pollutants (high, medium, low) following the update.	Updated as needed within 30 days following the completion a new facility or development/ redevelopment. Ongoing Throughout Permit Cycle	100% of stormwater structural controls inventoried.	Maintain list of inventories and potential to discharge priority level. Submit updated list with progress report, noting if priority levels have changed.	Flushing Community Schools
BMP #2.6.11.2 SWPPP development & implementation (SOP)	Develop a "Stormwater Pollution Prevention Plan (SWPPP)" for maintenance, transportation, and storage facilities/Implement policies & procedures.	Developed & Implemented Ongoing Throughout Permit Cycle	SWPPP completed and 100% of inspections implemented.	Copy of SWPPP and copy of inspections.	Flushing Community Schools
BMP #2.6.11.3 Stormwater Structural Control Inspections	Visually inspect stormwater controls identified on facility maps.	Annually Throughout Permit Cycle	Routine schedule implemented and inspections reviewed by stormwater manager.	Maintain inspection forms/reports.	Flushing Community Schools
BMP #2.6.11.4 Review for BMP's Implemented	While inspecting stormwater controls, review the site for BMPs currently implemented to prevent or reduce pollutant runoff at each facility, such as storm drain stencils, garden areas, areas cleaned, areas repaired, SEMCOG poster placement, Illicit discharge education posters, and spill kits.	Annually Throughout Permit Cycle	Annual inspections completed and reviewed by stormwater manager.	Documentation of inspection findings (number of posters, number of spill kits, inventory of gardens, pictures of stencils, pictures of spill kits).	Flushing Community Schools

BMP	Description of BMP	Timeframe	Measurable Goal	Measure of Assessment	Responsible Party
BMP #2.6.11.5 Prioritization of Storm Sewer Locations for Maintenance & Cleaning	Following the inspection, the stormwater controls will be prioritized for cleaning and maintenance. Prioritize locations based on: (1) drainage structures that are designated as consistently generating the highest volumes of trash and/or debris, (2) areas with high amounts of build-up sediment, (3) areas of significant cracking or sinkholes.	Annually Throughout Permit Cycle	Prioritization locations identified.	Copy of prioritization.	Flushing Community Schools
BMP #2.6.11.6 Cleaning & Maintenance (Catch Basin/ Manhole Cleaning)	Flushing Community Schools will ensure that cleaning of the catch basins/manholes occur, and all waste materials generated during operation and maintenance of structural stormwater controls are properly characterized, transported, and disposed as required under State of Michigan PA 451 Part 111 (hazardous wastes), Part 121 (Liquid Industrial By-Products), and Part 115 (solid wastes).	Once per permit cycle Or More often if prioritized due to a build-up of accumulated solid material that is greater than or equal to the one-third guideline outlined in the Storm Sewer Structure Controls Inspection & Maintenance Policy & Procedure	Cleaning completed once per permit cycle or more often if build-up of accumulated solid material reaches the action level per the procedure in section 2.6.4. All waste disposed of as required.	Copies of Waste Manifests.	Flushing Community Schools
BMP #2.6.11.7 Roadways & Parking Lots	Storm drains stenciled to prevent disposal of wash water into storm drains.	As needed Throughout Permit Cycle	Storm drain stencils inspected and maintained as need.	Copy of work order. Photos of stenciling.	Flushing Community Schools
BMP #2.6.11.8 Cold Weather Operations	Proper salt storage management. Maintain storage bags/equipment in good working condition and maintain application equipment per manufacturer's recommendations.	Ongoing Throughout Permit Cycle	Continue proper salt storage and management as previously implemented.	Copy of SWPPP comprehensive inspection report.	Flushing Community Schools

BMP	Description of BMP	Timeframe	Measurable Goal	Measure of Assessment	Responsible Party
BMP #2.6.11.9 Vehicle Washing	All vehicle washing and maintenance is to be performed indoors where drains connecting to the sanitary system can receive all wastes. Alternatively, vehicle washing can be performed at a commercial auto wash facility.	Ongoing Throughout Permit Cycle	100 % of applicable staff trained on were to wash vehicles.	Copy of sign-in sheets and Agenda (if available).	Flushing Community Schools
	Alternatively, rinse grass from lawn care equipment on permeable (grassed) areas.		100 % of applicable staff trained on were to wash vehicles.	Copy of sign-in sheets and Agenda (if available).	
	School car wash fundraising events will not be permitted on school grounds.		Notice sent to staff regarding policy.	Copy of e-mail or policy.	
BMP #2.6.11.10 Vehicle Maintenance	Any floor drain suspected to drain to the stormwater system will be dye traced as needed.	Throughout Permit Cycle	100% of floor drains inspected.	Copy of inspection report.	Flushing Community Schools
	Recycle used motor oil, diesel oil, other vehicle fluids, and vehicle parts whenever possible.	As needed Throughout Permit Cycle	Reduction in amount of disposed material and amount of material shipped for off-site disposal.	Copy of invoices or shipping papers.	
BMP #2.6.11.12 Land Disturbance	Place temporary stockpiled material away from storm drains, and berm or cover stockpiles to prevent material releases into the storm drain. Protect against sediment flowing into drains.	As needed Throughout Permit Cycle	100 % of applicable staff trained.	Copy of sign-in sheets and Agenda (if available).	Flushing Community Schools

BMP	Description of BMP	Timeframe	Measurable Goal	Measure of Assessment	Responsible Party
BMP #2.6.11.xx Unpaved Roads & Parking Areas	Protect against sediment flowing into drains, install sediment barriers, and maintain unpaved roads and parking lots to reduce dust, raveling, potholes, and depressions.	As needed Throughout Permit Cycle	100 % of applicable staff trained.	Copy of sign-in sheets and Agenda (if available).	Flushing Community Schools
BMP #2.6.11.13 Street Sweeping	Conduct hand sweeping in the parking lots/roadways in the spring and fall.	Spring & Fall Throughout Permit Cycle	Inspections completed.	Copy of work order or schedule.	Flushing Community Schools
	Street sweeping conducted by a professional sweeping company.	As needed Throughout Permit Cycle		Copy of invoice or disposal documentation.	
BMP #2.6.11.14 Vegetated Properties (Pesticides)	Flushing Community Schools requires all contracted personnel who participate in the application of pesticides will be trained and licensed by the State of Michigan under the Commercial Pesticide Application Certification Program for relevant categories as applicable, to prevent or reduce pollutant runoff from vegetated land.	Ongoing Throughout Permit Cycle	Application of pesticides will only be completed by trained and licensed applicators.	Documentation of in-house staff license or copy of contractor receipt.	Flushing Community Schools
BMP #2.6.11.15 Contractor Oversight	Flushing Community Schools requires contractors to comply with pollution prevention and good housekeeping BMPs. Flushing Community Schools will complete contractor notification, pre-project meeting and periodic inspections to provide oversight to ensure compliance.	As needed Throughout Permit Cycle	Contractors trained and informed of pollution prevention and good housekeeping techniques.	Copy of sign-in sheets, pre-project meeting notes or inspections.	Flushing Community Schools & Contractors/ Vendors

BMP	Description of BMP	Timeframe	Measurable Goal	Measure of Assessment	Responsible Party
	Prior to conducting work, contractors shall be provided a "Stormwater Contractor Oversight Record" form.				
BMP #2.6.11.16 Training	Pollution prevention and good housekeeping training.	Once per permit cycle or during the 1st year of employment Throughout Permit Cycle	Goal of providing training to maintenance staff who work for Flushing Community Schools. **[All Stormwater Training is outlined in Section 3.0 Training]**	Copy of sign-in sheets and Agenda (if available).	Flushing Community Schools
BMP #2.6.11.17 Pollution Prevention & Good Housekeeping Activities Effectiveness Review	Summary of annual activities for the "Pollution Prevention and Good Housekeeping".	Annually Throughout Permit Cycle	Annual review of SWMP performed. Maintain copy of SWMP annual review. Determine the level of district involvement and identify areas of improvement.	Maintain copy of SWMP annual review and evaluation information for progress reporting.	Flushing Community Schools

3.0 Training

Flushing Community Schools will provide education and training for applicable employees and contractors using a variety of methods depending on their specific job function. At a minimum, all applicable Flushing Community Schools employees will be encouraged to have general awareness training on the topics included in the PEP. All applicable Flushing Community Schools employees will be encouraged to attend or otherwise obtain general awareness training at least once per permit cycle or during the 1st year of employment.

Flushing Community Schools has implemented a comprehensive staff training program based on each employee's participation and responsibilities under this program. The employee training program is categorized in four (4) separate levels summarized as follows:

LEVEL I TRAINING-General Awareness Training

Level I training is encouraged for all district employees, parents, and students. General Awareness training is provided in the form of an 11-minute video produced by Arch Environmental Group titled, **"When it Rains, It Drains…The Stormwater Question".** This video is also available on the stormwater webpage.

LEVEL II TRAINING-General Awareness, Pollution Prevention & Good Housekeeping, and Illicit Discharge Reporting

Level II training is required for all employees whose job responsibilities involve illicit discharge related activities, or indicate a potential to cause, witness, or report and illicit discharge or connection. This training includes the previously described video as well as a review of the districts Stormwater Management Program Plan and instruction on identification and notification of illicit discharges or connections. This training is provided to applicable transportation, maintenance, custodial, and food service employees.

LEVEL III TRAINING-Maintenance and Storage Facility Stormwater Pollution Prevention Plans, Lawn Maintenance, and Structural Control Inspection, Maintenance, and Repair Training

Level III training is provided in the form of videos, PowerPoint presentations, and hands-on training. This training is provided to district supervisors, maintenance, and lawn service staff.

LEVEL IV (CONTRACTORS) – Contractor Training/Oversight

Contractors employed by Flushing Community Schools to conduct activities with a potential to impact water quality. Prior to conducting work, contractors shall be provided a "Stormwater Contractor Oversight Record" form.

3.1 Training Table

BMP	Description	Measurable Goal	Target Audience	Timeframe
I **General Awareness Training**	Encourage teachers, administrative and support staff to watch the General Awareness Stormwater Video "When it Rains it Drains".	Maintain on district website and Record attendance with sign-in sheets. Flushing Community Schools will retain records of trainings for future review regarding SWMP.	Teachers, administrative and support staff.	Ongoing Throughout Permit Cycle
II **IDEP & PPGH Training**	General Awareness, Pollution Prevention & Good Housekeeping, and Illicit Discharge Elimination Program	Record attendance with sign-in sheets for each training session. Flushing Community Schools will retain records of trainings for future review regarding SWMP.	In-house custodial, maintenance, transportation, and food service employees.	Required once during permit cycle current employees and during the 1st year of employment for new employees. Throughout Permit Cycle
III **Routine Storm Sewer Inspection Training**	Train appropriate employees how to conduct a storm sewer system inspection.	Record attendance with sign-in sheets for each training session. Flushing Community Schools will retain records of trainings for future review regarding SWMP.	District supervisors, in-house maintenance, and lawn service staff.	As Needed Throughout Permit Cycle
IV **Contractor Training/ Oversight**	Stormwater specific training for on-site contractors.	Utilize a "Stormwater Contractor Oversight Record" form to review stormwater compliance with contractors hired to perform municipal operation and maintenance activities and to obtain signatures. Obtain records of training for future review of the SWMP.	Contractors employed by Flushing Community Schools to conduct activities with a potential to impact water quality.	Required at the time of employment. Throughout Permit Cycle

4.0 Total Maximum Daily Load (TMDL) Restrictions

4.1 What are TMDLs

When a lake or stream fails to meet federal water quality standards, the Clean Water Act requires that a "Total Maximum Daily Load (TMDL)" limit be developed. Studies are completed to determine the sources impacting the water body and to develop goals so that the water body can meet the applicable standards.

A TMDL describes the process used to determine how much of a particular pollutant a lake or stream can assimilate and sets pollution reduction targets for the water body.

Flushing Community Schools will review and prioritize BMPs currently implemented or to be implemented during the permit cycle to make progress toward achieving the pollutant load reduction requirement in each TMDL identified. TMDLs assigned the discharges for Flushing Community Schools are described in the below sections.

4.2 Statewide E. coli TMDL


The Statewide **E. coli** TMDL was approved by the United States Environmental Protection Agency (USEPA) on July 29, 2019. This TMDL addresses all surface waters (inland lakes, Great Lakes, streams, rivers, wetlands, and beaches) in the state of Michigan that are impaired by E. coli. The goal of the TMDL is to identify problem areas, address sources of E. coli statewide, and provide guidance to restore these waters.

The targets in this TMDL are concentrations of E. coli per 100 milliliters (mL) of water, set equal to Michigan's Water Quality Standard (WQS) for recreation (described in Section 3). This target is easier to understand and communicate than a load-based target, which would vary by water body, and is also easier to measure with limited resources.

Each District facility was evaluated for the Statewide E. coli TMDL applicability using the Michigan Department of Environment, Great Lakes, and Energy TMDL Watershed Screening Tool. The following District facilities discharge stormwater either directly or indirectly to watersheds included within the Statewide TMDL boundaries as identified in Map 3 below:

1. Central Elementary School / Football Field Complex
2. Early Childhood Center
3. Seymour Elementary School / Soccer Fields Complex
4. Flushing RVA – there are no stormwater structures on this site.

Map 3 – Total Maximum Daily Load Map[5]



4.3 TMDL Implementation – Monitoring Plan

4.3.1 Sampling

1. The goal is to collect samples from at least 50% of the outfall/discharge points at facilities associated with TMDL. An effort will be made to sample water quality parameters during a representative (i.e., >0.25" and <1.5") wet weather event over a 24-hour period, and within 30 to 60 minutes of the start of the wet weather event in order to capture the first flush. Monitoring shall be specific for the pollutant identified in the applicable TMDL for each permitted facility. TMDL Sample locations are located in Appendix G.
2. The Part 4 Water Quality Standards for E. coli is 1,000 counts per 100 ml for outfall monitoring. If the monitoring results conducted in the initial round of TMDL monitoring are below the benchmark standard for E. coli, then a second round of monitoring for E. coli (within the same permit cycle) is not required.

[5] Total maximum daily load boundaries based on Michigan Department of Environment, Great Lakes, and Energy Shapefiles.

3. If a designated TMDL in a receiving waterbody to which one or more district facilities discharges is being attained, outfall discharge point monitoring will not be conducted at the district facilities that discharge to that receiving waterbody.

4.3.2 Prioritized TMDL Best Management Practices

The below lists stormwater BMPs that are targeted to improve water quality impairments associated by the TMDL.

E. COLI

1. Flushing Community Schools will use its website to provide the public with information regarding pet waste (SEMCOG links). Additionally, SEMCOG pet waste posters are placed at various school buildings.
2. Flushing Community Schools will prohibit illicit discharges, inspect, and monitor suspected illicit discharges, and enforce elimination of the illicit discharges and connections.
3. Flushing Community Schools has reviewed all facilities for cross-connections between the sanitary and storm sewer systems.
4. Flushing Community Schools will conduct hand sweeping in the parking lots/roadways in the spring and fall.
5. Flushing Community Schools has established programs for soil erosion and sediment control from new or redevelopment construction. Such developments require permits and inspections for practices to keep exposed soils on site or controlled from runoff.
6. Flushing Community Schools has implemented routine visual inspections of stormwater structural controls.
7. Flushing Community Schools will remove excessive sediments from structural sediment removal systems to maintain the maximum designed performance. Sediments will be disposed of offsite in accordance with Parts 115 or 121.

ALL TMDLs

1. Flushing Community Schools will continue to use its website to provide the public information regarding local TMDL issues (E. coli TMDL Best Management Practice).
2. Flushing Community Schools will continue to educate staff, faculty, and students using various venues including the **"Seven Simple Steps to Clean Water"** program educational materials developed by the various watershed groups specifically related to these issues on the stormwater management webpage.
3. The district has implemented an Illicit Discharge Regulatory Policy.
4. The district has implemented a Post-Construction Policy and Procedure.
5. The district has implemented an Enforcement Response Procedure.
6. Adequately maintains vegetation around stormwater facilities, ditches, and ponds.
7. Provide training to applicable staff and confirm training from contractors including restrictions on the use of phosphorous containing fertilizers, soaps, cleaners, and other chemicals that could impact the separate storm drain system.

Procedure

Prioritization of BMPs is based on <DISTRICT> targeted TMDL pollutants. Priority is given to BMPs that reduce E. coli loads. The goal will be to conduct TMDL monitoring at designated outfall/discharge points in the first and fourth years of the permit cycle. If the monitoring results conducted in the initial round of TMDL monitoring for a specific TMDL parameter was below the benchmark standard, then a second round of monitoring (within the same permit cycle) is not required for that specific parameter.

Assessment

The EGLE Stormwater Discharge Permit Application requires a monitoring plan for assessing the effectiveness of the BMPs currently being implemented, or to be implemented, in making progress toward achieving the TMDL pollutant load reduction requirement. Monitoring shall be specifically for the pollutant identified in the TMDL.

Flushing Community Schools will implement the following practices for applicable TMDLs:

1. Monitoring results and conclusions related to TMDL sampling will be provided during progress reporting.
2. Based on a review of the sampling results, BMP implementation will be reviewed for effectiveness and BMPs may be updated or revised to ensure progress toward achieving TMDL pollutant load reductions.

4.3.3 Total Maximum Daily Load (TMDL) – BMP Table

BMP	Description of BMP	Timeframe	Measurable Goal	Measure of Assessment	Responsible Party
BMP #4.3.3.1 Public Education	SEMCOG posters are placed strategically through the District to educate the public on impacts of discharges to surface waters. The District will continue to use its website to provide the public with information regarding local TMDL issues (E. coli TMDL Best Management Practice).	Ongoing Throughout Permit Cycle	Posters placed throughout Flushing Community Schools facilities. Material available on webpages.	Maintain three (3) various SEMCOG posters at each facility. Strategic locations include Main Office, Lounge, and Receiving Area (if available). Maintain links on webpage. Maintain copies of webpage review.	Flushing Community Schools
BMP #4.3.3.2 Outfall Monitoring	Select outfall/discharge points at facilities associated with the TMDL will be monitored. An effort will be made to sample water quality parameters during a representative wet weather event over a 24-hour period, and within 30 to 60 minutes of the start of the wet weather event in order to capture the first flush. Monitoring shall be specific for the pollutant identified in the applicable TMDL for each permitted facility.	Once per Permit Cycle Throughout Permit Cycle. Second Round as Needed based on Initial Results	The goal is to collect samples from at least 50% of the outfall/points of discharge at facilities associated with the applicable TMDL.	Monitoring results and conclusions related to TMDL sampling will be provided during progress reporting.	Flushing Community Schools
BMP #4.3.3.3 TMDL Implementation Effectiveness Review	Review performance measures to evaluate the effectiveness of BMPs currently being implemented based on sampling results for TMDL pollutant load reduction.	Annually Throughout Permit Cycle	Annual review of TMDL BMPs for effectiveness towards TMDL pollutant load reduction.	Maintain a copy of SWMP Annual Review and Evaluation information for progress reporting.	Flushing Community Schools

Appendix A

Outfall/Discharge Point Receiving Water Table & Site Stormwater Structure Maps

Development Date: May 17, 2025
Revision Date: February 10, 2025
Revision Date: May 27, 2025

Receiving Waters Table
Permit Cycle 2023-2028

Flushing Community Schools							
Facility	**Structure ID**	**Outfall or Point of Discharge**	**GPS Coordinates (Latitude/Longitude)**		**Receiving Regulated MS4 or Waters of the State**	**Receiving Waters**	**Watershed**
Bus Garage & Maintenance	FBG-01.CB.DP	Point of Discharge	43.067541	-83.867852	City of Flushing MS4	Flint River	Flint River
Central Elementary School-Football Field Complex	CEN-02.MH.DP	Point of Discharge	43.067466	-83.847773	City of Flushing MS4	Great Lakes Region	Flint River
	CEN-16-MH.DP	Point of Discharge	43.069741	-83.845660	City of Flushing MS4	Great Lakes Region	Flint River
Central Office	FCO-01.MH.DP	Point of Discharge	43.070221	-83.852571	City of Flushing MS4	Freeman Drain-Flat River	Flint River
Early Childhood Center	FEC-02.MH.DP	Point of Discharge	43.066336	-83.848844	City of Flushing MS4	Cole Creek-Flint River	Flint River
	FEC-03.CB.DP	Point of Discharge	43.066164	-83.849382	City of Flushing MS4	Cole Creek-Flint River	Flint River
	FEC-06.DB.DP	Point of Discharge	43.067142	-83.849333	City of Flushing MS4	Cole Creek-Flint River	Flint River
Elms Elementary School	ELM-11.OP.OF	Outfall	43.094521	-83.814404	Surface Waters of the State	Armstrong Creek-Flint River	Flint River
	ELM-17.OP.OF	Outfall	43.094203	-83.813723	Surface Waters of the State	Armstrong Creek-Flint River	Flint River
	ELM-18.OP.OF	Outfall	43.094419	-83.814180	Surface Waters of the State	Armstrong Creek-Flint River	Flint River
	ELM-19.OP.OF	Outfall	43.095483	-83.814526	Surface Waters of the State	Armstrong Creek-Flint River	Flint River
	ELM-20.OP.OF	Outfall	43.094574	-83.814724	Surface Waters of the State	Armstrong Creek-Flint River	Flint River

Date Updated: March 24, 2025

Receiving Waters Table
Permit Cycle 2023-2028


Flushing Community Schools							
Facility	**Structure ID**	**Outfall or Point of Discharge**	**GPS Coordinates (Latitude/Longitude)**		**Receiving Regulated MS4 or Waters of the State**	**Receiving Waters**	**Watershed**
	ELM-21.OP.OF	Outfall	43.094406	-83.814076	Surface Waters of the State	Armstrong Creek-Flint River	Flint River
Flushing High School	FHS-04.SCC.DP	Point of Discharge	43.074831	-83.843226	City of Flushing MS4	Freeman Drain-Flat River	Flint River
	FHS-05.SCC.DP	Point of Discharge	43.074848	-83.843519	City of Flushing MS4	Freeman Drain-Flat River	Flint River
	FHS-06.SCC.DP	Point of Discharge	43.074854	-83.843905	City of Flushing MS4	Freeman Drain-Flat River	Flint River
	FHS-07.SCC.DP	Point of Discharge	43.074829	-83.844761	City of Flushing MS4	Freeman Drain-Flat River	Flint River
	FHS-13.SCC.DP	Point of Discharge	43.074815	-83.845516	City of Flushing MS4	Freeman Drain-Flat River	Flint River
	FHS-38.MH.DP	Point of Discharge	43.076799	-83.843821	City of Flushing MS4	Armstrong Creek-Flint River	Flint River
	FHS-39.OP.OF	Outfall	43.076708	-83.843108	City of Flushing MS4	Armstrong Creek-Flint River	Flint River
	FHS-40.SCC.DP	Point of Discharge	43.078238	-83.843232	City of Flushing MS4	Armstrong Creek-Flint River	Flint River
	FHS-54.OP.DP	Point of Discharge	43.076961	-83.843047	City of Flushing MS4	Armstrong Creek-Flint River	Flint River
	FHS-55.SCC.DP	Point of Discharge	43.077355	-83.843205	City of Flushing MS4	Armstrong Creek-Flint River	Flint River
	FMS-10-OP.OF	Outfall	43.07852	-83.831479	Surface Waters of the State	Bowman Drain	Flint River

Date Updated: March 24, 2025

Receiving Waters Table
Permit Cycle 2023-2028

Flushing Community Schools							
Facility	**Structure ID**	**Outfall or Point of Discharge**	**GPS Coordinates (Latitude/Longitude)**		**Receiving Regulated MS4 or Waters of the State**	**Receiving Waters**	**Watershed**
Flushing Middle School	FMS-13-OP.OF	Outfall	43.079831	-83.831793	Surface Waters of the State	Bowman Drain	Flint River
	FMS-41.DR.DP	Point of Discharge	43.079076	-83.836825	City of Flushing MS4	Bowman Drain	Flint River
Seymour Elementary School-Soccer Fields Complex	SES-04.DR.DP	Point of Discharge	43.048578	-83.861991	City of Flushing MS4	Cole Creek-Flint River	Flint River
Springview Elementary School	SPV-05.CB.DP	Point of Discharge	43.071489	-83.825546	City of Flushing MS4	Armstrong Creek-Flint River	Flint River
	SPV-08.SCC.DP	Point of Discharge	43.073477	-83.825549	City of Flushing MS4	Armstrong Creek-Flint River	Flint River

Date Updated: March 24, 2025



= Property Lines

= Offsite MS4

= Catch Basin

= Manhole

North

4335 North Seymour Road, Flushing, Michigan 48433

Bus Garage & Maintenance

Flushing Community Schools

environmental group
37720 Interchange Drive
Farmington Hills, MI 48335
Phone: 248-426-0165
Fax: 248-427-0305

Revision Date :	6/19/2020
Drawn by:	CD
Reviewed:	LE
Page #:	1 of 2
Scale:	Not to Scale



4335 North Seymour Road, Flushing, Michigan 48433

= Property Line


North

Bus Garage and Maintenance

Flushing Community Schools

37720 Interchange Drive
Farmington Hills, MI 48335
Phone: 248-426-0165
Fax: 248-427-0305

Revision Date :	6/19/2020
Drawn by:	CD
Reviewed:	LE
Page #:	2 of 2
Scale:	Not to Scale



= Catch Basin
= Manhole
= French Drain
= Offsite MS4
= Sanitary
= Infiltration Basin
= Open Pipe Outlet
= Drainage Receptor
= Trench Drain
= Property Lines
= Buried Structure
= Stabilized Outlet
= Flow Splitter
= Hydrodynamic Separator
= Pond/Basin
= Swale/Stormwater Conveyance Channel
= Underground Detention System

North


525 Coutant St, Flushing, MI 48433

Central Elementary School / Football Field Complex

Flushing Community Schools

37720 Interchange Drive
Farmington Hills, MI 48335
Phone: 248-426-0165
Fax: 248-427-0305

Revision Date :	12/15/2023
Drawn by:	SF
Reviewed:	LEK
Page #:	1 of 2
Scale:	Not to Scale



= Catch Basin
= Manhole
= French Drain
= Offsite MS4
= Sanitary
= Infiltration Basin
= Open Pipe Outlet
= Drainage Receptor
= Trench Drain
= Property Lines
= Buried Structure
= Stabilized Outlet
= Flow Splitter
= Hydrodynamic Separator
= Pond/Basin
= Swale/Stormwater Conveyance Channel
= Underground Detention System

North

525 Coutant St, Flushing, MI 48433

Central Elementary School / Football Field Complex

Flushing Community Schools

37720 Interchange Drive
Farmington Hills, MI 48335
Phone: 248-426-0165
Fax: 248-427-0305

Revision Date :	12/15/2023
Drawn by:	SF
Reviewed:	LEK
Page #:	2 of 2
Scale:	Not to Scale



522 North McKinley Road, Flushing, Michigan 48433

= Property Line

= Manhole

= Sanitary Sewer


North

Central Office

Flushing Community Schools

environmental group
37720 Interchange Drive
Farmington Hills, MI 48335
Phone: 248-426-0165
Fax: 248-427-0305

Revision Date :	6/18/2020
Drawn by:	CD
Reviewed:	LE
Page #:	1 of 1
Scale:	Not to Scale



409 Chamberlain Street, Flushing, Michigan 48433

= Property Line

= Catch Basin

= Manhole

= Infiltration Basin

= Open Pipe Outlet

= Stabilized Outlet

= Drainage Receptor

= Sanitary Sewer


North

Early Childhood Center

Flushing Community Schools

37720 Interchange Drive
Farmington Hills, MI 48335
Phone: 248-426-0165
Fax: 248-427-0305

Revision Date :	6/26/2020
Drawn by:	CD
Reviewed:	LE
Page #:	1 of 2
Scale:	Not to Scale



409 Chamerlain Street, Flushing, Michigan 48433

= Property Line

= Offsite MS4

= Catch Basin

= Manhole

North


Early Childhood Center

Flushing Community Schools

environmental group

37720 Interchange Drive
Farmington Hills, MI 48335
Phone: 248-426-0165
Fax: 248-427-0305

Revision Date :	6/22/2020
Drawn by:	CD
Reviewed:	LE
Page #:	2 of 2
Scale:	Not to Scale



= Catch Basin
= Manhole
= French Drain
= Offsite MS4
= Sanitary
= Infiltration Basin
= Open Pipe Outlet
= Drainage Receptor
= Trench Drain
= Property Lines
= Buried Structure
= Stabilized Outlet
= Flow Splitter
= Hydrodynamic Separator
= Pond/Basin
= Swale/Stormwater Conveyance Channel
= Underground Detention System

North

6125 Elms Road, Flushing Township, Michigan 48433

Elms Elementary School

Flushing Community Schools

environmental group
37720 Interchange Drive
Farmington Hills, MI 48335
Phone: 248-426-0165
Fax: 248-427-0305

Revision Date :	07/30/2024
Drawn by:	EG
Reviewed:	KD
Page #:	1 of 1
Scale:	Not to Scale



= Catch Basin
= Manhole
= French Drain
= Offsite MS4
= Sanitary
= Infiltration Basin
= Open Pipe Outlet
= Drainage Receptor
= Trench Drain
= Property Lines
= Buried Structure
= Stabilized Outlet
= Flow Splitter
= Hydrodynamic Separator
= Pond/Basin
= Swale/Stormwater Conveyance Channel
= Underground Detention System

North


5039 Deland Rd, Flushing, MI 48433

Flushing High School

Flushing Community Schools

37720 Interchange Drive
Farmington Hills, MI 48335
Phone: 248-426-0165
Fax: 248-427-0305

Revision Date :	12/22/2023
Drawn by:	EDG
Reviewed:	LEK
Page #:	1 of 4
Scale:	Not to Scale



= Catch Basin
= Manhole
= French Drain
= Offsite MS4
= Sanitary
= Infiltration Basin
= Open Pipe Outlet
= Drainage Receptor
= Trench Drain
= Property Lines
= Buried Structure
= Stabilized Outlet
= Flow Splitter
= Hydrodynamic Separator
= Pond/Basin
= Swale/Stormwater Conveyance Channel
= Underground Detention System

North

5039 Deland Rd, Flushing, MI 48433

Flushing High School

Flushing Community Schools

37720 Interchange Drive
Farmington Hills, MI 48335
Phone: 248-426-0165
Fax: 248-427-0305

Revision Date :	12/22/2023
Drawn by:	EDG
Reviewed:	LEK
Page #:	2 of 4
Scale:	Not to Scale



5039 Deland Rd, Flushing, MI 48433

= Catch Basin
= Manhole
= French Drain
= Offsite MS4
= Sanitary
= Infiltration Basin
= Open Pipe Outlet
= Drainage Receptor
= Trench Drain
= Property Lines
= Buried Structure
= Stabilized Outlet
= Flow Splitter
= Hydrodynamic Separator
= Pond/Basin
= Swale/Stormwater Conveyance Channel
= Underground Detention System

North

Flushing High School

Flushing Community Schools

37720 Interchange Drive
Farmington Hills, MI 48335
Phone: 248-426-0165
Fax: 248-427-0305

Revision Date :	12/22/2023
Drawn by:	EDG
Reviewed:	LEK
Page #:	3 of 4
Scale:	Not to Scale



= Catch Basin
= Manhole
= French Drain
= Offsite MS4
= Sanitary
= Infiltration Basin
= Open Pipe Outlet
= Drainage Receptor
= Trench Drain
= Property Lines
= Buried Structure
= Stabilized Outlet
= Flow Splitter
= Hydrodynamic Separator
= Pond/Basin
= Swale/Stormwater Conveyance Channel
= Underground Detention System

North


5039 Deland Rd, Flushing, MI 48433

Flushing High School

Flushing Community Schools

37720 Interchange Drive
Farmington Hills, MI 48335
Phone: 248-426-0165
Fax: 248-427-0305

Revision Date :	12/22/2023
Drawn by:	EDG
Reviewed:	LEK
Page #:	4 of 4
Scale:	Not to Scale



= Property Lines
= Open Pipe Outlet
= Infiltration Basin
= Catch Basin
= Sanitary
= Drainage Receptor
= Manhole
= Pond

North

8100 West Carpenter Road, Flushing, MI 48433

Flushing Middle School

Flushing Community Schools

37720 Interchange Drive
Farmington Hills, MI 48335
Phone: 248-426-0165
Fax: 248-427-0305

Revision Date :	05/04/2021
Drawn by:	JLP
Reviewed:	EDG
Page #:	1 of 1
Scale:	Not to Scale



= Catch Basin
= Manhole
= French Drain
= Offsite MS4
= Sanitary
= Infiltration Basin
= Open Pipe Outlet
= Drainage Receptor
= Trench Drain
= Property Lines
= Buried Structure
= Stabilized Outlet
= Flow Splitter
= Hydrodynamic Separator
= Pond/Basin
= Swale/Stormwater Conveyance Channel
= Underground Detention System

North

3088 N Seymour Rd, Flushing, MI 48433

Seymour Elementary School/ Soccer COMPLEX

Flushing Community Schools

environmental group
37720 Interchange Drive
Farmington Hills, MI 48335
Phone: 248-426-0165
Fax: 248-427-0305

Revision Date :	12/14/2023
Drawn by:	CCD
Reviewed:	LEK
Page #:	3 of 3
Scale:	Not to Scale



= Catch Basin
= Manhole
= French Drain
= Offsite MS4
= Sanitary
= Infiltration Basin
= Open Pipe Outlet
= Drainage Receptor
= Trench Drain
= Property Lines
= Buried Structure
= Stabilized Outlet
= Flow Splitter
= Hydrodynamic Separator
= Pond/Basin
= Swale/Stormwater Conveyance Channel
= Underground Detention System

North


3088 N Seymour Rd, Flushing, MI 48433

Seymour Elementary School/ Soccer COMPLEX

Flushing Community Schools

37720 Interchange Drive
Farmington Hills, MI 48335
Phone: 248-426-0165
Fax: 248-427-0305

Revision Date :	12/14/2023
Drawn by:	CCD
Reviewed:	LEK
Page #:	2 of 3
Scale:	Not to Scale



= Catch Basin
= Manhole
= French Drain
= Offsite MS4
= Sanitary
= Infiltration Basin
= Open Pipe Outlet
= Drainage Receptor
= Trench Drain
= Property Lines
= Buried Structure
= Stabilized Outlet
= Flow Splitter
= Hydrodynamic Separator
= Pond/Basin
= Swale/Stormwater Conveyance Channel
= Underground Detention System

North


3088 N Seymour Rd, Flushing, MI 48433

Seymour Elementary School/ Soccer COMPLEX

Flushing Community Schools

37720 Interchange Drive
Farmington Hills, MI 48335
Phone: 248-426-0165
Fax: 248-427-0305

Revision Date :	10/03/2024
Drawn by:	CCD
Reviewed:	LEK
Page #:	1 of 3
Scale:	Not to Scale



1233 Springview Drive, Flushing, Michigan

= Catch Basin
= Manhole
= Open Pipe Outlet
= Sanitary
= City of Flushing MS4
= Property Line
= Stormwater Conveyance Channel

North

Springview Elementary School

Flushing Community Schools

37720 Interchange Drive
Farmington Hills, MI 48335
Phone: 248-426-0165
Fax: 248-427-0305

Revision Date :	12/4/20
Drawn by:	EG
Reviewed:	JK
Page #:	1 of 1
Scale:	Not to Scale

Appendix B

Enforcement Policies and Tracking Forms

Development Date: May 17, 2025
Revision Date: February 10, 2025
Revision Date: May 27, 2025

Municipal Separate Storm Sewer System Noncompliance Enforcement Tracking
Flushing Community Schools
Permit No. TBD

Report Number	Name	Date	Location of Violation	Business/ Organization	Description of Violation	Description of Enforcement Response	Compliance Schedule Date	Date Violation Resolved
1								
2								
3								
4								
5								
6								
7								
8								
9								
10								
11								
12								
13								

District Illicit Discharge/Illegal Dumping Reporting Form
Flushing Community Schools

Date:_____ Time_____

Inspectors:_____

I. ORIGIN OF REPORT

1. Describe the reason for conducting the investigation.

- ❑ Illicit Discharge Inspection (Routine)
- ❑ Facility Staff
- ❑ Citizen Complaint
- ❑ Other _____

II. SOURCE

1. Describe location of source of discharge (company name, address, cross streets, physical features, etc.)

_____

_____

2. Describe the Source:

- ❑ Residential
- ❑ Transportation Facility
- ❑ Construction Site
- ❑ Custodial
- ❑ Other _____

3. Facility of the Source:_____

_____

III. TYPE

1. Describe the type of material discharged:

- ❑ Sanitary Leak/Spill
- ❑ Paint Discharge
- ❑ Dumpster Discharge
- ❑ Cleaning Discharge
- ❑ Unhardened Cement Discharge
- ❑ Paint Discharge
- ❑ Vehicle Repair
- ❑ Vehicle Washing
- ❑ Grey Water Discharge
- ❑ Landscape Material Dumping
- ❑ Cooling Water Discharge
- ❑ Allowable Discharge
- ❑ Other _____

Provide Additional Information:_____

_____

2. Other Sources:

- ❑ Illicit Connection
- ❑ Construction Site
- ❑ Other _____

IV. FOLLOW-UP AND ENFOREMENT ACTIVITIES

1. Describe Corrective Actions:_____

_____

2. Describe Enforcement Action:

- ❑ None/Incident Resolved
- ❑ Verbal Notice
- ❑ Administrative Action
- ❑ Cleaning Discharge

3. Date Resolved:_____

4. Responsible Party

Signature:_____

Flushing Community Schools
Board of Education
Resolution in Support of Stormwater Management Plan

WHEREAS Flushing Community Schools owns and operates facilities within the boundaries of the Flint urbanized area which discharges stormwater though a municipal separate storm sewer system (MS4) to surface waters of the State of Michigan; and

WHEREAS The Michigan Department of Environment, Great Lakes, and Energy maintains oversight and regulatory authority for compliance with the terms and conditions of the NPDES Municipal Separate Storm Sewer System discharge permit; and

WHEREAS Flushing Community Schools has applied for and received permit coverage to discharge stormwater from Flushing Community Schools facilities to the MS4; and

WHEREAS Flushing Community Schools agrees to comply with the NPDES Municipal Separate Storm Sewer System discharge permit requirements, and

WHEREAS Flushing Community Schools has developed a Stormwater Management Program Plan (SWMP) outlining the policies, procedures, and best management practices to be employed by the district to comply with the permit requirements, and

WHEREAS the conditions of the NPDES Municipal Separate Storm Sewer System discharge permit require Flushing Community Schools to develop policies and procedures that prohibit illicit discharges to their stormwater system and to implement appropriate enforcement procedures and actions to detect and eliminate sueh illicit discharges, and

WHEREAS Flushing Community Schools agrees to prohibit the discharge of non-stormwater discharges into the storm drain system, including but not limited to pollutants or waters containing any pollutants, and

WHEREAS Flushing Community Schools agrees to eliminate illicit discharges and illicit connections, and

WHEREAS Flushing Community Schools agrees to prohibit the construction, use, maintenance, or continued existence of illicit connections to the storm drain system. This prohibition expressly includes, without limitation, illicit connections made in the past, regardless of whether the connection was permissible under law or praetiees applicable or prevailing at the time of connection, and

WHEREAS Flushing Community Schools agrees to obtain a Part 91 permit from the appropriate state, county, or local governmental soil erosion permitting agency for new development and redevelopment projects that disturb one or more acres, and

WHEREAS Flushing Community Schools agrees to obtain a construction site permit from the local municipality or other governing unit for new development and redevelopment projects that disturb one or more acres, and

WHEREAS Flushing Community Schools agrees to inspect, operate, and maintain structural controls for the purpose of reducing pollutant contribution, control runoff, and decrease or eliminate stream bank erosion due to stormwater runoff, and

WHEREAS Flushing Community Schools agrees to comply with the requirements of the State of Michigan Permit (Rule 323.2190) for stormwater discharge from construction activity.

THEREFORE, be it resolved that the Flushing Community Schools Board of Edueation is highly committed to practicing sound environmental principles including the reduction of pollutants to surface waters though discharges of stormwater. The Board hereby approves and instructs the district Superintendent to enforce the above listed policies and procedures for illicit discharge elimination, control of stormwater runoff and long-term operation and maintenance of structural controls as part of the overall Flushing Community Schools Stormwater Management Program Plan.

Duly passed and approved by the Flushing Community Schools Board of Education, Genesee, Michigan this 13th day of June, 2023.

Approved: Sheldon, Strnad, Winkel, Ausiello, Dolgan, LeCureux (6) **Attest:** none (0)

Janice R Winkel
President

Megan LeCureux
Secretary

Stormwater Management – Illicit Discharge Regulatory Policy

Flushing Community Schools
Permit Number: TBD
Issue date: May 17, 2023

This illicit discharge regulatory policy was developed as a regulatory policy for prevention of pollution from storm water runoff and to protect the quality of the waters of the State of Michigan through the regulation of non-stormwater discharges to the municipal separate storm sewer system (MS4) to the maximum extent practicable as required by federal and state law. This regulatory mechanism establishes methods for controlling the introduction of pollutants into the MS4 in order to comply with the requirements of the National Pollutant Discharge Elimination System (NPDES) permit through the Michigan Department of Environment, Great Lakes, and Energy (EGLE). The objectives of the regulatory mechanism are:

1. To regulate the contribution of pollutants to the MS4 by stormwater discharges by any user.
2. To prohibit illicit connections and discharges into the MS4.
3. To establish authority to investigate, inspect, and monitor suspected illicit discharges.

District properties include all Flushing Community Schools properties.

Illicit Discharge means any discharge to, or seepage into the separate stormwater drainage system that is not composed entirely of stormwater or uncontaminated groundwater except discharges pursuant to an NPDES permit.

Illicit Connection means a physical connection to the MS4 separate stormwater system that primarily conveys non-stormwater discharges other than uncontaminated groundwater into the MS4 separate storm sewer system; or a physical connection not authorized or permitted by the local authority, where a local authority requires authorization or a permit for physical connections.

Prohibitions of Illicit Discharges

1. Prohibition of Illicit Discharges:
    a. Flushing Community Schools prohibits the discharge of non-stormwater discharges into the storm drain system, including but not limited to pollutants or waters containing any pollutants.
    b. No person shall throw, drain, or otherwise discharge, cause, or allow others under its control to throw, drain, or otherwise discharge into the MS4 any pollutants or waters containing any pollutants, other than stormwater.

2. The following discharge is **not prohibited**:
    a. This policy excludes prohibitions from the discharge or flows from firefighting activities to the Flushing Community Schools MS4. Discharge or flows from firefighting activities will

be addressed only if they are identified as significant sources of pollutants to surface waters of the state.

b. The following activities are **not prohibited** under this policy unless they are determined to be significant sources of pollutants to surface waters of the state:
    - Water line flushing and discharges from potable water sources.
    - Landscape irrigation runoff, lawn water runoff, and irrigation waters.
    - Diverted stream flows and flows from riparian habitats and wetlands.
    - Rising groundwater and springs.
    - Uncontaminated groundwater infiltration and seepage.
    - Uncontaminated pumped groundwater, except groundwater cleanups specifically authorized by NPDES permits.
    - Air conditioning condensation.

Prohibition of Illicit Connections

1. The construction, use, maintenance, or continued existence of illicit connections to the MS4 is prohibited.
2. This prohibition expressly includes, without limitation, illicit connections made in the past, regardless of whether the connection was permissible under law or practices applicable or prevailing at the time of connection.
3. A person is considered to be in violation of this regulatory mechanism if the person connects a line conveying sewage to the MS4 or allows such a connection to continue.
4. Improper connections in violation of this regulatory mechanism must be disconnected and redirected.
5. Illicit discharge and connections will be eliminated immediately.

Enforcement

The District Stormwater Program Manager will administer and enforce the stormwater management program, including investigate, inspect, and monitor suspected illicit discharges or illicit connections.

If you witness or think a discharge is taking place, please contact the Flushing Community Schools at (810) 955-8682.

Stormwater Management - Post-Construction Policy & Procedure

Flushing Community Schools
Permit Number: TBD
Issue date: May 17, 2023

Applies To: As required by the National Pollutant Discharge Elimination System (NPDES) permit for Flushing Community Schools, the scope of this Guideline includes all development and redevelopment projects on District properties that involve either:

a. earth disturbance of one (1) acre or greater,
   OR
b. earth disturbance of less than one (1) acre, but which are part of a larger common plan of development or sale that would disturb one (1) acre or more.

Post-Construction Requirements Policy Statement

Flushing Community Schools development and redevelopment projects on District property are regulated under and must comply with the Flushing Community Schools NPDES permit for stormwater discharges, as issued by the Michigan Department of Environment, Great Lakes and Energy (EGLE). The Stormwater Management Post-Construction Requirements Guideline has been developed to provide guidance regarding responsibilities and actions to meet the NPDES permit conditions for development and redevelopment projects on district owned properties.

Post-Construction Plan for Stormwater Management

The post-construction plan for stormwater management on regulated sites **must** include:

- A minimum treatment volume standard to address water quality impacts.
- Channel protection criteria to address resource impairment resulting from flow volumes and rates.
- Review sites with known soil and/or groundwater contamination, including potential “hot spots” and evaluate the use of infiltration BMPs to meet water quality treatment and channel protection criteria to ensure that infiltration BMPs do not exacerbate existing conditions. Hot spots include areas with the potential for significant pollutant loading such as vehicle service and maintenance facilities, vehicle equipment cleaning facilities, fleet storage areas for buses, and outdoor liquid container storage.
- Drawings showing the location of stormwater control measures and the storm system.
- Details on the proposed stormwater control measures.
- Operation & Maintenance (O&M) requirements.
- Supporting information
    - Calculations used for designing all components of the stormwater management systems.
    - Total Suspended Solids (TSS) design removal rates and supporting manufacturer documentation, if applicable.

- Geotechnical report including soil boring and infiltration test data.

The project team [Architecture, Engineering & Construction, Other Project Manager, Project Developer and/or Contractors] shall develop the post-construction plan for stormwater management in accordance with this guideline and the NPDES permit.

Water Quality Treatment Volume Standard

The minimum treatment volume standard **must** be either:

a. Treat the first one (1) inch of runoff from the entire site.
   OR
b. Treat the runoff generated from ninety percent (90%) of all runoff-producing storms for the project site, as summarized in MDEQ's memo dated March 24, 2006 https://www.michigan.gov/documents/deq/wrd-hsu-ninety-percent_557709_7.pdf

Total Suspended Solids

The treatment methods must be designed on a site-specific basis to achieve the following:

a. A minimum of eighty percent (80%) removal of total suspended solids (TSS), as compared with uncontrolled runoff.
   OR
b. Discharge concentrations of TSS not to exceed 80 milligrams per liter (80mg/L).

A minimum treatment volume standard is not required where site conditions are such that TSS concentrations in storm water discharges will not exceed 80mg/L.

Channel Protection Criteria

The channel protection criteria must maintain post-development site runoff volume and peak flow rate at or below existing levels for all storms up to the 2-year, 24-hour event. "Existing levels" means the runoff volume and peak flow rate for the last land use prior to the planned new development or redevelopment. More restrictive channel protection criteria may be utilized on a case-by-case basis, as appropriate.

Site Plan Review

This policy is to establish a requirement to submit a site plan for review as required by the EGLE NPDES Stormwater Discharge Permit and ensure that water quality objectives, erosion and sediment control requirements, and BMP maintenance are considered to the maximum extent practicable.

Flushing Community Schools shall evaluate proposed construction activities to determine:

- If the activity meets the criteria of a development or redevelopment project with an earth disturbance greater than or equal to 1 acre, or part of a common plan of development resulting in a development or redevelopment activity greater than or equal to 1 acre in size.
- Does the development or redevelopment project discharge to waters of the state, or to a county, city, or township MS4.

If the development or redevelopment project discharges directly to waters of the state, Flushing Community Schools shall comply with the post-construction standards outlined in this SWMP.

If the development or redevelopment project discharges to a regulated county, city, or township MS4, Flushing Community Schools shall submit the site plan for review and approval. Site plan approval by the county, city, or township of an equivalent post-construction standard ensures acceptable compliance with the Flushing Community Schools NPDES MS4 Stormwater Discharge Permit. Flushing Community Schools shall obtain and maintain a copy of the site plan approval *document*.

If the development or redevelopment project discharges to a county, city, or township MS4 that is not regulated or require site plan review, Flushing Community Schools shall comply with the post-construction standards outlined in this SWMP.

Operations & Maintenance Plans

All structural and vegetative stormwater control measures installed as a requirement under this section of the permit shall include a plan for maintaining maximum design performance through long-term operation and maintenance.

Enforcement

The Flushing Community Schools Stormwater Program Manager will administer and enforce the stormwater management program, including maintaining procedures, guidance, information, etc. to aid district staff and contractors in complying with the post-construction requirements for stormwater management.

Appendix C

SEMCOG Posters & Illicit Discharge Poster

How to Spot Illicit Discharges

Sanitary Sewer Discharge Observations:

- Sanitary Debris
- Staining on pipe
- Heavy Foam
- Gray or Discolored Water
- Odors (sewage, chlorine, rotten eggs and detergents)





Illegal Dumping, Spills, or Floor Drain Connection Observations:

- Oily Sheen
- Trash, non-sanitary debris
- Petroleum odors
- Stained sediment, rocks, and vegetation
- Vehicle bay washout






Agricultural Runoff, Fertilizers, or Sanitary Sewer Waste Observations:

- Algae growth at or near outlet
- Heavy vegetation at or near outlet




What to Report

- **Spills and Contamination to lakes, river and streams**
  District Stormwater Coordinator, MDEQ, Environmental Health Department, Drain Commissioner's Office
- **Suspicious dumping or discharges from pipes**
  District Stormwater Coordinator, MDEQ, Environmental Health Department, Drain Commissioner's Office
- **Sewage on the ground or in surface water**
  District Stormwater Coordinator, Environmental Health Department
- **Large number of dead fish in waterways**
  District Stormwater Coordinator, MDEQ, Environmental Health Department
- **Failing or leaking septic systems**
  District Stormwater Coordinator, Environmental Health Department
- **Construction site soil erosion to waterways**
  District Stormwater Coordinator, local SESC Enforcing Agency
- **Polluted runoff from storage piles/dumpsters entering waterways**
  District Stormwater Coordinator, Environmental Health Department, Drain Commissioner's Office

Important Numbers

Emergency Call 9-1-1

- Pollution Emergency Alerting System (PEAS) **1-800-292-4706**
- 24 Hour Spill Hot Line – Arch Environmental Group **1-248-522-2821**

Non-Emergency

- School District Contact Number _____
- DEQ Environmental Assistance Center **1-800-662-9278**
- Eaton County Drain Commissioner **1-800-292-4706**
- Genesee County Drain Commissioner **1-810-732-2940**
- Livingston County Department of Public Health **1-517-546-9858**
- Macomb County Public Works **1-877-679-4357**
- Oakland County Water Resources **1-248-858-0958**
- Washtenaw County Drain Commissioner **1-724-222-6860**
- Wayne County Department of the Environment **1-888-223-2363**

KEEP OUR WATER CLEAN



onewater

mionewater.com

IF YOU SEE POLLUTION, REPORT IT

KEEP OUR WATER CLEAN

onewater

mionewater.com



CLEAN UP AFTER YOUR PETS

BUILD ON WATER QUALITY

onewater

mionewater.com

DISPOSE OF ALL GREASE IN THE TRASH

BUILD ON WATER QUALITY

onewater

mionewater.com

ONLY RAIN DOWN THE STORM DRAIN

Remember, you're not just washing your car

Our Water. Our Future.

Ours to Protect



Practice good car care

Did you know there are over four million vehicles in Southeast Michigan? **Practicing good car care helps protect our lakes and streams.**

How? Storm drains and roadside ditches lead to our lakes and streams. So, if motor fluids or dirty water from washing our cars are washed or dumped into the storm drain, it pollutes our local waterways.

What can you do? Simple. **Keep your car tuned and fix leaks** promptly, **recycle used motor oil** and other fluids, **take your car to the carwash or wash your car on the grass.**

Find out more at www.semcog.org.

Brought to you by the Southeast Michigan Partners for Clean Water.

Support provided by SEMCOG, the Southeast Michigan Council of Governments (313-961-4266) and the Rouge River National Wet Weather Demonstration Project.

Remember, you're not just fertilizing your lawn

Our Water. Our Future.

Ours to Protect



Fertilize sparingly and caringly

Storm drains found in our streets and yards empty into our lakes and streams. So, **when we fertilize our lawn we could also be fertilizing our lakes and streams**. While fertilizer is good for our lawn, it's bad for our water. Fertilizer in our lakes and streams causes algae to grow. Algae can form large blooms and uses up oxygen that fish need to survive. With 1.5 million homes in Southeast Michigan, all of us need to be aware of the far-reaching effects of our lawn care practices.

What can you do? Simple. Use a **no or low phosphorus fertilizer,** select a **slow release** fertilizer where at least half of the nitrogen is water insoluble (check the ingredients on the label), keep fertilizer away from lakes, streams, and storm drains, and **sweep excess fertilizer** back onto your lawn. Not only will our lakes and streams thank you, but so will your pocketbook!

Find out more at www.semcog.org.

Brought to you by the Southeast Michigan Partners for Clean Water.

Support provided by SEMCOG, the Southeast Michigan Council of Governments (313-961-4266) and the Rouge River National Wet Weather Demonstration Project.

Seven Simple Steps to Clean Water

Our Water. Our Future.

Ours to Protect

1. Help keep pollution out of storm drains
2. Fertilize sparingly and caringly
3. Carefully store and dispose of household cleaners, chemicals, and oil
4. Clean up after your pet
5. Practice good car care
6. Choose earth friendly landscaping
7. Save water

Our Water. Our Future. Ours to Protect.

Find out more at www.semcog.org.

Brought to you by the Southeast Michigan Partners for Clean Water.
Support provided by SEMCOG, the Southeast Michigan Council of Governments (313-961-4266) and the Rouge River National Wet Weather Demonstration Project.

Remember, it's not just toxic to you

Our Water. Our Future.

Ours to Protect



Carefully store and dispose of household cleaners, chemicals, and oil

Did you know that many **household products are dangerous to our pets, kids, and the environment?**
These materials get into our lakes and rivers if washed or dumped into a storm drain or roadside ditch.

What can you do? Simple.

Proper disposal is key. Take household cleaners, pesticides, gasoline, antifreeze, used oil, and other dangerous products to your **community's household hazardous waste collection day.** Contact your community for more information on these events.

Find out more at www.semcog.org.

Brought to you by the Southeast Michigan Partners for Clean Water.

Support provided by SEMCOG, the Southeast Michigan Council of Governments (313-961-4266) and the Rouge River National Wet Weather Demonstration Project.

Remember, you're not just getting rid of weeds and pests

Our Water. Our Future.
Ours to Protect



Choose earth-friendly landscaping

Did you know you can **protect your kids, pets, and the environment** from the harmful effects of herbicides & pesticides by choosing earth-friendly landscaping? These chemicals wash off our lawns and gardens into our storm drains, which lead to our lakes and rivers.

What can you do? Simple.
Spot treat for specific pests and weeds or remove by hand. Mulch around plants. **Water your lawn only when it needs it.** Attract butterflies and birds by **adding plants that are native to Southeast Michigan.**

Find out more at www.semcog.org.

Brought to you by the Southeast Michigan Partners for Clean Water.

Support provided by SEMCOG, the Southeast Michigan Council of Governments (313-961-4266) and the Rouge River National Wet Weather Demonstration Project.

Remember, you're not just walking the dog

Our Water. Our Future.

Ours to Protect



Clean up after your pet

Did you know that pet waste has bacteria that makes our lakes and rivers unsafe for swimming and other recreational activities?
That happens when **pet waste left on sidewalks or yards gets washed into storm drains**
or roadside ditches that lead directly to our lakes and rivers.

What can you do? Simple.
No matter where you are **dispose of your pet's waste promptly** in the toilet or trash.

Find out more at www.semcog.org.

Brought to you by the Southeast Michigan Partners for Clean Water.

Support provided by SEMCOG, the Southeast Michigan Council of Governments (313-961-4266) and the Rouge River National Wet Weather Demonstration Project.

Remember, it ALL drains to our lakes and rivers

Our Water. Our Future.

Ours to Protect



Keep pollution out of storm drains

Storm drains and roadside ditches lead to our lakes and streams. **So, any oil, pet waste, leaves, or dirty water from washing your car or other outside activities** that enters a storm drain gets into our lakes and streams.

How can you help? Simple. **Use a broom instead of a hose** to clean your driveway. Keep leaves, grass clippings, and trash away from the storm drain, and **never dump motor oil, pet waste, or dirty, soapy water** down the storm drain.
Remember, only rain in the drain!

Find out more at www.semcog.org.

Brought to you by the Southeast Michigan Partners for Clean Water.

Support provided by SEMCOG, the Southeast Michigan Council of Governments (313-961-4266) and the Rouge River National Wet Weather Demonstration Project.

Vehicle Fluid Tips

Pollution prevention



Keep lids closed



Avoid placing near floor drains



Keep tops of barrels clean



Clean out secondary containment pallets monthly



Containers should have a clear, readable label



Keep floor clean (of spills and oil dry)

SEMCOG . . . *Reinventing Southeast Michigan*

Southeast Michigan Council of Governments



Keeping it Clean

Municipal operations for clean water

Dumpsters and loading docks



Keep dumpster lids closed and inspect for leaks.
Never place hazardous wastes in a dumpster or trash bin.
Do not hose out the dumpster interior or loading docks. Apply absorbent over any fluids spilled in the dumpster.
Check loading and unloading equipment regularly for leaks.



Vehicle and equipment fueling

Look for and report leaks on vehicles when adding fuel.
Use secondary containment when transferring fuel from the tank truck to the fuel tank. Cover storm drains in the vicinity during transfer.
Place spill cleanup materials where they are readily accessible.
Clean up small spills with absorbent materials rather than hosing down the area. Remove the absorbent materials promptly and dispose of in the trash.

Vehicle and equipment washing



Take vehicles to a commercial car wash. These facilities collect and treat the wastewater.
If you wash vehicles onsite, wash equipment and vehicles ONLY in designated facilities where the wash water drains to the sanitary sewer system or is collected and recycled.
Clean parts in a self contained unit. Make sure that the parts washer is not connected to the storm drain.
Use steam cleaning and pressure washing instead of solvents.



Vehicle parking and equipment storage

Inspect parking and storage areas for leaks.
Store vehicles and equipment inside or under cover to prevent precipitation from washing pollutants into the storm drain.
Store vehicles on a paved area that you can street sweep regularly to remove drips, leaks, and dirt.
Drain all fluids from wrecked cars when they arrive to prevent any spills or leaks.

Vehicle and equipment maintenance



Keep accurate maintenance logs and up-to-date inventory of materials.
Perform vehicle maintenance in covered, designated service bays where spills and leaks can be properly contained.
Recycle spent fluids. Do not dump down the drain or in the trash.
Avoid hosing down your work areas. Use rags for small spills, a damp mop for general cleanup, and dry absorbent for larger spills.



Chemical management – preventing leaks and spills

Fit oil and chemical storage containers with secondary containment structures to contain spilled materials.
Store materials indoors. If you do have outdoor storage areas, keep them covered to prevent rain from contacting the material.
Cover and/or contain, through erosion control practices, stockpiles of raw materials (e.g., salt, soil) to prevent polluted stormwater runoff.
Inspect storage areas regularly for spills and leaks. Keep containers and other storage devices in good condition without leaky seams or corrosion.

Chemical management – when a spill occurs



If a spill occurs, notify the key spill response personnel. If the material is hazardous, contact the local fire department.
Never wash a spill into the storm drain or leave it without cleaning it up. Contain spills and block the nearby storm drain.
Clean up non-hazardous spills by using a rag, damp cloth, or absorbent materials.

SEMCOG

Funding provided, in part, by the Rouge River National Wet Weather Demonstration Project grant #XP993743-06, and SEMCOG, the Southeast Michigan Council of Governments.

Aggregate Storage Tips

Pollution prevention



Keep salt covered



Keep cold patch materials covered



Keep aggregate materials in bins



Avoid placing materials near storm drains



Keep material areas swept



Catch basin cleanings and street sweepings must be contained

SEMCOG . . . *Reinventing Southeast Michigan*

Southeast Michigan Council of Governments

Appendix D

Inspection Field Worksheets

Development Date: May 17, 2025
Revision Date: February 10, 2025
Revision Date: May 27, 2025

Routine Storm Sewer System Inspection Table

Building:			**Client:**	
Inspectors:			**Start Date:**	
			Inspection Type:	

ID #	Type	Inspected	Standing Water	Color	Odor	Structure Staining	Suds	Oil Sheen	Bacterial Sheen	Sewage	Algae	Slimes	Abnormal Vegetation	Flow Observed	Velocity of Flow	Color of Flow	Blockages	Erosion	Needs Cleaning?	Structural Issues	Structural Trend	Stenciled

environmental group

Routine Storm Sewer System Inspection Table

Building:	"School/Location"		**Client:**	"School District"	
Inspectors:	"Inspectors Name"		**Start Date:**	"Start Date"	"End Date"
			Inspection Type:	"Routine Storm Sewer Inspection or other"	

ID #	Type	Inspected	Standing Water	Color	Odor	Structure Staining	Suds	Oil Sheen	Bacterial Sheen	Sewage	Algae	Slimes	Abnormal Vegetation	Flow Observed	Velocity of Flow	Color of Flow	Blockages	Erosion	Needs Cleaning?	Structural Issues	Structural Trend	Stenciled
"Storm Structure ID" Ex. ADM-01.CB(ADM represents building such as Admin, 01=number of structure, and CB=structure type.	Type of Structure (Catch Basin, Manhole, Pond, Swale, Pipe, etc.)	Was it inspected this round. (Yes or No)	Was there standing water in the structure? (Yes or No)	What color is the standing water if present? (Clear, Cloudy, Brown, White, etc.)	Does the basin have a noticeable odor? (Yes or No)	Is there staining on the interior of the structure? (Yes or No) This could be staining caused by a current illicit discharge, remnants of a past illicit discharge, or natural staining from iron oxidizing bacteria etc.	Are there suds present in the structure (organic suds - caused by aeration/natural causes, soapy suds, or no)	Is there oil sheen present on the water surface in the structure? (Significant - indicative of an illicit discharge, OR No)	Is there bacterial sheen on water surface of the structure? (Yes or No) - We ask this to confirm that a sheen in a photo was bacterial instead of oil.	Is evidence of sewage present in water in structure? (toilet paper, poo, etc.) - (Yes or No)	Is Algae growth present in the structure? (Yes or No)	Are there slimes present in the structure? (Yes or No)	Is there abnormal veg. growth in structure? (Yes or No)	Was there water flow observed in the structures pipes? (No, Trickle(light flow), Intermittent(Indicative of a sump), or continuous(usually occurs during/after a rain event))	What is the estimated velocity of the water flow if present? (N/A, Trickle, slow, moderate, or substantial) Substantial occurs during or after a rain event.	What is the color of the flow within the structure? (N/A, Brown, Yellow, Clear, Cloudy, etc.) Used to be sure there is no evidence of illicit activities during or after rain events.	Are any pipes blocked? (Yes or No) This would be evident if there was a visible blockage in a pipe OR if the water level in the structure is high.	Is there erosion occurring around the structure? (Yes or No)	Does the structure have sediment build-up in the sump or bottom? (Significant - for 40% full sump depth below outpipe or higher, moderate - for 30% to 40% sump depth below outpipe, preventative - for 20% to 30% sump depth, OR no cleaning for below 20%. Or Cleaned)	Are there any issues with the structure itself and how severe is it? - This could be for cracking on the interior/exterior, sink holes, erosion, etc. (Significant, Moderate, Preventative, or None, Repaired-since last inspection, or Partial Repair)	If there is a structural issue, is the structural issue worsening since the previous inspection? (Stable - appears the same/hasn't worsened, Improving - appears better/usually for a repair or for erosion lessening, OR deteriorating - the condition has worsened)	Does the structure have a "No Dumping - Drains to River" stencil in place? (No - means it needs one, Yes - it has one, Update - it has one, but it is fading, OR N/A - the structure is in the grass)

environmental group

Pond Inspection Form

Building:		**Client:**	
Inspectors:			
Date of Inspection:			

Structure Information:

Structure ID:		Number of Inlet(s) (OP):	
Pond Type:		Number of Outlet(s) (DR):	
Age of Pond:		Number of Stabilized Outlets (SO):	

Inlet(s)/Outlet(s) (OP/DR) Observations:

Are there any structural issues with the inlet(s)/outlet(s) (OP/DR)?		Structural Comments:	
Is there excess sediment buildup at the inlet(s)/outlet(s) (OP/DR)?		Are the inlet(s)/outlet(s) (OP/DR) below the water level?	

Are the inlet(s)/outlet(s) (OP/DR) accessible or overgrown with vegetation?

Pond Structure Observations:

Is there grass along the sides of the pond cut between 4" and 9"?		Is there excess vegetation along the sides of the pond (not grass)?	
Are there signs of erosion along the side slopes, berms and/or emergency spillway?		Is there evidence of animal burrows around the sidewalls of the pond?	

Pond Vegetation Observations:

How much emergent vegetation is present in the pond bottom?		Vegetation Comments:	
Is emergent vegetation made up of native or invasive species?		Is there decomposing vegetation or organic matter decaying on the pond bottom?	

General Pond Observations:

Is the pond free of trash/other debris?		Types of trash/debris present:	

General Comments:

Arch Environmental Group
37720 Interchange Drive,
Farmington Hills MI 48370

Phone: (248) 426-0135
Fax: (248) 426-0136
www.archenvgroup.com

Pond Inpsection Table Description

ID #	Enter structure ID
Type	Select from the following options: Retention Pond, Detention Pond, Retention Basin, Detention Basin
Inspected	Select Yes or No. If unable to inspect the structure, please make a comment under "General Comments" as to why you could no inspect the structure
Approximate Age of the Pond	This can be found using the history function in Google Earth for the site. Remember, this is an approximate age determination. We are interested in this information because pond life spans are between 15 and 20 years
Number of Inlet(s) (OP)	Select the number of inlet pipe(s) from the drop down menu
Number of Outlet(s) (DR)	Select the number of outlet pipe(s) from the drop down menu
Number of Stabilized Outlet(s) (SO)	Select the number of stabilized outlet(s) from the drop down menu
Are there any structural issues with the inlet(s)/outlet(s) (OP/DR)?	Examples include detached pipes, missing riprap around the inlet(s), missing stone around DR, etc. Select one of the following options: None, Preventative, Moderate, Signficant, or Repaired. Preventative = beginning signs of deterioration Moderate = signs of deterioration present but does not hinder the function of the structure Significant = deterioration has hindered the function of the structure as it was designed
Structural Comments	Describe the structural issues observed
Is there excess sediment buildup at the inlet(s)/outlet(s) (OP/DR)?	Examples include pipes that are buried under sediment or sediment levels higher than the bottom of the inlet(s)/outle
Are the inlet(s)/outlet(s) (OP/DR) below the water level?	This could be a sign that the MS4 is backed up causing water to back up into the pond. If you suspect that, please investigate if that is the case. If the MS4 is not backed up, this could be a sign that the pond is not functioning as designed
Are the inlet(s)/outlet(s) (OP/DR) accessible or overgrown with vegetation (native or invasive)?	Overgrown vegetation at the inlet(s)/outlet(s) can prevent water from freely flowing in/out of the structure
Is the grass along the sides of the pond cut between 4" and 9"?	This is an ideal height range of grass around the pond to stabilize the sidewalls of the pond and to prevent erosion around the side walls of the pond
Is there excess vegetation along the sidewalls of the pond (not grass)	Does the area look overgrown and unkept? Select from the following options: Yes or No
Are there signs of erosion along the side slopes, berms and/or emergency overflow?	Select from the following options: Yes or no
Is there evidence of animal burrows around the sidewalls of the pond?	Select from the following options: Yes or No. Animal burrows can destabilize the sidewalls of the pond
How much emergent vegetation is present in the pond bottom?	Select from the following options: 0%-25%, 25%-50%, or 50%-100%. Use your best judgement to determine this percentage. Ideally, the pond bottom should be made up of around 25% emergent vegetation Emergent Vegetation Definition: Aquatic plants that grow with their roots under water but their leaves and stems above the surface of the water
Is emergent vegetation made up of native or invasive species (phragmites or purple loosestrife)?	See reference page in the Pond Inspection Reference page for photos of Phragmites and Purple Loosestrife to see if it is present.
Vegetation Comments	If there are invasive species present, please write which ones are present
Is there vegetation or organic matter decaying on the pond bottom?	Select from the following options: Yes, No, or Unknown. If you can tell, great, this could have impact on DO or could cause flow issues through the pond
Is the pond free of trash/other debris?	Select from the following options: Yes or No. This can include trash/inorganic debris or organic material (like grass clippings, leaves, etc.)
Types of trash/debris present	Select from the following options: Trash, Natural Debris (organic material) or N/A
General Comments	Please add any other comments that you feel are important to note about the pond condition

Stream Bank Inspection Table

Client:				**Stream Name:**	
Inspectors:				**Site :**	
				Date:	
Weather in the past 24 hours:				**Current Weather:**	

Field Analysis:

Uptream Turbidity:		NTU	Upstream Temprature:		Upstream pH:		
Downstream Turbidity:		NTU	Downstream Temprature:		Downstream pH:		

Physical Characterization:

In-Stream Characteristics

Pools:	N/A
Runs:	N/A
Riffles:	N/A
Stream Bed Features:	
% of Embedded Bottom:	
Organic Materials:	
Large Wooded Debris	
Water Appearance:	
Water Odor:	

Streambank & Channel Characteristics

Depth of Run:		Stream Erodible Soils:	
Depth of Pool(s):		Bank Modifications:	
Width of Stream:		Condition of Bank:	
Stream Velocity:		Bank Slope:	
Vegitative Cover:			
Shape of Channel:			

Additional Comments:

Watershed / Biological Characteristics:

Wildlife Around Stream:	
Fish In Stream:	
Aquatic Plants in Stream:	
Extent of Alge :	
Potential Stream Impact:	

Stream Photos:

Arch Environmental Group
37720 Interchange Drive,
Farmington Hills MI 48370

Phone: (248) 426-0135
Fax: (248) 426-0136
www.archenvgroup.com

Screening Inspection Log

Building:		**Client:**	
Inspectors:		**Date**	
		Inspection Type:	

Structure Information:

ID Number:		Structure Type		Lat:		Long:	
Discharge Point/Outfall:		Location:					
Outfall Dimensions							

Observations:

Standing Water Characteristics

Standing Water:	
Color:	
Odor:	
Suds:	
Staining:	
Oil Sheen:	
Sewage:	
Bacterial Sheen:	
Floatables:	
Slimes:	
Abnormal Growth:	

Flow Characteristics

Flow Observed:	
Source of Flow:	
Velocity of Flow:	
Color of Flow:	
Flow Odor	

Maintenance

Cleaning:	
Blockages	
Structural Issues	
Structural Trend	
Stenciling:	

Additional Comments:

Sample ID And Information

Sample Collected?	
Permit Cycle:	
Last Rain Event:	
Current Weather:	
Screening Location Type:	
Other Screening Activities Conducted:	
Outfall Characterization:	
Sample sent to Lab:	

Field Analysis:	Results:	Units:	Initials:
pH:		pH units	
Temperature:		Celsius	
Surfactants:		mg/L	
Ammonia:		mg/L	
Chlorine:		mg/L	
Turbidity:		NTU	
Conductivity:		uohm/cm	

Equipment Calibration:

Date: Cal. By:

Photo ID:

Arch Environmental Group
37720 Interchange Drive,
Farmington Hills MI 48370

Phone: (248) 426-0135
Fax: (248) 426-0136
www.archenvgroup.com

TMDL Screening Inspection Log

Building:		**Client:**	
Inspectors:		**Date**	
		Inspection Type:	

Structure Information:

ID Number:		Structure Type		Lat:		Long:	
Type:		Location:					
Outfall Dimensions							

Observations:

Standing Water Characteristics

Standing Water:	
Color:	
Odor:	
Suds:	
Staining:	
Oil Sheen:	
Sewage:	
Bacterial Sheen:	
Algae:	
Slimes:	
Abnormal Growth:	

Flow Characteristics

Flow Observed:	
Source of Flow:	
Velocity of Flow:	
Color of Flow:	
Flow Odor	

Additional Comments:

Sample ID And Information		**Lab Analysis:**	**Results:**	**TMDL Threshold:**	**Units:**	**Photo ID:**
Sample ID:		pH:		6.5 - 9	pH units	
Time Collected:		Temperature:		N/A	Celsius	
Last Rain Event:		E. coli:		1000	CFU per 100mL	
Current Weather:		Total Phosphorus:		Watershed Dependent	ug/L	
Screening Location Type:		Total Suspended Solids:		Watershed Dependent	mg/L	
Total Rainfall (Inches):		Dissolved Oxygen:		Watershed Dependent	mg/L	
		Other:				
Outfall Characterization:						
Sample sent to Lab:						

Arch Environmental Group
37720 Interchange Drive,
Farmington Hills MI 48370

Phone: (248) 426-0135
Fax: (248) 426-0136
www.archenvgroup.com

DMB-SESC_Eform

SOIL EROSION AND SEDIMENTATION CONTROL (SESC) INSPECTION REPORT

DEPARTMENT OF MANAGEMENT AND BUDGET
INFRASTRUCTURE SERVICES, DESIGN AND CONSTRUCTION DIVISION
Second Floor, Stevens T. Mason Building
P.O. Box 30026, Lansing, Michigan 48909
This report is required to document soil erosion and sedimentation control on State of Michigan projects. (Authority: Part 91, PA 451)

REPORT NUMBER	SESC PERMIT NUMBER	REPORT DATE		PERIOD (FROM WHEN - TO WHEN)
INDEX NUMBER(S)	AGENCY NUMBER	FILE NUMBER	CONTRACT NUMBER	DEPARTMENT/UNIVERSITY/COLLEGE
PROJECT NAME				
CONTRACTOR				
PROFESSIONAL				

A. REASON FOR INSPECTION: ☐ Regular Inspection ☐ Post-Rain Event Inspection (explain below)

☐ Weekly ☐ Daily

B. CURRENT WEATHER CONDITIONS:

☐ Sunny ☐ Cloudy ☐ Partly Cloudy ☐ Windy Temperature_____

Precipitation: ☐ Rain ☐ Snow ☐ Sleet ☐ Hail Other (explain) _____

C. DESCRIBE SEVERE WEATHER (if applicable):

D. DESCRIBE WEATHER CONDITIONS SINCE LAST INSPECTION (Date of Last Inspection _____):

E. ARE THE CONTROLS INSTALLED ACCORDING TO THE PLANS AND SPECIFICATIONS? ☐ Yes ☐ No (Describe):

F. ARE THE CONTROLS IN PLACE FUNCTIONING PROPERLY? ☐ Yes ☐ No (Describe):

G. ARE THE CONTROLS BEING PROPERLY MAINTAINED? ☐ Yes ☐ No (Describe):

H. INDICATE THE SESC CONTROLS IN PLACE ON SITE (According to the DMB SESC Keying System):

Best Management Practice	Present (check)	Number or Lin Ft of Controls	Best Management Practice	Present (check)	Number or Lin Ft of Controls
Erosion Controls:			**Erosion/Sediment Controls:**		
(E1) Selective Grading & Shaping	☐		(ES31) Check Dam	☐	
(E2) Grubbing Omitted	☐		(ES32) Stone Filter Berm	☐	
(E3) Slope Roughening & Scarification	☐		(ES33) Filter Rolls	☐	
(E4) Terraces	☐		(ES34) Sand Fence	☐	
(E5) Dust Control	☐		(ES35) Dewatering	☐	
(E6) Mulch	☐		(ES36) Diversion Dike/Berm	☐	
(E7) Temporary Seeding	☐		(ES37) Diversion Ditch	☐	
(E8) Permanent Seeding	☐		(ES38) Cofferdam/Sheet Pilings	☐	
(E9) Mulch Blankets	☐		(ES39) Streambank Biostabilization	☐	
(E10) Sodding	☐		(ES40) Polymers	☐	
(E11) Vegetated Channels	☐		(ES41) Wattles	☐	
(E12) Rip Rap	☐		**Sediment Controls:**		
(E13) Gabion Walls	☐		(S51) Silt Fence	☐	
(E14) Energy Dissipator	☐		(S52) Catch Basin Sediment Guard	☐	
(E15) Temporary Slope Drain	☐		(S53) Stabilized Construction Access	☐	
(E16) Slope Drain	☐		(S54) Tire Wash	☐	
(E17) Cellular Confinement Systems	☐		(S55) Sediment Basin	☐	
(E18) Plastic Sheets	☐		(S56) Sediment Trap	☐	
(E19) Temporary Drainageway/ Stream Crossing	☐		(S57) Vegetated Buffer/Filter Strip	☐	
(E20) Temporary Bypass Channel	☐		(S58) Inlet Protection Fabric Drop	☐	
(E21) Live Staking	☐		(S59) Inlet Protection Fabric Fence	☐	
OTHER	☐		(S60) Inlet Protection Stone	☐	

I. WHAT CORRECTIVE ACTIONS SHOULD BE TAKEN BY THE CONTRACTOR?

J. BY WHAT DATE MUST THESE ACTIONS BE IMPLEMENTED: _____

K. OBSERVATIONS / COMMENTS:

_____ _____

Signature of Inspector Date

cc:

Appendix E

Property Structural Controls Inventory, Inspection, & Maintenance Schedule

Development Date: May 17, 2025
Revision Date: February 10, 2025
Revision Date: May 27, 2025

Flushing Community Schools – Bus Garage & Maintenance
Structural Control Inventory, Inspection, & Maintenance Schedule

Facility	Priority Level of Potential Discharge (High, Medium, Low)	Type of Structural Control	Number of Controls	Inspection/Maintenance Schedule
Bus Garage & Maintenance 4335 N Seymour Rd Flushing, MI 48433	High	Catch Basin/Manholes	7	Inspect Annually, Clean Once per Permit Cycle or if Build-Up of Accumulated Solid Material is Between 30 and 50% of the Total Sump Depth.

Revision Date: November 15, 2024

Flushing Community Schools – Central Elementary School-Football Field Complex
Structural Control Inventory, Inspection, & Maintenance Schedule

Facility	Priority Level of Potential Discharge (High, Medium, Low)	Type of Structural Control	Number of Controls	Inspection/Maintenance Schedule
Central Elementary School-Football Field Complex 525 Coutant St Flushing, MI 48433	Low	Catch Basin/Manholes	14	Inspect Annually, Clean Once per Permit Cycle or if Build-Up of Accumulated Solid Material is Between 30 and 50% of the Total Sump Depth.
		Infiltration Basin	2	Inspect Annually, Maintain as Needed

Revision Date: November 15, 2024

Flushing Community Schools – Central Office
Structural Control Inventory, Inspection, & Maintenance Schedule

Facility	Priority Level of Potential Discharge (High, Medium, Low)	Type of Structural Control	Number of Controls	Inspection/Maintenance Schedule
Central Office 522 N McKinley Rd Flushing, MI 48433	Low	Catch Basin/Manholes	1	Inspect Annually, Clean Once per Permit Cycle or if Build-Up of Accumulated Solid Material is Between 30 and 50% of the Total Sump Depth.

Revision Date: November 15, 2024

Flushing Community Schools – Early Childhood Center
Structural Control Inventory, Inspection, & Maintenance Schedule

Facility	Priority Level of Potential Discharge (High, Medium, Low)	Type of Structural Control	Number of Controls	Inspection/Maintenance Schedule
Early Childhood Center 409 Chamberlain St Flushing, MI 48433	Low	Catch Basin/Manholes	7	Inspect Annually, Clean Once per Permit Cycle or if Build-Up of Accumulated Solid Material is Between 30 and 50% of the Total Sump Depth.
		Infiltration Basin	4	Inspect Annually, Maintain as Needed
		Detention Basin	1	Inspect Annually, Maintain as Needed
		Stormwater Conveyance Channel	1	Inspect Annually, Maintain as Needed

Revision Date: November 15, 2024

Flushing Community Schools – Elms Elementary School
Structural Control Inventory, Inspection, & Maintenance Schedule

Facility	Priority Level of Potential Discharge (High, Medium, Low)	Type of Structural Control	Number of Controls	Inspection/Maintenance Schedule
Elms Elementary School 6125 Elms Rd Flushing, MI 48433	Low	Catch Basin/Manholes	11	Inspect Annually, Clean Once per Permit Cycle or if Build-Up of Accumulated Solid Material is Between 30 and 50% of the Total Sump Depth.
		Open Pipe Outlet	6	Inspect Annually, Maintain as Needed
		Infiltration Basin	2	Inspect Annually, Maintain as Needed
		Detention Basin	1	Inspect Annually, Maintain as Needed
		Hydrodynamic Separator	1	Inspect Annually, Maintain as Needed

Revision Date: November 15, 2024

Flushing Community Schools – Flushing High School
Structural Control Inventory, Inspection, & Maintenance Schedule

Facility	Priority Level of Potential Discharge (High, Medium, Low)	Type of Structural Control	Number of Controls	Inspection/Maintenance Schedule
Flushing High School 5039 Deland Rd Flushing, MI 48433	Low	Catch Basin/Manholes	30	Inspect Annually, Clean Once per Permit Cycle or if Build-Up of Accumulated Solid Material is Between 30 and 50% of the Total Sump Depth.
		Detention Basin	3	Inspect Annually, Maintain as Needed
		Stormwater Conveyance Channel	13	Inspect Annually, Maintain as Needed
		Swale	1	Inspect Annually, Maintain as Needed
		Open Pipe Outlet	2	Inspect Annually, Maintain as Needed
		Infiltration Basin	5	Inspect Annually, Maintain as Needed

Revision Date: November 15, 2024

Flushing Community Schools – Flushing Middle School
Structural Control Inventory, Inspection, & Maintenance Schedule

Facility	Priority Level of Potential Discharge (High, Medium, Low)	Type of Structural Control	Number of Controls	Inspection/Maintenance Schedule
Flushing Middle School 8100 Carpenter Rd Flushing, MI 48433	Medium	Catch Basin/Manholes	30	Inspect Annually, Clean Once per Permit Cycle or if Build-Up of Accumulated Solid Material is Between 30 and 50% of the Total Sump Depth.
		Open Pipe Outlet	2	Inspect Annually, Maintain as Needed
		Drainage Receptor	3	Inspect Annually, Maintain as Needed
		Infiltration Basin	1	Inspect Annually, Maintain as Needed
		Detention Pond	5	Inspect Annually, Maintain as Needed

Revision Date: November 15, 2024

Flushing Community Schools – Seymour Elementary School-Soccer Fields Complex Structural Control Inventory, Inspection, & Maintenance Schedule

Facility	Priority Level of Potential Discharge (High, Medium, Low)	Type of Structural Control	Number of Controls	Inspection/Maintenance Schedule
Seymour Elementary School-Soccer Fields Complex 3088 North Seymour, Flushing, MI 48433	Low	Catch Basin/Manholes	2	Inspect Annually, Clean Once per Permit Cycle or if Build-Up of Accumulated Solid Material is Between 30 and 50% of the Total Sump Depth.
		Drainage Receptor	1	Inspect Annually, Maintain as Needed
		Infiltration Basin	4	Inspect Annually, Maintain as Needed
		Stormwater Conveyance Channel	11	Inspect Annually, Maintain as Needed
		Dirt/Gravel Parking Lot	1	Inspect Annually for dust, loose aggregate (Raveling), Potholes, and Depressions. Maintain as Needed

Revision Date: November 15, 2024

Flushing Community School – Springview Elementary School
Structural Control Inventory, Inspection, & Maintenance Schedule

Facility	Priority Level of Potential Discharge (High, Medium, Low)	Type of Structural Control	Number of Controls	Inspection/Maintenance Schedule
Springview Elementary School 1233 Springview Dr Flushing, MI 48433	Medium	Catch Basin/Manholes	7	Inspect Annually, Clean Once per Permit Cycle or if Build-Up of Accumulated Solid Material is Between 30 and 50% of the Total Sump Depth.
		Stormwater Conveyance Channel	2	Inspect Annually, Maintain as Needed

Revision Date: November 15, 2024

Appendix F

Contractor Oversight & Employee Training Documentation

Development Date: May 17, 2025
Revision Date: February 10, 2025
Revision Date: May 27, 2025

IDEP/PPGH STORMWATER TRAINING RECORD

Client	Location	Date
Flushing Community Schools Permit Number TBD		

Illicit Discharge Elimination Program (IDEP): Training on techniques for identifying illicit discharges and connections, Training on procedures for reporting, responding to, and eliminating an illicit discharge or connection and the proper enforcement response.
Pollution Prevention & Good Housekeeping: Training on BMPs that are important such as good housekeeping, spill response, materials storage and handling, landscape maintenance, street maintenance, fleet maintenance, and garages.

Employee Name	Employee Signature	Job Title/Department

Instructor Name	Instructor Signature

Arch Environmental Group, Inc.
248-426-0165

Flushing Community Schools
STORMWATER CONTRACTOR OVERSIGHT RECORD

Flushing Community Schools (FluCS) shall implement the procedure requiring contractors hired by FluCS to perform municipal operation and maintenance activities that comply with the FluCS pollution prevention and good housekeeping program and contractor oversight to ensure compliance with the FluCS National Pollutant Discharge Elimination System (NPDES) Municipal Separate Storm Sewer System (MS4) Storm Water Discharge Permit, Section A. Limitations and Monitoring Requirements, #7 Contractor Requirements and Oversight.

1. Identify the potential pollutant-generating activities and pollutants expected to be exposed to stormwater.
2. Describe the location where the potential pollutant-generating activities will occur.
3. Identify the person responsible for implementing the pollution prevention practice or practices for each pollutant-generating activity.

Please initial each line of the procedure.

_____ Prevent and respond to leaks, spills and other releases;

_____ Prevent the discharge of spilled and leaked fuels and chemicals from vehicle fueling and maintenance activities;

_____ Prevent the discharge of soaps, solvents, detergents, and wash water from construction materials, including the clean-up of stucco,
paint, form release oils, and curing compounds. Collection and proper disposal in a manner to prevent contact with stormwater and prevent discharge of these pollutants.

_____ Minimize the discharge of pollutants from vehicle and equipment washing, wheel wash water and other types of washing (e.g., locating activities away from surface waters and stormwater inlets or conveyance and directing wash waters to sediment basins or traps, using filtration devices such as filter bags or sand filters or using similarly effective controls);

_____ Direct concrete wash water into a leak-proof container or leak-proof settling basin. The container or basin shall be designed so that no overflows can occur due to inadequate sizing or precipitation. Hardened concrete wastes shall be removed and disposed of in a manner consistent with the handling of other construction wastes. Liquid concrete wastes shall be removed and disposed of in a manner consistent with the handling of other construction wash waters and shall not be discharged to surface waters;

_____ Minimize the discharge of pollutants from storage, handling, and disposal of construction products, materials and wastes including (i) building products such as asphalt sealants, copper flashing, roofing materials, adhesives, concrete admixtures; (ii) pesticides, herbicides, insecticides, fertilizers, and landscape materials; and (iii) construction and domestic wastes such as packaging materials, scrap construction materials, masonry products, timber, pipe and electrical cuttings, plastics, Styrofoam, concrete, and other trash or building materials;

_____ Prevent the discharge of fuels, oils, and other petroleum products, hazardous or toxic wastes, and sanitary wastes.

_____ Report any other discharge from the potential pollutant-generating activities not addressed above to <SCHOOL DISTRICT>.

_____
Name of Business

_____ _____
Business Representative Date

Appendix G

TMDL Sample Location Table

Development Date: May 17, 2025
Revision Date: February 10, 2025
Revision Date: May 27, 2025

TMDL Sample Locations

Flushing Community Schools				
Facility	**Point of Discharge**	**Receiving Waters**	**Watershed**	**Parameter**
Central Elementary School	CEN-02.MH.DP	Cole Creek	Flint River	E. coli
Early Childhood Center	FEC-06.DB.DP	Cole Creek	Flint River	E. coli
Seymour Elementary School/Soccer Field Complex	SES-04.DR.DP	Cole Creek	Flint River	E. coli