



1548 WEST WINTON AVENUE HAYWARD, CA 94545
(510)635-6383 INFO@ACMESUNSHADES.COM
WWW.ACMESUNSHADES.COM CONTRACTORS LICENSE #499660



CONTRACT

Keeping You Cool Since 1922

Menlo Park City School District

Attention: Sandra Franco
181 Encinal Avenue, Atherton, CA 94027
Email: sfranco@mpcsd.org

Project: TK and Lunch Area Roman Shade
Replacement at Oak Knoll School

Date: 03/30/2026

Sales Rep: *Chad*

Lead Source: Google

Job Address: Oak Knoll School
1895 Oak Knoll Ln
Menlo Park, CA 94025

Acme Sunshades Enterprises, Inc. agrees to furnish all materials and perform all labor to manufacture & install the following:

TO RECOVER SIXTEEN (16) Roman Shades, per details below:

Fabric Type: Textilene Nano 95 Frame Type: Roman Shades (Existing)
Fabric Color: Stone Texture Frame Color: SS Turnbuckles/Galvanized Cable & Quick links (Existing)

Roman Shades Dimensions:

- TK Area: 9 @ 7'8" wide x 27'0" projection
- Lunch Area: 7 @ 8'5" wide x 20'0" projection

NOTE: ACME will replace all bent flat bars and rods sewn into the fabric panels with new lightweight aluminum tubing.

NOTE: This quote is based on the existing Roman shade hardware being in good working condition and reusable. ACME will reuse the existing cables, turnbuckles, and quick links and will tighten and shorten the existing cables to the best of its ability to help reduce sagging. Any additional hardware replacement, if needed, will be at extra cost.

DISCLAIMER: No warranty on existing Roman shade attachment hardware, including any adjustments, patching, or repairs.

Included in the below costs are the following: Labor, materials, and installation. A 15-year limited manufacturer warranty on Textilene Nano 95 mesh material. Cover is sewn with Tenara Teflon thread with a warranty against ultra-violet damage and rotting for the life of the fabric. Some seams may be welded in lieu of sewing.

Not included in the below costs are the following: Price excludes permits, permit fees, or permit procurement, special inspections, or engineering. Shop drawings prevail. Price subject to change due to clients' call out. Backing or blocking. Electrician customer to provide an energized J box within 6ft of any one unit. No warranty on the existing roman shade hardware, moving, adjusting, painting, or repairing them.

All the above work to be completed in a substantial and workmanlike manner for the sum of:

Fifty-Eight Thousand Six Hundred Dollars (\$58,600.00)

One half down (\$29,300.00). Balance due on completion (\$29,300.00).

A service charge of 1.5% monthly (18% annually) will be added to all past-due accounts

Completion of installation is approximately: 4-6 Weeks (after final approval & deposit).

This proposal may be withdrawn if not accepted within thirty days of contractor's execution. To accept this proposal, please sign in the space below and return the signed agreement to Acme Sunshades Enterprise, Inc. within the thirty-day period.

Respectfully submitted by: _____ President

For ACME SUNSHADES ENTERPRISE, INC.
Contractor's State License #499660

Title

ACCEPTANCE

SIGN: _____

DATE: 4/16/26