



Bid 26-003 - Painting at Village/MVM
Addendum #1
May 7, 2026

Addendum #1

RFI:

1. When are the Start and End Dates for this project?

June 15, 2026-July 31, 2026

Job Walk Notes:

Village

There are three guaranteed murals that will not be painted.

Gutter drops will need to be painted as pencils, as they are now.

Any fencing that is painted now will be repainted

Shade structure off MPR will be painted, poles and roof (base color). The shade structure in the kinder area will NOT be painted.

All ramps will be painted. The base will need to be painted gray with anti skid.

Portables with window screens will need to be painted inside and out (base color).

No metal areas will need to be backrolled.

The following will all be painted throughout the site: conex boxes, light poles in parking lot, fire hydrants, ballards, and seating planters around trees.

Mountain View Montessori

Murals are staying but the lettering needs to be matched and repainted.

Do not paint the galvanized drip edge.

Stucco eve vents need paint, the district requested to use rust block. (They are currently galvanized but starting to rust).

