ENTHALPY ANALYTICAL

Batch QC

Type: Blank	Lab ID: QC1342069	Batch: 395782
Matrix: Filtrate	Method: EPA 6010B	Prep Method: EPA 3015A

QC1342069 Analyte	Result	Qual	Units	RL	Prepared	Analyzed
Lead	ND		mg/L	0.010	02/19/26	02/19/26

Type: Lab Control Sample	Lab ID: QC1342070	Batch: 395782
Matrix: Filtrate	Method: EPA 6010B	Prep Method: EPA 3015A

QC1342070 Analyte	Result	Spiked	Units	Recovery	Qual	Limits
Lead	0.3580	0.4000	mg/L	89%		80-120

Type: Matrix Spike	Lab ID: QC1342071	Batch: 395782
Matrix (Source ID): Water (553648-003)	Method: EPA 6010B	Prep Method: EPA 3015A

QC1342071 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	DF
Lead	3.354	0.05160	4.000	mg/L	83%		75-125	10

Type: Matrix Spike Duplicate	Lab ID: QC1342072	Batch: 395782
Matrix (Source ID): Water (553648-003)	Method: EPA 6010B	Prep Method: EPA 3015A

QC1342072 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	RPD	RPD Lim	DF
Lead	3.307	0.05160	4.000	mg/L	81%		75-125	1	20	10

Type: Serial Dilution	Lab ID: QC1342099	Batch: 395782
Matrix (Source ID): Water (553648-001)	Method: EPA 6010B	Prep Method: EPA 3015A

QC1342099 Analyte	Result	Source Sample Result	Units	Qual	RPD	RPD Lim	DF
Lead	0.1877	0.05977	mg/L	J			50

Type: Blank	Lab ID: QC1340915	Batch: 395443
Matrix: Soil	Method: EPA 6010B	Prep Method: EPA 3050B

QC1340915 Analyte	Result	Qual	Units	RL	Prepared	Analyzed
Lead	ND		mg/Kg	1.0	02/16/26	02/17/26

Type: Lab Control Sample	Lab ID: QC1340916	Batch: 395443
Matrix: Soil	Method: EPA 6010B	Prep Method: EPA 3050B

QC1340916 Analyte	Result	Spiked	Units	Recovery	Qual	Limits
Lead	104.5	100.0	mg/Kg	104%		80-120

ENTHALPY ANALYTICAL

Batch QC

Type:	Matrix Spike	Lab ID:	QC1340917	Batch:	395443
Matrix (Source ID):	Soil (553156-001)	Method:	EPA 6010B	Prep Method:	EPA 3050B

QC1340917 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	DF
Lead	106.5	11.32	97.09	mg/Kg	98%		75-125	0.97

Type:	Matrix Spike Duplicate	Lab ID:	QC1340918	Batch:	395443
Matrix (Source ID):	Soil (553156-001)	Method:	EPA 6010B	Prep Method:	EPA 3050B

QC1340918 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	RPD	RPD Lim	DF
Lead	109.0	11.32	97.09	mg/Kg	101%		75-125	2	28	0.97

Type:	Serial Dilution	Lab ID:	QC1340919	Batch:	395443
Matrix (Source ID):	Soil (553156-001)	Method:	EPA 6010B	Prep Method:	EPA 3050B

QC1340919 Analyte	Result	Source Sample Result	Units	Qual	RPD	RPD Lim	DF
Lead	10.56	11.32	mg/Kg				4.9

Type:	Post Digest Spike	Lab ID:	QC1340920	Batch:	395443
Matrix (Source ID):	Soil (553156-001)	Method:	EPA 6010B	Prep Method:	EPA 3050B

QC1340920 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	DF
Lead	99.26	11.32	98.04	mg/Kg	90%		75-125	0.98

Type:	Blank	Lab ID:	QC1341586	Batch:	395655
Matrix:	Soil	Method:	EPA 6010B	Prep Method:	EPA 3050B

QC1341586 Analyte	Result	Qual	Units	RL	Prepared	Analyzed
Lead	ND		mg/Kg	1.0	02/18/26	02/18/26

Type:	Lab Control Sample	Lab ID:	QC1341587	Batch:	395655
Matrix:	Soil	Method:	EPA 6010B	Prep Method:	EPA 3050B

QC1341587 Analyte	Result	Spiked	Units	Recovery	Qual	Limits
Lead	108.3	100.0	mg/Kg	108%		80-120

ENTHALPY ANALYTICAL

Batch QC

Type:	Matrix Spike	Lab ID:	QC1341588	Batch:	395655
Matrix (Source ID):	Soil (553104-001)	Method:	EPA 6010B	Prep Method:	EPA 3050B

QC1341588 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	DF
Lead	112.7	8.523	99.01	mg/Kg	105%		75-125	0.99

Type:	Matrix Spike Duplicate	Lab ID:	QC1341589	Batch:	395655
Matrix (Source ID):	Soil (553104-001)	Method:	EPA 6010B	Prep Method:	EPA 3050B

QC1341589 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	RPD	RPD Lim	DF
Lead	109.1	8.523	96.15	mg/Kg	105%		75-125	1	28	0.96

Type:	Post Digest Spike	Lab ID:	QC1341703	Batch:	395655
Matrix (Source ID):	Soil (553104-001)	Method:	EPA 6010B	Prep Method:	EPA 3050B

QC1341703 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	DF
Lead	98.21	8.523	95.24	mg/Kg	94%		75-125	0.95

Type:	Serial Dilution	Lab ID:	QC1341759	Batch:	395655
Matrix (Source ID):	Soil (553104-001)	Method:	EPA 6010B	Prep Method:	EPA 3050B

QC1341759 Analyte	Result	Source Sample Result	Units	Qual	RPD	RPD Lim	DF
Lead	9.014	8.523	mg/Kg				4.8

Type:	Blank	Lab ID:	QC1341220	Batch:	395533
Matrix:	Water	Method:	EPA 6020	Prep Method:	EPA 3015A

QC1341220 Analyte	Result	Qual	Units	RL	Prepared	Analyzed
Arsenic	ND		ug/L	2.0	02/17/26	02/17/26

Type:	Lab Control Sample	Lab ID:	QC1341221	Batch:	395533
Matrix:	Water	Method:	EPA 6020	Prep Method:	EPA 3015A

QC1341221 Analyte	Result	Spiked	Units	Recovery	Qual	Limits
Arsenic	98.43	100.0	ug/L	98%		80-120

ENTHALPY ANALYTICAL

Batch QC

Type:	Matrix Spike	Lab ID:	QC1341234	Batch:	395533
Matrix (Source ID):	Water (553180-001)	Method:	EPA 6020	Prep Method:	EPA 3015A

QC1341234 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	DF
Arsenic	101.4	3.322	100.0	ug/L	98%		75-125	10

Type:	Matrix Spike Duplicate	Lab ID:	QC1341235	Batch:	395533
Matrix (Source ID):	Water (553180-001)	Method:	EPA 6020	Prep Method:	EPA 3015A

QC1341235 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	RPD	RPD Lim	DF
Arsenic	97.31	3.322	100.0	ug/L	94%		75-125	4	20	10

Type:	Matrix Spike	Lab ID:	QC1341236	Batch:	395533
Matrix (Source ID):	Water (553180-002)	Method:	EPA 6020	Prep Method:	EPA 3015A

QC1341236 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	DF
Arsenic	100.2	1.647	100.0	ug/L	99%		75-125	10

Type:	Matrix Spike Duplicate	Lab ID:	QC1341237	Batch:	395533
Matrix (Source ID):	Water (553180-002)	Method:	EPA 6020	Prep Method:	EPA 3015A

QC1341237 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	RPD	RPD Lim	DF
Arsenic	102.2	1.647	100.0	ug/L	101%		75-125	2	20	10

Type:	Blank	Lab ID:	QC1340713	Batch:	395399
Matrix:	Soil	Method:	EPA 6020	Prep Method:	EPA 3050B

QC1340713 Analyte	Result	Qual	Units	RL	Prepared	Analyzed
Arsenic	ND		mg/Kg	1.0	02/14/26	02/17/26

Type:	Lab Control Sample	Lab ID:	QC1340714	Batch:	395399
Matrix:	Soil	Method:	EPA 6020	Prep Method:	EPA 3050B

QC1340714 Analyte	Result	Spiked	Units	Recovery	Qual	Limits
Arsenic	100.0	100.0	mg/Kg	100%		80-120

ENTHALPY ANALYTICAL

Batch QC

Type:	Matrix Spike	Lab ID:	QC1340715	Batch:	395399
Matrix (Source ID):	Soil (553016-001)	Method:	EPA 6020	Prep Method:	EPA 3050B

QC1340715 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	DF
Arsenic	105.9	8.003	97.09	mg/Kg	101%		75-125	0.97

Type:	Matrix Spike Duplicate	Lab ID:	QC1340716	Batch:	395399
Matrix (Source ID):	Soil (553016-001)	Method:	EPA 6020	Prep Method:	EPA 3050B

QC1340716 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	RPD	RPD Lim	DF
Arsenic	105.6	8.003	96.15	mg/Kg	102%		75-125	1	22	0.96

Type:	Post Digest Spike	Lab ID:	QC1340717	Batch:	395399
Matrix (Source ID):	Soil (553016-001)	Method:	EPA 6020	Prep Method:	EPA 3050B

QC1340717 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	DF
Arsenic	108.5	8.003	99.01	mg/Kg	101%		75-125	0.99

Type:	Serial Dilution	Lab ID:	QC1340900	Batch:	395399
Matrix (Source ID):	Soil (553016-001)	Method:	EPA 6020	Prep Method:	EPA 3050B

QC1340900 Analyte	Result	Source Sample Result	Units	Qual	RPD	RPD Lim	DF
Arsenic	8.867	8.003	mg/Kg				5

ENTHALPY ANALYTICAL

Batch QC

Type:	**Blank**	**Lab ID:**	**QC1341696**	**Batch:**	**395687**
Matrix:	**Soil**	**Method:**	**EPA 8081A**	**Prep Method:**	**EPA 3546**

QC1341696 Analyte	Result	Qual	Units	RL	Prepared	Analyzed
alpha-BHC	ND		ug/Kg	5.0	02/18/26	02/19/26
beta-BHC	ND		ug/Kg	5.0	02/18/26	02/19/26
gamma-BHC	ND		ug/Kg	5.0	02/18/26	02/19/26
delta-BHC	ND		ug/Kg	5.0	02/18/26	02/19/26
Heptachlor	ND		ug/Kg	5.0	02/18/26	02/19/26
Aldrin	ND		ug/Kg	5.0	02/18/26	02/19/26
Heptachlor epoxide	ND		ug/Kg	5.0	02/18/26	02/19/26
Endosulfan I	ND		ug/Kg	5.0	02/18/26	02/19/26
Dieldrin	ND		ug/Kg	5.0	02/18/26	02/19/26
4,4'-DDE	ND		ug/Kg	5.0	02/18/26	02/19/26
Endrin	ND		ug/Kg	5.0	02/18/26	02/19/26
Endosulfan II	ND		ug/Kg	5.0	02/18/26	02/19/26
Endosulfan sulfate	ND		ug/Kg	5.0	02/18/26	02/19/26
4,4'-DDD	ND		ug/Kg	5.0	02/18/26	02/19/26
Endrin aldehyde	ND		ug/Kg	5.0	02/18/26	02/19/26
Endrin ketone	ND		ug/Kg	5.0	02/18/26	02/19/26
4,4'-DDT	ND		ug/Kg	5.0	02/18/26	02/19/26
Methoxychlor	ND		ug/Kg	10	02/18/26	02/19/26
Toxaphene	ND		ug/Kg	100	02/18/26	02/19/26
Chlordane (Technical)	ND		ug/Kg	50	02/18/26	02/19/26
Surrogates				**Limits**		
TCMX	64%		%REC	58-120	02/18/26	02/19/26
Decachlorobiphenyl	51%		%REC	47-120	02/18/26	02/19/26

ENTHALPY ANALYTICAL

Batch QC

Type: Lab Control Sample	**Lab ID: QC1341697**	**Batch: 395687**
Matrix: Soil	**Method: EPA 8081A**	**Prep Method: EPA 3546**

QC1341697 Analyte	Result	Spiked	Units	Recovery	Qual	Limits
alpha-BHC	36.54	49.46	ug/Kg	74%		53-132
beta-BHC	37.95	49.46	ug/Kg	77%		59-131
gamma-BHC	37.19	49.46	ug/Kg	75%		54-132
delta-BHC	37.65	49.46	ug/Kg	76%		54-134
Heptachlor	35.78	49.46	ug/Kg	72%		50-130
Aldrin	31.63	49.46	ug/Kg	64%		46-120
Heptachlor epoxide	33.33	49.46	ug/Kg	67%		52-127
Endosulfan I	34.09	49.46	ug/Kg	69%		53-132
Dieldrin	34.44	49.46	ug/Kg	70%		53-134
4,4'-DDE	36.50	49.46	ug/Kg	74%		53-140
Endrin	37.47	49.46	ug/Kg	76%		53-142
Endosulfan II	36.18	49.46	ug/Kg	73%		53-138
Endosulfan sulfate	34.06	49.46	ug/Kg	69%		50-134
4,4'-DDD	34.39	49.46	ug/Kg	70%		50-136
Endrin aldehyde	24.71	49.46	ug/Kg	50%		15-120
Endrin ketone	34.42	49.46	ug/Kg	70%		50-146
4,4'-DDT	31.73	49.46	ug/Kg	64%		46-142
Methoxychlor	35.00	49.46	ug/Kg	71%		48-156
Surrogates						
TCMX	33.10	49.46	ug/Kg	67%		58-120
Decachlorobiphenyl	29.09	49.46	ug/Kg	59%		47-120

ENTHALPY ANALYTICAL

Batch QC

Type:	**Matrix Spike**	**Lab ID:**	**QC1341698**	**Batch:**	**395687**
Matrix (Source ID):	**Miscell. (553054-001)**	**Method:**	**EPA 8081A**	**Prep Method:**	**EPA 3546**

QC1341698 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	DF
alpha-BHC	49.59	ND	99.40	ug/Kg	50%	*	52-120	2
beta-BHC	69.94	ND	99.40	ug/Kg	70%		57-126	2
gamma-BHC	42.60	ND	99.40	ug/Kg	43%	*	54-122	2
delta-BHC	6.897	ND	99.40	ug/Kg	7%	*	44-127	2
Heptachlor	60.97	ND	99.40	ug/Kg	61%		51-122	2
Aldrin	59.26	ND	99.40	ug/Kg	60%		51-120	2
Heptachlor epoxide	58.35	ND	99.40	ug/Kg	59%		50-122	2
Endosulfan I	55.98	ND	99.40	ug/Kg	56%		48-123	2
Dieldrin	59.19	ND	99.40	ug/Kg	60%		48-128	2
4,4'-DDE	63.53	ND	99.40	ug/Kg	64%		50-139	2
Endrin	70.65	ND	99.40	ug/Kg	71%		53-132	2
Endosulfan II	61.12	ND	99.40	ug/Kg	61%		47-131	2
Endosulfan sulfate	40.96	ND	99.40	ug/Kg	41%		40-126	2
4,4'-DDD	58.27	ND	99.40	ug/Kg	59%		48-130	2
Endrin aldehyde	26.22	ND	99.40	ug/Kg	26%		26-120	2
Endrin ketone	57.88	ND	99.40	ug/Kg	58%		51-133	2
4,4'-DDT	47.04	ND	99.40	ug/Kg	47%		40-144	2
Methoxychlor	57.03	ND	99.40	ug/Kg	57%		49-148	2
Surrogates								
TCMX	57.72		99.40	ug/Kg	58%		58-120	2
Decachlorobiphenyl	51.94		99.40	ug/Kg	52%		47-120	2

ENTHALPY ANALYTICAL

Batch QC

Type:	**Matrix Spike Duplicate**	**Lab ID:**	**QC1341699**	**Batch:**	**395687**
Matrix (Source ID):	**Miscell. (553054-001)**	**Method:**	**EPA 8081A**	**Prep Method:**	**EPA 3546**

QC1341699 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	RPD	RPD Lim	DF
alpha-BHC	50.71	ND	103.1	ug/Kg	49%	*	52-120	1	37	2.1
beta-BHC	62.87	ND	103.1	ug/Kg	61%		57-126	14	38	2.1
gamma-BHC	44.46	ND	103.1	ug/Kg	43%	*	54-122	1	39	2.1
delta-BHC	6.573	ND	103.1	ug/Kg	6%	*	44-127	8	54	2.1
Heptachlor	62.42	ND	103.1	ug/Kg	61%		51-122	1	44	2.1
Aldrin	57.32	ND	103.1	ug/Kg	56%		51-120	7	39	2.1
Heptachlor epoxide	59.91	ND	103.1	ug/Kg	58%		50-122	1	39	2.1
Endosulfan I	59.17	ND	103.1	ug/Kg	57%		48-123	2	47	2.1
Dieldrin	59.96	ND	103.1	ug/Kg	58%		48-128	2	43	2.1
4,4'-DDE	60.10	ND	103.1	ug/Kg	58%		50-139	9	42	2.1
Endrin	70.72	ND	103.1	ug/Kg	69%		53-132	4	45	2.1
Endosulfan II	61.92	ND	103.1	ug/Kg	60%		47-131	2	46	2.1
Endosulfan sulfate	39.22	ND	103.1	ug/Kg	38%	*	40-126	8	52	2.1
4,4'-DDD	59.59	ND	103.1	ug/Kg	58%		48-130	1	46	2.1
Endrin aldehyde	25.51	ND	103.1	ug/Kg	25%	*	26-120	6	57	2.1
Endrin ketone	59.51	ND	103.1	ug/Kg	58%		51-133	1	43	2.1
4,4'-DDT	46.82	ND	103.1	ug/Kg	45%		40-144	4	56	2.1
Methoxychlor	56.97	ND	103.1	ug/Kg	55%		49-148	4	53	2.1
Surrogates										
TCMX	63.83		103.1	ug/Kg	62%		58-120			2.1
Decachlorobiphenyl	51.99		103.1	ug/Kg	50%		47-120			2.1

ENTHALPY ANALYTICAL

Batch QC

Type: Blank	Lab ID: QC1340997	Batch: 395462
Matrix: Water		

QC1340997 Analyte	Result	Qual	Units	RL	Prepared	Analyzed
Method: EPA 8081A Prep Method: EPA 3510C						
alpha-BHC	ND		ug/L	0.05	02/16/26	02/17/26
beta-BHC	ND		ug/L	0.05	02/16/26	02/17/26
gamma-BHC	ND		ug/L	0.05	02/16/26	02/17/26
delta-BHC	ND		ug/L	0.05	02/16/26	02/17/26
Heptachlor	ND		ug/L	0.05	02/16/26	02/17/26
Aldrin	ND		ug/L	0.05	02/16/26	02/17/26
Heptachlor epoxide	ND		ug/L	0.05	02/16/26	02/17/26
Endosulfan I	ND		ug/L	0.05	02/16/26	02/17/26
Dieldrin	ND		ug/L	0.1	02/16/26	02/17/26
4,4'-DDE	ND		ug/L	0.1	02/16/26	02/17/26
Endrin	ND		ug/L	0.1	02/16/26	02/17/26
Endosulfan II	ND		ug/L	0.1	02/16/26	02/17/26
Endosulfan sulfate	ND		ug/L	0.1	02/16/26	02/17/26
4,4'-DDD	ND		ug/L	0.1	02/16/26	02/17/26
Endrin aldehyde	ND		ug/L	0.1	02/16/26	02/17/26
Endrin ketone	ND		ug/L	0.1	02/16/26	02/17/26
4,4'-DDT	ND		ug/L	0.1	02/16/26	02/17/26
Methoxychlor	ND		ug/L	0.1	02/16/26	02/17/26
Toxaphene	ND		ug/L	2.0	02/16/26	02/17/26
Chlordane (Technical)	ND		ug/L	1.0	02/16/26	02/17/26
Surrogates				**Limits**		
TCMX	88%		%REC	29-120	02/16/26	02/17/26
Decachlorobiphenyl	108%		%REC	33-132	02/16/26	02/17/26
Method: EPA 8082 Prep Method: EPA 3510C						
Aroclor-1016	ND		ug/L	0.50	02/16/26	02/17/26
Aroclor-1221	ND		ug/L	0.50	02/16/26	02/17/26
Aroclor-1232	ND		ug/L	0.50	02/16/26	02/17/26
Aroclor-1242	ND		ug/L	0.50	02/16/26	02/17/26
Aroclor-1248	ND		ug/L	0.50	02/16/26	02/17/26
Aroclor-1254	ND		ug/L	0.50	02/16/26	02/17/26
Aroclor-1260	ND		ug/L	0.50	02/16/26	02/17/26
Aroclor-1262	ND		ug/L	0.50	02/16/26	02/17/26
Aroclor-1268	ND		ug/L	0.50	02/16/26	02/17/26
Total PCBs	ND		ug/L	0.50	02/16/26	02/17/26
Surrogates				**Limits**		
Decachlorobiphenyl (PCB)	89%		%REC	28-138	02/16/26	02/17/26

ENTHALPY ANALYTICAL

Batch QC

Type:	**Lab Control Sample**	**Lab ID:**	**QC1340998**	**Batch:**	**395462**
Matrix:	**Water**	**Method:**	**EPA 8081A**	**Prep Method:**	**EPA 3510C**

QC1340998 Analyte	Result	Spiked	Units	Recovery	Qual	Limits
alpha-BHC	0.5462	0.5000	ug/L	109%		66-121
beta-BHC	0.5538	0.5000	ug/L	111%		73-120
gamma-BHC	0.5469	0.5000	ug/L	109%		68-125
delta-BHC	0.5638	0.5000	ug/L	113%		68-131
Heptachlor	0.5632	0.5000	ug/L	113%		63-120
Aldrin	0.4820	0.5000	ug/L	96%		56-120
Heptachlor epoxide	0.4862	0.5000	ug/L	97%		65-120
Endosulfan I	0.4895	0.5000	ug/L	98%		68-124
Dieldrin	0.4981	0.5000	ug/L	100%		66-124
4,4'-DDE	0.5125	0.5000	ug/L	103%		67-131
Endrin	0.5266	0.5000	ug/L	105%		68-135
Endosulfan II	0.5326	0.5000	ug/L	107%		71-130
Endosulfan sulfate	0.5310	0.5000	ug/L	106%		68-128
4,4'-DDD	0.5573	0.5000	ug/L	111%		65-130
Endrin aldehyde	0.4986	0.5000	ug/L	100%		67-124
Endrin ketone	0.5663	0.5000	ug/L	113%		69-137
4,4'-DDT	0.5415	0.5000	ug/L	108%		65-136
Methoxychlor	0.5582	0.5000	ug/L	112%		69-150
Surrogates						
TCMX	0.4970	0.5000	ug/L	99%		29-120
Decachlorobiphenyl	0.5611	0.5000	ug/L	112%		33-132

ENTHALPY ANALYTICAL

Batch QC

Type:	**Lab Control Sample Duplicate**	**Lab ID:**	**QC1340999**	**Batch:**	**395462**
Matrix:	**Water**	**Method:**	**EPA 8081A**	**Prep Method:**	**EPA 3510C**

QC1340999 Analyte	Result	Spiked	Units	Recovery	Qual	Limits	RPD	RPD Lim
alpha-BHC	0.5355	0.5000	ug/L	107%		66-121	2	20
beta-BHC	0.5360	0.5000	ug/L	107%		73-120	3	20
gamma-BHC	0.5335	0.5000	ug/L	107%		68-125	2	20
delta-BHC	0.5469	0.5000	ug/L	109%		68-131	3	20
Heptachlor	0.5447	0.5000	ug/L	109%		63-120	3	24
Aldrin	0.4581	0.5000	ug/L	92%		56-120	5	30
Heptachlor epoxide	0.4652	0.5000	ug/L	93%		65-120	4	20
Endosulfan I	0.4664	0.5000	ug/L	93%		68-124	5	20
Dieldrin	0.4743	0.5000	ug/L	95%		66-124	5	22
4,4'-DDE	0.4794	0.5000	ug/L	96%		67-131	7	21
Endrin	0.4968	0.5000	ug/L	99%		68-135	6	20
Endosulfan II	0.5066	0.5000	ug/L	101%		71-130	5	21
Endosulfan sulfate	0.4998	0.5000	ug/L	100%		68-128	6	21
4,4'-DDD	0.5195	0.5000	ug/L	104%		65-130	7	22
Endrin aldehyde	0.4667	0.5000	ug/L	93%		67-124	7	20
Endrin ketone	0.5296	0.5000	ug/L	106%		69-137	7	21
4,4'-DDT	0.5076	0.5000	ug/L	102%		65-136	6	23
Methoxychlor	0.5215	0.5000	ug/L	104%		69-150	7	23
Surrogates								
TCMX	0.4821	0.5000	ug/L	96%		29-120		
Decachlorobiphenyl	0.5315	0.5000	ug/L	106%		33-132		

Type:	**Lab Control Sample**	**Lab ID:**	**QC1341000**	**Batch:**	**395462**
Matrix:	**Water**	**Method:**	**EPA 8082**	**Prep Method:**	**EPA 3510C**

QC1341000 Analyte	Result	Spiked	Units	Recovery	Qual	Limits
Aroclor-1016	5.818	5.000	ug/L	116%		69-120
Aroclor-1260	5.630	5.000	ug/L	113%		72-124
Surrogates						
Decachlorobiphenyl (PCB)	0.4904	0.5000	ug/L	98%		28-138

Type:	**Lab Control Sample Duplicate**	**Lab ID:**	**QC1341001**	**Batch:**	**395462**
Matrix:	**Water**	**Method:**	**EPA 8082**	**Prep Method:**	**EPA 3510C**

QC1341001 Analyte	Result	Spiked	Units	Recovery	Qual	Limits	RPD	RPD Lim
Aroclor-1016	5.478	5.000	ug/L	110%		69-120	6	22
Aroclor-1260	5.259	5.000	ug/L	105%		72-124	7	25
Surrogates								
Decachlorobiphenyl (PCB)	0.4628	0.5000	ug/L	93%		28-138		

ENTHALPY ANALYTICAL

Batch QC

Type: Blank	Lab ID: QC1341492	Batch: 395626
Matrix: Soil	Method: EPA 8082	Prep Method: EPA 3546

QC1341492 Analyte	Result	Qual	Units	RL	Prepared	Analyzed
Aroclor-1016	ND		ug/Kg	50	02/18/26	02/19/26
Aroclor-1221	ND		ug/Kg	50	02/18/26	02/19/26
Aroclor-1232	ND		ug/Kg	50	02/18/26	02/19/26
Aroclor-1242	ND		ug/Kg	50	02/18/26	02/19/26
Aroclor-1248	ND		ug/Kg	50	02/18/26	02/19/26
Aroclor-1254	ND		ug/Kg	50	02/18/26	02/19/26
Aroclor-1260	ND		ug/Kg	50	02/18/26	02/19/26
Aroclor-1262	ND		ug/Kg	50	02/18/26	02/19/26
Aroclor-1268	ND		ug/Kg	50	02/18/26	02/19/26
Total PCBs	ND		ug/Kg	50	02/18/26	02/19/26
Surrogates				**Limits**		
Decachlorobiphenyl (PCB)	128%	*	%REC	50-127	02/18/26	02/19/26

Type: Lab Control Sample	Lab ID: QC1341493	Batch: 395626
Matrix: Soil	Method: EPA 8082	Prep Method: EPA 3546

QC1341493 Analyte	Result	Spiked	Units	Recovery	Qual	Limits
Aroclor-1016	505.9	493.6	ug/Kg	102%		66-120
Aroclor-1260	574.3	493.6	ug/Kg	116%		63-126
Surrogates						
Decachlorobiphenyl (PCB)	61.10	49.36	ug/Kg	124%		50-127

Type: Matrix Spike	Lab ID: QC1341494	Batch: 395626
Matrix (Source ID): Soil (553104-001)	Method: EPA 8082	Prep Method: EPA 3546

QC1341494 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	DF
Aroclor-1016	488.4	ND	492.6	ug/Kg	99%		60-123	0.99
Aroclor-1260	516.6	ND	492.6	ug/Kg	105%		55-136	0.99
Surrogates								
Decachlorobiphenyl (PCB)	51.57		49.26	ug/Kg	105%		50-127	0.99

Type: Matrix Spike Duplicate	Lab ID: QC1341495	Batch: 395626
Matrix (Source ID): Soil (553104-001)	Method: EPA 8082	Prep Method: EPA 3546

QC1341495 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	RPD	RPD Lim	DF
Aroclor-1016	479.1	ND	500.0	ug/Kg	96%		60-123	3	37	1
Aroclor-1260	487.9	ND	500.0	ug/Kg	98%		55-136	7	41	1
Surrogates										
Decachlorobiphenyl (PCB)	47.99		50.00	ug/Kg	96%		50-127			1

ENTHALPY ANALYTICAL

Batch QC

Type: Blank	Lab ID: QC1341832	Batch: 395719
Matrix: Miscell.	Method: EPA 8082	Prep Method: EPA 3546

QC1341832 Analyte	Result	Qual	Units	RL	Prepared	Analyzed
Aroclor-1016	ND		ug/Kg	51	02/18/26	02/19/26
Aroclor-1221	ND		ug/Kg	51	02/18/26	02/19/26
Aroclor-1232	ND		ug/Kg	51	02/18/26	02/19/26
Aroclor-1242	ND		ug/Kg	51	02/18/26	02/19/26
Aroclor-1248	ND		ug/Kg	51	02/18/26	02/19/26
Aroclor-1254	ND		ug/Kg	51	02/18/26	02/19/26
Aroclor-1260	ND		ug/Kg	51	02/18/26	02/19/26
Aroclor-1262	ND		ug/Kg	51	02/18/26	02/19/26
Aroclor-1268	ND		ug/Kg	51	02/18/26	02/19/26
Total PCBs	ND		ug/Kg	51	02/18/26	02/19/26
Surrogates				**Limits**		
Decachlorobiphenyl (PCB)	86%		%REC	50-127	02/18/26	02/19/26

Type: Lab Control Sample	Lab ID: QC1342128	Batch: 395719
Matrix: Miscell.	Method: EPA 8082	Prep Method: EPA 3546

QC1342128 Analyte	Result	Spiked	Units	Recovery	Qual	Limits
Aroclor-1016	444.0	490.2	ug/Kg	91%		66-120
Aroclor-1260	452.9	490.2	ug/Kg	92%		63-126
Surrogates						
Decachlorobiphenyl (PCB)	45.86	49.02	ug/Kg	94%		50-127

Type: Matrix Spike	Lab ID: QC1342351	Batch: 395719
Matrix (Source ID): Soil (553104-027)	Method: EPA 8082	Prep Method: EPA 3546

QC1342351 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	DF
Aroclor-1016	445.0	ND	505.1	ug/Kg	88%		60-123	1
Aroclor-1260	424.7	ND	505.1	ug/Kg	84%		55-136	1
Surrogates								
Decachlorobiphenyl (PCB)	40.79		50.51	ug/Kg	81%		50-127	1

Type: Matrix Spike Duplicate	Lab ID: QC1342352	Batch: 395719
Matrix (Source ID): Soil (553104-027)	Method: EPA 8082	Prep Method: EPA 3546

QC1342352 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	RPD	RPD Lim	DF
Aroclor-1016	394.0	ND	490.2	ug/Kg	80%		60-123	9	37	0.98
Aroclor-1260	392.1	ND	490.2	ug/Kg	80%		55-136	5	41	0.98
Surrogates										
Decachlorobiphenyl (PCB)	36.97		49.02	ug/Kg	75%		50-127			0.98

* Value is outside QC limits
J Estimated value
ND Not Detected

Laboratory Job Number 553104

Subcontracted Products

AmeriSci Los Angeles

AmeriSci Richmond
13635 GENITO ROAD
MIDLOTHIAN, VIRGINIA 23112
TEL: (804) 763-1200 • FAX: (804) 763-0493

February 28, 2026

Enthalpy Analytical
Attn: Patty Mata
931 West Barkley Ave
Orange, CA 92868

RE: Enthalpy Analytical
Job Number 126021834
P.O. #098707
553104

Dear Patty Mata:

Enclosed are the results of Asbestos Analysis - Bulk Qualitative Protocol of the following Enthalpy Analytical samples, received at AmeriSci on Thursday, February 19, 2026, for a 5 day turnaround:

CG-13-0.5, CG-13-2.5, CG-14-0.5, CG-14-2.5, CG-15-0.5, CG-15-2.5, CG-16-0.5, CG-16-2.5, CG-16-0.5-DUP, CG-16-2.5-DUP, CG-17-0.5, CG-17-2.5, CG-18-0.5, CG-18-2.5, CG-19-0.5, CG-19-2.5

The 16 samples, placed in zip lock bag, were shipped to AmeriSci via Fed Ex 7178 3973 9808. Enthalpy Analytical requested Bulk-Qualitative analysis of these samples.

The samples were prepared and analyzed by using a Standard Operating Procedure developed by AmeriSci, Inc.. After preparation, using non-quantitative matrix reduction if necessary, the presence or absence of asbestos is determined by PLM and/or TEM as indicated on the attached summary table. Quantification after the fact is not possible without a new preparation. This report relates ONLY to the analysis expressed as "asbestos present" or "no asbestos visible". This report must not be used to claim product endorsement or approval by AmeriSci, NVLAP, ELAP or any other associated AmeriSci certifying agency. The National Institute of Standards and Technology accreditation requirements, mandate that this report must not be reproduced, except in full without the approval of the laboratory.

AmeriSci appreciates this opportunity to serve your organization. Please contact us for any further assistance or with any questions.

Sincerely,



Cory M. Parnell

Laboratory Director | Authorized Signatory

AmeriSci Richmond
13635 GENITO ROAD
MIDLOTHIAN, VIRGINIA 23112
TEL: (804) 763-1200 • FAX: (804) 763-0493

PLM Bulk Asbestos Report

Enthalpy Analytical
Attn: Patty Mata
931 West Barkley Ave

Orange, CA 92868

Date Received 2/19/2026
Date Examined 02/26/26

RE: 553104

AmeriSci Job # 126021834
P.O. # 098707
Page 1 **of** 3

Client No. / HGA	Lab No.	Asbestos Present	Total % Asbestos	Notes
CG-13-0.5	126021834-01	***No***	NVA by C. David Mintz on 02/26/26	
Location: **Analyst Description:** Brown, Homogeneous, Non-Fibrous, Soil **Asbestos Types:** **Other Material:** Cellulose Present, Non-fibrous Present **Comment:** All samples placed in drying oven 4 hours.				
CG-13-2.5	126021834-02	***No***	NVA by C. David Mintz on 02/26/26	*1*
Location: **Analyst Description:** Brown, Homogeneous, Non-Fibrous, Soil **Asbestos Types:** **Other Material:** Cellulose Present, Non-fibrous Present				
CG-14-0.5	126021834-03	***No***	NVA by C. David Mintz on 02/26/26	*1*
Location: **Analyst Description:** Brown, Homogeneous, Non-Fibrous, Soil **Asbestos Types:** **Other Material:** Cellulose Present, Non-fibrous Present				
CG-14-2.5	126021834-04	***No***	NVA by C. David Mintz on 02/26/26	*1*
Location: **Analyst Description:** Brown, Homogeneous, Non-Fibrous, Soil **Asbestos Types:** **Other Material:** Non-fibrous Present				
CG-15-0.5	126021834-05	***No***	NVA by C. David Mintz on 02/26/26	*1*
Location: **Analyst Description:** Brown, Homogeneous, Non-Fibrous, Soil **Asbestos Types:** **Other Material:** Non-fibrous Present				

See Reporting notes on last page

PLM Bulk Asbestos Report

553104

Client No. / HGA	Lab No.	Asbestos Present	Total % Asbestos	Notes
CG-15-2.5	126021834-06	***No***	NVA by C. David Mintz on 02/26/26	*1*
Location: **Analyst Description:** Brown, Homogeneous, Non-Fibrous, Soil **Asbestos Types:** **Other Material:** Non-fibrous Present				
CG-16-0.5	126021834-07	***No***	NVA by C. David Mintz on 02/26/26	*1*
Location: **Analyst Description:** Brown, Homogeneous, Non-Fibrous, Soil **Asbestos Types:** **Other Material:** Non-fibrous Present				
CG-16-2.5	126021834-08	***No***	NVA by C. David Mintz on 02/26/26	*1*
Location: **Analyst Description:** Brown, Homogeneous, Non-Fibrous, Soil **Asbestos Types:** **Other Material:** Cellulose Present, Non-fibrous Present				
CG-16-0.5-DUP	126021834-09	***No***	NVA by C. David Mintz on 02/26/26	*1*
Location: **Analyst Description:** Brown, Homogeneous, Non-Fibrous, Soil **Asbestos Types:** **Other Material:** Cellulose Present, Non-fibrous Present				
CG-16-2.5-DUP	126021834-10	***No***	NVA by C. David Mintz on 02/26/26	*1*
Location: **Analyst Description:** Brown, Homogeneous, Non-Fibrous, Soil **Asbestos Types:** **Other Material:** Cellulose Present, Non-fibrous Present				
CG-17-0.5	126021834-11	***No***	NVA by C. David Mintz on 02/26/26	*1*
Location: **Analyst Description:** Brown, Homogeneous, Non-Fibrous, Soil **Asbestos Types:** **Other Material:** Non-fibrous Present				
CG-17-2.5	126021834-12	***No***	NVA by C. David Mintz on 02/26/26	*1*
Location: **Analyst Description:** Brown, Homogeneous, Non-Fibrous, Soil **Asbestos Types:** **Other Material:** Non-fibrous Present				

See Reporting notes on last page

PLM Bulk Asbestos Report

553104

Client No. / HGA	Lab No.	Asbestos Present	Total % Asbestos	Notes
CG-18-0.5	126021834-13	***No***	NVA by C. David Mintz on 02/26/26	*1*

Location:
Analyst Description: Brown, Homogeneous, Non-Fibrous, Soil, granular
Asbestos Types:
Other Material: Cellulose Present, Non-fibrous Present

CG-18-2.5	126021834-14	***No***	NVA by C. David Mintz on 02/26/26	*1*

Location:
Analyst Description: Brown, Homogeneous, Non-Fibrous, Soil
Asbestos Types:
Other Material: Non-fibrous Present

CG-19-0.5	126021834-15	***No***	NVA by C. David Mintz on 02/26/26	*1*


Location:
Analyst Description: Dark Brown, Homogeneous, Non-Fibrous, Soil
Asbestos Types:
Other Material: Non-fibrous Present

CG-19-2.5	126021834-16	***No***	NVA by C. David Mintz on 02/26/26	*1*

Location:
Analyst Description: Dark Brown, Homogeneous, Non-Fibrous, Soil
Asbestos Types:
Other Material: Non-fibrous Present

Reporting Notes:

(1) Sample homogenized by grinding to a powder prior to analysis.

Analyzed by: C. David Mintz 
Date: 2/26/2026

Reviewed by: Cory M. Parnell 

*NAD = no asbestos detected, Detection Limit <1%, Reporting Limits: CVES = 1%, 400 Pt Ct = 0.25%, 1000 Pt Ct = 0.1%; "Present" or NVA = "No Visible Asbestos" are observations made during a qualitative analysis (Not covered by NVLAP or NY ELAP accreditations); NA = not analyzed; NA/PS = not analyzed / positive stop; PLM Bulk Asbestos Analysis using Olympus, Model BH-2 microscope, Serial #210972, by EPA 600/R-93/116 per 40 CFR 763 (NVLAP Lab Code 101904-0) and ELAP PLM Analysis Protocol 198.1 for New York friable samples which includes quantitation of any vermiculite observed (198.6 for NOB samples) or EPA 400 pt ct by EPA 600/M4-82-020 (NYSDOH ELAP Lab # 10984); CA ELAP Lab # 2508; Note: PLM is not consistently reliable in detecting asbestos in floor coverings and similar NOB materials. NAD or Trace results by PLM are inconclusive, TEM is currently the only method that can be used to determine if this material can be considered or treated as non-asbestos-containing in New York State (also see EPA Advisory for floor tile, FR 59, 146, 38970, 8/1/94). NIST Accreditation requirements mandate that this report must not be reproduced except in full without the approval of the laboratory. This PLM report relates ONLY to the items tested.

ENTHALPY ANALYTICAL

931 West Barkley Ave
Orange, CA 92868
(714) 771-6900

126021834 on 2/19/26

Subcontract Laboratory:
AmeriSci Los Angeles
24416 S. Main Street
Suite 308
Carson, CA 90745
ATTN: Sample Control
PO #: Required, to be sent via email

Enthalpy Order: EO-553104
PM: Patty Mata
Email: patty.mata@enthalpy.com
CC: incomingreports@enthalpy.com
Phone: (714) 771-6900

Results Due: Standard TAT
Report Level: II
Report To: RL
EDDs:

Notes:

mple ID	Collected	Lab ID	# Cont.	Matrix	Analysis Requested	Comment
-13-0.5	12-FEB-2026 00:00	553104-053	1	Soil	Asbestos by PLM	PLM qualitative
-13-2.5	12-FEB-2026 00:00	553104-054	1	Soil	Asbestos by PLM	PLM qualitative
-14-0.5	12-FEB-2026 00:00	553104-055	1	Soil	Asbestos by PLM	PLM qualitative
-14-2.5	12-FEB-2026 00:00	553104-056	1	Soil	Asbestos by PLM	PLM qualitative
-15-0.5	12-FEB-2026 00:00	553104-057	1	Soil	Asbestos by PLM	PLM qualitative
-15-2.5	12-FEB-2026 00:00	553104-058	1	Soil	Asbestos by PLM	PLM qualitative
-16-0.5	12-FEB-2026 00:00	553104-059	1	Soil	Asbestos by PLM	PLM qualitative
-16-2.5	12-FEB-2026 00:00	553104-060	1	Soil	Asbestos by PLM	PLM qualitative
16-0.5-DUP	12-FEB-2026 00:00	553104-061	1	Soil	Asbestos by PLM	PLM qualitative
16-2.5-DUP	12-FEB-2026 00:00	553104-062	1	Soil	Asbestos by PLM	PLM qualitative
17-0.5	12-FEB-2026 00:00	553104-063	1	Soil	Asbestos by PLM	PLM qualitative
17-2.5	12-FEB-2026 00:00	553104-064	1	Soil	Asbestos by PLM	PLM qualitative
18-0.5	12-FEB-2026 00:00	553104-065	1	Soil	Asbestos by PLM	PLM qualitative
18-2.5	12-FEB-2026 00:00	553104-066	1	Soil	Asbestos by PLM	PLM qualitative
19-0.5	12-FEB-2026 00:00	553104-067	1	Soil	Asbestos by PLM	PLM qualitative
19-2.5	12-FEB-2026 00:00	553104-068	1	Soil	Asbestos by PLM	PLM qualitative
1-268212	12-FEB-2026 14:45	553104-069	1	Water	Asbestos	Wastewater TEM method

Already Sent 2/17/26

Notes:	Relinquished By:	Received By:
	[signature]	M. RIVERO
	Date: 2-18-26 1340	Date: 2/18/26 @ 1345
	M. RIVERO	
	Date: 2/18/26 @ 1345	Date:
	Date:	Date:

Received
FEB 19 2026

AmeriSci Richmond
13635 GENITO ROAD
MIDLOTHIAN, VIRGINIA 23112
TEL: (804) 763-1200 • FAX: (804) 763-0493

February 28, 2026

Enthalpy Analytical
Attn: Patty Mata
931 West Barkley Ave
Orange, CA 92868

RE: Enthalpy Analytical
Job Number 126021827
P.O. #098707
EO-553104

Dear Patty Mata:

Enclosed are the results for TEM asbestos analysis of the following Enthalpy Analytical samples received at AmeriSci on Thursday, February 19, 2026, for a 5 day turnaround:

EB-01-260212

The 1 samples were filtered and prepared according to Water analysis under the EPA-600/4-83-043 "Analytical Method for Determination of Asbestos Fibers in Water" (1983). Samples with high organic content may be prepared following EPA-600/4-80-005 if necessary and are so noted on the TEM count sheets. AmeriSci, Inc. uses the "Grid Square" method of counting and the concentration is calculated in millions of fibers per liter (MFL).

Table I represents a summary of all pertinent information used for the calculations. Included are the size of each structure counted, concentration, structure concentration greater than 10 microns in length, type of asbestiform material detected and the analytical sensitivity, which represents the concentration by the detection of one fiber in the TEM fiber count. Copies of the Fiber Count Sheets, show the raw data for examination. These data sheets contain information for fiber length/width, fiber type, structure morphology and pertinent information on EDS, SAED and photography.

This report relates ONLY to the sample analysis expressed as millions of fibers per liter (MFL). AmeriSci assumes no responsibility for customer supplied data such as “sample location” or “the condition of the water sample before arriving at AmeriSci”. This report must not be used to claim product endorsement by AmeriSci, NVLAP, ELAP or any agency of the U. S. Government. The National Institute of Standards and Technology accreditation requirements, mandate that this report must not be reproduced, except in full without the approval of the laboratory.

AmeriSci appreciates this opportunity to serve your organization. Please contact us for any further assistance or with any questions.

Sincerely,



Cory M. Parnell

Laboratory Director | Authorized Signatory

AmeriSci Job #: **126021827**
Client Name: Enthalpy Analytical

Table I
Summary of Transmission Electron Microscopy (TEM) Results for Asbestos (Water)


EO-553104

AmeriSci Sample #	Client Sample No./Location	Liquid Filtered (liters)	Temp (Celcius)	Structures Detected* (total)	Structures Detected* (>10 µm)	Analytical Sensitivity (MF/L)	Asbestos Conc (total) (MF/L)	Asbestos Conc (>10 µm) (MF/L)	Asbestos Type
01	EB-01-260212	0.01	17.7	NSD	NSD	0.22	<0.22	<0.22	----

* NAD/NSD = no asbestos detected, NA = not analyzed, MF/L = million fibers per liter; Drinking Water accreditations do not cover waste water analysis. NOTE: Drinking water analysis by EPA-600/4-83-043 (100.1). Fiber criteria (>=0.5 microns, for 100.1; >10 microns for 100.2; 5:1 aspect ratio for both), organic rich waste water prepped by EPA-600/4-80-005. Analytical sensitivity calculated as though 1 fiber had been detected on the TEM GRID area analyzed. Sample temperatures reported above were measured upon receipt. Water samples are refrigerated upon receipt and filtered within four hours.

Reviewed By: _____ Analyzed By: Cory M. Parnell _____ Date: 2/25/2026

TEM Asbestos (Water) Count Sheet



Client Name: Enthalpy Analytical
Job #: 126021827
Lab Sample #: 01
Client Sample #: EB-01-260212
Received: 2/19/2026 12:00:00
Date Analyzed: 2/25/2026
Temp: 17.7

Volume (liters): 0.01
Filter Type / Filter Area: MCE 214 mm2
Grid Opening Size: 0.00967
Area Examined: 0.09670 mm2
Magnification: 20,000
Accelerating Voltage: 100 KeV

Analysis Performed by: Cory M. Parnell

Location	Grid Opening	Fiber	Length µM	Width µM	Fiber Type	Morphology	EDS	Orient.	SAED	Photo
B9-A1	1	NSD								
B9-A3	2	NSD								
B9-A5	3	NSD								
B9-A7	4	NSD								
B9-J3	5	NSD								
B8-G4	6	NSD								
B8-G6	7	NSD								
B8-C1	8	NSD								
B8-C4	9	NSD								
B8-C6	10	NSD								

NSD: No Asbestos Structures Detected

Scope #: Front 4: Jeol JEM-100CX II, Serial No.156147-247

Comments

		Concentration (million fibers/liter)
Total Grid Openings:	10	
Chrysotile Asbestos Structures:	0	<0.221
Amphibole Asbestos Structures:	0	<0.221
Asbestos Structures >10 microns:	0	<0.221
Total Asbestos Structures:	0	<0.221
Analytical Sensitivity:		0.221

Grid Evaluation

- [x] Grid Openings Covered > 50%
- [x] Intact Grid Opening >
- [x] Undissolved Filter < 10%
- [x] Folded Replica < 50%
- [x] Filter Loading < 25%
- [x] Particulate Even

ENTHALPY ANALYTICAL

931 West Barkley Ave
Orange, CA 92868
(714) 771-6900

1260218 27

Subcontract Laboratory:
AmeriSci Los Angeles
24416 S. Main Street
Suite 308
Carson, CA 90745
ATTN: Sample Control
PO #: Required, to be sent via email

Enthalpy Order: EO-553104
PM: Patty Mata
Email: patty.mata@enthalpy.com
CC: incomingreports@enthalpy.com
Phone: (714) 771-6900

Results Due: Standard TAT
Report Level: II
Report To: RL
EDDs:

Notes:

Sample ID	Collected	Lab ID	# Cont.	Matrix	Analysis Requested	Comment
CG-13-0.5	12-FEB-2026 00:00	553104-053	1	Soil	Asbestos by PLM	PLM qualitative
CG-13-2.5	12-FEB-2026 00:00	553104-054	1	Soil	Asbestos by PLM	PLM qualitative
CG-14-0.5	12-FEB-2026 00:00	553104-055	1	Soil	Asbestos by PLM	PLM qualitative
CG-14-2.5	12-FEB-2026 00:00	553104-056	1	Soil	Asbestos by PLM	PLM qualitative
CG-15-0.5	12-FEB-2026 00:00	553104-057	1	Soil	Asbestos by PLM	PLM qualitative
CG-15-2.5	12-FEB-2026 00:00	553104-058	1	Soil	Asbestos by PLM	PLM qualitative
CG-16-0.5	12-FEB-2026 00:00	553104-059	1	Soil	Asbestos by PLM	PLM qualitative
CG-16-2.5	12-FEB-2026 00:00	553104-060	1	Soil	Asbestos by PLM	PLM qualitative
CG-16-0.5-DUP	12-FEB-2026 00:00	553104-061	1	Soil	Asbestos by PLM	PLM qualitative
CG-16-2.5-DUP	12-FEB-2026 00:00	553104-062	1	Soil	Asbestos by PLM	PLM qualitative
CG-17-0.5	12-FEB-2026 00:00	553104-063	1	Soil	Asbestos by PLM	PLM qualitative
CG-17-2.5	12-FEB-2026 00:00	553104-064	1	Soil	Asbestos by PLM	PLM qualitative
CG-18-0.5	12-FEB-2026 00:00	553104-065	1	Soil	Asbestos by PLM	PLM qualitative
CG-18-2.5	12-FEB-2026 00:00	553104-066	1	Soil	Asbestos by PLM	PLM qualitative
CG-19-0.5	12-FEB-2026 00:00	553104-067	1	Soil	Asbestos by PLM	PLM qualitative
CG-19-2.5	12-FEB-2026 00:00	553104-068	1	Soil	Asbestos by PLM	PLM qualitative
EB-01-260212	12-FEB-2026 14:45	553104-069	1	Water	Asbestos	Wastewater TEM method

Notes:	Relinquished By:	Received By:
	[signature]	M. RIVERO
	Date: 2-17-26 1250	Date: 2/17/26 @ 1255
	M. RIVERO	
	Date: 2/17/26 @ 1255	Date:
	Date:	Date:

Received
FEB 19 2026

Enthalpy Analytical
931 West Barkley Ave
Orange, CA 92868
(714) 771-6900

enthalpy.com

Lab Job Number : 553195
Report Level : II
Report Date : 02/25/2026

Analytical Report *prepared for:*

Vanya Keyes
Terraphase Engineering
18401 Von Karman Ave, Suite #410
Irvine, CA 92612

Location: Centennial High School, 2606 N Central Ave., Compton, CA 90222

Authorized for release by:



Patty Mata, Project Manager
patty.mata@enthalpy.com

This data package has been reviewed for technical correctness and completeness. Release of this data has been authorized by the Laboratory Manager or the Manager's designee, as verified by the above signature which applies to this PDF file as well as any associated electronic data deliverable files. The results contained in this report meet all requirements of NELAP and pertain only to those samples which were submitted for analysis. This report may be reproduced only in its entirety.

CA ELAP# 1338, CA ELAP #1338-S1, NELAP# 4038, SCAQMD LAP# 18LA0518, LACSD ID# 10105, ORELAP# 4197

ENTHALPY ANALYTICAL

Sample Summary

Vanya Keyes Terraphase Engineering 18401 Von Karman Ave, Suite #410 Irvine, CA 92612	Lab Job #: Location: Date Received:	553195 Centennial High School, 2606 N Central Ave., Compton, CA 90222 02/13/26	

Sample ID	Lab ID	Collected	Matrix
AOC3-SB-19-0.5	553195-001	02/13/26 07:25	Soil
AOC3-SB-18-0.5	553195-002	02/13/26 07:40	Soil
AOC3-SB-17-0.5	553195-003	02/13/26 07:50	Soil
AOC3-SB-19-2.5	553195-004	02/13/26 07:30	Soil
AOC3-SB-18-2.5	553195-005	02/13/26 07:45	Soil
AOC3-SB-17-2.5	553195-006	02/13/26 07:55	Soil
AOC3-SB-20-0.5	553195-007	02/13/26 08:45	Soil
AOC3-SB-21-0.5	553195-008	02/13/26 08:55	Soil
AOC3-SB-22-0.5	553195-009	02/13/26 09:05	Soil
AOC3-SB-20-2.5	553195-010	02/13/26 08:50	Soil
AOC3-SB-21-2.5	553195-011	02/13/26 09:00	Soil
AOC3-SB-22-2.5	553195-012	02/13/26 09:10	Soil
AOC3-SB-23-0.5	553195-013	02/13/26 09:15	Soil
AOC3-SB-24-0.5	553195-014	02/13/26 09:55	Soil
AOC3-SB-25-0.5	553195-015	02/13/26 09:45	Soil
AOC3-SB-23-2.5	553195-016	02/13/26 09:20	Soil
AOC3-SB-24-2.5	553195-017	02/13/26 10:00	Soil
AOC3-SB-25-2.5	553195-018	02/13/26 09:50	Soil
DUP-01-0.5-260213	553195-019	02/13/26 00:00	Soil
DUP-01-2.5-260213	553195-020	02/13/26 00:00	Soil
AOC3-SB-26-0.5	553195-021	02/13/26 08:20	Soil
AOC3-SB-27-0.5	553195-022	02/13/26 08:10	Soil
AOC3-SB-28-0.5	553195-023	02/13/26 08:00	Soil
AOC3-SB-26-2.5	553195-024	02/13/26 08:25	Soil
AOC3-SB-27-2.5	553195-025	02/13/26 08:15	Soil
AOC3-SB-28-2.5	553195-026	02/13/26 08:05	Soil

ENTHALPY ANALYTICAL

Sample Summary

Vanya Keyes Terraphase Engineering 18401 Von Karman Ave, Suite #410 Irvine, CA 92612	Lab Job #: Location: Date Received:	553195 Centennial High School, 2606 N Central Ave., Compton, CA 90222 02/13/26

Sample ID	Lab ID	Collected	Matrix
AOC3-SB-29-0.5	553195-027	02/13/26 11:50	Soil
AOC3-SB-30-0.5	553195-028	02/13/26 11:35	Soil
AOC3-SB-31-0.5	553195-029	02/13/26 11:25	Soil
AOC3-SB-29-2.5	553195-030	02/13/26 11:55	Soil
AOC3-SB-30-2.5	553195-031	02/13/26 11:40	Soil
AOC3-SB-31-2.5	553195-032	02/13/26 11:30	Soil
AOC3-SB-32-0.5	553195-033	02/13/26 10:45	Soil
AOC3-SB-33-0.5	553195-034	02/13/26 10:35	Soil
AOC3-SB-34-0.5	553195-035	02/13/26 10:15	Soil
AOC3-SB-32-2.5	553195-036	02/13/26 10:50	Soil
AOC3-SB-33-2.5	553195-037	02/13/26 10:40	Soil
AOC3-SB-34-2.5	553195-038	02/13/26 10:20	Soil
AOC3-SB-35-0.5	553195-039	02/13/26 13:20	Soil
AOC3-SB-36-0.5	553195-040	02/13/26 13:10	Soil
AOC3-SB-37-0.5	553195-041	02/13/26 13:00	Soil
AOC3-SB-35-2.5	553195-042	02/13/26 13:25	Soil
AOC3-SB-36-2.5	553195-043	02/13/26 13:15	Soil
AOC3-SB-37-2.5	553195-044	02/13/26 13:05	Soil
DUP-02-0.5-260213	553195-045	02/13/26 00:00	Soil
DUP-02-2.5-260213	553195-046	02/13/26 00:00	Soil
AOC3-SB-38-0.5	553195-047	02/13/26 12:20	Soil
AOC3-SB-39-0.5	553195-048	02/13/26 12:10	Soil
AOC3-SB-40-0.5	553195-049	02/13/26 12:00	Soil
AOC3-SB-38-2.5	553195-050	02/13/26 12:25	Soil
AOC3-SB-39-2.5	553195-051	02/13/26 12:15	Soil
AOC3-SB-40-2.5	553195-052	02/13/26 12:05	Soil

ENTHALPY ANALYTICAL

Sample Summary

Vanya Keyes Terraphase Engineering 18401 Von Karman Ave, Suite #410 Irvine, CA 92612		Lab Job #: Location: Date Received:	553195 Centennial High School, 2606 N Central Ave., Compton, CA 90222 02/13/26

Sample ID	Lab ID	Collected	Matrix
AOC3-SB-46-0.5	553195-053	02/13/26 13:30	Soil
AOC3-SB-45-0.5	553195-054	02/13/26 13:40	Soil
AOC3-SB-44-0.5	553195-055	02/13/26 13:50	Soil
AOC3-SB-46-2.5	553195-056	02/13/26 13:35	Soil
AOC3-SB-45-2.5	553195-057	02/13/26 13:45	Soil
AOC3-SB-44-2.5	553195-058	02/13/26 13:55	Soil
CG-20-0.5	553195-059	02/13/26 00:00	Soil
CG-20-2.5	553195-060	02/13/26 00:00	Soil
CG-21-0.5	553195-061	02/13/26 00:00	Soil
CG-21-2.5	553195-062	02/13/26 00:00	Soil
CG-22-0.5	553195-063	02/13/26 00:00	Soil
CG-22-2.5	553195-064	02/13/26 00:00	Soil
CG-22-0.5-DUP	553195-065	02/13/26 00:00	Soil
CG-22-2.5-DUP	553195-066	02/13/26 00:00	Soil
CG-23-0.5	553195-067	02/13/26 00:00	Soil
CG-23-2.5	553195-068	02/13/26 00:00	Soil
CG-24-0.5	553195-069	02/13/26 00:00	Soil
CG-24-2.5	553195-070	02/13/26 00:00	Soil
CG-25-0.5	553195-071	02/13/26 00:00	Soil
CG-25-2.5	553195-072	02/13/26 00:00	Soil
CG-26-0.5	553195-073	02/13/26 00:00	Soil
CG-26-2.5	553195-074	02/13/26 00:00	Soil
CG-26-0.5-DUP	553195-075	02/13/26 00:00	Soil
CG-26-2.5-DUP	553195-076	02/13/26 00:00	Soil
CG-27-0.5	553195-077	02/13/26 00:00	Soil
CG-27-2.5	553195-078	02/13/26 00:00	Soil

ENTHALPY ANALYTICAL

Sample Summary

Vanya Keyes Terraphase Engineering 18401 Von Karman Ave, Suite #410 Irvine, CA 92612	Lab Job #: Location: Date Received:	553195 Centennial High School, 2606 N Central Ave., Compton, CA 90222 02/13/26

Sample ID	Lab ID	Collected	Matrix
CG-29-0.5	553195-079	02/13/26 00:00	Soil
CG-29-2.5	553195-080	02/13/26 00:00	Soil
EB-01-260213	553195-081	02/13/26 14:15	Water

Case Narrative

Terraphase Engineering 18401 Von Karman Ave, Suite #410 Irvine, CA 92612 Vanya Keyes	Lab Job Number: 553195 Location: Centennial High School, 2606 N Central Ave., Compton, CA 90222 Date Received: 02/13/26

This data package contains sample and QC results for twenty nine soil samples, eighteen three-point soil composites, and one water sample, requested for the above referenced project on 02/13/26. The samples were received in good condition.

Pesticides (EPA 8081A) Water:
No analytical problems were encountered.

Pesticides (EPA 8081A) Soil:

- High recovery was observed for delta-BHC in the MSD for batch 395755; the parent sample was not a project sample, the LCS was within limits, the associated RPD was within limits, and this analyte was not detected at or above the RL in the associated samples.
- Lab numbers 553195-065, 553195-071, 553195-073, 553195-075, 553195-077, and 553195-079 were diluted due to the color of the sample extracts. Elevated reporting limits were due to necessary dilutions.
- The presence of target compound was confirmed but the relative percent difference (RPD) between columns exceeded 40%. Affected result was flagged with "C" qualifiers.
- No other analytical problems were encountered.

PCBs (EPA 8082) Water:
No analytical problems were encountered.

PCBs (EPA 8082) Soil:

- High surrogate recoveries were observed for decachlorobiphenyl (PCB) in AOC3-SB-27-0.5 (lab # 553195-022), AOC3-SB-28-0.5 (lab # 553195-023), and AOC3-SB-35-0.5 (lab # 553195-039); no target analytes were detected in these samples.
- Aroclor-1260 was detected above the RL in the method blank for batch 395871; this analyte was not detected in samples at or above the RL.
- Many samples were treated with sulfuric acid to reduce analytical interferences or due to the presence of color.
- AOC3-SB-21-0.5 (lab # 553195-008) was treated with a copper powder cleanup procedure to reduce analytical interferences due to the presence of sulfur.
- No other analytical problems were encountered.

Metals (EPA 6010B) Water:
No analytical problems were encountered.

Metals (EPA 6010B) Soil:

- Low recovery was observed for lead in the MSD of AOC3-SB-19-0.5 (lab # 553195-001); the LCS was within limits, and the associated RPD was within limits.
- No other analytical problems were encountered.

100.1 Asbestos (EPA 100.1 Asbestos):
AmeriSci Los Angeles in Carson, CA performed the analysis (see sublab report section for certifications). Please see the AmeriSci Los Angeles case narrative.

Asbestos by PLM (EPA 600/R-93-116):
AmeriSci Los Angeles in Carson, CA performed the analysis (see sublab report section for certifications). Please see the AmeriSci Los Angeles case narrative.

ENTHALPY ANALYTICAL

Detection Summary

Vanya Keyes
Terraphase Engineering
18401 Von Karman Ave, Suite #410
Irvine, CA 92612

Lab Job #: 553195
Location: Centennial High School, 2606 N Central Ave., Compton, CA 90222
Date Received: 02/13/26

Sample ID: AOC3-SB-19-0.5 **Lab ID: 553195-001** **Collected: 02/13/26 07:25**
Matrix: Soil

553195-001 Analyte	Result	Qual	Units	RL
Method: EPA 6010B Prep Method: EPA 3050B				
Lead	**44**		mg/Kg	0.99
Method: EPA 8082 Prep Method: EPA 3546				
Aroclor-1260	**51**		ug/Kg	50
Total PCBs	**51**		ug/Kg	50

Sample ID: AOC3-SB-18-0.5 **Lab ID: 553195-002** **Collected: 02/13/26 07:40**
Matrix: Soil

553195-002 Analyte	Result	Qual	Units	RL
Method: EPA 6010B Prep Method: EPA 3050B				
Lead	**9.8**		mg/Kg	0.99

Sample ID: AOC3-SB-17-0.5 **Lab ID: 553195-003** **Collected: 02/13/26 07:50**
Matrix: Soil

553195-003 Analyte	Result	Qual	Units	RL
Method: EPA 6010B Prep Method: EPA 3050B				
Lead	**43**		mg/Kg	0.97

Sample ID: AOC3-SB-20-0.5 **Lab ID: 553195-007** **Collected: 02/13/26 08:45**
Matrix: Soil

553195-007 Analyte	Result	Qual	Units	RL
Method: EPA 6010B Prep Method: EPA 3050B				
Lead	**17**		mg/Kg	0.95

Sample ID: AOC3-SB-21-0.5 **Lab ID: 553195-008** **Collected: 02/13/26 08:55**
Matrix: Soil

553195-008 Analyte	Result	Qual	Units	RL
Method: EPA 6010B Prep Method: EPA 3050B				
Lead	**32**		mg/Kg	0.97

Results for any subcontracted analyses are not included in this summary. Data qualifiers and additional information necessary for the interpretation of the test results are contained in the PDF file and may not be included in this summary.

ENTHALPY ANALYTICAL

Detection Summary

Sample ID: AOC3-SB-22-0.5 **Lab ID: 553195-009** **Collected: 02/13/26 09:05**
Matrix: Soil

553195-009 Analyte	Result	Qual	Units	RL
Method: EPA 6010B Prep Method: EPA 3050B				
Lead	**15**		mg/Kg	1.0

Sample ID: AOC3-SB-23-0.5 **Lab ID: 553195-013** **Collected: 02/13/26 09:15**
Matrix: Soil

553195-013 Analyte	Result	Qual	Units	RL
Method: EPA 6010B Prep Method: EPA 3050B				
Lead	**61**		mg/Kg	0.98

Sample ID: AOC3-SB-24-0.5 **Lab ID: 553195-014** **Collected: 02/13/26 09:55**
Matrix: Soil

553195-014 Analyte	Result	Qual	Units	RL
Method: EPA 6010B Prep Method: EPA 3050B				
Lead	**83**		mg/Kg	1.0
Method: EPA 8082 Prep Method: EPA 3546				
Aroclor-1254	**100**		ug/Kg	51
Aroclor-1260	**150**		ug/Kg	51
Total PCBs	**250**		ug/Kg	51

Sample ID: AOC3-SB-25-0.5 **Lab ID: 553195-015** **Collected: 02/13/26 09:45**
Matrix: Soil

553195-015 Analyte	Result	Qual	Units	RL
Method: EPA 6010B Prep Method: EPA 3050B				
Lead	**25**		mg/Kg	0.99

Sample ID: DUP-01-0.5-260213 **Lab ID: 553195-019** **Collected: 02/13/26**
Matrix: Soil

553195-019 Analyte	Result	Qual	Units	RL
Method: EPA 6010B Prep Method: EPA 3050B				
Lead	**19**		mg/Kg	0.99

Results for any subcontracted analyses are not included in this summary. Data qualifiers and additional information necessary for the interpretation of the test results are contained in the PDF file and may not be included in this summary.

ENTHALPY ANALYTICAL

Detection Summary

Sample ID: AOC3-SB-26-0.5 **Lab ID: 553195-021** **Collected: 02/13/26 08:20**
Matrix: Soil

553195-021 Analyte	Result	Qual	Units	RL
Method: EPA 6010B Prep Method: EPA 3050B				
Lead	**11**		mg/Kg	0.98

Sample ID: AOC3-SB-27-0.5 **Lab ID: 553195-022** **Collected: 02/13/26 08:10**
Matrix: Soil

553195-022 Analyte	Result	Qual	Units	RL
Method: EPA 6010B Prep Method: EPA 3050B				
Lead	**10**		mg/Kg	0.99

Sample ID: AOC3-SB-28-0.5 **Lab ID: 553195-023** **Collected: 02/13/26 08:00**
Matrix: Soil

553195-023 Analyte	Result	Qual	Units	RL
Method: EPA 6010B Prep Method: EPA 3050B				
Lead	**4.2**		mg/Kg	0.98

Sample ID: AOC3-SB-29-0.5 **Lab ID: 553195-027** **Collected: 02/13/26 11:50**
Matrix: Soil

553195-027 Analyte	Result	Qual	Units	RL
Method: EPA 6010B Prep Method: EPA 3050B				
Lead	**35**		mg/Kg	0.99
Method: EPA 8082 Prep Method: EPA 3546				
Aroclor-1254	**89**		ug/Kg	51
Aroclor-1260	**51**		ug/Kg	51
Total PCBs	**140**		ug/Kg	51

Sample ID: AOC3-SB-30-0.5 **Lab ID: 553195-028** **Collected: 02/13/26 11:35**
Matrix: Soil

553195-028 Analyte	Result	Qual	Units	RL
Method: EPA 6010B Prep Method: EPA 3050B				
Lead	**12**		mg/Kg	0.97

Results for any subcontracted analyses are not included in this summary. Data qualifiers and additional information necessary for the interpretation of the test results are contained in the PDF file and may not be included in this summary.

ENTHALPY ANALYTICAL

Detection Summary

Sample ID: AOC3-SB-31-0.5 **Lab ID: 553195-029** **Collected: 02/13/26 11:25**
Matrix: Soil

553195-029 Analyte	Result	Qual	Units	RL
Method: EPA 6010B Prep Method: EPA 3050B				
Lead	**64**		mg/Kg	0.95

Sample ID: AOC3-SB-32-0.5 **Lab ID: 553195-033** **Collected: 02/13/26 10:45**
Matrix: Soil

553195-033 Analyte	Result	Qual	Units	RL
Method: EPA 6010B Prep Method: EPA 3050B				
Lead	**37**		mg/Kg	0.96

Sample ID: AOC3-SB-33-0.5 **Lab ID: 553195-034** **Collected: 02/13/26 10:35**
Matrix: Soil

553195-034 Analyte	Result	Qual	Units	RL
Method: EPA 6010B Prep Method: EPA 3050B				
Lead	**29**		mg/Kg	1.0

Sample ID: AOC3-SB-34-0.5 **Lab ID: 553195-035** **Collected: 02/13/26 10:15**
Matrix: Soil

553195-035 Analyte	Result	Qual	Units	RL
Method: EPA 6010B Prep Method: EPA 3050B				
Lead	**31**		mg/Kg	0.99
Method: EPA 8082 Prep Method: EPA 3546				
Aroclor-1254	**110**		ug/Kg	51
Total PCBs	**110**		ug/Kg	51

Sample ID: AOC3-SB-35-0.5 **Lab ID: 553195-039** **Collected: 02/13/26 13:20**
Matrix: Soil

553195-039 Analyte	Result	Qual	Units	RL
Method: EPA 6010B Prep Method: EPA 3050B				
Lead	**23**		mg/Kg	0.96

Results for any subcontracted analyses are not included in this summary. Data qualifiers and additional information necessary for the interpretation of the test results are contained in the PDF file and may not be included in this summary.

ENTHALPY ANALYTICAL

Detection Summary

Sample ID: AOC3-SB-36-0.5 **Lab ID: 553195-040** **Collected: 02/13/26 13:10**
Matrix: Soil

553195-040 Analyte	Result	Qual	Units	RL
Method: EPA 6010B Prep Method: EPA 3050B				
Lead	**42**		mg/Kg	1.0

Sample ID: AOC3-SB-37-0.5 **Lab ID: 553195-041** **Collected: 02/13/26 13:00**
Matrix: Soil

553195-041 Analyte	Result	Qual	Units	RL
Method: EPA 6010B Prep Method: EPA 3050B				
Lead	**49**		mg/Kg	0.96

Sample ID: DUP-02-0.5-260213 **Lab ID: 553195-045** **Collected: 02/13/26**
Matrix: Soil

553195-045 Analyte	Result	Qual	Units	RL
Method: EPA 6010B Prep Method: EPA 3050B				
Lead	**35**		mg/Kg	1.0

Sample ID: AOC3-SB-38-0.5 **Lab ID: 553195-047** **Collected: 02/13/26 12:20**
Matrix: Soil

553195-047 Analyte	Result	Qual	Units	RL
Method: EPA 6010B Prep Method: EPA 3050B				
Lead	**34**		mg/Kg	0.97

Sample ID: AOC3-SB-39-0.5 **Lab ID: 553195-048** **Collected: 02/13/26 12:10**
Matrix: Soil

553195-048 Analyte	Result	Qual	Units	RL
Method: EPA 6010B Prep Method: EPA 3050B				
Lead	**41**		mg/Kg	0.95

Sample ID: AOC3-SB-40-0.5 **Lab ID: 553195-049** **Collected: 02/13/26 12:00**
Matrix: Soil

553195-049 Analyte	Result	Qual	Units	RL
Method: EPA 6010B Prep Method: EPA 3050B				
Lead	**80**		mg/Kg	0.96

Results for any subcontracted analyses are not included in this summary. Data qualifiers and additional information necessary for the interpretation of the test results are contained in the PDF file and may not be included in this summary.

ENTHALPY ANALYTICAL

Detection Summary

Sample ID: AOC3-SB-46-0.5 **Lab ID: 553195-053** **Collected: 02/13/26 13:30**
Matrix: Soil

553195-053 Analyte	Result	Qual	Units	RL
Method: EPA 6010B Prep Method: EPA 3050B				
Lead	**50**		mg/Kg	0.95
Method: EPA 8082 Prep Method: EPA 3546				
Aroclor-1254	**54**		ug/Kg	50
Total PCBs	**54**		ug/Kg	50

Sample ID: AOC3-SB-45-0.5 **Lab ID: 553195-054** **Collected: 02/13/26 13:40**
Matrix: Soil

553195-054 Analyte	Result	Qual	Units	RL
Method: EPA 6010B Prep Method: EPA 3050B				
Lead	**45**		mg/Kg	0.99

Sample ID: AOC3-SB-44-0.5 **Lab ID: 553195-055** **Collected: 02/13/26 13:50**
Matrix: Soil

553195-055 Analyte	Result	Qual	Units	RL
Method: EPA 6010B Prep Method: EPA 3050B				
Lead	**280**		mg/Kg	1.0

Sample ID: CG-20-0.5 **Lab ID: 553195-059** **Collected: 02/13/26**
Matrix: Soil

553195-059 Analyte	Result	Qual	Units	RL
Method: EPA 8081A Prep Method: EPA 3546				
4,4'-DDE	**6.2**		ug/Kg	5.0
4,4'-DDT	**10**		ug/Kg	5.0

Sample ID: CG-20-2.5 **Lab ID: 553195-060** **Collected: 02/13/26**

No Detections

Sample ID: CG-21-0.5 **Lab ID: 553195-061** **Collected: 02/13/26**
Matrix: Soil

553195-061 Analyte	Result	Qual	Units	RL
Method: EPA 8081A Prep Method: EPA 3546				
4,4'-DDE	**6.5**		ug/Kg	5.0
4,4'-DDT	**5.4**		ug/Kg	5.0

Results for any subcontracted analyses are not included in this summary. Data qualifiers and additional information necessary for the interpretation of the test results are contained in the PDF file and may not be included in this summary.

ENTHALPY ANALYTICAL

Detection Summary

Sample ID: CG-21-2.5	Lab ID: 553195-062	Collected: 02/13/26

No Detections

Sample ID: CG-22-0.5	Lab ID: 553195-063	Collected: 02/13/26
	Matrix: Soil	

553195-063 Analyte	Result	Qual	Units	RL
Method: EPA 8081A Prep Method: EPA 3546				
4,4'-DDT	**13**	C	ug/Kg	5.0

Sample ID: CG-22-2.5	Lab ID: 553195-064	Collected: 02/13/26

No Detections

Sample ID: CG-22-0.5-DUP	Lab ID: 553195-065	Collected: 02/13/26

No Detections

Sample ID: CG-22-2.5-DUP	Lab ID: 553195-066	Collected: 02/13/26

No Detections

Sample ID: CG-23-0.5	Lab ID: 553195-067	Collected: 02/13/26

No Detections

Sample ID: CG-23-2.5	Lab ID: 553195-068	Collected: 02/13/26

No Detections

Sample ID: CG-24-0.5	Lab ID: 553195-069	Collected: 02/13/26
	Matrix: Soil	

553195-069 Analyte	Result	Qual	Units	RL
Method: EPA 8081A Prep Method: EPA 3546				
4,4'-DDT	**10**		ug/Kg	4.9

Sample ID: CG-24-2.5	Lab ID: 553195-070	Collected: 02/13/26

No Detections

Sample ID: CG-25-0.5	Lab ID: 553195-071	Collected: 02/13/26

No Detections

Results for any subcontracted analyses are not included in this summary. Data qualifiers and additional information necessary for the interpretation of the test results are contained in the PDF file and may not be included in this summary.

ENTHALPY ANALYTICAL

Detection Summary

Sample ID: CG-25-2.5	Lab ID: 553195-072	Collected: 02/13/26

No Detections

Sample ID: CG-26-0.5	Lab ID: 553195-073	Collected: 02/13/26

No Detections

Sample ID: CG-26-2.5	Lab ID: 553195-074	Collected: 02/13/26

No Detections

Sample ID: CG-26-0.5-DUP	Lab ID: 553195-075	Collected: 02/13/26

No Detections

Sample ID: CG-26-2.5-DUP	Lab ID: 553195-076	Collected: 02/13/26

No Detections

Sample ID: CG-27-0.5	Lab ID: 553195-077	Collected: 02/13/26

No Detections

Sample ID: CG-27-2.5	Lab ID: 553195-078	Collected: 02/13/26

No Detections

Sample ID: CG-29-0.5	Lab ID: 553195-079	Collected: 02/13/26
	Matrix: Soil	

553195-079 Analyte		Result	Qual	Units	RL
Method: EPA 8081A Prep Method: EPA 3546					
	4,4'-DDT	**12**		ug/Kg	10

Sample ID: CG-29-2.5	Lab ID: 553195-080	Collected: 02/13/26
	Matrix: Soil	

553195-080 Analyte		Result	Qual	Units	RL
Method: EPA 8081A Prep Method: EPA 3546					
	4,4'-DDE	**8.1**		ug/Kg	5.1

Sample ID: EB-01-260213	Lab ID: 553195-081	Collected: 02/13/26 14:15

No Detections

Results for any subcontracted analyses are not included in this summary. Data qualifiers and additional information necessary for the interpretation of the test results are contained in the PDF file and may not be included in this summary.

Detection Summary

C Presence confirmed, but RPD between columns exceeds 40%

Results for any subcontracted analyses are not included in this summary. Data qualifiers and additional information necessary for the interpretation of the test results are contained in the PDF file and may not be included in this summary.

Login 553195

E

931 W. Barkley Avenue, Orange, CA 92868

Phone 714-771-6900

ALPY ICAL

Chain of Custody Record

Lab No: 553195

Page: 1 of 12

Turn Around Time (rush by advanced notice only)

Standard:	X	5 Day:		3 Day:	
2 Day:		1 Day:		Custom TAT:	

Matrix: A = Air, S = Soil/Solid, W = Water, DW = Drinking Water, P = Product, O = Oil, SD = Sediment, T = Tissue, WP = Wipe, WW = Wastewater, X = Other

Sample Type: C = Composite, G = Grab or Discrete, B = Blank, O = Other

Preservatives: 0 = none, 1 = $Na_2S_2O_3$, 2 = HCl, 3 = HNO_3, 4 = H_2SO_4, 5 = NaOH, 6 = Other

Sample Receipt Temp and Notes: (lab use only)

CUSTOMER INFORMATION

Company:	Terraphase Engineering
Report To:	Vanya Keyes
Email:	vanya.keyes@terraphase.com
Address:	18401 Von Karman Ave,
	Irvine, CA
Phone:	949-377-2227
Fax:	

PROJECT INFORMATION

Name:	Centennial High School
Number:	
P.O. #:	~~1820 Rimpau Ave~~ MG, ~~Corona, CA 92881~~ MG, 2606 N Central Ave, Compton, CA 90222
Address:	
Global ID:	
Sampled By:	Madison Garcia

	Sample ID	Sampling Date	Sampling Time (24 hr)	Matrix	Sample Type	Pres.	Cont. No.	Cont. Size	Initials	Arsenic by USEPA 6020	Lead by USEPA 6010B	PCBs by USEPA 8082	Title 22 Metals by USEPA 6020/7471A	Dioxins & Furans by UESPA 8290A	VOCs by USEPA 8260B	TPH by USEPA 8015	
1	AOC3-SB-19-0.5	2/13/26	0725	S	G	0	1	8oz	MG		X	X					
2	AOC3-SB-18-0.5		0740								X	X					
3	AOC3-SB-17-0.5		0750								X	X					
4	AOC3-SB-19-2.5		0730														
5	AOC3-SB-18-2.5		0745														
6	AOC3-SB-17-2.5	2/13/26	0755	S	G	0	1	8oz	MG								
7																	
8																	
9																	
10																	

Test Instructions / Comments

Please also send report to clare.steedman@terraphase.com, madison.garcia@terraphase.com

} composite to CG-20-0.5

} composite to CG-20-2.5

5-0 | 5.4

5.8 | 6.2 | ~~11~~ -15

	Signature	Print Name	Company / Title	Date / Time
1 Relinquished By:		Madison Garcia	TEJ / Eng	2/13/26 1500
1 Received By:		GEMA O.	EANH	2-13-26 15:00
2 Relinquished By:		GEMA O	EANH	2-13-26 16:35
2 Received By:		D. Saucedo	EA	2/13/26 1645
3 Relinquished By:		D. Saucedo	EA	2/13/26 1735
3 Received By:		Adam Dinkmeyer	EA	2/13/26 1735

ENTHALPY ANALYTICAL

Chain of Custody Record

Lab No: 553195

Page: 2 of 12

Turn Around Time (rush by advanced notice only)

Standard:	X	5 Day:		3 Day:	
2 Day:		1 Day:		Custom TAT:	

Enthalpy Analytical - Orange

931 W. Barkley Avenue, Orange, CA 92868

Phone 714-771-6900

Matrix: A = Air, S = Soil/Solid, W = Water, DW = Drinking Water, P = Product, O = Oil, SD = Sediment, T = Tissue, WP = Wipe, WW = Wastewater, X = Other

Sample Type: C = Composite, G = Grab or Discrete, B = Blank, O = Other

Preservatives: 0 = none, 1 = $Na_2S_2O_3$, 2 = HCl, 3 = HNO_3, 4 = H_2SO_4, 5 = NaOH, 6 = Other

Sample Receipt Temp and Notes: (lab use only)

CUSTOMER INFORMATION		PROJECT INFORMATION	
Company:	Terraphase Engineering	Name:	Centennial High School
Report To:	Vanya Keyes	Number:	~~1820 Rimpau Ave~~ MG
Email:	vanya.keyes@terraphase.com	P.O. #:	~~Corona, CA 92881~~ MG
Address:	18401 Von Karman Ave,	Address:	2606 N Central Ave, Compton CA 90222
	Irvine, CA		
Phone:	949-377-2227	Global ID:	
Fax:		Sampled By:	Madison Garcia

	Sample ID	Sampling Date	Sampling Time (24 hr)	Matrix	Sample Type	Pres.	Cont. No.	Cont. Size	Initials	Arsenic by USEPA 6020	Lead by USEPA 6010B	PCBs by USEPA 8082	Title 22 Metals by USEPA 6020/7471A	Dioxins & Furans by UESPA 8290A	VOCs by USEPA 8260B	TPH by USEPA 8015		Test Instructions / Comments
1	AOC3-SB-20-0.5	2/13/26	0845	S	G	O	1	8oz	MG		X	X						composite to CG-21-0.5
2	AOC3-SB-21-0.5		0855								X	X						
3	AOC3-SB-22-0.5		0905								X	X						
4	AOC3-SB-20-2.5		0850															composite to CG-21-2.5
5	AOC3-SB-21-2.5		0900															
6	AOC3-SB-22-2.5	2/13/26	0910	S	G	O	1	8oz	MG									
7																		
8																		
9																		
10																		

Analysis Request

Test Instructions / Comments: Please also send report to clare.steedman@terraphase.com, madison.garcia@terraphase.com

	Signature	Print Name	Company / Title	Date / Time
[1] Relinquished By:		Madison Garcia	TEI / Eng	2/13/26 1500
[1] Received By:		GEMA O.	EAMH	2-13-26 15:00
[2] Relinquished By:		GEMA O.	EAWH	2-13-26 16:35
[2] Received By:		D. Saucedo	EA	2/13/26 1644
[3] Relinquished By:		D. Saucedo	EA	2/13/26 1735
[3] Received By:		Adam Dirksmeyer	EA	2/13/26 1735

ENTHALPY ANALYTICAL

Chain of Custody Record

Lab No: 553195

Page: 3 of 12

Turn Around Time (rush by advanced notice only)

Standard:	X	5 Day:		3 Day:	
2 Day:		1 Day:		Custom TAT:	

Enthalpy Analytical - Orange
931 W. Barkley Avenue, Orange, CA 92868
Phone 714-771-6900

Matrix: **A** = Air **S** = Soil/Solid **W** = Water **DW** = Drinking Water **P** = Product **O** = Oil **SD** = Sediment **T** = Tissue **WP** = Wipe **WW** = Wastewater **X** = Other

Sample Type: **C** = Composite **G** = Grab or Discrete **B** = Blank **O** = Other

Preservatives: **0** = none **1** = $Na_2S_2O_3$ **2** = HCl **3** = HNO_3 **4** = H_2SO_4 **5** = NaOH **6** = Other

Sample Receipt Temp and Notes: (lab use only)

CUSTOMER INFORMATION		PROJECT INFORMATION	
Company:	Terraphase Engineering	Name:	Centennial High School
Report To:	Vanya Keyes	Number:	
Email:	vanya.keyes@terraphase.com	P.O. #:	
Address:	18401 Von Karman Ave,	Address:	~~1820 Rimpau Ave~~ MG ~~Corona, CA 92881~~ MG 2606 N Central Ave, Compton, CA 90222
	Irvine, CA		
Phone:	949-377-2227	Global ID:	
Fax:		Sampled By:	Madison Garcia

	Sample ID	Sampling Date	Sampling Time (24 hr)	Matrix	Sample Type	Pres.	Cont. No.	Cont. Size	Initials	Arsenic by USEPA 6020	Lead by USEPA 6010B	PCBs by USEPA 8082	Title 22 Metals by USEPA 6020/7471A	Dioxins & Furans by UESPA 8290A	VOCs by USEPA 8260B	TPH by USEPA 8015	Test Instructions / Comments
1	AOC3-SB-23-0.5	2/13/26	0915	S	G	O	2	802	MG		X	X					composite to CG-22-0.5
2	AOC3-SB-24-0.5		0955								X	X					
3	AOC3-SB-25-0.5		0945								X	X					
4	AOC3-SB-23-2.5		0920														composite to CG-22-2.5
5	AOC3-SB-24-2.5		1000				↓	↓									
6	AOC3-SB-25-2.5		0950				2	802									
7	DUP-01-0.5-260213	↓	—	↓	↓	↓	1	802	↓		X	X					
8	DUP-01-2.5-260213	2/13/26	—	S	G	O	1	802	MG								
9																	
10																	

Please also send report to clare.steedman@terraphase.com, madison.garcia@terraphase.com

	Signature	Print Name	Company / Title	Date / Time
1 Relinquished By:		Madison Garcia	TEI / Eng	2/13/26 1900
1 Received By:		Gema O.	EANH	2-13-26 15:00
2 Relinquished By:		GEMA O.	EANH	2-13-26 16:35
2 Received By:		D. Sanchez	EA	2/13/26 1644
3 Relinquished By:		D. Sanchez	EA	2/13/26 1735
3 Received By:		Adam Dinkmeyer	EA	2/13/26 1735

ENTHALPY ANALYTICAL

Chain of Custody Record

Lab No: 553195

Page: 4 of 12

Turn Around Time (rush by advanced notice only)

Standard:	X	5 Day:		3 Day:	
2 Day:		1 Day:		Custom TAT:	

Enthalpy Analytical - Orange

931 W. Barkley Avenue, Orange, CA 92868

Phone 714-771-6900

Matrix: A = Air, S = Soil/Solid, W = Water, DW = Drinking Water, P = Product, O = Oil, SD = Sediment, T = Tissue, WP = Wipe, WW = Wastewater, X = Other

Sample Type: C = Composite, G = Grab or Discrete, B = Blank, O = Other

Preservatives: 0 = none, 1 = $Na_2S_2O_3$, 2 = HCl, 3 = HNO_3, 4 = H_2SO_4, 5 = NaOH, 6 = Other

Sample Receipt Temp and Notes: (lab use only)

CUSTOMER INFORMATION		PROJECT INFORMATION	
Company:	Terraphase Engineering	Name:	Centennial High School
Report To:	Vanya Keyes	Number:	~~1820 Rimpau Ave~~ MG
Email:	vanya.keyes@terraphase.com	P.O. #:	~~Corona, CA 92881~~ MG
Address:	18401 Von Karman Ave,	Address:	2600 N Central Ave, Compton, CA 90222
	Irvine, CA		
Phone:	949-377-2227	Global ID:	
Fax:		Sampled By:	Madison Garcia

	Sample ID	Sampling Date	Sampling Time (24 hr)	Matrix	Sample Type	Pres.	Cont. No.	Cont. Size	Initials	Arsenic by USEPA 6020	Lead by USEPA 6010B	PCBs by USEPA 8082	Title 22 Metals by USEPA 6020/7471A	Dioxins & Furans by UESPA 8290A	VOCs by USEPA 8260B	TPH by USEPA 8015	Test Instructions / Comments
1	AOC3-SB-26-0.5	2/13/26	0820	S	G	O	1	8oz	MG		X	X					Composite to CG-23-0.5
2	AOC3-SB-27-0.5		0810								X	X					
3	AOC3-SB-28-0.5		0800								X	X					
4	AOC3-SB-26-2.5		0825														Composite to CG-23-2.5
5	AOC3-SB-27-2.5		0815														
6	AOC3-SB-28-2.5	2/13/26	0805	S	G	O	1	8oz	MG								
7																	
8																	
9																	
10																	

Please also send report to clare.steedman@terraphase.com, madison.garcia@terraphase.com

	Signature	Print Name	Company / Title	Date / Time
[1] Relinquished By:		Madison Garcia	TEI / Eng	2/13/26 1500
[1] Received By:		GEMA O.	EANM	2-13-26 15:00
[2] Relinquished By:		GEMA O	EANM	2-13-26 16:35
[2] Received By:		D. Sanchez	EA	2/13/26 1635
[3] Relinquished By:		D. Sanchez	EA	2/13/26 1735
[3] Received By:		Adam Dickmeyer	EA	2/13/26 1735

ENTHALPY ANALYTICAL

Chain of Custody Record

Lab No: 553195

Page: 5 of 12

Turn Around Time (rush by advanced notice only)

Standard:	X	5 Day:		3 Day:	
2 Day:		1 Day:		Custom TAT:	

Enthalpy Analytical - Orange
931 W. Barkley Avenue, Orange, CA 92868
Phone 714-771-6900

Matrix: A = Air, S = Soil/Solid, W = Water, DW = Drinking Water, P = Product, O = Oil, SD = Sediment, T = Tissue, WP = Wipe, WW = Wastewater, X = Other

Sample Type: C = Composite, G = Grab or Discrete, B = Blank, O = Other

Preservatives: 0 = none, 1 = $Na_2S_2O_3$, 2 = HCl, 3 = HNO_3, 4 = H_2SO_4, 5 = NaOH, 6 = Other

Sample Receipt Temp and Notes: (lab use only)

CUSTOMER INFORMATION		PROJECT INFORMATION	
Company:	Terraphase Engineering	Name:	Centennial High School
Report To:	Vanya Keyes	Number:	
Email:	vanya.keyes@terraphase.com	P.O. #:	
Address:	18401 Von Karman Ave,	Address:	~~1820 Rimpau Ave~~ MG ~~Corona, CA 92881~~ MG 2606 N Central Ave, Compton, CA 90222
	Irvine, CA		
Phone:	949-377-2227	Global ID:	
Fax:		Sampled By:	Madison Garcia

	Sample ID	Sampling Date	Sampling Time (24 hr)	Matrix	Sample Type	Pres.	Cont. No.	Cont. Size	Initials	Arsenic by USEPA 6020	Lead by USEPA 6010B	PCBs by USEPA 8082	Title 22 Metals by USEPA 6020/7471A	Dioxins & Furans by UESPA 8290A	VOCs by USEPA 8260B	TPH by USEPA 8015	Test Instructions / Comments
1	AOC3-SB-29-0.5	2/13/26	1150	S	G	0	1	8oz	MG		X	X					composite to CG-24-0.5
2	AOC3-SB-30-0.5		1135								X	X					
3	AOC3-SB-31-0.5		1125								X	X					
4	AOC3-SB-29-2.5		1155														composite to CG-24-2.5
5	AOC3-SB-30-~~2~~2.5		1140														
6	AOC3-SB-31-2.5	2/13/26	1130	S	G	0	1	8oz	MG								
7																	
8																	
9																	
10																	

Please also send report to clare.steedman@terraphase.com, madison.garcia@terraphase.com

	Signature	Print Name	Company / Title	Date / Time
[1] Relinquished By:		Madison Garcia	TEJ / Eng	2/13/26 1500
[1] Received By:		ITEMA O.	EANH	2-13-26 1500
[2] Relinquished By:		ITEMA O	EANH	2-13-26 1630
[2] Received By:		D Sanchez	EA	2/13/26 1645
[3] Relinquished By:		D. Sanchez	EA	2/13/26 1735
[3] Received By:		Adam Dinkmeyer	EA	2/13/26 1735

ENTHALPY ANALYTICAL

Chain of Custody Record

Lab No: 553195

Page: 6 of 12

Turn Around Time (rush by advanced notice only)

Standard:	X	5 Day:		3 Day:	
2 Day:		1 Day:		Custom TAT:	

Enthalpy Analytical - Orange

931 W. Barkley Avenue, Orange, CA 92868

Phone 714-771-6900

Matrix: **A** = Air **S** = Soil/Solid **W** = Water **DW** = Drinking Water **P** = Product **O** = Oil **SD** = Sediment **T** = Tissue **WP** = Wipe **WW** = Wastewater **X** = Other

Sample Type: **C** = Composite **G** = Grab or Discrete **B** = Blank **O** = Other

Preservatives: **0** = none **1** = $Na_2S_2O_3$ **2** = HCl **3** = HNO_3 **4** = H_2SO_4 **5** = NaOH **6** = Other

Sample Receipt Temp and Notes: (lab use only)

CUSTOMER INFORMATION		PROJECT INFORMATION	
Company:	Terraphase Engineering	Name:	Centennial High School
Report To:	Vanya Keyes	Number:	~~1820 Rimpau Ave~~ MG
Email:	vanya.keyes@terraphase.com	P.O. #:	~~Corona, CA 92881~~ MG
Address:	18401 Von Karman Ave,	Address:	2606 N Central Ave, Compton CA 90222
	Irvine, CA		
Phone:	949-377-2227	Global ID:	
Fax:		Sampled By:	Madison Garcia

	Sample ID	Sampling Date	Sampling Time (24 hr)	Matrix	Sample Type	Pres.	Cont. No.	Cont. Size	Initials	Arsenic by USEPA 6020	Lead by USEPA 6010B	PCBs by USEPA 8082	Title 22 Metals by USEPA 6020/7471A	Dioxins & Furans by UESPA 8290A	VOCs by USEPA 8260B	TPH by USEPA 8015	Test Instructions / Comments
1	AOC3-SB-32-0.5	2/13/26	1045	S	G	O	1	8oz	MG		X	X					Please also send report to clare.steedman@terraphase.com, madison.garcia@terraphase.com; composite to CO1-25-0.5
2	AOC3-SB-33-0.5		1035								X	X					
3	AOC3-SB-34-0.5		1015								X	X					
4	AOC3-SB-32-2.5		1050														composite to CO1-25-2.5
5	AOC3-SB-33-2.5		1040														
6	AOC3-SB-34-2.5	2/13/26	1020	S	G	O	1	8oz	MG								
7																	
8																	
9																	
10																	

	Signature	Print Name	Company / Title	Date / Time
[1] Relinquished By:		Madison Garcia	TEI / Eng	2/13/26 1500
[1] Received By:		GEMA O.	EANH	2-13-26 15:00
[2] Relinquished By:		GEMA O.	EANH	2-13-26 16:30
[2] Received By:		D. Sanchez	EA	2/13/26 1645
[3] Relinquished By:		D. Sanchez	EA	2/13/26 1735
[3] Received By:		Adam Dijkmeyer	EA	2/13/26 1735

ENTHALPY ANALYTICAL

Chain of Custody Record

Lab No: 553195

Page: 7 of 12

Turn Around Time (rush by advanced notice only)

Standard:	X	5 Day:		3 Day:	
2 Day:		1 Day:		Custom TAT:	

Enthalpy Analytical - Orange
931 W. Barkley Avenue, Orange, CA 92868
Phone 714-771-6900

Matrix: A = Air, S = Soil/Solid, W = Water, DW = Drinking Water, P = Product, O = Oil, SD = Sediment, T = Tissue, WP = Wipe, WW = Wastewater, X = Other

Sample Type: C = Composite, G = Grab or Discrete, B = Blank, O = Other

Preservatives: 0 = none, 1 = $Na_2S_2O_3$, 2 = HCl, 3 = HNO_3, 4 = H_2SO_4, 5 = NaOH, 6 = Other

Sample Receipt Temp and Notes: (lab use only)

CUSTOMER INFORMATION

Company:	Terraphase Engineering
Report To:	Vanya Keyes
Email:	vanya.keyes@terraphase.com
Address:	18401 Von Karman Ave,
	Irvine, CA
Phone:	949-377-2227
Fax:	

PROJECT INFORMATION

Name:	Centennial High School
Number:	
P.O. #:	
Address:	~~1820 Rimpau Ave~~ MG Corona, ~~CA 92881~~ MG 2606 N Central Ave Compton CA 90222
Global ID:	
Sampled By:	Madison Garcia

Analysis Request

Sample ID	Sampling Date	Sampling Time (24 hr)	Matrix	Sample Type	Pres.	Cont. No.	Cont. Size	Initials	Arsenic by USEPA 6020	Lead by USEPA 6010B	PCBs by USEPA 8082	Title 22 Metals by USEPA 6020/7471A	Dioxins & Furans by UESPA 8290A	VOCs by USEPA 8260B	TPH by USEPA 8015	Test Instructions / Comments
1 AOC3-SB-35-0.5	2/13/26	1320	S	G	0	2	8oz	MG		X	X					Please also send report to clare.steedman@terraphase.com, madison.garcia@terraphase.com
2 AOC3-SB-36-0.5		1310								X	X					composite CG-26-0.5
3 AOC3-SB-37-0.5		1300								X	X					
4 AOC3-SB-35-2.5		1325														composite CG-26-2.5
5 AOC3-SB-36-2.5		1315														
6 AOC3-SB-37-2.5		1305				2	8oz									
7 DUP-02-0.5-260213	↓	—	↓	↓	↓	1	8oz	↓		X	X					
8 DUP-02-2.5-260213	2/13/26	—	S	G	0	1	8oz	MG								
9																
10																

	Signature	Print Name	Company / Title	Date / Time
1 Relinquished By:		Madison Garcia	TEI / Eng	2/13/26 / 1500
1 Received By:		[illegible]	EANH	2-13-26 1500
2 Relinquished By:		[illegible]	EANH	2-13-26 1630
2 Received By:		D Sanchez	EA	2/13/26 1644
3 Relinquished By:		D Sanchez	EA	2/13/26 1735
3 Received By:		Adam Dishmaya	EA	2/13/26 1735

ENTHALPY ANALYTICAL

Chain of Custody Record

Lab No: 553195

Page: 8 of 12

Turn Around Time (rush by advanced notice only)

Standard:	X	5 Day:		3 Day:	
2 Day:		1 Day:		Custom TAT:	

Enthalpy Analytical - Orange
931 W. Barkley Avenue, Orange, CA 92868
Phone 714-771-6900

Matrix: A = Air, S = Soil/Solid, W = Water, DW = Drinking Water, P = Product, O = Oil, SD = Sediment, T = Tissue, WP = Wipe, WW = Wastewater, X = Other

Sample Type: C = Composite, G = Grab or Discrete, B = Blank, O = Other

Preservatives: 0 = none, 1 = $Na_2S_2O_3$, 2 = HCl, 3 = HNO_3, 4 = H_2SO_4, 5 = NaOH, 6 = Other

Sample Receipt Temp and Notes: (lab use only)

CUSTOMER INFORMATION		PROJECT INFORMATION	
Company:	Terraphase Engineering	Name:	Centennial High School
Report To:	Vanya Keyes	Number:	
Email:	vanya.keyes@terraphase.com	P.O. #:	
Address:	18401 Von Karman Ave,	Address:	~~1820 Rimpau Ave~~ MG ~~Corona, CA 92881~~ MG 2606 N Central Ave, Compton, CA
	Irvine, CA		
Phone:	949-377-2227	Global ID:	
Fax:		Sampled By:	Madison Garcia

	Sample ID	Sampling Date	Sampling Time (24 hr)	Matrix	Sample Type	Pres.	Cont. No.	Cont. Size	Initials	Arsenic by USEPA 6020	Lead by USEPA 6010B	PCBs by USEPA 8082	Title 22 Metals by USEPA 6020/7471A	Dioxins & Furans by UESPA 8290A	VOCs by USEPA 8260B	TPH by USEPA 8015		Test Instructions / Comments
1	AOC3-SB-38-0.5	2/13/26	1220	S	G	O	1	8oz	MG		X	X						Please also send report to clare.steedman@terraphase.com, madison.garcia@terraphase.com; composite CG-27-0.5
2	AOC3-SB-39-0.5		1210								X	X						
3	AOC3-SB-40-0.5		1200								X	X						
4	AOC3-SB-38-2.5		1225															composite CG-27-2.5
5	AOC3-SB-39-2.5		1215															
6	AOC3-SB-40-2.5	2/13/26	1205	S	G	O	1	8oz	MG									
7																		
8																		
9																		
10																		

	Signature	Print Name	Company / Title	Date / Time
[1] Relinquished By:		Madison Garcia	TF / Engr	2/13/26 1500
[1] Received By:		GEMA O.	EANH	2-13-26 1500
[2] Relinquished By:		GEMA O.	EANH	2/13/26 16:30
[2] Received By:		D. Sanchez	EA	2/13/26 1645
[3] Relinquished By:		D. Sanchez	EA	2/13/26 1735
[3] Received By:		Adam Dickmeyer	EA	2/13/26 1735

ENTHALPY ANALYTICAL

Chain of Custody Record

Lab No: 553195

Page: 9 of 12

Turn Around Time (rush by advanced notice only)

Standard:	X	5 Day:		3 Day:	
2 Day:		1 Day:		Custom TAT:	

Enthalpy Analytical - Orange
931 W. Barkley Avenue, Orange, CA 92868
Phone 714-771-6900

Matrix: A = Air, S = Soil/Solid, W = Water, DW = Drinking Water, P = Product, O = Oil, SD = Sediment, T = Tissue, WP = Wipe, WW = Wastewater, X = Other

Sample Type: C = Composite, G = Grab or Discrete, B = Blank, O = Other

Preservatives: 0 = none, 1 = $Na_2S_2O_3$, 2 = HCl, 3 = HNO_3, 4 = H_2SO_4, 5 = NaOH, 6 = Other

Sample Receipt Temp and Notes: (lab use only)

CUSTOMER INFORMATION

Company:	Terraphase Engineering
Report To:	Vanya Keyes
Email:	vanya.keyes@terraphase.com
Address:	18401 Von Karman Ave,
	Irvine, CA
Phone:	949-377-2227
Fax:	

PROJECT INFORMATION

Name:	Centennial High School
Number:	~~1820 Rimpau Ave~~ MG
P.O. #:	~~Corona, CA 92881~~ MG
Address:	2600 N Central Ave, Compton, CA 90222
Global ID:	
Sampled By:	Madison Garcia

Test Instructions / Comments: Please also send report to clare.steedman@terraphase.com, madison.garcia@terraphase.com

	Sample ID	Sampling Date	Sampling Time (24 hr)	Matrix	Sample Type	Pres.	Cont. No.	Cont. Size	Initials	Arsenic by USEPA 6020	Lead by USEPA 6010B	PCBs by USEPA 8082	Title 22 Metals by USEPA 6020/7471A	Dioxins & Furans by UESPA 8290A	VOCs by USEPA 8260B	TPH by USEPA 8015		Test Instructions / Comments
1	AOC3-SB-46-0.5	2/13/26	1330	S	G	O	1	8oz	MG		X	X						composite to CG-29-0.5
2	AOC3-SB-45-0.5		1340								X	X						
3	AOC3-SB-44-0.5		1350								X	X						
4	AOC3-SB-46-2.5		1335															composite to CG-29-2.5
5	AOC3-SB-45-2.5		1345															
6	AOC3-SB-44-2.5		1355	S	G	O	1	8oz	MG									
7																		
8																		
9																		
10																		

	Signature	Print Name	Company / Title	Date / Time
[1] Relinquished By:		Madison Garcia	TEI / Eng	2/13/26 1500
[1] Received By:		Gema O.	EANH	2-13-26 15:00
[2] Relinquished By:		~~GEMA~~ O	EANH	2/13/26 16:30
[2] Received By:		D. Sanchez	EA	2/13/26 1645
[3] Relinquished By:		D. Sanchez	EA	2/13/26 1735
[3] Received By:		Adam Dinkmeyer	EA	2/13/26 1735

ENTHALPY ANALYTICAL

Chain of Custody Record

Lab No: 553195

Page: 10 of 12

Turn Around Time (rush by advanced notice only)

Standard:	X	5 Day:		3 Day:	
2 Day:		1 Day:		Custom TAT:	

Enthalpy Analytical - Orange

931 W. Barkley Avenue, Orange, CA 92868

Phone 714-771-6900

Matrix: **A** = Air **S** = Soil/Solid **W** = Water **DW** = Drinking Water **P** = Product **O** = Oil **SD** = Sediment **T** = Tissue **WP** = Wipe **WW** = Wastewater **X** = Other

Sample Type: **C** = Composite **G** = Grab or Discrete **B** = Blank **O** = Other

Preservatives: **0** = none **1** = $Na_2S_2O_3$ **2** = HCl **3** = HNO_3 **4** = H_2SO_4 **5** = NaOH **6** = Other

Sample Receipt Temp and Notes: (lab use only)

CUSTOMER INFORMATION		PROJECT INFORMATION	
Company:	Terraphase Engineering	Name:	Centennial High School
Report To:	Vanya Keyes	Number:	~~1820 Rimpau Ave~~ MG
Email:	vanya.keyes@terraphase.com	P.O. #:	~~Corona, CA 92881~~ MG
Address:	18401 Von Karman Ave,	Address:	2606 N Central Ave Compton, CA 90222
	Irvine, CA		
Phone:	949-377-2227	Global ID:	
Fax:		Sampled By:	Madison Garcia

	Sample ID	Sampling Date	Sampling Time (24 hr)	Matrix	Sample Type	Pres.	Cont. No.	Cont. Size	Initials	OCPs by USEPA 8081A	Asbestos by PLM							Test Instructions / Comments
1	CG-20-0.5									X	X							Please also send report to clare.steedman@terraphase.com, madison.garcia@terraphase.com
2	CG-20-2.5									X	X							
3	CG-21-0.5									X	X							
4	CG-21-2.5									X	X							
5	CG-22-0.5									X	X							
6	CG-22-2.5									X	X							
7	CG-22-0.5-DUP									X	X							Split from CG-22-0.5
8	CG-22-2.5-DUP									X	X							Split from CG-22-2.5
9	CG-23-0.5									X	X							
10	CG-23-2.5									X	X							

	Signature	Print Name	Company / Title	Date / Time
[1] Relinquished By:		Madison Garcia	TEI / Eng	2/13/26 1500
[1] Received By:		GEMA O.	EANH	2-13-26 15:00
[2] Relinquished By:		GEMA O.	EANH	2/13/26 16:30
[2] Received By:		D. Saucier	EA	2/13/26 1644
[3] Relinquished By:		D. Saucier	EA	2/13/26 1735
[3] Received By:		Adam Diekmeyer	EA	2/13/26 1735

ENTHALPY ANALYTICAL

Chain of Custody Record

Lab No: 553195

Page: 11 of 12

Turn Around Time (rush by advanced notice only)

Standard:	X	5 Day:		3 Day:	
2 Day:		1 Day:		Custom TAT:	

Enthalpy Analytical - Orange

931 W. Barkley Avenue, Orange, CA 92868

Phone 714-771-6900

Matrix: **A** = Air **S** = Soil/Solid **W** = Water **DW** = Drinking Water **P** = Product **O** = Oil **SD** = Sediment **T** = Tissue **WP** = Wipe **WW** = Wastewater **X** = Other

Sample Type: **C** = Composite **G** = Grab or Discrete **B** = Blank **O** = Other

Preservatives: **0** = none **1** = $Na_2S_2O_3$ **2** = HCl **3** = HNO_3 **4** = H_2SO_4 **5** = NaOH **6** = Other

Sample Receipt Temp and Notes: (lab use only)

CUSTOMER INFORMATION		PROJECT INFORMATION	
Company:	Terraphase Engineering	Name:	Centennial High School
Report To:	Vanya Keyes	Number:	~~1820 Rimpau Ave~~ NG
Email:	vanya.keyes@terraphase.com	P.O. #:	~~Corona, CA 92881~~ NG
Address:	18401 Von Karman Ave,	Address:	2600 N Central Ave, Compton CA 90222
	Irvine, CA		
Phone:	949-377-2227	Global ID:	
Fax:		Sampled By:	Madison Garcia

	Sample ID	Sampling Date	Sampling Time (24 hr)	Matrix	Sample Type	Pres.	Cont. No.	Cont. Size	Initials	OCPs by USEPA 8081A	Asbestos by PLM	Test Instructions / Comments
1	CG-24-0.5									X	X	Please also send report to clare.steedman@terraphase.com, madison.garcia@terraphase.com
2	CG-24-2.5									X	X	
3	CG-25-0.5									X	X	
4	CG-25-2.5									X	X	
5	CG-26-0.5									X	X	
6	CG-26-2.5									X	X	
7	CG-26-0.5-DUP									X	X	Split from CG-26-0.5
8	CG-26-2.5-DUP									X	X	Split from CG-26-2.5
9	CG-27-0.5									X	X	
10	CG-27-2.5									X	X	

	Signature	Print Name	Company / Title	Date / Time
[1] Relinquished By:		Madison Garcia	TEI / Eng	2/13/26 1500
[1] Received By:		GEMA	EANH	2-13-26 1500
[2] Relinquished By:		GEMA O.	EANH	2/13/26 16:30
[2] Received By:		D. Sanchez	EA	2/13/26 1645
[3] Relinquished By:		D. Sanchez	EA	2/13/26 1735
[3] Received By:		Adam Dinkmeyer	EA	2/13/26 1735

ENTHALPY ANALYTICAL

Chain of Custody Record

Lab No: 553195

Page: 12 of 12

Turn Around Time (rush by advanced notice only)

Standard:	X	5 Day:		3 Day:	
2 Day:		1 Day:		Custom TAT:	

Enthalpy Analytical - Orange
931 W. Barkley Avenue, Orange, CA 92868
Phone 714-771-6900

Matrix: **A** = Air **S** = Soil/Solid **W** = Water **DW** = Drinking Water **P** = Product **O** = Oil **SD** = Sediment **T** = Tissue **WP** = Wipe **WW** = Wastewater **X** = Other

Sample Type: **C** = Composite **G** = Grab or Discrete **B** = Blank **O** = Other

Preservatives: **0** = none **1** = $Na_2S_2O_3$ **2** = HCl **3** = HNO_3 **4** = H_2SO_4 **5** = NaOH **6** = Other

Sample Receipt Temp and Notes: (lab use only)

CUSTOMER INFORMATION		PROJECT INFORMATION	
Company:	Terraphase Engineering	Name:	Centennial High School
Report To:	Vanya Keyes	Number:	~~1820 Rimpau Ave~~ NG
Email:	vanya.keyes@terraphase.com	P.O. #:	~~Corona, CA 92881~~ NG
Address:	18401 Von Karman Ave,	Address:	2606 N Central Ave, Compton, CA 90222
	Irvine, CA		
Phone:	949-377-2227	Global ID:	
Fax:		Sampled By:	Madison Garcia

Analysis Request

	Sample ID	Sampling Date	Sampling Time (24 hr)	Matrix	Sample Type	Pres.	Cont. No.	Cont. Size	Initials	OCPs by USEPA 8081A	Asbestos by PLM	Lead by 6010B	PCBs by 8082					Test Instructions / Comments
1	CG-29-0.5									X	X							Please also send report to clare.steedman@terraphase.com, madison.garcia@terraphase.com
2	CG-29-2.5									X	X							
3	EB-01-260213	2/13/26	1415	W	G	6	3	2amber 1x20mL	NG	X	X	X	X					
4																		
5																		
6																		
7																		
8																		
9																		
10																		

	Signature	Print Name	Company / Title	Date / Time
[1] Relinquished By:		Madison Garcia	TEI / Eng	2/13/26 1500
[1] Received By:		Gema O.	EANH	2-13-26 1500
[2] Relinquished By:		GEMA O.	EANH	2/13/26 16:30
[2] Received By:		D. Saucedo	EA	2/13/26 1645
[3] Relinquished By:		D. Saucedo	EA	2/13/26 1735
[3] Received By:		Adam Dickmeyer	EA	2/13/26 1735

SAMPLE RECEIPT CHECKLIST

Section 1: General Info

Date Received: 2/13/26 WO# 553195 Client: Terraphase

Section 2: Shipping / Custody **Are custody seals present?** ☐ Yes ☒ No

Custody seals intact on arrival? ■ N/A ☐ Yes ☐ No ☐ On cooler / box ☐ On samples

■ Courier ☐ Walk-In ☐ Field Sampling ☐ Shipping Info: _____

Section 3a: Condition / Packaging ☐ **Outside 0.0 - 6.0°C (0.0 - 10.0°C for microbiology) (PM notified)**

Date Opened 2/13/26 By (initials) DXS Type of ice used: ■ Wet ☐ Blue/Gel ☐ None

☒ Samples received on ice directly from the field; cooling process had begun. (if checked, skip temperatures)

☐ Sample matrix doesn't require cooling (e.g. air, bulk PCB). (if checked, skip temperatures)

If no cooler: Observed/Adjusted Temp (°C): _____ / _____ Thermometer/IR Gun: IR 15 CF: +0.4

Cooler Temp (°C) #1: 5.0 / 5.4 #2: 5.8 / 6.2 #3: ____ / ____ #4: ____ / ____ #5: ____ / ____ #6: ____ / ____

Section 3b: Microbiology Samples ■ **No microbiology samples submitted (skip 3b)**

☐ Within temp range 0.0 - 10.0°C or received on ice directly from field.

☐ Adequate headspace for microbiology analysis.

Section 3c: Air Samples ■ **No air samples submitted (skip 3c)**

☐ 1.4L Canisters ☐ 6L Canisters ☐ Tedlar Bags ☐ MCE Cassettes ☐ Sorbent Tubes ☐ Other_____

Section 4: Containers / Labels / Samples	YES	NO	N/A
1) Were custody papers present, filled properly, and legible?	X		
2) Is the sampler's name present on the CoC?	X		
3) Were containers received in good condition (unbroken / unopened / uncompromised)?	X		
4) Were the samples bagged? (required for microbiology samples; recommended for soil samples)	X		
5) Were all of, and only, the correct samples received?	X		
6) Are sample labels present, legible, and in agreement with the CoC?	X		
7) Does the container count match the CoC?	X		
8) Was sufficient sample volume / mass received for the analyses requested?	X		
9) Were samples received in proper containers for the analyses requested?	X		
10) Were samples received with > 1/2 holding time remaining?	X		
11) Are samples properly preserved as indicated by CoC / labels?	X		
12) Unpreserved VOAs received - If necessary, was the hold time changed in LIMS?			X
13) Are VOA vials free from headspace/bubbles > 6mm?			X

Section 5: Explanations / Comments

(If no comments are made, then no discrepancies noted.)

☐ **No additional discrepancies**

Date Logged 2/13/26 **By (print)** ABD **(sign)** AdJ's

Date Labeled 2/13/26 **By (print)** AGR/MSK **(sign)** AdJ's for AGR/MSK

ENTHALPY ANALYTICAL

Analysis Results for 553195

Vanya Keyes
Terraphase Engineering
18401 Von Karman Ave, Suite #410
Irvine, CA 92612

Lab Job #: 553195
Location: Centennial High School, 2606 N Central Ave., Compton, CA 90222
Date Received: 02/13/26

Sample ID: AOC3-SB-19-0.5 **Lab ID: 553195-001** **Collected: 02/13/26 07:25**
Matrix: Soil

553195-001 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3050B									
Lead	**44**		mg/Kg	0.99	0.99	395654	02/18/26	02/18/26	SBW
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	50	0.99	395809	02/19/26	02/20/26	MES
Aroclor-1221	ND		ug/Kg	50	0.99	395809	02/19/26	02/20/26	MES
Aroclor-1232	ND		ug/Kg	50	0.99	395809	02/19/26	02/20/26	MES
Aroclor-1242	ND		ug/Kg	50	0.99	395809	02/19/26	02/20/26	MES
Aroclor-1248	ND		ug/Kg	50	0.99	395809	02/19/26	02/20/26	MES
Aroclor-1254	ND		ug/Kg	50	0.99	395809	02/19/26	02/20/26	MES
Aroclor-1260	**51**		ug/Kg	50	0.99	395809	02/19/26	02/20/26	MES
Aroclor-1262	ND		ug/Kg	50	0.99	395809	02/19/26	02/20/26	MES
Aroclor-1268	ND		ug/Kg	50	0.99	395809	02/19/26	02/20/26	MES
Total PCBs	**51**		ug/Kg	50	0.99	395809	02/19/26	02/20/26	MES
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	121%		%REC	50-127	0.99	395809	02/19/26	02/20/26	MES

Sample ID: AOC3-SB-18-0.5 **Lab ID: 553195-002** **Collected: 02/13/26 07:40**
Matrix: Soil

553195-002 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3050B									
Lead	**9.8**		mg/Kg	0.99	0.99	395654	02/18/26	02/18/26	SBW
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	50	1	395809	02/19/26	02/20/26	MES
Aroclor-1221	ND		ug/Kg	50	1	395809	02/19/26	02/20/26	MES
Aroclor-1232	ND		ug/Kg	50	1	395809	02/19/26	02/20/26	MES
Aroclor-1242	ND		ug/Kg	50	1	395809	02/19/26	02/20/26	MES
Aroclor-1248	ND		ug/Kg	50	1	395809	02/19/26	02/20/26	MES
Aroclor-1254	ND		ug/Kg	50	1	395809	02/19/26	02/20/26	MES
Aroclor-1260	ND		ug/Kg	50	1	395809	02/19/26	02/20/26	MES
Aroclor-1262	ND		ug/Kg	50	1	395809	02/19/26	02/20/26	MES
Aroclor-1268	ND		ug/Kg	50	1	395809	02/19/26	02/20/26	MES
Total PCBs	ND		ug/Kg	50	1	395809	02/19/26	02/20/26	MES
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	116%		%REC	50-127	1	395809	02/19/26	02/20/26	MES

Results for any subcontracted analyses are not included in this section.

ENTHALPY ANALYTICAL

Analysis Results for 553195

Sample ID: AOC3-SB-17-0.5 **Lab ID: 553195-003** **Collected: 02/13/26 07:50**
Matrix: Soil

553195-003 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3050B									
Lead	**43**		mg/Kg	0.97	0.97	395654	02/18/26	02/18/26	SBW
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	51	1	395809	02/19/26	02/20/26	MES
Aroclor-1221	ND		ug/Kg	51	1	395809	02/19/26	02/20/26	MES
Aroclor-1232	ND		ug/Kg	51	1	395809	02/19/26	02/20/26	MES
Aroclor-1242	ND		ug/Kg	51	1	395809	02/19/26	02/20/26	MES
Aroclor-1248	ND		ug/Kg	51	1	395809	02/19/26	02/20/26	MES
Aroclor-1254	ND		ug/Kg	51	1	395809	02/19/26	02/20/26	MES
Aroclor-1260	ND		ug/Kg	51	1	395809	02/19/26	02/20/26	MES
Aroclor-1262	ND		ug/Kg	51	1	395809	02/19/26	02/20/26	MES
Aroclor-1268	ND		ug/Kg	51	1	395809	02/19/26	02/20/26	MES
Total PCBs	ND		ug/Kg	51	1	395809	02/19/26	02/20/26	MES
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	104%		%REC	50-127	1	395809	02/19/26	02/20/26	MES

Sample ID: AOC3-SB-20-0.5 **Lab ID: 553195-007** **Collected: 02/13/26 08:45**
Matrix: Soil

553195-007 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3050B									
Lead	**17**		mg/Kg	0.95	0.95	395654	02/18/26	02/18/26	SBW
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	51	1	395809	02/19/26	02/20/26	MES
Aroclor-1221	ND		ug/Kg	51	1	395809	02/19/26	02/20/26	MES
Aroclor-1232	ND		ug/Kg	51	1	395809	02/19/26	02/20/26	MES
Aroclor-1242	ND		ug/Kg	51	1	395809	02/19/26	02/20/26	MES
Aroclor-1248	ND		ug/Kg	51	1	395809	02/19/26	02/20/26	MES
Aroclor-1254	ND		ug/Kg	51	1	395809	02/19/26	02/20/26	MES
Aroclor-1260	ND		ug/Kg	51	1	395809	02/19/26	02/20/26	MES
Aroclor-1262	ND		ug/Kg	51	1	395809	02/19/26	02/20/26	MES
Aroclor-1268	ND		ug/Kg	51	1	395809	02/19/26	02/20/26	MES
Total PCBs	ND		ug/Kg	51	1	395809	02/19/26	02/20/26	MES
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	121%		%REC	50-127	1	395809	02/19/26	02/20/26	MES

Results for any subcontracted analyses are not included in this section.

Analysis Results for 553195

Sample ID: AOC3-SB-21-0.5	Lab ID: 553195-008	Collected: 02/13/26 08:55
	Matrix: Soil	

553195-008 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3050B									
Lead	**32**		mg/Kg	0.97	0.97	395654	02/18/26	02/18/26	SBW
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	50	1	395809	02/19/26	02/20/26	MES
Aroclor-1221	ND		ug/Kg	50	1	395809	02/19/26	02/20/26	MES
Aroclor-1232	ND		ug/Kg	50	1	395809	02/19/26	02/20/26	MES
Aroclor-1242	ND		ug/Kg	50	1	395809	02/19/26	02/20/26	MES
Aroclor-1248	ND		ug/Kg	50	1	395809	02/19/26	02/20/26	MES
Aroclor-1254	ND		ug/Kg	50	1	395809	02/19/26	02/20/26	MES
Aroclor-1260	ND		ug/Kg	50	1	395809	02/19/26	02/20/26	MES
Aroclor-1262	ND		ug/Kg	50	1	395809	02/19/26	02/20/26	MES
Aroclor-1268	ND		ug/Kg	50	1	395809	02/19/26	02/20/26	MES
Total PCBs	ND		ug/Kg	50	1	395809	02/19/26	02/20/26	MES
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	116%		%REC	50-127	1	395809	02/19/26	02/20/26	MES

Sample ID: AOC3-SB-22-0.5	Lab ID: 553195-009	Collected: 02/13/26 09:05
	Matrix: Soil	

553195-009 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3050B									
Lead	**15**		mg/Kg	1.0	1	395654	02/18/26	02/18/26	SBW
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	50	1	395809	02/19/26	02/20/26	MES
Aroclor-1221	ND		ug/Kg	50	1	395809	02/19/26	02/20/26	MES
Aroclor-1232	ND		ug/Kg	50	1	395809	02/19/26	02/20/26	MES
Aroclor-1242	ND		ug/Kg	50	1	395809	02/19/26	02/20/26	MES
Aroclor-1248	ND		ug/Kg	50	1	395809	02/19/26	02/20/26	MES
Aroclor-1254	ND		ug/Kg	50	1	395809	02/19/26	02/20/26	MES
Aroclor-1260	ND		ug/Kg	50	1	395809	02/19/26	02/20/26	MES
Aroclor-1262	ND		ug/Kg	50	1	395809	02/19/26	02/20/26	MES
Aroclor-1268	ND		ug/Kg	50	1	395809	02/19/26	02/20/26	MES
Total PCBs	ND		ug/Kg	50	1	395809	02/19/26	02/20/26	MES
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	119%		%REC	50-127	1	395809	02/19/26	02/20/26	MES

Results for any subcontracted analyses are not included in this section.

Analysis Results for 553195

Sample ID: AOC3-SB-23-0.5	Lab ID: 553195-013	Collected: 02/13/26 09:15
	Matrix: Soil	

553195-013 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3050B									
Lead	**61**		mg/Kg	0.98	0.98	395654	02/18/26	02/18/26	SBW
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	49	0.98	395809	02/19/26	02/20/26	MES
Aroclor-1221	ND		ug/Kg	49	0.98	395809	02/19/26	02/20/26	MES
Aroclor-1232	ND		ug/Kg	49	0.98	395809	02/19/26	02/20/26	MES
Aroclor-1242	ND		ug/Kg	49	0.98	395809	02/19/26	02/20/26	MES
Aroclor-1248	ND		ug/Kg	49	0.98	395809	02/19/26	02/20/26	MES
Aroclor-1254	ND		ug/Kg	49	0.98	395809	02/19/26	02/20/26	MES
Aroclor-1260	ND		ug/Kg	49	0.98	395809	02/19/26	02/20/26	MES
Aroclor-1262	ND		ug/Kg	49	0.98	395809	02/19/26	02/20/26	MES
Aroclor-1268	ND		ug/Kg	49	0.98	395809	02/19/26	02/20/26	MES
Total PCBs	ND		ug/Kg	49	0.98	395809	02/19/26	02/20/26	MES
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	118%		%REC	50-127	0.98	395809	02/19/26	02/20/26	MES

Sample ID: AOC3-SB-24-0.5	Lab ID: 553195-014	Collected: 02/13/26 09:55
	Matrix: Soil	

553195-014 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3050B									
Lead	**83**		mg/Kg	1.0	1	395654	02/18/26	02/18/26	SBW
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	51	1	395809	02/19/26	02/20/26	MES
Aroclor-1221	ND		ug/Kg	51	1	395809	02/19/26	02/20/26	MES
Aroclor-1232	ND		ug/Kg	51	1	395809	02/19/26	02/20/26	MES
Aroclor-1242	ND		ug/Kg	51	1	395809	02/19/26	02/20/26	MES
Aroclor-1248	ND		ug/Kg	51	1	395809	02/19/26	02/20/26	MES
Aroclor-1254	**100**		ug/Kg	51	1	395809	02/19/26	02/20/26	MES
Aroclor-1260	**150**		ug/Kg	51	1	395809	02/19/26	02/20/26	MES
Aroclor-1262	ND		ug/Kg	51	1	395809	02/19/26	02/20/26	MES
Aroclor-1268	ND		ug/Kg	51	1	395809	02/19/26	02/20/26	MES
Total PCBs	**250**		ug/Kg	51	1	395809	02/19/26	02/20/26	MES
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	112%		%REC	50-127	1	395809	02/19/26	02/20/26	MES

Results for any subcontracted analyses are not included in this section.

Analysis Results for 553195

Sample ID: AOC3-SB-25-0.5 **Lab ID: 553195-015** **Collected: 02/13/26 09:45**
Matrix: Soil

553195-015 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3050B									
Lead	**25**		mg/Kg	0.99	0.99	395654	02/18/26	02/18/26	SBW
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	50	1	395809	02/19/26	02/20/26	MES
Aroclor-1221	ND		ug/Kg	50	1	395809	02/19/26	02/20/26	MES
Aroclor-1232	ND		ug/Kg	50	1	395809	02/19/26	02/20/26	MES
Aroclor-1242	ND		ug/Kg	50	1	395809	02/19/26	02/20/26	MES
Aroclor-1248	ND		ug/Kg	50	1	395809	02/19/26	02/20/26	MES
Aroclor-1254	ND		ug/Kg	50	1	395809	02/19/26	02/20/26	MES
Aroclor-1260	ND		ug/Kg	50	1	395809	02/19/26	02/20/26	MES
Aroclor-1262	ND		ug/Kg	50	1	395809	02/19/26	02/20/26	MES
Aroclor-1268	ND		ug/Kg	50	1	395809	02/19/26	02/20/26	MES
Total PCBs	ND		ug/Kg	50	1	395809	02/19/26	02/20/26	MES
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	112%		%REC	50-127	1	395809	02/19/26	02/20/26	MES

Sample ID: DUP-01-0.5-260213 **Lab ID: 553195-019** **Collected: 02/13/26**
Matrix: Soil

553195-019 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3050B									
Lead	**19**		mg/Kg	0.99	0.99	395654	02/18/26	02/18/26	SBW
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	50	0.99	395809	02/19/26	02/20/26	MES
Aroclor-1221	ND		ug/Kg	50	0.99	395809	02/19/26	02/20/26	MES
Aroclor-1232	ND		ug/Kg	50	0.99	395809	02/19/26	02/20/26	MES
Aroclor-1242	ND		ug/Kg	50	0.99	395809	02/19/26	02/20/26	MES
Aroclor-1248	ND		ug/Kg	50	0.99	395809	02/19/26	02/20/26	MES
Aroclor-1254	ND		ug/Kg	50	0.99	395809	02/19/26	02/20/26	MES
Aroclor-1260	ND		ug/Kg	50	0.99	395809	02/19/26	02/20/26	MES
Aroclor-1262	ND		ug/Kg	50	0.99	395809	02/19/26	02/20/26	MES
Aroclor-1268	ND		ug/Kg	50	0.99	395809	02/19/26	02/20/26	MES
Total PCBs	ND		ug/Kg	50	0.99	395809	02/19/26	02/20/26	MES
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	124%		%REC	50-127	0.99	395809	02/19/26	02/20/26	MES

Results for any subcontracted analyses are not included in this section.

Analysis Results for 553195

Sample ID: AOC3-SB-26-0.5	Lab ID: 553195-021	Collected: 02/13/26 08:20
	Matrix: Soil	

553195-021 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3050B									
Lead	**11**		mg/Kg	0.98	0.98	395654	02/18/26	02/18/26	SBW
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	50	1	395809	02/19/26	02/20/26	MES
Aroclor-1221	ND		ug/Kg	50	1	395809	02/19/26	02/20/26	MES
Aroclor-1232	ND		ug/Kg	50	1	395809	02/19/26	02/20/26	MES
Aroclor-1242	ND		ug/Kg	50	1	395809	02/19/26	02/20/26	MES
Aroclor-1248	ND		ug/Kg	50	1	395809	02/19/26	02/20/26	MES
Aroclor-1254	ND		ug/Kg	50	1	395809	02/19/26	02/20/26	MES
Aroclor-1260	ND		ug/Kg	50	1	395809	02/19/26	02/20/26	MES
Aroclor-1262	ND		ug/Kg	50	1	395809	02/19/26	02/20/26	MES
Aroclor-1268	ND		ug/Kg	50	1	395809	02/19/26	02/20/26	MES
Total PCBs	ND		ug/Kg	50	1	395809	02/19/26	02/20/26	MES
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	116%		%REC	50-127	1	395809	02/19/26	02/20/26	MES

Sample ID: AOC3-SB-27-0.5	Lab ID: 553195-022	Collected: 02/13/26 08:10
	Matrix: Soil	

553195-022 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3050B									
Lead	**10**		mg/Kg	0.99	0.99	395654	02/18/26	02/18/26	SBW
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	51	1	395809	02/19/26	02/20/26	MES
Aroclor-1221	ND		ug/Kg	51	1	395809	02/19/26	02/20/26	MES
Aroclor-1232	ND		ug/Kg	51	1	395809	02/19/26	02/20/26	MES
Aroclor-1242	ND		ug/Kg	51	1	395809	02/19/26	02/20/26	MES
Aroclor-1248	ND		ug/Kg	51	1	395809	02/19/26	02/20/26	MES
Aroclor-1254	ND		ug/Kg	51	1	395809	02/19/26	02/20/26	MES
Aroclor-1260	ND		ug/Kg	51	1	395809	02/19/26	02/20/26	MES
Aroclor-1262	ND		ug/Kg	51	1	395809	02/19/26	02/20/26	MES
Aroclor-1268	ND		ug/Kg	51	1	395809	02/19/26	02/20/26	MES
Total PCBs	ND		ug/Kg	51	1	395809	02/19/26	02/20/26	MES
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	133%	*	%REC	50-127	1	395809	02/19/26	02/20/26	MES

Results for any subcontracted analyses are not included in this section.

Analysis Results for 553195

Sample ID: AOC3-SB-28-0.5	Lab ID: 553195-023	Collected: 02/13/26 08:00
	Matrix: Soil	

553195-023 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3050B									
Lead	**4.2**		mg/Kg	0.98	0.98	395654	02/18/26	02/18/26	SBW
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	49	0.98	395809	02/19/26	02/20/26	MES
Aroclor-1221	ND		ug/Kg	49	0.98	395809	02/19/26	02/20/26	MES
Aroclor-1232	ND		ug/Kg	49	0.98	395809	02/19/26	02/20/26	MES
Aroclor-1242	ND		ug/Kg	49	0.98	395809	02/19/26	02/20/26	MES
Aroclor-1248	ND		ug/Kg	49	0.98	395809	02/19/26	02/20/26	MES
Aroclor-1254	ND		ug/Kg	49	0.98	395809	02/19/26	02/20/26	MES
Aroclor-1260	ND		ug/Kg	49	0.98	395809	02/19/26	02/20/26	MES
Aroclor-1262	ND		ug/Kg	49	0.98	395809	02/19/26	02/20/26	MES
Aroclor-1268	ND		ug/Kg	49	0.98	395809	02/19/26	02/20/26	MES
Total PCBs	ND		ug/Kg	49	0.98	395809	02/19/26	02/20/26	MES
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	134%	*	%REC	50-127	0.98	395809	02/19/26	02/20/26	MES

Sample ID: AOC3-SB-29-0.5	Lab ID: 553195-027	Collected: 02/13/26 11:50
	Matrix: Soil	

553195-027 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3050B									
Lead	**35**		mg/Kg	0.99	0.99	395654	02/18/26	02/18/26	SBW
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	51	1	395809	02/19/26	02/20/26	MES
Aroclor-1221	ND		ug/Kg	51	1	395809	02/19/26	02/20/26	MES
Aroclor-1232	ND		ug/Kg	51	1	395809	02/19/26	02/20/26	MES
Aroclor-1242	ND		ug/Kg	51	1	395809	02/19/26	02/20/26	MES
Aroclor-1248	ND		ug/Kg	51	1	395809	02/19/26	02/20/26	MES
Aroclor-1254	**89**		ug/Kg	51	1	395809	02/19/26	02/20/26	MES
Aroclor-1260	**51**		ug/Kg	51	1	395809	02/19/26	02/20/26	MES
Aroclor-1262	ND		ug/Kg	51	1	395809	02/19/26	02/20/26	MES
Aroclor-1268	ND		ug/Kg	51	1	395809	02/19/26	02/20/26	MES
Total PCBs	**140**		ug/Kg	51	1	395809	02/19/26	02/20/26	MES
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	125%		%REC	50-127	1	395809	02/19/26	02/20/26	MES

Results for any subcontracted analyses are not included in this section.

Analysis Results for 553195

Sample ID: AOC3-SB-30-0.5	Lab ID: 553195-028	Collected: 02/13/26 11:35
	Matrix: Soil	

553195-028 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3050B									
Lead	**12**		mg/Kg	0.97	0.97	395654	02/18/26	02/18/26	SBW
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	51	1	395809	02/19/26	02/20/26	MES
Aroclor-1221	ND		ug/Kg	51	1	395809	02/19/26	02/20/26	MES
Aroclor-1232	ND		ug/Kg	51	1	395809	02/19/26	02/20/26	MES
Aroclor-1242	ND		ug/Kg	51	1	395809	02/19/26	02/20/26	MES
Aroclor-1248	ND		ug/Kg	51	1	395809	02/19/26	02/20/26	MES
Aroclor-1254	ND		ug/Kg	51	1	395809	02/19/26	02/20/26	MES
Aroclor-1260	ND		ug/Kg	51	1	395809	02/19/26	02/20/26	MES
Aroclor-1262	ND		ug/Kg	51	1	395809	02/19/26	02/20/26	MES
Aroclor-1268	ND		ug/Kg	51	1	395809	02/19/26	02/20/26	MES
Total PCBs	ND		ug/Kg	51	1	395809	02/19/26	02/20/26	MES
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	124%		%REC	50-127	1	395809	02/19/26	02/20/26	MES

Sample ID: AOC3-SB-31-0.5	Lab ID: 553195-029	Collected: 02/13/26 11:25
	Matrix: Soil	

553195-029 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3050B									
Lead	**64**		mg/Kg	0.95	0.95	395654	02/18/26	02/18/26	SBW
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	51	1	395809	02/19/26	02/20/26	MES
Aroclor-1221	ND		ug/Kg	51	1	395809	02/19/26	02/20/26	MES
Aroclor-1232	ND		ug/Kg	51	1	395809	02/19/26	02/20/26	MES
Aroclor-1242	ND		ug/Kg	51	1	395809	02/19/26	02/20/26	MES
Aroclor-1248	ND		ug/Kg	51	1	395809	02/19/26	02/20/26	MES
Aroclor-1254	ND		ug/Kg	51	1	395809	02/19/26	02/20/26	MES
Aroclor-1260	ND		ug/Kg	51	1	395809	02/19/26	02/20/26	MES
Aroclor-1262	ND		ug/Kg	51	1	395809	02/19/26	02/20/26	MES
Aroclor-1268	ND		ug/Kg	51	1	395809	02/19/26	02/20/26	MES
Total PCBs	ND		ug/Kg	51	1	395809	02/19/26	02/20/26	MES
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	124%		%REC	50-127	1	395809	02/19/26	02/20/26	MES

Results for any subcontracted analyses are not included in this section.

Analysis Results for 553195

Sample ID: AOC3-SB-32-0.5 **Lab ID: 553195-033** **Collected: 02/13/26 10:45**
Matrix: Soil

553195-033 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3050B									
Lead	**37**		mg/Kg	0.96	0.96	395654	02/18/26	02/18/26	SBW
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	50	1	395809	02/19/26	02/20/26	MES
Aroclor-1221	ND		ug/Kg	50	1	395809	02/19/26	02/20/26	MES
Aroclor-1232	ND		ug/Kg	50	1	395809	02/19/26	02/20/26	MES
Aroclor-1242	ND		ug/Kg	50	1	395809	02/19/26	02/20/26	MES
Aroclor-1248	ND		ug/Kg	50	1	395809	02/19/26	02/20/26	MES
Aroclor-1254	ND		ug/Kg	50	1	395809	02/19/26	02/20/26	MES
Aroclor-1260	ND		ug/Kg	50	1	395809	02/19/26	02/20/26	MES
Aroclor-1262	ND		ug/Kg	50	1	395809	02/19/26	02/20/26	MES
Aroclor-1268	ND		ug/Kg	50	1	395809	02/19/26	02/20/26	MES
Total PCBs	ND		ug/Kg	50	1	395809	02/19/26	02/20/26	MES
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	116%		%REC	50-127	1	395809	02/19/26	02/20/26	MES

Sample ID: AOC3-SB-33-0.5 **Lab ID: 553195-034** **Collected: 02/13/26 10:35**
Matrix: Soil

553195-034 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3050B									
Lead	**29**		mg/Kg	1.0	1	395654	02/18/26	02/18/26	SBW
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	51	1	395809	02/19/26	02/20/26	MES
Aroclor-1221	ND		ug/Kg	51	1	395809	02/19/26	02/20/26	MES
Aroclor-1232	ND		ug/Kg	51	1	395809	02/19/26	02/20/26	MES
Aroclor-1242	ND		ug/Kg	51	1	395809	02/19/26	02/20/26	MES
Aroclor-1248	ND		ug/Kg	51	1	395809	02/19/26	02/20/26	MES
Aroclor-1254	ND		ug/Kg	51	1	395809	02/19/26	02/20/26	MES
Aroclor-1260	ND		ug/Kg	51	1	395809	02/19/26	02/20/26	MES
Aroclor-1262	ND		ug/Kg	51	1	395809	02/19/26	02/20/26	MES
Aroclor-1268	ND		ug/Kg	51	1	395809	02/19/26	02/20/26	MES
Total PCBs	ND		ug/Kg	51	1	395809	02/19/26	02/20/26	MES
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	121%		%REC	50-127	1	395809	02/19/26	02/20/26	MES

Results for any subcontracted analyses are not included in this section.

Analysis Results for 553195

Sample ID: AOC3-SB-34-0.5	Lab ID: 553195-035	Collected: 02/13/26 10:15
	Matrix: Soil	

553195-035 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3050B									
Lead	**31**		mg/Kg	0.99	0.99	395654	02/18/26	02/18/26	SBW
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	51	1	395809	02/19/26	02/23/26	MES
Aroclor-1221	ND		ug/Kg	51	1	395809	02/19/26	02/23/26	MES
Aroclor-1232	ND		ug/Kg	51	1	395809	02/19/26	02/23/26	MES
Aroclor-1242	ND		ug/Kg	51	1	395809	02/19/26	02/23/26	MES
Aroclor-1248	ND		ug/Kg	51	1	395809	02/19/26	02/23/26	MES
Aroclor-1254	**110**		ug/Kg	51	1	395809	02/19/26	02/23/26	MES
Aroclor-1260	ND		ug/Kg	51	1	395809	02/19/26	02/23/26	MES
Aroclor-1262	ND		ug/Kg	51	1	395809	02/19/26	02/23/26	MES
Aroclor-1268	ND		ug/Kg	51	1	395809	02/19/26	02/23/26	MES
Total PCBs	**110**		ug/Kg	51	1	395809	02/19/26	02/23/26	MES
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	117%		%REC	50-127	1	395809	02/19/26	02/23/26	MES

Sample ID: AOC3-SB-35-0.5	Lab ID: 553195-039	Collected: 02/13/26 13:20
	Matrix: Soil	

553195-039 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3050B									
Lead	**23**		mg/Kg	0.96	0.96	395654	02/18/26	02/18/26	SBW
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	51	1	395809	02/19/26	02/20/26	MES
Aroclor-1221	ND		ug/Kg	51	1	395809	02/19/26	02/20/26	MES
Aroclor-1232	ND		ug/Kg	51	1	395809	02/19/26	02/20/26	MES
Aroclor-1242	ND		ug/Kg	51	1	395809	02/19/26	02/20/26	MES
Aroclor-1248	ND		ug/Kg	51	1	395809	02/19/26	02/20/26	MES
Aroclor-1254	ND		ug/Kg	51	1	395809	02/19/26	02/20/26	MES
Aroclor-1260	ND		ug/Kg	51	1	395809	02/19/26	02/20/26	MES
Aroclor-1262	ND		ug/Kg	51	1	395809	02/19/26	02/20/26	MES
Aroclor-1268	ND		ug/Kg	51	1	395809	02/19/26	02/20/26	MES
Total PCBs	ND		ug/Kg	51	1	395809	02/19/26	02/20/26	MES
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	159%	*	%REC	50-127	1	395809	02/19/26	02/20/26	MES

Results for any subcontracted analyses are not included in this section.

Analysis Results for 553195

Sample ID: AOC3-SB-36-0.5	Lab ID: 553195-040	Collected: 02/13/26 13:10
	Matrix: Soil	

553195-040 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3050B									
Lead	**42**		mg/Kg	1.0	1	395658	02/18/26	02/18/26	SBW
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	51	1	395871	02/20/26	02/23/26	KMB
Aroclor-1221	ND		ug/Kg	51	1	395871	02/20/26	02/23/26	KMB
Aroclor-1232	ND		ug/Kg	51	1	395871	02/20/26	02/23/26	KMB
Aroclor-1242	ND		ug/Kg	51	1	395871	02/20/26	02/23/26	KMB
Aroclor-1248	ND		ug/Kg	51	1	395871	02/20/26	02/23/26	KMB
Aroclor-1254	ND		ug/Kg	51	1	395871	02/20/26	02/23/26	KMB
Aroclor-1260	ND		ug/Kg	51	1	395871	02/20/26	02/23/26	KMB
Aroclor-1262	ND		ug/Kg	51	1	395871	02/20/26	02/23/26	KMB
Aroclor-1268	ND		ug/Kg	51	1	395871	02/20/26	02/23/26	KMB
Total PCBs	ND		ug/Kg	51	1	395871	02/20/26	02/23/26	KMB
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	107%		%REC	50-127	1	395871	02/20/26	02/23/26	KMB

Sample ID: AOC3-SB-37-0.5	Lab ID: 553195-041	Collected: 02/13/26 13:00
	Matrix: Soil	

553195-041 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3050B									
Lead	**49**		mg/Kg	0.96	0.96	395658	02/18/26	02/18/26	SBW
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	51	1	395871	02/20/26	02/21/26	XLY
Aroclor-1221	ND		ug/Kg	51	1	395871	02/20/26	02/21/26	XLY
Aroclor-1232	ND		ug/Kg	51	1	395871	02/20/26	02/21/26	XLY
Aroclor-1242	ND		ug/Kg	51	1	395871	02/20/26	02/21/26	XLY
Aroclor-1248	ND		ug/Kg	51	1	395871	02/20/26	02/21/26	XLY
Aroclor-1254	ND		ug/Kg	51	1	395871	02/20/26	02/21/26	XLY
Aroclor-1260	ND		ug/Kg	51	1	395871	02/20/26	02/21/26	XLY
Aroclor-1262	ND		ug/Kg	51	1	395871	02/20/26	02/21/26	XLY
Aroclor-1268	ND		ug/Kg	51	1	395871	02/20/26	02/21/26	XLY
Total PCBs	ND		ug/Kg	51	1	395871	02/20/26	02/21/26	XLY
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	91%		%REC	50-127	1	395871	02/20/26	02/21/26	XLY

Results for any subcontracted analyses are not included in this section.

Analysis Results for 553195

Sample ID: DUP-02-0.5-260213	Lab ID: 553195-045	Collected: 02/13/26
	Matrix: Soil	

553195-045 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3050B									
Lead	**35**		mg/Kg	1.0	1	395658	02/18/26	02/18/26	SBW
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	50	1	395871	02/20/26	02/21/26	XLY
Aroclor-1221	ND		ug/Kg	50	1	395871	02/20/26	02/21/26	XLY
Aroclor-1232	ND		ug/Kg	50	1	395871	02/20/26	02/21/26	XLY
Aroclor-1242	ND		ug/Kg	50	1	395871	02/20/26	02/21/26	XLY
Aroclor-1248	ND		ug/Kg	50	1	395871	02/20/26	02/21/26	XLY
Aroclor-1254	ND		ug/Kg	50	1	395871	02/20/26	02/21/26	XLY
Aroclor-1260	ND		ug/Kg	50	1	395871	02/20/26	02/21/26	XLY
Aroclor-1262	ND		ug/Kg	50	1	395871	02/20/26	02/21/26	XLY
Aroclor-1268	ND		ug/Kg	50	1	395871	02/20/26	02/21/26	XLY
Total PCBs	ND		ug/Kg	50	1	395871	02/20/26	02/21/26	XLY
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	96%		%REC	50-127	1	395871	02/20/26	02/21/26	XLY

Sample ID: AOC3-SB-38-0.5	Lab ID: 553195-047	Collected: 02/13/26 12:20
	Matrix: Soil	

553195-047 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3050B									
Lead	**34**		mg/Kg	0.97	0.97	395658	02/18/26	02/18/26	SBW
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	51	1	395871	02/20/26	02/23/26	KMB
Aroclor-1221	ND		ug/Kg	51	1	395871	02/20/26	02/23/26	KMB
Aroclor-1232	ND		ug/Kg	51	1	395871	02/20/26	02/23/26	KMB
Aroclor-1242	ND		ug/Kg	51	1	395871	02/20/26	02/23/26	KMB
Aroclor-1248	ND		ug/Kg	51	1	395871	02/20/26	02/23/26	KMB
Aroclor-1254	ND		ug/Kg	51	1	395871	02/20/26	02/23/26	KMB
Aroclor-1260	ND		ug/Kg	51	1	395871	02/20/26	02/23/26	KMB
Aroclor-1262	ND		ug/Kg	51	1	395871	02/20/26	02/23/26	KMB
Aroclor-1268	ND		ug/Kg	51	1	395871	02/20/26	02/23/26	KMB
Total PCBs	ND		ug/Kg	51	1	395871	02/20/26	02/23/26	KMB
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	108%		%REC	50-127	1	395871	02/20/26	02/23/26	KMB

Results for any subcontracted analyses are not included in this section.

Analysis Results for 553195

Sample ID: AOC3-SB-39-0.5	Lab ID: 553195-048	Collected: 02/13/26 12:10
	Matrix: Soil	

553195-048 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3050B									
Lead	**41**		mg/Kg	0.95	0.95	395658	02/18/26	02/18/26	SBW
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	50	1	395871	02/20/26	02/21/26	XLY
Aroclor-1221	ND		ug/Kg	50	1	395871	02/20/26	02/21/26	XLY
Aroclor-1232	ND		ug/Kg	50	1	395871	02/20/26	02/21/26	XLY
Aroclor-1242	ND		ug/Kg	50	1	395871	02/20/26	02/21/26	XLY
Aroclor-1248	ND		ug/Kg	50	1	395871	02/20/26	02/21/26	XLY
Aroclor-1254	ND		ug/Kg	50	1	395871	02/20/26	02/21/26	XLY
Aroclor-1260	ND		ug/Kg	50	1	395871	02/20/26	02/21/26	XLY
Aroclor-1262	ND		ug/Kg	50	1	395871	02/20/26	02/21/26	XLY
Aroclor-1268	ND		ug/Kg	50	1	395871	02/20/26	02/21/26	XLY
Total PCBs	ND		ug/Kg	50	1	395871	02/20/26	02/21/26	XLY
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	82%		%REC	50-127	1	395871	02/20/26	02/21/26	XLY

Sample ID: AOC3-SB-40-0.5	Lab ID: 553195-049	Collected: 02/13/26 12:00
	Matrix: Soil	

553195-049 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3050B									
Lead	**80**		mg/Kg	0.96	0.96	395658	02/18/26	02/19/26	SBW
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	50	1	395871	02/20/26	02/21/26	XLY
Aroclor-1221	ND		ug/Kg	50	1	395871	02/20/26	02/21/26	XLY
Aroclor-1232	ND		ug/Kg	50	1	395871	02/20/26	02/21/26	XLY
Aroclor-1242	ND		ug/Kg	50	1	395871	02/20/26	02/21/26	XLY
Aroclor-1248	ND		ug/Kg	50	1	395871	02/20/26	02/21/26	XLY
Aroclor-1254	ND		ug/Kg	50	1	395871	02/20/26	02/21/26	XLY
Aroclor-1260	ND		ug/Kg	50	1	395871	02/20/26	02/21/26	XLY
Aroclor-1262	ND		ug/Kg	50	1	395871	02/20/26	02/21/26	XLY
Aroclor-1268	ND		ug/Kg	50	1	395871	02/20/26	02/21/26	XLY
Total PCBs	ND		ug/Kg	50	1	395871	02/20/26	02/21/26	XLY
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	81%		%REC	50-127	1	395871	02/20/26	02/21/26	XLY

Results for any subcontracted analyses are not included in this section.

Analysis Results for 553195

Sample ID: AOC3-SB-46-0.5 **Lab ID: 553195-053** **Collected: 02/13/26 13:30**
Matrix: Soil

553195-053 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3050B									
Lead	**50**		mg/Kg	0.95	0.95	395658	02/18/26	02/19/26	SBW
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	50	0.99	395871	02/20/26	02/21/26	XLY
Aroclor-1221	ND		ug/Kg	50	0.99	395871	02/20/26	02/21/26	XLY
Aroclor-1232	ND		ug/Kg	50	0.99	395871	02/20/26	02/21/26	XLY
Aroclor-1242	ND		ug/Kg	50	0.99	395871	02/20/26	02/21/26	XLY
Aroclor-1248	ND		ug/Kg	50	0.99	395871	02/20/26	02/21/26	XLY
Aroclor-1254	**54**		ug/Kg	50	0.99	395871	02/20/26	02/21/26	XLY
Aroclor-1260	ND		ug/Kg	50	0.99	395871	02/20/26	02/21/26	XLY
Aroclor-1262	ND		ug/Kg	50	0.99	395871	02/20/26	02/21/26	XLY
Aroclor-1268	ND		ug/Kg	50	0.99	395871	02/20/26	02/21/26	XLY
Total PCBs	**54**		ug/Kg	50	0.99	395871	02/20/26	02/21/26	XLY
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	91%		%REC	50-127	0.99	395871	02/20/26	02/21/26	XLY

Sample ID: AOC3-SB-45-0.5 **Lab ID: 553195-054** **Collected: 02/13/26 13:40**
Matrix: Soil

553195-054 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3050B									
Lead	**45**		mg/Kg	0.99	0.99	395658	02/18/26	02/19/26	SBW
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	51	1	395871	02/20/26	02/21/26	XLY
Aroclor-1221	ND		ug/Kg	51	1	395871	02/20/26	02/21/26	XLY
Aroclor-1232	ND		ug/Kg	51	1	395871	02/20/26	02/21/26	XLY
Aroclor-1242	ND		ug/Kg	51	1	395871	02/20/26	02/21/26	XLY
Aroclor-1248	ND		ug/Kg	51	1	395871	02/20/26	02/21/26	XLY
Aroclor-1254	ND		ug/Kg	51	1	395871	02/20/26	02/21/26	XLY
Aroclor-1260	ND		ug/Kg	51	1	395871	02/20/26	02/21/26	XLY
Aroclor-1262	ND		ug/Kg	51	1	395871	02/20/26	02/21/26	XLY
Aroclor-1268	ND		ug/Kg	51	1	395871	02/20/26	02/21/26	XLY
Total PCBs	ND		ug/Kg	51	1	395871	02/20/26	02/21/26	XLY
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	86%		%REC	50-127	1	395871	02/20/26	02/21/26	XLY

Results for any subcontracted analyses are not included in this section.

ENTHALPY ANALYTICAL

Analysis Results for 553195

Sample ID: AOC3-SB-44-0.5 **Lab ID: 553195-055** **Collected: 02/13/26 13:50**
Matrix: Soil

553195-055 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3050B									
Lead	**280**		mg/Kg	1.0	1	395658	02/18/26	02/19/26	SBW
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	50	0.99	395871	02/20/26	02/21/26	XLY
Aroclor-1221	ND		ug/Kg	50	0.99	395871	02/20/26	02/21/26	XLY
Aroclor-1232	ND		ug/Kg	50	0.99	395871	02/20/26	02/21/26	XLY
Aroclor-1242	ND		ug/Kg	50	0.99	395871	02/20/26	02/21/26	XLY
Aroclor-1248	ND		ug/Kg	50	0.99	395871	02/20/26	02/21/26	XLY
Aroclor-1254	ND		ug/Kg	50	0.99	395871	02/20/26	02/21/26	XLY
Aroclor-1260	ND		ug/Kg	50	0.99	395871	02/20/26	02/21/26	XLY
Aroclor-1262	ND		ug/Kg	50	0.99	395871	02/20/26	02/21/26	XLY
Aroclor-1268	ND		ug/Kg	50	0.99	395871	02/20/26	02/21/26	XLY
Total PCBs	ND		ug/Kg	50	0.99	395871	02/20/26	02/21/26	XLY
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	79%		%REC	50-127	0.99	395871	02/20/26	02/21/26	XLY

Sample ID: CG-20-0.5 **Lab ID: 553195-059** **Collected: 02/13/26**
Matrix: Soil

553195-059 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 8081A Prep Method: EPA 3546									
alpha-BHC	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
beta-BHC	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
gamma-BHC	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
delta-BHC	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
Heptachlor	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
Aldrin	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
Heptachlor epoxide	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
Endosulfan I	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
Dieldrin	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
4,4'-DDE	**6.2**		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
Endrin	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
Endosulfan II	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
Endosulfan sulfate	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
4,4'-DDD	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
Endrin aldehyde	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
Endrin ketone	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
4,4'-DDT	**10**		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
Methoxychlor	ND		ug/Kg	10	1	395785	02/19/26	02/20/26	KLR
Toxaphene	ND		ug/Kg	100	1	395785	02/19/26	02/20/26	KLR
Chlordane (Technical)	ND		ug/Kg	50	1	395785	02/19/26	02/20/26	KLR
Surrogates				**Limits**					
TCMX	80%		%REC	58-120	1	395785	02/19/26	02/20/26	KLR
Decachlorobiphenyl	87%		%REC	47-120	1	395785	02/19/26	02/20/26	KLR

Results for any subcontracted analyses are not included in this section.

ENTHALPY ANALYTICAL

Analysis Results for 553195

Sample ID: CG-20-2.5	Lab ID: 553195-060	Collected: 02/13/26
	Matrix: Soil	

553195-060 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 8081A Prep Method: EPA 3546									
alpha-BHC	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
beta-BHC	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
gamma-BHC	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
delta-BHC	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
Heptachlor	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
Aldrin	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
Heptachlor epoxide	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
Endosulfan I	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
Dieldrin	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
4,4'-DDE	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
Endrin	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
Endosulfan II	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
Endosulfan sulfate	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
4,4'-DDD	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
Endrin aldehyde	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
Endrin ketone	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
4,4'-DDT	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
Methoxychlor	ND		ug/Kg	10	1	395785	02/19/26	02/20/26	KLR
Toxaphene	ND		ug/Kg	100	1	395785	02/19/26	02/20/26	KLR
Chlordane (Technical)	ND		ug/Kg	50	1	395785	02/19/26	02/20/26	KLR
Surrogates				**Limits**					
TCMX	86%		%REC	58-120	1	395785	02/19/26	02/20/26	KLR
Decachlorobiphenyl	99%		%REC	47-120	1	395785	02/19/26	02/20/26	KLR

Results for any subcontracted analyses are not included in this section.

Analysis Results for 553195

Sample ID: CG-21-0.5	Lab ID: 553195-061	Collected: 02/13/26
	Matrix: Soil	

553195-061 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 8081A Prep Method: EPA 3546									
alpha-BHC	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
beta-BHC	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
gamma-BHC	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
delta-BHC	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
Heptachlor	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
Aldrin	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
Heptachlor epoxide	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
Endosulfan I	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
Dieldrin	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
4,4'-DDE	**6.5**		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
Endrin	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
Endosulfan II	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
Endosulfan sulfate	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
4,4'-DDD	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
Endrin aldehyde	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
Endrin ketone	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
4,4'-DDT	**5.4**		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
Methoxychlor	ND		ug/Kg	10	1	395785	02/19/26	02/20/26	KLR
Toxaphene	ND		ug/Kg	100	1	395785	02/19/26	02/20/26	KLR
Chlordane (Technical)	ND		ug/Kg	50	1	395785	02/19/26	02/20/26	KLR
Surrogates				**Limits**					
TCMX	79%		%REC	58-120	1	395785	02/19/26	02/20/26	KLR
Decachlorobiphenyl	84%		%REC	47-120	1	395785	02/19/26	02/20/26	KLR

Results for any subcontracted analyses are not included in this section.

ENTHALPY ANALYTICAL

Analysis Results for 553195

Sample ID: CG-21-2.5	Lab ID: 553195-062	Collected: 02/13/26
	Matrix: Soil	

553195-062 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 8081A Prep Method: EPA 3546									
alpha-BHC	ND		ug/Kg	5.1	1	395785	02/19/26	02/20/26	KLR
beta-BHC	ND		ug/Kg	5.1	1	395785	02/19/26	02/20/26	KLR
gamma-BHC	ND		ug/Kg	5.1	1	395785	02/19/26	02/20/26	KLR
delta-BHC	ND		ug/Kg	5.1	1	395785	02/19/26	02/20/26	KLR
Heptachlor	ND		ug/Kg	5.1	1	395785	02/19/26	02/20/26	KLR
Aldrin	ND		ug/Kg	5.1	1	395785	02/19/26	02/20/26	KLR
Heptachlor epoxide	ND		ug/Kg	5.1	1	395785	02/19/26	02/20/26	KLR
Endosulfan I	ND		ug/Kg	5.1	1	395785	02/19/26	02/20/26	KLR
Dieldrin	ND		ug/Kg	5.1	1	395785	02/19/26	02/20/26	KLR
4,4'-DDE	ND		ug/Kg	5.1	1	395785	02/19/26	02/20/26	KLR
Endrin	ND		ug/Kg	5.1	1	395785	02/19/26	02/20/26	KLR
Endosulfan II	ND		ug/Kg	5.1	1	395785	02/19/26	02/20/26	KLR
Endosulfan sulfate	ND		ug/Kg	5.1	1	395785	02/19/26	02/20/26	KLR
4,4'-DDD	ND		ug/Kg	5.1	1	395785	02/19/26	02/20/26	KLR
Endrin aldehyde	ND		ug/Kg	5.1	1	395785	02/19/26	02/20/26	KLR
Endrin ketone	ND		ug/Kg	5.1	1	395785	02/19/26	02/20/26	KLR
4,4'-DDT	ND		ug/Kg	5.1	1	395785	02/19/26	02/20/26	KLR
Methoxychlor	ND		ug/Kg	10	1	395785	02/19/26	02/20/26	KLR
Toxaphene	ND		ug/Kg	100	1	395785	02/19/26	02/20/26	KLR
Chlordane (Technical)	ND		ug/Kg	51	1	395785	02/19/26	02/20/26	KLR
Surrogates				**Limits**					
TCMX	87%		%REC	58-120	1	395785	02/19/26	02/20/26	KLR
Decachlorobiphenyl	93%		%REC	47-120	1	395785	02/19/26	02/20/26	KLR

Results for any subcontracted analyses are not included in this section.

ENTHALPY ANALYTICAL

Analysis Results for 553195

Sample ID: CG-22-0.5	Lab ID: 553195-063	Collected: 02/13/26
	Matrix: Soil	

553195-063 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 8081A Prep Method: EPA 3546									
alpha-BHC	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
beta-BHC	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
gamma-BHC	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
delta-BHC	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
Heptachlor	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
Aldrin	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
Heptachlor epoxide	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
Endosulfan I	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
Dieldrin	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
4,4'-DDE	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
Endrin	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
Endosulfan II	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
Endosulfan sulfate	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
4,4'-DDD	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
Endrin aldehyde	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
Endrin ketone	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
4,4'-DDT	**13**	C	ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
Methoxychlor	ND		ug/Kg	10	1	395785	02/19/26	02/20/26	KLR
Toxaphene	ND		ug/Kg	100	1	395785	02/19/26	02/20/26	KLR
Chlordane (Technical)	ND		ug/Kg	50	1	395785	02/19/26	02/20/26	KLR
Surrogates				**Limits**					
TCMX	87%		%REC	58-120	1	395785	02/19/26	02/20/26	KLR
Decachlorobiphenyl	100%		%REC	47-120	1	395785	02/19/26	02/20/26	KLR

Results for any subcontracted analyses are not included in this section.

ENTHALPY ANALYTICAL

Analysis Results for 553195

Sample ID: CG-22-2.5	Lab ID: 553195-064	Collected: 02/13/26
	Matrix: Soil	

553195-064 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 8081A Prep Method: EPA 3546									
alpha-BHC	ND		ug/Kg	4.9	0.98	395785	02/19/26	02/20/26	KLR
beta-BHC	ND		ug/Kg	4.9	0.98	395785	02/19/26	02/20/26	KLR
gamma-BHC	ND		ug/Kg	4.9	0.98	395785	02/19/26	02/20/26	KLR
delta-BHC	ND		ug/Kg	4.9	0.98	395785	02/19/26	02/20/26	KLR
Heptachlor	ND		ug/Kg	4.9	0.98	395785	02/19/26	02/20/26	KLR
Aldrin	ND		ug/Kg	4.9	0.98	395785	02/19/26	02/20/26	KLR
Heptachlor epoxide	ND		ug/Kg	4.9	0.98	395785	02/19/26	02/20/26	KLR
Endosulfan I	ND		ug/Kg	4.9	0.98	395785	02/19/26	02/20/26	KLR
Dieldrin	ND		ug/Kg	4.9	0.98	395785	02/19/26	02/20/26	KLR
4,4'-DDE	ND		ug/Kg	4.9	0.98	395785	02/19/26	02/20/26	KLR
Endrin	ND		ug/Kg	4.9	0.98	395785	02/19/26	02/20/26	KLR
Endosulfan II	ND		ug/Kg	4.9	0.98	395785	02/19/26	02/20/26	KLR
Endosulfan sulfate	ND		ug/Kg	4.9	0.98	395785	02/19/26	02/20/26	KLR
4,4'-DDD	ND		ug/Kg	4.9	0.98	395785	02/19/26	02/20/26	KLR
Endrin aldehyde	ND		ug/Kg	4.9	0.98	395785	02/19/26	02/20/26	KLR
Endrin ketone	ND		ug/Kg	4.9	0.98	395785	02/19/26	02/20/26	KLR
4,4'-DDT	ND		ug/Kg	4.9	0.98	395785	02/19/26	02/20/26	KLR
Methoxychlor	ND		ug/Kg	9.8	0.98	395785	02/19/26	02/20/26	KLR
Toxaphene	ND		ug/Kg	98	0.98	395785	02/19/26	02/20/26	KLR
Chlordane (Technical)	ND		ug/Kg	49	0.98	395785	02/19/26	02/20/26	KLR
Surrogates				**Limits**					
TCMX	80%		%REC	58-120	0.98	395785	02/19/26	02/20/26	KLR
Decachlorobiphenyl	81%		%REC	47-120	0.98	395785	02/19/26	02/20/26	KLR

Results for any subcontracted analyses are not included in this section.

ENTHALPY ANALYTICAL

Analysis Results for 553195

Sample ID: CG-22-0.5-DUP	Lab ID: 553195-065	Collected: 02/13/26
	Matrix: Soil	

553195-065 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 8081A Prep Method: EPA 3546									
alpha-BHC	ND		ug/Kg	25	5	395785	02/19/26	02/20/26	KLR
beta-BHC	ND		ug/Kg	25	5	395785	02/19/26	02/20/26	KLR
gamma-BHC	ND		ug/Kg	25	5	395785	02/19/26	02/20/26	KLR
delta-BHC	ND		ug/Kg	25	5	395785	02/19/26	02/20/26	KLR
Heptachlor	ND		ug/Kg	25	5	395785	02/19/26	02/20/26	KLR
Aldrin	ND		ug/Kg	25	5	395785	02/19/26	02/20/26	KLR
Heptachlor epoxide	ND		ug/Kg	25	5	395785	02/19/26	02/20/26	KLR
Endosulfan I	ND		ug/Kg	25	5	395785	02/19/26	02/20/26	KLR
Dieldrin	ND		ug/Kg	25	5	395785	02/19/26	02/20/26	KLR
4,4'-DDE	ND		ug/Kg	25	5	395785	02/19/26	02/20/26	KLR
Endrin	ND		ug/Kg	25	5	395785	02/19/26	02/20/26	KLR
Endosulfan II	ND		ug/Kg	25	5	395785	02/19/26	02/20/26	KLR
Endosulfan sulfate	ND		ug/Kg	25	5	395785	02/19/26	02/20/26	KLR
4,4'-DDD	ND		ug/Kg	25	5	395785	02/19/26	02/20/26	KLR
Endrin aldehyde	ND		ug/Kg	25	5	395785	02/19/26	02/20/26	KLR
Endrin ketone	ND		ug/Kg	25	5	395785	02/19/26	02/20/26	KLR
4,4'-DDT	ND		ug/Kg	25	5	395785	02/19/26	02/20/26	KLR
Methoxychlor	ND		ug/Kg	50	5	395785	02/19/26	02/20/26	KLR
Toxaphene	ND		ug/Kg	500	5	395785	02/19/26	02/20/26	KLR
Chlordane (Technical)	ND		ug/Kg	250	5	395785	02/19/26	02/20/26	KLR
Surrogates				**Limits**					
TCMX	85%		%REC	58-120	5	395785	02/19/26	02/20/26	KLR
Decachlorobiphenyl	92%		%REC	47-120	5	395785	02/19/26	02/20/26	KLR

Results for any subcontracted analyses are not included in this section.

Analysis Results for 553195

Sample ID: CG-22-2.5-DUP	Lab ID: 553195-066	Collected: 02/13/26
	Matrix: Soil	

553195-066 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 8081A Prep Method: EPA 3546									
alpha-BHC	ND		ug/Kg	5.0	0.99	395785	02/19/26	02/20/26	KLR
beta-BHC	ND		ug/Kg	5.0	0.99	395785	02/19/26	02/20/26	KLR
gamma-BHC	ND		ug/Kg	5.0	0.99	395785	02/19/26	02/20/26	KLR
delta-BHC	ND		ug/Kg	5.0	0.99	395785	02/19/26	02/20/26	KLR
Heptachlor	ND		ug/Kg	5.0	0.99	395785	02/19/26	02/20/26	KLR
Aldrin	ND		ug/Kg	5.0	0.99	395785	02/19/26	02/20/26	KLR
Heptachlor epoxide	ND		ug/Kg	5.0	0.99	395785	02/19/26	02/20/26	KLR
Endosulfan I	ND		ug/Kg	5.0	0.99	395785	02/19/26	02/20/26	KLR
Dieldrin	ND		ug/Kg	5.0	0.99	395785	02/19/26	02/20/26	KLR
4,4'-DDE	ND		ug/Kg	5.0	0.99	395785	02/19/26	02/20/26	KLR
Endrin	ND		ug/Kg	5.0	0.99	395785	02/19/26	02/20/26	KLR
Endosulfan II	ND		ug/Kg	5.0	0.99	395785	02/19/26	02/20/26	KLR
Endosulfan sulfate	ND		ug/Kg	5.0	0.99	395785	02/19/26	02/20/26	KLR
4,4'-DDD	ND		ug/Kg	5.0	0.99	395785	02/19/26	02/20/26	KLR
Endrin aldehyde	ND		ug/Kg	5.0	0.99	395785	02/19/26	02/20/26	KLR
Endrin ketone	ND		ug/Kg	5.0	0.99	395785	02/19/26	02/20/26	KLR
4,4'-DDT	ND		ug/Kg	5.0	0.99	395785	02/19/26	02/20/26	KLR
Methoxychlor	ND		ug/Kg	9.9	0.99	395785	02/19/26	02/20/26	KLR
Toxaphene	ND		ug/Kg	99	0.99	395785	02/19/26	02/20/26	KLR
Chlordane (Technical)	ND		ug/Kg	50	0.99	395785	02/19/26	02/20/26	KLR
Surrogates				**Limits**					
TCMX	93%		%REC	58-120	0.99	395785	02/19/26	02/20/26	KLR
Decachlorobiphenyl	97%		%REC	47-120	0.99	395785	02/19/26	02/20/26	KLR

Results for any subcontracted analyses are not included in this section.

Analysis Results for 553195

Sample ID: CG-23-0.5	Lab ID: 553195-067	Collected: 02/13/26
	Matrix: Soil	

553195-067 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 8081A Prep Method: EPA 3546									
alpha-BHC	ND		ug/Kg	4.9	0.99	395785	02/19/26	02/20/26	KLR
beta-BHC	ND		ug/Kg	4.9	0.99	395785	02/19/26	02/20/26	KLR
gamma-BHC	ND		ug/Kg	4.9	0.99	395785	02/19/26	02/20/26	KLR
delta-BHC	ND		ug/Kg	4.9	0.99	395785	02/19/26	02/20/26	KLR
Heptachlor	ND		ug/Kg	4.9	0.99	395785	02/19/26	02/20/26	KLR
Aldrin	ND		ug/Kg	4.9	0.99	395785	02/19/26	02/20/26	KLR
Heptachlor epoxide	ND		ug/Kg	4.9	0.99	395785	02/19/26	02/20/26	KLR
Endosulfan I	ND		ug/Kg	4.9	0.99	395785	02/19/26	02/20/26	KLR
Dieldrin	ND		ug/Kg	4.9	0.99	395785	02/19/26	02/20/26	KLR
4,4'-DDE	ND		ug/Kg	4.9	0.99	395785	02/19/26	02/20/26	KLR
Endrin	ND		ug/Kg	4.9	0.99	395785	02/19/26	02/20/26	KLR
Endosulfan II	ND		ug/Kg	4.9	0.99	395785	02/19/26	02/20/26	KLR
Endosulfan sulfate	ND		ug/Kg	4.9	0.99	395785	02/19/26	02/20/26	KLR
4,4'-DDD	ND		ug/Kg	4.9	0.99	395785	02/19/26	02/20/26	KLR
Endrin aldehyde	ND		ug/Kg	4.9	0.99	395785	02/19/26	02/20/26	KLR
Endrin ketone	ND		ug/Kg	4.9	0.99	395785	02/19/26	02/20/26	KLR
4,4'-DDT	ND		ug/Kg	4.9	0.99	395785	02/19/26	02/20/26	KLR
Methoxychlor	ND		ug/Kg	9.9	0.99	395785	02/19/26	02/20/26	KLR
Toxaphene	ND		ug/Kg	99	0.99	395785	02/19/26	02/20/26	KLR
Chlordane (Technical)	ND		ug/Kg	49	0.99	395785	02/19/26	02/20/26	KLR
Surrogates				**Limits**					
TCMX	103%		%REC	58-120	0.99	395785	02/19/26	02/20/26	KLR
Decachlorobiphenyl	100%		%REC	47-120	0.99	395785	02/19/26	02/20/26	KLR

Results for any subcontracted analyses are not included in this section.

Analysis Results for 553195

Sample ID: CG-23-2.5	Lab ID: 553195-068	Collected: 02/13/26
	Matrix: Soil	

553195-068 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 8081A Prep Method: EPA 3546									
alpha-BHC	ND		ug/Kg	4.9	0.98	395785	02/19/26	02/20/26	KLR
beta-BHC	ND		ug/Kg	4.9	0.98	395785	02/19/26	02/20/26	KLR
gamma-BHC	ND		ug/Kg	4.9	0.98	395785	02/19/26	02/20/26	KLR
delta-BHC	ND		ug/Kg	4.9	0.98	395785	02/19/26	02/20/26	KLR
Heptachlor	ND		ug/Kg	4.9	0.98	395785	02/19/26	02/20/26	KLR
Aldrin	ND		ug/Kg	4.9	0.98	395785	02/19/26	02/20/26	KLR
Heptachlor epoxide	ND		ug/Kg	4.9	0.98	395785	02/19/26	02/20/26	KLR
Endosulfan I	ND		ug/Kg	4.9	0.98	395785	02/19/26	02/20/26	KLR
Dieldrin	ND		ug/Kg	4.9	0.98	395785	02/19/26	02/20/26	KLR
4,4'-DDE	ND		ug/Kg	4.9	0.98	395785	02/19/26	02/20/26	KLR
Endrin	ND		ug/Kg	4.9	0.98	395785	02/19/26	02/20/26	KLR
Endosulfan II	ND		ug/Kg	4.9	0.98	395785	02/19/26	02/20/26	KLR
Endosulfan sulfate	ND		ug/Kg	4.9	0.98	395785	02/19/26	02/20/26	KLR
4,4'-DDD	ND		ug/Kg	4.9	0.98	395785	02/19/26	02/20/26	KLR
Endrin aldehyde	ND		ug/Kg	4.9	0.98	395785	02/19/26	02/20/26	KLR
Endrin ketone	ND		ug/Kg	4.9	0.98	395785	02/19/26	02/20/26	KLR
4,4'-DDT	ND		ug/Kg	4.9	0.98	395785	02/19/26	02/20/26	KLR
Methoxychlor	ND		ug/Kg	9.8	0.98	395785	02/19/26	02/20/26	KLR
Toxaphene	ND		ug/Kg	98	0.98	395785	02/19/26	02/20/26	KLR
Chlordane (Technical)	ND		ug/Kg	49	0.98	395785	02/19/26	02/20/26	KLR
Surrogates				**Limits**					
TCMX	94%		%REC	58-120	0.98	395785	02/19/26	02/20/26	KLR
Decachlorobiphenyl	100%		%REC	47-120	0.98	395785	02/19/26	02/20/26	KLR

Results for any subcontracted analyses are not included in this section.

Analysis Results for 553195

Sample ID: CG-24-0.5	Lab ID: 553195-069	Collected: 02/13/26
	Matrix: Soil	

553195-069 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 8081A Prep Method: EPA 3546									
alpha-BHC	ND		ug/Kg	4.9	0.99	395785	02/19/26	02/20/26	KLR
beta-BHC	ND		ug/Kg	4.9	0.99	395785	02/19/26	02/20/26	KLR
gamma-BHC	ND		ug/Kg	4.9	0.99	395785	02/19/26	02/20/26	KLR
delta-BHC	ND		ug/Kg	4.9	0.99	395785	02/19/26	02/20/26	KLR
Heptachlor	ND		ug/Kg	4.9	0.99	395785	02/19/26	02/20/26	KLR
Aldrin	ND		ug/Kg	4.9	0.99	395785	02/19/26	02/20/26	KLR
Heptachlor epoxide	ND		ug/Kg	4.9	0.99	395785	02/19/26	02/20/26	KLR
Endosulfan I	ND		ug/Kg	4.9	0.99	395785	02/19/26	02/20/26	KLR
Dieldrin	ND		ug/Kg	4.9	0.99	395785	02/19/26	02/20/26	KLR
4,4'-DDE	ND		ug/Kg	4.9	0.99	395785	02/19/26	02/20/26	KLR
Endrin	ND		ug/Kg	4.9	0.99	395785	02/19/26	02/20/26	KLR
Endosulfan II	ND		ug/Kg	4.9	0.99	395785	02/19/26	02/20/26	KLR
Endosulfan sulfate	ND		ug/Kg	4.9	0.99	395785	02/19/26	02/20/26	KLR
4,4'-DDD	ND		ug/Kg	4.9	0.99	395785	02/19/26	02/20/26	KLR
Endrin aldehyde	ND		ug/Kg	4.9	0.99	395785	02/19/26	02/20/26	KLR
Endrin ketone	ND		ug/Kg	4.9	0.99	395785	02/19/26	02/20/26	KLR
4,4'-DDT	**10**		ug/Kg	4.9	0.99	395785	02/19/26	02/20/26	KLR
Methoxychlor	ND		ug/Kg	9.9	0.99	395785	02/19/26	02/20/26	KLR
Toxaphene	ND		ug/Kg	99	0.99	395785	02/19/26	02/20/26	KLR
Chlordane (Technical)	ND		ug/Kg	49	0.99	395785	02/19/26	02/20/26	KLR
Surrogates				**Limits**					
TCMX	81%		%REC	58-120	0.99	395785	02/19/26	02/20/26	KLR
Decachlorobiphenyl	88%		%REC	47-120	0.99	395785	02/19/26	02/20/26	KLR

Results for any subcontracted analyses are not included in this section.

ENTHALPY ANALYTICAL

Analysis Results for 553195

Sample ID: CG-24-2.5	Lab ID: 553195-070	Collected: 02/13/26
	Matrix: Soil	

553195-070 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 8081A Prep Method: EPA 3546									
alpha-BHC	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
beta-BHC	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
gamma-BHC	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
delta-BHC	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
Heptachlor	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
Aldrin	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
Heptachlor epoxide	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
Endosulfan I	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
Dieldrin	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
4,4'-DDE	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
Endrin	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
Endosulfan II	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
Endosulfan sulfate	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
4,4'-DDD	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
Endrin aldehyde	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
Endrin ketone	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
4,4'-DDT	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
Methoxychlor	ND		ug/Kg	10	1	395785	02/19/26	02/20/26	KLR
Toxaphene	ND		ug/Kg	100	1	395785	02/19/26	02/20/26	KLR
Chlordane (Technical)	ND		ug/Kg	50	1	395785	02/19/26	02/20/26	KLR
Surrogates				**Limits**					
TCMX	89%		%REC	58-120	1	395785	02/19/26	02/20/26	KLR
Decachlorobiphenyl	92%		%REC	47-120	1	395785	02/19/26	02/20/26	KLR

Results for any subcontracted analyses are not included in this section.

ENTHALPY ANALYTICAL

Analysis Results for 553195

Sample ID: CG-25-0.5	Lab ID: 553195-071	Collected: 02/13/26
	Matrix: Soil	

553195-071 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 8081A Prep Method: EPA 3546									
alpha-BHC	ND		ug/Kg	10	2	395785	02/19/26	02/20/26	KLR
beta-BHC	ND		ug/Kg	10	2	395785	02/19/26	02/20/26	KLR
gamma-BHC	ND		ug/Kg	10	2	395785	02/19/26	02/20/26	KLR
delta-BHC	ND		ug/Kg	10	2	395785	02/19/26	02/20/26	KLR
Heptachlor	ND		ug/Kg	10	2	395785	02/19/26	02/20/26	KLR
Aldrin	ND		ug/Kg	10	2	395785	02/19/26	02/20/26	KLR
Heptachlor epoxide	ND		ug/Kg	10	2	395785	02/19/26	02/20/26	KLR
Endosulfan I	ND		ug/Kg	10	2	395785	02/19/26	02/20/26	KLR
Dieldrin	ND		ug/Kg	10	2	395785	02/19/26	02/20/26	KLR
4,4'-DDE	ND		ug/Kg	10	2	395785	02/19/26	02/20/26	KLR
Endrin	ND		ug/Kg	10	2	395785	02/19/26	02/20/26	KLR
Endosulfan II	ND		ug/Kg	10	2	395785	02/19/26	02/20/26	KLR
Endosulfan sulfate	ND		ug/Kg	10	2	395785	02/19/26	02/20/26	KLR
4,4'-DDD	ND		ug/Kg	10	2	395785	02/19/26	02/20/26	KLR
Endrin aldehyde	ND		ug/Kg	10	2	395785	02/19/26	02/20/26	KLR
Endrin ketone	ND		ug/Kg	10	2	395785	02/19/26	02/20/26	KLR
4,4'-DDT	ND		ug/Kg	10	2	395785	02/19/26	02/20/26	KLR
Methoxychlor	ND		ug/Kg	20	2	395785	02/19/26	02/20/26	KLR
Toxaphene	ND		ug/Kg	200	2	395785	02/19/26	02/20/26	KLR
Chlordane (Technical)	ND		ug/Kg	100	2	395785	02/19/26	02/20/26	KLR
Surrogates				**Limits**					
TCMX	79%		%REC	58-120	2	395785	02/19/26	02/20/26	KLR
Decachlorobiphenyl	82%		%REC	47-120	2	395785	02/19/26	02/20/26	KLR

Results for any subcontracted analyses are not included in this section.

ENTHALPY ANALYTICAL

Analysis Results for 553195

Sample ID: CG-25-2.5	Lab ID: 553195-072	Collected: 02/13/26
	Matrix: Soil	

553195-072 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 8081A Prep Method: EPA 3546									
alpha-BHC	ND		ug/Kg	4.9	0.99	395785	02/19/26	02/20/26	KLR
beta-BHC	ND		ug/Kg	4.9	0.99	395785	02/19/26	02/20/26	KLR
gamma-BHC	ND		ug/Kg	4.9	0.99	395785	02/19/26	02/20/26	KLR
delta-BHC	ND		ug/Kg	4.9	0.99	395785	02/19/26	02/20/26	KLR
Heptachlor	ND		ug/Kg	4.9	0.99	395785	02/19/26	02/20/26	KLR
Aldrin	ND		ug/Kg	4.9	0.99	395785	02/19/26	02/20/26	KLR
Heptachlor epoxide	ND		ug/Kg	4.9	0.99	395785	02/19/26	02/20/26	KLR
Endosulfan I	ND		ug/Kg	4.9	0.99	395785	02/19/26	02/20/26	KLR
Dieldrin	ND		ug/Kg	4.9	0.99	395785	02/19/26	02/20/26	KLR
4,4'-DDE	ND		ug/Kg	4.9	0.99	395785	02/19/26	02/20/26	KLR
Endrin	ND		ug/Kg	4.9	0.99	395785	02/19/26	02/20/26	KLR
Endosulfan II	ND		ug/Kg	4.9	0.99	395785	02/19/26	02/20/26	KLR
Endosulfan sulfate	ND		ug/Kg	4.9	0.99	395785	02/19/26	02/20/26	KLR
4,4'-DDD	ND		ug/Kg	4.9	0.99	395785	02/19/26	02/20/26	KLR
Endrin aldehyde	ND		ug/Kg	4.9	0.99	395785	02/19/26	02/20/26	KLR
Endrin ketone	ND		ug/Kg	4.9	0.99	395785	02/19/26	02/20/26	KLR
4,4'-DDT	ND		ug/Kg	4.9	0.99	395785	02/19/26	02/20/26	KLR
Methoxychlor	ND		ug/Kg	9.9	0.99	395785	02/19/26	02/20/26	KLR
Toxaphene	ND		ug/Kg	99	0.99	395785	02/19/26	02/20/26	KLR
Chlordane (Technical)	ND		ug/Kg	49	0.99	395785	02/19/26	02/20/26	KLR
Surrogates				**Limits**					
TCMX	88%		%REC	58-120	0.99	395785	02/19/26	02/20/26	KLR
Decachlorobiphenyl	90%		%REC	47-120	0.99	395785	02/19/26	02/20/26	KLR

Results for any subcontracted analyses are not included in this section.

Analysis Results for 553195

Sample ID: CG-26-0.5	Lab ID: 553195-073	Collected: 02/13/26
	Matrix: Soil	

553195-073 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 8081A Prep Method: EPA 3546									
alpha-BHC	ND		ug/Kg	10	2	395785	02/19/26	02/20/26	KLR
beta-BHC	ND		ug/Kg	10	2	395785	02/19/26	02/20/26	KLR
gamma-BHC	ND		ug/Kg	10	2	395785	02/19/26	02/20/26	KLR
delta-BHC	ND		ug/Kg	10	2	395785	02/19/26	02/20/26	KLR
Heptachlor	ND		ug/Kg	10	2	395785	02/19/26	02/20/26	KLR
Aldrin	ND		ug/Kg	10	2	395785	02/19/26	02/20/26	KLR
Heptachlor epoxide	ND		ug/Kg	10	2	395785	02/19/26	02/20/26	KLR
Endosulfan I	ND		ug/Kg	10	2	395785	02/19/26	02/20/26	KLR
Dieldrin	ND		ug/Kg	10	2	395785	02/19/26	02/20/26	KLR
4,4'-DDE	ND		ug/Kg	10	2	395785	02/19/26	02/20/26	KLR
Endrin	ND		ug/Kg	10	2	395785	02/19/26	02/20/26	KLR
Endosulfan II	ND		ug/Kg	10	2	395785	02/19/26	02/20/26	KLR
Endosulfan sulfate	ND		ug/Kg	10	2	395785	02/19/26	02/20/26	KLR
4,4'-DDD	ND		ug/Kg	10	2	395785	02/19/26	02/20/26	KLR
Endrin aldehyde	ND		ug/Kg	10	2	395785	02/19/26	02/20/26	KLR
Endrin ketone	ND		ug/Kg	10	2	395785	02/19/26	02/20/26	KLR
4,4'-DDT	ND		ug/Kg	10	2	395785	02/19/26	02/20/26	KLR
Methoxychlor	ND		ug/Kg	20	2	395785	02/19/26	02/20/26	KLR
Toxaphene	ND		ug/Kg	200	2	395785	02/19/26	02/20/26	KLR
Chlordane (Technical)	ND		ug/Kg	100	2	395785	02/19/26	02/20/26	KLR
Surrogates				**Limits**					
TCMX	96%		%REC	58-120	2	395785	02/19/26	02/20/26	KLR
Decachlorobiphenyl	110%		%REC	47-120	2	395785	02/19/26	02/20/26	KLR

Results for any subcontracted analyses are not included in this section.

ENTHALPY ANALYTICAL

Analysis Results for 553195

Sample ID: CG-26-2.5	Lab ID: 553195-074	Collected: 02/13/26
	Matrix: Soil	

553195-074 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 8081A Prep Method: EPA 3546									
alpha-BHC	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
beta-BHC	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
gamma-BHC	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
delta-BHC	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
Heptachlor	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
Aldrin	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
Heptachlor epoxide	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
Endosulfan I	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
Dieldrin	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
4,4'-DDE	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
Endrin	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
Endosulfan II	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
Endosulfan sulfate	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
4,4'-DDD	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
Endrin aldehyde	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
Endrin ketone	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
4,4'-DDT	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
Methoxychlor	ND		ug/Kg	10	1	395785	02/19/26	02/20/26	KLR
Toxaphene	ND		ug/Kg	100	1	395785	02/19/26	02/20/26	KLR
Chlordane (Technical)	ND		ug/Kg	50	1	395785	02/19/26	02/20/26	KLR
Surrogates				**Limits**					
TCMX	91%		%REC	58-120	1	395785	02/19/26	02/20/26	KLR
Decachlorobiphenyl	97%		%REC	47-120	1	395785	02/19/26	02/20/26	KLR

Results for any subcontracted analyses are not included in this section.

ENTHALPY ANALYTICAL

Analysis Results for 553195

Sample ID: CG-26-0.5-DUP	Lab ID: 553195-075	Collected: 02/13/26
	Matrix: Soil	

553195-075 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 8081A Prep Method: EPA 3546									
alpha-BHC	ND		ug/Kg	9.8	2	395785	02/19/26	02/20/26	KLR
beta-BHC	ND		ug/Kg	9.8	2	395785	02/19/26	02/20/26	KLR
gamma-BHC	ND		ug/Kg	9.8	2	395785	02/19/26	02/20/26	KLR
delta-BHC	ND		ug/Kg	9.8	2	395785	02/19/26	02/20/26	KLR
Heptachlor	ND		ug/Kg	9.8	2	395785	02/19/26	02/20/26	KLR
Aldrin	ND		ug/Kg	9.8	2	395785	02/19/26	02/20/26	KLR
Heptachlor epoxide	ND		ug/Kg	9.8	2	395785	02/19/26	02/20/26	KLR
Endosulfan I	ND		ug/Kg	9.8	2	395785	02/19/26	02/20/26	KLR
Dieldrin	ND		ug/Kg	9.8	2	395785	02/19/26	02/20/26	KLR
4,4'-DDE	ND		ug/Kg	9.8	2	395785	02/19/26	02/20/26	KLR
Endrin	ND		ug/Kg	9.8	2	395785	02/19/26	02/20/26	KLR
Endosulfan II	ND		ug/Kg	9.8	2	395785	02/19/26	02/20/26	KLR
Endosulfan sulfate	ND		ug/Kg	9.8	2	395785	02/19/26	02/20/26	KLR
4,4'-DDD	ND		ug/Kg	9.8	2	395785	02/19/26	02/20/26	KLR
Endrin aldehyde	ND		ug/Kg	9.8	2	395785	02/19/26	02/20/26	KLR
Endrin ketone	ND		ug/Kg	9.8	2	395785	02/19/26	02/20/26	KLR
4,4'-DDT	ND		ug/Kg	9.8	2	395785	02/19/26	02/20/26	KLR
Methoxychlor	ND		ug/Kg	20	2	395785	02/19/26	02/20/26	KLR
Toxaphene	ND		ug/Kg	200	2	395785	02/19/26	02/20/26	KLR
Chlordane (Technical)	ND		ug/Kg	98	2	395785	02/19/26	02/20/26	KLR
Surrogates				**Limits**					
TCMX	94%		%REC	58-120	2	395785	02/19/26	02/20/26	KLR
Decachlorobiphenyl	97%		%REC	47-120	2	395785	02/19/26	02/20/26	KLR

Results for any subcontracted analyses are not included in this section.

Analysis Results for 553195

Sample ID: CG-26-2.5-DUP	Lab ID: 553195-076	Collected: 02/13/26
	Matrix: Soil	

553195-076 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 8081A Prep Method: EPA 3546									
alpha-BHC	ND		ug/Kg	4.9	0.99	395785	02/19/26	02/20/26	KLR
beta-BHC	ND		ug/Kg	4.9	0.99	395785	02/19/26	02/20/26	KLR
gamma-BHC	ND		ug/Kg	4.9	0.99	395785	02/19/26	02/20/26	KLR
delta-BHC	ND		ug/Kg	4.9	0.99	395785	02/19/26	02/20/26	KLR
Heptachlor	ND		ug/Kg	4.9	0.99	395785	02/19/26	02/20/26	KLR
Aldrin	ND		ug/Kg	4.9	0.99	395785	02/19/26	02/20/26	KLR
Heptachlor epoxide	ND		ug/Kg	4.9	0.99	395785	02/19/26	02/20/26	KLR
Endosulfan I	ND		ug/Kg	4.9	0.99	395785	02/19/26	02/20/26	KLR
Dieldrin	ND		ug/Kg	4.9	0.99	395785	02/19/26	02/20/26	KLR
4,4'-DDE	ND		ug/Kg	4.9	0.99	395785	02/19/26	02/20/26	KLR
Endrin	ND		ug/Kg	4.9	0.99	395785	02/19/26	02/20/26	KLR
Endosulfan II	ND		ug/Kg	4.9	0.99	395785	02/19/26	02/20/26	KLR
Endosulfan sulfate	ND		ug/Kg	4.9	0.99	395785	02/19/26	02/20/26	KLR
4,4'-DDD	ND		ug/Kg	4.9	0.99	395785	02/19/26	02/20/26	KLR
Endrin aldehyde	ND		ug/Kg	4.9	0.99	395785	02/19/26	02/20/26	KLR
Endrin ketone	ND		ug/Kg	4.9	0.99	395785	02/19/26	02/20/26	KLR
4,4'-DDT	ND		ug/Kg	4.9	0.99	395785	02/19/26	02/20/26	KLR
Methoxychlor	ND		ug/Kg	9.9	0.99	395785	02/19/26	02/20/26	KLR
Toxaphene	ND		ug/Kg	99	0.99	395785	02/19/26	02/20/26	KLR
Chlordane (Technical)	ND		ug/Kg	49	0.99	395785	02/19/26	02/20/26	KLR
Surrogates				**Limits**					
TCMX	105%		%REC	58-120	0.99	395785	02/19/26	02/20/26	KLR
Decachlorobiphenyl	103%		%REC	47-120	0.99	395785	02/19/26	02/20/26	KLR

Results for any subcontracted analyses are not included in this section.

ENTHALPY ANALYTICAL

Analysis Results for 553195

Sample ID: CG-27-0.5	Lab ID: 553195-077	Collected: 02/13/26
	Matrix: Soil	

553195-077 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 8081A Prep Method: EPA 3546									
alpha-BHC	ND		ug/Kg	25	5	395785	02/19/26	02/20/26	KLR
beta-BHC	ND		ug/Kg	25	5	395785	02/19/26	02/20/26	KLR
gamma-BHC	ND		ug/Kg	25	5	395785	02/19/26	02/20/26	KLR
delta-BHC	ND		ug/Kg	25	5	395785	02/19/26	02/20/26	KLR
Heptachlor	ND		ug/Kg	25	5	395785	02/19/26	02/20/26	KLR
Aldrin	ND		ug/Kg	25	5	395785	02/19/26	02/20/26	KLR
Heptachlor epoxide	ND		ug/Kg	25	5	395785	02/19/26	02/20/26	KLR
Endosulfan I	ND		ug/Kg	25	5	395785	02/19/26	02/20/26	KLR
Dieldrin	ND		ug/Kg	25	5	395785	02/19/26	02/20/26	KLR
4,4'-DDE	ND		ug/Kg	25	5	395785	02/19/26	02/20/26	KLR
Endrin	ND		ug/Kg	25	5	395785	02/19/26	02/20/26	KLR
Endosulfan II	ND		ug/Kg	25	5	395785	02/19/26	02/20/26	KLR
Endosulfan sulfate	ND		ug/Kg	25	5	395785	02/19/26	02/20/26	KLR
4,4'-DDD	ND		ug/Kg	25	5	395785	02/19/26	02/20/26	KLR
Endrin aldehyde	ND		ug/Kg	25	5	395785	02/19/26	02/20/26	KLR
Endrin ketone	ND		ug/Kg	25	5	395785	02/19/26	02/20/26	KLR
4,4'-DDT	ND		ug/Kg	25	5	395785	02/19/26	02/20/26	KLR
Methoxychlor	ND		ug/Kg	50	5	395785	02/19/26	02/20/26	KLR
Toxaphene	ND		ug/Kg	500	5	395785	02/19/26	02/20/26	KLR
Chlordane (Technical)	ND		ug/Kg	250	5	395785	02/19/26	02/20/26	KLR
Surrogates				**Limits**					
TCMX	94%		%REC	58-120	5	395785	02/19/26	02/20/26	KLR
Decachlorobiphenyl	87%		%REC	47-120	5	395785	02/19/26	02/20/26	KLR

Results for any subcontracted analyses are not included in this section.

ENTHALPY ANALYTICAL

Analysis Results for 553195

Sample ID: CG-27-2.5	Lab ID: 553195-078	Collected: 02/13/26
	Matrix: Soil	

553195-078 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 8081A Prep Method: EPA 3546									
alpha-BHC	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
beta-BHC	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
gamma-BHC	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
delta-BHC	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
Heptachlor	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
Aldrin	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
Heptachlor epoxide	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
Endosulfan I	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
Dieldrin	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
4,4'-DDE	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
Endrin	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
Endosulfan II	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
Endosulfan sulfate	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
4,4'-DDD	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
Endrin aldehyde	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
Endrin ketone	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
4,4'-DDT	ND		ug/Kg	5.0	1	395785	02/19/26	02/20/26	KLR
Methoxychlor	ND		ug/Kg	10	1	395785	02/19/26	02/20/26	KLR
Toxaphene	ND		ug/Kg	100	1	395785	02/19/26	02/20/26	KLR
Chlordane (Technical)	ND		ug/Kg	50	1	395785	02/19/26	02/20/26	KLR
Surrogates				**Limits**					
TCMX	95%		%REC	58-120	1	395785	02/19/26	02/20/26	KLR
Decachlorobiphenyl	93%		%REC	47-120	1	395785	02/19/26	02/20/26	KLR

Results for any subcontracted analyses are not included in this section.

ENTHALPY ANALYTICAL

Analysis Results for 553195

Sample ID: CG-29-0.5	Lab ID: 553195-079	Collected: 02/13/26
	Matrix: Soil	

553195-079 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 8081A Prep Method: EPA 3546									
alpha-BHC	ND		ug/Kg	10	2	395755	02/19/26	02/20/26	HQN
beta-BHC	ND		ug/Kg	10	2	395755	02/19/26	02/20/26	HQN
gamma-BHC	ND		ug/Kg	10	2	395755	02/19/26	02/20/26	HQN
delta-BHC	ND		ug/Kg	10	2	395755	02/19/26	02/20/26	HQN
Heptachlor	ND		ug/Kg	10	2	395755	02/19/26	02/20/26	HQN
Aldrin	ND		ug/Kg	10	2	395755	02/19/26	02/20/26	HQN
Heptachlor epoxide	ND		ug/Kg	10	2	395755	02/19/26	02/20/26	HQN
Endosulfan I	ND		ug/Kg	10	2	395755	02/19/26	02/20/26	HQN
Dieldrin	ND		ug/Kg	10	2	395755	02/19/26	02/20/26	HQN
4,4'-DDE	ND		ug/Kg	10	2	395755	02/19/26	02/20/26	HQN
Endrin	ND		ug/Kg	10	2	395755	02/19/26	02/20/26	HQN
Endosulfan II	ND		ug/Kg	10	2	395755	02/19/26	02/20/26	HQN
Endosulfan sulfate	ND		ug/Kg	10	2	395755	02/19/26	02/20/26	HQN
4,4'-DDD	ND		ug/Kg	10	2	395755	02/19/26	02/20/26	HQN
Endrin aldehyde	ND		ug/Kg	10	2	395755	02/19/26	02/20/26	HQN
Endrin ketone	ND		ug/Kg	10	2	395755	02/19/26	02/20/26	HQN
4,4'-DDT	**12**		ug/Kg	10	2	395755	02/19/26	02/20/26	HQN
Methoxychlor	ND		ug/Kg	20	2	395755	02/19/26	02/20/26	HQN
Toxaphene	ND		ug/Kg	200	2	395755	02/19/26	02/20/26	HQN
Chlordane (Technical)	ND		ug/Kg	100	2	395755	02/19/26	02/20/26	HQN
Surrogates				**Limits**					
TCMX	95%		%REC	58-120	2	395755	02/19/26	02/20/26	HQN
Decachlorobiphenyl	100%		%REC	47-120	2	395755	02/19/26	02/20/26	HQN

Results for any subcontracted analyses are not included in this section.

Analysis Results for 553195

Sample ID: CG-29-2.5	Lab ID: 553195-080	Collected: 02/13/26
	Matrix: Soil	

553195-080 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 8081A Prep Method: EPA 3546									
alpha-BHC	ND		ug/Kg	5.1	1	395755	02/19/26	02/20/26	HQN
beta-BHC	ND		ug/Kg	5.1	1	395755	02/19/26	02/20/26	HQN
gamma-BHC	ND		ug/Kg	5.1	1	395755	02/19/26	02/20/26	HQN
delta-BHC	ND		ug/Kg	5.1	1	395755	02/19/26	02/20/26	HQN
Heptachlor	ND		ug/Kg	5.1	1	395755	02/19/26	02/20/26	HQN
Aldrin	ND		ug/Kg	5.1	1	395755	02/19/26	02/20/26	HQN
Heptachlor epoxide	ND		ug/Kg	5.1	1	395755	02/19/26	02/20/26	HQN
Endosulfan I	ND		ug/Kg	5.1	1	395755	02/19/26	02/20/26	HQN
Dieldrin	ND		ug/Kg	5.1	1	395755	02/19/26	02/20/26	HQN
4,4'-DDE	**8.1**		ug/Kg	5.1	1	395755	02/19/26	02/20/26	HQN
Endrin	ND		ug/Kg	5.1	1	395755	02/19/26	02/20/26	HQN
Endosulfan II	ND		ug/Kg	5.1	1	395755	02/19/26	02/20/26	HQN
Endosulfan sulfate	ND		ug/Kg	5.1	1	395755	02/19/26	02/20/26	HQN
4,4'-DDD	ND		ug/Kg	5.1	1	395755	02/19/26	02/20/26	HQN
Endrin aldehyde	ND		ug/Kg	5.1	1	395755	02/19/26	02/20/26	HQN
Endrin ketone	ND		ug/Kg	5.1	1	395755	02/19/26	02/20/26	HQN
4,4'-DDT	ND		ug/Kg	5.1	1	395755	02/19/26	02/20/26	HQN
Methoxychlor	ND		ug/Kg	10	1	395755	02/19/26	02/20/26	HQN
Toxaphene	ND		ug/Kg	100	1	395755	02/19/26	02/20/26	HQN
Chlordane (Technical)	ND		ug/Kg	51	1	395755	02/19/26	02/20/26	HQN
Surrogates				**Limits**					
TCMX	86%		%REC	58-120	1	395755	02/19/26	02/20/26	HQN
Decachlorobiphenyl	105%		%REC	47-120	1	395755	02/19/26	02/20/26	HQN

Results for any subcontracted analyses are not included in this section.

ENTHALPY ANALYTICAL

Analysis Results for 553195

Sample ID: EB-01-260213	Lab ID: 553195-081	Collected: 02/13/26 14:15
	Matrix: Water	

553195-081 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3015A									
Lead	ND		mg/L	0.010	1	395445	02/16/26	02/16/26	KAM
Method: EPA 8081A Prep Method: EPA 3510C									
alpha-BHC	ND		ug/L	0.05	1	395462	02/17/26	02/18/26	HQN
beta-BHC	ND		ug/L	0.05	1	395462	02/17/26	02/18/26	HQN
gamma-BHC	ND		ug/L	0.05	1	395462	02/17/26	02/18/26	HQN
delta-BHC	ND		ug/L	0.05	1	395462	02/17/26	02/18/26	HQN
Heptachlor	ND		ug/L	0.05	1	395462	02/17/26	02/18/26	HQN
Aldrin	ND		ug/L	0.05	1	395462	02/17/26	02/18/26	HQN
Heptachlor epoxide	ND		ug/L	0.05	1	395462	02/17/26	02/18/26	HQN
Endosulfan I	ND		ug/L	0.05	1	395462	02/17/26	02/18/26	HQN
Dieldrin	ND		ug/L	0.1	1	395462	02/17/26	02/18/26	HQN
4,4'-DDE	ND		ug/L	0.1	1	395462	02/17/26	02/18/26	HQN
Endrin	ND		ug/L	0.1	1	395462	02/17/26	02/18/26	HQN
Endosulfan II	ND		ug/L	0.1	1	395462	02/17/26	02/18/26	HQN
Endosulfan sulfate	ND		ug/L	0.1	1	395462	02/17/26	02/18/26	HQN
4,4'-DDD	ND		ug/L	0.1	1	395462	02/17/26	02/18/26	HQN
Endrin aldehyde	ND		ug/L	0.1	1	395462	02/17/26	02/18/26	HQN
Endrin ketone	ND		ug/L	0.1	1	395462	02/17/26	02/18/26	HQN
4,4'-DDT	ND		ug/L	0.1	1	395462	02/17/26	02/18/26	HQN
Methoxychlor	ND		ug/L	0.1	1	395462	02/17/26	02/18/26	HQN
Toxaphene	ND		ug/L	2.0	1	395462	02/17/26	02/18/26	HQN
Chlordane (Technical)	ND		ug/L	1.0	1	395462	02/17/26	02/18/26	HQN
Surrogates				**Limits**					
TCMX	78%		%REC	29-120	1	395462	02/17/26	02/18/26	HQN
Decachlorobiphenyl	89%		%REC	33-132	1	395462	02/17/26	02/18/26	HQN
Method: EPA 8082 Prep Method: EPA 3510C									
Aroclor-1016	ND		ug/L	0.50	1	395462	02/17/26	02/18/26	HQN
Aroclor-1221	ND		ug/L	0.50	1	395462	02/17/26	02/18/26	HQN
Aroclor-1232	ND		ug/L	0.50	1	395462	02/17/26	02/18/26	HQN
Aroclor-1242	ND		ug/L	0.50	1	395462	02/17/26	02/18/26	HQN
Aroclor-1248	ND		ug/L	0.50	1	395462	02/17/26	02/18/26	HQN
Aroclor-1254	ND		ug/L	0.50	1	395462	02/17/26	02/18/26	HQN
Aroclor-1260	ND		ug/L	0.50	1	395462	02/17/26	02/18/26	HQN
Aroclor-1262	ND		ug/L	0.50	1	395462	02/17/26	02/18/26	HQN
Aroclor-1268	ND		ug/L	0.50	1	395462	02/17/26	02/18/26	HQN
Total PCBs	ND		ug/L	0.50	1	395462	02/17/26	02/18/26	HQN
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	74%		%REC	28-138	1	395462	02/17/26	02/18/26	HQN

* Value is outside QC limits
C Presence confirmed, but RPD between columns exceeds 40%
ND Not Detected

Results for any subcontracted analyses are not included in this section.

ENTHALPY ANALYTICAL

Batch QC

Type: Blank	Lab ID: QC1340925	Batch: 395445
Matrix: Water	Method: EPA 6010B	Prep Method: EPA 3015A

QC1340925 Analyte	Result	Qual	Units	RL	Prepared	Analyzed
Lead	ND		mg/L	0.010	02/16/26	02/16/26

Type: Lab Control Sample	Lab ID: QC1340926	Batch: 395445
Matrix: Water	Method: EPA 6010B	Prep Method: EPA 3015A

QC1340926 Analyte	Result	Spiked	Units	Recovery	Qual	Limits
Lead	0.3628	0.4000	mg/L	91%		80-120

Type: Matrix Spike	Lab ID: QC1340927	Batch: 395445
Matrix (Source ID): Water (553195-081)	Method: EPA 6010B	Prep Method: EPA 3015A

QC1340927 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	DF
Lead	0.3475	ND	0.4000	mg/L	87%		75-125	1

Type: Matrix Spike Duplicate	Lab ID: QC1340928	Batch: 395445
Matrix (Source ID): Water (553195-081)	Method: EPA 6010B	Prep Method: EPA 3015A

QC1340928 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	RPD	RPD Lim	DF
Lead	0.3441	ND	0.4000	mg/L	86%		75-125	1	20	1

Type: Serial Dilution	Lab ID: QC1340929	Batch: 395445
Matrix (Source ID): Water (553201-003)	Method: EPA 6010B	Prep Method: EPA 3015A

QC1340929 Analyte	Result	Source Sample Result	Units	Qual	RPD	RPD Lim	DF
Lead	0.2734	0.3482	mg/L	J			50

Type: Blank	Lab ID: QC1341582	Batch: 395654
Matrix: Soil	Method: EPA 6010B	Prep Method: EPA 3050B

QC1341582 Analyte	Result	Qual	Units	RL	Prepared	Analyzed
Lead	ND		mg/Kg	1.0	02/18/26	02/18/26

Type: Lab Control Sample	Lab ID: QC1341583	Batch: 395654
Matrix: Soil	Method: EPA 6010B	Prep Method: EPA 3050B

QC1341583 Analyte	Result	Spiked	Units	Recovery	Qual	Limits
Lead	97.03	100.0	mg/Kg	97%		80-120

ENTHALPY ANALYTICAL

Batch QC

Type:	Matrix Spike	Lab ID:	QC1341584	Batch:	395654
Matrix (Source ID):	Soil (553195-001)	Method:	EPA 6010B	Prep Method:	EPA 3050B

QC1341584 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	DF
Lead	138.0	43.76	99.01	mg/Kg	95%		75-125	0.99

Type:	Matrix Spike Duplicate	Lab ID:	QC1341585	Batch:	395654
Matrix (Source ID):	Soil (553195-001)	Method:	EPA 6010B	Prep Method:	EPA 3050B

QC1341585 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	RPD	RPD Lim	DF
Lead	114.6	43.76	100.0	mg/Kg	71%	*	75-125	19	28	1

Type:	Post Digest Spike	Lab ID:	QC1341755	Batch:	395654
Matrix (Source ID):	Soil (553195-001)	Method:	EPA 6010B	Prep Method:	EPA 3050B

QC1341755 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	DF
Lead	130.2	43.76	99.01	mg/Kg	87%		75-125	0.99

Type:	Serial Dilution	Lab ID:	QC1341756	Batch:	395654
Matrix (Source ID):	Soil (553195-001)	Method:	EPA 6010B	Prep Method:	EPA 3050B

QC1341756 Analyte	Result	Source Sample Result	Units	Qual	RPD	RPD Lim	DF
Lead	45.36	43.76	mg/Kg				5

Type:	Blank	Lab ID:	QC1341594	Batch:	395658
Matrix:	Soil	Method:	EPA 6010B	Prep Method:	EPA 3050B

QC1341594 Analyte	Result	Qual	Units	RL	Prepared	Analyzed
Lead	ND		mg/Kg	1.0	02/18/26	02/18/26

Type:	Lab Control Sample	Lab ID:	QC1341595	Batch:	395658
Matrix:	Soil	Method:	EPA 6010B	Prep Method:	EPA 3050B

QC1341595 Analyte	Result	Spiked	Units	Recovery	Qual	Limits
Lead	101.0	100.0	mg/Kg	101%		80-120

ENTHALPY ANALYTICAL

Batch QC

Type:	Matrix Spike	Lab ID:	QC1341596	Batch:	395658
Matrix (Source ID):	Soil (553279-001)	Method:	EPA 6010B	Prep Method:	EPA 3050B

QC1341596 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	DF
Lead	106.3	4.988	98.04	mg/Kg	103%		75-125	0.98

Type:	Matrix Spike Duplicate	Lab ID:	QC1341597	Batch:	395658
Matrix (Source ID):	Soil (553279-001)	Method:	EPA 6010B	Prep Method:	EPA 3050B

QC1341597 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	RPD	RPD Lim	DF
Lead	108.4	4.988	100.0	mg/Kg	103%		75-125	0	28	1

Type:	Serial Dilution	Lab ID:	QC1341779	Batch:	395658
Matrix (Source ID):	Soil (553279-001)	Method:	EPA 6010B	Prep Method:	EPA 3050B

QC1341779 Analyte	Result	Source Sample Result	Units	Qual	RPD	RPD Lim	DF
Lead	5.825	4.988	mg/Kg				5

Type:	Post Digest Spike	Lab ID:	QC1341780	Batch:	395658
Matrix (Source ID):	Soil (553279-001)	Method:	EPA 6010B	Prep Method:	EPA 3050B

QC1341780 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	DF
Lead	105.2	4.988	100.0	mg/Kg	100%		75-125	1

ENTHALPY ANALYTICAL

Batch QC

Type:	**Blank**	**Lab ID:**	**QC1341956**	**Batch:**	**395755**
Matrix:	**Soil**	**Method:**	**EPA 8081A**	**Prep Method:**	**EPA 3546**

QC1341956 Analyte	Result	Qual	Units	RL	Prepared	Analyzed
alpha-BHC	ND		ug/Kg	5.1	02/19/26	02/20/26
beta-BHC	ND		ug/Kg	5.1	02/19/26	02/20/26
gamma-BHC	ND		ug/Kg	5.1	02/19/26	02/20/26
delta-BHC	ND		ug/Kg	5.1	02/19/26	02/20/26
Heptachlor	ND		ug/Kg	5.1	02/19/26	02/20/26
Aldrin	ND		ug/Kg	5.1	02/19/26	02/20/26
Heptachlor epoxide	ND		ug/Kg	5.1	02/19/26	02/20/26
Endosulfan I	ND		ug/Kg	5.1	02/19/26	02/20/26
Dieldrin	ND		ug/Kg	5.1	02/19/26	02/20/26
4,4'-DDE	ND		ug/Kg	5.1	02/19/26	02/20/26
Endrin	ND		ug/Kg	5.1	02/19/26	02/20/26
Endosulfan II	ND		ug/Kg	5.1	02/19/26	02/20/26
Endosulfan sulfate	ND		ug/Kg	5.1	02/19/26	02/20/26
4,4'-DDD	ND		ug/Kg	5.1	02/19/26	02/20/26
Endrin aldehyde	ND		ug/Kg	5.1	02/19/26	02/20/26
Endrin ketone	ND		ug/Kg	5.1	02/19/26	02/20/26
4,4'-DDT	ND		ug/Kg	5.1	02/19/26	02/20/26
Methoxychlor	ND		ug/Kg	10	02/19/26	02/20/26
Toxaphene	ND		ug/Kg	100	02/19/26	02/20/26
Chlordane (Technical)	ND		ug/Kg	51	02/19/26	02/20/26
Surrogates				**Limits**		
TCMX	84%		%REC	58-120	02/19/26	02/20/26
Decachlorobiphenyl	94%		%REC	47-120	02/19/26	02/20/26

ENTHALPY ANALYTICAL

Batch QC

Type: Lab Control Sample	**Lab ID: QC1341957**	**Batch: 395755**
Matrix: Soil	**Method: EPA 8081A**	**Prep Method: EPA 3546**

QC1341957 Analyte	Result	Spiked	Units	Recovery	Qual	Limits
alpha-BHC	50.83	50.51	ug/Kg	101%		53-132
beta-BHC	47.03	50.51	ug/Kg	93%		59-131
gamma-BHC	50.77	50.51	ug/Kg	101%		54-132
delta-BHC	53.22	50.51	ug/Kg	105%		54-134
Heptachlor	49.03	50.51	ug/Kg	97%		50-130
Aldrin	44.32	50.51	ug/Kg	88%		46-120
Heptachlor epoxide	44.39	50.51	ug/Kg	88%		52-127
Endosulfan I	45.65	50.51	ug/Kg	90%		53-132
Dieldrin	45.18	50.51	ug/Kg	89%		53-134
4,4'-DDE	48.12	50.51	ug/Kg	95%		53-140
Endrin	49.87	50.51	ug/Kg	99%		53-142
Endosulfan II	43.54	50.51	ug/Kg	86%		53-138
Endosulfan sulfate	49.48	50.51	ug/Kg	98%		50-134
4,4'-DDD	44.72	50.51	ug/Kg	89%		50-136
Endrin aldehyde	39.73	50.51	ug/Kg	79%		15-120
Endrin ketone	56.22	50.51	ug/Kg	111%		50-146
4,4'-DDT	48.06	50.51	ug/Kg	95%		46-142
Methoxychlor	52.23	50.51	ug/Kg	103%		48-156
Surrogates						
TCMX	39.64	50.51	ug/Kg	78%		58-120
Decachlorobiphenyl	45.78	50.51	ug/Kg	91%		47-120

ENTHALPY ANALYTICAL

Batch QC

Type:	**Matrix Spike**	**Lab ID:**	**QC1341958**	**Batch:**	**395755**
Matrix (Source ID):	**Soil (553184-002)**	**Method:**	**EPA 8081A**	**Prep Method:**	**EPA 3546**

QC1341958 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	DF
alpha-BHC	51.87	ND	49.50	ug/Kg	105%		52-120	0.99
beta-BHC	48.65	ND	49.50	ug/Kg	98%		57-126	0.99
gamma-BHC	51.20	ND	49.50	ug/Kg	103%		54-122	0.99
delta-BHC	55.88	ND	49.50	ug/Kg	113%		44-127	0.99
Heptachlor	48.98	ND	49.50	ug/Kg	99%		51-122	0.99
Aldrin	46.45	ND	49.50	ug/Kg	94%		51-120	0.99
Heptachlor epoxide	45.72	ND	49.50	ug/Kg	92%		50-122	0.99
Endosulfan I	44.79	ND	49.50	ug/Kg	90%		48-123	0.99
Dieldrin	45.18	ND	49.50	ug/Kg	91%		48-128	0.99
4,4'-DDE	48.26	ND	49.50	ug/Kg	97%		50-139	0.99
Endrin	50.97	ND	49.50	ug/Kg	103%		53-132	0.99
Endosulfan II	45.20	ND	49.50	ug/Kg	91%		47-131	0.99
Endosulfan sulfate	51.61	ND	49.50	ug/Kg	104%		40-126	0.99
4,4'-DDD	46.02	ND	49.50	ug/Kg	93%		48-130	0.99
Endrin aldehyde	41.43	ND	49.50	ug/Kg	84%		26-120	0.99
Endrin ketone	58.14	ND	49.50	ug/Kg	117%		51-133	0.99
4,4'-DDT	49.29	ND	49.50	ug/Kg	100%		40-144	0.99
Methoxychlor	54.12	ND	49.50	ug/Kg	109%		49-148	0.99
Surrogates								
TCMX	40.49		49.50	ug/Kg	82%		58-120	0.99
Decachlorobiphenyl	47.47		49.50	ug/Kg	96%		47-120	0.99

ENTHALPY ANALYTICAL

Batch QC

Type:	**Matrix Spike Duplicate**	**Lab ID:**	**QC1341959**	**Batch:**	**395755**
Matrix (Source ID):	**Soil (553184-002)**	**Method:**	**EPA 8081A**	**Prep Method:**	**EPA 3546**

QC1341959 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	RPD	RPD Lim	DF
alpha-BHC	58.93	ND	49.50	ug/Kg	119%		52-120	13	37	0.99
beta-BHC	54.92	ND	49.50	ug/Kg	111%		57-126	12	38	0.99
gamma-BHC	58.19	ND	49.50	ug/Kg	118%		54-122	13	39	0.99
delta-BHC	64.75	ND	49.50	ug/Kg	131%	*	44-127	15	54	0.99
Heptachlor	55.93	ND	49.50	ug/Kg	113%		51-122	13	44	0.99
Aldrin	52.37	ND	49.50	ug/Kg	106%		51-120	12	39	0.99
Heptachlor epoxide	51.02	ND	49.50	ug/Kg	103%		50-122	11	39	0.99
Endosulfan I	51.55	ND	49.50	ug/Kg	104%		48-123	14	47	0.99
Dieldrin	51.41	ND	49.50	ug/Kg	104%		48-128	13	43	0.99
4,4'-DDE	54.76	ND	49.50	ug/Kg	111%		50-139	13	42	0.99
Endrin	56.35	ND	49.50	ug/Kg	114%		53-132	10	45	0.99
Endosulfan II	51.40	ND	49.50	ug/Kg	104%		47-131	13	46	0.99
Endosulfan sulfate	56.73	ND	49.50	ug/Kg	115%		40-126	9	52	0.99
4,4'-DDD	50.97	ND	49.50	ug/Kg	103%		48-130	10	46	0.99
Endrin aldehyde	44.52	ND	49.50	ug/Kg	90%		26-120	7	57	0.99
Endrin ketone	62.95	ND	49.50	ug/Kg	127%		51-133	8	43	0.99
4,4'-DDT	54.97	ND	49.50	ug/Kg	111%		40-144	11	56	0.99
Methoxychlor	57.69	ND	49.50	ug/Kg	117%		49-148	6	53	0.99
Surrogates										
TCMX	45.42		49.50	ug/Kg	92%		58-120			0.99
Decachlorobiphenyl	49.30		49.50	ug/Kg	100%		47-120			0.99

ENTHALPY ANALYTICAL

Batch QC

Type:	**Blank**	**Lab ID:**	**QC1342073**	**Batch:**	**395785**
Matrix:	**Soil**	**Method:**	**EPA 8081A**	**Prep Method:**	**EPA 3546**

QC1342073 Analyte	Result	Qual	Units	RL	Prepared	Analyzed
alpha-BHC	ND		ug/Kg	5.0	02/19/26	02/20/26
beta-BHC	ND		ug/Kg	5.0	02/19/26	02/20/26
gamma-BHC	ND		ug/Kg	5.0	02/19/26	02/20/26
delta-BHC	ND		ug/Kg	5.0	02/19/26	02/20/26
Heptachlor	ND		ug/Kg	5.0	02/19/26	02/20/26
Aldrin	ND		ug/Kg	5.0	02/19/26	02/20/26
Heptachlor epoxide	ND		ug/Kg	5.0	02/19/26	02/20/26
Endosulfan I	ND		ug/Kg	5.0	02/19/26	02/20/26
Dieldrin	ND		ug/Kg	5.0	02/19/26	02/20/26
4,4'-DDE	ND		ug/Kg	5.0	02/19/26	02/20/26
Endrin	ND		ug/Kg	5.0	02/19/26	02/20/26
Endosulfan II	ND		ug/Kg	5.0	02/19/26	02/20/26
Endosulfan sulfate	ND		ug/Kg	5.0	02/19/26	02/20/26
4,4'-DDD	ND		ug/Kg	5.0	02/19/26	02/20/26
Endrin aldehyde	ND		ug/Kg	5.0	02/19/26	02/20/26
Endrin ketone	ND		ug/Kg	5.0	02/19/26	02/20/26
4,4'-DDT	ND		ug/Kg	5.0	02/19/26	02/20/26
Methoxychlor	ND		ug/Kg	9.9	02/19/26	02/20/26
Toxaphene	ND		ug/Kg	99	02/19/26	02/20/26
Chlordane (Technical)	ND		ug/Kg	50	02/19/26	02/20/26
Surrogates				**Limits**		
TCMX	85%		%REC	58-120	02/19/26	02/20/26
Decachlorobiphenyl	97%		%REC	47-120	02/19/26	02/20/26

ENTHALPY ANALYTICAL

Batch QC

Type: Lab Control Sample	**Lab ID: QC1342074**	**Batch: 395785**
Matrix: Soil	**Method: EPA 8081A**	**Prep Method: EPA 3546**

QC1342074 Analyte	Result	Spiked	Units	Recovery	Qual	Limits
alpha-BHC	43.70	49.80	ug/Kg	88%		53-132
beta-BHC	45.06	49.80	ug/Kg	90%		59-131
gamma-BHC	44.44	49.80	ug/Kg	89%		54-132
delta-BHC	43.46	49.80	ug/Kg	87%		54-134
Heptachlor	42.84	49.80	ug/Kg	86%		50-130
Aldrin	36.95	49.80	ug/Kg	74%		46-120
Heptachlor epoxide	40.06	49.80	ug/Kg	80%		52-127
Endosulfan I	43.15	49.80	ug/Kg	87%		53-132
Dieldrin	42.28	49.80	ug/Kg	85%		53-134
4,4'-DDE	44.76	49.80	ug/Kg	90%		53-140
Endrin	47.44	49.80	ug/Kg	95%		53-142
Endosulfan II	45.36	49.80	ug/Kg	91%		53-138
Endosulfan sulfate	45.03	49.80	ug/Kg	90%		50-134
4,4'-DDD	43.18	49.80	ug/Kg	87%		50-136
Endrin aldehyde	34.41	49.80	ug/Kg	69%		15-120
Endrin ketone	54.00	49.80	ug/Kg	108%		50-146
4,4'-DDT	43.94	49.80	ug/Kg	88%		46-142
Methoxychlor	53.45	49.80	ug/Kg	107%		48-156
Surrogates						
TCMX	42.20	49.80	ug/Kg	85%		58-120
Decachlorobiphenyl	46.40	49.80	ug/Kg	93%		47-120

ENTHALPY ANALYTICAL

Batch QC

Type:	**Matrix Spike**	**Lab ID:**	**QC1342075**	**Batch:**	**395785**
Matrix (Source ID):	**Soil (553195-060)**	**Method:**	**EPA 8081A**	**Prep Method:**	**EPA 3546**

QC1342075 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	DF
alpha-BHC	44.65	ND	49.75	ug/Kg	90%		52-120	1
beta-BHC	58.29	ND	49.75	ug/Kg	117%		57-126	1
gamma-BHC	45.54	ND	49.75	ug/Kg	92%		54-122	1
delta-BHC	46.30	ND	49.75	ug/Kg	93%		44-127	1
Heptachlor	44.75	ND	49.75	ug/Kg	90%		51-122	1
Aldrin	41.86	ND	49.75	ug/Kg	84%		51-120	1
Heptachlor epoxide	41.79	ND	49.75	ug/Kg	84%		50-122	1
Endosulfan I	43.32	ND	49.75	ug/Kg	87%		48-123	1
Dieldrin	44.62	ND	49.75	ug/Kg	90%		48-128	1
4,4'-DDE	47.27	ND	49.75	ug/Kg	95%		50-139	1
Endrin	49.37	ND	49.75	ug/Kg	99%		53-132	1
Endosulfan II	48.06	ND	49.75	ug/Kg	97%		47-131	1
Endosulfan sulfate	47.58	ND	49.75	ug/Kg	96%		40-126	1
4,4'-DDD	44.69	ND	49.75	ug/Kg	90%		48-130	1
Endrin aldehyde	36.83	ND	49.75	ug/Kg	74%		26-120	1
Endrin ketone	47.87	ND	49.75	ug/Kg	96%		51-133	1
4,4'-DDT	48.43	ND	49.75	ug/Kg	97%		40-144	1
Methoxychlor	55.49	ND	49.75	ug/Kg	112%		49-148	1
Surrogates								
TCMX	44.01		49.75	ug/Kg	88%		58-120	1
Decachlorobiphenyl	49.29		49.75	ug/Kg	99%		47-120	1

ENTHALPY ANALYTICAL

Batch QC

Type:	**Matrix Spike Duplicate**	**Lab ID:**	**QC1342076**	**Batch:**	**395785**
Matrix (Source ID):	**Soil (553195-060)**	**Method:**	**EPA 8081A**	**Prep Method:**	**EPA 3546**

QC1342076 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	RPD	RPD Lim	DF
alpha-BHC	45.16	ND	50.51	ug/Kg	89%		52-120	0	37	1
beta-BHC	55.95	ND	50.51	ug/Kg	111%		57-126	6	38	1
gamma-BHC	46.47	ND	50.51	ug/Kg	92%		54-122	1	39	1
delta-BHC	46.83	ND	50.51	ug/Kg	93%		44-127	0	54	1
Heptachlor	45.70	ND	50.51	ug/Kg	90%		51-122	1	44	1
Aldrin	42.52	ND	50.51	ug/Kg	84%		51-120	0	39	1
Heptachlor epoxide	42.35	ND	50.51	ug/Kg	84%		50-122	0	39	1
Endosulfan I	44.02	ND	50.51	ug/Kg	87%		48-123	0	47	1
Dieldrin	44.67	ND	50.51	ug/Kg	88%		48-128	1	43	1
4,4'-DDE	47.94	ND	50.51	ug/Kg	95%		50-139	0	42	1
Endrin	49.23	ND	50.51	ug/Kg	97%		53-132	2	45	1
Endosulfan II	48.19	ND	50.51	ug/Kg	95%		47-131	1	46	1
Endosulfan sulfate	47.61	ND	50.51	ug/Kg	94%		40-126	1	52	1
4,4'-DDD	44.36	ND	50.51	ug/Kg	88%		48-130	2	46	1
Endrin aldehyde	36.13	ND	50.51	ug/Kg	72%		26-120	3	57	1
Endrin ketone	48.02	ND	50.51	ug/Kg	95%		51-133	1	43	1
4,4'-DDT	49.09	ND	50.51	ug/Kg	97%		40-144	0	56	1
Methoxychlor	54.71	ND	50.51	ug/Kg	108%		49-148	3	53	1
Surrogates										
TCMX	43.48		50.51	ug/Kg	86%		58-120			1
Decachlorobiphenyl	49.12		50.51	ug/Kg	97%		47-120			1

ENTHALPY ANALYTICAL

Batch QC

Type: Blank	Lab ID: QC1340997	Batch: 395462
Matrix: Water		

QC1340997 Analyte	Result	Qual	Units	RL	Prepared	Analyzed
Method: EPA 8081A Prep Method: EPA 3510C						
alpha-BHC	ND		ug/L	0.05	02/16/26	02/17/26
beta-BHC	ND		ug/L	0.05	02/16/26	02/17/26
gamma-BHC	ND		ug/L	0.05	02/16/26	02/17/26
delta-BHC	ND		ug/L	0.05	02/16/26	02/17/26
Heptachlor	ND		ug/L	0.05	02/16/26	02/17/26
Aldrin	ND		ug/L	0.05	02/16/26	02/17/26
Heptachlor epoxide	ND		ug/L	0.05	02/16/26	02/17/26
Endosulfan I	ND		ug/L	0.05	02/16/26	02/17/26
Dieldrin	ND		ug/L	0.1	02/16/26	02/17/26
4,4'-DDE	ND		ug/L	0.1	02/16/26	02/17/26
Endrin	ND		ug/L	0.1	02/16/26	02/17/26
Endosulfan II	ND		ug/L	0.1	02/16/26	02/17/26
Endosulfan sulfate	ND		ug/L	0.1	02/16/26	02/17/26
4,4'-DDD	ND		ug/L	0.1	02/16/26	02/17/26
Endrin aldehyde	ND		ug/L	0.1	02/16/26	02/17/26
Endrin ketone	ND		ug/L	0.1	02/16/26	02/17/26
4,4'-DDT	ND		ug/L	0.1	02/16/26	02/17/26
Methoxychlor	ND		ug/L	0.1	02/16/26	02/17/26
Toxaphene	ND		ug/L	2.0	02/16/26	02/17/26
Chlordane (Technical)	ND		ug/L	1.0	02/16/26	02/17/26
Surrogates				**Limits**		
TCMX	88%		%REC	29-120	02/16/26	02/17/26
Decachlorobiphenyl	108%		%REC	33-132	02/16/26	02/17/26
Method: EPA 8082 Prep Method: EPA 3510C						
Aroclor-1016	ND		ug/L	0.50	02/16/26	02/17/26
Aroclor-1221	ND		ug/L	0.50	02/16/26	02/17/26
Aroclor-1232	ND		ug/L	0.50	02/16/26	02/17/26
Aroclor-1242	ND		ug/L	0.50	02/16/26	02/17/26
Aroclor-1248	ND		ug/L	0.50	02/16/26	02/17/26
Aroclor-1254	ND		ug/L	0.50	02/16/26	02/17/26
Aroclor-1260	ND		ug/L	0.50	02/16/26	02/17/26
Aroclor-1262	ND		ug/L	0.50	02/16/26	02/17/26
Aroclor-1268	ND		ug/L	0.50	02/16/26	02/17/26
Total PCBs	ND		ug/L	0.50	02/16/26	02/17/26
Surrogates				**Limits**		
Decachlorobiphenyl (PCB)	89%		%REC	28-138	02/16/26	02/17/26

ENTHALPY ANALYTICAL

Batch QC

Type:	**Lab Control Sample**	**Lab ID:**	**QC1340998**	**Batch:**	**395462**
Matrix:	**Water**	**Method:**	**EPA 8081A**	**Prep Method:**	**EPA 3510C**

QC1340998 Analyte	Result	Spiked	Units	Recovery	Qual	Limits
alpha-BHC	0.5462	0.5000	ug/L	109%		66-121
beta-BHC	0.5538	0.5000	ug/L	111%		73-120
gamma-BHC	0.5469	0.5000	ug/L	109%		68-125
delta-BHC	0.5638	0.5000	ug/L	113%		68-131
Heptachlor	0.5632	0.5000	ug/L	113%		63-120
Aldrin	0.4820	0.5000	ug/L	96%		56-120
Heptachlor epoxide	0.4862	0.5000	ug/L	97%		65-120
Endosulfan I	0.4895	0.5000	ug/L	98%		68-124
Dieldrin	0.4981	0.5000	ug/L	100%		66-124
4,4'-DDE	0.5125	0.5000	ug/L	103%		67-131
Endrin	0.5266	0.5000	ug/L	105%		68-135
Endosulfan II	0.5326	0.5000	ug/L	107%		71-130
Endosulfan sulfate	0.5310	0.5000	ug/L	106%		68-128
4,4'-DDD	0.5573	0.5000	ug/L	111%		65-130
Endrin aldehyde	0.4986	0.5000	ug/L	100%		67-124
Endrin ketone	0.5663	0.5000	ug/L	113%		69-137
4,4'-DDT	0.5415	0.5000	ug/L	108%		65-136
Methoxychlor	0.5582	0.5000	ug/L	112%		69-150
Surrogates						
TCMX	0.4970	0.5000	ug/L	99%		29-120
Decachlorobiphenyl	0.5611	0.5000	ug/L	112%		33-132

Batch QC

Type:	Lab Control Sample Duplicate	Lab ID:	QC1340999	Batch:	395462
Matrix:	Water	Method:	EPA 8081A	Prep Method:	EPA 3510C

QC1340999 Analyte	Result	Spiked	Units	Recovery	Qual	Limits	RPD	RPD Lim
alpha-BHC	0.5355	0.5000	ug/L	107%		66-121	2	20
beta-BHC	0.5360	0.5000	ug/L	107%		73-120	3	20
gamma-BHC	0.5335	0.5000	ug/L	107%		68-125	2	20
delta-BHC	0.5469	0.5000	ug/L	109%		68-131	3	20
Heptachlor	0.5447	0.5000	ug/L	109%		63-120	3	24
Aldrin	0.4581	0.5000	ug/L	92%		56-120	5	30
Heptachlor epoxide	0.4652	0.5000	ug/L	93%		65-120	4	20
Endosulfan I	0.4664	0.5000	ug/L	93%		68-124	5	20
Dieldrin	0.4743	0.5000	ug/L	95%		66-124	5	22
4,4'-DDE	0.4794	0.5000	ug/L	96%		67-131	7	21
Endrin	0.4968	0.5000	ug/L	99%		68-135	6	20
Endosulfan II	0.5066	0.5000	ug/L	101%		71-130	5	21
Endosulfan sulfate	0.4998	0.5000	ug/L	100%		68-128	6	21
4,4'-DDD	0.5195	0.5000	ug/L	104%		65-130	7	22
Endrin aldehyde	0.4667	0.5000	ug/L	93%		67-124	7	20
Endrin ketone	0.5296	0.5000	ug/L	106%		69-137	7	21
4,4'-DDT	0.5076	0.5000	ug/L	102%		65-136	6	23
Methoxychlor	0.5215	0.5000	ug/L	104%		69-150	7	23
Surrogates								
TCMX	0.4821	0.5000	ug/L	96%		29-120		
Decachlorobiphenyl	0.5315	0.5000	ug/L	106%		33-132		

Type:	Lab Control Sample	Lab ID:	QC1341000	Batch:	395462
Matrix:	Water	Method:	EPA 8082	Prep Method:	EPA 3510C

QC1341000 Analyte	Result	Spiked	Units	Recovery	Qual	Limits
Aroclor-1016	5.818	5.000	ug/L	116%		69-120
Aroclor-1260	5.630	5.000	ug/L	113%		72-124
Surrogates						
Decachlorobiphenyl (PCB)	0.4904	0.5000	ug/L	98%		28-138

Type:	Lab Control Sample Duplicate	Lab ID:	QC1341001	Batch:	395462
Matrix:	Water	Method:	EPA 8082	Prep Method:	EPA 3510C

QC1341001 Analyte	Result	Spiked	Units	Recovery	Qual	Limits	RPD	RPD Lim
Aroclor-1016	5.478	5.000	ug/L	110%		69-120	6	22
Aroclor-1260	5.259	5.000	ug/L	105%		72-124	7	25
Surrogates								
Decachlorobiphenyl (PCB)	0.4628	0.5000	ug/L	93%		28-138		

ENTHALPY ANALYTICAL

Batch QC

Type: Blank	Lab ID: QC1342151	Batch: 395809
Matrix: Soil	Method: EPA 8082	Prep Method: EPA 3546

QC1342151 Analyte	Result	Qual	Units	RL	Prepared	Analyzed
Aroclor-1016	ND		ug/Kg	49	02/19/26	02/20/26
Aroclor-1221	ND		ug/Kg	49	02/19/26	02/20/26
Aroclor-1232	ND		ug/Kg	49	02/19/26	02/20/26
Aroclor-1242	ND		ug/Kg	49	02/19/26	02/20/26
Aroclor-1248	ND		ug/Kg	49	02/19/26	02/20/26
Aroclor-1254	ND		ug/Kg	49	02/19/26	02/20/26
Aroclor-1260	ND		ug/Kg	49	02/19/26	02/20/26
Aroclor-1262	ND		ug/Kg	49	02/19/26	02/20/26
Aroclor-1268	ND		ug/Kg	49	02/19/26	02/20/26
Total PCBs	ND		ug/Kg	49	02/19/26	02/20/26
Surrogates				**Limits**		
Decachlorobiphenyl (PCB)	110%		%REC	50-127	02/19/26	02/20/26

Type: Lab Control Sample	Lab ID: QC1342152	Batch: 395809
Matrix: Soil	Method: EPA 8082	Prep Method: EPA 3546

QC1342152 Analyte	Result	Spiked	Units	Recovery	Qual	Limits
Aroclor-1016	524.8	510.2	ug/Kg	103%		66-120
Aroclor-1260	569.2	510.2	ug/Kg	112%		63-126
Surrogates						
Decachlorobiphenyl (PCB)	56.98	51.02	ug/Kg	112%		50-127

Type: Matrix Spike	Lab ID: QC1342153	Batch: 395809
Matrix (Source ID): Soil (553195-001)	Method: EPA 8082	Prep Method: EPA 3546

QC1342153 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	DF
Aroclor-1016	536.5	ND	495.0	ug/Kg	108%		60-123	0.99
Aroclor-1260	620.0	50.83	495.0	ug/Kg	115%		55-136	0.99
Surrogates								
Decachlorobiphenyl (PCB)	61.31		49.50	ug/Kg	124%		50-127	0.99

Type: Matrix Spike Duplicate	Lab ID: QC1342154	Batch: 395809
Matrix (Source ID): Soil (553195-001)	Method: EPA 8082	Prep Method: EPA 3546

QC1342154 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	RPD	RPD Lim	DF
Aroclor-1016	508.5	ND	505.1	ug/Kg	101%		60-123	7	37	1
Aroclor-1260	566.8	50.83	505.1	ug/Kg	102%		55-136	11	41	1
Surrogates										
Decachlorobiphenyl (PCB)	54.76		50.51	ug/Kg	108%		50-127			1

ENTHALPY ANALYTICAL

Batch QC

Type: Blank	Lab ID: QC1342398	Batch: 395871
Matrix: Soil	Method: EPA 8082	Prep Method: EPA 3546

QC1342398 Analyte	Result	Qual	Units	RL	Prepared	Analyzed
Aroclor-1016	ND		ug/Kg	50	02/20/26	02/21/26
Aroclor-1221	ND		ug/Kg	50	02/20/26	02/21/26
Aroclor-1232	ND		ug/Kg	50	02/20/26	02/21/26
Aroclor-1242	ND		ug/Kg	50	02/20/26	02/21/26
Aroclor-1248	ND		ug/Kg	50	02/20/26	02/21/26
Aroclor-1254	ND		ug/Kg	50	02/20/26	02/21/26
Aroclor-1260	170		ug/Kg	50	02/20/26	02/21/26
Aroclor-1262	ND		ug/Kg	50	02/20/26	02/21/26
Aroclor-1268	ND		ug/Kg	50	02/20/26	02/21/26
Total PCBs	170		ug/Kg	50	02/20/26	02/21/26
Surrogates				**Limits**		
Decachlorobiphenyl (PCB)	102%		%REC	50-127	02/20/26	02/21/26

Type: Lab Control Sample	Lab ID: QC1342399	Batch: 395871
Matrix: Soil	Method: EPA 8082	Prep Method: EPA 3546

QC1342399 Analyte	Result	Spiked	Units	Recovery	Qual	Limits
Aroclor-1016	535.9	505.1	ug/Kg	106%		66-120
Aroclor-1260	584.6	505.1	ug/Kg	116%		63-126
Surrogates						
Decachlorobiphenyl (PCB)	56.71	50.51	ug/Kg	112%		50-127

Type: Matrix Spike	Lab ID: QC1342402	Batch: 395871
Matrix (Source ID): Soil (553195-040)	Method: EPA 8082	Prep Method: EPA 3546

QC1342402 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	DF
Aroclor-1016	530.4	ND	500.0	ug/Kg	106%		60-123	1
Aroclor-1260	597.5	ND	500.0	ug/Kg	119%		55-136	1
Surrogates								
Decachlorobiphenyl (PCB)	53.40		50.00	ug/Kg	107%		50-127	1

Type: Matrix Spike Duplicate	Lab ID: QC1342403	Batch: 395871
Matrix (Source ID): Soil (553195-040)	Method: EPA 8082	Prep Method: EPA 3546

QC1342403 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	RPD	RPD Lim	DF
Aroclor-1016	478.4	ND	505.1	ug/Kg	95%		60-123	11	37	1
Aroclor-1260	520.7	ND	505.1	ug/Kg	103%		55-136	15	41	1
Surrogates										
Decachlorobiphenyl (PCB)	46.98		50.51	ug/Kg	93%		50-127			1

* Value is outside QC limits
J Estimated value
ND Not Detected

Laboratory Job Number 553195

Subcontracted Products

AmeriSci Los Angeles

AmeriSci Richmond
13635 GENITO ROAD
MIDLOTHIAN, VIRGINIA 23112
TEL: (804) 763-1200 • FAX: (804) 763-0493

February 24, 2026

Enthalpy Analytical
Attn: Project Manager
931 West Barkley Ave
Orange, CA 92868

RE: Enthalpy Analytical
Job Number 126021981
P.O. #098798
553195

Dear Project Manager:

Enclosed are the results of Asbestos Analysis - Bulk Qualitative Protocol of the following Enthalpy Analytical samples, received at AmeriSci on Friday, February 20, 2026, for a 5 day turnaround:

CG-20-0.5, CG-20-2.5, CG-21-0.5, CG-21-2.5, CG-22-0.5-DUP, CG-22-2.5-DUP, CG-22-0.5, CG-22-2.5, CG-23-0.5, CG-23-2.5, CG-24-0.5, CG-24-2.5, CG-25-0.5, CG-25-2.5, CG-26-0.5, CG-26-2.5, CG-26-0.5-DUP, CG-26-2.5-DUP, CG-27-0.5, CG-27-2.5, CG-29-0.5, CG-29-2.5

The 22 samples, placed in zip lock bag, were shipped to AmeriSci via Fed Ex 717839739819. Enthalpy Analytical requested Bulk-Qualitative analysis of these samples.

The samples were prepared and analyzed by using a Standard Operating Procedure developed by AmeriSci, Inc.. After preparation, using non-quantitative matrix reduction if necessary, the presence or absence of asbestos is determined by PLM and/or TEM as indicated on the attached summary table. Quantification after the fact is not possible without a new preparation. This report relates ONLY to the analysis expressed as "asbestos present" or "no asbestos visible". This report must not be used to claim product endorsement or approval by AmeriSci, NVLAP, ELAP or any other associated AmeriSci certifying agency. The National Institute of Standards and Technology accreditation requirements, mandate that this report must not be reproduced, except in full without the approval of the laboratory.

AmeriSci appreciates this opportunity to serve your organization. Please contact us for any further assistance or with any questions.

Sincerely,

Cory M. Parnell

Laboratory Director | Authorized Signatory

AmeriSci Richmond
13635 GENITO ROAD
MIDLOTHIAN, VIRGINIA 23112
TEL: (804) 763-1200 • FAX: (804) 763-0493

PLM Bulk Asbestos Report

Enthalpy Analytical
Attn: Project Manager
931 West Barkley Ave

Orange, CA 92868

Date Received 2/20/2026
Date Examined 02/24/26

RE: 553195

AmeriSci Job # 126021981
P.O. # 098798
Page 1 **of** 4

Client No. / HGA	Lab No.	Asbestos Present	Total % Asbestos	Notes
CG-20-0.5	126021981-01	***No***	NVA by C. David Mintz on 02/24/26	*1*

Location:
Analyst Description: Brown, Homogeneous, Non-Fibrous, Soil
Asbestos Types:
Other Material: Cellulose Present, Non-fibrous Present
Comment: Soil Samples Placed in Drying Oven 4 hours.

CG-20-2.5	126021981-02	***No***	NVA by C. David Mintz on 02/24/26	*1*

Location:
Analyst Description: Brown, Homogeneous, Non-Fibrous, Soil
Asbestos Types:
Other Material: Non-fibrous Present

CG-21-0.5	126021981-03	***No***	NVA by C. David Mintz on 02/24/26	*1*

Location:
Analyst Description: Brown, Homogeneous, Non-Fibrous, Soil, granular
Asbestos Types:
Other Material: Non-fibrous Present

CG-21-2.5	126021981-04	***No***	NVA by C. David Mintz on 02/24/26	*1*

Location:
Analyst Description: Brown, Homogeneous, Non-Fibrous, Soil
Asbestos Types:
Other Material: Non-fibrous Present

CG-22-0.5-DUP	126021981-05	***No***	NVA by C. David Mintz on 02/24/26	*1*

Location:
Analyst Description: Brown, Homogeneous, Non-Fibrous, Soil, granular
Asbestos Types:
Other Material: Cellulose Present, Non-fibrous Present

See Reporting notes on last page

PLM Bulk Asbestos Report

553195

Client No. / HGA	Lab No.	Asbestos Present	Total % Asbestos	Notes
CG-22-2.5-DUP	126021981-06	***No***	NVA by C. David Mintz on 02/24/26	*1*
Location: **Analyst Description:** Brown, Homogeneous, Non-Fibrous, Soil **Asbestos Types:** **Other Material:** Non-fibrous Present				
CG-22-0.5	126021981-07	***No***	NVA by C. David Mintz on 02/24/26	*1*
Location: **Analyst Description:** Brown, Homogeneous, Non-Fibrous, Soil **Asbestos Types:** **Other Material:** Non-fibrous Present				
CG-22-2.5	126021981-08	***No***	NVA by C. David Mintz on 02/24/26	*1*
Location: **Analyst Description:** Brown, Homogeneous, Non-Fibrous, Soil **Asbestos Types:** **Other Material:** Non-fibrous Present				
CG-23-0.5	126021981-09	***No***	NVA by C. David Mintz on 02/24/26	*1*
Location: **Analyst Description:** Brown, Homogeneous, Non-Fibrous, Soil **Asbestos Types:** **Other Material:** Non-fibrous Present				
CG-23-2.5	126021981-10	***No***	NVA by C. David Mintz on 02/24/26	*1*
Location: **Analyst Description:** Brown, Homogeneous, Non-Fibrous, Soil **Asbestos Types:** **Other Material:** Non-fibrous Present				
CG-24-0.5	126021981-11	***No***	NVA by C. David Mintz on 02/24/26	*1*
Location: **Analyst Description:** Brown, Homogeneous, Non-Fibrous, Soil **Asbestos Types:** **Other Material:** Cellulose Present, Non-fibrous Present				
CG-24-2.5	126021981-12	***No***	NVA by C. David Mintz on 02/24/26	*1*
Location: **Analyst Description:** Brown, Homogeneous, Non-Fibrous, Soil **Asbestos Types:** **Other Material:** Non-fibrous Present				

See Reporting notes on last page

PLM Bulk Asbestos Report

553195

Client No. / HGA	Lab No.	Asbestos Present	Total % Asbestos	Notes
CG-25-0.5	126021981-13	***No***	NVA by C. David Mintz on 02/24/26	*1*
Location: **Analyst Description:** Brown, Homogeneous, Non-Fibrous, Soil **Asbestos Types:** **Other Material:** Non-fibrous Present				
CG-25-2.5	126021981-14	***No***	NVA by C. David Mintz on 02/24/26	*1*
Location: **Analyst Description:** Brown, Homogeneous, Non-Fibrous, Soil **Asbestos Types:** **Other Material:** Non-fibrous Present				
CG-26-0.5	126021981-15	***No***	NVA by C. David Mintz on 02/24/26	*1*
Location: **Analyst Description:** Brown, Homogeneous, Non-Fibrous, Soil **Asbestos Types:** **Other Material:** Cellulose Present, Non-fibrous Present				
CG-26-2.5	126021981-16	***No***	NVA by C. David Mintz on 02/24/26	*1*
Location: **Analyst Description:** Brown, Homogeneous, Non-Fibrous, Soil **Asbestos Types:** **Other Material:** Cellulose Present, Non-fibrous Present				
CG-26-0.5-DUP	126021981-17	***No***	NVA by C. David Mintz on 02/24/26	*1*
Location: **Analyst Description:** Brown, Homogeneous, Non-Fibrous, Soil **Asbestos Types:** **Other Material:** Non-fibrous Present				
CG-26-2.5-DUP	126021981-18	***No***	NVA by C. David Mintz on 02/24/26	*1*
Location: **Analyst Description:** Brown, Homogeneous, Non-Fibrous, Soil **Asbestos Types:** **Other Material:** Non-fibrous Present				
CG-27-0.5	126021981-19	***No***	NVA by C. David Mintz on 02/24/26	*1*
Location: **Analyst Description:** Brown, Homogeneous, Non-Fibrous, Soil, granular **Asbestos Types:** **Other Material:** Non-fibrous Present				

See Reporting notes on last page

PLM Bulk Asbestos Report

553195

Client No. / HGA	Lab No.	Asbestos Present	Total % Asbestos	Notes
CG-27-2.5	126021981-20	***No***	NVA by C. David Mintz on 02/24/26	*1*

Location:
Analyst Description: Brown, Homogeneous, Non-Fibrous, Soil
Asbestos Types:
Other Material: Non-fibrous Present

CG-29-0.5	126021981-21	***No***	NVA by C. David Mintz on 02/24/26	*1*

Location:
Analyst Description: Brown, Homogeneous, Non-Fibrous, Soil
Asbestos Types:
Other Material: Glass fragments Present, Non-fibrous Present


CG-29-2.5	126021981-22	***No***	NVA by C. David Mintz on 02/24/26	*1*

Location:
Analyst Description: Brown, Homogeneous, Non-Fibrous, Soil
Asbestos Types:
Other Material: Non-fibrous Present

Reporting Notes:

(1) Sample homogenized by grinding to a powder prior to analysis.

Analyzed by: C. David Mintz
Date: 2/24/2026



Reviewed by: Cory M. Parnell



*NAD = no asbestos detected, Detection Limit <1%, Reporting Limits: CVES = 1%, 400 Pt Ct = 0.25%, 1000 Pt Ct = 0.1%; "Present" or NVA = "No Visible Asbestos" are observations made during a qualitative analysis (Not covered by NVLAP or NY ELAP accreditations); NA = not analyzed; NA/PS = not analyzed / positive stop; PLM Bulk Asbestos Analysis using Olympus, Model BH-2 microscope, Serial #210972, by EPA 600/R-93/116 per 40 CFR 763 (NVLAP Lab Code 101904-0) and ELAP PLM Analysis Protocol 198.1 for New York friable samples which includes quantitation of any vermiculite observed (198.6 for NOB samples) or EPA 400 pt ct by EPA 600/M4-82-020 (NYSDOH ELAP Lab # 10984); CA ELAP Lab # 2508; Note: PLM is not consistently reliable in detecting asbestos in floor coverings and similar NOB materials. NAD or Trace results by PLM are inconclusive, TEM is currently the only method that can be used to determine if this material can be considered or treated as non-asbestos-containing in New York State (also see EPA Advisory for floor tile, FR 59, 146, 38970, 8/1/94). NIST Accreditation requirements mandate that this report must not be reproduced except in full without the approval of the laboratory. This PLM report relates ONLY to the items tested.

Subject: Re: [External] - Order Confirmation - NEED PO# - 126021981
From: Patricia Mata <patty.mata@enthalpy.com>
Date: 2/23/2026, 11:48 AM
To: "varesults@amerisci.com" <varesults@amerisci.com>
CC: Jocelyn Nguyen <JocelynNguyen@enthalpy.com>

Hello,

Please use PO-098798 on the invoice for my lab # 553195.

With Regards,

Patty Mata
Project Manager
Enthalpy Analytical
Direct: +1-714-771-9930 | Mobile: +1-714-323-2586
patty.mata@enthalpy.com

From: varesults@amerisci.com <varesults@amerisci.com>
Sent: Monday, February 23, 2026 6:03 AM
To: Patricia Mata <patty.mata@enthalpy.com>; varesults@amerisci.com <varesults@amerisci.com>
Subject: [External] - Order Confirmation - NEED PO# - 126021981

***Please provide PO# as soon as possible

Thank you

This is to confirm our receipt of 22 samples on 2/23/2026.

Our Job #: 126021981

Your Job Number: 553195
Your Job Name:
Your Job Site:
Your Analysis Type: PLM-BULK-QUALITATIVE
Your Turnaround Time: 5 day

CONFIDENTIALITY NOTICE: The contents of this email message and any attachments are intended solely for the addressee(s) and may contain confidential, proprietary and/or privileged information and may be legally protected from disclosure. If you are not the intended recipient of this message or their agent, or if this message has been addressed to you in error, please immediately alert the sender by reply email and then delete this message and any attachments and the reply from your system. If you are not the intended recipient, you are hereby notified that any disclosure, use, dissemination, copying, or storage of this message or its attachments is strictly prohibited.

The information contained in this e-mail and any attachments from Montrose Environmental Group, Inc. may contain confidential and/or proprietary information, and is intended only for the named recipient to whom it was originally addressed. If you are not the intended recipient, any disclosure, distribution, or copying of this e-mail or its attachments is strictly prohibited. If you have received this e-mail in error, please notify the sender immediately by return e-mail and permanently delete the e-mail and any attachments.

CONFIDENTIALITY NOTICE: The contents of this email message and any attachments are intended solely for the addressee(s) and may contain

ENTHALPY ANALYTICAL
931 West Barkley Ave
Orange, CA 92868
(714) 771-6900

1260219 81

Subcontract Laboratory:
AmeriSci Los Angeles
24416 S. Main Street
Suite 308
Carson, CA 90745
ATTN: Sample Control
PO #: Required, to be sent via email

Enthalpy Order: EO-553195
PM: Patty Mata
Email: patty.mata@enthalpy.com
CC: incomingreports@enthalpy.com
Phone: (714) 771-6900

Results Due: Standard TAT
Report Level: II
Report To: RL
EDDs:

Notes:

Sample ID	Collected	Lab ID	# Cont.	Matrix	Analysis Requested	Comment
CG-20-0.5	13-FEB-2026 00:00	553195-059	1	Soil	Asbestos by PLM	PLM qualitative
CG-20-2.5	13-FEB-2026 00:00	553195-060	1	Soil	Asbestos by PLM	PLM qualitative
CG-21-0.5	13-FEB-2026 00:00	553195-061	1	Soil	Asbestos by PLM	PLM qualitative
CG-21-2.5	13-FEB-2026 00:00	553195-062	1	Soil	Asbestos by PLM	PLM qualitative
CG-22-0.5	13-FEB-2026 00:00	553195-063	1	Soil	Asbestos by PLM	PLM qualitative
CG-22-2.5	13-FEB-2026 00:00	553195-064	1	Soil	Asbestos by PLM	PLM qualitative
CG-22-0.5-DUP	13-FEB-2026 00:00	553195-065	1	Soil	Asbestos by PLM	PLM qualitative
CG-22-2.5-DUP	13-FEB-2026 00:00	553195-066	1	Soil	Asbestos by PLM	PLM qualitative
CG-23-0.5	13-FEB-2026 00:00	553195-067	1	Soil	Asbestos by PLM	PLM qualitative
CG-23-2.5	13-FEB-2026 00:00	553195-068	1	Soil	Asbestos by PLM	PLM qualitative
CG-24-0.5	13-FEB-2026 00:00	553195-069	1	Soil	Asbestos by PLM	PLM qualitative
CG-24-2.5	13-FEB-2026 00:00	553195-070	1	Soil	Asbestos by PLM	PLM qualitative
CG-25-0.5	13-FEB-2026 00:00	553195-071	1	Soil	Asbestos by PLM	PLM qualitative
CG-25-2.5	13-FEB-2026 00:00	553195-072	1	Soil	Asbestos by PLM	PLM qualitative
CG-26-0.5	13-FEB-2026 00:00	553195-073	1	Soil	Asbestos by PLM	PLM qualitative
CG-26-2.5	13-FEB-2026 00:00	553195-074	1	Soil	Asbestos by PLM	PLM qualitative
CG-26-0.5-DUP	13-FEB-2026 00:00	553195-075	1	Soil	Asbestos by PLM	PLM qualitative
CG-26-2.5-DUP	13-FEB-2026 00:00	553195-076	1	Soil	Asbestos by PLM	PLM qualitative
CG-27-0.5	13-FEB-2026 00:00	553195-077	1	Soil	Asbestos by PLM	PLM qualitative
CG-27-2.5	13-FEB-2026 00:00	553195-078	1	Soil	Asbestos by PLM	PLM qualitative
CG-29-0.5	13-FEB-2026 00:00	553195-079	1	Soil	Asbestos by PLM	PLM qualitative
CG-29-2.5	13-FEB-2026 00:00	553195-080	1	Soil	Asbestos by PLM	PLM qualitative
EB-01-260213	13-FEB-2026 14:15	553195-081	1	Water	Asbestos	Non-potable water TEM

Already sent

Notes:	Relinquished By:	Received By:
	[signature]	M. RIVERO
	Date: 2-19-26 1235	Date: 2/19/26 @ 1240
	M. RIVERO	
	Date: 2/19/26 @ 1240	Date:
	Date:	Date:

Received
FEB 20 2026

AmeriSci Richmond
13635 GENITO ROAD
MIDLOTHIAN, VIRGINIA 23112
TEL: (804) 763-1200 • FAX: (804) 763-0493

February 25, 2026

Enthalpy Analytical
Attn: Patty Mata
931 West Barkley Ave
Orange, CA 92868

RE: Enthalpy Analytical
Job Number 126021831
P.O. #098798
EO-553195

Dear Patty Mata:

Enclosed are the results for TEM asbestos analysis of the following Enthalpy Analytical samples received at AmeriSci on Thursday, February 19, 2026, for a 5 day turnaround:

EB-01-260213

The 1 samples were filtered and prepared according to Water analysis under the EPA-600/4-83-043 "Analytical Method for Determination of Asbestos Fibers in Water" (1983). Samples with high organic content may be prepared following EPA-600/4-80-005 if necessary and are so noted on the TEM count sheets. AmeriSci, Inc. uses the "Grid Square" method of counting and the concentration is calculated in millions of fibers per liter (MFL).

Table I represents a summary of all pertinent information used for the calculations. Included are the size of each structure counted, concentration, structure concentration greater than 10 microns in length, type of asbestiform material detected and the analytical sensitivity, which represents the concentration by the detection of one fiber in the TEM fiber count. Copies of the Fiber Count Sheets, show the raw data for examination. These data sheets contain information for fiber length/width, fiber type, structure morphology and pertinent information on EDS, SAED and photography.

This report relates ONLY to the sample analysis expressed as millions of fibers per liter (MFL). AmeriSci assumes no responsibility for customer supplied data such as “sample location” or “the condition of the water sample before arriving at AmeriSci”. This report must not be used to claim product endorsement by AmeriSci, NVLAP, ELAP or any agency of the U. S. Government. The National Institute of Standards and Technology accreditation requirements, mandate that this report must not be reproduced, except in full without the approval of the laboratory.

AmeriSci appreciates this opportunity to serve your organization. Please contact us for any further assistance or with any questions.

Sincerely,



Cory M. Parnell

Laboratory Director | Authorized Signatory

AmeriSci Job #: **126021831**
Client Name: Enthalpy Analytical

Table I
Summary of Transmission Electron Microscopy (TEM) Results for Asbestos (Water)


EO-553195

AmeriSci Sample #	Client Sample No./Location	Liquid Filtered (liters)	Temp (Celcius)	Structures Detected* (total)	Structures Detected* (>10 µm)	Analytical Sensitivity (MF/L)	Asbestos Conc (total) (MF/L)	Asbestos Conc (>10 µm) (MF/L)	Asbestos Type
01	EB-01-260213	0.01	17	NSD	NSD	0.22	<0.22	<0.22	----

* NAD/NSD = no asbestos detected, NA = not analyzed, MF/L = million fibers per liter; Drinking Water accreditations do not cover waste water analysis. NOTE: Drinking water analysis by EPA-600/4-83-043 (100.1). Fiber criteria (>=0.5 microns, for 100.1; >10 microns for 100.2; 5:1 aspect ratio for both), organic rich waste water prepped by EPA-600/4-80-005. Analytical sensitivity calculated as though 1 fiber had been detected on the TEM GRID area analyzed. Sample temperatures reported above were measured upon receipt. Water samples are refrigerated upon receipt and filtered within four hours.

Reviewed By: _____ Analyzed By: Cory M. Parnell _____ Date: 2/25/2026

TEM Asbestos (Water) Count Sheet



Client Name:	Enthalpy Analytical		
Job #:	126021831	Volume (liters):	0.01
Lab Sample #:	01	Filter Type / Filter Area:	MCE 214 mm2
Client Sample #:	EB-01-260213	Grid Opening Size:	0.00967
Received:	2/19/2026 12:00:00	Area Examined:	0.09670 mm2
Date Analyzed:	2/25/2026	Magnification:	20,000
	Temp: 17	Accelerating Voltage:	100 KeV

Analysis Performed by: Cory M. Parnell

Location	Grid Opening	Fiber	Length µM	Width µM	Fiber Type	Morphology	EDS	Orient.	SAED	Photo
C6-J2	1	NSD							☐	
C6-J4	2	NSD							☐	
C6-J6	3	NSD							☐	
C6-J8	4	NSD							☐	
C6-J10	5	NSD							☐	
C7-J1	6	NSD							☐	
C7-J3	7	NSD							☐	
C7-J5	8	NSD							☐	
C7-J7	9	NSD							☐	
C7-J9	10	NSD							☐	

NSD: No Asbestos Structures Detected

Scope #: Front 4: Jeol JEM-100CX II, Serial No.156147-247

Comments

		Concentration (million fibers/liter)	Grid Evaluation
Total Grid Openings:	10		☑ Grid Openings Covered > 50%
Chrysotile Asbestos Structures:	0	<0.221	☑ Intact Grid Opening > 50%
Amphibole Asbestos Structures:	0	<0.221	☑ Undissolved Filter < 10%
Asbestos Structures >10 microns:	0	<0.221	☑ Folded Replica < 50%
Total Asbestos Structures:	0	<0.221	☑ Filter Loading < 25%
Analytical Sensitivity:		0.221	☑ Particulate Even

126021831

ENTHALPY ANALYTICAL
931 West Barkley Ave
Orange, CA 92868
(714) 771-6900

Subcontract Laboratory:
AmeriSci Los Angeles
24416 S. Main Street
Suite 308
Carson, CA 90745
ATTN: Sample Control
PO #: Required, to be sent via email

Enthalpy Order: EO-553195
PM: Patty Mata
Email: patty.mata@enthalpy.com
CC: incomingreports@enthalpy.com
Phone: (714) 771-6900

Results Due: Standard TAT
Report Level: II
Report To: RL
EDDs:

Notes:

Sample ID	Collected	Lab ID	# Cont.	Matrix	Analysis Requested	Comment
CG-20-0.5	13-FEB-2026 00:00	553195-059	1	Soil	Asbestos by PLM	PLM qualitative
CG-20-2.5	13-FEB-2026 00:00	553195-060	1	Soil	Asbestos by PLM	PLM qualitative
CG-21-0.5	13-FEB-2026 00:00	553195-061	1	Soil	Asbestos by PLM	PLM qualitative
CG-21-2.5	13-FEB-2026 00:00	553195-062	1	Soil	Asbestos by PLM	PLM qualitative
CG-22-0.5	13-FEB-2026 00:00	553195-063	1	Soil	Asbestos by PLM	PLM qualitative
CG-22-2.5	13-FEB-2026 00:00	553195-064	1	Soil	Asbestos by PLM	PLM qualitative
CG-22-0.5-DUP	13-FEB-2026 00:00	553195-065	1	Soil	Asbestos by PLM	PLM qualitative
CG-22-2.5-DUP	13-FEB-2026 00:00	553195-066	1	Soil	Asbestos by PLM	PLM qualitative
CG-23-0.5	13-FEB-2026 00:00	553195-067	1	Soil	Asbestos by PLM	PLM qualitative
CG-23-2.5	13-FEB-2026 00:00	553195-068	1	Soil	Asbestos by PLM	PLM qualitative
CG-24-0.5	13-FEB-2026 00:00	553195-069	1	Soil	Asbestos by PLM	PLM qualitative
CG-24-2.5	13-FEB-2026 00:00	553195-070	1	Soil	Asbestos by PLM	PLM qualitative
CG-25-0.5	13-FEB-2026 00:00	553195-071	1	Soil	Asbestos by PLM	PLM qualitative
CG-25-2.5	13-FEB-2026 00:00	553195-072	1	Soil	Asbestos by PLM	PLM qualitative
CG-26-0.5	13-FEB-2026 00:00	553195-073	1	Soil	Asbestos by PLM	PLM qualitative
CG-26-2.5	13-FEB-2026 00:00	553195-074	1	Soil	Asbestos by PLM	PLM qualitative
CG-26-0.5-DUP	13-FEB-2026 00:00	553195-075	1	Soil	Asbestos by PLM	PLM qualitative
CG-26-2.5-DUP	13-FEB-2026 00:00	553195-076	1	Soil	Asbestos by PLM	PLM qualitative
CG-27-0.5	13-FEB-2026 00:00	553195-077	1	Soil	Asbestos by PLM	PLM qualitative
CG-27-2.5	13-FEB-2026 00:00	553195-078	1	Soil	Asbestos by PLM	PLM qualitative
CG-29-0.5	13-FEB-2026 00:00	553195-079	1	Soil	Asbestos by PLM	PLM qualitative
CG-29-2.5	13-FEB-2026 00:00	553195-080	1	Soil	Asbestos by PLM	PLM qualitative
EB-01-260213	13-FEB-2026 14:15	553195-081	1	Water	Asbestos	Non-potable water TEM

Notes:	Relinquished By:	Received By:
	[signature]	M. RIVERO
	Date: 2-18-26 1340	Date: 2/18/26 @ 1345
	M. RIVERO	
	Date: 2/18/26 @ 1345	Date:
	Date:	Date: Received

FEB 19 2026

Subject: Re: [External] - Order Confirmation Need PO # 126021831
From: Patricia Mata <patty.mata@enthalpy.com>
Date: 2/24/2026, 6:47 PM
To: "varesults@amerisci.com" <varesults@amerisci.com>

Hello,

When do you expect results for this sample?

My lab # 553195, 1 TEM non-postable water sample, PO-098798.

With Regards,
Patty Mata
Project Manager
Enthalpy Analytical
Direct: +1-714-771-9930 | Mobile: +1-714-323-2586
patty.mata@enthalpy.com

From: varesults@amerisci.com <varesults@amerisci.com>
Sent: Thursday, February 19, 2026 2:31 PM
To: Patricia Mata <patty.mata@enthalpy.com>; Varesults@amerisci.com <Varesults@amerisci.com>
Subject: [External] - Order Confirmation Need PO # 126021831

This is to confirm our receipt of 1 samples on 2/19/2026.

Our Job #: 126021831

Your Job Number: 553195

Your Job Name:

Your Job Site:

Your Analysis Type: Water (waste)

Your Turnaround Time: 5 day

CONFIDENTIALITY NOTICE: The contents of this email message and any attachments are intended solely for the addressee(s) and may contain confidential, proprietary and/or privileged information and may be legally protected from disclosure. If you are not the intended recipient of this message or their agent, or if this message has been addressed to you in error, please immediately alert the sender by reply email and then delete this message and any attachments and the reply from your system. If you are not the intended recipient, you are hereby notified that any disclosure, use, dissemination, copying, or storage of this message or its attachments is strictly prohibited.

Enthalpy Analytical
931 West Barkley Ave
Orange, CA 92868
(714) 771-6900

enthalpy.com

Lab Job Number : 553481
Report Level : II
Report Date : 03/03/2026

Analytical Report *prepared for:*

Vanya Keyes
Terraphase Engineering
18401 Von Karman Ave, Suite #410
Irvine, CA 92612

Project: CENTENNIAL HS - Centennial High School, 2606 N Central Ave., Compton, CA 90222

Authorized for release by:



Patty Mata, Project Manager
patty.mata@enthalpy.com

This data package has been reviewed for technical correctness and completeness. Release of this data has been authorized by the Laboratory Manager or the Manager's designee, as verified by the above signature which applies to this PDF file as well as any associated electronic data deliverable files. The results contained in this report meet all requirements of NELAP and pertain only to those samples which were submitted for analysis. This report may be reproduced only in its entirety.

CA ELAP# 1338, CA ELAP #1338-S1, NELAP# 4038, SCAQMD LAP# 18LA0518, LACSD ID# 10105, ORELAP# 4197

ENTHALPY ANALYTICAL

Sample Summary

Vanya Keyes
Terraphase Engineering
18401 Von Karman Ave, Suite #410
Irvine, CA 92612

Lab Job #: 553481
Project No: CENTENNIAL HS
Location: Centennial High School, 2606 N Central Ave., Compton, CA 90222
Date Received: 02/17/26

Sample ID	Lab ID	Collected	Matrix
AOC3-SB-49-0.5	553481-001	02/17/26 09:28	Soil
AOC3-SB-48-0.5	553481-002	02/17/26 10:38	Soil
AOC3-SB-47-0.5	553481-003	02/17/26 10:03	Soil
AOC3-SB-49-2.5	553481-004	02/17/26 09:35	Soil
AOC3-SB-48-2.5	553481-005	02/17/26 10:48	Soil
AOC3-SB-47-2.5	553481-006	02/17/26 10:28	Soil
CG-28-0.5	553481-007	02/17/26 00:00	Soil
CG-28-2.5	553481-008	02/17/26 00:00	Soil
CG-30-0.5	553481-009	02/17/26 00:00	Soil
CG-30-2.5	553481-010	02/17/26 00:00	Soil
CG-31-0.5	553481-011	02/17/26 00:00	Soil
CG-31-2.5	553481-012	02/17/26 00:00	Soil
CG-32-0.5	553481-013	02/17/26 00:00	Soil
CG-32-2.5	553481-014	02/17/26 00:00	Soil
EB-01-260217	553481-015	02/17/26 15:30	Water
AOC4-SB-09-0.5	553481-016	02/17/26 14:21	Soil
AOC4-SB-10-0.5	553481-017	02/17/26 14:38	Soil
AOC4-SB-09-2.5	553481-018	02/17/26 14:30	Soil
AOC4-SB-10-2.5	553481-019	02/17/26 14:42	Soil
AOC4-SB-11-0.5	553481-020	02/17/26 15:00	Soil
AOC4-SB-12-0.5	553481-021	02/17/26 15:12	Soil
AOC4-SB-11-2.5	553481-022	02/17/26 15:05	Soil
AOC4-SB-12-2.5	553481-023	02/17/26 15:16	Soil
DUP-04-0.5-260217	553481-024	02/17/26 00:00	Soil
DUP-04-2.5-260217	553481-025	02/17/26 00:00	Soil
AOC4-SB-05-0.5	553481-026	02/17/26 12:00	Soil

ENTHALPY ANALYTICAL

Sample Summary

Vanya Keyes
Terraphase Engineering
18401 Von Karman Ave, Suite #410
Irvine, CA 92612

Lab Job #: 553481
Project No: CENTENNIAL HS
Location: Centennial High School, 2606 N Central Ave., Compton, CA 90222
Date Received: 02/17/26

Sample ID	Lab ID	Collected	Matrix
AOC4-SB-05-2.5	553481-027	02/17/26 12:06	Soil
AOC4-SB-06-0.5	553481-028	02/17/26 12:10	Soil
AOC4-SB-06-2.5	553481-029	02/17/26 12:21	Soil
AOC4-SB-07-0.5	553481-030	02/17/26 13:45	Soil
AOC4-SB-07-2.5	553481-031	02/17/26 13:50	Soil
AOC4-SB-08-0.5	553481-032	02/17/26 13:52	Soil
AOC4-SB-08-2.5	553481-033	02/17/26 13:57	Soil
DUP-03-0.5-260217	553481-034	02/17/26 00:00	Soil
DUP-03-2.5-260217	553481-035	02/17/26 00:00	Soil
AOC4-SB-01-0.5	553481-036	02/17/26 11:06	Soil
AOC4-SB-01-2.5	553481-037	02/17/26 11:10	Soil
AOC4-SB-02-0.5	553481-038	02/17/26 11:14	Soil
AOC4-SB-02-2.5	553481-039	02/17/26 11:21	Soil
DUP-02-0.5-260217	553481-040	02/17/26 00:00	Soil
DUP-02-2.5-260217	553481-041	02/17/26 00:00	Soil
AOC4-SB-03-0.5	553481-042	02/17/26 11:27	Soil
AOC4-SB-03-2.5	553481-043	02/17/26 11:38	Soil
AOC4-SB-04-0.5	553481-044	02/17/26 11:50	Soil
AOC4-SB-04-2.5	553481-045	02/17/26 11:53	Soil
AOC3-SB-43-0.5	553481-046	02/17/26 07:55	Soil
AOC3-SB-42-0.5	553481-047	02/17/26 08:18	Soil
AOC3-SB-41-0.5	553481-048	02/17/26 08:39	Soil
AOC3-SB-43-2.5	553481-049	02/17/26 08:12	Soil
AOC3-SB-42-2.5	553481-050	02/17/26 08:42	Soil
AOC3-SB-41-2.5	553481-051	02/17/26 08:46	Soil
DUP-01-0.5-260217	553481-052	02/17/26 00:00	Soil

ENTHALPY ANALYTICAL

Sample Summary

Vanya Keyes Terraphase Engineering 18401 Von Karman Ave, Suite #410 Irvine, CA 92612	Lab Job #: Project No: Location: Date Received:	553481 CENTENNIAL HS Centennial High School, 2606 N Central Ave., Compton, CA 90222 02/17/26

Sample ID	Lab ID	Collected	Matrix
DUP-01-2.5-260217	553481-053	02/17/26 00:00	Soil

Case Narrative

Terraphase Engineering 18401 Von Karman Ave, Suite #410 Irvine, CA 92612 Vanya Keyes	Lab Job Number: 553481 Project No: CENTENNIAL HS Location: Centennial High School, 2606 N Central Ave., Compton, CA 90222 Date Received: 02/17/26

This data package contains sample and QC results for thirty two soil samples, four three-point soil composites, four two-point soil composites, and one water sample, requested for the above referenced project on 02/17/26. The samples were received in good condition.

Pesticides (EPA 8081A) Water:
No analytical problems were encountered.

Pesticides (EPA 8081A) Soil:

- Lab numbers 553481-007, 553481-009, 553481-013, and 553481-014 were diluted due to the color of the sample extracts. Extract color and/or viscosity are used as indicators of possible matrix interference. Elevated reporting limits were due to the necessary dilutions.
- No other analytical problems were encountered.

PCBs (EPA 8082) Water:
No analytical problems were encountered.

PCBs (EPA 8082) Soil:

- Many samples were treated with sulfuric acid to reduce analytical interferences or due to the presence of color.
- No other analytical problems were encountered.

Metals (EPA 6010B) Water:
No analytical problems were encountered.

Metals (EPA 6010B) Soil:
No analytical problems were encountered.

100.1 Asbestos (EPA 100.1 Asbestos):
AmeriSci Los Angeles in Carson, CA performed the analysis (see sublab report section for certifications). Please see the AmeriSci Los Angeles case narrative.

Asbestos by PLM (EPA 600/R-93-116):
AmeriSci Los Angeles in Carson, CA performed the analysis (see sublab report section for certifications). Please see the AmeriSci Los Angeles case narrative.

ENTHALPY ANALYTICAL

Detection Summary

Vanya Keyes
Terraphase Engineering
18401 Von Karman Ave, Suite #410
Irvine, CA 92612

Lab Job #: 553481
Project No: CENTENNIAL HS
Location: Centennial High School, 2606 N Central Ave., Compton, CA 90222
Date Received: 02/17/26

Sample ID: AOC3-SB-49-0.5 **Lab ID: 553481-001** **Collected: 02/17/26 09:28**
Matrix: Soil

553481-001 Analyte	Result	Qual	Units	RL
Method: EPA 6010B Prep Method: EPA 3050B				
Lead	**8.0**		mg/Kg	0.95

Sample ID: AOC3-SB-48-0.5 **Lab ID: 553481-002** **Collected: 02/17/26 10:38**
Matrix: Soil

553481-002 Analyte	Result	Qual	Units	RL
Method: EPA 6010B Prep Method: EPA 3050B				
Lead	**38**		mg/Kg	0.98

Sample ID: AOC3-SB-47-0.5 **Lab ID: 553481-003** **Collected: 02/17/26 10:03**
Matrix: Soil

553481-003 Analyte	Result	Qual	Units	RL
Method: EPA 6010B Prep Method: EPA 3050B				
Lead	**15**		mg/Kg	0.96

Sample ID: CG-28-0.5 **Lab ID: 553481-007** **Collected: 02/17/26**

No Detections

Sample ID: CG-28-2.5 **Lab ID: 553481-008** **Collected: 02/17/26**

No Detections

Sample ID: CG-30-0.5 **Lab ID: 553481-009** **Collected: 02/17/26**

No Detections

Sample ID: CG-30-2.5 **Lab ID: 553481-010** **Collected: 02/17/26**

No Detections

Sample ID: CG-31-0.5 **Lab ID: 553481-011** **Collected: 02/17/26**

No Detections

Results for any subcontracted analyses are not included in this summary. Data qualifiers and additional information necessary for the interpretation of the test results are contained in the PDF file and may not be included in this summary.

ENTHALPY ANALYTICAL

Detection Summary

Sample ID: CG-31-2.5	Lab ID: 553481-012	Collected: 02/17/26

No Detections

Sample ID: CG-32-0.5	Lab ID: 553481-013	Collected: 02/17/26

No Detections

Sample ID: CG-32-2.5	Lab ID: 553481-014	Collected: 02/17/26

No Detections

Sample ID: EB-01-260217	Lab ID: 553481-015	Collected: 02/17/26 15:30

No Detections

Sample ID: AOC4-SB-09-0.5	Lab ID: 553481-016	Collected: 02/17/26 14:21
	Matrix: Soil	

553481-016 Analyte	Result	Qual	Units	RL
Method: EPA 6010B Prep Method: EPA 3050B				
Lead	**15**		mg/Kg	0.95

Sample ID: AOC4-SB-10-0.5	Lab ID: 553481-017	Collected: 02/17/26 14:38
	Matrix: Soil	

553481-017 Analyte	Result	Qual	Units	RL
Method: EPA 6010B Prep Method: EPA 3050B				
Lead	**25**		mg/Kg	0.97

Sample ID: AOC4-SB-11-0.5	Lab ID: 553481-020	Collected: 02/17/26 15:00
	Matrix: Soil	

553481-020 Analyte	Result	Qual	Units	RL
Method: EPA 6010B Prep Method: EPA 3050B				
Lead	**15**		mg/Kg	0.99

Sample ID: AOC4-SB-12-0.5	Lab ID: 553481-021	Collected: 02/17/26 15:12
	Matrix: Soil	

553481-021 Analyte	Result	Qual	Units	RL
Method: EPA 6010B Prep Method: EPA 3050B				
Lead	**39**		mg/Kg	1.0

Results for any subcontracted analyses are not included in this summary. Data qualifiers and additional information necessary for the interpretation of the test results are contained in the PDF file and may not be included in this summary.

ENTHALPY ANALYTICAL

Detection Summary

Sample ID: DUP-04-0.5-260217	Lab ID: 553481-024	Collected: 02/17/26
	Matrix: Soil	

553481-024 Analyte	Result	Qual	Units	RL
Method: EPA 6010B Prep Method: EPA 3050B				
Lead	**17**		mg/Kg	0.96

Sample ID: AOC4-SB-05-0.5	Lab ID: 553481-026	Collected: 02/17/26 12:00

No Detections

Sample ID: AOC4-SB-05-2.5	Lab ID: 553481-027	Collected: 02/17/26 12:06

No Detections

Sample ID: AOC4-SB-06-0.5	Lab ID: 553481-028	Collected: 02/17/26 12:10

No Detections

Sample ID: AOC4-SB-06-2.5	Lab ID: 553481-029	Collected: 02/17/26 12:21

No Detections

Sample ID: AOC4-SB-07-0.5	Lab ID: 553481-030	Collected: 02/17/26 13:45

No Detections

Sample ID: AOC4-SB-07-2.5	Lab ID: 553481-031	Collected: 02/17/26 13:50

No Detections

Sample ID: AOC4-SB-08-0.5	Lab ID: 553481-032	Collected: 02/17/26 13:52

No Detections

Sample ID: AOC4-SB-08-2.5	Lab ID: 553481-033	Collected: 02/17/26 13:57

No Detections

Sample ID: DUP-03-0.5-260217	Lab ID: 553481-034	Collected: 02/17/26

No Detections

Results for any subcontracted analyses are not included in this summary. Data qualifiers and additional information necessary for the interpretation of the test results are contained in the PDF file and may not be included in this summary.

ENTHALPY ANALYTICAL

Detection Summary

Sample ID: DUP-03-2.5-260217	Lab ID: 553481-035	Collected: 02/17/26

No Detections

Sample ID: AOC4-SB-01-0.5	Lab ID: 553481-036	Collected: 02/17/26 11:06

No Detections

Sample ID: AOC4-SB-01-2.5	Lab ID: 553481-037	Collected: 02/17/26 11:10

No Detections

Sample ID: AOC4-SB-02-0.5	Lab ID: 553481-038	Collected: 02/17/26 11:14

No Detections

Sample ID: AOC4-SB-02-2.5	Lab ID: 553481-039	Collected: 02/17/26 11:21

No Detections

Sample ID: DUP-02-0.5-260217	Lab ID: 553481-040	Collected: 02/17/26

No Detections

Sample ID: DUP-02-2.5-260217	Lab ID: 553481-041	Collected: 02/17/26

No Detections

Sample ID: AOC4-SB-03-0.5	Lab ID: 553481-042	Collected: 02/17/26 11:27

No Detections

Sample ID: AOC4-SB-03-2.5	Lab ID: 553481-043	Collected: 02/17/26 11:38

No Detections

Sample ID: AOC4-SB-04-0.5	Lab ID: 553481-044	Collected: 02/17/26 11:50

No Detections

Sample ID: AOC4-SB-04-2.5	Lab ID: 553481-045	Collected: 02/17/26 11:53

No Detections

Results for any subcontracted analyses are not included in this summary. Data qualifiers and additional information necessary for the interpretation of the test results are contained in the PDF file and may not be included in this summary.

ENTHALPY ANALYTICAL

Detection Summary

Sample ID: AOC3-SB-43-0.5	Lab ID: 553481-046	Collected: 02/17/26 07:55
	Matrix: Soil	

553481-046 Analyte	Result	Qual	Units	RL
Method: EPA 6010B Prep Method: EPA 3050B				
Lead	**32**		mg/Kg	0.97

Sample ID: AOC3-SB-42-0.5	Lab ID: 553481-047	Collected: 02/17/26 08:18
	Matrix: Soil	

553481-047 Analyte	Result	Qual	Units	RL
Method: EPA 6010B Prep Method: EPA 3050B				
Lead	**32**		mg/Kg	0.95

Sample ID: AOC3-SB-41-0.5	Lab ID: 553481-048	Collected: 02/17/26 08:39
	Matrix: Soil	

553481-048 Analyte	Result	Qual	Units	RL
Method: EPA 6010B Prep Method: EPA 3050B				
Lead	**25**		mg/Kg	0.95

Sample ID: DUP-01-0.5-260217	Lab ID: 553481-052	Collected: 02/17/26
	Matrix: Soil	

553481-052 Analyte	Result	Qual	Units	RL
Method: EPA 6010B Prep Method: EPA 3050B				
Lead	**25**		mg/Kg	0.95

Results for any subcontracted analyses are not included in this summary. Data qualifiers and additional information necessary for the interpretation of the test results are contained in the PDF file and may not be included in this summary.

Login 553481

931 W. Barkley Avenue, Orange, CA 92868

Phone 714-771-6900

ALPY ICAL

Chain of Custody Record

Lab No: 553481

Page: 1 of 6

Turn Around Time (rush by advanced notice only)

Standard:	X	5 Day:		3 Day:	
2 Day:		1 Day:		Custom TAT	

Matrix: A = Air, S = Soil/Solid, W = Water, DW = Drinking Water, P = Product, O = Oil, SD = Sediment, T = Tissue, WP = Wipe, WW = Wastewater, X = Other

Sample Type: C = Composite, G = Grab or Discrete, B = Blank, O = Other

Preservatives: 0 = none, 1 = $Na_2S_2O_3$, 2 = HCl, 3 = HNO_3, 4 = H_2SO_4, 5 = NaOH, 6 = Other

Sample Receipt Temp and Notes: (lab use only)

CUSTOMER INFORMATION

Company:	Terraphase Engineering Inc.
Report To:	Vanya Keyes
Email:	vanya.keyes@terraphase.com
Address:	18401 Von Karman Ave
	Irvine CA
Phone:	949-377-2227
Fax:	

PROJECT INFORMATION

Name:	Centennial High School
Number:	0215.002.002
P.O. #:	
Address:	2606 N Central Ave
	Compton, CA, 90222
Global ID:	
Sampled By:	Portia C. Ibarra

Test Instructions / Comments

Please also send report to
clare.steedman@terraphase.com
portia.ibarra@terraphase.com

1R10
0.810 gms
1.0

	Sample ID	Sampling Date	Sampling Time (24 hr)	Matrix	Sample Type	Pres.	Cont. No.	Cont. Size	Initials	Arsenic (6020)	Lead (6010B)	PCBs (8082)	Title 22 Metals (6020/7471A)	Dioxins & Furins (8290A)	VOCs (8260B)	TPH (8015)		Test Instructions / Comments
1	AOC3-SB-49-0.5	2/17/26	928	S	G	0	1	80z	PCI		X	X						
2	AOC3-SB-48-0.5	"	1038	"	"	"	"	"	"		X	X						CG-30-0.5
3	AOC3-SB-47-0.5	"	1003	"	"	"	"	"	"		X	X						
4	AOC3-SB-49-2.5	"	935	"	"	"	"	"	"	PI	X	X	PI					
5	AOC3-SB-48-2.5	"	1048	"	"	"	"	"	"	PI	X	X	PI					CG-30-2.5
6	AOC3-SB-47-2.5	"	1028	S	G	0	1	80z	PCI	PI	X	X	PI					
~~7~~	~~EB-01-260217~~	~~2/17/26~~	~~1530~~	~~W~~	~~G~~	~~3~~	~~3~~	~~2 amb 1 poly~~	~~PCI~~									
8	PI																	
9																		
10																		

	Signature	Print Name	Company / Title	Date / Time
1 Relinquished By:		PORTIA IBARRA	TER / GEO	2/17/26 / 1550
1 Received By:		John Zachman	EA/WH	02/17/26 1550
2 Relinquished By:		John Zachman	EA/WH	02/17/26 1630
2 Received By:		Kierstoken	EA	2/17/26 1703
3 Relinquished By:		Kierstoken	EA	2/17/26 1738

Rec'd 2/18/26 EA 2/17/26 1738

11 of 65

ENTHALPY ANALYTICAL

Chain of Custody Record

Lab No: 553481

Page: 2 of 6

Turn Around Time (rush by advanced notice only)

Standard:	X	5 Day:		3 Day:	
2 Day:		1 Day:		Custom TAT	

Enthalpy Analytical - Orange

931 W. Barkley Avenue, Orange, CA 92868

Phone 714-771-6900

Matrix: A = Air, S = Soil/Solid, W = Water, DW = Drinking Water, P = Product, O = Oil, SD = Sediment, T = Tissue, WP = Wipe, WW = Wastewater, X = Other

Sample Type: C = Composite, G = Grab or Discrete, B = Blank, O = Other

Preservatives: 0 = none, 1 = $Na_2S_2O_3$, 2 = HCl, 3 = HNO_3, 4 = H_2SO_4, 5 = NaOH, 6 = Other

Sample Receipt Temp and Notes: (lab use only)

CUSTOMER INFORMATION		PROJECT INFORMATION	
Company:	Terraphase Engineering Inc.	Name:	Centennial High School
Report To:	Vanya Keyes	Number:	
Email:	vanya.keyes@terraphase.com	P.O. #:	0215.002.002
Address:	18401 Von Karman Ave	Address:	2606 N Central Ave
	Irvine CA		Compton, CA, 90222
Phone:	949-377-2227	Global ID:	
Fax:		Sampled By:	Portia C. Ibarra

Test Instructions / Comments: Please also send report to clare.steedman@terraphase.com portia.ibarra@terraphase.com

	Sample ID	Sampling Date	Sampling Time (24 hr)	Matrix	Sample Type	Pres.	Cont. No.	Cont. Size	Initials	OCPs by USEPA 8081A	Asbestos by PLM	PCBs 8082	Lead 6010					
1	CG-28-0.5	~~2/17/26~~								X	X							
2	CG-28-2.5									X	X							
3	CG-30-0.5									X	X							
4	CG-30-2.5									X	X							
5	CG-31-0.5									X	X							
6	CG-31-2.5									X	X							
7	CG-32-0.5									X	X							
8	CG-32-2.5									X	X							
9	EB-01-260217	2/17/26	1530	W	G	3	3	2amb 1poly	PCI	X	X	X	X					
10																		

	Signature	Print Name	Company / Title	Date / Time
1 Relinquished By:		Portia Ibarra	TE/EA	2/17/26 / 1550
1 Received By:		John Zachman	EA/NH	02/17/26 1550
2 Relinquished By:		John Zachman	EA/NH	02/17/26 EEJX2 ~~1730~~ 1630
2 Received By:		Portia Ibarra	EA	2/17/26 1730
3 Relinquished By:		Portia Ibarra	EA	2/17/26 1735

Rec'd by EA 2/17/26 1735

ENTHALPY ANALYTICAL

Chain of Custody Record

Lab No: 553481

Page: 3 of 6

Turn Around Time (rush by advanced notice only)

Standard:	X	5 Day:		3 Day:	
2 Day:		1 Day:		Custom TAT	

Enthalpy Analytical - Orange

931 W. Barkley Avenue, Orange, CA 92868

Phone 714-771-6900

Matrix: **A** = Air **S** = Soil/Solid **W** = Water **DW** = Drinking Water **P** = Product **O** = Oil **SD** = Sediment **T** = Tissue **WP** = Wipe **WW** = Wastewater **X** = Other

Sample Type: **C** = Composite **G** = Grab or Discrete **B** = Blank **O** = Other

Preservatives: **0** = none **1** = $Na_2S_2O_3$ **2** = HCl **3** = HNO_3 **4** = H_2SO_4 **5** = NaOH **6** = Other

Sample Receipt Temp and Notes: (lab use only)

CUSTOMER INFORMATION		PROJECT INFORMATION	
Company:	Terraphase Engineering Inc.	Name:	Centennial High School
Report To:	Vanya Keyes	Number:	
Email:	vanya.keyes@terraphase.com	P.O. #:	0215.002.002
Address:	18401 Von Karman Ave	Address:	2606 N Central Ave
	Irvine CA		Compton, CA, 90222
Phone:	949-377-2227	Global ID:	
Fax:		Sampled By:	Portia C. Ibarra

Test Instructions / Comments: Please also send report to clare.steedman@terraphase.com portia.ibarra@terraphase.com

	Sample ID	Sampling Date	Sampling Time (24 hr)	Matrix	Sample Type	Pres.	Cont. No.	Cont. Size	Initials	Arsenic (6020)	Lead (6010B)	PCBs (8082)	Title 22 Metals (6020/7471A)	Dioxins & Furins (8290A)	VOCs (8260B)	TPH (8015)		Test Instructions / Comments
1	GOCY-SB-09-0.5	2/17/26	1421	S	G	0	1	80z	PCI		X	X						CG-31-0.5
2	GOCY-SB-10-0.5	"	1438	"	"	"	"	"	"		X	X						"
3	GOCY-SB-09-2.5	"	1430	"	"	"	"	"	"									CG-31-2.5
4	GOCY-SB-10-25	"	1442	"	"	"	"	"	"									"
5	GOCY-SB-11-0.5	"	1500	"	"	"	"	"	"		X	X						CG-32-0.5
6	GOCY-SB-12-0.5	"	1512	"	"	"	"	"	"		X	X						"
7	GOCY-SB-11-2.5	"	1505	"	"	"	"	"	"									CG-32-2.5
8	GOCY-SB-12-2.5	"	1516	"	"	"	"	"	"									"
9	DUP-04-0.5-260217	"	—	"	"	"	"	"	"		X	X						
10	DUP-04-2.5-260217	2/17/26	—	S	G	0	1	80z	PCI									hold

	Signature	Print Name	Company / Title	Date / Time
1 Relinquished By:		PORTIA IBARRA	TCI / TERRAPHASE	2/17/26 1550
1 Received By:		John Zuckman	EA/NH	02/17/26 1550
2 Relinquished By:		John Zuckman	EA/NH	02/17/26 1630
2 Received By:		Ron Dohm	EA	2/17/26 1723
3 Relinquished By:		Ron Dohm	EA	2/17/26 1738

Rec: AdOk FA 2/19/26 1738

ENTHALPY ANALYTICAL

Chain of Custody Record

Lab No: 553481

Page: 4 of 6

Turn Around Time (rush by advanced notice only)

Standard:	X	5 Day:		3 Day:	
2 Day:		1 Day:		Custom TAT	

Enthalpy Analytical - Orange

931 W. Barkley Avenue, Orange, CA 92868

Phone 714-771-6900

Matrix: **A** = Air **S** = Soil/Solid **W** = Water **DW** = Drinking Water **P** = Product **O** = Oil **SD** = Sediment **T** = Tissue **WP** = Wipe **WW** = Wastewater **X** = Other

Sample Type: **C** = Composite **G** = Grab or Discrete **B** = Blank **O** = Other

Preservatives: **0** = none **1** = $Na_2S_2O_3$ **2** = HCl **3** = HNO_3 **4** = H_2SO_4 **5** = NaOH **6** = Other

Sample Receipt Temp and Notes: (lab use only)

CUSTOMER INFORMATION		PROJECT INFORMATION	
Company:	Terraphase Engineering Inc.	Name:	Centennial High School
Report To:	Vanya Keyes	Number:	
Email:	vanya.keyes@terraphase.com	P.O. #:	0215.002.002
Address:	18401 Von Karman Ave	Address:	2606 N Central Ave
			Compton, CA, 90222
Phone:	949-377-2227	Global ID:	
Fax:		Sampled By:	Portia C. Ibarra

Test Instructions / Comments: Please also send report to clare.steedman@terraphase.com portia.ibarra@terraphase.com

	Sample ID	Sampling Date	Sampling Time (24 hr)	Matrix	Sample Type	Pres.	Cont. No.	Cont. Size	Initials	Arsenic (6020)	Lead (6010B)	PCBs (8082)	Title 22 Metals (6020/7471A)	Dioxins & Furins (8290A)	VOCs (8260B)	TPH (8015)	
1	AOC4-SB-05-0.5	2/17/26	1200	S	G	0	1	8oz	PCI			X					
2	AOC4-SB-05-2.5		1206									X					
3	AOC4-SB-06-0.5		1210									X					
4	AOC4-SB-06-2.5		1221									X					
5	AOC4-SB-07-0.5		1345									X					
6	AOC4-SB-07-2.5		1350									X					
7	AOC4-SB-08-0.5		1352									X					
8	AOC4-SB-08-2.5		1357									X					
9	DUP-03-0.5-260217		—									X					
10	DUP-03-0.5-260217	2/17/26	—	S	G	0	1	8oz	PCI			X					

	Signature	Print Name	Company / Title	Date / Time
1 Relinquished By:		Portia Ibarra	TEI / GDL	2/17/26 1550
1 Received By:		John Zachman	EA / WH	02/17/26 1550
2 Relinquished By:		John Zachman	EA / WH	02/17/26 1630
2 Received By:			EA	2/17/26 1705
3 Relinquished By:			EA	2/17/26 1738

Rec'd Addn'l EA 2/17/26 1738

ENTHALPY ANALYTICAL

Chain of Custody Record

Lab No: 553481

Page: 5 of 6

Turn Around Time (rush by advanced notice only)

Standard:	X	5 Day:		3 Day:	
2 Day:		1 Day:		Custom TAT	

Enthalpy Analytical - Orange

931 W. Barkley Avenue, Orange, CA 92868

Phone 714-771-6900

Matrix: **A** = Air **S** = Soil/Solid **W** = Water **DW** = Drinking Water **P** = Product **O** = Oil **SD** = Sediment **T** = Tissue **WP** = Wipe **WW** = Wastewater **X** = Other

Sample Type: **C** = Composite **G** = Grab or Discrete **B** = Blank **O** = Other

Preservatives: **0** = none **1** = $Na_2S_2O_3$ **2** = HCl **3** = HNO_3 **4** = H_2SO_4 **5** = NaOH **6** = Other

Sample Receipt Temp and Notes: (lab use only)

CUSTOMER INFORMATION		PROJECT INFORMATION	
Company:	Terraphase Engineering Inc.	Name:	Centennial High School
Report To:	Vanya Keyes	Number:	
Email:	vanya.keyes@terraphase.com	P.O. #:	0215.002.002
Address:	18401 Von Karman Ave	Address:	2606 N Central Ave
	Irvine CA		Compton, CA, 90222
Phone:	949-377-2227	Global ID:	
Fax:		Sampled By:	Portia C. Ibarra

Test Instructions / Comments: Please also send report to clare.steedman@terraphase.com portia.ibarra@terraphase.com

	Sample ID	Sampling Date	Sampling Time (24 hr)	Matrix	Sample Type	Pres.	Cont. No.	Cont. Size	Initials	Arsenic (6020)	Lead (6010B)	PCBs (8082)	Title 22 Metals (6020/7471A)	Dioxins & Furins (8290A)	VOCs (8260B)	TPH (8015)	
1	AOC4-SB-01-0.5	2/17/26	1106	S	G	O	1	807	PCI			X					
2	AOC4-SB-01-2.5		1110									X					
3	AOC4-SB-02-0.5		1114									X					
4	AOC4-SB-02-2.5		1121									X					
5	DUP-02-0.5-260217		~~1127~~ PI									X					
6	DUP-02-2.5-260217		—									X					
7	AOC4-SB-03-0.5		1127									X					
8	AOC4-SB-03-2.5		1138									X					
9	AOC4-SB-04-0.5		1150									X					
10	AOC4-SB-04-2.5	2/17/26	1153	S	G	O	1	807	PCI			X					

	Signature	Print Name	Company / Title	Date / Time
1 Relinquished By:		Portia Ibarra	TEI / Geol	2/17/26 / 1550
1 Received By:		John Zachman	EA / WH	02/17/26 1550
2 Relinquished By:		John Zachman	EA / WH	02/17/26 1630
2 Received By:			EA	2/17/26 1903
3 Relinquished By:			EA	2/17/26 1738

Rec: Add'l FA 2/17/26 1738

ENTHALPY ANALYTICAL

Chain of Custody Record

Lab No: 553481

Page: 6 of 6

Turn Around Time (rush by advanced notice only)

Standard:	X	5 Day:		3 Day:	
2 Day:		1 Day:		Custom TAT	

Enthalpy Analytical - Orange

931 W. Barkley Avenue, Orange, CA 92868

Phone 714-771-6900

Matrix: **A** = Air **S** = Soil/Solid **W** = Water **DW** = Drinking Water **P** = Product **O** = Oil **SD** = Sediment **T** = Tissue **WP** = Wipe **WW** = Wastewater **X** = Other

Sample Type: **C** = Composite **G** = Grab or Discrete **B** = Blank **O** = Other

Preservatives: **0** = none **1** = $Na_2S_2O_3$ **2** = HCl **3** = HNO_3 **4** = H_2SO_4 **5** = NaOH **6** = Other

Sample Receipt Temp and Notes: (lab use only)

CUSTOMER INFORMATION		PROJECT INFORMATION	
Company:	Terraphase Engineering Inc.	Name:	Centennial High School
Report To:	Vanya Keyes	Number:	
Email:	vanya.keyes@terraphase.com	P.O. #:	0215.002.002
Address:	18401 Von Karman Ave	Address:	2606 N Central Ave
	Irvine CA		Compton, CA, 90222
Phone:	949-377-2227	Global ID:	
Fax:		Sampled By:	Portia C. Ibarra

Test Instructions / Comments: Please also send report to clare.steedman@terraphase.com portia.ibarra@terraphase.com

	Sample ID	Sampling Date	Sampling Time (24 hr)	Matrix	Sample Type	Pres.	Cont. No.	Cont. Size	Initials	Arsenic (6020)	Lead (6010B)	PCBs (8082)	Title 22 Metals (6020/7471A)	Dioxins & Furins (8290A)	VOCs (8260B)	TPH (8015)		Test Instructions / Comments
16	1 AOC3-SB-43-0.5	2/17/26	0755	S	G	0	1	807	PCI		X	X						}
17	2 AOC3-SB-42-0.5	"	0818	"	"	"	"	"	"		X	X						} CG-28-0.5
18	3 AOC3-SB-41-0.5	"	0839	"	"	"	"	"	"		X	X						}
4	4 AOC3-SB-43-2.5	"	0812	"	"	"	"	"	"									}
5	5 AOC3-SB-42-2.5	"	0842	"	"	"	"	"	"									} CG-28-2.5
1	6 AOC3-SB-41-2.5	"	0846	"	"	"	"	"	"									}
2	7 DUP-01-0.5-260217	"	—	"	"	"	"	"	"		X	X						
3	8 DUP-01-2.5-260217	2/17/26	—	S	G	0	1	807	PCI									hold
	9																	
	10																	

	Signature	Print Name	Company / Title	Date / Time
1 Relinquished By:	[signature]	Portia Ibarra	TEI / Geol	2/17/26 / 1550
1 Received By:	[signature]	John Zachman	EA/WH	02/17/26 1550
2 Relinquished By:	[signature]	John Zachman	EA/WH	02/17/26 1630
2 Received By:	[signature]	[signature]	EA	2/17/26 1703
3 Relinquished By:	[signature]	[signature]	EA	2/17/26 1738

Received at EA 2/17/26 1738

SAMPLE RECEIPT CHECKLIST

Section 1: General Info

Date Received: 2/17/26 WO# 553481 Client: Terraphase

Section 2: Shipping / Custody **Are custody seals present?** ☐ Yes ☒ No

Custody seals intact on arrival? ■ N/A ☐ Yes ☐ No ☐ On cooler / box ☐ On samples

■ Courier ☐ Walk-In ☐ Field Sampling ☐ Shipping Info: _____

Section 3a: Condition / Packaging ☐ **Outside 0.0 - 6.0°C (0.0 - 10.0°C for microbiology) (PM notified)**

Date Opened 2/17/26 By (initials) RRS Type of ice used: ■ Wet ☐ Blue/Gel ☐ None

☐ Samples received on ice directly from the field; cooling process had begun. (if checked, skip temperatures)

☐ Sample matrix doesn't require cooling (e.g. air, bulk PCB). (if checked, skip temperatures)

If no cooler: Observed/Adjusted Temp (°C): _____ / _____ Thermometer/IR Gun: IR10 CF: +0.2

Cooler Temp (°C) #1: 0.8 / 1.0 #2: ____ / ____ #3: ____ / ____ #4: ____ / ____ #5: ____ / ____ #6: ____ / ____

Section 3b: Microbiology Samples ■ **No microbiology samples submitted (skip 3b)**

☐ Within temp range 0.0 - 10.0°C or received on ice directly from field.

☐ Adequate headspace for microbiology analysis.

Section 3c: Air Samples ■ **No air samples submitted (skip 3c)**

☐ 1.4L Canisters ☐ 6L Canisters ☐ Tedlar Bags ☐ MCE Cassettes ☐ Sorbent Tubes ☐ Other _____

Section 4: Containers / Labels / Samples	YES	NO	N/A
1) Were custody papers present, filled properly, and legible?	X		
2) Is the sampler's name present on the CoC?	X		
3) Were containers received in good condition (unbroken / unopened / uncompromised)?	X		
4) Were the samples bagged? (required for microbiology samples; recommended for soil samples)			
5) Were all of, and only, the correct samples received?			
6) Are sample labels present, legible, and in agreement with the CoC?			
7) Does the container count match the CoC?			
8) Was sufficient sample volume / mass received for the analyses requested?	X		
9) Were samples received in proper containers for the analyses requested?	X		
10) Were samples received with > 1/2 holding time remaining?	X		
11) Are samples properly preserved as indicated by CoC / labels?	X		
12) Unpreserved VOAs received - If necessary, was the hold time changed in LIMS?			X
13) Are VOA vials free from headspace/bubbles > 6mm?			X

Section 5: Explanations / Comments

(If no comments are made, then no discrepancies noted.)

☐ **No additional discrepancies**

Date Logged 2/17/26 **By (print)** ABD **(sign)** AdW

Date Labeled _____ **By (print)** _____ **(sign)** _____

ENTHALPY ANALYTICAL

Analysis Results for 553481

Vanya Keyes
Terraphase Engineering
18401 Von Karman Ave, Suite #410
Irvine, CA 92612

Lab Job #: 553481
Project No: CENTENNIAL HS
Location: Centennial High School, 2606 N Central Ave., Compton, CA 90222
Date Received: 02/17/26

Sample ID: AOC3-SB-49-0.5 **Lab ID: 553481-001** **Collected: 02/17/26 09:28**
Matrix: Soil

553481-001 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3050B									
Lead	**8.0**		mg/Kg	0.95	0.95	395888	02/20/26	02/20/26	KAM
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1221	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1232	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1242	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1248	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1254	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1260	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1262	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1268	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Total PCBs	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	95%		%REC	50-127	1	396025	02/21/26	02/23/26	KLR

Sample ID: AOC3-SB-48-0.5 **Lab ID: 553481-002** **Collected: 02/17/26 10:38**
Matrix: Soil

553481-002 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3050B									
Lead	**38**		mg/Kg	0.98	0.98	395888	02/20/26	02/20/26	KAM
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	50	1	396025	02/21/26	02/23/26	KLR
Aroclor-1221	ND		ug/Kg	50	1	396025	02/21/26	02/23/26	KLR
Aroclor-1232	ND		ug/Kg	50	1	396025	02/21/26	02/23/26	KLR
Aroclor-1242	ND		ug/Kg	50	1	396025	02/21/26	02/23/26	KLR
Aroclor-1248	ND		ug/Kg	50	1	396025	02/21/26	02/23/26	KLR
Aroclor-1254	ND		ug/Kg	50	1	396025	02/21/26	02/23/26	KLR
Aroclor-1260	ND		ug/Kg	50	1	396025	02/21/26	02/23/26	KLR
Aroclor-1262	ND		ug/Kg	50	1	396025	02/21/26	02/23/26	KLR
Aroclor-1268	ND		ug/Kg	50	1	396025	02/21/26	02/23/26	KLR
Total PCBs	ND		ug/Kg	50	1	396025	02/21/26	02/23/26	KLR
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	97%		%REC	50-127	1	396025	02/21/26	02/23/26	KLR

Results for any subcontracted analyses are not included in this section.

ENTHALPY ANALYTICAL

Analysis Results for 553481

Sample ID: AOC3-SB-47-0.5 **Lab ID: 553481-003** **Collected: 02/17/26 10:03**
Matrix: Soil

553481-003 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3050B									
Lead	**15**		mg/Kg	0.96	0.96	395888	02/20/26	02/20/26	KAM
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	49	0.98	396025	02/21/26	02/23/26	KLR
Aroclor-1221	ND		ug/Kg	49	0.98	396025	02/21/26	02/23/26	KLR
Aroclor-1232	ND		ug/Kg	49	0.98	396025	02/21/26	02/23/26	KLR
Aroclor-1242	ND		ug/Kg	49	0.98	396025	02/21/26	02/23/26	KLR
Aroclor-1248	ND		ug/Kg	49	0.98	396025	02/21/26	02/23/26	KLR
Aroclor-1254	ND		ug/Kg	49	0.98	396025	02/21/26	02/23/26	KLR
Aroclor-1260	ND		ug/Kg	49	0.98	396025	02/21/26	02/23/26	KLR
Aroclor-1262	ND		ug/Kg	49	0.98	396025	02/21/26	02/23/26	KLR
Aroclor-1268	ND		ug/Kg	49	0.98	396025	02/21/26	02/23/26	KLR
Total PCBs	ND		ug/Kg	49	0.98	396025	02/21/26	02/23/26	KLR
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	89%		%REC	50-127	0.98	396025	02/21/26	02/23/26	KLR

Sample ID: CG-28-0.5 **Lab ID: 553481-007** **Collected: 02/17/26**
Matrix: Soil

553481-007 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 8081A Prep Method: EPA 3546									
alpha-BHC	ND		ug/Kg	9.9	2	395871	02/20/26	02/22/26	XLY
beta-BHC	ND		ug/Kg	9.9	2	395871	02/20/26	02/22/26	XLY
gamma-BHC	ND		ug/Kg	9.9	2	395871	02/20/26	02/22/26	XLY
delta-BHC	ND		ug/Kg	9.9	2	395871	02/20/26	02/22/26	XLY
Heptachlor	ND		ug/Kg	9.9	2	395871	02/20/26	02/22/26	XLY
Aldrin	ND		ug/Kg	9.9	2	395871	02/20/26	02/22/26	XLY
Heptachlor epoxide	ND		ug/Kg	9.9	2	395871	02/20/26	02/22/26	XLY
Endosulfan I	ND		ug/Kg	9.9	2	395871	02/20/26	02/22/26	XLY
Dieldrin	ND		ug/Kg	9.9	2	395871	02/20/26	02/22/26	XLY
4,4'-DDE	ND		ug/Kg	9.9	2	395871	02/20/26	02/22/26	XLY
Endrin	ND		ug/Kg	9.9	2	395871	02/20/26	02/22/26	XLY
Endosulfan II	ND		ug/Kg	9.9	2	395871	02/20/26	02/22/26	XLY
Endosulfan sulfate	ND		ug/Kg	9.9	2	395871	02/20/26	02/22/26	XLY
4,4'-DDD	ND		ug/Kg	9.9	2	395871	02/20/26	02/22/26	XLY
Endrin aldehyde	ND		ug/Kg	9.9	2	395871	02/20/26	02/22/26	XLY
Endrin ketone	ND		ug/Kg	9.9	2	395871	02/20/26	02/22/26	XLY
4,4'-DDT	ND		ug/Kg	9.9	2	395871	02/20/26	02/22/26	XLY
Methoxychlor	ND		ug/Kg	20	2	395871	02/20/26	02/22/26	XLY
Toxaphene	ND		ug/Kg	200	2	395871	02/20/26	02/22/26	XLY
Chlordane (Technical)	ND		ug/Kg	99	2	395871	02/20/26	02/22/26	XLY
Surrogates				**Limits**					
TCMX	89%		%REC	58-120	2	395871	02/20/26	02/22/26	XLY
Decachlorobiphenyl	106%		%REC	47-120	2	395871	02/20/26	02/22/26	XLY

Results for any subcontracted analyses are not included in this section.

ENTHALPY ANALYTICAL

Analysis Results for 553481

Sample ID: CG-28-2.5	Lab ID: 553481-008	Collected: 02/17/26
	Matrix: Soil	

553481-008 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 8081A Prep Method: EPA 3546									
alpha-BHC	ND		ug/Kg	5.1	1	395871	02/20/26	02/23/26	XLY
beta-BHC	ND		ug/Kg	5.1	1	395871	02/20/26	02/23/26	XLY
gamma-BHC	ND		ug/Kg	5.1	1	395871	02/20/26	02/23/26	XLY
delta-BHC	ND		ug/Kg	5.1	1	395871	02/20/26	02/23/26	XLY
Heptachlor	ND		ug/Kg	5.1	1	395871	02/20/26	02/23/26	XLY
Aldrin	ND		ug/Kg	5.1	1	395871	02/20/26	02/23/26	XLY
Heptachlor epoxide	ND		ug/Kg	5.1	1	395871	02/20/26	02/23/26	XLY
Endosulfan I	ND		ug/Kg	5.1	1	395871	02/20/26	02/23/26	XLY
Dieldrin	ND		ug/Kg	5.1	1	395871	02/20/26	02/23/26	XLY
4,4'-DDE	ND		ug/Kg	5.1	1	395871	02/20/26	02/23/26	XLY
Endrin	ND		ug/Kg	5.1	1	395871	02/20/26	02/23/26	XLY
Endosulfan II	ND		ug/Kg	5.1	1	395871	02/20/26	02/23/26	XLY
Endosulfan sulfate	ND		ug/Kg	5.1	1	395871	02/20/26	02/23/26	XLY
4,4'-DDD	ND		ug/Kg	5.1	1	395871	02/20/26	02/23/26	XLY
Endrin aldehyde	ND		ug/Kg	5.1	1	395871	02/20/26	02/23/26	XLY
Endrin ketone	ND		ug/Kg	5.1	1	395871	02/20/26	02/23/26	XLY
4,4'-DDT	ND		ug/Kg	5.1	1	395871	02/20/26	02/23/26	XLY
Methoxychlor	ND		ug/Kg	10	1	395871	02/20/26	02/23/26	XLY
Toxaphene	ND		ug/Kg	100	1	395871	02/20/26	02/23/26	XLY
Chlordane (Technical)	ND		ug/Kg	51	1	395871	02/20/26	02/23/26	XLY
Surrogates				**Limits**					
TCMX	88%		%REC	58-120	1	395871	02/20/26	02/23/26	XLY
Decachlorobiphenyl	94%		%REC	47-120	1	395871	02/20/26	02/23/26	XLY

Results for any subcontracted analyses are not included in this section.

ENTHALPY ANALYTICAL

Analysis Results for 553481

Sample ID: CG-30-0.5	Lab ID: 553481-009	Collected: 02/17/26
	Matrix: Soil	

553481-009 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 8081A Prep Method: EPA 3546									
alpha-BHC	ND		ug/Kg	10	2	395871	02/20/26	02/23/26	XLY
beta-BHC	ND		ug/Kg	10	2	395871	02/20/26	02/23/26	XLY
gamma-BHC	ND		ug/Kg	10	2	395871	02/20/26	02/23/26	XLY
delta-BHC	ND		ug/Kg	10	2	395871	02/20/26	02/23/26	XLY
Heptachlor	ND		ug/Kg	10	2	395871	02/20/26	02/23/26	XLY
Aldrin	ND		ug/Kg	10	2	395871	02/20/26	02/23/26	XLY
Heptachlor epoxide	ND		ug/Kg	10	2	395871	02/20/26	02/23/26	XLY
Endosulfan I	ND		ug/Kg	10	2	395871	02/20/26	02/23/26	XLY
Dieldrin	ND		ug/Kg	10	2	395871	02/20/26	02/23/26	XLY
4,4'-DDE	ND		ug/Kg	10	2	395871	02/20/26	02/23/26	XLY
Endrin	ND		ug/Kg	10	2	395871	02/20/26	02/23/26	XLY
Endosulfan II	ND		ug/Kg	10	2	395871	02/20/26	02/23/26	XLY
Endosulfan sulfate	ND		ug/Kg	10	2	395871	02/20/26	02/23/26	XLY
4,4'-DDD	ND		ug/Kg	10	2	395871	02/20/26	02/23/26	XLY
Endrin aldehyde	ND		ug/Kg	10	2	395871	02/20/26	02/23/26	XLY
Endrin ketone	ND		ug/Kg	10	2	395871	02/20/26	02/23/26	XLY
4,4'-DDT	ND		ug/Kg	10	2	395871	02/20/26	02/23/26	XLY
Methoxychlor	ND		ug/Kg	20	2	395871	02/20/26	02/23/26	XLY
Toxaphene	ND		ug/Kg	200	2	395871	02/20/26	02/23/26	XLY
Chlordane (Technical)	ND		ug/Kg	100	2	395871	02/20/26	02/23/26	XLY
Surrogates				**Limits**					
TCMX	86%		%REC	58-120	2	395871	02/20/26	02/23/26	XLY
Decachlorobiphenyl	99%		%REC	47-120	2	395871	02/20/26	02/23/26	XLY

Results for any subcontracted analyses are not included in this section.

ENTHALPY ANALYTICAL

Analysis Results for 553481

Sample ID: CG-30-2.5	Lab ID: 553481-010	Collected: 02/17/26
	Matrix: Soil	

553481-010 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 8081A Prep Method: EPA 3546									
alpha-BHC	ND		ug/Kg	5.0	1	395871	02/20/26	02/23/26	XLY
beta-BHC	ND		ug/Kg	5.0	1	395871	02/20/26	02/23/26	XLY
gamma-BHC	ND		ug/Kg	5.0	1	395871	02/20/26	02/23/26	XLY
delta-BHC	ND		ug/Kg	5.0	1	395871	02/20/26	02/23/26	XLY
Heptachlor	ND		ug/Kg	5.0	1	395871	02/20/26	02/23/26	XLY
Aldrin	ND		ug/Kg	5.0	1	395871	02/20/26	02/23/26	XLY
Heptachlor epoxide	ND		ug/Kg	5.0	1	395871	02/20/26	02/23/26	XLY
Endosulfan I	ND		ug/Kg	5.0	1	395871	02/20/26	02/23/26	XLY
Dieldrin	ND		ug/Kg	5.0	1	395871	02/20/26	02/23/26	XLY
4,4'-DDE	ND		ug/Kg	5.0	1	395871	02/20/26	02/23/26	XLY
Endrin	ND		ug/Kg	5.0	1	395871	02/20/26	02/23/26	XLY
Endosulfan II	ND		ug/Kg	5.0	1	395871	02/20/26	02/23/26	XLY
Endosulfan sulfate	ND		ug/Kg	5.0	1	395871	02/20/26	02/23/26	XLY
4,4'-DDD	ND		ug/Kg	5.0	1	395871	02/20/26	02/23/26	XLY
Endrin aldehyde	ND		ug/Kg	5.0	1	395871	02/20/26	02/23/26	XLY
Endrin ketone	ND		ug/Kg	5.0	1	395871	02/20/26	02/23/26	XLY
4,4'-DDT	ND		ug/Kg	5.0	1	395871	02/20/26	02/23/26	XLY
Methoxychlor	ND		ug/Kg	10	1	395871	02/20/26	02/23/26	XLY
Toxaphene	ND		ug/Kg	100	1	395871	02/20/26	02/23/26	XLY
Chlordane (Technical)	ND		ug/Kg	50	1	395871	02/20/26	02/23/26	XLY
Surrogates				**Limits**					
TCMX	86%		%REC	58-120	1	395871	02/20/26	02/23/26	XLY
Decachlorobiphenyl	86%		%REC	47-120	1	395871	02/20/26	02/23/26	XLY

Results for any subcontracted analyses are not included in this section.

Analysis Results for 553481

Sample ID: CG-31-0.5	Lab ID: 553481-011	Collected: 02/17/26
	Matrix: Soil	

553481-011 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 8081A Prep Method: EPA 3546									
alpha-BHC	ND		ug/Kg	5.0	0.99	395871	02/20/26	02/23/26	XLY
beta-BHC	ND		ug/Kg	5.0	0.99	395871	02/20/26	02/23/26	XLY
gamma-BHC	ND		ug/Kg	5.0	0.99	395871	02/20/26	02/23/26	XLY
delta-BHC	ND		ug/Kg	5.0	0.99	395871	02/20/26	02/23/26	XLY
Heptachlor	ND		ug/Kg	5.0	0.99	395871	02/20/26	02/23/26	XLY
Aldrin	ND		ug/Kg	5.0	0.99	395871	02/20/26	02/23/26	XLY
Heptachlor epoxide	ND		ug/Kg	5.0	0.99	395871	02/20/26	02/23/26	XLY
Endosulfan I	ND		ug/Kg	5.0	0.99	395871	02/20/26	02/23/26	XLY
Dieldrin	ND		ug/Kg	5.0	0.99	395871	02/20/26	02/23/26	XLY
4,4'-DDE	ND		ug/Kg	5.0	0.99	395871	02/20/26	02/23/26	XLY
Endrin	ND		ug/Kg	5.0	0.99	395871	02/20/26	02/23/26	XLY
Endosulfan II	ND		ug/Kg	5.0	0.99	395871	02/20/26	02/23/26	XLY
Endosulfan sulfate	ND		ug/Kg	5.0	0.99	395871	02/20/26	02/23/26	XLY
4,4'-DDD	ND		ug/Kg	5.0	0.99	395871	02/20/26	02/23/26	XLY
Endrin aldehyde	ND		ug/Kg	5.0	0.99	395871	02/20/26	02/23/26	XLY
Endrin ketone	ND		ug/Kg	5.0	0.99	395871	02/20/26	02/23/26	XLY
4,4'-DDT	ND		ug/Kg	5.0	0.99	395871	02/20/26	02/23/26	XLY
Methoxychlor	ND		ug/Kg	9.9	0.99	395871	02/20/26	02/23/26	XLY
Toxaphene	ND		ug/Kg	99	0.99	395871	02/20/26	02/23/26	XLY
Chlordane (Technical)	ND		ug/Kg	50	0.99	395871	02/20/26	02/23/26	XLY
Surrogates				**Limits**					
TCMX	78%		%REC	58-120	0.99	395871	02/20/26	02/23/26	XLY
Decachlorobiphenyl	76%		%REC	47-120	0.99	395871	02/20/26	02/23/26	XLY

Results for any subcontracted analyses are not included in this section.

ENTHALPY ANALYTICAL

Analysis Results for 553481

Sample ID: CG-31-2.5	Lab ID: 553481-012	Collected: 02/17/26
	Matrix: Soil	

553481-012 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 8081A Prep Method: EPA 3546									
alpha-BHC	ND		ug/Kg	5.1	1	395871	02/20/26	02/23/26	XLY
beta-BHC	ND		ug/Kg	5.1	1	395871	02/20/26	02/23/26	XLY
gamma-BHC	ND		ug/Kg	5.1	1	395871	02/20/26	02/23/26	XLY
delta-BHC	ND		ug/Kg	5.1	1	395871	02/20/26	02/23/26	XLY
Heptachlor	ND		ug/Kg	5.1	1	395871	02/20/26	02/23/26	XLY
Aldrin	ND		ug/Kg	5.1	1	395871	02/20/26	02/23/26	XLY
Heptachlor epoxide	ND		ug/Kg	5.1	1	395871	02/20/26	02/23/26	XLY
Endosulfan I	ND		ug/Kg	5.1	1	395871	02/20/26	02/23/26	XLY
Dieldrin	ND		ug/Kg	5.1	1	395871	02/20/26	02/23/26	XLY
4,4'-DDE	ND		ug/Kg	5.1	1	395871	02/20/26	02/23/26	XLY
Endrin	ND		ug/Kg	5.1	1	395871	02/20/26	02/23/26	XLY
Endosulfan II	ND		ug/Kg	5.1	1	395871	02/20/26	02/23/26	XLY
Endosulfan sulfate	ND		ug/Kg	5.1	1	395871	02/20/26	02/23/26	XLY
4,4'-DDD	ND		ug/Kg	5.1	1	395871	02/20/26	02/23/26	XLY
Endrin aldehyde	ND		ug/Kg	5.1	1	395871	02/20/26	02/23/26	XLY
Endrin ketone	ND		ug/Kg	5.1	1	395871	02/20/26	02/23/26	XLY
4,4'-DDT	ND		ug/Kg	5.1	1	395871	02/20/26	02/23/26	XLY
Methoxychlor	ND		ug/Kg	10	1	395871	02/20/26	02/23/26	XLY
Toxaphene	ND		ug/Kg	100	1	395871	02/20/26	02/23/26	XLY
Chlordane (Technical)	ND		ug/Kg	51	1	395871	02/20/26	02/23/26	XLY
Surrogates				**Limits**					
TCMX	89%		%REC	58-120	1	395871	02/20/26	02/23/26	XLY
Decachlorobiphenyl	83%		%REC	47-120	1	395871	02/20/26	02/23/26	XLY

Results for any subcontracted analyses are not included in this section.

ENTHALPY ANALYTICAL

Analysis Results for 553481

Sample ID: CG-32-0.5	Lab ID: 553481-013	Collected: 02/17/26
	Matrix: Soil	

553481-013 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 8081A Prep Method: EPA 3546									
alpha-BHC	ND		ug/Kg	9.8	2	395871	02/20/26	02/23/26	XLY
beta-BHC	ND		ug/Kg	9.8	2	395871	02/20/26	02/23/26	XLY
gamma-BHC	ND		ug/Kg	9.8	2	395871	02/20/26	02/23/26	XLY
delta-BHC	ND		ug/Kg	9.8	2	395871	02/20/26	02/23/26	XLY
Heptachlor	ND		ug/Kg	9.8	2	395871	02/20/26	02/23/26	XLY
Aldrin	ND		ug/Kg	9.8	2	395871	02/20/26	02/23/26	XLY
Heptachlor epoxide	ND		ug/Kg	9.8	2	395871	02/20/26	02/23/26	XLY
Endosulfan I	ND		ug/Kg	9.8	2	395871	02/20/26	02/23/26	XLY
Dieldrin	ND		ug/Kg	9.8	2	395871	02/20/26	02/23/26	XLY
4,4'-DDE	ND		ug/Kg	9.8	2	395871	02/20/26	02/23/26	XLY
Endrin	ND		ug/Kg	9.8	2	395871	02/20/26	02/23/26	XLY
Endosulfan II	ND		ug/Kg	9.8	2	395871	02/20/26	02/23/26	XLY
Endosulfan sulfate	ND		ug/Kg	9.8	2	395871	02/20/26	02/23/26	XLY
4,4'-DDD	ND		ug/Kg	9.8	2	395871	02/20/26	02/23/26	XLY
Endrin aldehyde	ND		ug/Kg	9.8	2	395871	02/20/26	02/23/26	XLY
Endrin ketone	ND		ug/Kg	9.8	2	395871	02/20/26	02/23/26	XLY
4,4'-DDT	ND		ug/Kg	9.8	2	395871	02/20/26	02/23/26	XLY
Methoxychlor	ND		ug/Kg	20	2	395871	02/20/26	02/23/26	XLY
Toxaphene	ND		ug/Kg	200	2	395871	02/20/26	02/23/26	XLY
Chlordane (Technical)	ND		ug/Kg	98	2	395871	02/20/26	02/23/26	XLY
Surrogates				**Limits**					
TCMX	83%		%REC	58-120	2	395871	02/20/26	02/23/26	XLY
Decachlorobiphenyl	101%		%REC	47-120	2	395871	02/20/26	02/23/26	XLY

Results for any subcontracted analyses are not included in this section.

ENTHALPY ANALYTICAL

Analysis Results for 553481

Sample ID: CG-32-2.5	Lab ID: 553481-014	Collected: 02/17/26
	Matrix: Soil	

553481-014 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 8081A Prep Method: EPA 3546									
alpha-BHC	ND		ug/Kg	10	2	395871	02/20/26	02/23/26	XLY
beta-BHC	ND		ug/Kg	10	2	395871	02/20/26	02/23/26	XLY
gamma-BHC	ND		ug/Kg	10	2	395871	02/20/26	02/23/26	XLY
delta-BHC	ND		ug/Kg	10	2	395871	02/20/26	02/23/26	XLY
Heptachlor	ND		ug/Kg	10	2	395871	02/20/26	02/23/26	XLY
Aldrin	ND		ug/Kg	10	2	395871	02/20/26	02/23/26	XLY
Heptachlor epoxide	ND		ug/Kg	10	2	395871	02/20/26	02/23/26	XLY
Endosulfan I	ND		ug/Kg	10	2	395871	02/20/26	02/23/26	XLY
Dieldrin	ND		ug/Kg	10	2	395871	02/20/26	02/23/26	XLY
4,4'-DDE	ND		ug/Kg	10	2	395871	02/20/26	02/23/26	XLY
Endrin	ND		ug/Kg	10	2	395871	02/20/26	02/23/26	XLY
Endosulfan II	ND		ug/Kg	10	2	395871	02/20/26	02/23/26	XLY
Endosulfan sulfate	ND		ug/Kg	10	2	395871	02/20/26	02/23/26	XLY
4,4'-DDD	ND		ug/Kg	10	2	395871	02/20/26	02/23/26	XLY
Endrin aldehyde	ND		ug/Kg	10	2	395871	02/20/26	02/23/26	XLY
Endrin ketone	ND		ug/Kg	10	2	395871	02/20/26	02/23/26	XLY
4,4'-DDT	ND		ug/Kg	10	2	395871	02/20/26	02/23/26	XLY
Methoxychlor	ND		ug/Kg	20	2	395871	02/20/26	02/23/26	XLY
Toxaphene	ND		ug/Kg	200	2	395871	02/20/26	02/23/26	XLY
Chlordane (Technical)	ND		ug/Kg	100	2	395871	02/20/26	02/23/26	XLY
Surrogates				**Limits**					
TCMX	90%		%REC	58-120	2	395871	02/20/26	02/23/26	XLY
Decachlorobiphenyl	93%		%REC	47-120	2	395871	02/20/26	02/23/26	XLY

Results for any subcontracted analyses are not included in this section.

Analysis Results for 553481

Sample ID: EB-01-260217	Lab ID: 553481-015	Collected: 02/17/26 15:30
	Matrix: Water	

553481-015 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3015A									
Lead	ND		mg/L	0.010	1	395922	02/20/26	02/22/26	SBW
Method: EPA 8081A Prep Method: EPA 3510C									
alpha-BHC	ND		ug/L	0.05	0.94	396077	02/22/26	02/25/26	XLY
beta-BHC	ND		ug/L	0.05	0.94	396077	02/22/26	02/25/26	XLY
gamma-BHC	ND		ug/L	0.05	0.94	396077	02/22/26	02/25/26	XLY
delta-BHC	ND		ug/L	0.05	0.94	396077	02/22/26	02/25/26	XLY
Heptachlor	ND		ug/L	0.05	0.94	396077	02/22/26	02/25/26	XLY
Aldrin	ND		ug/L	0.05	0.94	396077	02/22/26	02/25/26	XLY
Heptachlor epoxide	ND		ug/L	0.05	0.94	396077	02/22/26	02/25/26	XLY
Endosulfan I	ND		ug/L	0.05	0.94	396077	02/22/26	02/25/26	XLY
Dieldrin	ND		ug/L	0.09	0.94	396077	02/22/26	02/25/26	XLY
4,4'-DDE	ND		ug/L	0.09	0.94	396077	02/22/26	02/25/26	XLY
Endrin	ND		ug/L	0.09	0.94	396077	02/22/26	02/25/26	XLY
Endosulfan II	ND		ug/L	0.09	0.94	396077	02/22/26	02/25/26	XLY
Endosulfan sulfate	ND		ug/L	0.09	0.94	396077	02/22/26	02/25/26	XLY
4,4'-DDD	ND		ug/L	0.09	0.94	396077	02/22/26	02/25/26	XLY
Endrin aldehyde	ND		ug/L	0.09	0.94	396077	02/22/26	02/25/26	XLY
Endrin ketone	ND		ug/L	0.09	0.94	396077	02/22/26	02/25/26	XLY
4,4'-DDT	ND		ug/L	0.09	0.94	396077	02/22/26	02/25/26	XLY
Methoxychlor	ND		ug/L	0.09	0.94	396077	02/22/26	02/25/26	XLY
Toxaphene	ND		ug/L	1.9	0.94	396077	02/22/26	02/25/26	XLY
Chlordane (Technical)	ND		ug/L	0.9	0.94	396077	02/22/26	02/25/26	XLY
Surrogates				**Limits**					
TCMX	81%		%REC	29-120	0.94	396077	02/22/26	02/25/26	XLY
Decachlorobiphenyl	122%		%REC	33-132	0.94	396077	02/22/26	02/25/26	XLY
Method: EPA 8082 Prep Method: EPA 3510C									
Aroclor-1016	ND		ug/L	0.47	0.94	396077	02/22/26	02/25/26	XLY
Aroclor-1221	ND		ug/L	0.47	0.94	396077	02/22/26	02/25/26	XLY
Aroclor-1232	ND		ug/L	0.47	0.94	396077	02/22/26	02/25/26	XLY
Aroclor-1242	ND		ug/L	0.47	0.94	396077	02/22/26	02/25/26	XLY
Aroclor-1248	ND		ug/L	0.47	0.94	396077	02/22/26	02/25/26	XLY
Aroclor-1254	ND		ug/L	0.47	0.94	396077	02/22/26	02/25/26	XLY
Aroclor-1260	ND		ug/L	0.47	0.94	396077	02/22/26	02/25/26	XLY
Aroclor-1262	ND		ug/L	0.47	0.94	396077	02/22/26	02/25/26	XLY
Aroclor-1268	ND		ug/L	0.47	0.94	396077	02/22/26	02/25/26	XLY
Total PCBs	ND		ug/L	0.47	0.94	396077	02/22/26	02/25/26	XLY
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	93%		%REC	28-138	0.94	396077	02/22/26	02/25/26	XLY

Results for any subcontracted analyses are not included in this section.

Analysis Results for 553481

Sample ID: AOC4-SB-09-0.5	Lab ID: 553481-016	Collected: 02/17/26 14:21
	Matrix: Soil	

553481-016 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3050B									
Lead	**15**		mg/Kg	0.95	0.95	395888	02/20/26	02/20/26	KAM
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1221	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1232	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1242	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1248	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1254	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1260	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1262	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1268	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Total PCBs	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	88%		%REC	50-127	1	396025	02/21/26	02/23/26	KLR

Sample ID: AOC4-SB-10-0.5	Lab ID: 553481-017	Collected: 02/17/26 14:38
	Matrix: Soil	

553481-017 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3050B									
Lead	**25**		mg/Kg	0.97	0.97	395888	02/20/26	02/20/26	KAM
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1221	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1232	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1242	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1248	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1254	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1260	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1262	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1268	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Total PCBs	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	94%		%REC	50-127	1	396025	02/21/26	02/23/26	KLR

Results for any subcontracted analyses are not included in this section.

ENTHALPY ANALYTICAL

Analysis Results for 553481

Sample ID: AOC4-SB-11-0.5 **Lab ID: 553481-020** **Collected: 02/17/26 15:00**
Matrix: Soil

553481-020 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3050B									
Lead	**15**		mg/Kg	0.99	0.99	395888	02/20/26	02/20/26	KAM
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1221	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1232	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1242	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1248	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1254	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1260	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1262	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1268	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Total PCBs	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	96%		%REC	50-127	1	396025	02/21/26	02/23/26	KLR

Sample ID: AOC4-SB-12-0.5 **Lab ID: 553481-021** **Collected: 02/17/26 15:12**
Matrix: Soil

553481-021 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3050B									
Lead	**39**		mg/Kg	1.0	1	395888	02/20/26	02/20/26	KAM
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1221	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1232	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1242	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1248	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1254	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1260	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1262	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1268	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Total PCBs	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	90%		%REC	50-127	1	396025	02/21/26	02/23/26	KLR

Results for any subcontracted analyses are not included in this section.

Analysis Results for 553481

Sample ID: DUP-04-0.5-260217	Lab ID: 553481-024	Collected: 02/17/26
	Matrix: Soil	

553481-024 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3050B									
Lead	**17**		mg/Kg	0.96	0.96	395888	02/20/26	02/20/26	KAM
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	50	0.99	396025	02/21/26	02/23/26	KLR
Aroclor-1221	ND		ug/Kg	50	0.99	396025	02/21/26	02/23/26	KLR
Aroclor-1232	ND		ug/Kg	50	0.99	396025	02/21/26	02/23/26	KLR
Aroclor-1242	ND		ug/Kg	50	0.99	396025	02/21/26	02/23/26	KLR
Aroclor-1248	ND		ug/Kg	50	0.99	396025	02/21/26	02/23/26	KLR
Aroclor-1254	ND		ug/Kg	50	0.99	396025	02/21/26	02/23/26	KLR
Aroclor-1260	ND		ug/Kg	50	0.99	396025	02/21/26	02/23/26	KLR
Aroclor-1262	ND		ug/Kg	50	0.99	396025	02/21/26	02/23/26	KLR
Aroclor-1268	ND		ug/Kg	50	0.99	396025	02/21/26	02/23/26	KLR
Total PCBs	ND		ug/Kg	50	0.99	396025	02/21/26	02/23/26	KLR
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	85%		%REC	50-127	0.99	396025	02/21/26	02/23/26	KLR

Sample ID: AOC4-SB-05-0.5	Lab ID: 553481-026	Collected: 02/17/26 12:00
	Matrix: Soil	

553481-026 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	49	0.98	396025	02/21/26	02/23/26	KLR
Aroclor-1221	ND		ug/Kg	49	0.98	396025	02/21/26	02/23/26	KLR
Aroclor-1232	ND		ug/Kg	49	0.98	396025	02/21/26	02/23/26	KLR
Aroclor-1242	ND		ug/Kg	49	0.98	396025	02/21/26	02/23/26	KLR
Aroclor-1248	ND		ug/Kg	49	0.98	396025	02/21/26	02/23/26	KLR
Aroclor-1254	ND		ug/Kg	49	0.98	396025	02/21/26	02/23/26	KLR
Aroclor-1260	ND		ug/Kg	49	0.98	396025	02/21/26	02/23/26	KLR
Aroclor-1262	ND		ug/Kg	49	0.98	396025	02/21/26	02/23/26	KLR
Aroclor-1268	ND		ug/Kg	49	0.98	396025	02/21/26	02/23/26	KLR
Total PCBs	ND		ug/Kg	49	0.98	396025	02/21/26	02/23/26	KLR
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	85%		%REC	50-127	0.98	396025	02/21/26	02/23/26	KLR

Results for any subcontracted analyses are not included in this section.

Analysis Results for 553481

Sample ID: AOC4-SB-05-2.5	Lab ID: 553481-027	Collected: 02/17/26 12:06
	Matrix: Soil	

553481-027 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1221	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1232	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1242	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1248	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1254	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1260	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1262	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1268	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Total PCBs	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	80%		%REC	50-127	1	396025	02/21/26	02/23/26	KLR

Sample ID: AOC4-SB-06-0.5	Lab ID: 553481-028	Collected: 02/17/26 12:10
	Matrix: Soil	

553481-028 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1221	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1232	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1242	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1248	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1254	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1260	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1262	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1268	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Total PCBs	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	88%		%REC	50-127	1	396025	02/21/26	02/23/26	KLR

Results for any subcontracted analyses are not included in this section.

Analysis Results for 553481

Sample ID: AOC4-SB-06-2.5	Lab ID: 553481-029	Collected: 02/17/26 12:21
	Matrix: Soil	

553481-029 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	50	0.99	396025	02/21/26	02/23/26	KLR
Aroclor-1221	ND		ug/Kg	50	0.99	396025	02/21/26	02/23/26	KLR
Aroclor-1232	ND		ug/Kg	50	0.99	396025	02/21/26	02/23/26	KLR
Aroclor-1242	ND		ug/Kg	50	0.99	396025	02/21/26	02/23/26	KLR
Aroclor-1248	ND		ug/Kg	50	0.99	396025	02/21/26	02/23/26	KLR
Aroclor-1254	ND		ug/Kg	50	0.99	396025	02/21/26	02/23/26	KLR
Aroclor-1260	ND		ug/Kg	50	0.99	396025	02/21/26	02/23/26	KLR
Aroclor-1262	ND		ug/Kg	50	0.99	396025	02/21/26	02/23/26	KLR
Aroclor-1268	ND		ug/Kg	50	0.99	396025	02/21/26	02/23/26	KLR
Total PCBs	ND		ug/Kg	50	0.99	396025	02/21/26	02/23/26	KLR
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	81%		%REC	50-127	0.99	396025	02/21/26	02/23/26	KLR

Sample ID: AOC4-SB-07-0.5	Lab ID: 553481-030	Collected: 02/17/26 13:45
	Matrix: Soil	

553481-030 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	49	0.98	396025	02/21/26	02/23/26	KLR
Aroclor-1221	ND		ug/Kg	49	0.98	396025	02/21/26	02/23/26	KLR
Aroclor-1232	ND		ug/Kg	49	0.98	396025	02/21/26	02/23/26	KLR
Aroclor-1242	ND		ug/Kg	49	0.98	396025	02/21/26	02/23/26	KLR
Aroclor-1248	ND		ug/Kg	49	0.98	396025	02/21/26	02/23/26	KLR
Aroclor-1254	ND		ug/Kg	49	0.98	396025	02/21/26	02/23/26	KLR
Aroclor-1260	ND		ug/Kg	49	0.98	396025	02/21/26	02/23/26	KLR
Aroclor-1262	ND		ug/Kg	49	0.98	396025	02/21/26	02/23/26	KLR
Aroclor-1268	ND		ug/Kg	49	0.98	396025	02/21/26	02/23/26	KLR
Total PCBs	ND		ug/Kg	49	0.98	396025	02/21/26	02/23/26	KLR
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	87%		%REC	50-127	0.98	396025	02/21/26	02/23/26	KLR

Results for any subcontracted analyses are not included in this section.

Analysis Results for 553481

Sample ID: AOC4-SB-07-2.5	Lab ID: 553481-031	Collected: 02/17/26 13:50
	Matrix: Soil	

553481-031 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	49	0.98	396025	02/21/26	02/23/26	KLR
Aroclor-1221	ND		ug/Kg	49	0.98	396025	02/21/26	02/23/26	KLR
Aroclor-1232	ND		ug/Kg	49	0.98	396025	02/21/26	02/23/26	KLR
Aroclor-1242	ND		ug/Kg	49	0.98	396025	02/21/26	02/23/26	KLR
Aroclor-1248	ND		ug/Kg	49	0.98	396025	02/21/26	02/23/26	KLR
Aroclor-1254	ND		ug/Kg	49	0.98	396025	02/21/26	02/23/26	KLR
Aroclor-1260	ND		ug/Kg	49	0.98	396025	02/21/26	02/23/26	KLR
Aroclor-1262	ND		ug/Kg	49	0.98	396025	02/21/26	02/23/26	KLR
Aroclor-1268	ND		ug/Kg	49	0.98	396025	02/21/26	02/23/26	KLR
Total PCBs	ND		ug/Kg	49	0.98	396025	02/21/26	02/23/26	KLR
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	84%		%REC	50-127	0.98	396025	02/21/26	02/23/26	KLR

Sample ID: AOC4-SB-08-0.5	Lab ID: 553481-032	Collected: 02/17/26 13:52
	Matrix: Soil	

553481-032 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1221	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1232	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1242	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1248	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1254	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1260	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1262	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1268	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Total PCBs	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	88%		%REC	50-127	1	396025	02/21/26	02/23/26	KLR

Results for any subcontracted analyses are not included in this section.

Analysis Results for 553481

Sample ID: AOC4-SB-08-2.5	Lab ID: 553481-033	Collected: 02/17/26 13:57
	Matrix: Soil	

553481-033 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1221	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1232	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1242	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1248	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1254	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1260	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1262	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1268	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Total PCBs	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	82%		%REC	50-127	1	396025	02/21/26	02/23/26	KLR

Sample ID: DUP-03-0.5-260217	Lab ID: 553481-034	Collected: 02/17/26
	Matrix: Soil	

553481-034 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1221	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1232	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1242	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1248	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1254	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1260	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1262	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1268	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Total PCBs	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	84%		%REC	50-127	1	396025	02/21/26	02/23/26	KLR

Results for any subcontracted analyses are not included in this section.

Analysis Results for 553481

Sample ID: DUP-03-2.5-260217	Lab ID: 553481-035	Collected: 02/17/26
	Matrix: Soil	

553481-035 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1221	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1232	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1242	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1248	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1254	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1260	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1262	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1268	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Total PCBs	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	80%		%REC	50-127	1	396025	02/21/26	02/23/26	KLR

Sample ID: AOC4-SB-01-0.5	Lab ID: 553481-036	Collected: 02/17/26 11:06
	Matrix: Soil	

553481-036 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1221	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1232	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1242	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1248	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1254	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1260	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1262	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Aroclor-1268	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Total PCBs	ND		ug/Kg	51	1	396025	02/21/26	02/23/26	KLR
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	88%		%REC	50-127	1	396025	02/21/26	02/23/26	KLR

Results for any subcontracted analyses are not included in this section.

Analysis Results for 553481

Sample ID: AOC4-SB-01-2.5	Lab ID: 553481-037	Collected: 02/17/26 11:10
	Matrix: Soil	

553481-037 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	49	0.98	396025	02/21/26	02/23/26	KLR
Aroclor-1221	ND		ug/Kg	49	0.98	396025	02/21/26	02/23/26	KLR
Aroclor-1232	ND		ug/Kg	49	0.98	396025	02/21/26	02/23/26	KLR
Aroclor-1242	ND		ug/Kg	49	0.98	396025	02/21/26	02/23/26	KLR
Aroclor-1248	ND		ug/Kg	49	0.98	396025	02/21/26	02/23/26	KLR
Aroclor-1254	ND		ug/Kg	49	0.98	396025	02/21/26	02/23/26	KLR
Aroclor-1260	ND		ug/Kg	49	0.98	396025	02/21/26	02/23/26	KLR
Aroclor-1262	ND		ug/Kg	49	0.98	396025	02/21/26	02/23/26	KLR
Aroclor-1268	ND		ug/Kg	49	0.98	396025	02/21/26	02/23/26	KLR
Total PCBs	ND		ug/Kg	49	0.98	396025	02/21/26	02/23/26	KLR
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	83%		%REC	50-127	0.98	396025	02/21/26	02/23/26	KLR

Sample ID: AOC4-SB-02-0.5	Lab ID: 553481-038	Collected: 02/17/26 11:14
	Matrix: Soil	

553481-038 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	50	0.99	396028	02/21/26	02/23/26	XLY
Aroclor-1221	ND		ug/Kg	50	0.99	396028	02/21/26	02/23/26	XLY
Aroclor-1232	ND		ug/Kg	50	0.99	396028	02/21/26	02/23/26	XLY
Aroclor-1242	ND		ug/Kg	50	0.99	396028	02/21/26	02/23/26	XLY
Aroclor-1248	ND		ug/Kg	50	0.99	396028	02/21/26	02/23/26	XLY
Aroclor-1254	ND		ug/Kg	50	0.99	396028	02/21/26	02/23/26	XLY
Aroclor-1260	ND		ug/Kg	50	0.99	396028	02/21/26	02/23/26	XLY
Aroclor-1262	ND		ug/Kg	50	0.99	396028	02/21/26	02/23/26	XLY
Aroclor-1268	ND		ug/Kg	50	0.99	396028	02/21/26	02/23/26	XLY
Total PCBs	ND		ug/Kg	50	0.99	396028	02/21/26	02/23/26	XLY
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	78%		%REC	50-127	0.99	396028	02/21/26	02/23/26	XLY

Results for any subcontracted analyses are not included in this section.

Analysis Results for 553481

Sample ID: AOC4-SB-02-2.5	Lab ID: 553481-039	Collected: 02/17/26 11:21
	Matrix: Soil	

553481-039 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	49	0.98	396028	02/21/26	02/23/26	XLY
Aroclor-1221	ND		ug/Kg	49	0.98	396028	02/21/26	02/23/26	XLY
Aroclor-1232	ND		ug/Kg	49	0.98	396028	02/21/26	02/23/26	XLY
Aroclor-1242	ND		ug/Kg	49	0.98	396028	02/21/26	02/23/26	XLY
Aroclor-1248	ND		ug/Kg	49	0.98	396028	02/21/26	02/23/26	XLY
Aroclor-1254	ND		ug/Kg	49	0.98	396028	02/21/26	02/23/26	XLY
Aroclor-1260	ND		ug/Kg	49	0.98	396028	02/21/26	02/23/26	XLY
Aroclor-1262	ND		ug/Kg	49	0.98	396028	02/21/26	02/23/26	XLY
Aroclor-1268	ND		ug/Kg	49	0.98	396028	02/21/26	02/23/26	XLY
Total PCBs	ND		ug/Kg	49	0.98	396028	02/21/26	02/23/26	XLY
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	84%		%REC	50-127	0.98	396028	02/21/26	02/23/26	XLY

Sample ID: DUP-02-0.5-260217	Lab ID: 553481-040	Collected: 02/17/26
	Matrix: Soil	

553481-040 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	50	1	396028	02/21/26	02/23/26	XLY
Aroclor-1221	ND		ug/Kg	50	1	396028	02/21/26	02/23/26	XLY
Aroclor-1232	ND		ug/Kg	50	1	396028	02/21/26	02/23/26	XLY
Aroclor-1242	ND		ug/Kg	50	1	396028	02/21/26	02/23/26	XLY
Aroclor-1248	ND		ug/Kg	50	1	396028	02/21/26	02/23/26	XLY
Aroclor-1254	ND		ug/Kg	50	1	396028	02/21/26	02/23/26	XLY
Aroclor-1260	ND		ug/Kg	50	1	396028	02/21/26	02/23/26	XLY
Aroclor-1262	ND		ug/Kg	50	1	396028	02/21/26	02/23/26	XLY
Aroclor-1268	ND		ug/Kg	50	1	396028	02/21/26	02/23/26	XLY
Total PCBs	ND		ug/Kg	50	1	396028	02/21/26	02/23/26	XLY
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	86%		%REC	50-127	1	396028	02/21/26	02/23/26	XLY

Results for any subcontracted analyses are not included in this section.

Analysis Results for 553481

Sample ID: DUP-02-2.5-260217	Lab ID: 553481-041	Collected: 02/17/26
	Matrix: Soil	

553481-041 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	50	0.99	396028	02/21/26	02/23/26	XLY
Aroclor-1221	ND		ug/Kg	50	0.99	396028	02/21/26	02/23/26	XLY
Aroclor-1232	ND		ug/Kg	50	0.99	396028	02/21/26	02/23/26	XLY
Aroclor-1242	ND		ug/Kg	50	0.99	396028	02/21/26	02/23/26	XLY
Aroclor-1248	ND		ug/Kg	50	0.99	396028	02/21/26	02/23/26	XLY
Aroclor-1254	ND		ug/Kg	50	0.99	396028	02/21/26	02/23/26	XLY
Aroclor-1260	ND		ug/Kg	50	0.99	396028	02/21/26	02/23/26	XLY
Aroclor-1262	ND		ug/Kg	50	0.99	396028	02/21/26	02/23/26	XLY
Aroclor-1268	ND		ug/Kg	50	0.99	396028	02/21/26	02/23/26	XLY
Total PCBs	ND		ug/Kg	50	0.99	396028	02/21/26	02/23/26	XLY
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	83%		%REC	50-127	0.99	396028	02/21/26	02/23/26	XLY

Sample ID: AOC4-SB-03-0.5	Lab ID: 553481-042	Collected: 02/17/26 11:27
	Matrix: Soil	

553481-042 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	51	1	396028	02/21/26	02/23/26	XLY
Aroclor-1221	ND		ug/Kg	51	1	396028	02/21/26	02/23/26	XLY
Aroclor-1232	ND		ug/Kg	51	1	396028	02/21/26	02/23/26	XLY
Aroclor-1242	ND		ug/Kg	51	1	396028	02/21/26	02/23/26	XLY
Aroclor-1248	ND		ug/Kg	51	1	396028	02/21/26	02/23/26	XLY
Aroclor-1254	ND		ug/Kg	51	1	396028	02/21/26	02/23/26	XLY
Aroclor-1260	ND		ug/Kg	51	1	396028	02/21/26	02/23/26	XLY
Aroclor-1262	ND		ug/Kg	51	1	396028	02/21/26	02/23/26	XLY
Aroclor-1268	ND		ug/Kg	51	1	396028	02/21/26	02/23/26	XLY
Total PCBs	ND		ug/Kg	51	1	396028	02/21/26	02/23/26	XLY
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	79%		%REC	50-127	1	396028	02/21/26	02/23/26	XLY

Results for any subcontracted analyses are not included in this section.

Analysis Results for 553481

Sample ID: AOC4-SB-03-2.5	Lab ID: 553481-043	Collected: 02/17/26 11:38
	Matrix: Soil	

553481-043 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	49	0.98	396028	02/21/26	02/23/26	XLY
Aroclor-1221	ND		ug/Kg	49	0.98	396028	02/21/26	02/23/26	XLY
Aroclor-1232	ND		ug/Kg	49	0.98	396028	02/21/26	02/23/26	XLY
Aroclor-1242	ND		ug/Kg	49	0.98	396028	02/21/26	02/23/26	XLY
Aroclor-1248	ND		ug/Kg	49	0.98	396028	02/21/26	02/23/26	XLY
Aroclor-1254	ND		ug/Kg	49	0.98	396028	02/21/26	02/23/26	XLY
Aroclor-1260	ND		ug/Kg	49	0.98	396028	02/21/26	02/23/26	XLY
Aroclor-1262	ND		ug/Kg	49	0.98	396028	02/21/26	02/23/26	XLY
Aroclor-1268	ND		ug/Kg	49	0.98	396028	02/21/26	02/23/26	XLY
Total PCBs	ND		ug/Kg	49	0.98	396028	02/21/26	02/23/26	XLY
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	82%		%REC	50-127	0.98	396028	02/21/26	02/23/26	XLY

Sample ID: AOC4-SB-04-0.5	Lab ID: 553481-044	Collected: 02/17/26 11:50
	Matrix: Soil	

553481-044 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	49	0.98	396028	02/21/26	02/23/26	XLY
Aroclor-1221	ND		ug/Kg	49	0.98	396028	02/21/26	02/23/26	XLY
Aroclor-1232	ND		ug/Kg	49	0.98	396028	02/21/26	02/23/26	XLY
Aroclor-1242	ND		ug/Kg	49	0.98	396028	02/21/26	02/23/26	XLY
Aroclor-1248	ND		ug/Kg	49	0.98	396028	02/21/26	02/23/26	XLY
Aroclor-1254	ND		ug/Kg	49	0.98	396028	02/21/26	02/23/26	XLY
Aroclor-1260	ND		ug/Kg	49	0.98	396028	02/21/26	02/23/26	XLY
Aroclor-1262	ND		ug/Kg	49	0.98	396028	02/21/26	02/23/26	XLY
Aroclor-1268	ND		ug/Kg	49	0.98	396028	02/21/26	02/23/26	XLY
Total PCBs	ND		ug/Kg	49	0.98	396028	02/21/26	02/23/26	XLY
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	104%		%REC	50-127	0.98	396028	02/21/26	02/23/26	XLY

Results for any subcontracted analyses are not included in this section.

Analysis Results for 553481

Sample ID: AOC4-SB-04-2.5	Lab ID: 553481-045	Collected: 02/17/26 11:53
	Matrix: Soil	

553481-045 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	51	1	396028	02/21/26	02/23/26	XLY
Aroclor-1221	ND		ug/Kg	51	1	396028	02/21/26	02/23/26	XLY
Aroclor-1232	ND		ug/Kg	51	1	396028	02/21/26	02/23/26	XLY
Aroclor-1242	ND		ug/Kg	51	1	396028	02/21/26	02/23/26	XLY
Aroclor-1248	ND		ug/Kg	51	1	396028	02/21/26	02/23/26	XLY
Aroclor-1254	ND		ug/Kg	51	1	396028	02/21/26	02/23/26	XLY
Aroclor-1260	ND		ug/Kg	51	1	396028	02/21/26	02/23/26	XLY
Aroclor-1262	ND		ug/Kg	51	1	396028	02/21/26	02/23/26	XLY
Aroclor-1268	ND		ug/Kg	51	1	396028	02/21/26	02/23/26	XLY
Total PCBs	ND		ug/Kg	51	1	396028	02/21/26	02/23/26	XLY
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	89%		%REC	50-127	1	396028	02/21/26	02/23/26	XLY

Sample ID: AOC3-SB-43-0.5	Lab ID: 553481-046	Collected: 02/17/26 07:55
	Matrix: Soil	

553481-046 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3050B									
Lead	**32**		mg/Kg	0.97	0.97	395888	02/20/26	02/20/26	KAM
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	51	1	396028	02/21/26	02/23/26	XLY
Aroclor-1221	ND		ug/Kg	51	1	396028	02/21/26	02/23/26	XLY
Aroclor-1232	ND		ug/Kg	51	1	396028	02/21/26	02/23/26	XLY
Aroclor-1242	ND		ug/Kg	51	1	396028	02/21/26	02/23/26	XLY
Aroclor-1248	ND		ug/Kg	51	1	396028	02/21/26	02/23/26	XLY
Aroclor-1254	ND		ug/Kg	51	1	396028	02/21/26	02/23/26	XLY
Aroclor-1260	ND		ug/Kg	51	1	396028	02/21/26	02/23/26	XLY
Aroclor-1262	ND		ug/Kg	51	1	396028	02/21/26	02/23/26	XLY
Aroclor-1268	ND		ug/Kg	51	1	396028	02/21/26	02/23/26	XLY
Total PCBs	ND		ug/Kg	51	1	396028	02/21/26	02/23/26	XLY
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	79%		%REC	50-127	1	396028	02/21/26	02/23/26	XLY

Results for any subcontracted analyses are not included in this section.

Analysis Results for 553481

Sample ID: AOC3-SB-42-0.5	Lab ID: 553481-047	Collected: 02/17/26 08:18
	Matrix: Soil	

553481-047 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3050B									
Lead	**32**		mg/Kg	0.95	0.95	395888	02/20/26	02/20/26	KAM
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	50	1	396028	02/21/26	02/23/26	XLY
Aroclor-1221	ND		ug/Kg	50	1	396028	02/21/26	02/23/26	XLY
Aroclor-1232	ND		ug/Kg	50	1	396028	02/21/26	02/23/26	XLY
Aroclor-1242	ND		ug/Kg	50	1	396028	02/21/26	02/23/26	XLY
Aroclor-1248	ND		ug/Kg	50	1	396028	02/21/26	02/23/26	XLY
Aroclor-1254	ND		ug/Kg	50	1	396028	02/21/26	02/23/26	XLY
Aroclor-1260	ND		ug/Kg	50	1	396028	02/21/26	02/23/26	XLY
Aroclor-1262	ND		ug/Kg	50	1	396028	02/21/26	02/23/26	XLY
Aroclor-1268	ND		ug/Kg	50	1	396028	02/21/26	02/23/26	XLY
Total PCBs	ND		ug/Kg	50	1	396028	02/21/26	02/23/26	XLY
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	78%		%REC	50-127	1	396028	02/21/26	02/23/26	XLY

Sample ID: AOC3-SB-41-0.5	Lab ID: 553481-048	Collected: 02/17/26 08:39
	Matrix: Soil	

553481-048 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3050B									
Lead	**25**		mg/Kg	0.95	0.95	395888	02/20/26	02/20/26	KAM
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	50	0.99	396028	02/21/26	02/23/26	XLY
Aroclor-1221	ND		ug/Kg	50	0.99	396028	02/21/26	02/23/26	XLY
Aroclor-1232	ND		ug/Kg	50	0.99	396028	02/21/26	02/23/26	XLY
Aroclor-1242	ND		ug/Kg	50	0.99	396028	02/21/26	02/23/26	XLY
Aroclor-1248	ND		ug/Kg	50	0.99	396028	02/21/26	02/23/26	XLY
Aroclor-1254	ND		ug/Kg	50	0.99	396028	02/21/26	02/23/26	XLY
Aroclor-1260	ND		ug/Kg	50	0.99	396028	02/21/26	02/23/26	XLY
Aroclor-1262	ND		ug/Kg	50	0.99	396028	02/21/26	02/23/26	XLY
Aroclor-1268	ND		ug/Kg	50	0.99	396028	02/21/26	02/23/26	XLY
Total PCBs	ND		ug/Kg	50	0.99	396028	02/21/26	02/23/26	XLY
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	78%		%REC	50-127	0.99	396028	02/21/26	02/23/26	XLY

Results for any subcontracted analyses are not included in this section.

Analysis Results for 553481

Sample ID: DUP-01-0.5-260217	Lab ID: 553481-052	Collected: 02/17/26
	Matrix: Soil	

553481-052 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3050B									
Lead	**25**		mg/Kg	0.95	0.95	395888	02/20/26	02/20/26	KAM
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	49	0.98	396028	02/21/26	02/23/26	XLY
Aroclor-1221	ND		ug/Kg	49	0.98	396028	02/21/26	02/23/26	XLY
Aroclor-1232	ND		ug/Kg	49	0.98	396028	02/21/26	02/23/26	XLY
Aroclor-1242	ND		ug/Kg	49	0.98	396028	02/21/26	02/23/26	XLY
Aroclor-1248	ND		ug/Kg	49	0.98	396028	02/21/26	02/23/26	XLY
Aroclor-1254	ND		ug/Kg	49	0.98	396028	02/21/26	02/23/26	XLY
Aroclor-1260	ND		ug/Kg	49	0.98	396028	02/21/26	02/23/26	XLY
Aroclor-1262	ND		ug/Kg	49	0.98	396028	02/21/26	02/23/26	XLY
Aroclor-1268	ND		ug/Kg	49	0.98	396028	02/21/26	02/23/26	XLY
Total PCBs	ND		ug/Kg	49	0.98	396028	02/21/26	02/23/26	XLY
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	78%		%REC	50-127	0.98	396028	02/21/26	02/23/26	XLY

ND Not Detected

Results for any subcontracted analyses are not included in this section.

ENTHALPY ANALYTICAL

Batch QC

Type: Blank	Lab ID: QC1342577	Batch: 395922
Matrix: Water	Method: EPA 6010B	Prep Method: EPA 3015A

QC1342577 Analyte	Result	Qual	Units	RL	Prepared	Analyzed
Lead	ND		mg/L	0.010	02/20/26	02/22/26

Type: Lab Control Sample	Lab ID: QC1342578	Batch: 395922
Matrix: Water	Method: EPA 6010B	Prep Method: EPA 3015A

QC1342578 Analyte	Result	Spiked	Units	Recovery	Qual	Limits
Lead	0.3806	0.4000	mg/L	95%		80-120

Type: Matrix Spike	Lab ID: QC1342579	Batch: 395922
Matrix (Source ID): Water (553528-001)	Method: EPA 6010B	Prep Method: EPA 3015A

QC1342579 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	DF
Lead	0.3664	ND	0.4000	mg/L	92%		75-125	1

Type: Matrix Spike Duplicate	Lab ID: QC1342580	Batch: 395922
Matrix (Source ID): Water (553528-001)	Method: EPA 6010B	Prep Method: EPA 3015A

QC1342580 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	RPD	RPD Lim	DF
Lead	0.3685	ND	0.4000	mg/L	92%		75-125	1	20	1

Type: Matrix Spike	Lab ID: QC1342581	Batch: 395922
Matrix (Source ID): Water (553528-002)	Method: EPA 6010B	Prep Method: EPA 3015A

QC1342581 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	DF
Lead	0.3713	ND	0.4000	mg/L	93%		75-125	1

Type: Matrix Spike Duplicate	Lab ID: QC1342582	Batch: 395922
Matrix (Source ID): Water (553528-002)	Method: EPA 6010B	Prep Method: EPA 3015A

QC1342582 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	RPD	RPD Lim	DF
Lead	0.3691	ND	0.4000	mg/L	92%		75-125	1	20	1

ENTHALPY ANALYTICAL

Batch QC

Type:	Serial Dilution	Lab ID:	QC1342602	Batch:	395922
Matrix (Source ID):	Water (553528-001)	Method:	EPA 6010B	Prep Method:	EPA 3015A

QC1342602 Analyte	Result	Source Sample Result	Units	Qual	RPD	RPD Lim	DF
Lead	ND	ND	mg/L				5

Type:	Blank	Lab ID:	QC1342469	Batch:	395888
Matrix:	Soil	Method:	EPA 6010B	Prep Method:	EPA 3050B

QC1342469 Analyte	Result	Qual	Units	RL	Prepared	Analyzed
Lead	ND		mg/Kg	1.0	02/20/26	02/20/26

Type:	Lab Control Sample	Lab ID:	QC1342470	Batch:	395888
Matrix:	Soil	Method:	EPA 6010B	Prep Method:	EPA 3050B

QC1342470 Analyte	Result	Spiked	Units	Recovery	Qual	Limits
Lead	101.2	100.0	mg/Kg	101%		80-120

Type:	Matrix Spike	Lab ID:	QC1342471	Batch:	395888
Matrix (Source ID):	Soil (553481-001)	Method:	EPA 6010B	Prep Method:	EPA 3050B

QC1342471 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	DF
Lead	101.5	8.012	100.0	mg/Kg	94%		75-125	1

Type:	Matrix Spike Duplicate	Lab ID:	QC1342472	Batch:	395888
Matrix (Source ID):	Soil (553481-001)	Method:	EPA 6010B	Prep Method:	EPA 3050B

QC1342472 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	RPD	RPD Lim	DF
Lead	101.1	8.012	98.04	mg/Kg	95%		75-125	1	28	0.98

Type:	Serial Dilution	Lab ID:	QC1342473	Batch:	395888
Matrix (Source ID):	Soil (553481-001)	Method:	EPA 6010B	Prep Method:	EPA 3050B

QC1342473 Analyte	Result	Source Sample Result	Units	Qual	RPD	RPD Lim	DF
Lead	8.198	8.012	mg/Kg				4.8

ENTHALPY ANALYTICAL

Batch QC

Type:	**Post Digest Spike**	**Lab ID:**	**QC1342474**	**Batch:**	**395888**
Matrix (Source ID):	**Soil (553481-001)**	**Method:**	**EPA 6010B**	**Prep Method:**	**EPA 3050B**

QC1342474 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	DF
Lead	95.42	8.012	95.24	mg/Kg	92%		75-125	0.95

Type:	**Blank**	**Lab ID:**	**QC1342398**	**Batch:**	**395871**
Matrix:	**Soil**	**Method:**	**EPA 8081A**	**Prep Method:**	**EPA 3546**

QC1342398 Analyte	Result	Qual	Units	RL	Prepared	Analyzed
alpha-BHC	ND		ug/Kg	5.0	02/20/26	02/22/26
beta-BHC	ND		ug/Kg	5.0	02/20/26	02/22/26
gamma-BHC	ND		ug/Kg	5.0	02/20/26	02/22/26
delta-BHC	ND		ug/Kg	5.0	02/20/26	02/22/26
Heptachlor	ND		ug/Kg	5.0	02/20/26	02/22/26
Aldrin	ND		ug/Kg	5.0	02/20/26	02/22/26
Heptachlor epoxide	ND		ug/Kg	5.0	02/20/26	02/22/26
Endosulfan I	ND		ug/Kg	5.0	02/20/26	02/22/26
Dieldrin	ND		ug/Kg	5.0	02/20/26	02/22/26
4,4'-DDE	ND		ug/Kg	5.0	02/20/26	02/22/26
Endrin	ND		ug/Kg	5.0	02/20/26	02/22/26
Endosulfan II	ND		ug/Kg	5.0	02/20/26	02/22/26
Endosulfan sulfate	ND		ug/Kg	5.0	02/20/26	02/22/26
4,4'-DDD	ND		ug/Kg	5.0	02/20/26	02/22/26
Endrin aldehyde	ND		ug/Kg	5.0	02/20/26	02/22/26
Endrin ketone	ND		ug/Kg	5.0	02/20/26	02/22/26
4,4'-DDT	ND		ug/Kg	5.0	02/20/26	02/22/26
Methoxychlor	ND		ug/Kg	10	02/20/26	02/22/26
Toxaphene	ND		ug/Kg	100	02/20/26	02/22/26
Chlordane (Technical)	ND		ug/Kg	50	02/20/26	02/22/26
Surrogates				**Limits**		
TCMX	88%		%REC	58-120	02/20/26	02/22/26
Decachlorobiphenyl	96%		%REC	47-120	02/20/26	02/22/26

ENTHALPY ANALYTICAL

Batch QC

Type: Lab Control Sample	**Lab ID: QC1342400**	**Batch: 395871**
Matrix: Soil	**Method: EPA 8081A**	**Prep Method: EPA 3546**

QC1342400 Analyte	Result	Spiked	Units	Recovery	Qual	Limits
alpha-BHC	52.25	50.25	ug/Kg	104%		53-132
beta-BHC	45.49	50.25	ug/Kg	91%		59-131
gamma-BHC	52.29	50.25	ug/Kg	104%		54-132
delta-BHC	51.05	50.25	ug/Kg	102%		54-134
Heptachlor	48.43	50.25	ug/Kg	96%		50-130
Aldrin	42.20	50.25	ug/Kg	84%		46-120
Heptachlor epoxide	43.85	50.25	ug/Kg	87%		52-127
Endosulfan I	43.14	50.25	ug/Kg	86%		53-132
Dieldrin	43.97	50.25	ug/Kg	88%		53-134
4,4'-DDE	47.46	50.25	ug/Kg	94%		53-140
Endrin	49.34	50.25	ug/Kg	98%		53-142
Endosulfan II	44.02	50.25	ug/Kg	88%		53-138
Endosulfan sulfate	48.60	50.25	ug/Kg	97%		50-134
4,4'-DDD	43.28	50.25	ug/Kg	86%		50-136
Endrin aldehyde	36.17	50.25	ug/Kg	72%		15-120
Endrin ketone	54.87	50.25	ug/Kg	109%		50-146
4,4'-DDT	47.06	50.25	ug/Kg	94%		46-142
Methoxychlor	49.83	50.25	ug/Kg	99%		48-156
Surrogates						
TCMX	44.36	50.25	ug/Kg	88%		58-120
Decachlorobiphenyl	46.97	50.25	ug/Kg	93%		47-120

ENTHALPY ANALYTICAL

Batch QC

Type:	**Matrix Spike**	**Lab ID:**	**QC1342404**	**Batch:**	**395871**
Matrix (Source ID):	**Soil (553481-007)**	**Method:**	**EPA 8081A**	**Prep Method:**	**EPA 3546**

QC1342404 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	DF
alpha-BHC	47.62	ND	51.02	ug/Kg	93%		52-120	2
beta-BHC	42.18	ND	51.02	ug/Kg	83%		57-126	2
gamma-BHC	47.08	ND	51.02	ug/Kg	92%		54-122	2
delta-BHC	40.23	ND	51.02	ug/Kg	79%		44-127	2
Heptachlor	47.03	ND	51.02	ug/Kg	92%		51-122	2
Aldrin	44.03	ND	51.02	ug/Kg	86%		51-120	2
Heptachlor epoxide	43.68	ND	51.02	ug/Kg	86%		50-122	2
Endosulfan I	44.37	ND	51.02	ug/Kg	87%		48-123	2
Dieldrin	42.11	ND	51.02	ug/Kg	83%		48-128	2
4,4'-DDE	48.17	ND	51.02	ug/Kg	94%		50-139	2
Endrin	46.27	ND	51.02	ug/Kg	91%		53-132	2
Endosulfan II	42.58	ND	51.02	ug/Kg	83%		47-131	2
Endosulfan sulfate	42.74	ND	51.02	ug/Kg	84%		40-126	2
4,4'-DDD	40.59	ND	51.02	ug/Kg	80%		48-130	2
Endrin aldehyde	39.27	ND	51.02	ug/Kg	77%		26-120	2
Endrin ketone	50.77	ND	51.02	ug/Kg	100%		51-133	2
4,4'-DDT	50.97	7.619	51.02	ug/Kg	85%		40-144	2
Methoxychlor	49.34	ND	51.02	ug/Kg	97%		49-148	2
Surrogates								
TCMX	44.95		51.02	ug/Kg	88%		58-120	2
Decachlorobiphenyl	47.23		51.02	ug/Kg	93%		47-120	2

ENTHALPY ANALYTICAL

Batch QC

Type:	**Matrix Spike Duplicate**	**Lab ID:**	**QC1342405**	**Batch:**	**395871**
Matrix (Source ID):	**Soil (553481-007)**	**Method:**	**EPA 8081A**	**Prep Method:**	**EPA 3546**

QC1342405 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	RPD	RPD Lim	DF
alpha-BHC	46.97	ND	49.50	ug/Kg	95%		52-120	2	37	2
beta-BHC	44.61	ND	49.50	ug/Kg	90%		57-126	9	38	2
gamma-BHC	46.55	ND	49.50	ug/Kg	94%		54-122	2	39	2
delta-BHC	39.43	ND	49.50	ug/Kg	80%		44-127	1	54	2
Heptachlor	46.95	ND	49.50	ug/Kg	95%		51-122	3	44	2
Aldrin	42.39	ND	49.50	ug/Kg	86%		51-120	1	39	2
Heptachlor epoxide	41.95	ND	49.50	ug/Kg	85%		50-122	1	39	2
Endosulfan I	43.99	ND	49.50	ug/Kg	89%		48-123	2	47	2
Dieldrin	40.83	ND	49.50	ug/Kg	82%		48-128	0	43	2
4,4'-DDE	47.16	ND	49.50	ug/Kg	95%		50-139	1	42	2
Endrin	45.19	ND	49.50	ug/Kg	91%		53-132	1	45	2
Endosulfan II	42.41	ND	49.50	ug/Kg	86%		47-131	3	46	2
Endosulfan sulfate	43.65	ND	49.50	ug/Kg	88%		40-126	5	52	2
4,4'-DDD	40.30	ND	49.50	ug/Kg	81%		48-130	2	46	2
Endrin aldehyde	39.21	ND	49.50	ug/Kg	79%		26-120	3	57	2
Endrin ketone	48.68	ND	49.50	ug/Kg	98%		51-133	1	43	2
4,4'-DDT	49.27	7.619	49.50	ug/Kg	84%		40-144	1	56	2
Methoxychlor	46.96	ND	49.50	ug/Kg	95%		49-148	2	53	2
Surrogates										
TCMX	43.21		49.50	ug/Kg	87%		58-120			2
Decachlorobiphenyl	47.67		49.50	ug/Kg	96%		47-120			2

Batch QC

Type: Blank	Lab ID: QC1343118	Batch: 396077
Matrix: Water		

QC1343118 Analyte	Result	Qual	Units	RL	Prepared	Analyzed
Method: EPA 8081A Prep Method: EPA 3510C						
alpha-BHC	ND		ug/L	0.05	02/22/26	02/25/26
beta-BHC	ND		ug/L	0.05	02/22/26	02/25/26
gamma-BHC	ND		ug/L	0.05	02/22/26	02/25/26
delta-BHC	ND		ug/L	0.05	02/22/26	02/25/26
Heptachlor	ND		ug/L	0.05	02/22/26	02/25/26
Aldrin	ND		ug/L	0.05	02/22/26	02/25/26
Heptachlor epoxide	ND		ug/L	0.05	02/22/26	02/25/26
Endosulfan I	ND		ug/L	0.05	02/22/26	02/25/26
Dieldrin	ND		ug/L	0.1	02/22/26	02/25/26
4,4'-DDE	ND		ug/L	0.1	02/22/26	02/25/26
Endrin	ND		ug/L	0.1	02/22/26	02/25/26
Endosulfan II	ND		ug/L	0.1	02/22/26	02/25/26
Endosulfan sulfate	ND		ug/L	0.1	02/22/26	02/25/26
4,4'-DDD	ND		ug/L	0.1	02/22/26	02/25/26
Endrin aldehyde	ND		ug/L	0.1	02/22/26	02/25/26
Endrin ketone	ND		ug/L	0.1	02/22/26	02/25/26
4,4'-DDT	ND		ug/L	0.1	02/22/26	02/25/26
Methoxychlor	ND		ug/L	0.1	02/22/26	02/25/26
Toxaphene	ND		ug/L	2.0	02/22/26	02/25/26
Chlordane (Technical)	ND		ug/L	1.0	02/22/26	02/25/26
Surrogates				**Limits**		
TCMX	61%		%REC	29-120	02/22/26	02/25/26
Decachlorobiphenyl	90%		%REC	33-132	02/22/26	02/25/26
Method: EPA 8082 Prep Method: EPA 3510C						
Aroclor-1016	ND		ug/L	0.50	02/22/26	02/25/26
Aroclor-1221	ND		ug/L	0.50	02/22/26	02/25/26
Aroclor-1232	ND		ug/L	0.50	02/22/26	02/25/26
Aroclor-1242	ND		ug/L	0.50	02/22/26	02/25/26
Aroclor-1248	ND		ug/L	0.50	02/22/26	02/25/26
Aroclor-1254	ND		ug/L	0.50	02/22/26	02/25/26
Aroclor-1260	ND		ug/L	0.50	02/22/26	02/25/26
Aroclor-1262	ND		ug/L	0.50	02/22/26	02/25/26
Aroclor-1268	ND		ug/L	0.50	02/22/26	02/25/26
Total PCBs	ND		ug/L	0.50	02/22/26	02/25/26
Surrogates				**Limits**		
Decachlorobiphenyl (PCB)	66%		%REC	28-138	02/22/26	02/25/26

ENTHALPY ANALYTICAL

Batch QC

Type:	**Lab Control Sample**	**Lab ID:**	**QC1343119**	**Batch:**	**396077**
Matrix:	**Water**	**Method:**	**EPA 8081A**	**Prep Method:**	**EPA 3510C**

QC1343119 Analyte	Result	Spiked	Units	Recovery	Qual	Limits
alpha-BHC	0.5820	0.5000	ug/L	116%		66-121
beta-BHC	0.5036	0.5000	ug/L	101%		73-120
gamma-BHC	0.5751	0.5000	ug/L	115%		68-125
delta-BHC	0.6048	0.5000	ug/L	121%		68-131
Heptachlor	0.5575	0.5000	ug/L	112%		63-120
Aldrin	0.5066	0.5000	ug/L	101%		56-120
Heptachlor epoxide	0.5066	0.5000	ug/L	101%		65-120
Endosulfan I	0.5282	0.5000	ug/L	106%		68-124
Dieldrin	0.5117	0.5000	ug/L	102%		66-124
4,4'-DDE	0.5771	0.5000	ug/L	115%		67-131
Endrin	0.5664	0.5000	ug/L	113%		68-135
Endosulfan II	0.5169	0.5000	ug/L	103%		71-130
Endosulfan sulfate	0.5706	0.5000	ug/L	114%		68-128
4,4'-DDD	0.5348	0.5000	ug/L	107%		65-130
Endrin aldehyde	0.4895	0.5000	ug/L	98%		67-124
Endrin ketone	0.5896	0.5000	ug/L	118%		69-137
4,4'-DDT	0.5526	0.5000	ug/L	111%		65-136
Methoxychlor	0.5817	0.5000	ug/L	116%		69-150
Surrogates						
TCMX	0.4030	0.5000	ug/L	81%		29-120
Decachlorobiphenyl	0.5506	0.5000	ug/L	110%		33-132

Batch QC

Type:	Lab Control Sample Duplicate	Lab ID:	QC1343120	Batch:	396077
Matrix:	Water	Method:	EPA 8081A	Prep Method:	EPA 3510C

QC1343120 Analyte	Result	Spiked	Units	Recovery	Qual	Limits	RPD	RPD Lim
alpha-BHC	0.5242	0.5000	ug/L	105%		66-121	10	20
beta-BHC	0.4595	0.5000	ug/L	92%		73-120	9	20
gamma-BHC	0.5102	0.5000	ug/L	102%		68-125	12	20
delta-BHC	0.5429	0.5000	ug/L	109%		68-131	11	20
Heptachlor	0.4883	0.5000	ug/L	98%		63-120	13	24
Aldrin	0.4468	0.5000	ug/L	89%		56-120	13	30
Heptachlor epoxide	0.4498	0.5000	ug/L	90%		65-120	12	20
Endosulfan I	0.4733	0.5000	ug/L	95%		68-124	11	20
Dieldrin	0.4657	0.5000	ug/L	93%		66-124	9	22
4,4'-DDE	0.5143	0.5000	ug/L	103%		67-131	12	21
Endrin	0.5116	0.5000	ug/L	102%		68-135	10	20
Endosulfan II	0.4701	0.5000	ug/L	94%		71-130	9	21
Endosulfan sulfate	0.5303	0.5000	ug/L	106%		68-128	7	21
4,4'-DDD	0.4800	0.5000	ug/L	96%		65-130	11	22
Endrin aldehyde	0.4516	0.5000	ug/L	90%		67-124	8	20
Endrin ketone	0.5806	0.5000	ug/L	116%		69-137	2	21
4,4'-DDT	0.5169	0.5000	ug/L	103%		65-136	7	23
Methoxychlor	0.5628	0.5000	ug/L	113%		69-150	3	23
Surrogates								
TCMX	0.3680	0.5000	ug/L	74%		29-120		
Decachlorobiphenyl	0.5513	0.5000	ug/L	110%		33-132		

Type:	Lab Control Sample	Lab ID:	QC1343121	Batch:	396077
Matrix:	Water	Method:	EPA 8082	Prep Method:	EPA 3510C

QC1343121 Analyte	Result	Spiked	Units	Recovery	Qual	Limits
Aroclor-1016	5.021	5.000	ug/L	100%		69-120
Aroclor-1260	4.668	5.000	ug/L	93%		72-124
Surrogates						
Decachlorobiphenyl (PCB)	0.3945	0.5000	ug/L	79%		28-138

Type:	Lab Control Sample Duplicate	Lab ID:	QC1343122	Batch:	396077
Matrix:	Water	Method:	EPA 8082	Prep Method:	EPA 3510C

QC1343122 Analyte	Result	Spiked	Units	Recovery	Qual	Limits	RPD	RPD Lim
Aroclor-1016	4.883	5.000	ug/L	98%		69-120	3	22
Aroclor-1260	4.546	5.000	ug/L	91%		72-124	3	25
Surrogates								
Decachlorobiphenyl (PCB)	0.3967	0.5000	ug/L	79%		28-138		

ENTHALPY ANALYTICAL

Batch QC

Type: Blank	Lab ID: QC1342902	Batch: 396025
Matrix: Soil	Method: EPA 8082	Prep Method: EPA 3546

QC1342902 Analyte	Result	Qual	Units	RL	Prepared	Analyzed
Aroclor-1016	ND		ug/Kg	51	02/21/26	02/23/26
Aroclor-1221	ND		ug/Kg	51	02/21/26	02/23/26
Aroclor-1232	ND		ug/Kg	51	02/21/26	02/23/26
Aroclor-1242	ND		ug/Kg	51	02/21/26	02/23/26
Aroclor-1248	ND		ug/Kg	51	02/21/26	02/23/26
Aroclor-1254	ND		ug/Kg	51	02/21/26	02/23/26
Aroclor-1260	ND		ug/Kg	51	02/21/26	02/23/26
Aroclor-1262	ND		ug/Kg	51	02/21/26	02/23/26
Aroclor-1268	ND		ug/Kg	51	02/21/26	02/23/26
Total PCBs	ND		ug/Kg	51	02/21/26	02/23/26
Surrogates				**Limits**		
Decachlorobiphenyl (PCB)	92%		%REC	50-127	02/21/26	02/23/26

Type: Lab Control Sample	Lab ID: QC1342903	Batch: 396025
Matrix: Soil	Method: EPA 8082	Prep Method: EPA 3546

QC1342903 Analyte	Result	Spiked	Units	Recovery	Qual	Limits
Aroclor-1016	467.4	510.2	ug/Kg	92%		66-120
Aroclor-1260	463.1	510.2	ug/Kg	91%		63-126
Surrogates						
Decachlorobiphenyl (PCB)	44.31	51.02	ug/Kg	87%		50-127

Type: Matrix Spike	Lab ID: QC1342904	Batch: 396025
Matrix (Source ID): Soil (553481-001)	Method: EPA 8082	Prep Method: EPA 3546

QC1342904 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	DF
Aroclor-1016	419.0	ND	510.2	ug/Kg	82%		60-123	1
Aroclor-1260	407.5	ND	510.2	ug/Kg	80%		55-136	1
Surrogates								
Decachlorobiphenyl (PCB)	38.26		51.02	ug/Kg	75%		50-127	1

Type: Matrix Spike Duplicate	Lab ID: QC1342905	Batch: 396025
Matrix (Source ID): Soil (553481-001)	Method: EPA 8082	Prep Method: EPA 3546

QC1342905 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	RPD	RPD Lim	DF
Aroclor-1016	426.8	ND	505.1	ug/Kg	85%		60-123	3	37	1
Aroclor-1260	419.4	ND	505.1	ug/Kg	83%		55-136	4	41	1
Surrogates										
Decachlorobiphenyl (PCB)	40.42		50.51	ug/Kg	80%		50-127			1

ENTHALPY ANALYTICAL

Batch QC

Type: Blank	Lab ID: QC1342919	Batch: 396028
Matrix: Soil	Method: EPA 8082	Prep Method: EPA 3546

QC1342919 Analyte	Result	Qual	Units	RL	Prepared	Analyzed
Aroclor-1016	ND		ug/Kg	51	02/21/26	02/23/26
Aroclor-1221	ND		ug/Kg	51	02/21/26	02/23/26
Aroclor-1232	ND		ug/Kg	51	02/21/26	02/23/26
Aroclor-1242	ND		ug/Kg	51	02/21/26	02/23/26
Aroclor-1248	ND		ug/Kg	51	02/21/26	02/23/26
Aroclor-1254	ND		ug/Kg	51	02/21/26	02/23/26
Aroclor-1260	ND		ug/Kg	51	02/21/26	02/23/26
Aroclor-1262	ND		ug/Kg	51	02/21/26	02/23/26
Aroclor-1268	ND		ug/Kg	51	02/21/26	02/23/26
Total PCBs	ND		ug/Kg	51	02/21/26	02/23/26
Surrogates				**Limits**		
Decachlorobiphenyl (PCB)	80%		%REC	50-127	02/21/26	02/23/26

Type: Lab Control Sample	Lab ID: QC1342920	Batch: 396028
Matrix: Soil	Method: EPA 8082	Prep Method: EPA 3546

QC1342920 Analyte	Result	Spiked	Units	Recovery	Qual	Limits
Aroclor-1016	428.6	510.2	ug/Kg	84%		66-120
Aroclor-1260	454.3	510.2	ug/Kg	89%		63-126
Surrogates						
Decachlorobiphenyl (PCB)	46.38	51.02	ug/Kg	91%		50-127

Type: Matrix Spike	Lab ID: QC1342921	Batch: 396028
Matrix (Source ID): Soil (553481-038)	Method: EPA 8082	Prep Method: EPA 3546

QC1342921 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	DF
Aroclor-1016	390.1	ND	510.2	ug/Kg	76%		60-123	1
Aroclor-1260	430.4	ND	510.2	ug/Kg	84%		55-136	1
Surrogates								
Decachlorobiphenyl (PCB)	46.00		51.02	ug/Kg	90%		50-127	1

Type: Matrix Spike Duplicate	Lab ID: QC1342922	Batch: 396028
Matrix (Source ID): Soil (553481-038)	Method: EPA 8082	Prep Method: EPA 3546

QC1342922 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	RPD	RPD Lim	DF
Aroclor-1016	417.8	ND	510.2	ug/Kg	82%		60-123	7	37	1
Aroclor-1260	459.6	ND	510.2	ug/Kg	90%		55-136	7	41	1
Surrogates										
Decachlorobiphenyl (PCB)	43.61		51.02	ug/Kg	85%		50-127			1

ND Not Detected

Laboratory Job Number 553481

Subcontracted Products

AmeriSci Los Angeles

AmeriSci Richmond
13635 GENITO ROAD
MIDLOTHIAN, VIRGINIA 23112
TEL: (804) 763-1200 • FAX: (804) 763-0493

March 3, 2026

Enthalpy Analytical
Attn: Patty Mata
931 West Barkley Ave
Orange, CA 92868

RE: Enthalpy Analytical
Job Number 126022042
P.O. #098962
EO-553481

Dear Patty Mata:

Enclosed are the results of Asbestos Analysis - Bulk Qualitative Protocol of the following Enthalpy Analytical samples, received at AmeriSci on Tuesday, February 24, 2026, for a 5 day turnaround:

CG-28-0.5, CG-28-2.5, CG-30-0.5, CG-30-2.5, CG-31-0.5, CG-31-2.5, CG-32-0.5, CG-32-2.5

The 8 samples, placed in zip lock bag, were shipped to AmeriSci via Fed Ex. Enthalpy Analytical requested Bulk-Qualitative analysis of these samples.

The samples were prepared and analyzed by using a Standard Operating Procedure developed by AmeriSci, Inc.. After preparation, using non-quantitative matrix reduction if necessary, the presence or absence of asbestos is determined by PLM and/or TEM as indicated on the attached summary table. Quantification after the fact is not possible without a new preparation. This report relates ONLY to the analysis expressed as "asbestos present" or "no asbestos visible". This report must not be used to claim product endorsement or approval by AmeriSci, NVLAP, ELAP or any other associated AmeriSci certifying agency. The National Institute of Standards and Technology accreditation requirements, mandate that this report must not be reproduced, except in full without the approval of the laboratory.

AmeriSci appreciates this opportunity to serve your organization. Please contact us for any further assistance or with any questions.

Sincerely,



Glenn F. Massey

QA Manager | Authorized Signatory

AmeriSci Richmond
13635 GENITO ROAD
MIDLOTHIAN, VIRGINIA 23112
TEL: (804) 763-1200 • FAX: (804) 763-0493

PLM Bulk Asbestos Report

Enthalpy Analytical
Attn: Patty Mata
931 West Barkley Ave

Orange, CA 92868

Date Received 2/24/2026
Date Examined 02/25/26

RE: EO-553481

AmeriSci Job # 126022042
P.O. # 098962
Page 1 **of** 2

Client No. / HGA	Lab No.	Asbestos Present	Total % Asbestos	Notes
CG-28-0.5	126022042-01	***No***	NVA by C. David Mintz on 02/25/26	*1*
Location: **Analyst Description:** Brown, Homogeneous, Non-Fibrous, Soil **Asbestos Types:** **Other Material:** Cellulose Present, Non-fibrous Present				
CG-28-2.5	126022042-02	***No***	NVA by C. David Mintz on 02/25/26	*1*
Location: **Analyst Description:** Brown, Homogeneous, Non-Fibrous, Soil **Asbestos Types:** **Other Material:** Cellulose Present, Non-fibrous Present				
CG-30-0.5	126022042-03	***No***	NVA by C. David Mintz on 02/25/26	*1*
Location: **Analyst Description:** Brown, Homogeneous, Non-Fibrous, Soil **Asbestos Types:** **Other Material:** Cellulose Present, Non-fibrous Present				
CG-30-2.5	126022042-04	***No***	NVA by C. David Mintz on 02/25/26	*1*
Location: **Analyst Description:** Brown, Homogeneous, Non-Fibrous, Soil **Asbestos Types:** **Other Material:** Non-fibrous Present				
CG-31-0.5	126022042-05	***No***	NVA by C. David Mintz on 02/25/26	*1*
Location: **Analyst Description:** Brown, Homogeneous, Non-Fibrous, Soil **Asbestos Types:** **Other Material:** Cellulose Present, Non-fibrous Present				
CG-31-2.5	126022042-06	***No***	NVA by C. David Mintz on 02/25/26	*1*
Location: **Analyst Description:** Brown, Heterogeneous, Non-Fibrous, Soil **Asbestos Types:** **Other Material:** Cellulose Present, Non-fibrous Present				

See Reporting notes on last page

PLM Bulk Asbestos Report

EO-553481

Client No. / HGA	Lab No.	Asbestos Present	Total % Asbestos	Notes
CG-32-0.5	126022042-07	***No***	NVA by C. David Mintz on 02/25/26	*1*


Location:
Analyst Description: Brown, Homogeneous, Non-Fibrous, Soil
Asbestos Types:
Other Material: Cellulose Present, Non-fibrous Present

CG-32-2.5	126022042-08	***No***	NVA by C. David Mintz on 02/25/26	*1*

Location:
Analyst Description: Brown, Homogeneous, Non-Fibrous, Soil
Asbestos Types:
Other Material: Cellulose Present, Non-fibrous 100%

Reporting Notes:

(1) Sample homogenized by grinding to a powder prior to analysis.

Analyzed by: C. David Mintz 
Date: 2/25/2026

Reviewed by: Glenn F. Massey 

*NAD = no asbestos detected, Detection Limit <1%, Reporting Limits: CVES = 1%, 400 Pt Ct = 0.25%, 1000 Pt Ct = 0.1%; "Present" or NVA = "No Visible Asbestos" are observations made during a qualitative analysis (Not covered by NVLAP or NY ELAP accreditations); NA = not analyzed; NA/PS = not analyzed / positive stop; PLM Bulk Asbestos Analysis using Olympus, Model BH-2 microscope, Serial #210972, by EPA 600/R-93/116 per 40 CFR 763 (NVLAP Lab Code 101904-0) and ELAP PLM Analysis Protocol 198.1 for New York friable samples which includes quantitation of any vermiculite observed (198.6 for NOB samples) or EPA 400 pt ct by EPA 600/M4-82-020 (NYSDOH ELAP Lab # 10984); CA ELAP Lab # 2508; Note: PLM is not consistently reliable in detecting asbestos in floor coverings and similar NOB materials. NAD or Trace results by PLM are inconclusive, TEM is currently the only method that can be used to determine if this material can be considered or treated as non-asbestos-containing in New York State (also see EPA Advisory for floor tile, FR 59, 146, 38970, 8/1/94). NIST Accreditation requirements mandate that this report must not be reproduced except in full without the approval of the laboratory. This PLM report relates ONLY to the items tested.

Subject: Re: [External] - ACTION NEEDED - NEED PO#S
From: Jocelyn Nguyen <JocelynNguyen@enthalpy.com>
Date: 2/26/2026, 1:28 PM
To: Patricia Mata <patty.mata@enthalpy.com>
CC: Kenyell Morris <varesults@amerisci.com>

126-02-2042

Hello,
The PO#'s for these were sent and had included on the invoices .
126021641/552829
126021827/553104
126021832/552829

For 126022042/553481: PO-098962

Thank you,

Jocelyn Nguyen
Project Manager Assistant
Enthalpy Analytical
931 W Barkley Ave. | Orange, CA 92868
Office: +1-714-771-6900 X 10315
JocelynNguyen@enthalpy.com |enthalpy.com
Terms and Conditions

From: Patricia Mata <patty.mata@enthalpy.com>
Sent: Thursday, February 26, 2026 9:37 AM
To: Jocelyn Nguyen <JocelynNguyen@enthalpy.com>
Subject: Fw: [External] - ACTION NEEDED - NEED PO#S

Hi Jocelyn,

Can you please email PO numbers to AmeriSci for me?

Thank you!

With Regards,
Patty Mata
Project Manager
Enthalpy Analytical
Direct: +1-714-771-9930 | Mobile: +1-714-323-2586
patty.mata@enthalpy.com

From: Tiffany Goodwyn <varesults@amerisci.com>
Sent: Thursday, February 26, 2026 6:14 AM
To: Patricia Mata <patty.mata@enthalpy.com>

126022042

ENTHALPY ANALYTICAL

931 West Barkley Ave
Orange, CA 92868
(714) 771-6900

Subcontract Laboratory:
AmeriSci Los Angeles
24416 S. Main Street
Suite 308
Carson, CA 90745
ATTN: Sample Control
PO #: Required, to be sent via email

Enthalpy Order: EO-553481
PM: Patty Mata
Email: patty.mata@enthalpy.com
CC: incomingreports@enthalpy.com
Phone: (714) 771-6900

Results Due: Standard TAT
Report Level: II
Report To: RL
EDDs:

Notes:

Sample ID	Collected	Lab ID	# Cont.	Matrix	Analysis Requested	Comment
CG-28-0.5	17-FEB-2026 00:00	553481-007	1	Soil	Asbestos by PLM	PLM qualitative
CG-28-2.5	17-FEB-2026 00:00	553481-008	1	Soil	Asbestos by PLM	PLM qualitative
CG-30-0.5	17-FEB-2026 00:00	553481-009	1	Soil	Asbestos by PLM	PLM qualitative
CG-30-2.5	17-FEB-2026 00:00	553481-010	1	Soil	Asbestos by PLM	PLM qualitative
CG-31-0.5	17-FEB-2026 00:00	553481-011	1	Soil	Asbestos by PLM	PLM qualitative
CG-31-2.5	17-FEB-2026 00:00	553481-012	1	Soil	Asbestos by PLM	PLM qualitative
CG-32-0.5	17-FEB-2026 00:00	553481-013	1	Soil	Asbestos by PLM	PLM qualitative
CG-32-2.5	17-FEB-2026 00:00	553481-014	1	Soil	Asbestos by PLM	PLM qualitative
EB-01-260217	17-FEB-2026 15:30	553481-015	1	Water	Asbestos	non-potable water for TEM

Notes:	Relinquished By:	Received By:
	[signature]	M. RIVERO
	Date: 2/20/26 1222	Date: 2/21/26 @ 1225
	M. RIVERO	
	Date: 2/21/26 @ 1225	Date:
	Date:	Date:

Received
FEB 23 2026

1260220 42

ENTHALPY ANALYTICAL

931 West Barkley Ave
Orange, CA 92868
(714) 771-6900

Subcontract Laboratory:
AmeriSci Los Angeles
24416 S. Main Street
Suite 308
Carson, CA 90745
ATTN: Sample Control
PO #: Required, to be sent via email

Enthalpy Order: EO-553481
PM: Patty Mata
Email: patty.mata@enthalpy.com
CC: incomingreports@enthalpy.com
Phone: (714) 771-6900

Results Due: Standard TAT
Report Level: II
Report To: RL
EDDs:

Notes:

Sample ID	Collected	Lab ID	# Cont.	Matrix	Analysis Requested	Comment
CG-28-0.5	17-FEB-2026 00:00	553481-007	1	Soil	Asbestos by PLM	PLM qualitative
CG-28-2.5	17-FEB-2026 00:00	553481-008	1	Soil	Asbestos by PLM	PLM qualitative
CG-30-0.5	17-FEB-2026 00:00	553481-009	1	Soil	Asbestos by PLM	PLM qualitative
CG-30-2.5	17-FEB-2026 00:00	553481-010	1	Soil	Asbestos by PLM	PLM qualitative
CG-31-0.5	17-FEB-2026 00:00	553481-011	1	Soil	Asbestos by PLM	PLM qualitative
CG-31-2.5	17-FEB-2026 00:00	553481-012	1	Soil	Asbestos by PLM	PLM qualitative
CG-32-0.5	17-FEB-2026 00:00	553481-013	1	Soil	Asbestos by PLM	PLM qualitative
CG-32-2.5	17-FEB-2026 00:00	553481-014	1	Soil	Asbestos by PLM	PLM qualitative
EB-01-260217	17-FEB-2026 15:30	553481-015	1	Water	Asbestos	non-potable water for TEM

Notes:	Relinquished By:	Received By:
	[signature]	M. RIVERA
	Date: 2/20/26 1222	Date: 2/21/26 @ 1225
	M. RIVERA	
	Date: 2/21/26 @ 1225	Date:
	Date:	Date:

Received
FEB 23 2026
AM

AmeriSci Richmond
13635 GENITO ROAD
MIDLOTHIAN, VIRGINIA 23112
TEL: (804) 763-1200 • FAX: (804) 763-0493

February 28, 2026

Enthalpy Analytical
Attn: Patty Mata
931 West Barkley Ave
Orange, CA 92868

RE: Enthalpy Analytical
Job Number 126022043
P.O. #098962
EO-553481

Dear Patty Mata:

Enclosed are the results for TEM asbestos analysis of the following Enthalpy Analytical samples received at AmeriSci on Tuesday, February 24, 2026, for a 5 day turnaround:

EB-01-260217

The 1 samples were filtered and prepared according to Water analysis under the EPA-600/4-83-043 "Analytical Method for Determination of Asbestos Fibers in Water" (1983). Samples with high organic content may be prepared following EPA-600/4-80-005 if necessary and are so noted on the TEM count sheets. AmeriSci, Inc. uses the "Grid Square" method of counting and the concentration is calculated in millions of fibers per liter (MFL).

Table I represents a summary of all pertinent information used for the calculations. Included are the size of each structure counted, concentration, structure concentration greater than 10 microns in length, type of asbestiform material detected and the analytical sensitivity, which represents the concentration by the detection of one fiber in the TEM fiber count. Copies of the Fiber Count Sheets, show the raw data for examination. These data sheets contain information for fiber length/width, fiber type, structure morphology and pertinent information on EDS, SAED and photography.

This report relates ONLY to the sample analysis expressed as millions of fibers per liter (MFL). AmeriSci assumes no responsibility for customer supplied data such as “sample location” or “the condition of the water sample before arriving at AmeriSci”. This report must not be used to claim product endorsement by AmeriSci, NVLAP, ELAP or any agency of the U. S. Government. The National Institute of Standards and Technology accreditation requirements, mandate that this report must not be reproduced, except in full without the approval of the laboratory.

AmeriSci appreciates this opportunity to serve your organization. Please contact us for any further assistance or with any questions.

Sincerely,



Cory M. Parnell

Laboratory Director | Authorized Signatory

AmeriSci Job #: **126022043**
Client Name: Enthalpy Analytical

Table I
Summary of Transmission Electron Microscopy (TEM) Results for Asbestos (Water)


EO-553481

AmeriSci Sample #	Client Sample No./Location	Liquid Filtered (liters)	Temp (Celcius)	Structures Detected* (total)	Structures Detected* (>10 µm)	Analytical Sensitivity (MF/L)	Asbestos Conc (total) (MF/L)	Asbestos Conc (>10 µm) (MF/L)	Asbestos Type
01	EB-01-260217	0.01	14.7	NSD	NSD	0.22	<0.22	<0.22	----

* NAD/NSD = no asbestos detected, NA = not analyzed, MF/L = million fibers per liter; Drinking Water accreditations do not cover waste water analysis. NOTE: Drinking water analysis by EPA-600/4-83-043 (100.1). Fiber criteria (>=0.5 microns, for 100.1; >10 microns for 100.2; 5:1 aspect ratio for both), organic rich waste water prepped by EPA-600/4-80-005. Analytical sensitivity calculated as though 1 fiber had been detected on the TEM GRID area analyzed. Sample temperatures reported above were measured upon receipt. Water samples are refrigerated upon receipt and filtered within four hours.

Reviewed By: _____ Analyzed By: Cory M. Parnell _____ Date: 2/28/2026

TEM Asbestos (Water) Count Sheet



Client Name:	Enthalpy Analytical		
Job #:	126022043	Volume (liters):	0.01
Lab Sample #:	01	Filter Type / Filter Area:	MCE 214 mm2
Client Sample #:	EB-01-260217	Grid Opening Size:	0.00967
Received:	2/24/2026 12:00:00	Area Examined:	0.09670 mm2
Date Analyzed:	2/28/2026	Magnification:	20,000
	Temp: 14.7	Accelerating Voltage:	100 KeV

Analysis Performed by: Cory M. Parnell

Location	Grid Opening	Fiber	Length µM	Width µM	Fiber Type	Morphology	EDS	Orient.	SAED	Photo
E10-G2	1	NSD							☐	
E10-G4	2	NSD							☐	
E10-G6	3	NSD							☐	
E10-G8	4	NSD							☐	
E10-G10	5	NSD							☐	
A1-H2	6	NSD							☐	
A1-H4	7	NSD							☐	
A1-H6	8	NSD							☐	
A1-H8	9	NSD							☐	
A1-H10	10	NSD							☐	

NSD: No Asbestos Structures Detected

Scope #: Back 2: Jeol JEM-100CX, Serial No.EM-156067-73

Comments

		Concentration (million fibers/liter)	Grid Evaluation
Total Grid Openings:	10		☑ Grid Openings Covered > 50%
Chrysotile Asbestos Structures:	0	<0.221	☑ Intact Grid Opening > 50%
Amphibole Asbestos Structures:	0	<0.221	☑ Undissolved Filter < 10%
Asbestos Structures >10 microns:	0	<0.221	☑ Folded Replica < 50%
Total Asbestos Structures:	0	<0.221	☑ Filter Loading < 25%
Analytical Sensitivity:		0.221	☑ Particulate Even

Subject: Re: [External] - Order Confirmation
From: Patricia Mata <patty.mata@enthalpy.com>
Date: 2/25/2026, 11:52 AM
To: "varesults@amerisci.com" <varesults@amerisci.com>

Hello,

Please use PO-098962 on the invoice for my lab # 553481.

Thank you!

With Regards,
Patty Mata
Project Manager
Enthalpy Analytical
Direct: +1-714-771-9930 | Mobile: +1-714-323-2586
patty.mata@enthalpy.com

From: varesults@amerisci.com <varesults@amerisci.com>
Sent: Wednesday, February 25, 2026 5:56 AM
To: Patricia Mata <patty.mata@enthalpy.com>; varesults@amerisci.com <varesults@amerisci.com>
Subject: [External] - Order Confirmation

This is to confirm our receipt of 1 samples on 2/25/2026.

Need PO number

Our Job #: 126022043

Your Job Number: EO-553481
Your Job Name:
Your Job Site:
Your Analysis Type: Water (waste)
Your Turnaround Time: 5 day

CONFIDENTIALITY NOTICE: The contents of this email message and any attachments are intended solely for the addressee(s) and may contain confidential, proprietary and/or privileged information and may be legally protected from disclosure. If you are not the intended recipient of this message or their agent, or if this message has been addressed to you in error, please immediately alert the sender by reply email and then delete this message and any attachments and the reply from your system. If you are not the intended recipient, you are hereby notified that any disclosure, use, dissemination, copying, or storage of this message or its attachments is strictly prohibited.

The information contained in this e-mail and any attachments from Montrose Environmental Group, Inc. may contain confidential and/or proprietary information, and is intended only for the named recipient to whom it was originally addressed. If you are not the intended recipient, any disclosure, distribution, or copying of this e-mail or its attachments is strictly prohibited. If you have received this e-mail in error, please notify the sender immediately by return e-mail and permanently delete the e-mail and any attachments.

CONFIDENTIALITY NOTICE: The contents of this email message and any attachments are intended solely for the addressee(s) and may contain confidential, proprietary and/or privileged information and may be legally protected from disclosure. If you are not the intended recipient of this message or their agent, or if this message has been addressed to you in error, please immediately alert the sender by reply email and then

126022043 apw 2/23/26

ENTHALPY ANALYTICAL

931 West Barkley Ave
Orange, CA 92868
(714) 771-6900

Subcontract Laboratory:
AmeriSci Los Angeles
24416 S. Main Street
Suite 308
Carson, CA 90745
ATTN: Sample Control
PO #: Required, to be sent via email

Enthalpy Order: EO-553481
PM: Patty Mata
Email: patty.mata@enthalpy.com
CC: incomingreports@enthalpy.com
Phone: (714) 771-6900

Results Due: Standard TAT
Report Level: II
Report To: RL
EDDs:

Notes:

Sample ID	Collected	Lab ID	# Cont.	Matrix	Analysis Requested	Comment
CG-28-0.5	17-FEB-2026 00:00	553481-007	1	Soil	Asbestos by PLM	PLM qualitative
CG-28-2.5	17-FEB-2026 00:00	553481-008	1	Soil	Asbestos by PLM	PLM qualitative
CG-30-0.5	17-FEB-2026 00:00	553481-009	1	Soil	Asbestos by PLM	PLM qualitative
CG-30-2.5	17-FEB-2026 00:00	553481-010	1	Soil	Asbestos by PLM	PLM qualitative
CG-31-0.5	17-FEB-2026 00:00	553481-011	1	Soil	Asbestos by PLM	PLM qualitative
CG-31-2.5	17-FEB-2026 00:00	553481-012	1	Soil	Asbestos by PLM	PLM qualitative
CG-32-0.5	17-FEB-2026 00:00	553481-013	1	Soil	Asbestos by PLM	PLM qualitative
CG-32-2.5	17-FEB-2026 00:00	553481-014	1	Soil	Asbestos by PLM	PLM qualitative
* EB-01-260217	17-FEB-2026 15:30	553481-015	1	Water	Asbestos	non-potable water for TEM

Notes:	Relinquished By:	Received By:
	[signature]	M. RIVERA
	Date: 2/20/26 1222	Date: 2/21/26 0 1225
	M. RIVERA	
	Date: 2/21/26 0 1225	Date:
	Date:	Date:

Received
FEB 23 2026

Enthalpy Analytical
931 West Barkley Ave
Orange, CA 92868
(714) 771-6900

enthalpy.com

Lab Job Number	:	553642
Report Level	:	II
Report Date	:	03/16/2026
Revision	:	**1 (See narrative)**

Analytical Report *prepared for:*

Vanya Keyes
Terraphase Engineering
18401 Von Karman Ave, Suite #410
Irvine, CA 92612

Project: CENTENNIAL HS - Centennial High School, 2606 N Central Ave., Compton, CA 90222

Authorized for release by:



Patty Mata, Project Manager
patty.mata@enthalpy.com

This data package has been reviewed for technical correctness and completeness. Release of this data has been authorized by the Laboratory Manager or the Manager's designee, as verified by the above signature which applies to this PDF file as well as any associated electronic data deliverable files. The results contained in this report meet all requirements of NELAP and pertain only to those samples which were submitted for analysis. This report may be reproduced only in its entirety.

CA ELAP# 1338, CA ELAP #1338-S1, NELAP# 4038, SCAQMD LAP# 18LA0518, LACSD ID# 10105, ORELAP# 4197

ENTHALPY ANALYTICAL

Sample Summary

Vanya Keyes
Terraphase Engineering
18401 Von Karman Ave, Suite #410
Irvine, CA 92612

Lab Job #: 553642
Project No: CENTENNIAL HS
Location: Centennial High School, 2606 N Central Ave., Compton, CA 90222
Date Received: 02/18/26

Sample ID	Lab ID	Collected	Matrix
AOC4-SB-16-0.5	553642-001	02/18/26 07:46	Soil
AOC4-SB-17-0.5	553642-002	02/18/26 08:12	Soil
AOC4-SB-18-0.5	553642-003	02/18/26 08:30	Soil
AOC4-SB-16-2.5	553642-004	02/18/26 08:02	Soil
AOC4-SB-17-2.5	553642-005	02/18/26 08:23	Soil
AOC4-SB-18-2.5	553642-006	02/18/26 08:34	Soil
AOC4-SB-19-0.5	553642-007	02/18/26 08:43	Soil
AOC4-SB-20-0.5	553642-008	02/18/26 08:50	Soil
AOC4-SB-21-0.5	553642-009	02/18/26 09:02	Soil
AOC4-SB-19-2.5	553642-010	02/18/26 08:47	Soil
AOC4-SB-20-2.5	553642-011	02/18/26 08:58	Soil
AOC4-SB-21-2.5	553642-012	02/18/26 09:08	Soil
AOC4-SB-22-0.5	553642-013	02/18/26 09:14	Soil
AOC4-SB-23-0.5	553642-014	02/18/26 09:27	Soil
AOC4-SB-24-0.5	553642-015	02/18/26 09:51	Soil
AOC4-SB-22-2.5	553642-016	02/18/26 09:20	Soil
AOC4-SB-23-2.5	553642-017	02/18/26 09:36	Soil
AOC4-SB-24-2.5	553642-018	02/18/26 10:00	Soil
CG-34-0.5	553642-019	02/18/26 00:00	Soil
CG-34-2.5	553642-020	02/18/26 00:00	Soil
CG-35-0.5	553642-021	02/18/26 00:00	Soil
CG-35-2.5	553642-022	02/18/26 00:00	Soil
CG-36-0.5	553642-023	02/18/26 00:00	Soil
CG-36-2.5	553642-024	02/18/26 00:00	Soil
CG-39-0.5	553642-025	02/18/26 00:00	Soil
CG-39-2.5	553642-026	02/18/26 00:00	Soil

ENTHALPY ANALYTICAL

Sample Summary

Vanya Keyes Terraphase Engineering 18401 Von Karman Ave, Suite #410 Irvine, CA 92612	Lab Job #: Project No: Location: Date Received:	553642 CENTENNIAL HS Centennial High School, 2606 N Central Ave., Compton, CA 90222 02/18/26

Sample ID	Lab ID	Collected	Matrix
CG-33-0.5	553642-027	02/18/26 00:00	Soil
CG-33-2.5	553642-028	02/18/26 00:00	Soil
AOC4-SB-31-0.5	553642-029	02/18/26 10:18	Soil
AOC4-SB-32-0.5	553642-030	02/18/26 10:37	Soil
AOC4-SB-33-0.5	553642-031	02/18/26 11:21	Soil
AOC4-SB-31-2.5	553642-032	02/18/26 10:25	Soil
AOC4-SB-32-2.5	553642-033	02/18/26 10:43	Soil
AOC4-SB-33-2.5	553642-034	02/18/26 11:27	Soil
AOC4-SB-13-0.5	553642-035	02/18/26 12:04	Soil
AOC4-SB-14-0.5	553642-036	02/18/26 13:44	Soil
AOC4-SB-15-0.5	553642-037	02/18/26 14:06	Soil
AOC4-SB-13-2.5	553642-038	02/18/26 12:07	Soil
AOC4-SB-14-2.5	553642-039	02/18/26 13:55	Soil
AOC4-SB-15-2.5	553642-040	02/18/26 14:12	Soil
AOC4-SB-25-0.5	553642-041	02/18/26 14:34	Soil
AOC4-SB-26-0.5	553642-042	02/18/26 14:54	Soil
AOC4-SB-27-0.5	553642-043	02/18/26 15:14	Soil
DUP-01-0.5-260218	553642-044	02/18/26 00:00	Soil
AOC4-SB-25-2.5	553642-045	02/18/26 14:39	Soil
AOC4-SB-26-2.5	553642-046	02/18/26 14:57	Soil
AOC4-SB-27-2.5	553642-047	02/18/26 15:23	Soil
DUP-01-2.5-260218	553642-048	02/18/26 00:00	Soil
CG-37-0.5	553642-049	02/18/26 00:00	Soil
CG-37-2.5	553642-050	02/18/26 00:00	Soil
EB-01-260218	553642-051	02/18/26 16:00	Water
CG-34-0.5-DUP	553642-052	02/18/26 00:00	Soil

ENTHALPY ANALYTICAL

Sample Summary

Vanya Keyes
Terraphase Engineering
18401 Von Karman Ave, Suite #410
Irvine, CA 92612

Lab Job #:	553642
Project No:	CENTENNIAL HS
Location:	Centennial High School, 2606 N Central Ave., Compton, CA 90222
Date Received:	02/18/26

Sample ID	Lab ID	Collected	Matrix
CG-34-2.5-DUP	553642-053	02/18/26 00:00	Soil

Case Narrative

Terraphase Engineering 18401 Von Karman Ave, Suite #410 Irvine, CA 92612 Vanya Keyes	Lab Job Number: 553642 Project No: CENTENNIAL HS Location: Centennial High School, 2606 N Central Ave., Compton, CA 90222 Date Received: 02/18/26

- This data package contains sample and QC results for twenty one soil samples, twelve three-point soil composites, and one water sample, requested for the above referenced project on 02/18/26. The samples were received in good condition.
- Revised report on 3/16/26 to include additional PCB test results as requested on 3/6/26.

Pesticides (EPA 8081A) Water:
No analytical problems were encountered.

Pesticides (EPA 8081A) Soil:

- CG-36-0.5 (lab # 553642-023) and CG-37-0.5 (lab # 553642-049) were diluted due to the color of the sample extracts. Extract color and/or viscosity are used as indicators of possible matrix interference. Elevated reporting limits were due to the necessary dilutions.
- For selected samples, the presence of target compound was confirmed but the relative percent difference (RPD) between columns exceeded 40%. Affected result was flagged with "C".
- No other analytical problems were encountered.

PCBs (EPA 8082) Water:
No analytical problems were encountered.

PCBs (EPA 8082) Soil:

- High recoveries were observed for Aroclor-1016 and Aroclor-1260 in the MSD of AOC4-SB-20-0.5 (lab # 553642-008); the LCS was within limits, and the associated RPDs were within limits.
- High surrogate recoveries were observed for decachlorobiphenyl (PCB surrogate) in AOC4-SB-23-0.5 (lab # 553642-014) and the MSD of AOC4-SB-20-0.5 (lab # 553642-008).
- PCB tests for lab numbers 553642-004 and 553642-032 were requested past the 14-day extraction hold time. The samples were prepared outside of hold time; affected data was qualified with "H".
- Many samples were treated with sulfuric acid to reduce analytical interferences or due to the presence of color.
- No other analytical problems were encountered.

Metals (EPA 6010B) Water:
No analytical problems were encountered.

Metals (EPA 6010B) Soil:
No analytical problems were encountered.

100.1 Asbestos (EPA 100.1 Asbestos):
AmeriSci Los Angeles in Carson, CA performed the analysis (see sublab report section for certifications). Please see the AmeriSci Los Angeles case narrative.

Asbestos by PLM (EPA 600/R-93-116):
AmeriSci Los Angeles in Carson, CA performed the analysis (see sublab report section for certifications). Please see the AmeriSci Los Angeles case narrative.

ENTHALPY ANALYTICAL

Detection Summary

Vanya Keyes
Terraphase Engineering
18401 Von Karman Ave, Suite #410
Irvine, CA 92612

Lab Job #: 553642
Project No: CENTENNIAL HS
Location: Centennial High School, 2606 N Central Ave., Compton, CA 90222
Date Received: 02/18/26

Sample ID: AOC4-SB-16-0.5 **Lab ID: 553642-001** **Collected: 02/18/26 07:46**
Matrix: Soil

553642-001 Analyte	Result	Qual	Units	RL
Method: EPA 6010B Prep Method: EPA 3050B				
Lead	**48**		mg/Kg	0.99
Method: EPA 8082 Prep Method: EPA 3546				
Aroclor-1254	**3,700**		ug/Kg	250
Aroclor-1260	**1,700**		ug/Kg	250
Total PCBs	**5,400**		ug/Kg	49

Sample ID: AOC4-SB-17-0.5 **Lab ID: 553642-002** **Collected: 02/18/26 08:12**
Matrix: Soil

553642-002 Analyte	Result	Qual	Units	RL
Method: EPA 6010B Prep Method: EPA 3050B				
Lead	**36**		mg/Kg	0.95

Sample ID: AOC4-SB-18-0.5 **Lab ID: 553642-003** **Collected: 02/18/26 08:30**
Matrix: Soil

553642-003 Analyte	Result	Qual	Units	RL
Method: EPA 6010B Prep Method: EPA 3050B				
Lead	**70**		mg/Kg	1.0

Sample ID: AOC4-SB-16-2.5 **Lab ID: 553642-004** **Collected: 02/18/26 08:02**

No Detections

Sample ID: AOC4-SB-19-0.5 **Lab ID: 553642-007** **Collected: 02/18/26 08:43**
Matrix: Soil

553642-007 Analyte	Result	Qual	Units	RL
Method: EPA 6010B Prep Method: EPA 3050B				
Lead	**44**		mg/Kg	0.97

Results for any subcontracted analyses are not included in this summary. Data qualifiers and additional information necessary for the interpretation of the test results are contained in the PDF file and may not be included in this summary.

ENTHALPY ANALYTICAL

Detection Summary

Sample ID: AOC4-SB-20-0.5 **Lab ID: 553642-008** **Collected: 02/18/26 08:50**
Matrix: Soil

553642-008 Analyte	Result	Qual	Units	RL
Method: EPA 6010B Prep Method: EPA 3050B				
Lead	**42**		mg/Kg	0.98

Sample ID: AOC4-SB-21-0.5 **Lab ID: 553642-009** **Collected: 02/18/26 09:02**
Matrix: Soil

553642-009 Analyte	Result	Qual	Units	RL
Method: EPA 6010B Prep Method: EPA 3050B				
Lead	**35**		mg/Kg	0.97

Sample ID: AOC4-SB-22-0.5 **Lab ID: 553642-013** **Collected: 02/18/26 09:14**
Matrix: Soil

553642-013 Analyte	Result	Qual	Units	RL
Method: EPA 6010B Prep Method: EPA 3050B				
Lead	**45**		mg/Kg	0.96

Sample ID: AOC4-SB-23-0.5 **Lab ID: 553642-014** **Collected: 02/18/26 09:27**
Matrix: Soil

553642-014 Analyte	Result	Qual	Units	RL
Method: EPA 6010B Prep Method: EPA 3050B				
Lead	**18**		mg/Kg	0.97

Sample ID: AOC4-SB-24-0.5 **Lab ID: 553642-015** **Collected: 02/18/26 09:51**
Matrix: Soil

553642-015 Analyte	Result	Qual	Units	RL
Method: EPA 6010B Prep Method: EPA 3050B				
Lead	**28**		mg/Kg	0.97

Sample ID: CG-34-0.5 **Lab ID: 553642-019** **Collected: 02/18/26**
Matrix: Soil

553642-019 Analyte	Result	Qual	Units	RL
Method: EPA 8081A Prep Method: EPA 3546				
Dieldrin	**9.3**	C	ug/Kg	5.1
4,4'-DDE	**6.9**	C	ug/Kg	5.1
4,4'-DDT	**17**	C	ug/Kg	5.1

Results for any subcontracted analyses are not included in this summary. Data qualifiers and additional information necessary for the interpretation of the test results are contained in the PDF file and may not be included in this summary.

ENTHALPY ANALYTICAL

Detection Summary

Sample ID: CG-34-2.5	Lab ID: 553642-020	Collected: 02/18/26

No Detections

Sample ID: CG-35-0.5	Lab ID: 553642-021	Collected: 02/18/26

No Detections

Sample ID: CG-35-2.5	Lab ID: 553642-022	Collected: 02/18/26

No Detections

Sample ID: CG-36-0.5	Lab ID: 553642-023	Collected: 02/18/26

No Detections

Sample ID: CG-36-2.5	Lab ID: 553642-024	Collected: 02/18/26

No Detections

Sample ID: CG-39-0.5	Lab ID: 553642-025	Collected: 02/18/26

No Detections

Sample ID: CG-39-2.5	Lab ID: 553642-026	Collected: 02/18/26

No Detections

Sample ID: CG-33-0.5	Lab ID: 553642-027	Collected: 02/18/26

No Detections

Sample ID: CG-33-2.5	Lab ID: 553642-028	Collected: 02/18/26

No Detections

Results for any subcontracted analyses are not included in this summary. Data qualifiers and additional information necessary for the interpretation of the test results are contained in the PDF file and may not be included in this summary.

ENTHALPY ANALYTICAL

Detection Summary

Sample ID: AOC4-SB-31-0.5 **Lab ID: 553642-029** **Collected: 02/18/26 10:18**
Matrix: Soil

553642-029 Analyte	Result	Qual	Units	RL
Method: EPA 6010B Prep Method: EPA 3050B				
Lead	**23**		mg/Kg	0.98
Method: EPA 8082 Prep Method: EPA 3546				
Aroclor-1254	**190**		ug/Kg	50
Aroclor-1260	**110**		ug/Kg	50
Total PCBs	**300**		ug/Kg	50

Sample ID: AOC4-SB-32-0.5 **Lab ID: 553642-030** **Collected: 02/18/26 10:37**
Matrix: Soil

553642-030 Analyte	Result	Qual	Units	RL
Method: EPA 6010B Prep Method: EPA 3050B				
Lead	**16**		mg/Kg	0.96

Sample ID: AOC4-SB-33-0.5 **Lab ID: 553642-031** **Collected: 02/18/26 11:21**
Matrix: Soil

553642-031 Analyte	Result	Qual	Units	RL
Method: EPA 6010B Prep Method: EPA 3050B				
Lead	**70**		mg/Kg	0.96

Sample ID: AOC4-SB-31-2.5 **Lab ID: 553642-032** **Collected: 02/18/26 10:25**

No Detections

Sample ID: AOC4-SB-13-0.5 **Lab ID: 553642-035** **Collected: 02/18/26 12:04**
Matrix: Soil

553642-035 Analyte	Result	Qual	Units	RL
Method: EPA 6010B Prep Method: EPA 3050B				
Lead	**21**		mg/Kg	0.99

Sample ID: AOC4-SB-14-0.5 **Lab ID: 553642-036** **Collected: 02/18/26 13:44**
Matrix: Soil

553642-036 Analyte	Result	Qual	Units	RL
Method: EPA 6010B Prep Method: EPA 3050B				
Lead	**20**		mg/Kg	0.95

Results for any subcontracted analyses are not included in this summary. Data qualifiers and additional information necessary for the interpretation of the test results are contained in the PDF file and may not be included in this summary.

ENTHALPY ANALYTICAL

Detection Summary

Sample ID: AOC4-SB-15-0.5 **Lab ID: 553642-037** **Collected: 02/18/26 14:06**
Matrix: Soil

553642-037 Analyte	Result	Qual	Units	RL
Method: EPA 6010B Prep Method: EPA 3050B				
Lead	**68**		mg/Kg	0.97
Method: EPA 8082 Prep Method: EPA 3546				
Aroclor-1260	**120**		ug/Kg	49
Total PCBs	**120**		ug/Kg	49

Sample ID: AOC4-SB-25-0.5 **Lab ID: 553642-041** **Collected: 02/18/26 14:34**
Matrix: Soil

553642-041 Analyte	Result	Qual	Units	RL
Method: EPA 6010B Prep Method: EPA 3050B				
Lead	**16**		mg/Kg	0.95

Sample ID: AOC4-SB-26-0.5 **Lab ID: 553642-042** **Collected: 02/18/26 14:54**
Matrix: Soil

553642-042 Analyte	Result	Qual	Units	RL
Method: EPA 6010B Prep Method: EPA 3050B				
Lead	**9.1**		mg/Kg	1.0

Sample ID: AOC4-SB-27-0.5 **Lab ID: 553642-043** **Collected: 02/18/26 15:14**
Matrix: Soil

553642-043 Analyte	Result	Qual	Units	RL
Method: EPA 6010B Prep Method: EPA 3050B				
Lead	**10**		mg/Kg	0.98

Sample ID: DUP-01-0.5-260218 **Lab ID: 553642-044** **Collected: 02/18/26**
Matrix: Soil

553642-044 Analyte	Result	Qual	Units	RL
Method: EPA 6010B Prep Method: EPA 3050B				
Lead	**13**		mg/Kg	0.98

Sample ID: CG-37-0.5 **Lab ID: 553642-049** **Collected: 02/18/26**

No Detections

Results for any subcontracted analyses are not included in this summary. Data qualifiers and additional information necessary for the interpretation of the test results are contained in the PDF file and may not be included in this summary.

ENTHALPY ANALYTICAL

Detection Summary

Sample ID: CG-37-2.5	Lab ID: 553642-050	Collected: 02/18/26

No Detections

Sample ID: EB-01-260218	Lab ID: 553642-051	Collected: 02/18/26 16:00

No Detections

Sample ID: CG-34-0.5-DUP	Lab ID: 553642-052 Matrix: Soil	Collected: 02/18/26

553642-052 Analyte		Result	Qual	Units	RL
Method: EPA 8081A Prep Method: EPA 3546					
	Dieldrin	**7.0**	C	ug/Kg	4.9
	4,4'-DDE	**6.2**	C	ug/Kg	4.9
	4,4'-DDT	**85**	C	ug/Kg	4.9

Sample ID: CG-34-2.5-DUP	Lab ID: 553642-053	Collected: 02/18/26

No Detections

C Presence confirmed, but RPD between columns exceeds 40%

Results for any subcontracted analyses are not included in this summary. Data qualifiers and additional information necessary for the interpretation of the test results are contained in the PDF file and may not be included in this summary.

Login 553642

ALPY TICAL

Chain of Custody Record

Lab No: 553642

Page: 1 of 7

Turn Around Time (rush by advanced notice only)

Standard:	X	5 Day:		3 Day:	
2 Day:		1 Day:		Custom TAT	

931 W. Barkley Avenue, Orange, CA 92868

Phone 714-771-6900

Matrix: A = Air, S = Soil/Solid, W = Water, DW = Drinking Water, P = Product, O = Oil, SD = Sediment, T = Tissue, WP = Wipe, WW = Wastewater, X = Other

Sample Type: C = Composite, G = Grab or Discrete, B = Blank, O = Other

Preservatives: 0 = none, 1 = $Na_2S_2O_3$, 2 = HCl, 3 = HNO_3, 4 = H_2SO_4, 5 = NaOH, 6 = Other

Sample Receipt Temp and Notes: (lab use only)

CUSTOMER INFORMATION

Company:	Terraphase Engineering Inc.
Report To:	Vanya Keyes
Email:	vanya.keyes@terraphase.com
Address:	18401 Von Karman Ave
Phone:	949-377-2227
Fax:	

PROJECT INFORMATION

Name:	Centennial High School
Number:	
P.O. #:	0215.002.002
Address:	2606 N Central Ave
	Compton, CA, 90222
Global ID:	
Sampled By:	Portia C. Ibarra

Analysis Request

Test Instructions / Comments

IR-15
Temp 23°C/+0.4

Please also send report to
clare.steedman@terraphase.com
portia.ibarra@terraphase.com

	Sample ID	Sampling Date	Sampling Time (24 hr)	Matrix	Sample Type	Pres.	Cont. No.	Cont. Size	Initials	Arsenic (6020)	Lead (6010B)	PCBs (8082)	Title 22 Metals (6020/7471A)	Dioxins & Furins (8290A)	VOCs (8260B)	TPH (8015)	
1	GOC4-SB-16-0.5	2/18/26	0746	S	G	0	2	80z	PCI		X	X					CG-34-0.5
2	GOC4-SB-17-0.5	"	0812	"	"	"	2	"	"		X	X					
3	GOC4-SB-18-0.5		0830				2				X	X					
4	GOC4-SB-16-2.5		0802				2										CG-34-2.5
5	GOC4-SB-17-2.5		0823				2										
6	GOC4-SB-18-2.5		0834				2										
7	GOC4-SB-19-0.5		0843				1				X	X					CG-35-0.5
8	GOC4-SB-20-0.5	↓	0850	↓	↓	↓	1	↓	↓		X	X					
9	GOC4-SB-21-0.5	2/18/26	0902	S	G	0	1	80z	PCI		X	X					
10																	

	Signature	Print Name	Company / Title	Date / Time
[1] Relinquished By:		Portia Ibarra	TEL / GMI	2/18/26 / 1650
[1] Received By:		GEMA O	EA	2-18-26 1630
[2] Relinquished By:		GEMA O.	EA	2-18-26 / 1735
[2] Received By:		Lee Bl	enth	2-18-26 1810
[3] Relinquished By:		Lee Bl	enth	

Rec'd Anna Roberts EA 2-18-26 18:10

ENTHALPY ANALYTICAL

Chain of Custody Record

Lab No:

Page: 2 of 7

Turn Around Time (rush by advanced notice only)

Standard:	X	5 Day:		3 Day:	
2 Day:		1 Day:		Custom TAT	

Enthalpy Analytical - Orange
931 W. Barkley Avenue, Orange, CA 92868
Phone 714-771-6900

Matrix: **A** = Air **S** = Soil/Solid **W** = Water **DW** = Drinking Water **P** = Product **O** = Oil **SD** = Sediment **T** = Tissue **WP** = Wipe **WW** = Wastewater **X** = Other

Sample Type: **C** = Composite **G** = Grab or Discrete **B** = Blank **O** = Other

Preservatives: **0** = none **1** = $Na_2S_2O_3$ **2** = HCl **3** = HNO_3 **4** = H_2SO_4 **5** = NaOH **6** = Other

Sample Receipt Temp and Notes: (lab use only)

CUSTOMER INFORMATION		PROJECT INFORMATION	
Company:	Terraphase Engineering Inc.	Name:	Centennial High School
Report To:	Vanya Keyes	Number:	
Email:	vanya.keyes@terraphase.com	P.O. #:	0215.002.002
Address:	18401 Von Karman Ave	Address:	2606 N Central Ave
			Compton, CA, 90222
Phone:	949-377-2227	Global ID:	
Fax:		Sampled By:	Portia C. Ibarra

Analysis Request

Test Instructions / Comments

IR-15
Temp 2.3 +0.4

Please also send report to
clare.steedman@terraphase.com
portia.ibarra@terraphase.com

	Sample ID	Sampling Date	Sampling Time (24 hr)	Matrix	Sample Type	Pres.	Cont. No.	Cont. Size	Initials	Arsenic (6020)	Lead (6010B)	PCBs (8082)	Title 22 Metals (6020/7471A)	Dioxins & Furins (8290A)	VOCs (8260B)	TPH (8015)	
10	1 GOCY-SB-19-2.5	2/18/26	0847	S	G	0	1	80z	PCI								}
11	2 GOCY-SB-20-2.5		0858														} CG-35-2.5
12	3 GOCY-SB-21-2.5		0908														
13	4 GOCY-SB-22-0.5		0914								X	X					}
14	5 GOCY-SB-23-0.5		0927								X	X					} CG-36-0.5
15	6 GOCY-SB-24-0.5		0951								X	X					}
16	7 GOCY-SB-22-2.5		0920														}
17	8 GOCY-SB-23-2.5		0936														} CG-36-2.5
18	9 GOCY-SB-24-2.5	2/18/26	1000	S	G	0	1	80z	PCI								}
	10																

	Signature	Print Name	Company / Title	Date / Time
[1] Relinquished By:		Portia Ibarra	TEI / GOCY	2/18/26 / 1630
[1] Received By:		Gema C.	EANT	2-18-26 1630
[2] Relinquished By:		GEMA	EANT	2-18-26
[2] Received By:		Leo Burks	EANT	2-18-26/1725
[3] Relinquished By:		Leo Burks	EANT	2-18-26/1810

Rec'd Anna Roberts EA 2-18-26 18:10

ENTHALPY ANALYTICAL

Chain of Custody Record

Lab No:

Page: 3 of 7

Turn Around Time (rush by advanced notice only)

Standard:	X	5 Day:		3 Day:	
2 Day:		1 Day:		Custom TAT	

Enthalpy Analytical - Orange

931 W. Barkley Avenue, Orange, CA 92868

Phone 714-771-6900

Matrix: **A** = Air **S** = Soil/Solid **W** = Water **DW** = Drinking Water **P** = Product **O** = Oil **SD** = Sediment **T** = Tissue **WP** = Wipe **WW** = Wastewater **X** = Other

Sample Type: **C** = Composite **G** = Grab or Discrete **B** = Blank **O** = Other

Preservatives: **0** = none **1** = $Na_2S_2O_3$ **2** = HCl **3** = HNO_3 **4** = H_2SO_4 **5** = NaOH **6** = Other

Sample Receipt Temp and Notes: (lab use only)

CUSTOMER INFORMATION		PROJECT INFORMATION	
Company:	Terraphase Engineering Inc.	Name:	Centennial High School
Report To:	Vanya Keyes	Number:	
Email:	vanya.keyes@terraphase.com	P.O. #:	0215.002.002
Address:	18401 Von Karman Ave	Address:	2606 N Central Ave
			Compton, CA, 90222
Phone:	949-377-2227	Global ID:	
Fax:		Sampled By:	Portia C. Ibarra

Analysis Request

Test Instructions / Comments

IR-15
Temp 2.3°C/+0.4

Please also send report to
clare.steedman@terraphase.com
portia.ibarra@terraphase.com

	Sample ID	Sampling Date	Sampling Time (24 hr)	Matrix	Sample Type	Pres.	Cont. No.	Cont. Size	Initials	OCPs by USEPA 8081A	Asbestos by PLM
19	1 CG-34-0.5									X	X
20	2 CG-34-2.5									X	X
21	3 CG-35-0.5									X	X
22	4 CG-35-2.5									X	X
23	5 CG-36-0.5									X	X
24	6 CG-36-2.5									X	X
25	7 CG-39-0.5									X	X
26	8 CG-39-2.5									X	X
27	9 CG-33-0.5									X	X
28	10 CG-33-2.5									X	X

	Signature	Print Name	Company / Title	Date / Time
[1] Relinquished By:		[illegible]	TPI / GeoT	2/18/26 / 1630
[1] Received By:		GEMPAC	EARTH	2-18-26 16:30
[2] Relinquished By:		GEMPAC	EARTH	2-18-26
[2] Received By:		Leo B	earth	2-18-26 1815
[3] Relinquished By:		Leo B	earth	2-18-26 1810

Rec: Anna Roberts EA 2-18-26 18:10

ENTHALPY ANALYTICAL

Chain of Custody Record

Lab No:

Page: 4 of 7

Turn Around Time (rush by advanced notice only)

Standard:	X	5 Day:		3 Day:	
2 Day:		1 Day:		Custom TAT	

Enthalpy Analytical - Orange
931 W. Barkley Avenue, Orange, CA 92868
Phone 714-771-6900

Matrix: A = Air, S = Soil/Solid, W = Water, DW = Drinking Water, P = Product, O = Oil, SD = Sediment, T = Tissue, WP = Wipe, WW = Wastewater, X = Other

Sample Type: C = Composite, G = Grab or Discrete, B = Blank, O = Other

Preservatives: 0 = none, 1 = $Na_2S_2O_3$, 2 = HCl, 3 = HNO_3, 4 = H_2SO_4, 5 = NaOH, 6 = Other

Sample Receipt Temp and Notes: (lab use only)

CUSTOMER INFORMATION		PROJECT INFORMATION	
Company:	Terraphase Engineering Inc.	Name:	Centennial High School
Report To:	Vanya Keyes	Number:	
Email:	vanya.keyes@terraphase.com	P.O. #:	0215.002.002
Address:	18401 Von Karman Ave	Address:	2606 N Central Ave
			Compton, CA, 90222
Phone:	949-377-2227	Global ID:	
Fax:		Sampled By:	Portia C. Ibarra

Test Instructions / Comments

IR-15
Temp 2.3/4.0/4.1

Please also send report to
clare.steedman@terraphase.com
portia.ibarra@terraphase.com

	#	Sample ID	Sampling Date	Sampling Time (24 hr)	Matrix	Sample Type	Pres.	Cont. No.	Cont. Size	Initials	Arsenic (6020)	Lead (6010B)	PCBs (8082)	Title 22 Metals (6020/7471A)	Dioxins & Furins (8290A)	VOCs (8260B)	TPH (8015)	
29	1	AOC4-SB-31-0.5	2/18/26	1018	S	G	0	8oz	1	PCI		X	X					CG-39-0.5
30	2	AOC4-SB-32-0.5		1037								X	X					
31	3	AOC4-SB-33-0.5		1121								X	X					
32	4	AOC4-SB-31-2.5		1025														CG-39-2.5
33	5	AOC4-SB-32-2.5		1043														
34	6	AOC4-SB-33-2.5		1127														
35	7	AOC4-SB-13-0.5		1204								X	X					
36	8	AOC4-SB-14-0.5		1344								X	X					CG-33-0.5
37	9	AOC4-SB-15-0.5	2/18/26	1406	S	G	0	8oz	1	PCI		X	X					
	10																	

	Signature	Print Name	Company / Title	Date / Time
1 Relinquished By:		Portia Ibarra	TPI / QM	2/18/26 / 1630
1 Received By:		Gema O	EA/NT	2-18-26 1630
2 Relinquished By:		Gema O	EA/NT	2-18-26
2 Received By:		Leo Barkley	enthalpy	2-18-26 / 1725
3 Relinquished By:		Leo Barkley	enthalpy	2-18-26 / 1810

Rec'd Anna Roberts EA 2-18-26 1810

ENTHALPY ANALYTICAL

Chain of Custody Record

Lab No:

Page: 5 of 7

Turn Around Time (rush by advanced notice only)

Standard:	X	5 Day:		3 Day:	
2 Day:		1 Day:		Custom TAT	

Enthalpy Analytical - Orange
931 W. Barkley Avenue, Orange, CA 92868
Phone 714-771-6900

Matrix: **A** = Air **S** = Soil/Solid **W** = Water **DW** = Drinking Water **P** = Product **O** = Oil **SD** = Sediment **T** = Tissue **WP** = Wipe **WW** = Wastewater **X** = Other

Sample Type: **C** = Composite **G** = Grab or Discrete **B** = Blank **O** = Other

Preservatives: **0** = none **1** = $Na_2S_2O_3$ **2** = HCl **3** = HNO_3 **4** = H_2SO_4 **5** = NaOH **6** = Other

Sample Receipt Temp and Notes: (lab use only)

CUSTOMER INFORMATION		PROJECT INFORMATION	
Company:	Terraphase Engineering Inc.	Name:	Centennial High School
Report To:	Vanya Keyes	Number:	
Email:	vanya.keyes@terraphase.com	P.O. #:	0215.002.002
Address:	18401 Von Karman Ave	Address:	2606 N Central Ave
			Compton, CA, 90222
Phone:	949-377-2227	Global ID:	
Fax:		Sampled By:	Portia C. Ibarra

Test Instructions / Comments

IR-15c
Temp 2.3±0.4

Please also send report to
clare.steedman@terraphase.com
portia.ibarra@terraphase.com

	Sample ID	Sampling Date	Sampling Time (24 hr)	Matrix	Sample Type	Pres.	Cont. No.	Cont. Size	Initials	Arsenic (6020)	Lead (6010B)	PCBs (8082)	Title 22 Metals (6020/7471A)	Dioxins & Furins (8290A)	VOCs (8260B)	TPH (8015)	
38	1 GOCY-SB-13-2.5	2/18/26	1207	S	G	0	8oz	1	PCI								
39	2 GOCY-SB-14-2.5		1355														
40	3 GOCY-SB-15-2.5		1412														
41	4 GOCY-SB-25-0.5		1434								X	X					
42	5 GOCY-SB-26-0.5		1454								X	X					
43	6 GOCY-SB 27-0.5		1514								X	X					
44	7 DUP-01-0.5-260218	2/18/26	—	S	G	0	8oz	1	PCI		X	X					
	8																
	9																
	10																

CG-33-2.5

CG-37-0.5

	Signature	Print Name	Company / Title	Date / Time
1 Relinquished By:		Portia Ibarra	TEI / GA	2/18/26 / 1850
1 Received By:		GEMA O	EARTH	2-18-26 16:30
2 Relinquished By:		GEMA O.	EARTH	2-18-26
2 Received By:		Leo Baltz	earth	2-18-26/1925
3 Relinquished By:		Leo Baltz	earth	2-18-26/1810

Rec'd Anna Roberts EA 2-18-26 1810

ENTHALPY ANALYTICAL

Chain of Custody Record

Lab No:

Page: 6 of 7

Turn Around Time (rush by advanced notice only)

Standard:	X	5 Day:		3 Day:	
2 Day:		1 Day:		Custom TAT	

Enthalpy Analytical - Orange
931 W. Barkley Avenue, Orange, CA 92868
Phone 714-771-6900

Matrix: **A** = Air **S** = Soil/Solid **W** = Water **DW** = Drinking Water **P** = Product **O** = Oil **SD** = Sediment **T** = Tissue **WP** = Wipe **WW** = Wastewater **X** = Other

Sample Type: **C** = Composite **G** = Grab or Discrete **B** = Blank **O** = Other

Preservatives: **0** = none **1** = $Na_2S_2O_3$ **2** = HCl **3** = HNO_3 **4** = H_2SO_4 **5** = NaOH **6** = Other

Sample Receipt Temp and Notes: (lab use only)

CUSTOMER INFORMATION		PROJECT INFORMATION	
Company:	Terraphase Engineering Inc.	Name:	Centennial High School
Report To:	Vanya Keyes	Number:	
Email:	vanya.keyes@terraphase.com	P.O. #:	0215.002.002
Address:	18401 Von Karman Ave	Address:	2606 N Central Ave
			Compton, CA, 90222
Phone:	949-377-2227	Global ID:	
Fax:		Sampled By:	Portia C. Ibarra

Test Instructions / Comments

IR-15
Tcp 2.3/40-4

Please also send report to
clare.steedman@terraphase.com
portia.ibarra@terraphase.com

	Sample ID	Sampling Date	Sampling Time (24 hr)	Matrix	Sample Type	Pres.	Cont. No.	Cont. Size	Initials	Arsenic (6020)	Lead (6010B)	PCBs (8082)	Title 22 Metals (6020/7471A)	Dioxins & Furins (8290A)	VOCs (8260B)	TPH (8015)	
45	1 AOC4-SB-25-2.5	2/18/26	1439	S	G	0	802	1	PCL	P			P				
46	2 AOC4-SB-26-2.5	↓	1457	↓	↓	↓	↓	↓	↓								
47	3 AOC4-SB-27-2.5	↓	1523	↓	↓	↓	↓	↓	↓								
48	4 DUP-01-2.5-260218	2/18/26	—	S	G	0	802	1	PCL								
	5 ~~EB-01~~ P1																
	6																
	7																
	8																
	9																
	10																

	Signature	Print Name	Company / Title	Date / Time
1 Relinquished By:		Portia Ibarra	TER / GOOL	2/18/26 1630
1 Received By:		Gema O	ENTH	218-26 1630
2 Relinquished By:		Gema O	ENTH	2-18-26
2 Received By:		Lee Burks	enth	2-18-26 1725
3 Relinquished By:		Lee Burks	enth	2-18-26 1810

Rec'd Anna Roberts EA 2-18-26 18:10

17 of 70

ENTHALPY ANALYTICAL

Chain of Custody Record

Lab No:

Page: 7 of 7

Turn Around Time (rush by advanced notice only)

Standard:	X	5 Day:		3 Day:	
2 Day:		1 Day:		Custom TAT	

Enthalpy Analytical - Orange

931 W. Barkley Avenue, Orange, CA 92868

Phone 714-771-6900

Matrix: **A** = Air **S** = Soil/Solid **W** = Water **DW** = Drinking Water **P** = Product **O** = Oil **SD** = Sediment **T** = Tissue **WP** = Wipe **WW** = Wastewater **X** = Other

Sample Type: **C** = Composite **G** = Grab or Discrete **B** = Blank **O** = Other

Preservatives: **0** = none **1** = $Na_2S_2O_3$ **2** = HCl **3** = HNO_3 **4** = H_2SO_4 **5** = NaOH **6** = Other

Sample Receipt Temp and Notes: (lab use only)

CUSTOMER INFORMATION		PROJECT INFORMATION	
Company:	Terraphase Engineering Inc.	Name:	Centennial High School
Report To:	Vanya Keyes	Number:	
Email:	vanya.keyes@terraphase.com	P.O. #:	0215.002.002
Address:	18401 Von Karman Ave	Address:	2606 N Central Ave
			Compton, CA, 90222
Phone:	949-377-2227	Global ID:	
Fax:		Sampled By:	Portia C. Ibarra

Test Instructions / Comments

IR-15
Temp 2.3°C/4 of 4

Please also send report to
clare.steedman@terraphase.com
portia.ibarra@terraphase.com

	Sample ID	Sampling Date	Sampling Time (24 hr)	Matrix	Sample Type	Pres.	Cont. No.	Cont. Size	Initials	OCPs by USEPA 8081A	Asbestos by PLM	Lead 6010B	PCBs (8082)					
49	1 CG-37-0.5									X	X							Page 5
50	2 CG-37-2.5									X	X							page 6
51	3 EB-01-260218	2/18/26	1600	W	G	3	3	1 L amb 1 poly	PCI	X	X	X	X					
52	4 CG-34-0.5-DUP									X	X							split from CG-34-0.5
53	5 CG-34-2.5-DUP									X	X							split from CG-34-2.5
	6																	
	7																	
	8																	
	9																	
	10																	

	Signature	Print Name	Company / Title	Date / Time
[1] Relinquished By:		PORTIA IBARRA	TEI / CAL	2/18/26 1630
[1] Received By:		GEMA O.	EARTH	2-18-26 1630
[2] Relinquished By:		GEMA O.	EARTH	2-18-26 1725
[2] Received By:		Leo Brady	enth	2-18-26/1725
[3] Relinquished By:		Leo Brady	enth	2-18-26/1810
Rec'd		Anna Roberts	E-A	2.18.26 1810

SAMPLE RECEIPT CHECKLIST

Section 1: General Info

Date Received: 2/18/26 WO# 553642 Client: Terraphase

Section 2: Shipping / Custody **Are custody seals present?** ☐ Yes ☒ No

Custody seals intact on arrival? ■ N/A ☐ Yes ☐ No ☐ On cooler / box ☐ On samples

■ Courier ☐ Walk-In ☐ Field Sampling ☐ Shipping Info: _____

Section 3a: Condition / Packaging ☐ **Outside 0.0 - 6.0°C (0.0 - 10.0°C for microbiology) (PM notified)**

Date Opened 2/18/26 By (initials) LXB Type of ice used: ■ Wet ☐ Blue/Gel ☐ None

☐ Samples received on ice directly from the field; cooling process had begun. (if checked, skip temperatures)

☐ Sample matrix doesn't require cooling (e.g. air, bulk PCB). (if checked, skip temperatures)

If no cooler: Observed/Adjusted Temp (°C): _____ / _____ Thermometer/IR Gun: IR15 CF: +0.4

Cooler Temp (°C) #1: 2.3 / 2.7 #2: ____/____ #3: ____/____ #4: ____/____ #5: ____/____ #6: ____/____

Section 3b: Microbiology Samples ■ **No microbiology samples submitted (skip 3b)**

☐ Within temp range 0.0 - 10.0°C or received on ice directly from field.

☐ Adequate headspace for microbiology analysis.

Section 3c: Air Samples ■ **No air samples submitted (skip 3c)**

☐ 1.4L Canisters ☐ 6L Canisters ☐ Tedlar Bags ☐ MCE Cassettes ☐ Sorbent Tubes ☐ Other _____

Section 4: Containers / Labels / Samples	YES	NO	N/A
1) Were custody papers present, filled properly, and legible?	X		
2) Is the sampler's name present on the CoC?	X		
3) Were containers received in good condition (unbroken / unopened / uncompromised)?	X		
4) Were the samples bagged? (required for microbiology samples; recommended for soil samples)	X		
5) Were all of, and only, the correct samples received?	X		
6) Are sample labels present, legible, and in agreement with the CoC?	X		
7) Does the container count match the CoC?	X		
8) Was sufficient sample volume / mass received for the analyses requested?	X		
9) Were samples received in proper containers for the analyses requested?	X		
10) Were samples received with > 1/2 holding time remaining?	X		
11) Are samples properly preserved as indicated by CoC / labels?	X		
12) Unpreserved VOAs received - If necessary, was the hold time changed in LIMS?			X
13) Are VOA vials free from headspace/bubbles > 6mm?			X

Section 5: Explanations / Comments

(If no comments are made, then no discrepancies noted.)

☐ **No additional discrepancies**

Date Logged 2/18/26 **By (print)** ABD **(sign)** ADW

Date Labeled 2/18/26 **By (print)** AGR **(sign)** ADW for AGR

Outlook

RE: [External] - RE: Analysis of deeper samples requested for Centennial

From Vanya Keyes <vanya.keyes@terraphase.com>
Date Fri 3/6/2026 11:42 AM
To Patricia Mata <patty.mata@enthalpy.com>
Cc Clare Steedman <clare.steedman@terraphase.com>

EXTERNAL EMAIL - This email was sent by a person from outside your organization. Exercise caution when clicking links, opening attachments or taking further action, before validating its authenticity.

Hi Patty,
Looking at the latest batch of data you just sent us, I'd like to add these additional samples to be analyzed:

- PCBs
  - AOC4-SB-16-2.5
  - AOC4-SB-31-2.5

Thank you!

Vanya Keyes
Senior Project Geologist
(949) 990-0182

From: Clare Steedman <clare.steedman@terraphase.com>
Sent: Tuesday, March 3, 2026 10:39 AM
To: Patricia Mata <patty.mata@enthalpy.com>; Vanya Keyes <vanya.keyes@terraphase.com>
Subject: RE: [External] - RE: Analysis of deeper samples requested for Centennial

Hi Patty, yes, please proceed with the two PCB analyses for samples past hold time.

Clare Steedman, P.G.
Cell: 213.422.5850
clare.steedman@terraphase.com
terraphase engineering

From: Patricia Mata <patty.mata@enthalpy.com>
Sent: Tuesday, March 3, 2026 10:22 AM
To: Clare Steedman <clare.steedman@terraphase.com>; Vanya Keyes <vanya.keyes@terraphase.com>
Subject: Re: [External] - RE: Analysis of deeper samples requested for Centennial

Clare,

Thank you for the extra information. I see that one PCB sample was collected on 2/10/26 & the other sample was collected on 2/13/26 so both are past hold time already. Are we OK to do the extraction & analysis past the hold time for PCBs?

ENTHALPY ANALYTICAL

Analysis Results for 553642

Vanya Keyes
Terraphase Engineering
18401 Von Karman Ave, Suite #410
Irvine, CA 92612

Lab Job #: 553642
Project No: CENTENNIAL HS
Location: Centennial High School, 2606 N Central Ave., Compton, CA 90222
Date Received: 02/18/26

Sample ID: AOC4-SB-16-0.5 **Lab ID: 553642-001** **Collected: 02/18/26 07:46**
Matrix: Soil

553642-001 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3050B									
Lead	**48**		mg/Kg	0.99	0.99	395889	02/20/26	02/20/26	SBW
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	49	0.98	396118	02/23/26	02/24/26	MES
Aroclor-1221	ND		ug/Kg	49	0.98	396118	02/23/26	02/24/26	MES
Aroclor-1232	ND		ug/Kg	49	0.98	396118	02/23/26	02/24/26	MES
Aroclor-1242	ND		ug/Kg	49	0.98	396118	02/23/26	02/24/26	MES
Aroclor-1248	ND		ug/Kg	49	0.98	396118	02/23/26	02/24/26	MES
Aroclor-1254	**3,700**		ug/Kg	250	4.9	396118	02/23/26	02/24/26	MES
Aroclor-1260	**1,700**		ug/Kg	250	4.9	396118	02/23/26	02/24/26	MES
Aroclor-1262	ND		ug/Kg	49	0.98	396118	02/23/26	02/24/26	MES
Aroclor-1268	ND		ug/Kg	49	0.98	396118	02/23/26	02/24/26	MES
Total PCBs	**5,400**		ug/Kg	49	0.98	396118	02/23/26	02/24/26	MES
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	121%		%REC	50-127	0.98	396118	02/23/26	02/24/26	MES

Sample ID: AOC4-SB-17-0.5 **Lab ID: 553642-002** **Collected: 02/18/26 08:12**
Matrix: Soil

553642-002 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3050B									
Lead	**36**		mg/Kg	0.95	0.95	395889	02/20/26	02/20/26	SBW
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Aroclor-1221	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Aroclor-1232	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Aroclor-1242	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Aroclor-1248	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Aroclor-1254	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Aroclor-1260	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Aroclor-1262	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Aroclor-1268	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Total PCBs	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	113%		%REC	50-127	1	396118	02/23/26	02/24/26	MES

Results for any subcontracted analyses are not included in this section.

Analysis Results for 553642

Sample ID: AOC4-SB-18-0.5	Lab ID: 553642-003	Collected: 02/18/26 08:30
	Matrix: Soil	

553642-003 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3050B									
Lead	**70**		mg/Kg	1.0	1	395889	02/20/26	02/20/26	SBW
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Aroclor-1221	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Aroclor-1232	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Aroclor-1242	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Aroclor-1248	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Aroclor-1254	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Aroclor-1260	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Aroclor-1262	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Aroclor-1268	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Total PCBs	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	101%		%REC	50-127	1	396118	02/23/26	02/24/26	MES

Sample ID: AOC4-SB-16-2.5	Lab ID: 553642-004	Collected: 02/18/26 08:02
	Matrix: Soil	

553642-004 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND	H	ug/Kg	50	1	397475	03/09/26	03/11/26	KMB
Aroclor-1221	ND	H	ug/Kg	50	1	397475	03/09/26	03/11/26	KMB
Aroclor-1232	ND	H	ug/Kg	50	1	397475	03/09/26	03/11/26	KMB
Aroclor-1242	ND	H	ug/Kg	50	1	397475	03/09/26	03/11/26	KMB
Aroclor-1248	ND	H	ug/Kg	50	1	397475	03/09/26	03/11/26	KMB
Aroclor-1254	ND	H	ug/Kg	50	1	397475	03/09/26	03/11/26	KMB
Aroclor-1260	ND	H	ug/Kg	50	1	397475	03/09/26	03/11/26	KMB
Aroclor-1262	ND	H	ug/Kg	50	1	397475	03/09/26	03/11/26	KMB
Aroclor-1268	ND	H	ug/Kg	50	1	397475	03/09/26	03/11/26	KMB
Total PCBs	ND		ug/Kg	50	1	397475	03/09/26	03/11/26	KMB
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	78%	H	%REC	50-127	1	397475	03/09/26	03/11/26	KMB

Results for any subcontracted analyses are not included in this section.

Analysis Results for 553642

Sample ID: AOC4-SB-19-0.5 **Lab ID: 553642-007** **Collected: 02/18/26 08:43**
Matrix: Soil

553642-007 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3050B									
Lead	**44**		mg/Kg	0.97	0.97	395889	02/20/26	02/20/26	SBW
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Aroclor-1221	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Aroclor-1232	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Aroclor-1242	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Aroclor-1248	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Aroclor-1254	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Aroclor-1260	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Aroclor-1262	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Aroclor-1268	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Total PCBs	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	116%		%REC	50-127	1	396118	02/23/26	02/24/26	MES

Sample ID: AOC4-SB-20-0.5 **Lab ID: 553642-008** **Collected: 02/18/26 08:50**
Matrix: Soil

553642-008 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3050B									
Lead	**42**		mg/Kg	0.98	0.98	395889	02/20/26	02/20/26	SBW
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	50	0.99	396118	02/23/26	02/24/26	MES
Aroclor-1221	ND		ug/Kg	50	0.99	396118	02/23/26	02/24/26	MES
Aroclor-1232	ND		ug/Kg	50	0.99	396118	02/23/26	02/24/26	MES
Aroclor-1242	ND		ug/Kg	50	0.99	396118	02/23/26	02/24/26	MES
Aroclor-1248	ND		ug/Kg	50	0.99	396118	02/23/26	02/24/26	MES
Aroclor-1254	ND		ug/Kg	50	0.99	396118	02/23/26	02/24/26	MES
Aroclor-1260	ND		ug/Kg	50	0.99	396118	02/23/26	02/24/26	MES
Aroclor-1262	ND		ug/Kg	50	0.99	396118	02/23/26	02/24/26	MES
Aroclor-1268	ND		ug/Kg	50	0.99	396118	02/23/26	02/24/26	MES
Total PCBs	ND		ug/Kg	50	0.99	396118	02/23/26	02/24/26	MES
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	123%		%REC	50-127	0.99	396118	02/23/26	02/24/26	MES

Results for any subcontracted analyses are not included in this section.

Analysis Results for 553642

Sample ID: AOC4-SB-21-0.5 **Lab ID: 553642-009** **Collected: 02/18/26 09:02**
Matrix: Soil

553642-009 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3050B									
Lead	**35**		mg/Kg	0.97	0.97	395889	02/20/26	02/20/26	SBW
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Aroclor-1221	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Aroclor-1232	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Aroclor-1242	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Aroclor-1248	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Aroclor-1254	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Aroclor-1260	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Aroclor-1262	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Aroclor-1268	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Total PCBs	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	113%		%REC	50-127	1	396118	02/23/26	02/24/26	MES

Sample ID: AOC4-SB-22-0.5 **Lab ID: 553642-013** **Collected: 02/18/26 09:14**
Matrix: Soil

553642-013 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3050B									
Lead	**45**		mg/Kg	0.96	0.96	395889	02/20/26	02/20/26	SBW
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	50	1	396118	02/23/26	02/24/26	MES
Aroclor-1221	ND		ug/Kg	50	1	396118	02/23/26	02/24/26	MES
Aroclor-1232	ND		ug/Kg	50	1	396118	02/23/26	02/24/26	MES
Aroclor-1242	ND		ug/Kg	50	1	396118	02/23/26	02/24/26	MES
Aroclor-1248	ND		ug/Kg	50	1	396118	02/23/26	02/24/26	MES
Aroclor-1254	ND		ug/Kg	50	1	396118	02/23/26	02/24/26	MES
Aroclor-1260	ND		ug/Kg	50	1	396118	02/23/26	02/24/26	MES
Aroclor-1262	ND		ug/Kg	50	1	396118	02/23/26	02/24/26	MES
Aroclor-1268	ND		ug/Kg	50	1	396118	02/23/26	02/24/26	MES
Total PCBs	ND		ug/Kg	50	1	396118	02/23/26	02/24/26	MES
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	105%		%REC	50-127	1	396118	02/23/26	02/24/26	MES

Results for any subcontracted analyses are not included in this section.

Analysis Results for 553642

Sample ID: AOC4-SB-23-0.5 **Lab ID: 553642-014** **Collected: 02/18/26 09:27**
Matrix: Soil

553642-014 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3050B									
Lead	**18**		mg/Kg	0.97	0.97	395889	02/20/26	02/20/26	SBW
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Aroclor-1221	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Aroclor-1232	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Aroclor-1242	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Aroclor-1248	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Aroclor-1254	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Aroclor-1260	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Aroclor-1262	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Aroclor-1268	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Total PCBs	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	130%	*	%REC	50-127	1	396118	02/23/26	02/24/26	MES

Sample ID: AOC4-SB-24-0.5 **Lab ID: 553642-015** **Collected: 02/18/26 09:51**
Matrix: Soil

553642-015 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3050B									
Lead	**28**		mg/Kg	0.97	0.97	395889	02/20/26	02/20/26	SBW
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	50	1	396118	02/23/26	02/24/26	MES
Aroclor-1221	ND		ug/Kg	50	1	396118	02/23/26	02/24/26	MES
Aroclor-1232	ND		ug/Kg	50	1	396118	02/23/26	02/24/26	MES
Aroclor-1242	ND		ug/Kg	50	1	396118	02/23/26	02/24/26	MES
Aroclor-1248	ND		ug/Kg	50	1	396118	02/23/26	02/24/26	MES
Aroclor-1254	ND		ug/Kg	50	1	396118	02/23/26	02/24/26	MES
Aroclor-1260	ND		ug/Kg	50	1	396118	02/23/26	02/24/26	MES
Aroclor-1262	ND		ug/Kg	50	1	396118	02/23/26	02/24/26	MES
Aroclor-1268	ND		ug/Kg	50	1	396118	02/23/26	02/24/26	MES
Total PCBs	ND		ug/Kg	50	1	396118	02/23/26	02/24/26	MES
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	124%		%REC	50-127	1	396118	02/23/26	02/24/26	MES

Results for any subcontracted analyses are not included in this section.

ENTHALPY ANALYTICAL

Analysis Results for 553642

Sample ID: CG-34-0.5	Lab ID: 553642-019	Collected: 02/18/26
	Matrix: Soil	

553642-019 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 8081A Prep Method: EPA 3546									
alpha-BHC	ND		ug/Kg	5.1	1	396196	02/24/26	02/24/26	XLY
beta-BHC	ND		ug/Kg	5.1	1	396196	02/24/26	02/24/26	XLY
gamma-BHC	ND		ug/Kg	5.1	1	396196	02/24/26	02/24/26	XLY
delta-BHC	ND		ug/Kg	5.1	1	396196	02/24/26	02/24/26	XLY
Heptachlor	ND		ug/Kg	5.1	1	396196	02/24/26	02/24/26	XLY
Aldrin	ND		ug/Kg	5.1	1	396196	02/24/26	02/24/26	XLY
Heptachlor epoxide	ND		ug/Kg	5.1	1	396196	02/24/26	02/24/26	XLY
Endosulfan I	ND		ug/Kg	5.1	1	396196	02/24/26	02/24/26	XLY
Dieldrin	**9.3**	C	ug/Kg	5.1	1	396196	02/24/26	02/24/26	XLY
4,4'-DDE	**6.9**	C	ug/Kg	5.1	1	396196	02/24/26	02/24/26	XLY
Endrin	ND		ug/Kg	5.1	1	396196	02/24/26	02/24/26	XLY
Endosulfan II	ND		ug/Kg	5.1	1	396196	02/24/26	02/24/26	XLY
Endosulfan sulfate	ND		ug/Kg	5.1	1	396196	02/24/26	02/24/26	XLY
4,4'-DDD	ND		ug/Kg	5.1	1	396196	02/24/26	02/24/26	XLY
Endrin aldehyde	ND		ug/Kg	5.1	1	396196	02/24/26	02/24/26	XLY
Endrin ketone	ND		ug/Kg	5.1	1	396196	02/24/26	02/24/26	XLY
4,4'-DDT	**17**	C	ug/Kg	5.1	1	396196	02/24/26	02/24/26	XLY
Methoxychlor	ND		ug/Kg	10	1	396196	02/24/26	02/24/26	XLY
Toxaphene	ND		ug/Kg	100	1	396196	02/24/26	02/24/26	XLY
Chlordane (Technical)	ND		ug/Kg	51	1	396196	02/24/26	02/24/26	XLY
Surrogates				**Limits**					
TCMX	74%		%REC	58-120	1	396196	02/24/26	02/24/26	XLY
Decachlorobiphenyl	83%		%REC	47-120	1	396196	02/24/26	02/24/26	XLY

Results for any subcontracted analyses are not included in this section.

Analysis Results for 553642

Sample ID: CG-34-2.5	Lab ID: 553642-020	Collected: 02/18/26
	Matrix: Soil	

553642-020 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 8081A Prep Method: EPA 3546									
alpha-BHC	ND		ug/Kg	5.0	1	396196	02/24/26	02/24/26	KLR
beta-BHC	ND		ug/Kg	5.0	1	396196	02/24/26	02/24/26	KLR
gamma-BHC	ND		ug/Kg	5.0	1	396196	02/24/26	02/24/26	KLR
delta-BHC	ND		ug/Kg	5.0	1	396196	02/24/26	02/24/26	KLR
Heptachlor	ND		ug/Kg	5.0	1	396196	02/24/26	02/24/26	KLR
Aldrin	ND		ug/Kg	5.0	1	396196	02/24/26	02/24/26	KLR
Heptachlor epoxide	ND		ug/Kg	5.0	1	396196	02/24/26	02/24/26	KLR
Endosulfan I	ND		ug/Kg	5.0	1	396196	02/24/26	02/24/26	KLR
Dieldrin	ND		ug/Kg	5.0	1	396196	02/24/26	02/24/26	KLR
4,4'-DDE	ND		ug/Kg	5.0	1	396196	02/24/26	02/24/26	KLR
Endrin	ND		ug/Kg	5.0	1	396196	02/24/26	02/24/26	KLR
Endosulfan II	ND		ug/Kg	5.0	1	396196	02/24/26	02/24/26	KLR
Endosulfan sulfate	ND		ug/Kg	5.0	1	396196	02/24/26	02/24/26	KLR
4,4'-DDD	ND		ug/Kg	5.0	1	396196	02/24/26	02/24/26	KLR
Endrin aldehyde	ND		ug/Kg	5.0	1	396196	02/24/26	02/24/26	KLR
Endrin ketone	ND		ug/Kg	5.0	1	396196	02/24/26	02/24/26	KLR
4,4'-DDT	ND		ug/Kg	5.0	1	396196	02/24/26	02/24/26	KLR
Methoxychlor	ND		ug/Kg	10	1	396196	02/24/26	02/24/26	KLR
Toxaphene	ND		ug/Kg	100	1	396196	02/24/26	02/24/26	KLR
Chlordane (Technical)	ND		ug/Kg	50	1	396196	02/24/26	02/24/26	KLR
Surrogates				**Limits**					
TCMX	83%		%REC	58-120	1	396196	02/24/26	02/24/26	KLR
Decachlorobiphenyl	83%		%REC	47-120	1	396196	02/24/26	02/24/26	KLR

Results for any subcontracted analyses are not included in this section.

ENTHALPY ANALYTICAL

Analysis Results for 553642

Sample ID: CG-35-0.5	Lab ID: 553642-021	Collected: 02/18/26
	Matrix: Soil	

553642-021 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 8081A Prep Method: EPA 3546									
alpha-BHC	ND		ug/Kg	5.1	1	396196	02/24/26	02/24/26	KLR
beta-BHC	ND		ug/Kg	5.1	1	396196	02/24/26	02/24/26	KLR
gamma-BHC	ND		ug/Kg	5.1	1	396196	02/24/26	02/24/26	KLR
delta-BHC	ND		ug/Kg	5.1	1	396196	02/24/26	02/24/26	KLR
Heptachlor	ND		ug/Kg	5.1	1	396196	02/24/26	02/24/26	KLR
Aldrin	ND		ug/Kg	5.1	1	396196	02/24/26	02/24/26	KLR
Heptachlor epoxide	ND		ug/Kg	5.1	1	396196	02/24/26	02/24/26	KLR
Endosulfan I	ND		ug/Kg	5.1	1	396196	02/24/26	02/24/26	KLR
Dieldrin	ND		ug/Kg	5.1	1	396196	02/24/26	02/24/26	KLR
4,4'-DDE	ND		ug/Kg	5.1	1	396196	02/24/26	02/24/26	KLR
Endrin	ND		ug/Kg	5.1	1	396196	02/24/26	02/24/26	KLR
Endosulfan II	ND		ug/Kg	5.1	1	396196	02/24/26	02/24/26	KLR
Endosulfan sulfate	ND		ug/Kg	5.1	1	396196	02/24/26	02/24/26	KLR
4,4'-DDD	ND		ug/Kg	5.1	1	396196	02/24/26	02/24/26	KLR
Endrin aldehyde	ND		ug/Kg	5.1	1	396196	02/24/26	02/24/26	KLR
Endrin ketone	ND		ug/Kg	5.1	1	396196	02/24/26	02/24/26	KLR
4,4'-DDT	ND		ug/Kg	5.1	1	396196	02/24/26	02/24/26	KLR
Methoxychlor	ND		ug/Kg	10	1	396196	02/24/26	02/24/26	KLR
Toxaphene	ND		ug/Kg	100	1	396196	02/24/26	02/24/26	KLR
Chlordane (Technical)	ND		ug/Kg	51	1	396196	02/24/26	02/24/26	KLR
Surrogates				**Limits**					
TCMX	82%		%REC	58-120	1	396196	02/24/26	02/24/26	KLR
Decachlorobiphenyl	99%		%REC	47-120	1	396196	02/24/26	02/24/26	KLR

Results for any subcontracted analyses are not included in this section.

Analysis Results for 553642

Sample ID: CG-35-2.5	Lab ID: 553642-022	Collected: 02/18/26
	Matrix: Soil	

553642-022 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 8081A Prep Method: EPA 3546									
alpha-BHC	ND		ug/Kg	5.0	0.99	396196	02/24/26	02/24/26	KLR
beta-BHC	ND		ug/Kg	5.0	0.99	396196	02/24/26	02/24/26	KLR
gamma-BHC	ND		ug/Kg	5.0	0.99	396196	02/24/26	02/24/26	KLR
delta-BHC	ND		ug/Kg	5.0	0.99	396196	02/24/26	02/24/26	KLR
Heptachlor	ND		ug/Kg	5.0	0.99	396196	02/24/26	02/24/26	KLR
Aldrin	ND		ug/Kg	5.0	0.99	396196	02/24/26	02/24/26	KLR
Heptachlor epoxide	ND		ug/Kg	5.0	0.99	396196	02/24/26	02/24/26	KLR
Endosulfan I	ND		ug/Kg	5.0	0.99	396196	02/24/26	02/24/26	KLR
Dieldrin	ND		ug/Kg	5.0	0.99	396196	02/24/26	02/24/26	KLR
4,4'-DDE	ND		ug/Kg	5.0	0.99	396196	02/24/26	02/24/26	KLR
Endrin	ND		ug/Kg	5.0	0.99	396196	02/24/26	02/24/26	KLR
Endosulfan II	ND		ug/Kg	5.0	0.99	396196	02/24/26	02/24/26	KLR
Endosulfan sulfate	ND		ug/Kg	5.0	0.99	396196	02/24/26	02/24/26	KLR
4,4'-DDD	ND		ug/Kg	5.0	0.99	396196	02/24/26	02/24/26	KLR
Endrin aldehyde	ND		ug/Kg	5.0	0.99	396196	02/24/26	02/24/26	KLR
Endrin ketone	ND		ug/Kg	5.0	0.99	396196	02/24/26	02/24/26	KLR
4,4'-DDT	ND		ug/Kg	5.0	0.99	396196	02/24/26	02/24/26	KLR
Methoxychlor	ND		ug/Kg	9.9	0.99	396196	02/24/26	02/24/26	KLR
Toxaphene	ND		ug/Kg	99	0.99	396196	02/24/26	02/24/26	KLR
Chlordane (Technical)	ND		ug/Kg	50	0.99	396196	02/24/26	02/24/26	KLR
Surrogates				**Limits**					
TCMX	87%		%REC	58-120	0.99	396196	02/24/26	02/24/26	KLR
Decachlorobiphenyl	98%		%REC	47-120	0.99	396196	02/24/26	02/24/26	KLR

Results for any subcontracted analyses are not included in this section.

ENTHALPY ANALYTICAL

Analysis Results for 553642

Sample ID: CG-36-0.5	Lab ID: 553642-023	Collected: 02/18/26
	Matrix: Soil	

553642-023 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 8081A Prep Method: EPA 3546									
alpha-BHC	ND		ug/Kg	10	2	396196	02/24/26	02/24/26	KLR
beta-BHC	ND		ug/Kg	10	2	396196	02/24/26	02/24/26	KLR
gamma-BHC	ND		ug/Kg	10	2	396196	02/24/26	02/24/26	KLR
delta-BHC	ND		ug/Kg	10	2	396196	02/24/26	02/24/26	KLR
Heptachlor	ND		ug/Kg	10	2	396196	02/24/26	02/24/26	KLR
Aldrin	ND		ug/Kg	10	2	396196	02/24/26	02/24/26	KLR
Heptachlor epoxide	ND		ug/Kg	10	2	396196	02/24/26	02/24/26	KLR
Endosulfan I	ND		ug/Kg	10	2	396196	02/24/26	02/24/26	KLR
Dieldrin	ND		ug/Kg	10	2	396196	02/24/26	02/24/26	KLR
4,4'-DDE	ND		ug/Kg	10	2	396196	02/24/26	02/24/26	KLR
Endrin	ND		ug/Kg	10	2	396196	02/24/26	02/24/26	KLR
Endosulfan II	ND		ug/Kg	10	2	396196	02/24/26	02/24/26	KLR
Endosulfan sulfate	ND		ug/Kg	10	2	396196	02/24/26	02/24/26	KLR
4,4'-DDD	ND		ug/Kg	10	2	396196	02/24/26	02/24/26	KLR
Endrin aldehyde	ND		ug/Kg	10	2	396196	02/24/26	02/24/26	KLR
Endrin ketone	ND		ug/Kg	10	2	396196	02/24/26	02/24/26	KLR
4,4'-DDT	ND		ug/Kg	10	2	396196	02/24/26	02/24/26	KLR
Methoxychlor	ND		ug/Kg	20	2	396196	02/24/26	02/24/26	KLR
Toxaphene	ND		ug/Kg	200	2	396196	02/24/26	02/24/26	KLR
Chlordane (Technical)	ND		ug/Kg	100	2	396196	02/24/26	02/24/26	KLR
Surrogates				**Limits**					
TCMX	80%		%REC	58-120	2	396196	02/24/26	02/24/26	KLR
Decachlorobiphenyl	97%		%REC	47-120	2	396196	02/24/26	02/24/26	KLR

Results for any subcontracted analyses are not included in this section.

ENTHALPY ANALYTICAL

Analysis Results for 553642

Sample ID: CG-36-2.5	Lab ID: 553642-024	Collected: 02/18/26
	Matrix: Soil	

553642-024 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 8081A Prep Method: EPA 3546									
alpha-BHC	ND		ug/Kg	5.0	1	396196	02/24/26	02/24/26	XLY
beta-BHC	ND		ug/Kg	5.0	1	396196	02/24/26	02/24/26	XLY
gamma-BHC	ND		ug/Kg	5.0	1	396196	02/24/26	02/24/26	XLY
delta-BHC	ND		ug/Kg	5.0	1	396196	02/24/26	02/24/26	XLY
Heptachlor	ND		ug/Kg	5.0	1	396196	02/24/26	02/24/26	XLY
Aldrin	ND		ug/Kg	5.0	1	396196	02/24/26	02/24/26	XLY
Heptachlor epoxide	ND		ug/Kg	5.0	1	396196	02/24/26	02/24/26	XLY
Endosulfan I	ND		ug/Kg	5.0	1	396196	02/24/26	02/24/26	XLY
Dieldrin	ND		ug/Kg	5.0	1	396196	02/24/26	02/24/26	XLY
4,4'-DDE	ND		ug/Kg	5.0	1	396196	02/24/26	02/24/26	XLY
Endrin	ND		ug/Kg	5.0	1	396196	02/24/26	02/24/26	XLY
Endosulfan II	ND		ug/Kg	5.0	1	396196	02/24/26	02/24/26	XLY
Endosulfan sulfate	ND		ug/Kg	5.0	1	396196	02/24/26	02/24/26	XLY
4,4'-DDD	ND		ug/Kg	5.0	1	396196	02/24/26	02/24/26	XLY
Endrin aldehyde	ND		ug/Kg	5.0	1	396196	02/24/26	02/24/26	XLY
Endrin ketone	ND		ug/Kg	5.0	1	396196	02/24/26	02/24/26	XLY
4,4'-DDT	ND		ug/Kg	5.0	1	396196	02/24/26	02/24/26	XLY
Methoxychlor	ND		ug/Kg	10	1	396196	02/24/26	02/24/26	XLY
Toxaphene	ND		ug/Kg	100	1	396196	02/24/26	02/24/26	XLY
Chlordane (Technical)	ND		ug/Kg	50	1	396196	02/24/26	02/24/26	XLY
Surrogates				**Limits**					
TCMX	86%		%REC	58-120	1	396196	02/24/26	02/24/26	XLY
Decachlorobiphenyl	93%		%REC	47-120	1	396196	02/24/26	02/24/26	XLY

Results for any subcontracted analyses are not included in this section.

ENTHALPY ANALYTICAL

Analysis Results for 553642

Sample ID: CG-39-0.5	Lab ID: 553642-025	Collected: 02/18/26
	Matrix: Soil	

553642-025 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 8081A Prep Method: EPA 3546									
alpha-BHC	ND		ug/Kg	4.9	0.98	396196	02/24/26	02/24/26	XLY
beta-BHC	ND		ug/Kg	4.9	0.98	396196	02/24/26	02/24/26	XLY
gamma-BHC	ND		ug/Kg	4.9	0.98	396196	02/24/26	02/24/26	XLY
delta-BHC	ND		ug/Kg	4.9	0.98	396196	02/24/26	02/24/26	XLY
Heptachlor	ND		ug/Kg	4.9	0.98	396196	02/24/26	02/24/26	XLY
Aldrin	ND		ug/Kg	4.9	0.98	396196	02/24/26	02/24/26	XLY
Heptachlor epoxide	ND		ug/Kg	4.9	0.98	396196	02/24/26	02/24/26	XLY
Endosulfan I	ND		ug/Kg	4.9	0.98	396196	02/24/26	02/24/26	XLY
Dieldrin	ND		ug/Kg	4.9	0.98	396196	02/24/26	02/24/26	XLY
4,4'-DDE	ND		ug/Kg	4.9	0.98	396196	02/24/26	02/24/26	XLY
Endrin	ND		ug/Kg	4.9	0.98	396196	02/24/26	02/24/26	XLY
Endosulfan II	ND		ug/Kg	4.9	0.98	396196	02/24/26	02/24/26	XLY
Endosulfan sulfate	ND		ug/Kg	4.9	0.98	396196	02/24/26	02/24/26	XLY
4,4'-DDD	ND		ug/Kg	4.9	0.98	396196	02/24/26	02/24/26	XLY
Endrin aldehyde	ND		ug/Kg	4.9	0.98	396196	02/24/26	02/24/26	XLY
Endrin ketone	ND		ug/Kg	4.9	0.98	396196	02/24/26	02/24/26	XLY
4,4'-DDT	ND		ug/Kg	4.9	0.98	396196	02/24/26	02/24/26	XLY
Methoxychlor	ND		ug/Kg	9.8	0.98	396196	02/24/26	02/24/26	XLY
Toxaphene	ND		ug/Kg	98	0.98	396196	02/24/26	02/24/26	XLY
Chlordane (Technical)	ND		ug/Kg	49	0.98	396196	02/24/26	02/24/26	XLY
Surrogates				**Limits**					
TCMX	84%		%REC	58-120	0.98	396196	02/24/26	02/24/26	XLY
Decachlorobiphenyl	89%		%REC	47-120	0.98	396196	02/24/26	02/24/26	XLY

Results for any subcontracted analyses are not included in this section.

ENTHALPY ANALYTICAL

Analysis Results for 553642

Sample ID: CG-39-2.5	Lab ID: 553642-026	Collected: 02/18/26
	Matrix: Soil	

553642-026 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 8081A Prep Method: EPA 3546									
alpha-BHC	ND		ug/Kg	4.9	0.99	396196	02/24/26	02/24/26	XLY
beta-BHC	ND		ug/Kg	4.9	0.99	396196	02/24/26	02/24/26	XLY
gamma-BHC	ND		ug/Kg	4.9	0.99	396196	02/24/26	02/24/26	XLY
delta-BHC	ND		ug/Kg	4.9	0.99	396196	02/24/26	02/24/26	XLY
Heptachlor	ND		ug/Kg	4.9	0.99	396196	02/24/26	02/24/26	XLY
Aldrin	ND		ug/Kg	4.9	0.99	396196	02/24/26	02/24/26	XLY
Heptachlor epoxide	ND		ug/Kg	4.9	0.99	396196	02/24/26	02/24/26	XLY
Endosulfan I	ND		ug/Kg	4.9	0.99	396196	02/24/26	02/24/26	XLY
Dieldrin	ND		ug/Kg	4.9	0.99	396196	02/24/26	02/24/26	XLY
4,4'-DDE	ND		ug/Kg	4.9	0.99	396196	02/24/26	02/24/26	XLY
Endrin	ND		ug/Kg	4.9	0.99	396196	02/24/26	02/24/26	XLY
Endosulfan II	ND		ug/Kg	4.9	0.99	396196	02/24/26	02/24/26	XLY
Endosulfan sulfate	ND		ug/Kg	4.9	0.99	396196	02/24/26	02/24/26	XLY
4,4'-DDD	ND		ug/Kg	4.9	0.99	396196	02/24/26	02/24/26	XLY
Endrin aldehyde	ND		ug/Kg	4.9	0.99	396196	02/24/26	02/24/26	XLY
Endrin ketone	ND		ug/Kg	4.9	0.99	396196	02/24/26	02/24/26	XLY
4,4'-DDT	ND		ug/Kg	4.9	0.99	396196	02/24/26	02/24/26	XLY
Methoxychlor	ND		ug/Kg	9.9	0.99	396196	02/24/26	02/24/26	XLY
Toxaphene	ND		ug/Kg	99	0.99	396196	02/24/26	02/24/26	XLY
Chlordane (Technical)	ND		ug/Kg	49	0.99	396196	02/24/26	02/24/26	XLY
Surrogates				**Limits**					
TCMX	85%		%REC	58-120	0.99	396196	02/24/26	02/24/26	XLY
Decachlorobiphenyl	87%		%REC	47-120	0.99	396196	02/24/26	02/24/26	XLY

Results for any subcontracted analyses are not included in this section.

ENTHALPY ANALYTICAL

Analysis Results for 553642

Sample ID: CG-33-0.5	Lab ID: 553642-027	Collected: 02/18/26
	Matrix: Soil	

553642-027 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 8081A Prep Method: EPA 3546									
alpha-BHC	ND		ug/Kg	5.1	1	396196	02/24/26	02/24/26	XLY
beta-BHC	ND		ug/Kg	5.1	1	396196	02/24/26	02/24/26	XLY
gamma-BHC	ND		ug/Kg	5.1	1	396196	02/24/26	02/24/26	XLY
delta-BHC	ND		ug/Kg	5.1	1	396196	02/24/26	02/24/26	XLY
Heptachlor	ND		ug/Kg	5.1	1	396196	02/24/26	02/24/26	XLY
Aldrin	ND		ug/Kg	5.1	1	396196	02/24/26	02/24/26	XLY
Heptachlor epoxide	ND		ug/Kg	5.1	1	396196	02/24/26	02/24/26	XLY
Endosulfan I	ND		ug/Kg	5.1	1	396196	02/24/26	02/24/26	XLY
Dieldrin	ND		ug/Kg	5.1	1	396196	02/24/26	02/24/26	XLY
4,4'-DDE	ND		ug/Kg	5.1	1	396196	02/24/26	02/24/26	XLY
Endrin	ND		ug/Kg	5.1	1	396196	02/24/26	02/24/26	XLY
Endosulfan II	ND		ug/Kg	5.1	1	396196	02/24/26	02/24/26	XLY
Endosulfan sulfate	ND		ug/Kg	5.1	1	396196	02/24/26	02/24/26	XLY
4,4'-DDD	ND		ug/Kg	5.1	1	396196	02/24/26	02/24/26	XLY
Endrin aldehyde	ND		ug/Kg	5.1	1	396196	02/24/26	02/24/26	XLY
Endrin ketone	ND		ug/Kg	5.1	1	396196	02/24/26	02/24/26	XLY
4,4'-DDT	ND		ug/Kg	5.1	1	396196	02/24/26	02/24/26	XLY
Methoxychlor	ND		ug/Kg	10	1	396196	02/24/26	02/24/26	XLY
Toxaphene	ND		ug/Kg	100	1	396196	02/24/26	02/24/26	XLY
Chlordane (Technical)	ND		ug/Kg	51	1	396196	02/24/26	02/24/26	XLY
Surrogates				**Limits**					
TCMX	83%		%REC	58-120	1	396196	02/24/26	02/24/26	XLY
Decachlorobiphenyl	83%		%REC	47-120	1	396196	02/24/26	02/24/26	XLY

Results for any subcontracted analyses are not included in this section.

ENTHALPY ANALYTICAL

Analysis Results for 553642

Sample ID: CG-33-2.5	Lab ID: 553642-028	Collected: 02/18/26
	Matrix: Soil	

553642-028 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 8081A Prep Method: EPA 3546									
alpha-BHC	ND		ug/Kg	5.1	1	396196	02/24/26	02/24/26	XLY
beta-BHC	ND		ug/Kg	5.1	1	396196	02/24/26	02/24/26	XLY
gamma-BHC	ND		ug/Kg	5.1	1	396196	02/24/26	02/24/26	XLY
delta-BHC	ND		ug/Kg	5.1	1	396196	02/24/26	02/24/26	XLY
Heptachlor	ND		ug/Kg	5.1	1	396196	02/24/26	02/24/26	XLY
Aldrin	ND		ug/Kg	5.1	1	396196	02/24/26	02/24/26	XLY
Heptachlor epoxide	ND		ug/Kg	5.1	1	396196	02/24/26	02/24/26	XLY
Endosulfan I	ND		ug/Kg	5.1	1	396196	02/24/26	02/24/26	XLY
Dieldrin	ND		ug/Kg	5.1	1	396196	02/24/26	02/24/26	XLY
4,4'-DDE	ND		ug/Kg	5.1	1	396196	02/24/26	02/24/26	XLY
Endrin	ND		ug/Kg	5.1	1	396196	02/24/26	02/24/26	XLY
Endosulfan II	ND		ug/Kg	5.1	1	396196	02/24/26	02/24/26	XLY
Endosulfan sulfate	ND		ug/Kg	5.1	1	396196	02/24/26	02/24/26	XLY
4,4'-DDD	ND		ug/Kg	5.1	1	396196	02/24/26	02/24/26	XLY
Endrin aldehyde	ND		ug/Kg	5.1	1	396196	02/24/26	02/24/26	XLY
Endrin ketone	ND		ug/Kg	5.1	1	396196	02/24/26	02/24/26	XLY
4,4'-DDT	ND		ug/Kg	5.1	1	396196	02/24/26	02/24/26	XLY
Methoxychlor	ND		ug/Kg	10	1	396196	02/24/26	02/24/26	XLY
Toxaphene	ND		ug/Kg	100	1	396196	02/24/26	02/24/26	XLY
Chlordane (Technical)	ND		ug/Kg	51	1	396196	02/24/26	02/24/26	XLY
Surrogates				**Limits**					
TCMX	82%		%REC	58-120	1	396196	02/24/26	02/24/26	XLY
Decachlorobiphenyl	83%		%REC	47-120	1	396196	02/24/26	02/24/26	XLY

Sample ID: AOC4-SB-31-0.5	Lab ID: 553642-029	Collected: 02/18/26 10:18
	Matrix: Soil	

553642-029 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3050B									
Lead	**23**		mg/Kg	0.98	0.98	395889	02/20/26	02/20/26	SBW
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	50	0.99	396118	02/23/26	02/24/26	MES
Aroclor-1221	ND		ug/Kg	50	0.99	396118	02/23/26	02/24/26	MES
Aroclor-1232	ND		ug/Kg	50	0.99	396118	02/23/26	02/24/26	MES
Aroclor-1242	ND		ug/Kg	50	0.99	396118	02/23/26	02/24/26	MES
Aroclor-1248	ND		ug/Kg	50	0.99	396118	02/23/26	02/24/26	MES
Aroclor-1254	**190**		ug/Kg	50	0.99	396118	02/23/26	02/24/26	MES
Aroclor-1260	**110**		ug/Kg	50	0.99	396118	02/23/26	02/24/26	MES
Aroclor-1262	ND		ug/Kg	50	0.99	396118	02/23/26	02/24/26	MES
Aroclor-1268	ND		ug/Kg	50	0.99	396118	02/23/26	02/24/26	MES
Total PCBs	**300**		ug/Kg	50	0.99	396118	02/23/26	02/24/26	MES
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	94%		%REC	50-127	0.99	396118	02/23/26	02/24/26	MES

Results for any subcontracted analyses are not included in this section.

Analysis Results for 553642

Sample ID: AOC4-SB-32-0.5	Lab ID: 553642-030	Collected: 02/18/26 10:37
	Matrix: Soil	

553642-030 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3050B									
Lead	**16**		mg/Kg	0.96	0.96	395889	02/20/26	02/20/26	SBW
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Aroclor-1221	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Aroclor-1232	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Aroclor-1242	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Aroclor-1248	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Aroclor-1254	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Aroclor-1260	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Aroclor-1262	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Aroclor-1268	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Total PCBs	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	127%		%REC	50-127	1	396118	02/23/26	02/24/26	MES

Sample ID: AOC4-SB-33-0.5	Lab ID: 553642-031	Collected: 02/18/26 11:21
	Matrix: Soil	

553642-031 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3050B									
Lead	**70**		mg/Kg	0.96	0.96	395889	02/20/26	02/20/26	SBW
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Aroclor-1221	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Aroclor-1232	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Aroclor-1242	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Aroclor-1248	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Aroclor-1254	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Aroclor-1260	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Aroclor-1262	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Aroclor-1268	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Total PCBs	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	93%		%REC	50-127	1	396118	02/23/26	02/24/26	MES

Results for any subcontracted analyses are not included in this section.

Analysis Results for 553642

Sample ID: AOC4-SB-31-2.5	Lab ID: 553642-032	Collected: 02/18/26 10:25
	Matrix: Soil	

553642-032 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND	H	ug/Kg	51	1	397475	03/09/26	03/12/26	KMB
Aroclor-1221	ND	H	ug/Kg	51	1	397475	03/09/26	03/12/26	KMB
Aroclor-1232	ND	H	ug/Kg	51	1	397475	03/09/26	03/12/26	KMB
Aroclor-1242	ND	H	ug/Kg	51	1	397475	03/09/26	03/12/26	KMB
Aroclor-1248	ND	H	ug/Kg	51	1	397475	03/09/26	03/12/26	KMB
Aroclor-1254	ND	H	ug/Kg	51	1	397475	03/09/26	03/12/26	KMB
Aroclor-1260	ND	H	ug/Kg	51	1	397475	03/09/26	03/12/26	KMB
Aroclor-1262	ND	H	ug/Kg	51	1	397475	03/09/26	03/12/26	KMB
Aroclor-1268	ND	H	ug/Kg	51	1	397475	03/09/26	03/12/26	KMB
Total PCBs	ND		ug/Kg	51	1	397475	03/09/26	03/12/26	KMB
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	98%	H	%REC	50-127	1	397475	03/09/26	03/12/26	KMB

Sample ID: AOC4-SB-13-0.5	Lab ID: 553642-035	Collected: 02/18/26 12:04
	Matrix: Soil	

553642-035 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3050B									
Lead	**21**		mg/Kg	0.99	0.99	395889	02/20/26	02/20/26	SBW
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	49	0.98	396118	02/23/26	02/24/26	MES
Aroclor-1221	ND		ug/Kg	49	0.98	396118	02/23/26	02/24/26	MES
Aroclor-1232	ND		ug/Kg	49	0.98	396118	02/23/26	02/24/26	MES
Aroclor-1242	ND		ug/Kg	49	0.98	396118	02/23/26	02/24/26	MES
Aroclor-1248	ND		ug/Kg	49	0.98	396118	02/23/26	02/24/26	MES
Aroclor-1254	ND		ug/Kg	49	0.98	396118	02/23/26	02/24/26	MES
Aroclor-1260	ND		ug/Kg	49	0.98	396118	02/23/26	02/24/26	MES
Aroclor-1262	ND		ug/Kg	49	0.98	396118	02/23/26	02/24/26	MES
Aroclor-1268	ND		ug/Kg	49	0.98	396118	02/23/26	02/24/26	MES
Total PCBs	ND		ug/Kg	49	0.98	396118	02/23/26	02/24/26	MES
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	118%		%REC	50-127	0.98	396118	02/23/26	02/24/26	MES

Results for any subcontracted analyses are not included in this section.

Analysis Results for 553642

Sample ID: AOC4-SB-14-0.5 **Lab ID: 553642-036** **Collected: 02/18/26 13:44**
Matrix: Soil

553642-036 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3050B									
Lead	**20**		mg/Kg	0.95	0.95	395889	02/20/26	02/20/26	SBW
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Aroclor-1221	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Aroclor-1232	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Aroclor-1242	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Aroclor-1248	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Aroclor-1254	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Aroclor-1260	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Aroclor-1262	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Aroclor-1268	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Total PCBs	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	120%		%REC	50-127	1	396118	02/23/26	02/24/26	MES

Sample ID: AOC4-SB-15-0.5 **Lab ID: 553642-037** **Collected: 02/18/26 14:06**
Matrix: Soil

553642-037 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3050B									
Lead	**68**		mg/Kg	0.97	0.97	395889	02/20/26	02/20/26	SBW
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	49	0.98	396118	02/23/26	02/24/26	MES
Aroclor-1221	ND		ug/Kg	49	0.98	396118	02/23/26	02/24/26	MES
Aroclor-1232	ND		ug/Kg	49	0.98	396118	02/23/26	02/24/26	MES
Aroclor-1242	ND		ug/Kg	49	0.98	396118	02/23/26	02/24/26	MES
Aroclor-1248	ND		ug/Kg	49	0.98	396118	02/23/26	02/24/26	MES
Aroclor-1254	ND		ug/Kg	49	0.98	396118	02/23/26	02/24/26	MES
Aroclor-1260	**120**		ug/Kg	49	0.98	396118	02/23/26	02/24/26	MES
Aroclor-1262	ND		ug/Kg	49	0.98	396118	02/23/26	02/24/26	MES
Aroclor-1268	ND		ug/Kg	49	0.98	396118	02/23/26	02/24/26	MES
Total PCBs	**120**		ug/Kg	49	0.98	396118	02/23/26	02/24/26	MES
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	119%		%REC	50-127	0.98	396118	02/23/26	02/24/26	MES

Results for any subcontracted analyses are not included in this section.

Analysis Results for 553642

Sample ID: AOC4-SB-25-0.5	Lab ID: 553642-041	Collected: 02/18/26 14:34
	Matrix: Soil	

553642-041 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3050B									
Lead	**16**		mg/Kg	0.95	0.95	395889	02/20/26	02/20/26	SBW
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Aroclor-1221	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Aroclor-1232	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Aroclor-1242	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Aroclor-1248	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Aroclor-1254	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Aroclor-1260	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Aroclor-1262	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Aroclor-1268	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Total PCBs	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	101%		%REC	50-127	1	396118	02/23/26	02/24/26	MES

Sample ID: AOC4-SB-26-0.5	Lab ID: 553642-042	Collected: 02/18/26 14:54
	Matrix: Soil	

553642-042 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3050B									
Lead	**9.1**		mg/Kg	1.0	1	395889	02/20/26	02/20/26	SBW
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	49	0.98	396118	02/23/26	02/24/26	MES
Aroclor-1221	ND		ug/Kg	49	0.98	396118	02/23/26	02/24/26	MES
Aroclor-1232	ND		ug/Kg	49	0.98	396118	02/23/26	02/24/26	MES
Aroclor-1242	ND		ug/Kg	49	0.98	396118	02/23/26	02/24/26	MES
Aroclor-1248	ND		ug/Kg	49	0.98	396118	02/23/26	02/24/26	MES
Aroclor-1254	ND		ug/Kg	49	0.98	396118	02/23/26	02/24/26	MES
Aroclor-1260	ND		ug/Kg	49	0.98	396118	02/23/26	02/24/26	MES
Aroclor-1262	ND		ug/Kg	49	0.98	396118	02/23/26	02/24/26	MES
Aroclor-1268	ND		ug/Kg	49	0.98	396118	02/23/26	02/24/26	MES
Total PCBs	ND		ug/Kg	49	0.98	396118	02/23/26	02/24/26	MES
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	118%		%REC	50-127	0.98	396118	02/23/26	02/24/26	MES

Results for any subcontracted analyses are not included in this section.

Analysis Results for 553642

Sample ID: AOC4-SB-27-0.5	Lab ID: 553642-043	Collected: 02/18/26 15:14
	Matrix: Soil	

553642-043 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3050B									
Lead	**10**		mg/Kg	0.98	0.98	395889	02/20/26	02/20/26	SBW
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Aroclor-1221	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Aroclor-1232	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Aroclor-1242	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Aroclor-1248	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Aroclor-1254	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Aroclor-1260	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Aroclor-1262	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Aroclor-1268	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Total PCBs	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	122%		%REC	50-127	1	396118	02/23/26	02/24/26	MES

Sample ID: DUP-01-0.5-260218	Lab ID: 553642-044	Collected: 02/18/26
	Matrix: Soil	

553642-044 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3050B									
Lead	**13**		mg/Kg	0.98	0.98	395889	02/20/26	02/20/26	SBW
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Aroclor-1221	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Aroclor-1232	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Aroclor-1242	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Aroclor-1248	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Aroclor-1254	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Aroclor-1260	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Aroclor-1262	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Aroclor-1268	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Total PCBs	ND		ug/Kg	51	1	396118	02/23/26	02/24/26	MES
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	116%		%REC	50-127	1	396118	02/23/26	02/24/26	MES

Results for any subcontracted analyses are not included in this section.

ENTHALPY ANALYTICAL

Analysis Results for 553642

Sample ID: CG-37-0.5	Lab ID: 553642-049	Collected: 02/18/26
	Matrix: Soil	

553642-049 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 8081A Prep Method: EPA 3546									
alpha-BHC	ND		ug/Kg	10	2	396196	02/24/26	02/24/26	XLY
beta-BHC	ND		ug/Kg	10	2	396196	02/24/26	02/24/26	XLY
gamma-BHC	ND		ug/Kg	10	2	396196	02/24/26	02/24/26	XLY
delta-BHC	ND		ug/Kg	10	2	396196	02/24/26	02/24/26	XLY
Heptachlor	ND		ug/Kg	10	2	396196	02/24/26	02/24/26	XLY
Aldrin	ND		ug/Kg	10	2	396196	02/24/26	02/24/26	XLY
Heptachlor epoxide	ND		ug/Kg	10	2	396196	02/24/26	02/24/26	XLY
Endosulfan I	ND		ug/Kg	10	2	396196	02/24/26	02/24/26	XLY
Dieldrin	ND		ug/Kg	10	2	396196	02/24/26	02/24/26	XLY
4,4'-DDE	ND		ug/Kg	10	2	396196	02/24/26	02/24/26	XLY
Endrin	ND		ug/Kg	10	2	396196	02/24/26	02/24/26	XLY
Endosulfan II	ND		ug/Kg	10	2	396196	02/24/26	02/24/26	XLY
Endosulfan sulfate	ND		ug/Kg	10	2	396196	02/24/26	02/24/26	XLY
4,4'-DDD	ND		ug/Kg	10	2	396196	02/24/26	02/24/26	XLY
Endrin aldehyde	ND		ug/Kg	10	2	396196	02/24/26	02/24/26	XLY
Endrin ketone	ND		ug/Kg	10	2	396196	02/24/26	02/24/26	XLY
4,4'-DDT	ND		ug/Kg	10	2	396196	02/24/26	02/24/26	XLY
Methoxychlor	ND		ug/Kg	20	2	396196	02/24/26	02/24/26	XLY
Toxaphene	ND		ug/Kg	200	2	396196	02/24/26	02/24/26	XLY
Chlordane (Technical)	ND		ug/Kg	100	2	396196	02/24/26	02/24/26	XLY
Surrogates				**Limits**					
TCMX	91%		%REC	58-120	2	396196	02/24/26	02/24/26	XLY
Decachlorobiphenyl	90%		%REC	47-120	2	396196	02/24/26	02/24/26	XLY

Results for any subcontracted analyses are not included in this section.

Analysis Results for 553642

Sample ID: CG-37-2.5	Lab ID: 553642-050	Collected: 02/18/26
	Matrix: Soil	

553642-050 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 8081A Prep Method: EPA 3546									
alpha-BHC	ND		ug/Kg	5.0	1	396196	02/24/26	02/24/26	XLY
beta-BHC	ND		ug/Kg	5.0	1	396196	02/24/26	02/24/26	XLY
gamma-BHC	ND		ug/Kg	5.0	1	396196	02/24/26	02/24/26	XLY
delta-BHC	ND		ug/Kg	5.0	1	396196	02/24/26	02/24/26	XLY
Heptachlor	ND		ug/Kg	5.0	1	396196	02/24/26	02/24/26	XLY
Aldrin	ND		ug/Kg	5.0	1	396196	02/24/26	02/24/26	XLY
Heptachlor epoxide	ND		ug/Kg	5.0	1	396196	02/24/26	02/24/26	XLY
Endosulfan I	ND		ug/Kg	5.0	1	396196	02/24/26	02/24/26	XLY
Dieldrin	ND		ug/Kg	5.0	1	396196	02/24/26	02/24/26	XLY
4,4'-DDE	ND		ug/Kg	5.0	1	396196	02/24/26	02/24/26	XLY
Endrin	ND		ug/Kg	5.0	1	396196	02/24/26	02/24/26	XLY
Endosulfan II	ND		ug/Kg	5.0	1	396196	02/24/26	02/24/26	XLY
Endosulfan sulfate	ND		ug/Kg	5.0	1	396196	02/24/26	02/24/26	XLY
4,4'-DDD	ND		ug/Kg	5.0	1	396196	02/24/26	02/24/26	XLY
Endrin aldehyde	ND		ug/Kg	5.0	1	396196	02/24/26	02/24/26	XLY
Endrin ketone	ND		ug/Kg	5.0	1	396196	02/24/26	02/24/26	XLY
4,4'-DDT	ND		ug/Kg	5.0	1	396196	02/24/26	02/24/26	XLY
Methoxychlor	ND		ug/Kg	10	1	396196	02/24/26	02/24/26	XLY
Toxaphene	ND		ug/Kg	100	1	396196	02/24/26	02/24/26	XLY
Chlordane (Technical)	ND		ug/Kg	50	1	396196	02/24/26	02/24/26	XLY
Surrogates				**Limits**					
TCMX	84%		%REC	58-120	1	396196	02/24/26	02/24/26	XLY
Decachlorobiphenyl	92%		%REC	47-120	1	396196	02/24/26	02/24/26	XLY

Results for any subcontracted analyses are not included in this section.

Analysis Results for 553642

Sample ID: EB-01-260218	Lab ID: 553642-051	Collected: 02/18/26 16:00
	Matrix: Water	

553642-051 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3015A									
Lead	ND		mg/L	0.010	1	395894	02/20/26	02/20/26	SBW
Method: EPA 8081A Prep Method: EPA 3510C									
alpha-BHC	ND		ug/L	0.05	1	396077	02/22/26	02/25/26	XLY
beta-BHC	ND		ug/L	0.05	1	396077	02/22/26	02/25/26	XLY
gamma-BHC	ND		ug/L	0.05	1	396077	02/22/26	02/25/26	XLY
delta-BHC	ND		ug/L	0.05	1	396077	02/22/26	02/25/26	XLY
Heptachlor	ND		ug/L	0.05	1	396077	02/22/26	02/25/26	XLY
Aldrin	ND		ug/L	0.05	1	396077	02/22/26	02/25/26	XLY
Heptachlor epoxide	ND		ug/L	0.05	1	396077	02/22/26	02/25/26	XLY
Endosulfan I	ND		ug/L	0.05	1	396077	02/22/26	02/25/26	XLY
Dieldrin	ND		ug/L	0.1	1	396077	02/22/26	02/25/26	XLY
4,4'-DDE	ND		ug/L	0.1	1	396077	02/22/26	02/25/26	XLY
Endrin	ND		ug/L	0.1	1	396077	02/22/26	02/25/26	XLY
Endosulfan II	ND		ug/L	0.1	1	396077	02/22/26	02/25/26	XLY
Endosulfan sulfate	ND		ug/L	0.1	1	396077	02/22/26	02/25/26	XLY
4,4'-DDD	ND		ug/L	0.1	1	396077	02/22/26	02/25/26	XLY
Endrin aldehyde	ND		ug/L	0.1	1	396077	02/22/26	02/25/26	XLY
Endrin ketone	ND		ug/L	0.1	1	396077	02/22/26	02/25/26	XLY
4,4'-DDT	ND		ug/L	0.1	1	396077	02/22/26	02/25/26	XLY
Methoxychlor	ND		ug/L	0.1	1	396077	02/22/26	02/25/26	XLY
Toxaphene	ND		ug/L	2.0	1	396077	02/22/26	02/25/26	XLY
Chlordane (Technical)	ND		ug/L	1.0	1	396077	02/22/26	02/25/26	XLY
Surrogates				**Limits**					
TCMX	77%		%REC	29-120	1	396077	02/22/26	02/25/26	XLY
Decachlorobiphenyl	105%		%REC	33-132	1	396077	02/22/26	02/25/26	XLY
Method: EPA 8082 Prep Method: EPA 3510C									
Aroclor-1016	ND		ug/L	0.50	1	396077	02/22/26	02/25/26	XLY
Aroclor-1221	ND		ug/L	0.50	1	396077	02/22/26	02/25/26	XLY
Aroclor-1232	ND		ug/L	0.50	1	396077	02/22/26	02/25/26	XLY
Aroclor-1242	ND		ug/L	0.50	1	396077	02/22/26	02/25/26	XLY
Aroclor-1248	ND		ug/L	0.50	1	396077	02/22/26	02/25/26	XLY
Aroclor-1254	ND		ug/L	0.50	1	396077	02/22/26	02/25/26	XLY
Aroclor-1260	ND		ug/L	0.50	1	396077	02/22/26	02/25/26	XLY
Aroclor-1262	ND		ug/L	0.50	1	396077	02/22/26	02/25/26	XLY
Aroclor-1268	ND		ug/L	0.50	1	396077	02/22/26	02/25/26	XLY
Total PCBs	ND		ug/L	0.50	1	396077	02/22/26	02/25/26	XLY
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	78%		%REC	28-138	1	396077	02/22/26	02/25/26	XLY

Results for any subcontracted analyses are not included in this section.

ENTHALPY ANALYTICAL

Analysis Results for 553642

Sample ID: CG-34-0.5-DUP	Lab ID: 553642-052	Collected: 02/18/26
	Matrix: Soil	

553642-052 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 8081A Prep Method: EPA 3546									
alpha-BHC	ND		ug/Kg	4.9	0.99	396196	02/24/26	02/24/26	XLY
beta-BHC	ND		ug/Kg	4.9	0.99	396196	02/24/26	02/24/26	XLY
gamma-BHC	ND		ug/Kg	4.9	0.99	396196	02/24/26	02/24/26	XLY
delta-BHC	ND		ug/Kg	4.9	0.99	396196	02/24/26	02/24/26	XLY
Heptachlor	ND		ug/Kg	4.9	0.99	396196	02/24/26	02/24/26	XLY
Aldrin	ND		ug/Kg	4.9	0.99	396196	02/24/26	02/24/26	XLY
Heptachlor epoxide	ND		ug/Kg	4.9	0.99	396196	02/24/26	02/24/26	XLY
Endosulfan I	ND		ug/Kg	4.9	0.99	396196	02/24/26	02/24/26	XLY
Dieldrin	**7.0**	C	ug/Kg	4.9	0.99	396196	02/24/26	02/24/26	XLY
4,4'-DDE	**6.2**	C	ug/Kg	4.9	0.99	396196	02/24/26	02/24/26	XLY
Endrin	ND		ug/Kg	4.9	0.99	396196	02/24/26	02/24/26	XLY
Endosulfan II	ND		ug/Kg	4.9	0.99	396196	02/24/26	02/24/26	XLY
Endosulfan sulfate	ND		ug/Kg	4.9	0.99	396196	02/24/26	02/24/26	XLY
4,4'-DDD	ND		ug/Kg	4.9	0.99	396196	02/24/26	02/24/26	XLY
Endrin aldehyde	ND		ug/Kg	4.9	0.99	396196	02/24/26	02/24/26	XLY
Endrin ketone	ND		ug/Kg	4.9	0.99	396196	02/24/26	02/24/26	XLY
4,4'-DDT	**85**	C	ug/Kg	4.9	0.99	396196	02/24/26	02/24/26	XLY
Methoxychlor	ND		ug/Kg	9.9	0.99	396196	02/24/26	02/24/26	XLY
Toxaphene	ND		ug/Kg	99	0.99	396196	02/24/26	02/24/26	XLY
Chlordane (Technical)	ND		ug/Kg	49	0.99	396196	02/24/26	02/24/26	XLY
Surrogates				**Limits**					
TCMX	88%		%REC	58-120	0.99	396196	02/24/26	02/24/26	XLY
Decachlorobiphenyl	93%		%REC	47-120	0.99	396196	02/24/26	02/24/26	XLY

Results for any subcontracted analyses are not included in this section.

Analysis Results for 553642

Sample ID: CG-34-2.5-DUP	Lab ID: 553642-053	Collected: 02/18/26
	Matrix: Soil	

553642-053 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 8081A Prep Method: EPA 3546									
alpha-BHC	ND		ug/Kg	5.0	1	396196	02/24/26	02/25/26	XLY
beta-BHC	ND		ug/Kg	5.0	1	396196	02/24/26	02/25/26	XLY
gamma-BHC	ND		ug/Kg	5.0	1	396196	02/24/26	02/25/26	XLY
delta-BHC	ND		ug/Kg	5.0	1	396196	02/24/26	02/25/26	XLY
Heptachlor	ND		ug/Kg	5.0	1	396196	02/24/26	02/25/26	XLY
Aldrin	ND		ug/Kg	5.0	1	396196	02/24/26	02/25/26	XLY
Heptachlor epoxide	ND		ug/Kg	5.0	1	396196	02/24/26	02/25/26	XLY
Endosulfan I	ND		ug/Kg	5.0	1	396196	02/24/26	02/25/26	XLY
Dieldrin	ND		ug/Kg	5.0	1	396196	02/24/26	02/25/26	XLY
4,4'-DDE	ND		ug/Kg	5.0	1	396196	02/24/26	02/25/26	XLY
Endrin	ND		ug/Kg	5.0	1	396196	02/24/26	02/25/26	XLY
Endosulfan II	ND		ug/Kg	5.0	1	396196	02/24/26	02/25/26	XLY
Endosulfan sulfate	ND		ug/Kg	5.0	1	396196	02/24/26	02/25/26	XLY
4,4'-DDD	ND		ug/Kg	5.0	1	396196	02/24/26	02/25/26	XLY
Endrin aldehyde	ND		ug/Kg	5.0	1	396196	02/24/26	02/25/26	XLY
Endrin ketone	ND		ug/Kg	5.0	1	396196	02/24/26	02/25/26	XLY
4,4'-DDT	ND		ug/Kg	5.0	1	396196	02/24/26	02/25/26	XLY
Methoxychlor	ND		ug/Kg	10	1	396196	02/24/26	02/25/26	XLY
Toxaphene	ND		ug/Kg	100	1	396196	02/24/26	02/25/26	XLY
Chlordane (Technical)	ND		ug/Kg	50	1	396196	02/24/26	02/25/26	XLY
Surrogates				**Limits**					
TCMX	82%		%REC	58-120	1	396196	02/24/26	02/25/26	XLY
Decachlorobiphenyl	93%		%REC	47-120	1	396196	02/24/26	02/25/26	XLY

* Value is outside QC limits
C Presence confirmed, but RPD between columns exceeds 40%
H Holding time was exceeded
ND Not Detected

Results for any subcontracted analyses are not included in this section.

ENTHALPY ANALYTICAL

Batch QC

Type: Blank	Lab ID: QC1342501	Batch: 395894
Matrix: Water	Method: EPA 6010B	Prep Method: EPA 3015A

QC1342501 Analyte	Result	Qual	Units	RL	Prepared	Analyzed
Lead	ND		mg/L	0.010	02/20/26	02/20/26

Type: Lab Control Sample	Lab ID: QC1342502	Batch: 395894
Matrix: Water	Method: EPA 6010B	Prep Method: EPA 3015A

QC1342502 Analyte	Result	Spiked	Units	Recovery	Qual	Limits
Lead	0.3460	0.4000	mg/L	87%		80-120

Type: Matrix Spike	Lab ID: QC1342503	Batch: 395894
Matrix (Source ID): Water (553532-001)	Method: EPA 6010B	Prep Method: EPA 3015A

QC1342503 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	DF
Lead	0.3329	ND	0.4000	mg/L	83%		75-125	1

Type: Matrix Spike Duplicate	Lab ID: QC1342504	Batch: 395894
Matrix (Source ID): Water (553532-001)	Method: EPA 6010B	Prep Method: EPA 3015A

QC1342504 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	RPD	RPD Lim	DF
Lead	0.3466	ND	0.4000	mg/L	87%		75-125	4	20	1

Type: Serial Dilution	Lab ID: QC1342558	Batch: 395894
Matrix (Source ID): Water (553532-001)	Method: EPA 6010B	Prep Method: EPA 3015A

QC1342558 Analyte	Result	Source Sample Result	Units	Qual	RPD	RPD Lim	DF
Lead	ND	ND	mg/L				5

Type: Blank	Lab ID: QC1342475	Batch: 395889
Matrix: Soil	Method: EPA 6010B	Prep Method: EPA 3050B

QC1342475 Analyte	Result	Qual	Units	RL	Prepared	Analyzed
Lead	ND		mg/Kg	1.0	02/20/26	02/20/26

Type: Lab Control Sample	Lab ID: QC1342476	Batch: 395889
Matrix: Soil	Method: EPA 6010B	Prep Method: EPA 3050B

QC1342476 Analyte	Result	Spiked	Units	Recovery	Qual	Limits
Lead	108.8	100.0	mg/Kg	109%		80-120

ENTHALPY ANALYTICAL

Batch QC

Type:	Matrix Spike	Lab ID:	QC1342480	Batch:	395889
Matrix (Source ID):	Soil (553642-001)	Method:	EPA 6010B	Prep Method:	EPA 3050B

QC1342480 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	DF
Lead	153.0	47.87	100.0	mg/Kg	105%		75-125	1

Type:	Matrix Spike Duplicate	Lab ID:	QC1342481	Batch:	395889
Matrix (Source ID):	Soil (553642-001)	Method:	EPA 6010B	Prep Method:	EPA 3050B

QC1342481 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	RPD	RPD Lim	DF
Lead	146.8	47.87	95.24	mg/Kg	104%		75-125	1	28	0.95

Type:	Serial Dilution	Lab ID:	QC1342482	Batch:	395889
Matrix (Source ID):	Soil (553642-001)	Method:	EPA 6010B	Prep Method:	EPA 3050B

QC1342482 Analyte	Result	Source Sample Result	Units	Qual	RPD	RPD Lim	DF
Lead	55.59	47.87	mg/Kg				5

Type:	Post Digest Spike	Lab ID:	QC1342483	Batch:	395889
Matrix (Source ID):	Soil (553642-001)	Method:	EPA 6010B	Prep Method:	EPA 3050B

QC1342483 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	DF
Lead	150.3	47.87	99.01	mg/Kg	103%		75-125	0.99

ENTHALPY ANALYTICAL

Batch QC

Type:	**Blank**	**Lab ID:**	**QC1343603**	**Batch:**	**396196**
Matrix:	**Soil**	**Method:**	**EPA 8081A**	**Prep Method:**	**EPA 3546**

QC1343603 Analyte	Result	Qual	Units	RL	Prepared	Analyzed
alpha-BHC	ND		ug/Kg	5.0	02/24/26	02/24/26
beta-BHC	ND		ug/Kg	5.0	02/24/26	02/24/26
gamma-BHC	ND		ug/Kg	5.0	02/24/26	02/24/26
delta-BHC	ND		ug/Kg	5.0	02/24/26	02/24/26
Heptachlor	ND		ug/Kg	5.0	02/24/26	02/24/26
Aldrin	ND		ug/Kg	5.0	02/24/26	02/24/26
Heptachlor epoxide	ND		ug/Kg	5.0	02/24/26	02/24/26
Endosulfan I	ND		ug/Kg	5.0	02/24/26	02/24/26
Dieldrin	ND		ug/Kg	5.0	02/24/26	02/24/26
4,4'-DDE	ND		ug/Kg	5.0	02/24/26	02/24/26
Endrin	ND		ug/Kg	5.0	02/24/26	02/24/26
Endosulfan II	ND		ug/Kg	5.0	02/24/26	02/24/26
Endosulfan sulfate	ND		ug/Kg	5.0	02/24/26	02/24/26
4,4'-DDD	ND		ug/Kg	5.0	02/24/26	02/24/26
Endrin aldehyde	ND		ug/Kg	5.0	02/24/26	02/24/26
Endrin ketone	ND		ug/Kg	5.0	02/24/26	02/24/26
4,4'-DDT	ND		ug/Kg	5.0	02/24/26	02/24/26
Methoxychlor	ND		ug/Kg	10	02/24/26	02/24/26
Toxaphene	ND		ug/Kg	100	02/24/26	02/24/26
Chlordane (Technical)	ND		ug/Kg	50	02/24/26	02/24/26
Surrogates				**Limits**		
TCMX	83%		%REC	58-120	02/24/26	02/24/26
Decachlorobiphenyl	85%		%REC	47-120	02/24/26	02/24/26

ENTHALPY ANALYTICAL

Batch QC

Type: Lab Control Sample	**Lab ID: QC1343604**	**Batch: 396196**
Matrix: Soil	**Method: EPA 8081A**	**Prep Method: EPA 3546**

QC1343604 Analyte	Result	Spiked	Units	Recovery	Qual	Limits
alpha-BHC	49.43	50.25	ug/Kg	98%		53-132
beta-BHC	41.94	50.25	ug/Kg	83%		59-131
gamma-BHC	48.08	50.25	ug/Kg	96%		54-132
delta-BHC	49.41	50.25	ug/Kg	98%		54-134
Heptachlor	44.85	50.25	ug/Kg	89%		50-130
Aldrin	37.59	50.25	ug/Kg	75%		46-120
Heptachlor epoxide	40.74	50.25	ug/Kg	81%		52-127
Endosulfan I	41.65	50.25	ug/Kg	83%		53-132
Dieldrin	40.13	50.25	ug/Kg	80%		53-134
4,4'-DDE	42.81	50.25	ug/Kg	85%		53-140
Endrin	45.56	50.25	ug/Kg	91%		53-142
Endosulfan II	40.12	50.25	ug/Kg	80%	#	53-138
Endosulfan sulfate	45.09	50.25	ug/Kg	90%		50-134
4,4'-DDD	39.20	50.25	ug/Kg	78%		50-136
Endrin aldehyde	37.10	50.25	ug/Kg	74%		15-120
Endrin ketone	50.74	50.25	ug/Kg	101%		50-146
4,4'-DDT	43.06	50.25	ug/Kg	86%		46-142
Methoxychlor	46.42	50.25	ug/Kg	92%		48-156
Surrogates						
TCMX	41.77	50.25	ug/Kg	83%		58-120
Decachlorobiphenyl	44.23	50.25	ug/Kg	88%		47-120

ENTHALPY ANALYTICAL

Batch QC

Type:	**Matrix Spike**	**Lab ID:**	**QC1343605**	**Batch:**	**396196**
Matrix (Source ID):	**Soil (553642-019)**	**Method:**	**EPA 8081A**	**Prep Method:**	**EPA 3546**

QC1343605 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	DF
alpha-BHC	47.83	ND	49.46	ug/Kg	97%		52-120	0.99
beta-BHC	42.10	ND	49.46	ug/Kg	85%		57-126	0.99
gamma-BHC	47.94	ND	49.46	ug/Kg	97%		54-122	0.99
delta-BHC	49.65	ND	49.46	ug/Kg	100%		44-127	0.99
Heptachlor	44.34	ND	49.46	ug/Kg	90%		51-122	0.99
Aldrin	42.75	ND	49.46	ug/Kg	86%		51-120	0.99
Heptachlor epoxide	46.02	ND	49.46	ug/Kg	93%	#	50-122	0.99
Endosulfan I	43.21	ND	49.46	ug/Kg	87%		48-123	0.99
Dieldrin	46.70	9.342	49.46	ug/Kg	76%		48-128	0.99
4,4'-DDE	54.89	6.930	49.46	ug/Kg	97%		50-139	0.99
Endrin	56.49	ND	49.46	ug/Kg	114%		53-132	0.99
Endosulfan II	41.83	ND	49.46	ug/Kg	85%	#	47-131	0.99
Endosulfan sulfate	52.22	ND	49.46	ug/Kg	106%		40-126	0.99
4,4'-DDD	40.71	ND	49.46	ug/Kg	82%		48-130	0.99
Endrin aldehyde	58.04	ND	49.46	ug/Kg	117%		26-120	0.99
Endrin ketone	52.37	ND	49.46	ug/Kg	106%		51-133	0.99
4,4'-DDT	63.22	16.61	49.46	ug/Kg	94%		40-144	0.99
Methoxychlor	48.67	ND	49.46	ug/Kg	98%		49-148	0.99
Surrogates								
TCMX	40.37		49.46	ug/Kg	82%		58-120	0.99
Decachlorobiphenyl	47.20		49.46	ug/Kg	95%		47-120	0.99

ENTHALPY ANALYTICAL

Batch QC

Type:	**Matrix Spike Duplicate**	**Lab ID:**	**QC1343606**	**Batch:**	**396196**
Matrix (Source ID):	**Soil (553642-019)**	**Method:**	**EPA 8081A**	**Prep Method:**	**EPA 3546**

QC1343606 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	RPD	RPD Lim	DF
alpha-BHC	46.91	ND	49.31	ug/Kg	95%		52-120	2	37	0.99
beta-BHC	41.56	ND	49.31	ug/Kg	84%		57-126	1	38	0.99
gamma-BHC	46.63	ND	49.31	ug/Kg	95%		54-122	2	39	0.99
delta-BHC	49.09	ND	49.31	ug/Kg	100%		44-127	1	54	0.99
Heptachlor	43.17	ND	49.31	ug/Kg	88%		51-122	2	44	0.99
Aldrin	40.04	ND	49.31	ug/Kg	81%		51-120	6	39	0.99
Heptachlor epoxide	46.45	ND	49.31	ug/Kg	94%	#	50-122	1	39	0.99
Endosulfan I	41.48	ND	49.31	ug/Kg	84%		48-123	4	47	0.99
Dieldrin	46.07	9.342	49.31	ug/Kg	74%		48-128	1	43	0.99
4,4'-DDE	53.15	6.930	49.31	ug/Kg	94%		50-139	3	42	0.99
Endrin	54.87	ND	49.31	ug/Kg	111%		53-132	3	45	0.99
Endosulfan II	41.24	ND	49.31	ug/Kg	84%	#	47-131	1	46	0.99
Endosulfan sulfate	49.57	ND	49.31	ug/Kg	101%		40-126	5	52	0.99
4,4'-DDD	38.02	ND	49.31	ug/Kg	77%		48-130	7	46	0.99
Endrin aldehyde	58.03	ND	49.31	ug/Kg	118%		26-120	0	57	0.99
Endrin ketone	49.27	ND	49.31	ug/Kg	100%		51-133	6	43	0.99
4,4'-DDT	62.93	16.61	49.31	ug/Kg	94%		40-144	0	56	0.99
Methoxychlor	47.46	ND	49.31	ug/Kg	96%		49-148	2	53	0.99
Surrogates										
TCMX	38.50		49.31	ug/Kg	78%		58-120			0.99
Decachlorobiphenyl	45.45		49.31	ug/Kg	92%		47-120			0.99

ENTHALPY ANALYTICAL

Batch QC

Type: Blank	Lab ID: QC1343118	Batch: 396077
Matrix: Water		

QC1343118 Analyte	Result	Qual	Units	RL	Prepared	Analyzed
Method: EPA 8081A Prep Method: EPA 3510C						
alpha-BHC	ND		ug/L	0.05	02/22/26	02/25/26
beta-BHC	ND		ug/L	0.05	02/22/26	02/25/26
gamma-BHC	ND		ug/L	0.05	02/22/26	02/25/26
delta-BHC	ND		ug/L	0.05	02/22/26	02/25/26
Heptachlor	ND		ug/L	0.05	02/22/26	02/25/26
Aldrin	ND		ug/L	0.05	02/22/26	02/25/26
Heptachlor epoxide	ND		ug/L	0.05	02/22/26	02/25/26
Endosulfan I	ND		ug/L	0.05	02/22/26	02/25/26
Dieldrin	ND		ug/L	0.1	02/22/26	02/25/26
4,4'-DDE	ND		ug/L	0.1	02/22/26	02/25/26
Endrin	ND		ug/L	0.1	02/22/26	02/25/26
Endosulfan II	ND		ug/L	0.1	02/22/26	02/25/26
Endosulfan sulfate	ND		ug/L	0.1	02/22/26	02/25/26
4,4'-DDD	ND		ug/L	0.1	02/22/26	02/25/26
Endrin aldehyde	ND		ug/L	0.1	02/22/26	02/25/26
Endrin ketone	ND		ug/L	0.1	02/22/26	02/25/26
4,4'-DDT	ND		ug/L	0.1	02/22/26	02/25/26
Methoxychlor	ND		ug/L	0.1	02/22/26	02/25/26
Toxaphene	ND		ug/L	2.0	02/22/26	02/25/26
Chlordane (Technical)	ND		ug/L	1.0	02/22/26	02/25/26
Surrogates				**Limits**		
TCMX	61%		%REC	29-120	02/22/26	02/25/26
Decachlorobiphenyl	90%		%REC	33-132	02/22/26	02/25/26
Method: EPA 8082 Prep Method: EPA 3510C						
Aroclor-1016	ND		ug/L	0.50	02/22/26	02/25/26
Aroclor-1221	ND		ug/L	0.50	02/22/26	02/25/26
Aroclor-1232	ND		ug/L	0.50	02/22/26	02/25/26
Aroclor-1242	ND		ug/L	0.50	02/22/26	02/25/26
Aroclor-1248	ND		ug/L	0.50	02/22/26	02/25/26
Aroclor-1254	ND		ug/L	0.50	02/22/26	02/25/26
Aroclor-1260	ND		ug/L	0.50	02/22/26	02/25/26
Aroclor-1262	ND		ug/L	0.50	02/22/26	02/25/26
Aroclor-1268	ND		ug/L	0.50	02/22/26	02/25/26
Total PCBs	ND		ug/L	0.50	02/22/26	02/25/26
Surrogates				**Limits**		
Decachlorobiphenyl (PCB)	66%		%REC	28-138	02/22/26	02/25/26

ENTHALPY ANALYTICAL

Batch QC

Type:	**Lab Control Sample**	**Lab ID:**	**QC1343119**	**Batch:**	**396077**
Matrix:	**Water**	**Method:**	**EPA 8081A**	**Prep Method:**	**EPA 3510C**

QC1343119 Analyte	Result	Spiked	Units	Recovery	Qual	Limits
alpha-BHC	0.5820	0.5000	ug/L	116%		66-121
beta-BHC	0.5036	0.5000	ug/L	101%		73-120
gamma-BHC	0.5751	0.5000	ug/L	115%		68-125
delta-BHC	0.6048	0.5000	ug/L	121%		68-131
Heptachlor	0.5575	0.5000	ug/L	112%		63-120
Aldrin	0.5066	0.5000	ug/L	101%		56-120
Heptachlor epoxide	0.5066	0.5000	ug/L	101%		65-120
Endosulfan I	0.5282	0.5000	ug/L	106%		68-124
Dieldrin	0.5117	0.5000	ug/L	102%		66-124
4,4'-DDE	0.5771	0.5000	ug/L	115%		67-131
Endrin	0.5664	0.5000	ug/L	113%		68-135
Endosulfan II	0.5169	0.5000	ug/L	103%		71-130
Endosulfan sulfate	0.5706	0.5000	ug/L	114%		68-128
4,4'-DDD	0.5348	0.5000	ug/L	107%		65-130
Endrin aldehyde	0.4895	0.5000	ug/L	98%		67-124
Endrin ketone	0.5896	0.5000	ug/L	118%		69-137
4,4'-DDT	0.5526	0.5000	ug/L	111%		65-136
Methoxychlor	0.5817	0.5000	ug/L	116%		69-150
Surrogates						
TCMX	0.4030	0.5000	ug/L	81%		29-120
Decachlorobiphenyl	0.5506	0.5000	ug/L	110%		33-132

Batch QC

Type:	Lab Control Sample Duplicate	Lab ID:	QC1343120	Batch:	396077
Matrix:	Water	Method:	EPA 8081A	Prep Method:	EPA 3510C

QC1343120 Analyte	Result	Spiked	Units	Recovery	Qual	Limits	RPD	RPD Lim
alpha-BHC	0.5242	0.5000	ug/L	105%		66-121	10	20
beta-BHC	0.4595	0.5000	ug/L	92%		73-120	9	20
gamma-BHC	0.5102	0.5000	ug/L	102%		68-125	12	20
delta-BHC	0.5429	0.5000	ug/L	109%		68-131	11	20
Heptachlor	0.4883	0.5000	ug/L	98%		63-120	13	24
Aldrin	0.4468	0.5000	ug/L	89%		56-120	13	30
Heptachlor epoxide	0.4498	0.5000	ug/L	90%		65-120	12	20
Endosulfan I	0.4733	0.5000	ug/L	95%		68-124	11	20
Dieldrin	0.4657	0.5000	ug/L	93%		66-124	9	22
4,4'-DDE	0.5143	0.5000	ug/L	103%		67-131	12	21
Endrin	0.5116	0.5000	ug/L	102%		68-135	10	20
Endosulfan II	0.4701	0.5000	ug/L	94%		71-130	9	21
Endosulfan sulfate	0.5303	0.5000	ug/L	106%		68-128	7	21
4,4'-DDD	0.4800	0.5000	ug/L	96%		65-130	11	22
Endrin aldehyde	0.4516	0.5000	ug/L	90%		67-124	8	20
Endrin ketone	0.5806	0.5000	ug/L	116%		69-137	2	21
4,4'-DDT	0.5169	0.5000	ug/L	103%		65-136	7	23
Methoxychlor	0.5628	0.5000	ug/L	113%		69-150	3	23
Surrogates								
TCMX	0.3680	0.5000	ug/L	74%		29-120		
Decachlorobiphenyl	0.5513	0.5000	ug/L	110%		33-132		

Type:	Lab Control Sample	Lab ID:	QC1343121	Batch:	396077
Matrix:	Water	Method:	EPA 8082	Prep Method:	EPA 3510C

QC1343121 Analyte	Result	Spiked	Units	Recovery	Qual	Limits
Aroclor-1016	5.021	5.000	ug/L	100%		69-120
Aroclor-1260	4.668	5.000	ug/L	93%		72-124
Surrogates						
Decachlorobiphenyl (PCB)	0.3945	0.5000	ug/L	79%		28-138

Type:	Lab Control Sample Duplicate	Lab ID:	QC1343122	Batch:	396077
Matrix:	Water	Method:	EPA 8082	Prep Method:	EPA 3510C

QC1343122 Analyte	Result	Spiked	Units	Recovery	Qual	Limits	RPD	RPD Lim
Aroclor-1016	4.883	5.000	ug/L	98%		69-120	3	22
Aroclor-1260	4.546	5.000	ug/L	91%		72-124	3	25
Surrogates								
Decachlorobiphenyl (PCB)	0.3967	0.5000	ug/L	79%		28-138		

ENTHALPY ANALYTICAL

Batch QC

Type: Blank	Lab ID: QC1343238	Batch: 396118
Matrix: Soil	Method: EPA 8082	Prep Method: EPA 3546

QC1343238 Analyte	Result	Qual	Units	RL	Prepared	Analyzed
Aroclor-1016	ND		ug/Kg	50	02/23/26	02/24/26
Aroclor-1221	ND		ug/Kg	50	02/23/26	02/24/26
Aroclor-1232	ND		ug/Kg	50	02/23/26	02/24/26
Aroclor-1242	ND		ug/Kg	50	02/23/26	02/24/26
Aroclor-1248	ND		ug/Kg	50	02/23/26	02/24/26
Aroclor-1254	ND		ug/Kg	50	02/23/26	02/24/26
Aroclor-1260	ND		ug/Kg	50	02/23/26	02/24/26
Aroclor-1262	ND		ug/Kg	50	02/23/26	02/24/26
Aroclor-1268	ND		ug/Kg	50	02/23/26	02/24/26
Total PCBs	ND		ug/Kg	50	02/23/26	02/24/26
Surrogates				**Limits**		
Decachlorobiphenyl (PCB)	100%		%REC	50-127	02/23/26	02/24/26

Type: Lab Control Sample	Lab ID: QC1343239	Batch: 396118
Matrix: Soil	Method: EPA 8082	Prep Method: EPA 3546

QC1343239 Analyte	Result	Spiked	Units	Recovery	Qual	Limits
Aroclor-1016	517.1	490.2	ug/Kg	105%		66-120
Aroclor-1260	564.6	490.2	ug/Kg	115%		63-126
Surrogates						
Decachlorobiphenyl (PCB)	52.23	49.02	ug/Kg	107%		50-127

Type: Matrix Spike	Lab ID: QC1343240	Batch: 396118
Matrix (Source ID): Soil (553642-008)	Method: EPA 8082	Prep Method: EPA 3546

QC1343240 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	DF
Aroclor-1016	560.3	ND	510.2	ug/Kg	110%		60-123	1
Aroclor-1260	619.8	ND	510.2	ug/Kg	121%		55-136	1
Surrogates								
Decachlorobiphenyl (PCB)	60.41		51.02	ug/Kg	118%		50-127	1

Type: Matrix Spike Duplicate	Lab ID: QC1343241	Batch: 396118
Matrix (Source ID): Soil (553642-008)	Method: EPA 8082	Prep Method: EPA 3546

QC1343241 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	RPD	RPD Lim	DF
Aroclor-1016	642.6	ND	510.2	ug/Kg	126%	*	60-123	14	37	1
Aroclor-1260	710.3	ND	510.2	ug/Kg	139%	*	55-136	14	41	1
Surrogates										
Decachlorobiphenyl (PCB)	69.36		51.02	ug/Kg	136%	*	50-127			1

ENTHALPY ANALYTICAL

Batch QC

Type:	**Blank**	**Lab ID:**	**QC1348030**	**Batch:**	**397475**
Matrix:	**Soil**	**Method:**	**EPA 8082**	**Prep Method:**	**EPA 3546**

QC1348030 Analyte	Result	Qual	Units	RL	Prepared	Analyzed
Aroclor-1016	ND		ug/Kg	49	03/09/26	03/11/26
Aroclor-1221	ND		ug/Kg	49	03/09/26	03/11/26
Aroclor-1232	ND		ug/Kg	49	03/09/26	03/11/26
Aroclor-1242	ND		ug/Kg	49	03/09/26	03/11/26
Aroclor-1248	ND		ug/Kg	49	03/09/26	03/11/26
Aroclor-1254	ND		ug/Kg	49	03/09/26	03/11/26
Aroclor-1260	ND		ug/Kg	49	03/09/26	03/11/26
Aroclor-1262	ND		ug/Kg	49	03/09/26	03/11/26
Aroclor-1268	ND		ug/Kg	49	03/09/26	03/11/26
Total PCBs	ND		ug/Kg	49	03/09/26	03/11/26
Surrogates				**Limits**		
Decachlorobiphenyl (PCB)	101%		%REC	50-127	03/09/26	03/11/26

Type:	**Matrix Spike**	**Lab ID:**	**QC1348034**	**Batch:**	**397475**
Matrix (Source ID):	**Soil (554861-005)**	**Method:**	**EPA 8082**	**Prep Method:**	**EPA 3546**

QC1348034 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	DF
Aroclor-1016	519.0	ND	500.0	ug/Kg	104%		60-123	1
Aroclor-1260	528.0	ND	500.0	ug/Kg	106%		55-136	1
Surrogates								
Decachlorobiphenyl (PCB)	48.74		50.00	ug/Kg	97%		50-127	1

Type:	**Matrix Spike Duplicate**	**Lab ID:**	**QC1348035**	**Batch:**	**397475**
Matrix (Source ID):	**Soil (554861-005)**	**Method:**	**EPA 8082**	**Prep Method:**	**EPA 3546**

QC1348035 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	RPD	RPD Lim	DF
Aroclor-1016	499.2	ND	505.1	ug/Kg	99%		60-123	5	37	1
Aroclor-1260	497.9	ND	505.1	ug/Kg	99%		55-136	7	41	1
Surrogates										
Decachlorobiphenyl (PCB)	45.13		50.51	ug/Kg	89%		50-127			1

Type:	**Lab Control Sample**	**Lab ID:**	**QC1348064**	**Batch:**	**397475**
Matrix:	**Soil**	**Method:**	**EPA 8082**	**Prep Method:**	**EPA 3546**

QC1348064 Analyte	Result	Spiked	Units	Recovery	Qual	Limits
Aroclor-1016	547.1	500.0	ug/Kg	109%		66-120
Aroclor-1260	578.6	500.0	ug/Kg	116%		63-126
Surrogates						
Decachlorobiphenyl (PCB)	55.53	50.00	ug/Kg	111%		50-127

Batch QC

#	CCV drift outside limits; average CCV drift within limits per method requirements
*	Value is outside QC limits
ND	Not Detected

Laboratory Job Number 553642

Subcontracted Products

AmeriSci Los Angeles

AmeriSci Richmond
13635 GENITO ROAD
MIDLOTHIAN, VIRGINIA 23112
TEL: (804) 763-1200 • FAX: (804) 763-0493

March 4, 2026

Enthalpy Analytical
Attn: Patty Mata
931 West Barkley Ave
Orange, CA 92868

RE: Enthalpy Analytical
Job Number 126022214
P.O. #098963
553642

Dear Patty Mata:

Enclosed are the results of Asbestos Analysis - Bulk Qualitative Protocol of the following Enthalpy Analytical samples, received at AmeriSci on Thursday, February 26, 2026, for a 5 day turnaround:

CG-34-0.5, CG-34-2.5, CG-35-0.5, CG-35-2.5, CG-36-0.5, CG-36-2.5, CG-39-0.5, CG-39-2.5, CG-33-0.5, CG-33-2.5, CG-37-0.5, CG-37-2.5, CG-34-0.5-DUP, CG-34-2.5-DUP

The 14 samples, placed in zip lock bag, were shipped to AmeriSci via Fed Ex 717839739830. Enthalpy Analytical requested Bulk-Qualitative analysis of these samples.

The samples were prepared and analyzed by using a Standard Operating Procedure developed by AmeriSci, Inc.. After preparation, using non-quantitative matrix reduction if necessary, the presence or absence of asbestos is determined by PLM and/or TEM as indicated on the attached summary table. Quantification after the fact is not possible without a new preparation. This report relates ONLY to the analysis expressed as "asbestos present" or "no asbestos visible". This report must not be used to claim product endorsement or approval by AmeriSci, NVLAP, ELAP or any other associated AmeriSci certifying agency. The National Institute of Standards and Technology accreditation requirements, mandate that this report must not be reproduced, except in full without the approval of the laboratory.

AmeriSci appreciates this opportunity to serve your organization. Please contact us for any further assistance or with any questions.

Sincerely,



Glenn F. Massey

QA Manager | Authorized Signatory

AmeriSci Richmond
13635 GENITO ROAD
MIDLOTHIAN, VIRGINIA 23112
TEL: (804) 763-1200 • FAX: (804) 763-0493

PLM Bulk Asbestos Report

Enthalpy Analytical
Attn: Patty Mata
931 West Barkley Ave

Orange, CA 92868

Date Received 2/26/2026
Date Examined 03/02/26

AmeriSci Job # 126022214
P.O. # 098963
Page 1 **of** 3

RE: 553642

Client No. / HGA	Lab No.	Asbestos Present	Total % Asbestos	Notes
CG-34-0.5	126022214-01	***No***	NVA by C. David Mintz on 03/02/26	*1*

Location:
Analyst Description: Brown, Homogeneous, Non-Fibrous, Soil
Asbestos Types:
Other Material: Non-fibrous Present

CG-34-2.5	126022214-02	***No***	NVA by C. David Mintz on 03/02/26	*1*

Location:
Analyst Description: Brown, Homogeneous, Non-Fibrous, Soil
Asbestos Types:
Other Material: Non-fibrous Present

CG-35-0.5	126022214-03	***No***	NVA by C. David Mintz on 03/02/26	*1*

Location:
Analyst Description: Brown, Homogeneous, Non-Fibrous, Soil
Asbestos Types:
Other Material: Non-fibrous Present

CG-35-2.5	126022214-04	***No***	NVA by C. David Mintz on 03/02/26	*1*

Location:
Analyst Description: Brown, Homogeneous, Non-Fibrous, Soil
Asbestos Types:
Other Material: Cellulose Present, Non-fibrous Present

CG-36-0.5	126022214-05	***No***	NVA by C. David Mintz on 03/02/26	*1*

Location:
Analyst Description: Brown, Homogeneous, Non-Fibrous, Soil
Asbestos Types:
Other Material: Non-fibrous Present

CG-36-2.5	126022214-06	***No***	NVA by C. David Mintz on 03/02/26	*1*

Location:
Analyst Description: Brown, Homogeneous, Non-Fibrous, Soil
Asbestos Types:
Other Material: Non-fibrous Present

See Reporting notes on last page

PLM Bulk Asbestos Report

553642

Client No. / HGA	Lab No.	Asbestos Present	Total % Asbestos	Notes
CG-39-0.5	126022214-07	***No***	NVA by C. David Mintz on 03/02/26	*1*
Location: **Analyst Description:** Brown, Homogeneous, Non-Fibrous, Soil **Asbestos Types:** **Other Material:** Non-fibrous Present				
CG-39-2.5	126022214-08	***No***	NVA by C. David Mintz on 03/02/26	*1*
Location: **Analyst Description:** Brown, Homogeneous, Non-Fibrous, Soil **Asbestos Types:** **Other Material:** Non-fibrous Present				
CG-33-0.5	126022214-09	***No***	NVA by C. David Mintz on 03/02/26	*1*
Location: **Analyst Description:** Brown, Homogeneous, Non-Fibrous, Soil **Asbestos Types:** **Other Material:** Cellulose Present, Non-fibrous Present				
CG-33-2.5	126022214-10	***No***	NVA by C. David Mintz on 03/02/26	*1*
Location: **Analyst Description:** Brown, Homogeneous, Non-Fibrous, Soil **Asbestos Types:** **Other Material:** Cellulose Present, Non-fibrous Present				
CG-37-0.5	126022214-11	***No***	NVA by C. David Mintz on 03/02/26	*1*
Location: **Analyst Description:** Brown, Homogeneous, Non-Fibrous, Soil **Asbestos Types:** **Other Material:** Non-fibrous Present				
CG-37-2.5	126022214-12	***No***	NVA by C. David Mintz on 03/02/26	*1*
Location: **Analyst Description:** Brown, Homogeneous, Non-Fibrous, Soil **Asbestos Types:** **Other Material:** Non-fibrous Present				
CG-34-0.5-DUP	126022214-13	***No***	NVA by C. David Mintz on 03/02/26	*1*
Location: **Analyst Description:** Brown, Homogeneous, Non-Fibrous, Soil **Asbestos Types:** **Other Material:** Non-fibrous Present				

See Reporting notes on last page

PLM Bulk Asbestos Report


553642

Client No. / HGA	Lab No.	Asbestos Present	Total % Asbestos	Notes
CG-34-2.5-DUP	126022214-14	***No***	NVA by C. David Mintz on 03/02/26	*1*

Location:
Analyst Description: Brown, Homogeneous, Non-Fibrous, Soil
Asbestos Types:
Other Material: Non-fibrous Present

Reporting Notes:

(1) Sample homogenized by grinding to a powder prior to analysis.

Analyzed by: C. David Mintz 
Date: 3/2/2026

Reviewed by: Glenn F. Massey 

*NAD = no asbestos detected, Detection Limit <1%, Reporting Limits: CVES = 1%, 400 Pt Ct = 0.25%, 1000 Pt Ct = 0.1%; "Present" or NVA = "No Visible Asbestos" are observations made during a qualitative analysis (Not covered by NVLAP or NY ELAP accreditations); NA = not analyzed; NA/PS = not analyzed / positive stop; PLM Bulk Asbestos Analysis using Olympus, Model BH-2 microscope, Serial #210972, by EPA 600/R-93/116 per 40 CFR 763 (NVLAP Lab Code 101904-0) and ELAP PLM Analysis Protocol 198.1 for New York friable samples which includes quantitation of any vermiculite observed (198.6 for NOB samples) or EPA 400 pt ct by EPA 600/M4-82-020 (NYSDOH ELAP Lab # 10984); CA ELAP Lab # 2508; Note: PLM is not consistently reliable in detecting asbestos in floor coverings and similar NOB materials. NAD or Trace results by PLM are inconclusive, TEM is currently the only method that can be used to determine if this material can be considered or treated as non-asbestos-containing in New York State (also see EPA Advisory for floor tile, FR 59, 146, 38970, 8/1/94). NIST Accreditation requirements mandate that this report must not be reproduced except in full without the approval of the laboratory. This PLM report relates ONLY to the items tested.

Subject: Re: [External] - ACTION NEEDED/PLEASE SUPPLY PO#s
From: Jocelyn Nguyen <JocelynNguyen@enthalpy.com>
Date: 2/26/2026, 4:34 PM
To: Tiffany Goodwyn <varesults@amerisci.com>, Patricia Mata <patty.mata@enthalpy.com>

Hi Tiffany,
No problem. You can reference PO-098963 for both of these COC.

Thank you,

Jocelyn Nguyen
Project Manager Assistant
Enthalpy Analytical
931 W Barkley Ave. | Orange, CA 92868
Office: +1-714-771-6900 X 10315
JocelynNguyen@enthalpy.com |enthalpy.com
Terms and Conditions

From: Tiffany Goodwyn <varesults@amerisci.com>
Sent: Thursday, February 26, 2026 12:58 PM
To: Patricia Mata <patty.mata@enthalpy.com>; Jocelyn Nguyen <JocelynNguyen@enthalpy.com>
Cc: varesults@amerisci.com <varesults@amerisci.com>
Subject: [External] - ACTION NEEDED/PLEASE SUPPLY PO#s

Hey there,

I apologize.

We were not thinking that since we are splitting jobs from you guys into two different AmeriSci #s due to different analyses, its best to include both of those #s in the same email when requesting POs to hopefully cut down on the confusion.

So, I will need a PO# for your EO# 553642 (AmeriSci #s 126022212 & 2214)

I have attached the COC(s) below

thank you

tif

CONFIDENTIALITY NOTICE: The contents of this email message and any attachments are intended solely for the addressee(s) and may contain confidential, proprietary and/or privileged information and may be legally protected

ENTHALPY ANALYTICAL

931 West Barkley Ave
Orange, CA 92868
(714) 771-6900

126022214

Subcontract Laboratory:
AmeriSci Los Angeles
24416 S. Main Street
Suite 308
Carson, CA 90745
ATTN: Sample Control
PO #: Required, to be sent via email

Enthalpy Order: EO-553642
PM: Patty Mata
Email: patty.mata@enthalpy.com
CC: incomingreports@enthalpy.com
Phone: (714) 771-6900

Results Due: Standard TAT
Report Level: II
Report To: RL
EDDs:

Notes:

Sample ID	Collected	Lab ID	# Cont.	Matrix	Analysis Requested	Comment
CG-34-0.5	18-FEB-2026 00:00	553642-019	1	Soil	Asbestos by PLM	PLM Qualitative
CG-34-2.5	18-FEB-2026 00:00	553642-020	1	Soil	Asbestos by PLM	PLM Qualitative
CG-35-0.5	18-FEB-2026 00:00	553642-021	1	Soil	Asbestos by PLM	PLM Qualitative
CG-35-2.5	18-FEB-2026 00:00	553642-022	1	Soil	Asbestos by PLM	PLM Qualitative
CG-36-0.5	18-FEB-2026 00:00	553642-023	1	Soil	Asbestos by PLM	PLM Qualitative
CG-36-2.5	18-FEB-2026 00:00	553642-024	1	Soil	Asbestos by PLM	PLM Qualitative
CG-39-0.5	18-FEB-2026 00:00	553642-025	1	Soil	Asbestos by PLM	PLM Qualitative
CG-39-2.5	18-FEB-2026 00:00	553642-026	1	Soil	Asbestos by PLM	PLM Qualitative
CG-33-0.5	18-FEB-2026 00:00	553642-027	1	Soil	Asbestos by PLM	PLM Qualitative
CG-33-2.5	18-FEB-2026 00:00	553642-028	1	Soil	Asbestos by PLM	PLM Qualitative
CG-37-0.5	18-FEB-2026 00:00	553642-049	1	Soil	Asbestos by PLM	PLM Qualitative
CG-37-2.5	18-FEB-2026 00:00	553642-050	1	Soil	Asbestos by PLM	PLM Qualitative
EB-01-260218	18-FEB-2026 16:00	553642-051	1	Water	Asbestos	Non-potable water TEM
CG-34-0.5-DUP	18-FEB-2026 00:00	553642-052	1	Soil	Asbestos by PLM	PLM Qualitative
CG-34-2.5-DUP	18-FEB-2026 00:00	553642-053	1	Soil	Asbestos by PLM	PLM Qualitative

Notes:	Relinquished By:	Received By:
	[signature]	M. RIVERO
	Date: 2-23-26 1212	Date: 2/23/26 @ 1215
	M. RIVERO	
	Date: 2/23/26 @ 1215	Date:
	Date:	Date:

Received
FEB 26 2026
KHH

ENTHALPY ANALYTICAL
931 West Barkley Ave
Orange, CA 92868
(714) 771-6900

126022214

Subcontract Laboratory:
AmeriSci Los Angeles
24416 S. Main Street
Suite 308
Carson, CA 90745
ATTN: Sample Control
PO #: Required, to be sent via email

Enthalpy Order: EO-553642
PM: Patty Mata
Email: patty.mata@enthalpy.com
CC: incomingreports@enthalpy.com
Phone: (714) 771-6900

Results Due: Standard TAT
Report Level: II
Report To: RL
EDDs:

Notes:

Sample ID	Collected	Lab ID	# Cont.	Matrix	Analysis Requested	Comment
CG-34-0.5	18-FEB-2026 00:00	553642-019	1	Soil	Asbestos by PLM	PLM Qualitative
CG-34-2.5	18-FEB-2026 00:00	553642-020	1	Soil	Asbestos by PLM	PLM Qualitative
CG-35-0.5	18-FEB-2026 00:00	553642-021	1	Soil	Asbestos by PLM	PLM Qualitative
CG-35-2.5	18-FEB-2026 00:00	553642-022	1	Soil	Asbestos by PLM	PLM Qualitative
CG-36-0.5	18-FEB-2026 00:00	553642-023	1	Soil	Asbestos by PLM	PLM Qualitative
CG-36-2.5	18-FEB-2026 00:00	553642-024	1	Soil	Asbestos by PLM	PLM Qualitative
CG-39-0.5	18-FEB-2026 00:00	553642-025	1	Soil	Asbestos by PLM	PLM Qualitative
CG-39-2.5	18-FEB-2026 00:00	553642-026	1	Soil	Asbestos by PLM	PLM Qualitative
CG-33-0.5	18-FEB-2026 00:00	553642-027	1	Soil	Asbestos by PLM	PLM Qualitative
CG-33-2.5	18-FEB-2026 00:00	553642-028	1	Soil	Asbestos by PLM	PLM Qualitative
CG-37-0.5	18-FEB-2026 00:00	553642-049	1	Soil	Asbestos by PLM	PLM Qualitative
CG-37-2.5	18-FEB-2026 00:00	553642-050	1	Soil	Asbestos by PLM	PLM Qualitative
EB-01-260218	18-FEB-2026 16:00	553642-051	1	Water	Asbestos	Non-potable water TEM
CG-34-0.5-DUP	18-FEB-2026 00:00	553642-052	1	Soil	Asbestos by PLM	PLM Qualitative
CG-34-2.5-DUP	18-FEB-2026 00:00	553642-053	1	Soil	Asbestos by PLM	PLM Qualitative

Notes:	Relinquished By:	Received By:
	[signature]	M.RIVERO
	Date: 2-23-26 1212	Date: 2/23/26 @ 1215
	M.RIVERO	
	Date: 2/23/26 @ 1215	Date:
	Date:	Date:

Received
FEB 26 2026
BHM

AmeriSci Richmond
13635 GENITO ROAD
MIDLOTHIAN, VIRGINIA 23112
TEL: (804) 763-1200 • FAX: (804) 763-0493

March 4, 2026

Enthalpy Analytical
Attn: Patty Mata
931 West Barkley Ave
Orange, CA 92868

RE: Enthalpy Analytical
Job Number 126022212
P.O. #098963
553642

Dear Patty Mata:

Enclosed are the results for TEM asbestos analysis of the following Enthalpy Analytical samples received at AmeriSci on Thursday, February 26, 2026, for a 5 day turnaround:

EB-01-260218

The 1 samples were filtered and prepared according to Water analysis under the EPA-600/4-83-043 "Analytical Method for Determination of Asbestos Fibers in Water" (1983). Samples with high organic content may be prepared following EPA-600/4-80-005 if necessary and are so noted on the TEM count sheets. AmeriSci, Inc. uses the "Grid Square" method of counting and the concentration is calculated in millions of fibers per liter (MFL).

Table I represents a summary of all pertinent information used for the calculations. Included are the size of each structure counted, concentration, structure concentration greater than 10 microns in length, type of asbestiform material detected and the analytical sensitivity, which represents the concentration by the detection of one fiber in the TEM fiber count. Copies of the Fiber Count Sheets, show the raw data for examination. These data sheets contain information for fiber length/width, fiber type, structure morphology and pertinent information on EDS, SAED and photography.

This report relates ONLY to the sample analysis expressed as millions of fibers per liter (MFL). AmeriSci assumes no responsibility for customer supplied data such as “sample location” or “the condition of the water sample before arriving at AmeriSci”. This report must not be used to claim product endorsement by AmeriSci, NVLAP, ELAP or any agency of the U. S. Government. The National Institute of Standards and Technology accreditation requirements, mandate that this report must not be reproduced, except in full without the approval of the laboratory.

AmeriSci appreciates this opportunity to serve your organization. Please contact us for any further assistance or with any questions.

Sincerely,



Cory M. Parnell

Laboratory Director | Authorized Signatory

AmeriSci Job #: **126022212**
Client Name: Enthalpy Analytical

Table I
Summary of Transmission Electron Microscopy (TEM) Results for Asbestos (Water)


553642

AmeriSci Sample #	Client Sample No./Location	Liquid Filtered (liters)	Temp (Celcius)	Structures Detected* (total)	Structures Detected* (>10 µm)	Analytical Sensitivity (MF/L)	Asbestos Conc (total) (MF/L)	Asbestos Conc (>10 µm) (MF/L)	Asbestos Type
01	EB-01-260218	0.01	17.8	NSD	NSD	0.22	<0.22	<0.22	----

* NAD/NSD = no asbestos detected, NA = not analyzed, MF/L = million fibers per liter; Drinking Water accreditations do not cover waste water analysis. NOTE: Drinking water analysis by EPA-600/4-83-043 (100.1). Fiber criteria (>=0.5 microns, for 100.1; >10 microns for 100.2; 5:1 aspect ratio for both), organic rich waste water prepped by EPA-600/4-80-005. Analytical sensitivity calculated as though 1 fiber had been detected on the TEM GRID area analyzed. Sample temperatures reported above were measured upon receipt. Water samples are refrigerated upon receipt and filtered within four hours.

Reviewed By: _____ Analyzed By: Cory M. Parnell _____ Date: 3/4/2026

TEM Asbestos (Water) Count Sheet



Client Name:	Enthalpy Analytical		
Job #:	126022212	Volume (liters):	0.01
Lab Sample #:	01	Filter Type / Filter Area:	MCE 214 mm2
Client Sample #:	EB-01-260218	Grid Opening Size:	0.00967
Received:	2/26/2026 12:00:00	Area Examined:	0.09670 mm2
Date Analyzed:	3/4/2026	Magnification:	20,000
	Temp: 17.8	Accelerating Voltage:	100 KeV

Analysis Performed by: Cory M. Parnell

Location	Grid Opening	Fiber	Length µM	Width µM	Fiber Type	Morphology	EDS	Orient.	SAED	Photo
C5-D2	1	NSD							☐	
C5-D4	2	NSD							☐	
C5-D6	3	NSD							☐	
C5-D8	4	NSD							☐	
C5-D10	5	NSD							☐	
D1-C2	6	NSD							☐	
D1-C4	7	NSD							☐	
D1-C6	8	NSD							☐	
D1-C8	9	NSD							☐	
D1-C10	10	NSD							☐	

NSD: No Asbestos Structures Detected

Scope #: Front 4: Jeol JEM-100CX II, Serial No.156147-247

Comments

		Concentration (million fibers/liter)	Grid Evaluation
Total Grid Openings:	10		☑ Grid Openings Covered > 50%
Chrysotile Asbestos Structures:	0	<0.221	☑ Intact Grid Opening > 50%
Amphibole Asbestos Structures:	0	<0.221	☑ Undissolved Filter < 10%
Asbestos Structures >10 microns:	0	<0.221	☑ Folded Replica < 50%
Total Asbestos Structures:	0	<0.221	☑ Filter Loading < 25%
Analytical Sensitivity:		0.221	☑ Particulate Even

Subject: Re: [External] - ACTION NEEDED/PLEASE SUPPLY PO#s
From: Jocelyn Nguyen <JocelynNguyen@enthalpy.com>
Date: 2/26/2026, 4:34 PM
To: Tiffany Goodwyn <varesults@amerisci.com>, Patricia Mata <patty.mata@enthalpy.com>

Hi Tiffany,
No problem. You can reference PO-098963 for both of these COC.

Thank you,

Jocelyn Nguyen
Project Manager Assistant
Enthalpy Analytical
931 W Barkley Ave. | Orange, CA 92868
Office: +1-714-771-6900 X 10315
JocelynNguyen@enthalpy.com |enthalpy.com
Terms and Conditions

From: Tiffany Goodwyn <varesults@amerisci.com>
Sent: Thursday, February 26, 2026 12:58 PM
To: Patricia Mata <patty.mata@enthalpy.com>; Jocelyn Nguyen <JocelynNguyen@enthalpy.com>
Cc: varesults@amerisci.com <varesults@amerisci.com>
Subject: [External] - ACTION NEEDED/PLEASE SUPPLY PO#s

Hey there,

I apologize.

We were not thinking that since we are splitting jobs from you guys into two different AmeriSci #s due to different analyses, its best to include both of those #s in the same email when requesting POs to hopefully cut down on the confusion.

So, I will need a PO# for your EO# 553642 (AmeriSci #s 126022212 & 2214)

I have attached the COC(s) below

thank you

tif

CONFIDENTIALITY NOTICE: The contents of this email message and any attachments are intended solely for the addressee(s) and may contain confidential, proprietary and/or privileged information and may be legally protected

ENTHALPY ANALYTICAL

931 West Barkley Ave
Orange, CA 92868
(714) 771-6900

126022212

Subcontract Laboratory:
AmeriSci Los Angeles
24416 S. Main Street
Suite 308
Carson, CA 90745
ATTN: Sample Control
PO #: Required, to be sent via email

Enthalpy Order: EO-553642
PM: Patty Mata
Email: patty.mata@enthalpy.com
CC: incomingreports@enthalpy.com
Phone: (714) 771-6900

Results Due: Standard TAT
Report Level: II
Report To: RL
EDDs:

Notes:

Sample ID	Collected	Lab ID	# Cont.	Matrix	Analysis Requested	Comment
CG-34-0.5	18-FEB-2026 00:00	553642-019	1	Soil	Asbestos by PLM	PLM Qualitative
CG-34-2.5	18-FEB-2026 00:00	553642-020	1	Soil	Asbestos by PLM	PLM Qualitative
CG-35-0.5	18-FEB-2026 00:00	553642-021	1	Soil	Asbestos by PLM	PLM Qualitative
CG-35-2.5	18-FEB-2026 00:00	553642-022	1	Soil	Asbestos by PLM	PLM Qualitative
CG-36-0.5	18-FEB-2026 00:00	553642-023	1	Soil	Asbestos by PLM	PLM Qualitative
CG-36-2.5	18-FEB-2026 00:00	553642-024	1	Soil	Asbestos by PLM	PLM Qualitative
CG-39-0.5	18-FEB-2026 00:00	553642-025	1	Soil	Asbestos by PLM	PLM Qualitative
CG-39-2.5	18-FEB-2026 00:00	553642-026	1	Soil	Asbestos by PLM	PLM Qualitative
CG-33-0.5	18-FEB-2026 00:00	553642-027	1	Soil	Asbestos by PLM	PLM Qualitative
CG-33-2.5	18-FEB-2026 00:00	553642-028	1	Soil	Asbestos by PLM	PLM Qualitative
CG-37-0.5	18-FEB-2026 00:00	553642-049	1	Soil	Asbestos by PLM	PLM Qualitative
CG-37-2.5	18-FEB-2026 00:00	553642-050	1	Soil	Asbestos by PLM	PLM Qualitative
EB-01-260218	18-FEB-2026 16:00	553642-051	1	Water	Asbestos	Non-potable water TEM
CG-34-0.5-DUP	18-FEB-2026 00:00	553642-052	1	Soil	Asbestos by PLM	PLM Qualitative
CG-34-2.5-DUP	18-FEB-2026 00:00	553642-053	1	Soil	Asbestos by PLM	PLM Qualitative

Notes:	Relinquished By:	Received By:
	[signature]	M. RIVERO
	Date: 2-23-26 1212	Date: 2/23/26 @ 1215
	M. RIVERO	
	Date: 2/23/26 @ 1215	Date:
	Date:	Date:

Received
FEB 26 2026
KHN

Enthalpy Analytical
931 West Barkley Ave
Orange, CA 92868
(714) 771-6900

enthalpy.com

Lab Job Number : 553784
Report Level : II
Report Date : 03/06/2026

Analytical Report *prepared for:*

Vanya Keyes
Terraphase Engineering
18401 Von Karman Ave, Suite #410
Irvine, CA 92612

Project: CENTENNIAL HS - Centennial High School, 2606 N Central Ave., Compton, CA 90222

Authorized for release by:



Patty Mata, Project Manager
patty.mata@enthalpy.com

This data package has been reviewed for technical correctness and completeness. Release of this data has been authorized by the Laboratory Manager or the Manager's designee, as verified by the above signature which applies to this PDF file as well as any associated electronic data deliverable files. The results contained in this report meet all requirements of NELAP and pertain only to those samples which were submitted for analysis. This report may be reproduced only in its entirety.

CA ELAP# 1338, CA ELAP #1338-S1, NELAP# 4038, SCAQMD LAP# 18LA0518, LACSD ID# 10105, ORELAP# 4197

ENTHALPY ANALYTICAL

Sample Summary

Vanya Keyes
Terraphase Engineering
18401 Von Karman Ave, Suite #410
Irvine, CA 92612

Lab Job #: 553784
Project No: CENTENNIAL HS
Location: Centennial High School, 2606 N Central Ave., Compton, CA 90222
Date Received: 02/19/26

Sample ID	Lab ID	Collected	Matrix
AOC4-SB-28-0.5	553784-001	02/19/26 08:00	Soil
AOC4-SB-29-0.5	553784-002	02/19/26 08:15	Soil
AOC4-SB-30-0.5	553784-003	02/19/26 08:41	Soil
AOC4-SB-28-2.5	553784-004	02/19/26 08:02	Soil
AOC4-SB-29-2.5	553784-005	02/19/26 08:19	Soil
AOC4-SB-30-2.5	553784-006	02/19/26 08:46	Soil
AOC4-SB-34-0.5	553784-007	02/19/26 10:13	Soil
AOC4-SB-35-0.5	553784-008	02/19/26 09:16	Soil
AOC4-SB-36-0.5	553784-009	02/19/26 09:50	Soil
AOC4-SB-34-2.5	553784-010	02/19/26 10:18	Soil
AOC4-SB-35-2.5	553784-011	02/19/26 09:21	Soil
AOC4-SB-36-2.5	553784-012	02/19/26 09:55	Soil
AOC4-SB-37-0.5	553784-013	02/19/26 10:30	Soil
AOC4-SB-38-0.5	553784-014	02/19/26 10:43	Soil
AOC4-SB-39-0.5	553784-015	02/19/26 10:57	Soil
DUP-01-0.5-260219	553784-016	02/19/26 00:00	Soil
AOC4-SB-40-0.5	553784-017	02/19/26 11:06	Soil
AOC4-SB-41-0.5	553784-018	02/19/26 13:09	Soil
AOC4-SB-42-0.5	553784-019	02/19/26 13:00	Soil
AOC4-SB-37-2.5	553784-020	02/19/26 10:35	Soil
AOC4-SB-38-2.5	553784-021	02/19/26 10:48	Soil
AOC4-SB-39-2.5	553784-022	02/19/26 11:02	Soil
DUP-01-2.5-260219	553784-023	02/19/26 00:00	Soil
AOC4-SB-40-2.5	553784-024	02/19/26 11:11	Soil
AOC4-SB-41-2.5	553784-025	02/19/26 13:14	Soil
AOC4-SB-42-2.5	553784-026	02/19/26 13:05	Soil

ENTHALPY ANALYTICAL

Sample Summary

Vanya Keyes
Terraphase Engineering
18401 Von Karman Ave, Suite #410
Irvine, CA 92612

Lab Job #: 553784
Project No: CENTENNIAL HS
Location: Centennial High School, 2606 N Central Ave., Compton, CA 90222
Date Received: 02/19/26

Sample ID	Lab ID	Collected	Matrix
AOC4-SB-43-0.5	553784-027	02/19/26 13:34	Soil
AOC4-SB-44-0.5	553784-028	02/19/26 13:47	Soil
AOC4-SB-45-0.5	553784-029	02/19/26 13:58	Soil
AOC4-SB-43-2.5	553784-030	02/19/26 13:40	Soil
AOC4-SB-44-2.5	553784-031	02/19/26 13:52	Soil
AOC4-SB-45-2.5	553784-032	02/19/26 14:02	Soil
CG-43-0.5	553784-033	02/19/26 00:00	Soil
CG-43-2.5	553784-034	02/19/26 00:00	Soil
EB-01-260219	553784-035	02/19/26 15:30	Water
CG-38-0.5	553784-036	02/19/26 00:00	Soil
CG-38-2.5	553784-037	02/19/26 00:00	Soil
CG-38-0.5-DUP	553784-038	02/19/26 00:00	Soil
CG-38-2.5-DUP	553784-039	02/19/26 00:00	Soil
CG-40-0.5	553784-040	02/19/26 00:00	Soil
CG-40-2.5	553784-041	02/19/26 00:00	Soil
CG-41-0.5	553784-042	02/19/26 00:00	Soil
CG-41-2.5	553784-043	02/19/26 00:00	Soil
CG-42-0.5	553784-044	02/19/26 00:00	Soil
CG-42-2.5	553784-045	02/19/26 00:00	Soil

Case Narrative

Terraphase Engineering 18401 Von Karman Ave, Suite #410 Irvine, CA 92612 Vanya Keyes	Lab Job Number: 553784 Project No: CENTENNIAL HS Location: Centennial High School, 2606 N Central Ave., Compton, CA 90222 Date Received: 02/19/26

This data package contains sample and QC results for sixteen soil samples, ten three-point soil composites, and one water sample, requested for the above referenced project on 02/20/26. The samples were received in good condition.

Pesticides (EPA 8081A) Water:
No analytical problems were encountered.

Pesticides (EPA 8081A) Soil:

- CG-43-0.5 (lab # 553784-033) and CG-43-2.5 (lab # 553784-034) were diluted due to the color of the sample extracts. Extract color and/or viscosity are used as indicators of possible matrix interference. Elevated reporting limits were due to the necessary dilutions.
- For selected samples, the presence of selected target compounds was confirmed but the relative percent difference (RPD) between columns exceeded 40%. Affected results were flagged with "C" qualifiers.
- No other analytical problems were encountered.

PCBs (EPA 8082) Water:
No analytical problems were encountered.

PCBs (EPA 8082) Soil:

- AOC4-SB-42-0.5 (lab # 553784-019) was treated with sulfuric acid to reduce analytical interferences or due to the presence of color.
- No other analytical problems were encountered.

Metals (EPA 6010B) Water:
No analytical problems were encountered.

Metals (EPA 6010B) Soil:
No analytical problems were encountered.

100.1 Asbestos (EPA 100.1 Asbestos):
AmeriSci Los Angeles in Carson, CA performed the analysis (see sublab report section for certifications). Please see the AmeriSci Los Angeles case narrative.

Asbestos by PLM (EPA 600/R-93-116):
AmeriSci Los Angeles in Carson, CA performed the analysis (see sublab report section for certifications). Please see the AmeriSci Los Angeles case narrative.

ENTHALPY ANALYTICAL

Detection Summary

Vanya Keyes
Terraphase Engineering
18401 Von Karman Ave, Suite #410
Irvine, CA 92612

Lab Job #: 553784
Project No: CENTENNIAL HS
Location: Centennial High School, 2606 N Central Ave., Compton, CA 90222
Date Received: 02/19/26

Sample ID: AOC4-SB-28-0.5 **Lab ID: 553784-001** **Collected: 02/19/26 08:00**
Matrix: Soil

553784-001 Analyte	Result	Qual	Units	RL
Method: EPA 6010B Prep Method: EPA 3050B				
Lead	**13**		mg/Kg	1.0

Sample ID: AOC4-SB-29-0.5 **Lab ID: 553784-002** **Collected: 02/19/26 08:15**
Matrix: Soil

553784-002 Analyte	Result	Qual	Units	RL
Method: EPA 6010B Prep Method: EPA 3050B				
Lead	**6.4**		mg/Kg	1.0

Sample ID: AOC4-SB-30-0.5 **Lab ID: 553784-003** **Collected: 02/19/26 08:41**
Matrix: Soil

553784-003 Analyte	Result	Qual	Units	RL
Method: EPA 6010B Prep Method: EPA 3050B				
Lead	**9.1**		mg/Kg	0.98

Sample ID: AOC4-SB-34-0.5 **Lab ID: 553784-007** **Collected: 02/19/26 10:13**
Matrix: Soil

553784-007 Analyte	Result	Qual	Units	RL
Method: EPA 6010B Prep Method: EPA 3050B				
Lead	**58**		mg/Kg	0.95

Sample ID: AOC4-SB-35-0.5 **Lab ID: 553784-008** **Collected: 02/19/26 09:16**
Matrix: Soil

553784-008 Analyte	Result	Qual	Units	RL
Method: EPA 6010B Prep Method: EPA 3050B				
Lead	**4.3**		mg/Kg	0.96

Results for any subcontracted analyses are not included in this summary. Data qualifiers and additional information necessary for the interpretation of the test results are contained in the PDF file and may not be included in this summary.

ENTHALPY ANALYTICAL

Detection Summary

Sample ID: AOC4-SB-36-0.5 **Lab ID: 553784-009** **Collected: 02/19/26 09:50**
Matrix: Soil

553784-009 Analyte	Result	Qual	Units	RL
Method: EPA 6010B Prep Method: EPA 3050B				
Lead	**8.4**		mg/Kg	0.98

Sample ID: AOC4-SB-37-0.5 **Lab ID: 553784-013** **Collected: 02/19/26 10:30**
Matrix: Soil

553784-013 Analyte	Result	Qual	Units	RL
Method: EPA 6010B Prep Method: EPA 3050B				
Lead	**38**		mg/Kg	0.97
Method: EPA 8082 Prep Method: EPA 3546				
Aroclor-1260	**190**		ug/Kg	51
Total PCBs	**190**		ug/Kg	51

Sample ID: AOC4-SB-38-0.5 **Lab ID: 553784-014** **Collected: 02/19/26 10:43**
Matrix: Soil

553784-014 Analyte	Result	Qual	Units	RL
Method: EPA 6010B Prep Method: EPA 3050B				
Lead	**38**		mg/Kg	0.99

Sample ID: AOC4-SB-39-0.5 **Lab ID: 553784-015** **Collected: 02/19/26 10:57**
Matrix: Soil

553784-015 Analyte	Result	Qual	Units	RL
Method: EPA 6010B Prep Method: EPA 3050B				
Lead	**20**		mg/Kg	0.95

Sample ID: DUP-01-0.5-260219 **Lab ID: 553784-016** **Collected: 02/19/26**
Matrix: Soil

553784-016 Analyte	Result	Qual	Units	RL
Method: EPA 6010B Prep Method: EPA 3050B				
Lead	**24**		mg/Kg	0.98
Method: EPA 8082 Prep Method: EPA 3546				
Aroclor-1260	**58**		ug/Kg	50
Total PCBs	**58**		ug/Kg	50

Results for any subcontracted analyses are not included in this summary. Data qualifiers and additional information necessary for the interpretation of the test results are contained in the PDF file and may not be included in this summary.

ENTHALPY ANALYTICAL

Detection Summary

Sample ID: AOC4-SB-40-0.5 **Lab ID: 553784-017** **Collected: 02/19/26 11:06**
Matrix: Soil

553784-017 Analyte	Result	Qual	Units	RL
Method: EPA 6010B Prep Method: EPA 3050B				
Lead	**10**		mg/Kg	1.0

Sample ID: AOC4-SB-41-0.5 **Lab ID: 553784-018** **Collected: 02/19/26 13:09**
Matrix: Soil

553784-018 Analyte	Result	Qual	Units	RL
Method: EPA 6010B Prep Method: EPA 3050B				
Lead	**15**		mg/Kg	0.96

Sample ID: AOC4-SB-42-0.5 **Lab ID: 553784-019** **Collected: 02/19/26 13:00**
Matrix: Soil

553784-019 Analyte	Result	Qual	Units	RL
Method: EPA 6010B Prep Method: EPA 3050B				
Lead	**18**		mg/Kg	1.0
Method: EPA 8082 Prep Method: EPA 3546				
Aroclor-1254	**160**		ug/Kg	51
Total PCBs	**160**		ug/Kg	51

Sample ID: AOC4-SB-43-0.5 **Lab ID: 553784-027** **Collected: 02/19/26 13:34**
Matrix: Soil

553784-027 Analyte	Result	Qual	Units	RL
Method: EPA 6010B Prep Method: EPA 3050B				
Lead	**24**		mg/Kg	0.96

Sample ID: AOC4-SB-44-0.5 **Lab ID: 553784-028** **Collected: 02/19/26 13:47**
Matrix: Soil

553784-028 Analyte	Result	Qual	Units	RL
Method: EPA 6010B Prep Method: EPA 3050B				
Lead	**27**		mg/Kg	1.0

Results for any subcontracted analyses are not included in this summary. Data qualifiers and additional information necessary for the interpretation of the test results are contained in the PDF file and may not be included in this summary.

ENTHALPY ANALYTICAL

Detection Summary

Sample ID: AOC4-SB-45-0.5	Lab ID: 553784-029	Collected: 02/19/26 13:58
	Matrix: Soil	

553784-029 Analyte	Result	Qual	Units	RL
Method: EPA 6010B Prep Method: EPA 3050B				
Lead	**34**		mg/Kg	0.98

Sample ID: CG-43-0.5	Lab ID: 553784-033	Collected: 02/19/26

No Detections

Sample ID: CG-43-2.5	Lab ID: 553784-034	Collected: 02/19/26

No Detections

Sample ID: EB-01-260219	Lab ID: 553784-035	Collected: 02/19/26 15:30

No Detections

Sample ID: CG-38-0.5	Lab ID: 553784-036	Collected: 02/19/26

No Detections

Sample ID: CG-38-2.5	Lab ID: 553784-037	Collected: 02/19/26

No Detections

Sample ID: CG-38-0.5-DUP	Lab ID: 553784-038	Collected: 02/19/26

No Detections

Sample ID: CG-38-2.5-DUP	Lab ID: 553784-039	Collected: 02/19/26

No Detections

Sample ID: CG-40-0.5	Lab ID: 553784-040	Collected: 02/19/26
	Matrix: Soil	

553784-040 Analyte	Result	Qual	Units	RL
Method: EPA 8081A Prep Method: EPA 3546				
Dieldrin	**12**	C	ug/Kg	4.9
4,4'-DDE	**150**		ug/Kg	4.9
4,4'-DDT	**42**		ug/Kg	4.9
Chlordane (Technical)	**110**		ug/Kg	49

Results for any subcontracted analyses are not included in this summary. Data qualifiers and additional information necessary for the interpretation of the test results are contained in the PDF file and may not be included in this summary.

ENTHALPY ANALYTICAL

Detection Summary

Sample ID: CG-40-2.5	Lab ID: 553784-041	Collected: 02/19/26

No Detections

Sample ID: CG-41-0.5	Lab ID: 553784-042	Collected: 02/19/26
	Matrix: Soil	

553784-042 Analyte		Result	Qual	Units	RL
Method: EPA 8081A Prep Method: EPA 3546					
	4,4'-DDE	**14**		ug/Kg	5.0
	4,4'-DDT	**5.8**		ug/Kg	5.0

Sample ID: CG-41-2.5	Lab ID: 553784-043	Collected: 02/19/26

No Detections

Sample ID: CG-42-0.5	Lab ID: 553784-044	Collected: 02/19/26
	Matrix: Soil	

553784-044 Analyte		Result	Qual	Units	RL
Method: EPA 8081A Prep Method: EPA 3546					
	4,4'-DDT	**5.4**		ug/Kg	5.1

Sample ID: CG-42-2.5	Lab ID: 553784-045	Collected: 02/19/26

No Detections

C Presence confirmed, but RPD between columns exceeds 40%

Results for any subcontracted analyses are not included in this summary. Data qualifiers and additional information necessary for the interpretation of the test results are contained in the PDF file and may not be included in this summary.

Login 553784

ALPY ICAL

Chain of Custody Record

Lab No: 553784

Page: 1 of 6

Turn Around Time (rush by advanced notice only)

Standard:	X	5 Day:		3 Day:	
2 Day:		1 Day:		Custom TAT	

931 W. Barkley Avenue, Orange, CA 92868

Phone 714-771-6900

Matrix: A = Air, S = Soil/Solid, W = Water, DW = Drinking Water, P = Product, O = Oil, SD = Sediment, T = Tissue, WP = Wipe, WW = Wastewater, X = Other

Sample Type: C = Composite, G = Grab or Discrete, B = Blank, O = Other

Preservatives: 0 = none, 1 = $Na_2S_2O_3$, 2 = HCl, 3 = HNO_3, 4 = H_2SO_4, 5 = NaOH, 6 = Other

Sample Receipt Temp and Notes: 3.1/3.3 ICE IR10 10.2 bag (lab use only)

CUSTOMER INFORMATION

Company:	Terraphase Engineering Inc.
Report To:	Vanya Keyes
Email:	vanya.keyes@terraphase.com
Address:	18401 Von Karman Ave
Phone:	949-377-2227
Fax:	

PROJECT INFORMATION

Name:	Centennial High School
Number:	0215.002.002
P.O. #:	
Address:	2606 N Central Ave, Compton, CA, 90222
Global ID:	
Sampled By:	Portia C. Ibarra

Test Instructions / Comments: Please also send report to clare.steedman@terraphase.com portia.ibarra@terraphase.com

	Sample ID	Sampling Date	Sampling Time (24 hr)	Matrix	Sample Type	Pres.	Cont. No.	Cont. Size	Initials	Arsenic (6020)	Lead (6010B)	PCBs (8082)	Title 22 Metals (6020/7471A)	Dioxins & Furins (8290A)	VOCs (8260B)	TPH (8015)	
1	QCC4-SB-28-0.5	2/19/26	0800	S	G	O	2	807	PCI		X	X					} CG-38-0.5
2	QCC4-SB-29-0.5		0818				2				X	X					
3	QCC4-SB-30-0.5		0841				2				X	X					
4	QCC4-SB-28-2.5		0802				2										} CG-38-2.5
5	QCC4-SB-29-2.5		0819				2										
6	QCC4-SB-30-2.5		0846				2										
7	QCC4-SB-34-0.5		1013				1				X	X					} CG-40-0.5
8	QCC4-SB-35-0.5		0916				1				X	X					
9	QCC4-SB-36-0.5	2/19/26	0950	S	G	O	1	807	PCI		X	X					
10																	

	Signature	Print Name	Company / Title	Date / Time
1 Relinquished By:		Portia Ibarra	TER / geotech	2/19/26 / 1600
1 Received By:		KEMA O	EANH	2-19-26 1600
2 Relinquished By:		KEMA O.	EANH	2-20-26 11:30
2 Received By:		Nicole Mendoza	EA	2-20-26 11:30
3 Relinquished By:				

ENTHALPY ANALYTICAL

Chain of Custody Record

Lab No:

Page: 2 of 6

Turn Around Time (rush by advanced notice only)

Standard:	X	5 Day:		3 Day:	
2 Day:		1 Day:		Custom TAT	

Enthalpy Analytical - Orange
931 W. Barkley Avenue, Orange, CA 92868
Phone 714-771-6900

Matrix: A = Air, S = Soil/Solid, W = Water, DW = Drinking Water, P = Product, O = Oil, SD = Sediment, T = Tissue, WP = Wipe, WW = Wastewater, X = Other

Sample Type: C = Composite, G = Grab or Discrete, B = Blank, O = Other

Preservatives: 0 = none, 1 = $Na_2S_2O_3$, 2 = HCl, 3 = HNO_3, 4 = H_2SO_4, 5 = NaOH, 6 = Other

Sample Receipt Temp and Notes: (lab use only)

CUSTOMER INFORMATION		PROJECT INFORMATION	
Company:	Terraphase Engineering Inc.	Name:	Centennial High School
Report To:	Vanya Keyes	Number:	
Email:	vanya.keyes@terraphase.com	P.O. #:	0215.002.002
Address:	18401 Von Karman Ave	Address:	2606 N Central Ave
			Compton, CA, 90222
Phone:	949-377-2227	Global ID:	
Fax:		Sampled By:	Portia C. Ibarra

Test Instructions / Comments: Please also send report to clare.steedman@terraphase.com portia.ibarra@terraphase.com

	Sample ID	Sampling Date	Sampling Time (24 hr)	Matrix	Sample Type	Pres.	Cont. No.	Cont. Size	Initials	Arsenic (6020)	Lead (6010B)	PCBs (8082)	Title 22 Metals (6020/7471A)	Dioxins & Furins (8290A)	VOCs (8260B)	TPH (8015)	
1	AOC4-SB-34-0.5	2/19/26	1018	S	G	0	1	8oz	PCI								CG-40-2.5
2	AOC4-SB-35-2.5		0921														
3	AOC4-SB-36-2.5		0955														
4	AOC4-SB-37-0.5		1030								X	X					CG-41-0.5
5	AOC4-SB-38-0.5		1043								X	X					
6	AOC4-SB-39-0.5		1057								X	X					
7	DUP-01-0.5-260219		—								X	X					
8	AOC4-SB-40-0.5		1106								X	X					CG-42-0.5
9	AOC4-SB-41-0.5	↓	1309	↓	↓	↓	↓	↓	↓		X	X					
10	AOC4-SB-42-0.5	2/19/26	1300	S	G	0	1	8oz	PCI		X	X					

	Signature	Print Name	Company / Title	Date / Time
1 Relinquished By:	[signature]	Portia Ibarra	TEI / Geologist	2/19/26 / 1600
1 Received By:	[signature]	~~GEMA O~~	~~EANH~~	2-19-26 16:00
2 Relinquished By:	[signature]	GEMA O.	EANH	2-19-26 11:30
2 Received By:	[signature]	Nicole Mendoza	EA	2-20-26 11:30
3 Relinquished By:				

ENTHALPY ANALYTICAL

Chain of Custody Record

Lab No:

Page: 3 of 6

Turn Around Time (rush by advanced notice only)

Standard:	✓	5 Day:		3 Day:	
2 Day:		1 Day:		Custom TAT	

Enthalpy Analytical - Orange
931 W. Barkley Avenue, Orange, CA 92868
Phone 714-771-6900

Matrix: **A** = Air **S** = Soil/Solid **W** = Water **DW** = Drinking Water **P** = Product **O** = Oil **SD** = Sediment **T** = Tissue **WP** = Wipe **WW** = Wastewater **X** = Other

Sample Type: **C** = Composite **G** = Grab or Discrete **B** = Blank **O** = Other

Preservatives: **0** = none **1** = $Na_2S_2O_3$ **2** = HCl **3** = HNO_3 **4** = H_2SO_4 **5** = NaOH **6** = Other

Sample Receipt Temp and Notes: (lab use only)

CUSTOMER INFORMATION		PROJECT INFORMATION	
Company:	Terraphase Engineering Inc.	Name:	Centennial High School
Report To:	Vanya Keyes	Number:	0215.002.002
Email:	vanya.keyes@terraphase.com	P.O. #:	
Address:	18401 Von Karman Ave	Address:	2606 N Central Ave, Compton, CA, 90222
Phone:	949-377-2227	Global ID:	
Fax:		Sampled By:	Portia C. Ibarra

Test Instructions / Comments: Please also send report to clare.steedman@terraphase.com portia.ibarra@terraphase.com

	Sample ID	Sampling Date	Sampling Time (24 hr)	Matrix	Sample Type	Pres.	Cont. No.	Cont. Size	Initials	Arsenic (6020)	Lead (6010B)	PCBs (8082)	Title 22 Metals (6020/7471A)	Dioxins & Furins (8290A)	VOCs (8260B)	TPH (8015)	Test Instructions / Comments
1	AOC4-SB-37-2.5	2/19/26	1035	S	G	0	1	8oz	PCI								} CG-41-2.5
2	AOC4-SB-38-2.5		1048														
3	AOC4-SB 39-2.5		1102														
4	DUP-01-2.5-260219		—														hold
5	AOC4-SB-40-2.5		1111														} CG-42-2.5
6	AOC4-SB-41-2.5		1314														
7	AOC4-SB-42-2.5		1305														
8	AOC4-SB-43-0.5		1334								X	X					} CG-43-0.5
9	AOC4-SB-44-0.5		1347								X	X					
10	AOC4-SB-45-0.5	2/17/26	1358	S	G	0	1	8oz	PCI		X	X					

	Signature	Print Name	Company / Title	Date / Time
1 Relinquished By:		Portia Ibarra	TEI / Geologist	2/19/26 / 1630
1 Received By:		Gema O	EAWH	2-19-26 16:00
2 Relinquished By:		Gema O.	EAWH	2-20-26 11:30
2 Received By:		Nicole Mendoza	EA	2-20-26 11:30
3 Relinquished By:				

ENTHALPY ANALYTICAL

Chain of Custody Record

Lab No:

Page: 4 of 6

Turn Around Time (rush by advanced notice only)

Standard:	X	5 Day:		3 Day:	
2 Day:		1 Day:		Custom TAT	

Enthalpy Analytical - Orange

931 W. Barkley Avenue, Orange, CA 92868

Phone 714-771-6900

Matrix: A = Air, S = Soil/Solid, W = Water, DW = Drinking Water, P = Product, O = Oil, SD = Sediment, T = Tissue, WP = Wipe, WW = Wastewater, X = Other

Sample Type: C = Composite, G = Grab or Discrete, B = Blank, O = Other

Preservatives: 0 = none, 1 = $Na_2S_2O_3$, 2 = HCl, 3 = HNO_3, 4 = H_2SO_4, 5 = NaOH, 6 = Other

Sample Receipt Temp and Notes: (lab use only)

CUSTOMER INFORMATION		PROJECT INFORMATION	
Company:	Terraphase Engineering Inc.	Name:	Centennial High School
Report To:	Vanya Keyes	Number:	
Email:	vanya.keyes@terraphase.com	P.O. #:	0215.002.002
Address:	18401 Von Karman Ave	Address:	2606 N Central Ave
			Compton, CA, 90222
Phone:	949-377-2227	Global ID:	
Fax:		Sampled By:	Portia C. Ibarra

Analysis Request: Arsenic (6020), Lead (6010B), PCBs (8082), Title 22 Metals (6020/7471A), Dioxins & Furins (8290A), VOCs (8260B), TPH (8015)

Test Instructions / Comments: Please also send report to clare.steedman@terraphase.com portia.ibarra@terraphase.com

	Sample ID	Sampling Date	Sampling Time (24 hr)	Matrix	Sample Type	Pres.	Cont. No.	Cont. Size	Initials	Arsenic (6020)	Lead (6010B)	PCBs (8082)	Title 22 Metals (6020/7471A)	Dioxins & Furins (8290A)	VOCs (8260B)	TPH (8015)	Test Instructions / Comments
1	CG-SB-43-2.5	2/19/26	1340	S	G	0	1	8oz	PCL								} CG-43-2.5
2	CG-SB-44-2.5	"	1352	"	"	"	"	"	"								
3	CG-SB-45-2.5	2/19/26	1402	S	G	0	1	8oz	PCL								
4																	
5																	
6																	
7																	
8																	
9																	
10																	

	Signature	Print Name	Company / Title	Date / Time
1 Relinquished By:		Portia Ibarra	TER / Geologist	2/19/26 / 16:00
1 Received By:		Gema O	EANH	2-19-26 16:00
2 Relinquished By:		Gema O.	EANH	2-20-26 11:30
2 Received By:		Nicole Mendoza	EA	2-20-26 11:30
3 Relinquished By:				

ENTHALPY ANALYTICAL

Chain of Custody Record

Lab No:

Page: 5 of 6

Turn Around Time (rush by advanced notice only)

Standard:	X	5 Day:		3 Day:	
2 Day:		1 Day:		Custom TAT	

Enthalpy Analytical - Orange

931 W. Barkley Avenue, Orange, CA 92868

Phone 714-771-6900

Matrix: **A** = Air **S** = Soil/Solid **W** = Water **DW** = Drinking Water **P** = Product **O** = Oil **SD** = Sediment **T** = Tissue **WP** = Wipe **WW** = Wastewater **X** = Other

Sample Type: **C** = Composite **G** = Grab or Discrete **B** = Blank **O** = Other

Preservatives: **0** = none **1** = $Na_2S_2O_3$ **2** = HCl **3** = HNO_3 **4** = H_2SO_4 **5** = NaOH **6** = Other

Sample Receipt Temp and Notes: (lab use only)

CUSTOMER INFORMATION

Company:	Terraphase Engineering Inc.
Report To:	Vanya Keyes
Email:	vanya.keyes@terraphase.com
Address:	18401 Von Karman Ave
Phone:	949-377-2227
Fax:	

PROJECT INFORMATION

Name:	Centennial High School
Number:	0215.002.002
P.O. #:	
Address:	2606 N Central Ave
	Compton, CA, 90222
Global ID:	
Sampled By:	Portia C. Ibarra

Analysis Request

Test Instructions / Comments

Please also send report to
clare.steedman@terraphase.com
portia.ibarra@terraphase.com

	Sample ID	Sampling Date	Sampling Time (24 hr)	Matrix	Sample Type	Pres.	Cont. No.	Cont. Size	Initials	OCPs by USEPA 8081A	Asbestos by PLM	Lead 6010B	PCBs 8082					
1	CG-43-0.5									X	X							
2	CG-43-2.5									X	X							
3	EB-01-260219	2/19/26	1530	W	G	3	3	2 amb 1 poly	PCI	X	X	X	X					
4																		
5																		
6																		
7																		
8																		
9																		
10																		

	Signature	Print Name	Company / Title	Date / Time
1 Relinquished By:		Portia Ibarra	TEI / Enthalpy	2/19/26 / 16:00
1 Received By:		Gema O.	EANH	2-19-26 16:00
2 Relinquished By:		Gema	EANH	2-20-26 11:30
2 Received By:		Nicole Mendoza	EA	2-20-26 11:30
3 Relinquished By:				

ENTHALPY ANALYTICAL

Chain of Custody Record

Lab No:

Page: 6 of 6

Turn Around Time (rush by advanced notice only)

Standard:	X	5 Day:		3 Day:	
2 Day:		1 Day:		Custom TAT	

Enthalpy Analytical - Orange

931 W. Barkley Avenue, Orange, CA 92868

Phone 714-771-6900

Matrix: **A** = Air **S** = Soil/Solid **W** = Water **DW** = Drinking Water **P** = Product **O** = Oil **SD** = Sediment **T** = Tissue **WP** = Wipe **WW** = Wastewater **X** = Other

Sample Type: **C** = Composite **G** = Grab or Discrete **B** = Blank **O** = Other

Preservatives: **0** = none **1** = $Na_2S_2O_3$ **2** = HCl **3** = HNO_3 **4** = H_2SO_4 **5** = NaOH **6** = Other

Sample Receipt Temp and Notes: (lab use only)

CUSTOMER INFORMATION		PROJECT INFORMATION	
Company:	Terraphase Engineering Inc.	Name:	Centennial High School
Report To:	Vanya Keyes	Number:	0215.002.002
Email:	vanya.keyes@terraphase.com	P.O. #:	
Address:	18401 Von Karman Ave	Address:	2606 N Central Ave
			Compton, CA, 90222
Phone:	949-377-2227	Global ID:	
Fax:		Sampled By:	Portia C. Ibarra

Test Instructions / Comments: Please also send report to clare.steedman@terraphase.com portia.ibarra@terraphase.com

	Sample ID	Sampling Date	Sampling Time (24 hr)	Matrix	Sample Type	Pres.	Cont. No.	Cont. Size	Initials	OCPs by USEPA 8081A	Asbestos by PLM	Test Instructions / Comments
1	CG-38-0.5									X	X	
2	CG-38-2.5									X	X	
3	CG-38-0.5-DUP									X	X	Split from CG-38-0.5
4	CG-38-2.5-DUP									X	X	Split from CG-38-2.5
5	CG-40-0.5									X	X	
6	CG-40-2.5									X	X	
7	CG-41-0.5									X	X	
8	CG-41-2.5									X	X	
9	CG-42-0.5									X	X	
10	CG-42-2.5									X	X	

	Signature	Print Name	Company / Title	Date / Time
1 Relinquished By:		Patricia Garcia	TEI / Garcia	2/19/26 / 1630
1 Received By:		Clema O.	EANH	2-19-26 16:00
2 Relinquished By:		Clema O	EANH	2-20-26 11:30
2 Received By:		Nicole Mendoza	EA	2-20-26 11:30
3 Relinquished By:				

SAMPLE RECEIPT CHECKLIST

Section 1: General Info

Date Received: 2/20/26 WO# 553784 Client: Terraphase

ENTHALPY

Section 2: Shipping / Custody **Are custody seals present?** ☐ **Yes** ☒ **No**

Custody seals intact on arrival? ■ N/A ☐ Yes ☐ No ☐ On cooler / box ☐ On samples

■ Courier ☐ Walk-In ☐ Field Sampling ☐ Shipping Info: _____

Section 3a: Condition / Packaging ☐ **Outside 0.0 - 6.0°C (0.0 - 10.0°C for microbiology) (PM notified)**

Date Opened 2/20/26 By (initials) GXO Type of ice used: ■ Wet ☐ Blue/Gel ☐ None

☐ Samples received on ice directly from the field; cooling process had begun. (if checked, skip temperatures)

☐ Sample matrix doesn't require cooling (e.g. air, bulk PCB). (if checked, skip temperatures)

If no cooler: Observed/Adjusted Temp (°C): _____ / _____ Thermometer/IR Gun: IR 10 CF: +0.2

Cooler Temp (°C) #1: 3.1 / 3.3 #2: ____/____ #3: ____/____ #4: ____/____ #5: ____/____ #6: ____/____

Section 3b: Microbiology Samples ■ **No microbiology samples submitted (skip 3b)**

☐ Within temp range 0.0 - 10.0°C or received on ice directly from field.

☐ Adequate headspace for microbiology analysis.

Section 3c: Air Samples ■ **No air samples submitted (skip 3c)**

☐ 1.4L Canisters ☐ 6L Canisters ☐ Tedlar Bags ☐ MCE Cassettes ☐ Sorbent Tubes ☐ Other_____

Section 4: Containers / Labels / Samples	YES	NO	N/A
1) Were custody papers present, filled properly, and legible?	X		
2) Is the sampler's name present on the CoC?	X		
3) Were containers received in good condition (unbroken / unopened / uncompromised)?	X		
4) Were the samples bagged? (required for microbiology samples; recommended for soil samples)	X		
5) Were all of, and only, the correct samples received?	X		
6) Are sample labels present, legible, and in agreement with the CoC?	X		
7) Does the container count match the CoC?	X		
8) Was sufficient sample volume / mass received for the analyses requested?	X		
9) Were samples received in proper containers for the analyses requested?	X		
10) Were samples received with > 1/2 holding time remaining?	X		
11) Are samples properly preserved as indicated by CoC / labels?	X		
12) Unpreserved VOAs received - If necessary, was the hold time changed in LIMS?			X
13) Are VOA vials free from headspace/bubbles > 6mm?			X

Section 5: Explanations / Comments

(If no comments are made, then no discrepancies noted.)

☐ **No additional discrepancies**

Date Logged 2/19/26 **By (print)** ABD **(sign)** _____

Date Labeled 2/20/26 **By (print)** AGR **(sign)** _____ for AGR

ENTHALPY ANALYTICAL

Analysis Results for 553784

Vanya Keyes
Terraphase Engineering
18401 Von Karman Ave, Suite #410
Irvine, CA 92612

Lab Job #: 553784
Project No: CENTENNIAL HS
Location: Centennial High School, 2606 N Central Ave., Compton, CA 90222
Date Received: 02/19/26

Sample ID: AOC4-SB-28-0.5 **Lab ID: 553784-001** **Collected: 02/19/26 08:00**
Matrix: Soil

553784-001 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3050B									
Lead	**13**		mg/Kg	1.0	1	396187	02/23/26	02/24/26	TWJ
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	51	1	396340	02/25/26	02/26/26	HQN
Aroclor-1221	ND		ug/Kg	51	1	396340	02/25/26	02/26/26	HQN
Aroclor-1232	ND		ug/Kg	51	1	396340	02/25/26	02/26/26	HQN
Aroclor-1242	ND		ug/Kg	51	1	396340	02/25/26	02/26/26	HQN
Aroclor-1248	ND		ug/Kg	51	1	396340	02/25/26	02/26/26	HQN
Aroclor-1254	ND		ug/Kg	51	1	396340	02/25/26	02/26/26	HQN
Aroclor-1260	ND		ug/Kg	51	1	396340	02/25/26	02/26/26	HQN
Aroclor-1262	ND		ug/Kg	51	1	396340	02/25/26	02/26/26	HQN
Aroclor-1268	ND		ug/Kg	51	1	396340	02/25/26	02/26/26	HQN
Total PCBs	ND		ug/Kg	51	1	396340	02/25/26	02/26/26	HQN
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	79%		%REC	50-127	1	396340	02/25/26	02/26/26	HQN

Sample ID: AOC4-SB-29-0.5 **Lab ID: 553784-002** **Collected: 02/19/26 08:15**
Matrix: Soil

553784-002 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3050B									
Lead	**6.4**		mg/Kg	1.0	1	396187	02/23/26	02/24/26	TWJ
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	50	1	396340	02/25/26	02/26/26	HQN
Aroclor-1221	ND		ug/Kg	50	1	396340	02/25/26	02/26/26	HQN
Aroclor-1232	ND		ug/Kg	50	1	396340	02/25/26	02/26/26	HQN
Aroclor-1242	ND		ug/Kg	50	1	396340	02/25/26	02/26/26	HQN
Aroclor-1248	ND		ug/Kg	50	1	396340	02/25/26	02/26/26	HQN
Aroclor-1254	ND		ug/Kg	50	1	396340	02/25/26	02/26/26	HQN
Aroclor-1260	ND		ug/Kg	50	1	396340	02/25/26	02/26/26	HQN
Aroclor-1262	ND		ug/Kg	50	1	396340	02/25/26	02/26/26	HQN
Aroclor-1268	ND		ug/Kg	50	1	396340	02/25/26	02/26/26	HQN
Total PCBs	ND		ug/Kg	50	1	396340	02/25/26	02/26/26	HQN
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	64%		%REC	50-127	1	396340	02/25/26	02/26/26	HQN

Results for any subcontracted analyses are not included in this section.

ENTHALPY ANALYTICAL

Analysis Results for 553784

Sample ID: AOC4-SB-30-0.5 **Lab ID: 553784-003** **Collected: 02/19/26 08:41**
Matrix: Soil

553784-003 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3050B									
Lead	**9.1**		mg/Kg	0.98	0.98	396187	02/23/26	02/24/26	TWJ
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	51	1	396340	02/25/26	02/26/26	HQN
Aroclor-1221	ND		ug/Kg	51	1	396340	02/25/26	02/26/26	HQN
Aroclor-1232	ND		ug/Kg	51	1	396340	02/25/26	02/26/26	HQN
Aroclor-1242	ND		ug/Kg	51	1	396340	02/25/26	02/26/26	HQN
Aroclor-1248	ND		ug/Kg	51	1	396340	02/25/26	02/26/26	HQN
Aroclor-1254	ND		ug/Kg	51	1	396340	02/25/26	02/26/26	HQN
Aroclor-1260	ND		ug/Kg	51	1	396340	02/25/26	02/26/26	HQN
Aroclor-1262	ND		ug/Kg	51	1	396340	02/25/26	02/26/26	HQN
Aroclor-1268	ND		ug/Kg	51	1	396340	02/25/26	02/26/26	HQN
Total PCBs	ND		ug/Kg	51	1	396340	02/25/26	02/26/26	HQN
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	63%		%REC	50-127	1	396340	02/25/26	02/26/26	HQN

Sample ID: AOC4-SB-34-0.5 **Lab ID: 553784-007** **Collected: 02/19/26 10:13**
Matrix: Soil

553784-007 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3050B									
Lead	**58**		mg/Kg	0.95	0.95	396187	02/23/26	02/24/26	TWJ
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	49	0.99	396340	02/25/26	02/26/26	HQN
Aroclor-1221	ND		ug/Kg	49	0.99	396340	02/25/26	02/26/26	HQN
Aroclor-1232	ND		ug/Kg	49	0.99	396340	02/25/26	02/26/26	HQN
Aroclor-1242	ND		ug/Kg	49	0.99	396340	02/25/26	02/26/26	HQN
Aroclor-1248	ND		ug/Kg	49	0.99	396340	02/25/26	02/26/26	HQN
Aroclor-1254	ND		ug/Kg	49	0.99	396340	02/25/26	02/26/26	HQN
Aroclor-1260	ND		ug/Kg	49	0.99	396340	02/25/26	02/26/26	HQN
Aroclor-1262	ND		ug/Kg	49	0.99	396340	02/25/26	02/26/26	HQN
Aroclor-1268	ND		ug/Kg	49	0.99	396340	02/25/26	02/26/26	HQN
Total PCBs	ND		ug/Kg	49	0.99	396340	02/25/26	02/26/26	HQN
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	81%		%REC	50-127	0.99	396340	02/25/26	02/26/26	HQN

Results for any subcontracted analyses are not included in this section.

ENTHALPY ANALYTICAL

Analysis Results for 553784

Sample ID: AOC4-SB-35-0.5 **Lab ID: 553784-008** **Collected: 02/19/26 09:16**
Matrix: Soil

553784-008 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3050B									
Lead	**4.3**		mg/Kg	0.96	0.96	396187	02/23/26	02/24/26	TWJ
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	51	1	396340	02/25/26	02/26/26	HQN
Aroclor-1221	ND		ug/Kg	51	1	396340	02/25/26	02/26/26	HQN
Aroclor-1232	ND		ug/Kg	51	1	396340	02/25/26	02/26/26	HQN
Aroclor-1242	ND		ug/Kg	51	1	396340	02/25/26	02/26/26	HQN
Aroclor-1248	ND		ug/Kg	51	1	396340	02/25/26	02/26/26	HQN
Aroclor-1254	ND		ug/Kg	51	1	396340	02/25/26	02/26/26	HQN
Aroclor-1260	ND		ug/Kg	51	1	396340	02/25/26	02/26/26	HQN
Aroclor-1262	ND		ug/Kg	51	1	396340	02/25/26	02/26/26	HQN
Aroclor-1268	ND		ug/Kg	51	1	396340	02/25/26	02/26/26	HQN
Total PCBs	ND		ug/Kg	51	1	396340	02/25/26	02/26/26	HQN
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	75%		%REC	50-127	1	396340	02/25/26	02/26/26	HQN

Sample ID: AOC4-SB-36-0.5 **Lab ID: 553784-009** **Collected: 02/19/26 09:50**
Matrix: Soil

553784-009 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3050B									
Lead	**8.4**		mg/Kg	0.98	0.98	396205	02/24/26	02/24/26	KCD
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	49	0.99	396340	02/25/26	02/26/26	HQN
Aroclor-1221	ND		ug/Kg	49	0.99	396340	02/25/26	02/26/26	HQN
Aroclor-1232	ND		ug/Kg	49	0.99	396340	02/25/26	02/26/26	HQN
Aroclor-1242	ND		ug/Kg	49	0.99	396340	02/25/26	02/26/26	HQN
Aroclor-1248	ND		ug/Kg	49	0.99	396340	02/25/26	02/26/26	HQN
Aroclor-1254	ND		ug/Kg	49	0.99	396340	02/25/26	02/26/26	HQN
Aroclor-1260	ND		ug/Kg	49	0.99	396340	02/25/26	02/26/26	HQN
Aroclor-1262	ND		ug/Kg	49	0.99	396340	02/25/26	02/26/26	HQN
Aroclor-1268	ND		ug/Kg	49	0.99	396340	02/25/26	02/26/26	HQN
Total PCBs	ND		ug/Kg	49	0.99	396340	02/25/26	02/26/26	HQN
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	81%		%REC	50-127	0.99	396340	02/25/26	02/26/26	HQN

Results for any subcontracted analyses are not included in this section.

Analysis Results for 553784

Sample ID: AOC4-SB-37-0.5 **Lab ID: 553784-013** **Collected: 02/19/26 10:30**
Matrix: Soil

553784-013 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3050B									
Lead	**38**		mg/Kg	0.97	0.97	396205	02/24/26	02/24/26	KCD
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	51	1	396340	02/25/26	02/26/26	HQN
Aroclor-1221	ND		ug/Kg	51	1	396340	02/25/26	02/26/26	HQN
Aroclor-1232	ND		ug/Kg	51	1	396340	02/25/26	02/26/26	HQN
Aroclor-1242	ND		ug/Kg	51	1	396340	02/25/26	02/26/26	HQN
Aroclor-1248	ND		ug/Kg	51	1	396340	02/25/26	02/26/26	HQN
Aroclor-1254	ND		ug/Kg	51	1	396340	02/25/26	02/26/26	HQN
Aroclor-1260	**190**		ug/Kg	51	1	396340	02/25/26	02/26/26	HQN
Aroclor-1262	ND		ug/Kg	51	1	396340	02/25/26	02/26/26	HQN
Aroclor-1268	ND		ug/Kg	51	1	396340	02/25/26	02/26/26	HQN
Total PCBs	**190**		ug/Kg	51	1	396340	02/25/26	02/26/26	HQN
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	80%		%REC	50-127	1	396340	02/25/26	02/26/26	HQN

Sample ID: AOC4-SB-38-0.5 **Lab ID: 553784-014** **Collected: 02/19/26 10:43**
Matrix: Soil

553784-014 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3050B									
Lead	**38**		mg/Kg	0.99	0.99	396205	02/24/26	02/24/26	KCD
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	50	1	396340	02/25/26	02/26/26	HQN
Aroclor-1221	ND		ug/Kg	50	1	396340	02/25/26	02/26/26	HQN
Aroclor-1232	ND		ug/Kg	50	1	396340	02/25/26	02/26/26	HQN
Aroclor-1242	ND		ug/Kg	50	1	396340	02/25/26	02/26/26	HQN
Aroclor-1248	ND		ug/Kg	50	1	396340	02/25/26	02/26/26	HQN
Aroclor-1254	ND		ug/Kg	50	1	396340	02/25/26	02/26/26	HQN
Aroclor-1260	ND		ug/Kg	50	1	396340	02/25/26	02/26/26	HQN
Aroclor-1262	ND		ug/Kg	50	1	396340	02/25/26	02/26/26	HQN
Aroclor-1268	ND		ug/Kg	50	1	396340	02/25/26	02/26/26	HQN
Total PCBs	ND		ug/Kg	50	1	396340	02/25/26	02/26/26	HQN
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	84%		%REC	50-127	1	396340	02/25/26	02/26/26	HQN

Results for any subcontracted analyses are not included in this section.

Analysis Results for 553784

Sample ID: AOC4-SB-39-0.5 **Lab ID: 553784-015** **Collected: 02/19/26 10:57**
Matrix: Soil

553784-015 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3050B									
Lead	**20**		mg/Kg	0.95	0.95	396205	02/24/26	02/24/26	KCD
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	50	1	396340	02/25/26	02/26/26	HQN
Aroclor-1221	ND		ug/Kg	50	1	396340	02/25/26	02/26/26	HQN
Aroclor-1232	ND		ug/Kg	50	1	396340	02/25/26	02/26/26	HQN
Aroclor-1242	ND		ug/Kg	50	1	396340	02/25/26	02/26/26	HQN
Aroclor-1248	ND		ug/Kg	50	1	396340	02/25/26	02/26/26	HQN
Aroclor-1254	ND		ug/Kg	50	1	396340	02/25/26	02/26/26	HQN
Aroclor-1260	ND		ug/Kg	50	1	396340	02/25/26	02/26/26	HQN
Aroclor-1262	ND		ug/Kg	50	1	396340	02/25/26	02/26/26	HQN
Aroclor-1268	ND		ug/Kg	50	1	396340	02/25/26	02/26/26	HQN
Total PCBs	ND		ug/Kg	50	1	396340	02/25/26	02/26/26	HQN
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	66%		%REC	50-127	1	396340	02/25/26	02/26/26	HQN

Sample ID: DUP-01-0.5-260219 **Lab ID: 553784-016** **Collected: 02/19/26**
Matrix: Soil

553784-016 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3050B									
Lead	**24**		mg/Kg	0.98	0.98	396205	02/24/26	02/24/26	KCD
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	50	1	396340	02/25/26	02/26/26	HQN
Aroclor-1221	ND		ug/Kg	50	1	396340	02/25/26	02/26/26	HQN
Aroclor-1232	ND		ug/Kg	50	1	396340	02/25/26	02/26/26	HQN
Aroclor-1242	ND		ug/Kg	50	1	396340	02/25/26	02/26/26	HQN
Aroclor-1248	ND		ug/Kg	50	1	396340	02/25/26	02/26/26	HQN
Aroclor-1254	ND		ug/Kg	50	1	396340	02/25/26	02/26/26	HQN
Aroclor-1260	**58**		ug/Kg	50	1	396340	02/25/26	02/26/26	HQN
Aroclor-1262	ND		ug/Kg	50	1	396340	02/25/26	02/26/26	HQN
Aroclor-1268	ND		ug/Kg	50	1	396340	02/25/26	02/26/26	HQN
Total PCBs	**58**		ug/Kg	50	1	396340	02/25/26	02/26/26	HQN
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	74%		%REC	50-127	1	396340	02/25/26	02/26/26	HQN

Results for any subcontracted analyses are not included in this section.

Analysis Results for 553784

Sample ID: AOC4-SB-40-0.5	Lab ID: 553784-017	Collected: 02/19/26 11:06
	Matrix: Soil	

553784-017 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3050B									
Lead	**10**		mg/Kg	1.0	1	396205	02/24/26	02/24/26	KCD
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	50	1	396340	02/25/26	02/26/26	HQN
Aroclor-1221	ND		ug/Kg	50	1	396340	02/25/26	02/26/26	HQN
Aroclor-1232	ND		ug/Kg	50	1	396340	02/25/26	02/26/26	HQN
Aroclor-1242	ND		ug/Kg	50	1	396340	02/25/26	02/26/26	HQN
Aroclor-1248	ND		ug/Kg	50	1	396340	02/25/26	02/26/26	HQN
Aroclor-1254	ND		ug/Kg	50	1	396340	02/25/26	02/26/26	HQN
Aroclor-1260	ND		ug/Kg	50	1	396340	02/25/26	02/26/26	HQN
Aroclor-1262	ND		ug/Kg	50	1	396340	02/25/26	02/26/26	HQN
Aroclor-1268	ND		ug/Kg	50	1	396340	02/25/26	02/26/26	HQN
Total PCBs	ND		ug/Kg	50	1	396340	02/25/26	02/26/26	HQN
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	75%		%REC	50-127	1	396340	02/25/26	02/26/26	HQN

Sample ID: AOC4-SB-41-0.5	Lab ID: 553784-018	Collected: 02/19/26 13:09
	Matrix: Soil	

553784-018 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3050B									
Lead	**15**		mg/Kg	0.96	0.96	396205	02/24/26	02/24/26	KCD
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	51	1	396340	02/25/26	02/26/26	HQN
Aroclor-1221	ND		ug/Kg	51	1	396340	02/25/26	02/26/26	HQN
Aroclor-1232	ND		ug/Kg	51	1	396340	02/25/26	02/26/26	HQN
Aroclor-1242	ND		ug/Kg	51	1	396340	02/25/26	02/26/26	HQN
Aroclor-1248	ND		ug/Kg	51	1	396340	02/25/26	02/26/26	HQN
Aroclor-1254	ND		ug/Kg	51	1	396340	02/25/26	02/26/26	HQN
Aroclor-1260	ND		ug/Kg	51	1	396340	02/25/26	02/26/26	HQN
Aroclor-1262	ND		ug/Kg	51	1	396340	02/25/26	02/26/26	HQN
Aroclor-1268	ND		ug/Kg	51	1	396340	02/25/26	02/26/26	HQN
Total PCBs	ND		ug/Kg	51	1	396340	02/25/26	02/26/26	HQN
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	82%		%REC	50-127	1	396340	02/25/26	02/26/26	HQN

Results for any subcontracted analyses are not included in this section.

Analysis Results for 553784

Sample ID: AOC4-SB-42-0.5	Lab ID: 553784-019	Collected: 02/19/26 13:00
	Matrix: Soil	

553784-019 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3050B									
Lead	**18**		mg/Kg	1.0	1	396205	02/24/26	02/24/26	KCD
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	51	1	396340	02/25/26	02/26/26	HQN
Aroclor-1221	ND		ug/Kg	51	1	396340	02/25/26	02/26/26	HQN
Aroclor-1232	ND		ug/Kg	51	1	396340	02/25/26	02/26/26	HQN
Aroclor-1242	ND		ug/Kg	51	1	396340	02/25/26	02/26/26	HQN
Aroclor-1248	ND		ug/Kg	51	1	396340	02/25/26	02/26/26	HQN
Aroclor-1254	**160**		ug/Kg	51	1	396340	02/25/26	02/26/26	HQN
Aroclor-1260	ND		ug/Kg	51	1	396340	02/25/26	02/26/26	HQN
Aroclor-1262	ND		ug/Kg	51	1	396340	02/25/26	02/26/26	HQN
Aroclor-1268	ND		ug/Kg	51	1	396340	02/25/26	02/26/26	HQN
Total PCBs	**160**		ug/Kg	51	1	396340	02/25/26	02/26/26	HQN
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	77%		%REC	50-127	1	396340	02/25/26	02/26/26	HQN

Sample ID: AOC4-SB-43-0.5	Lab ID: 553784-027	Collected: 02/19/26 13:34
	Matrix: Soil	

553784-027 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3050B									
Lead	**24**		mg/Kg	0.96	0.96	396205	02/24/26	02/24/26	KCD
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	49	0.99	396340	02/25/26	02/26/26	HQN
Aroclor-1221	ND		ug/Kg	49	0.99	396340	02/25/26	02/26/26	HQN
Aroclor-1232	ND		ug/Kg	49	0.99	396340	02/25/26	02/26/26	HQN
Aroclor-1242	ND		ug/Kg	49	0.99	396340	02/25/26	02/26/26	HQN
Aroclor-1248	ND		ug/Kg	49	0.99	396340	02/25/26	02/26/26	HQN
Aroclor-1254	ND		ug/Kg	49	0.99	396340	02/25/26	02/26/26	HQN
Aroclor-1260	ND		ug/Kg	49	0.99	396340	02/25/26	02/26/26	HQN
Aroclor-1262	ND		ug/Kg	49	0.99	396340	02/25/26	02/26/26	HQN
Aroclor-1268	ND		ug/Kg	49	0.99	396340	02/25/26	02/26/26	HQN
Total PCBs	ND		ug/Kg	49	0.99	396340	02/25/26	02/26/26	HQN
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	78%		%REC	50-127	0.99	396340	02/25/26	02/26/26	HQN

Results for any subcontracted analyses are not included in this section.

Analysis Results for 553784

Sample ID: AOC4-SB-44-0.5	Lab ID: 553784-028	Collected: 02/19/26 13:47
	Matrix: Soil	

553784-028 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3050B									
Lead	**27**		mg/Kg	1.0	1	396205	02/24/26	02/24/26	KCD
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	50	1	396340	02/25/26	02/26/26	HQN
Aroclor-1221	ND		ug/Kg	50	1	396340	02/25/26	02/26/26	HQN
Aroclor-1232	ND		ug/Kg	50	1	396340	02/25/26	02/26/26	HQN
Aroclor-1242	ND		ug/Kg	50	1	396340	02/25/26	02/26/26	HQN
Aroclor-1248	ND		ug/Kg	50	1	396340	02/25/26	02/26/26	HQN
Aroclor-1254	ND		ug/Kg	50	1	396340	02/25/26	02/26/26	HQN
Aroclor-1260	ND		ug/Kg	50	1	396340	02/25/26	02/26/26	HQN
Aroclor-1262	ND		ug/Kg	50	1	396340	02/25/26	02/26/26	HQN
Aroclor-1268	ND		ug/Kg	50	1	396340	02/25/26	02/26/26	HQN
Total PCBs	ND		ug/Kg	50	1	396340	02/25/26	02/26/26	HQN
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	78%		%REC	50-127	1	396340	02/25/26	02/26/26	HQN

Sample ID: AOC4-SB-45-0.5	Lab ID: 553784-029	Collected: 02/19/26 13:58
	Matrix: Soil	

553784-029 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3050B									
Lead	**34**		mg/Kg	0.98	0.98	396205	02/24/26	02/24/26	KCD
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	50	1	396340	02/25/26	02/26/26	HQN
Aroclor-1221	ND		ug/Kg	50	1	396340	02/25/26	02/26/26	HQN
Aroclor-1232	ND		ug/Kg	50	1	396340	02/25/26	02/26/26	HQN
Aroclor-1242	ND		ug/Kg	50	1	396340	02/25/26	02/26/26	HQN
Aroclor-1248	ND		ug/Kg	50	1	396340	02/25/26	02/26/26	HQN
Aroclor-1254	ND		ug/Kg	50	1	396340	02/25/26	02/26/26	HQN
Aroclor-1260	ND		ug/Kg	50	1	396340	02/25/26	02/26/26	HQN
Aroclor-1262	ND		ug/Kg	50	1	396340	02/25/26	02/26/26	HQN
Aroclor-1268	ND		ug/Kg	50	1	396340	02/25/26	02/26/26	HQN
Total PCBs	ND		ug/Kg	50	1	396340	02/25/26	02/26/26	HQN
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	82%		%REC	50-127	1	396340	02/25/26	02/26/26	HQN

Results for any subcontracted analyses are not included in this section.

ENTHALPY ANALYTICAL

Analysis Results for 553784

Sample ID: CG-43-0.5	Lab ID: 553784-033	Collected: 02/19/26
	Matrix: Soil	

553784-033 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 8081A Prep Method: EPA 3546									
alpha-BHC	ND		ug/Kg	10	2	396339	02/25/26	02/26/26	KMB
beta-BHC	ND		ug/Kg	10	2	396339	02/25/26	02/26/26	KMB
gamma-BHC	ND		ug/Kg	10	2	396339	02/25/26	02/26/26	KMB
delta-BHC	ND		ug/Kg	10	2	396339	02/25/26	02/26/26	KMB
Heptachlor	ND		ug/Kg	10	2	396339	02/25/26	02/26/26	KMB
Aldrin	ND		ug/Kg	10	2	396339	02/25/26	02/26/26	KMB
Heptachlor epoxide	ND		ug/Kg	10	2	396339	02/25/26	02/26/26	KMB
Endosulfan I	ND		ug/Kg	10	2	396339	02/25/26	02/26/26	KMB
Dieldrin	ND		ug/Kg	10	2	396339	02/25/26	02/26/26	KMB
4,4'-DDE	ND		ug/Kg	10	2	396339	02/25/26	02/26/26	KMB
Endrin	ND		ug/Kg	10	2	396339	02/25/26	02/26/26	KMB
Endosulfan II	ND		ug/Kg	10	2	396339	02/25/26	02/26/26	KMB
Endosulfan sulfate	ND		ug/Kg	10	2	396339	02/25/26	02/26/26	KMB
4,4'-DDD	ND		ug/Kg	10	2	396339	02/25/26	02/26/26	KMB
Endrin aldehyde	ND		ug/Kg	10	2	396339	02/25/26	02/26/26	KMB
Endrin ketone	ND		ug/Kg	10	2	396339	02/25/26	02/26/26	KMB
4,4'-DDT	ND		ug/Kg	10	2	396339	02/25/26	02/26/26	KMB
Methoxychlor	ND		ug/Kg	20	2	396339	02/25/26	02/26/26	KMB
Toxaphene	ND		ug/Kg	200	2	396339	02/25/26	02/26/26	KMB
Chlordane (Technical)	ND		ug/Kg	100	2	396339	02/25/26	02/26/26	KMB
Surrogates				**Limits**					
TCMX	78%		%REC	58-120	2	396339	02/25/26	02/26/26	KMB
Decachlorobiphenyl	72%		%REC	47-120	2	396339	02/25/26	02/26/26	KMB

Results for any subcontracted analyses are not included in this section.

ENTHALPY ANALYTICAL

Analysis Results for 553784

Sample ID: CG-43-2.5	Lab ID: 553784-034	Collected: 02/19/26
	Matrix: Soil	

553784-034 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 8081A Prep Method: EPA 3546									
alpha-BHC	ND		ug/Kg	9.9	2	396339	02/25/26	02/26/26	KMB
beta-BHC	ND		ug/Kg	9.9	2	396339	02/25/26	02/26/26	KMB
gamma-BHC	ND		ug/Kg	9.9	2	396339	02/25/26	02/26/26	KMB
delta-BHC	ND		ug/Kg	9.9	2	396339	02/25/26	02/26/26	KMB
Heptachlor	ND		ug/Kg	9.9	2	396339	02/25/26	02/26/26	KMB
Aldrin	ND		ug/Kg	9.9	2	396339	02/25/26	02/26/26	KMB
Heptachlor epoxide	ND		ug/Kg	9.9	2	396339	02/25/26	02/26/26	KMB
Endosulfan I	ND		ug/Kg	9.9	2	396339	02/25/26	02/26/26	KMB
Dieldrin	ND		ug/Kg	9.9	2	396339	02/25/26	02/26/26	KMB
4,4'-DDE	ND		ug/Kg	9.9	2	396339	02/25/26	02/26/26	KMB
Endrin	ND		ug/Kg	9.9	2	396339	02/25/26	02/26/26	KMB
Endosulfan II	ND		ug/Kg	9.9	2	396339	02/25/26	02/26/26	KMB
Endosulfan sulfate	ND		ug/Kg	9.9	2	396339	02/25/26	02/26/26	KMB
4,4'-DDD	ND		ug/Kg	9.9	2	396339	02/25/26	02/26/26	KMB
Endrin aldehyde	ND		ug/Kg	9.9	2	396339	02/25/26	02/26/26	KMB
Endrin ketone	ND		ug/Kg	9.9	2	396339	02/25/26	02/26/26	KMB
4,4'-DDT	ND		ug/Kg	9.9	2	396339	02/25/26	02/26/26	KMB
Methoxychlor	ND		ug/Kg	20	2	396339	02/25/26	02/26/26	KMB
Toxaphene	ND		ug/Kg	200	2	396339	02/25/26	02/26/26	KMB
Chlordane (Technical)	ND		ug/Kg	99	2	396339	02/25/26	02/26/26	KMB
Surrogates				**Limits**					
TCMX	84%		%REC	58-120	2	396339	02/25/26	02/26/26	KMB
Decachlorobiphenyl	76%		%REC	47-120	2	396339	02/25/26	02/26/26	KMB

Results for any subcontracted analyses are not included in this section.

Analysis Results for 553784

Sample ID: EB-01-260219	Lab ID: 553784-035	Collected: 02/19/26 15:30
	Matrix: Water	

553784-035 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3015A									
Lead	ND		mg/L	0.010	1	396012	02/21/26	02/21/26	KAM
Method: EPA 8081A Prep Method: EPA 3510C									
alpha-BHC	ND		ug/L	0.05	0.93	396077	02/22/26	02/25/26	XLY
beta-BHC	ND		ug/L	0.05	0.93	396077	02/22/26	02/25/26	XLY
gamma-BHC	ND		ug/L	0.05	0.93	396077	02/22/26	02/25/26	XLY
delta-BHC	ND		ug/L	0.05	0.93	396077	02/22/26	02/25/26	XLY
Heptachlor	ND		ug/L	0.05	0.93	396077	02/22/26	02/25/26	XLY
Aldrin	ND		ug/L	0.05	0.93	396077	02/22/26	02/25/26	XLY
Heptachlor epoxide	ND		ug/L	0.05	0.93	396077	02/22/26	02/25/26	XLY
Endosulfan I	ND		ug/L	0.05	0.93	396077	02/22/26	02/25/26	XLY
Dieldrin	ND		ug/L	0.09	0.93	396077	02/22/26	02/25/26	XLY
4,4'-DDE	ND		ug/L	0.09	0.93	396077	02/22/26	02/25/26	XLY
Endrin	ND		ug/L	0.09	0.93	396077	02/22/26	02/25/26	XLY
Endosulfan II	ND		ug/L	0.09	0.93	396077	02/22/26	02/25/26	XLY
Endosulfan sulfate	ND		ug/L	0.09	0.93	396077	02/22/26	02/25/26	XLY
4,4'-DDD	ND		ug/L	0.09	0.93	396077	02/22/26	02/25/26	XLY
Endrin aldehyde	ND		ug/L	0.09	0.93	396077	02/22/26	02/25/26	XLY
Endrin ketone	ND		ug/L	0.09	0.93	396077	02/22/26	02/25/26	XLY
4,4'-DDT	ND		ug/L	0.09	0.93	396077	02/22/26	02/25/26	XLY
Methoxychlor	ND		ug/L	0.09	0.93	396077	02/22/26	02/25/26	XLY
Toxaphene	ND		ug/L	1.9	0.93	396077	02/22/26	02/25/26	XLY
Chlordane (Technical)	ND		ug/L	0.9	0.93	396077	02/22/26	02/25/26	XLY
Surrogates				**Limits**					
TCMX	68%		%REC	29-120	0.93	396077	02/22/26	02/25/26	XLY
Decachlorobiphenyl	106%		%REC	33-132	0.93	396077	02/22/26	02/25/26	XLY
Method: EPA 8082 Prep Method: EPA 3510C									
Aroclor-1016	ND		ug/L	0.47	0.93	396077	02/22/26	02/25/26	XLY
Aroclor-1221	ND		ug/L	0.47	0.93	396077	02/22/26	02/25/26	XLY
Aroclor-1232	ND		ug/L	0.47	0.93	396077	02/22/26	02/25/26	XLY
Aroclor-1242	ND		ug/L	0.47	0.93	396077	02/22/26	02/25/26	XLY
Aroclor-1248	ND		ug/L	0.47	0.93	396077	02/22/26	02/25/26	XLY
Aroclor-1254	ND		ug/L	0.47	0.93	396077	02/22/26	02/25/26	XLY
Aroclor-1260	ND		ug/L	0.47	0.93	396077	02/22/26	02/25/26	XLY
Aroclor-1262	ND		ug/L	0.47	0.93	396077	02/22/26	02/25/26	XLY
Aroclor-1268	ND		ug/L	0.47	0.93	396077	02/22/26	02/25/26	XLY
Total PCBs	ND		ug/L	0.47	0.93	396077	02/22/26	02/25/26	XLY
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	64%		%REC	28-138	0.93	396077	02/22/26	02/25/26	XLY

Results for any subcontracted analyses are not included in this section.

ENTHALPY ANALYTICAL

Analysis Results for 553784

Sample ID: CG-38-0.5	Lab ID: 553784-036	Collected: 02/19/26
	Matrix: Soil	

553784-036 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 8081A Prep Method: EPA 3546									
alpha-BHC	ND		ug/Kg	4.9	0.98	396339	02/25/26	02/26/26	KMB
beta-BHC	ND		ug/Kg	4.9	0.98	396339	02/25/26	02/26/26	KMB
gamma-BHC	ND		ug/Kg	4.9	0.98	396339	02/25/26	02/26/26	KMB
delta-BHC	ND		ug/Kg	4.9	0.98	396339	02/25/26	02/26/26	KMB
Heptachlor	ND		ug/Kg	4.9	0.98	396339	02/25/26	02/26/26	KMB
Aldrin	ND		ug/Kg	4.9	0.98	396339	02/25/26	02/26/26	KMB
Heptachlor epoxide	ND		ug/Kg	4.9	0.98	396339	02/25/26	02/26/26	KMB
Endosulfan I	ND		ug/Kg	4.9	0.98	396339	02/25/26	02/26/26	KMB
Dieldrin	ND		ug/Kg	4.9	0.98	396339	02/25/26	02/26/26	KMB
4,4'-DDE	ND		ug/Kg	4.9	0.98	396339	02/25/26	02/26/26	KMB
Endrin	ND		ug/Kg	4.9	0.98	396339	02/25/26	02/26/26	KMB
Endosulfan II	ND		ug/Kg	4.9	0.98	396339	02/25/26	02/26/26	KMB
Endosulfan sulfate	ND		ug/Kg	4.9	0.98	396339	02/25/26	02/26/26	KMB
4,4'-DDD	ND		ug/Kg	4.9	0.98	396339	02/25/26	02/26/26	KMB
Endrin aldehyde	ND		ug/Kg	4.9	0.98	396339	02/25/26	02/26/26	KMB
Endrin ketone	ND		ug/Kg	4.9	0.98	396339	02/25/26	02/26/26	KMB
4,4'-DDT	ND		ug/Kg	4.9	0.98	396339	02/25/26	02/26/26	KMB
Methoxychlor	ND		ug/Kg	9.8	0.98	396339	02/25/26	02/26/26	KMB
Toxaphene	ND		ug/Kg	98	0.98	396339	02/25/26	02/26/26	KMB
Chlordane (Technical)	ND		ug/Kg	49	0.98	396339	02/25/26	02/26/26	KMB
Surrogates				**Limits**					
TCMX	86%		%REC	58-120	0.98	396339	02/25/26	02/26/26	KMB
Decachlorobiphenyl	76%		%REC	47-120	0.98	396339	02/25/26	02/26/26	KMB

Results for any subcontracted analyses are not included in this section.

ENTHALPY ANALYTICAL

Analysis Results for 553784

Sample ID: CG-38-2.5	Lab ID: 553784-037	Collected: 02/19/26
	Matrix: Soil	

553784-037 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 8081A Prep Method: EPA 3546									
alpha-BHC	ND		ug/Kg	5.1	1	396339	02/25/26	02/26/26	KMB
beta-BHC	ND		ug/Kg	5.1	1	396339	02/25/26	02/26/26	KMB
gamma-BHC	ND		ug/Kg	5.1	1	396339	02/25/26	02/26/26	KMB
delta-BHC	ND		ug/Kg	5.1	1	396339	02/25/26	02/26/26	KMB
Heptachlor	ND		ug/Kg	5.1	1	396339	02/25/26	02/26/26	KMB
Aldrin	ND		ug/Kg	5.1	1	396339	02/25/26	02/26/26	KMB
Heptachlor epoxide	ND		ug/Kg	5.1	1	396339	02/25/26	02/26/26	KMB
Endosulfan I	ND		ug/Kg	5.1	1	396339	02/25/26	02/26/26	KMB
Dieldrin	ND		ug/Kg	5.1	1	396339	02/25/26	02/26/26	KMB
4,4'-DDE	ND		ug/Kg	5.1	1	396339	02/25/26	02/26/26	KMB
Endrin	ND		ug/Kg	5.1	1	396339	02/25/26	02/26/26	KMB
Endosulfan II	ND		ug/Kg	5.1	1	396339	02/25/26	02/26/26	KMB
Endosulfan sulfate	ND		ug/Kg	5.1	1	396339	02/25/26	02/26/26	KMB
4,4'-DDD	ND		ug/Kg	5.1	1	396339	02/25/26	02/26/26	KMB
Endrin aldehyde	ND		ug/Kg	5.1	1	396339	02/25/26	02/26/26	KMB
Endrin ketone	ND		ug/Kg	5.1	1	396339	02/25/26	02/26/26	KMB
4,4'-DDT	ND		ug/Kg	5.1	1	396339	02/25/26	02/26/26	KMB
Methoxychlor	ND		ug/Kg	10	1	396339	02/25/26	02/26/26	KMB
Toxaphene	ND		ug/Kg	100	1	396339	02/25/26	02/26/26	KMB
Chlordane (Technical)	ND		ug/Kg	51	1	396339	02/25/26	02/26/26	KMB
Surrogates				**Limits**					
TCMX	80%		%REC	58-120	1	396339	02/25/26	02/26/26	KMB
Decachlorobiphenyl	72%		%REC	47-120	1	396339	02/25/26	02/26/26	KMB

Results for any subcontracted analyses are not included in this section.

Analysis Results for 553784

Sample ID: CG-38-0.5-DUP	Lab ID: 553784-038	Collected: 02/19/26
	Matrix: Soil	

553784-038 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 8081A Prep Method: EPA 3546									
alpha-BHC	ND		ug/Kg	5.0	1	396339	02/25/26	02/26/26	KMB
beta-BHC	ND		ug/Kg	5.0	1	396339	02/25/26	02/26/26	KMB
gamma-BHC	ND		ug/Kg	5.0	1	396339	02/25/26	02/26/26	KMB
delta-BHC	ND		ug/Kg	5.0	1	396339	02/25/26	02/26/26	KMB
Heptachlor	ND		ug/Kg	5.0	1	396339	02/25/26	02/26/26	KMB
Aldrin	ND		ug/Kg	5.0	1	396339	02/25/26	02/26/26	KMB
Heptachlor epoxide	ND		ug/Kg	5.0	1	396339	02/25/26	02/26/26	KMB
Endosulfan I	ND		ug/Kg	5.0	1	396339	02/25/26	02/26/26	KMB
Dieldrin	ND		ug/Kg	5.0	1	396339	02/25/26	02/26/26	KMB
4,4'-DDE	ND		ug/Kg	5.0	1	396339	02/25/26	02/26/26	KMB
Endrin	ND		ug/Kg	5.0	1	396339	02/25/26	02/26/26	KMB
Endosulfan II	ND		ug/Kg	5.0	1	396339	02/25/26	02/26/26	KMB
Endosulfan sulfate	ND		ug/Kg	5.0	1	396339	02/25/26	02/26/26	KMB
4,4'-DDD	ND		ug/Kg	5.0	1	396339	02/25/26	02/26/26	KMB
Endrin aldehyde	ND		ug/Kg	5.0	1	396339	02/25/26	02/26/26	KMB
Endrin ketone	ND		ug/Kg	5.0	1	396339	02/25/26	02/26/26	KMB
4,4'-DDT	ND		ug/Kg	5.0	1	396339	02/25/26	02/26/26	KMB
Methoxychlor	ND		ug/Kg	10	1	396339	02/25/26	02/26/26	KMB
Toxaphene	ND		ug/Kg	100	1	396339	02/25/26	02/26/26	KMB
Chlordane (Technical)	ND		ug/Kg	50	1	396339	02/25/26	02/26/26	KMB
Surrogates				**Limits**					
TCMX	82%		%REC	58-120	1	396339	02/25/26	02/26/26	KMB
Decachlorobiphenyl	68%		%REC	47-120	1	396339	02/25/26	02/26/26	KMB

Results for any subcontracted analyses are not included in this section.

ENTHALPY ANALYTICAL

Analysis Results for 553784

Sample ID: CG-38-2.5-DUP	Lab ID: 553784-039	Collected: 02/19/26
	Matrix: Soil	

553784-039 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 8081A Prep Method: EPA 3546									
alpha-BHC	ND		ug/Kg	5.0	1	396339	02/25/26	02/26/26	KMB
beta-BHC	ND		ug/Kg	5.0	1	396339	02/25/26	02/26/26	KMB
gamma-BHC	ND		ug/Kg	5.0	1	396339	02/25/26	02/26/26	KMB
delta-BHC	ND		ug/Kg	5.0	1	396339	02/25/26	02/26/26	KMB
Heptachlor	ND		ug/Kg	5.0	1	396339	02/25/26	02/26/26	KMB
Aldrin	ND		ug/Kg	5.0	1	396339	02/25/26	02/26/26	KMB
Heptachlor epoxide	ND		ug/Kg	5.0	1	396339	02/25/26	02/26/26	KMB
Endosulfan I	ND		ug/Kg	5.0	1	396339	02/25/26	02/26/26	KMB
Dieldrin	ND		ug/Kg	5.0	1	396339	02/25/26	02/26/26	KMB
4,4'-DDE	ND		ug/Kg	5.0	1	396339	02/25/26	02/26/26	KMB
Endrin	ND		ug/Kg	5.0	1	396339	02/25/26	02/26/26	KMB
Endosulfan II	ND		ug/Kg	5.0	1	396339	02/25/26	02/26/26	KMB
Endosulfan sulfate	ND		ug/Kg	5.0	1	396339	02/25/26	02/26/26	KMB
4,4'-DDD	ND		ug/Kg	5.0	1	396339	02/25/26	02/26/26	KMB
Endrin aldehyde	ND		ug/Kg	5.0	1	396339	02/25/26	02/26/26	KMB
Endrin ketone	ND		ug/Kg	5.0	1	396339	02/25/26	02/26/26	KMB
4,4'-DDT	ND		ug/Kg	5.0	1	396339	02/25/26	02/26/26	KMB
Methoxychlor	ND		ug/Kg	10	1	396339	02/25/26	02/26/26	KMB
Toxaphene	ND		ug/Kg	100	1	396339	02/25/26	02/26/26	KMB
Chlordane (Technical)	ND		ug/Kg	50	1	396339	02/25/26	02/26/26	KMB
Surrogates				**Limits**					
TCMX	81%		%REC	58-120	1	396339	02/25/26	02/26/26	KMB
Decachlorobiphenyl	67%		%REC	47-120	1	396339	02/25/26	02/26/26	KMB

Results for any subcontracted analyses are not included in this section.

ENTHALPY ANALYTICAL

Analysis Results for 553784

Sample ID: CG-40-0.5	Lab ID: 553784-040	Collected: 02/19/26
	Matrix: Soil	

553784-040 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 8081A Prep Method: EPA 3546									
alpha-BHC	ND		ug/Kg	4.9	0.98	396712	02/28/26	03/02/26	XLY
beta-BHC	ND		ug/Kg	4.9	0.98	396712	02/28/26	03/02/26	XLY
gamma-BHC	ND		ug/Kg	4.9	0.98	396712	02/28/26	03/02/26	XLY
delta-BHC	ND		ug/Kg	4.9	0.98	396712	02/28/26	03/02/26	XLY
Heptachlor	ND		ug/Kg	4.9	0.98	396712	02/28/26	03/02/26	XLY
Aldrin	ND		ug/Kg	4.9	0.98	396712	02/28/26	03/02/26	XLY
Heptachlor epoxide	ND		ug/Kg	4.9	0.98	396712	02/28/26	03/02/26	XLY
Endosulfan I	ND		ug/Kg	4.9	0.98	396712	02/28/26	03/02/26	XLY
Dieldrin	**12**	C	ug/Kg	4.9	0.98	396712	02/28/26	03/02/26	XLY
4,4'-DDE	**150**		ug/Kg	4.9	0.98	396712	02/28/26	03/02/26	XLY
Endrin	ND		ug/Kg	4.9	0.98	396712	02/28/26	03/02/26	XLY
Endosulfan II	ND		ug/Kg	4.9	0.98	396712	02/28/26	03/02/26	XLY
Endosulfan sulfate	ND		ug/Kg	4.9	0.98	396712	02/28/26	03/02/26	XLY
4,4'-DDD	ND		ug/Kg	4.9	0.98	396712	02/28/26	03/02/26	XLY
Endrin aldehyde	ND		ug/Kg	4.9	0.98	396712	02/28/26	03/02/26	XLY
Endrin ketone	ND		ug/Kg	4.9	0.98	396712	02/28/26	03/02/26	XLY
4,4'-DDT	**42**		ug/Kg	4.9	0.98	396712	02/28/26	03/02/26	XLY
Methoxychlor	ND		ug/Kg	9.8	0.98	396712	02/28/26	03/02/26	XLY
Toxaphene	ND		ug/Kg	98	0.98	396712	02/28/26	03/02/26	XLY
Chlordane (Technical)	**110**		ug/Kg	49	0.98	396712	02/28/26	03/02/26	XLY
Surrogates				**Limits**					
TCMX	87%		%REC	58-120	0.98	396712	02/28/26	03/02/26	XLY
Decachlorobiphenyl	70%		%REC	47-120	0.98	396712	02/28/26	03/02/26	XLY

Results for any subcontracted analyses are not included in this section.

Analysis Results for 553784

Sample ID: CG-40-2.5	Lab ID: 553784-041	Collected: 02/19/26
	Matrix: Soil	

553784-041 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 8081A Prep Method: EPA 3546									
alpha-BHC	ND		ug/Kg	5.0	1	396339	02/25/26	02/26/26	KMB
beta-BHC	ND		ug/Kg	5.0	1	396339	02/25/26	02/26/26	KMB
gamma-BHC	ND		ug/Kg	5.0	1	396339	02/25/26	02/26/26	KMB
delta-BHC	ND		ug/Kg	5.0	1	396339	02/25/26	02/26/26	KMB
Heptachlor	ND		ug/Kg	5.0	1	396339	02/25/26	02/26/26	KMB
Aldrin	ND		ug/Kg	5.0	1	396339	02/25/26	02/26/26	KMB
Heptachlor epoxide	ND		ug/Kg	5.0	1	396339	02/25/26	02/26/26	KMB
Endosulfan I	ND		ug/Kg	5.0	1	396339	02/25/26	02/26/26	KMB
Dieldrin	ND		ug/Kg	5.0	1	396339	02/25/26	02/26/26	KMB
4,4'-DDE	ND		ug/Kg	5.0	1	396339	02/25/26	02/26/26	KMB
Endrin	ND		ug/Kg	5.0	1	396339	02/25/26	02/26/26	KMB
Endosulfan II	ND		ug/Kg	5.0	1	396339	02/25/26	02/26/26	KMB
Endosulfan sulfate	ND		ug/Kg	5.0	1	396339	02/25/26	02/26/26	KMB
4,4'-DDD	ND		ug/Kg	5.0	1	396339	02/25/26	02/26/26	KMB
Endrin aldehyde	ND		ug/Kg	5.0	1	396339	02/25/26	02/26/26	KMB
Endrin ketone	ND		ug/Kg	5.0	1	396339	02/25/26	02/26/26	KMB
4,4'-DDT	ND		ug/Kg	5.0	1	396339	02/25/26	02/26/26	KMB
Methoxychlor	ND		ug/Kg	10	1	396339	02/25/26	02/26/26	KMB
Toxaphene	ND		ug/Kg	100	1	396339	02/25/26	02/26/26	KMB
Chlordane (Technical)	ND		ug/Kg	50	1	396339	02/25/26	02/26/26	KMB
Surrogates				**Limits**					
TCMX	86%		%REC	58-120	1	396339	02/25/26	02/26/26	KMB
Decachlorobiphenyl	72%		%REC	47-120	1	396339	02/25/26	02/26/26	KMB

Results for any subcontracted analyses are not included in this section.

ENTHALPY ANALYTICAL

Analysis Results for 553784

Sample ID: CG-41-0.5	Lab ID: 553784-042	Collected: 02/19/26
	Matrix: Soil	

553784-042 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 8081A Prep Method: EPA 3546									
alpha-BHC	ND		ug/Kg	5.0	1	396339	02/25/26	02/26/26	KMB
beta-BHC	ND		ug/Kg	5.0	1	396339	02/25/26	02/26/26	KMB
gamma-BHC	ND		ug/Kg	5.0	1	396339	02/25/26	02/26/26	KMB
delta-BHC	ND		ug/Kg	5.0	1	396339	02/25/26	02/26/26	KMB
Heptachlor	ND		ug/Kg	5.0	1	396339	02/25/26	02/26/26	KMB
Aldrin	ND		ug/Kg	5.0	1	396339	02/25/26	02/26/26	KMB
Heptachlor epoxide	ND		ug/Kg	5.0	1	396339	02/25/26	02/26/26	KMB
Endosulfan I	ND		ug/Kg	5.0	1	396339	02/25/26	02/26/26	KMB
Dieldrin	ND		ug/Kg	5.0	1	396339	02/25/26	02/26/26	KMB
4,4'-DDE	**14**		ug/Kg	5.0	1	396339	02/25/26	02/26/26	KMB
Endrin	ND		ug/Kg	5.0	1	396339	02/25/26	02/26/26	KMB
Endosulfan II	ND		ug/Kg	5.0	1	396339	02/25/26	02/26/26	KMB
Endosulfan sulfate	ND		ug/Kg	5.0	1	396339	02/25/26	02/26/26	KMB
4,4'-DDD	ND		ug/Kg	5.0	1	396339	02/25/26	02/26/26	KMB
Endrin aldehyde	ND		ug/Kg	5.0	1	396339	02/25/26	02/26/26	KMB
Endrin ketone	ND		ug/Kg	5.0	1	396339	02/25/26	02/26/26	KMB
4,4'-DDT	**5.8**		ug/Kg	5.0	1	396339	02/25/26	02/26/26	KMB
Methoxychlor	ND		ug/Kg	10	1	396339	02/25/26	02/26/26	KMB
Toxaphene	ND		ug/Kg	100	1	396339	02/25/26	02/26/26	KMB
Chlordane (Technical)	ND		ug/Kg	50	1	396339	02/25/26	02/26/26	KMB
Surrogates				**Limits**					
TCMX	79%		%REC	58-120	1	396339	02/25/26	02/26/26	KMB
Decachlorobiphenyl	76%		%REC	47-120	1	396339	02/25/26	02/26/26	KMB

Results for any subcontracted analyses are not included in this section.

ENTHALPY ANALYTICAL

Analysis Results for 553784

Sample ID: CG-41-2.5	Lab ID: 553784-043	Collected: 02/19/26
	Matrix: Soil	

553784-043 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 8081A Prep Method: EPA 3546									
alpha-BHC	ND		ug/Kg	5.1	1	396339	02/25/26	02/26/26	KMB
beta-BHC	ND		ug/Kg	5.1	1	396339	02/25/26	02/26/26	KMB
gamma-BHC	ND		ug/Kg	5.1	1	396339	02/25/26	02/26/26	KMB
delta-BHC	ND		ug/Kg	5.1	1	396339	02/25/26	02/26/26	KMB
Heptachlor	ND		ug/Kg	5.1	1	396339	02/25/26	02/26/26	KMB
Aldrin	ND		ug/Kg	5.1	1	396339	02/25/26	02/26/26	KMB
Heptachlor epoxide	ND		ug/Kg	5.1	1	396339	02/25/26	02/26/26	KMB
Endosulfan I	ND		ug/Kg	5.1	1	396339	02/25/26	02/26/26	KMB
Dieldrin	ND		ug/Kg	5.1	1	396339	02/25/26	02/26/26	KMB
4,4'-DDE	ND		ug/Kg	5.1	1	396339	02/25/26	02/26/26	KMB
Endrin	ND		ug/Kg	5.1	1	396339	02/25/26	02/26/26	KMB
Endosulfan II	ND		ug/Kg	5.1	1	396339	02/25/26	02/26/26	KMB
Endosulfan sulfate	ND		ug/Kg	5.1	1	396339	02/25/26	02/26/26	KMB
4,4'-DDD	ND		ug/Kg	5.1	1	396339	02/25/26	02/26/26	KMB
Endrin aldehyde	ND		ug/Kg	5.1	1	396339	02/25/26	02/26/26	KMB
Endrin ketone	ND		ug/Kg	5.1	1	396339	02/25/26	02/26/26	KMB
4,4'-DDT	ND		ug/Kg	5.1	1	396339	02/25/26	02/26/26	KMB
Methoxychlor	ND		ug/Kg	10	1	396339	02/25/26	02/26/26	KMB
Toxaphene	ND		ug/Kg	100	1	396339	02/25/26	02/26/26	KMB
Chlordane (Technical)	ND		ug/Kg	51	1	396339	02/25/26	02/26/26	KMB
Surrogates				**Limits**					
TCMX	83%		%REC	58-120	1	396339	02/25/26	02/26/26	KMB
Decachlorobiphenyl	65%		%REC	47-120	1	396339	02/25/26	02/26/26	KMB

Results for any subcontracted analyses are not included in this section.

ENTHALPY ANALYTICAL

Analysis Results for 553784

Sample ID: CG-42-0.5	Lab ID: 553784-044	Collected: 02/19/26
	Matrix: Soil	

553784-044 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 8081A Prep Method: EPA 3546									
alpha-BHC	ND		ug/Kg	5.1	1	396339	02/25/26	02/26/26	KMB
beta-BHC	ND		ug/Kg	5.1	1	396339	02/25/26	02/26/26	KMB
gamma-BHC	ND		ug/Kg	5.1	1	396339	02/25/26	02/26/26	KMB
delta-BHC	ND		ug/Kg	5.1	1	396339	02/25/26	02/26/26	KMB
Heptachlor	ND		ug/Kg	5.1	1	396339	02/25/26	02/26/26	KMB
Aldrin	ND		ug/Kg	5.1	1	396339	02/25/26	02/26/26	KMB
Heptachlor epoxide	ND		ug/Kg	5.1	1	396339	02/25/26	02/26/26	KMB
Endosulfan I	ND		ug/Kg	5.1	1	396339	02/25/26	02/26/26	KMB
Dieldrin	ND		ug/Kg	5.1	1	396339	02/25/26	02/26/26	KMB
4,4'-DDE	ND		ug/Kg	5.1	1	396339	02/25/26	02/26/26	KMB
Endrin	ND		ug/Kg	5.1	1	396339	02/25/26	02/26/26	KMB
Endosulfan II	ND		ug/Kg	5.1	1	396339	02/25/26	02/26/26	KMB
Endosulfan sulfate	ND		ug/Kg	5.1	1	396339	02/25/26	02/26/26	KMB
4,4'-DDD	ND		ug/Kg	5.1	1	396339	02/25/26	02/26/26	KMB
Endrin aldehyde	ND		ug/Kg	5.1	1	396339	02/25/26	02/26/26	KMB
Endrin ketone	ND		ug/Kg	5.1	1	396339	02/25/26	02/26/26	KMB
4,4'-DDT	**5.4**		ug/Kg	5.1	1	396339	02/25/26	02/26/26	KMB
Methoxychlor	ND		ug/Kg	10	1	396339	02/25/26	02/26/26	KMB
Toxaphene	ND		ug/Kg	100	1	396339	02/25/26	02/26/26	KMB
Chlordane (Technical)	ND		ug/Kg	51	1	396339	02/25/26	02/26/26	KMB
Surrogates				**Limits**					
TCMX	85%		%REC	58-120	1	396339	02/25/26	02/26/26	KMB
Decachlorobiphenyl	72%		%REC	47-120	1	396339	02/25/26	02/26/26	KMB

Results for any subcontracted analyses are not included in this section.

ENTHALPY ANALYTICAL

Analysis Results for 553784

Sample ID: CG-42-2.5	Lab ID: 553784-045	Collected: 02/19/26
	Matrix: Soil	

553784-045 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 8081A Prep Method: EPA 3546									
alpha-BHC	ND		ug/Kg	4.9	0.98	396339	02/25/26	02/26/26	KMB
beta-BHC	ND		ug/Kg	4.9	0.98	396339	02/25/26	02/26/26	KMB
gamma-BHC	ND		ug/Kg	4.9	0.98	396339	02/25/26	02/26/26	KMB
delta-BHC	ND		ug/Kg	4.9	0.98	396339	02/25/26	02/26/26	KMB
Heptachlor	ND		ug/Kg	4.9	0.98	396339	02/25/26	02/26/26	KMB
Aldrin	ND		ug/Kg	4.9	0.98	396339	02/25/26	02/26/26	KMB
Heptachlor epoxide	ND		ug/Kg	4.9	0.98	396339	02/25/26	02/26/26	KMB
Endosulfan I	ND		ug/Kg	4.9	0.98	396339	02/25/26	02/26/26	KMB
Dieldrin	ND		ug/Kg	4.9	0.98	396339	02/25/26	02/26/26	KMB
4,4'-DDE	ND		ug/Kg	4.9	0.98	396339	02/25/26	02/26/26	KMB
Endrin	ND		ug/Kg	4.9	0.98	396339	02/25/26	02/26/26	KMB
Endosulfan II	ND		ug/Kg	4.9	0.98	396339	02/25/26	02/26/26	KMB
Endosulfan sulfate	ND		ug/Kg	4.9	0.98	396339	02/25/26	02/26/26	KMB
4,4'-DDD	ND		ug/Kg	4.9	0.98	396339	02/25/26	02/26/26	KMB
Endrin aldehyde	ND		ug/Kg	4.9	0.98	396339	02/25/26	02/26/26	KMB
Endrin ketone	ND		ug/Kg	4.9	0.98	396339	02/25/26	02/26/26	KMB
4,4'-DDT	ND		ug/Kg	4.9	0.98	396339	02/25/26	02/26/26	KMB
Methoxychlor	ND		ug/Kg	9.8	0.98	396339	02/25/26	02/26/26	KMB
Toxaphene	ND		ug/Kg	98	0.98	396339	02/25/26	02/26/26	KMB
Chlordane (Technical)	ND		ug/Kg	49	0.98	396339	02/25/26	02/26/26	KMB
Surrogates				**Limits**					
TCMX	83%		%REC	58-120	0.98	396339	02/25/26	02/26/26	KMB
Decachlorobiphenyl	72%		%REC	47-120	0.98	396339	02/25/26	02/26/26	KMB

C Presence confirmed, but RPD between columns exceeds 40%
ND Not Detected

Results for any subcontracted analyses are not included in this section.

ENTHALPY ANALYTICAL

Batch QC

Type: Blank **Lab ID: QC1342828** **Batch: 396012**
Matrix: Water **Method: EPA 6010B** **Prep Method: EPA 3015A**

QC1342828 Analyte	Result	Qual	Units	RL	Prepared	Analyzed
Lead	ND		mg/L	0.010	02/21/26	02/21/26

Type: Lab Control Sample **Lab ID: QC1342829** **Batch: 396012**
Matrix: Water **Method: EPA 6010B** **Prep Method: EPA 3015A**

QC1342829 Analyte	Result	Spiked	Units	Recovery	Qual	Limits
Lead	0.3593	0.4000	mg/L	90%		80-120

Type: Matrix Spike **Lab ID: QC1342834** **Batch: 396012**
Matrix (Source ID): Water (553654-001) **Method: EPA 6010B** **Prep Method: EPA 3015A**

QC1342834 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	DF
Lead	0.3812	0.002315	0.4000	mg/L	95%		75-125	1

Type: Matrix Spike Duplicate **Lab ID: QC1342835** **Batch: 396012**
Matrix (Source ID): Water (553654-001) **Method: EPA 6010B** **Prep Method: EPA 3015A**

QC1342835 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	RPD	RPD Lim	DF
Lead	0.3650	0.002315	0.4000	mg/L	91%		75-125	4	20	1

Type: Serial Dilution **Lab ID: QC1342933** **Batch: 396012**
Matrix (Source ID): Water (553907-001) **Method: EPA 6010B** **Prep Method: EPA 3015A**

QC1342933 Analyte	Result	Source Sample Result	Units	Qual	RPD	RPD Lim	DF
Lead	ND	0.03966	mg/L				50

Type: Blank **Lab ID: QC1343463** **Batch: 396187**
Matrix: Soil **Method: EPA 6010B** **Prep Method: EPA 3050B**

QC1343463 Analyte	Result	Qual	Units	RL	Prepared	Analyzed
Lead	ND		mg/Kg	1.0	02/23/26	02/24/26

Type: Lab Control Sample **Lab ID: QC1343464** **Batch: 396187**
Matrix: Soil **Method: EPA 6010B** **Prep Method: EPA 3050B**

QC1343464 Analyte	Result	Spiked	Units	Recovery	Qual	Limits
Lead	108.5	100.0	mg/Kg	109%		80-120

ENTHALPY ANALYTICAL

Batch QC

Type:	Matrix Spike	Lab ID:	QC1343465	Batch:	396187
Matrix (Source ID):	Soil (553922-004)	Method:	EPA 6010B	Prep Method:	EPA 3050B

QC1343465 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	DF
Lead	105.9	3.884	98.04	mg/Kg	104%		75-125	0.98

Type:	Matrix Spike Duplicate	Lab ID:	QC1343466	Batch:	396187
Matrix (Source ID):	Soil (553922-004)	Method:	EPA 6010B	Prep Method:	EPA 3050B

QC1343466 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	RPD	RPD Lim	DF
Lead	106.6	3.884	100.0	mg/Kg	103%		75-125	1	28	1

Type:	Post Digest Spike	Lab ID:	QC1343467	Batch:	396187
Matrix (Source ID):	Soil (553922-004)	Method:	EPA 6010B	Prep Method:	EPA 3050B

QC1343467 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	DF
Lead	95.71	3.884	97.09	mg/Kg	95%		75-125	0.97

Type:	Serial Dilution	Lab ID:	QC1343701	Batch:	396187
Matrix (Source ID):	Soil (553922-004)	Method:	EPA 6010B	Prep Method:	EPA 3050B

QC1343701 Analyte	Result	Source Sample Result	Units	Qual	RPD	RPD Lim	DF
Lead	3.803	3.884	mg/Kg	J			4.9

Type:	Blank	Lab ID:	QC1343532	Batch:	396205
Matrix:	Soil	Method:	EPA 6010B	Prep Method:	EPA 3050B

QC1343532 Analyte	Result	Qual	Units	RL	Prepared	Analyzed
Lead	ND		mg/Kg	1.0	02/24/26	02/24/26

Type:	Lab Control Sample	Lab ID:	QC1343533	Batch:	396205
Matrix:	Soil	Method:	EPA 6010B	Prep Method:	EPA 3050B

QC1343533 Analyte	Result	Spiked	Units	Recovery	Qual	Limits
Lead	109.6	100.0	mg/Kg	110%		80-120

ENTHALPY ANALYTICAL

Batch QC

Type:	Matrix Spike	Lab ID:	QC1343534	Batch:	396205
Matrix (Source ID):	Soil (553784-009)	Method:	EPA 6010B	Prep Method:	EPA 3050B

QC1343534 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	DF
Lead	110.4	8.382	100.0	mg/Kg	102%		75-125	1

Type:	Matrix Spike Duplicate	Lab ID:	QC1343535	Batch:	396205
Matrix (Source ID):	Soil (553784-009)	Method:	EPA 6010B	Prep Method:	EPA 3050B

QC1343535 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	RPD	RPD Lim	DF
Lead	107.9	8.382	96.15	mg/Kg	104%		75-125	1	28	0.96

Type:	Post Digest Spike	Lab ID:	QC1343536	Batch:	396205
Matrix (Source ID):	Soil (553784-009)	Method:	EPA 6010B	Prep Method:	EPA 3050B

QC1343536 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	DF
Lead	103.9	8.382	98.04	mg/Kg	97%		75-125	0.98

Type:	Serial Dilution	Lab ID:	QC1343799	Batch:	396205
Matrix (Source ID):	Soil (553784-009)	Method:	EPA 6010B	Prep Method:	EPA 3050B

QC1343799 Analyte	Result	Source Sample Result	Units	Qual	RPD	RPD Lim	DF
Lead	10.08	8.382	mg/Kg				4.9

ENTHALPY ANALYTICAL

Batch QC

Type:	**Blank**	**Lab ID:**	**QC1344116**	**Batch:**	**396339**
Matrix:	**Soil**	**Method:**	**EPA 8081A**	**Prep Method:**	**EPA 3546**

QC1344116 Analyte	Result	Qual	Units	RL	Prepared	Analyzed
alpha-BHC	ND		ug/Kg	5.0	02/25/26	02/26/26
beta-BHC	ND		ug/Kg	5.0	02/25/26	02/26/26
gamma-BHC	ND		ug/Kg	5.0	02/25/26	02/26/26
delta-BHC	ND		ug/Kg	5.0	02/25/26	02/26/26
Heptachlor	ND		ug/Kg	5.0	02/25/26	02/26/26
Aldrin	ND		ug/Kg	5.0	02/25/26	02/26/26
Heptachlor epoxide	ND		ug/Kg	5.0	02/25/26	02/26/26
Endosulfan I	ND		ug/Kg	5.0	02/25/26	02/26/26
Dieldrin	ND		ug/Kg	5.0	02/25/26	02/26/26
4,4'-DDE	ND		ug/Kg	5.0	02/25/26	02/26/26
Endrin	ND		ug/Kg	5.0	02/25/26	02/26/26
Endosulfan II	ND		ug/Kg	5.0	02/25/26	02/26/26
Endosulfan sulfate	ND		ug/Kg	5.0	02/25/26	02/26/26
4,4'-DDD	ND		ug/Kg	5.0	02/25/26	02/26/26
Endrin aldehyde	ND		ug/Kg	5.0	02/25/26	02/26/26
Endrin ketone	ND		ug/Kg	5.0	02/25/26	02/26/26
4,4'-DDT	ND		ug/Kg	5.0	02/25/26	02/26/26
Methoxychlor	ND		ug/Kg	9.9	02/25/26	02/26/26
Toxaphene	ND		ug/Kg	99	02/25/26	02/26/26
Chlordane (Technical)	ND		ug/Kg	50	02/25/26	02/26/26
Surrogates				**Limits**		
TCMX	80%		%REC	58-120	02/25/26	02/26/26
Decachlorobiphenyl	77%		%REC	47-120	02/25/26	02/26/26

ENTHALPY ANALYTICAL

Batch QC

Type: Lab Control Sample	**Lab ID: QC1344117**	**Batch: 396339**
Matrix: Soil	**Method: EPA 8081A**	**Prep Method: EPA 3546**

QC1344117 Analyte	Result	Spiked	Units	Recovery	Qual	Limits
alpha-BHC	47.04	50.56	ug/Kg	93%		53-132
beta-BHC	47.61	50.56	ug/Kg	94%		59-131
gamma-BHC	47.75	50.56	ug/Kg	94%		54-132
delta-BHC	47.06	50.56	ug/Kg	93%		54-134
Heptachlor	45.65	50.56	ug/Kg	90%		50-130
Aldrin	40.47	50.56	ug/Kg	80%		46-120
Heptachlor epoxide	42.17	50.56	ug/Kg	83%		52-127
Endosulfan I	44.53	50.56	ug/Kg	88%		53-132
Dieldrin	43.42	50.56	ug/Kg	86%		53-134
4,4'-DDE	45.11	50.56	ug/Kg	89%		53-140
Endrin	51.59	50.56	ug/Kg	102%		53-142
Endosulfan II	45.67	50.56	ug/Kg	90%		53-138
Endosulfan sulfate	44.90	50.56	ug/Kg	89%		50-134
4,4'-DDD	41.48	50.56	ug/Kg	82%		50-136
Endrin aldehyde	39.33	50.56	ug/Kg	78%		15-120
Endrin ketone	43.68	50.56	ug/Kg	86%		50-146
4,4'-DDT	44.33	50.56	ug/Kg	88%		46-142
Methoxychlor	49.04	50.56	ug/Kg	97%		48-156
Surrogates						
TCMX	43.67	50.56	ug/Kg	86%		58-120
Decachlorobiphenyl	41.08	50.56	ug/Kg	81%		47-120

ENTHALPY ANALYTICAL

Batch QC

Type:	**Matrix Spike**	**Lab ID:**	**QC1344118**	**Batch:**	**396339**
Matrix (Source ID):	**Soil (553784-042)**	**Method:**	**EPA 8081A**	**Prep Method:**	**EPA 3546**

QC1344118 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	DF
alpha-BHC	43.04	ND	50.05	ug/Kg	86%		52-120	1
beta-BHC	46.20	ND	50.05	ug/Kg	85%		57-126	1
gamma-BHC	43.60	ND	50.05	ug/Kg	87%		54-122	1
delta-BHC	40.55	ND	50.05	ug/Kg	81%		44-127	1
Heptachlor	42.59	ND	50.05	ug/Kg	85%		51-122	1
Aldrin	38.89	ND	50.05	ug/Kg	72%		51-120	1
Heptachlor epoxide	38.60	ND	50.05	ug/Kg	77%		50-122	1
Endosulfan I	40.72	ND	50.05	ug/Kg	81%		48-123	1
Dieldrin	39.38	ND	50.05	ug/Kg	79%		48-128	1
4,4'-DDE	50.84	13.66	50.05	ug/Kg	74%		50-139	1
Endrin	43.14	ND	50.05	ug/Kg	86%		53-132	1
Endosulfan II	40.63	ND	50.05	ug/Kg	81%		47-131	1
Endosulfan sulfate	40.83	ND	50.05	ug/Kg	82%		40-126	1
4,4'-DDD	37.63	ND	50.05	ug/Kg	70%		48-130	1
Endrin aldehyde	35.25	ND	50.05	ug/Kg	70%		26-120	1
Endrin ketone	38.93	ND	50.05	ug/Kg	78%		51-133	1
4,4'-DDT	48.57	5.768	50.05	ug/Kg	86%		40-144	1
Methoxychlor	45.89	ND	50.05	ug/Kg	92%		49-148	1
Surrogates								
TCMX	40.34		50.05	ug/Kg	81%		58-120	1
Decachlorobiphenyl	36.54		50.05	ug/Kg	73%		47-120	1

ENTHALPY ANALYTICAL

Batch QC

Type:	**Matrix Spike Duplicate**	**Lab ID:**	**QC1344119**	**Batch:**	**396339**
Matrix (Source ID):	**Soil (553784-042)**	**Method:**	**EPA 8081A**	**Prep Method:**	**EPA 3546**

QC1344119 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	RPD	RPD Lim	DF
alpha-BHC	46.68	ND	49.90	ug/Kg	94%		52-120	8	37	1
beta-BHC	50.93	ND	49.90	ug/Kg	94%		57-126	10	38	1
gamma-BHC	47.35	ND	49.90	ug/Kg	95%		54-122	9	39	1
delta-BHC	41.68	ND	49.90	ug/Kg	84%		44-127	3	54	1
Heptachlor	47.53	ND	49.90	ug/Kg	95%		51-122	11	44	1
Aldrin	43.53	ND	49.90	ug/Kg	82%		51-120	12	39	1
Heptachlor epoxide	42.80	ND	49.90	ug/Kg	86%		50-122	11	39	1
Endosulfan I	45.73	ND	49.90	ug/Kg	92%		48-123	12	47	1
Dieldrin	44.61	ND	49.90	ug/Kg	89%		48-128	13	43	1
4,4'-DDE	64.48	13.66	49.90	ug/Kg	102%		50-139	24	42	1
Endrin	48.56	ND	49.90	ug/Kg	97%		53-132	12	45	1
Endosulfan II	45.25	ND	49.90	ug/Kg	91%		47-131	11	46	1
Endosulfan sulfate	43.44	ND	49.90	ug/Kg	87%		40-126	7	52	1
4,4'-DDD	43.22	ND	49.90	ug/Kg	82%		48-130	14	46	1
Endrin aldehyde	34.86	ND	49.90	ug/Kg	70%		26-120	1	57	1
Endrin ketone	43.03	ND	49.90	ug/Kg	86%		51-133	10	43	1
4,4'-DDT	50.52	5.768	49.90	ug/Kg	90%		40-144	4	56	1
Methoxychlor	50.32	ND	49.90	ug/Kg	101%		49-148	9	53	1
Surrogates										
TCMX	42.95		49.90	ug/Kg	86%		58-120			1
Decachlorobiphenyl	42.86		49.90	ug/Kg	86%		47-120			1

ENTHALPY ANALYTICAL

Batch QC

Type:	**Blank**	**Lab ID:**	**QC1345368**	**Batch:**	**396712**
Matrix:	**Soil**	**Method:**	**EPA 8081A**	**Prep Method:**	**EPA 3546**

QC1345368 Analyte	Result	Qual	Units	RL	Prepared	Analyzed
alpha-BHC	ND		ug/Kg	5.1	02/28/26	03/01/26
beta-BHC	ND		ug/Kg	5.1	02/28/26	03/01/26
gamma-BHC	ND		ug/Kg	5.1	02/28/26	03/01/26
delta-BHC	ND		ug/Kg	5.1	02/28/26	03/01/26
Heptachlor	ND		ug/Kg	5.1	02/28/26	03/01/26
Aldrin	ND		ug/Kg	5.1	02/28/26	03/01/26
Heptachlor epoxide	ND		ug/Kg	5.1	02/28/26	03/01/26
Endosulfan I	ND		ug/Kg	5.1	02/28/26	03/01/26
Dieldrin	ND		ug/Kg	5.1	02/28/26	03/01/26
4,4'-DDE	ND		ug/Kg	5.1	02/28/26	03/01/26
Endrin	ND		ug/Kg	5.1	02/28/26	03/01/26
Endosulfan II	ND		ug/Kg	5.1	02/28/26	03/01/26
Endosulfan sulfate	ND		ug/Kg	5.1	02/28/26	03/01/26
4,4'-DDD	ND		ug/Kg	5.1	02/28/26	03/01/26
Endrin aldehyde	ND		ug/Kg	5.1	02/28/26	03/01/26
Endrin ketone	ND		ug/Kg	5.1	02/28/26	03/01/26
4,4'-DDT	ND		ug/Kg	5.1	02/28/26	03/01/26
Methoxychlor	ND		ug/Kg	10	02/28/26	03/01/26
Toxaphene	ND		ug/Kg	100	02/28/26	03/01/26
Chlordane (Technical)	ND		ug/Kg	51	02/28/26	03/01/26
Surrogates				**Limits**		
TCMX	92%		%REC	58-120	02/28/26	03/01/26
Decachlorobiphenyl	94%		%REC	47-120	02/28/26	03/01/26

ENTHALPY ANALYTICAL

Batch QC

Type: Lab Control Sample	**Lab ID: QC1345369**	**Batch: 396712**
Matrix: Soil	**Method: EPA 8081A**	**Prep Method: EPA 3546**

QC1345369 Analyte	Result	Spiked	Units	Recovery	Qual	Limits
alpha-BHC	52.64	51.02	ug/Kg	103%		53-132
beta-BHC	49.48	51.02	ug/Kg	97%		59-131
gamma-BHC	53.90	51.02	ug/Kg	106%		54-132
delta-BHC	57.06	51.02	ug/Kg	112%		54-134
Heptachlor	49.91	51.02	ug/Kg	98%		50-130
Aldrin	45.99	51.02	ug/Kg	90%		46-120
Heptachlor epoxide	49.00	51.02	ug/Kg	96%		52-127
Endosulfan I	50.04	51.02	ug/Kg	98%		53-132
Dieldrin	48.26	51.02	ug/Kg	95%		53-134
4,4'-DDE	53.33	51.02	ug/Kg	105%		53-140
Endrin	54.79	51.02	ug/Kg	107%	#	53-142
Endosulfan II	49.90	51.02	ug/Kg	98%		53-138
Endosulfan sulfate	53.35	51.02	ug/Kg	105%		50-134
4,4'-DDD	49.26	51.02	ug/Kg	97%		50-136
Endrin aldehyde	44.57	51.02	ug/Kg	87%		15-120
Endrin ketone	58.42	51.02	ug/Kg	115%		50-146
4,4'-DDT	49.72	51.02	ug/Kg	97%		46-142
Methoxychlor	52.62	51.02	ug/Kg	103%		48-156
Surrogates						
TCMX	44.63	51.02	ug/Kg	87%		58-120
Decachlorobiphenyl	43.68	51.02	ug/Kg	86%		47-120

ENTHALPY ANALYTICAL

Batch QC

Type:	**Matrix Spike**	**Lab ID:**	**QC1345375**	**Batch:**	**396712**
Matrix (Source ID):	**Soil (553880-001)**	**Method:**	**EPA 8081A**	**Prep Method:**	**EPA 3546**

QC1345375 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	DF
alpha-BHC	45.36	ND	50.00	ug/Kg	91%		52-120	1
beta-BHC	39.43	ND	50.00	ug/Kg	79%		57-126	1
gamma-BHC	45.82	ND	50.00	ug/Kg	92%		54-122	1
delta-BHC	49.54	ND	50.00	ug/Kg	99%		44-127	1
Heptachlor	43.29	ND	50.00	ug/Kg	87%		51-122	1
Aldrin	42.10	ND	50.00	ug/Kg	84%		51-120	1
Heptachlor epoxide	44.75	2.930	50.00	ug/Kg	84%		50-122	1
Endosulfan I	41.56	ND	50.00	ug/Kg	83%		48-123	1
Dieldrin	52.88	10.68	50.00	ug/Kg	84%		48-128	1
4,4'-DDE	96.83	47.97	50.00	ug/Kg	98%		50-139	1
Endrin	49.35	ND	50.00	ug/Kg	99%	#	53-132	1
Endosulfan II	43.01	ND	50.00	ug/Kg	86%		47-131	1
Endosulfan sulfate	46.23	ND	50.00	ug/Kg	92%		40-126	1
4,4'-DDD	28.18	ND	50.00	ug/Kg	56%		48-130	1
Endrin aldehyde	37.65	ND	50.00	ug/Kg	75%		26-120	1
Endrin ketone	53.52	ND	50.00	ug/Kg	107%	#	51-133	1
4,4'-DDT	65.74	16.63	50.00	ug/Kg	98%		40-144	1
Methoxychlor	46.25	ND	50.00	ug/Kg	93%		49-148	1
Surrogates								
TCMX	38.95		50.00	ug/Kg	78%		58-120	1
Decachlorobiphenyl	47.26		50.00	ug/Kg	95%		47-120	1

ENTHALPY ANALYTICAL

Batch QC

Type:	**Matrix Spike Duplicate**	**Lab ID:**	**QC1345376**	**Batch:**	**396712**
Matrix (Source ID):	**Soil (553880-001)**	**Method:**	**EPA 8081A**	**Prep Method:**	**EPA 3546**

QC1345376 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	RPD	RPD Lim	DF
alpha-BHC	48.50	ND	51.02	ug/Kg	95%		52-120	5	37	1
beta-BHC	42.64	ND	51.02	ug/Kg	84%		57-126	6	38	1
gamma-BHC	48.67	ND	51.02	ug/Kg	95%		54-122	4	39	1
delta-BHC	53.73	ND	51.02	ug/Kg	105%		44-127	6	54	1
Heptachlor	46.18	ND	51.02	ug/Kg	91%		51-122	4	44	1
Aldrin	46.10	ND	51.02	ug/Kg	90%		51-120	7	39	1
Heptachlor epoxide	47.41	2.930	51.02	ug/Kg	87%		50-122	4	39	1
Endosulfan I	46.66	ND	51.02	ug/Kg	91%		48-123	10	47	1
Dieldrin	56.23	10.68	51.02	ug/Kg	89%		48-128	4	43	1
4,4'-DDE	100.1	47.97	51.02	ug/Kg	102%		50-139	2	42	1
Endrin	51.38	ND	51.02	ug/Kg	101%	#	53-132	2	45	1
Endosulfan II	46.66	ND	51.02	ug/Kg	91%		47-131	6	46	1
Endosulfan sulfate	49.34	ND	51.02	ug/Kg	97%		40-126	4	52	1
4,4'-DDD	45.41	ND	51.02	ug/Kg	89%		48-130	45	46	1
Endrin aldehyde	41.95	ND	51.02	ug/Kg	82%		26-120	9	57	1
Endrin ketone	56.03	ND	51.02	ug/Kg	110%	#	51-133	3	43	1
4,4'-DDT	64.44	16.63	51.02	ug/Kg	94%		40-144	4	56	1
Methoxychlor	49.78	ND	51.02	ug/Kg	98%		49-148	5	53	1
Surrogates										
TCMX	39.25		51.02	ug/Kg	77%		58-120			1
Decachlorobiphenyl	48.05		51.02	ug/Kg	94%		47-120			1

ENTHALPY ANALYTICAL

Batch QC

Type: Blank	Lab ID: QC1343118	Batch: 396077
Matrix: Water		

QC1343118 Analyte	Result	Qual	Units	RL	Prepared	Analyzed
Method: EPA 8081A Prep Method: EPA 3510C						
alpha-BHC	ND		ug/L	0.05	02/22/26	02/25/26
beta-BHC	ND		ug/L	0.05	02/22/26	02/25/26
gamma-BHC	ND		ug/L	0.05	02/22/26	02/25/26
delta-BHC	ND		ug/L	0.05	02/22/26	02/25/26
Heptachlor	ND		ug/L	0.05	02/22/26	02/25/26
Aldrin	ND		ug/L	0.05	02/22/26	02/25/26
Heptachlor epoxide	ND		ug/L	0.05	02/22/26	02/25/26
Endosulfan I	ND		ug/L	0.05	02/22/26	02/25/26
Dieldrin	ND		ug/L	0.1	02/22/26	02/25/26
4,4'-DDE	ND		ug/L	0.1	02/22/26	02/25/26
Endrin	ND		ug/L	0.1	02/22/26	02/25/26
Endosulfan II	ND		ug/L	0.1	02/22/26	02/25/26
Endosulfan sulfate	ND		ug/L	0.1	02/22/26	02/25/26
4,4'-DDD	ND		ug/L	0.1	02/22/26	02/25/26
Endrin aldehyde	ND		ug/L	0.1	02/22/26	02/25/26
Endrin ketone	ND		ug/L	0.1	02/22/26	02/25/26
4,4'-DDT	ND		ug/L	0.1	02/22/26	02/25/26
Methoxychlor	ND		ug/L	0.1	02/22/26	02/25/26
Toxaphene	ND		ug/L	2.0	02/22/26	02/25/26
Chlordane (Technical)	ND		ug/L	1.0	02/22/26	02/25/26
Surrogates				**Limits**		
TCMX	61%		%REC	29-120	02/22/26	02/25/26
Decachlorobiphenyl	90%		%REC	33-132	02/22/26	02/25/26
Method: EPA 8082 Prep Method: EPA 3510C						
Aroclor-1016	ND		ug/L	0.50	02/22/26	02/25/26
Aroclor-1221	ND		ug/L	0.50	02/22/26	02/25/26
Aroclor-1232	ND		ug/L	0.50	02/22/26	02/25/26
Aroclor-1242	ND		ug/L	0.50	02/22/26	02/25/26
Aroclor-1248	ND		ug/L	0.50	02/22/26	02/25/26
Aroclor-1254	ND		ug/L	0.50	02/22/26	02/25/26
Aroclor-1260	ND		ug/L	0.50	02/22/26	02/25/26
Aroclor-1262	ND		ug/L	0.50	02/22/26	02/25/26
Aroclor-1268	ND		ug/L	0.50	02/22/26	02/25/26
Total PCBs	ND		ug/L	0.50	02/22/26	02/25/26
Surrogates				**Limits**		
Decachlorobiphenyl (PCB)	66%		%REC	28-138	02/22/26	02/25/26

ENTHALPY ANALYTICAL

Batch QC

Type:	**Lab Control Sample**	**Lab ID:**	**QC1343119**	**Batch:**	**396077**
Matrix:	**Water**	**Method:**	**EPA 8081A**	**Prep Method:**	**EPA 3510C**

QC1343119 Analyte	Result	Spiked	Units	Recovery	Qual	Limits
alpha-BHC	0.5820	0.5000	ug/L	116%		66-121
beta-BHC	0.5036	0.5000	ug/L	101%		73-120
gamma-BHC	0.5751	0.5000	ug/L	115%		68-125
delta-BHC	0.6048	0.5000	ug/L	121%		68-131
Heptachlor	0.5575	0.5000	ug/L	112%		63-120
Aldrin	0.5066	0.5000	ug/L	101%		56-120
Heptachlor epoxide	0.5066	0.5000	ug/L	101%		65-120
Endosulfan I	0.5282	0.5000	ug/L	106%		68-124
Dieldrin	0.5117	0.5000	ug/L	102%		66-124
4,4'-DDE	0.5771	0.5000	ug/L	115%		67-131
Endrin	0.5664	0.5000	ug/L	113%		68-135
Endosulfan II	0.5169	0.5000	ug/L	103%		71-130
Endosulfan sulfate	0.5706	0.5000	ug/L	114%		68-128
4,4'-DDD	0.5348	0.5000	ug/L	107%		65-130
Endrin aldehyde	0.4895	0.5000	ug/L	98%		67-124
Endrin ketone	0.5896	0.5000	ug/L	118%		69-137
4,4'-DDT	0.5526	0.5000	ug/L	111%		65-136
Methoxychlor	0.5817	0.5000	ug/L	116%		69-150
Surrogates						
TCMX	0.4030	0.5000	ug/L	81%		29-120
Decachlorobiphenyl	0.5506	0.5000	ug/L	110%		33-132

ENTHALPY ANALYTICAL

Batch QC

Type:	Lab Control Sample Duplicate	Lab ID:	QC1343120	Batch:	396077
Matrix:	Water	Method:	EPA 8081A	Prep Method:	EPA 3510C

QC1343120 Analyte	Result	Spiked	Units	Recovery	Qual	Limits	RPD	RPD Lim
alpha-BHC	0.5242	0.5000	ug/L	105%		66-121	10	20
beta-BHC	0.4595	0.5000	ug/L	92%		73-120	9	20
gamma-BHC	0.5102	0.5000	ug/L	102%		68-125	12	20
delta-BHC	0.5429	0.5000	ug/L	109%		68-131	11	20
Heptachlor	0.4883	0.5000	ug/L	98%		63-120	13	24
Aldrin	0.4468	0.5000	ug/L	89%		56-120	13	30
Heptachlor epoxide	0.4498	0.5000	ug/L	90%		65-120	12	20
Endosulfan I	0.4733	0.5000	ug/L	95%		68-124	11	20
Dieldrin	0.4657	0.5000	ug/L	93%		66-124	9	22
4,4'-DDE	0.5143	0.5000	ug/L	103%		67-131	12	21
Endrin	0.5116	0.5000	ug/L	102%		68-135	10	20
Endosulfan II	0.4701	0.5000	ug/L	94%		71-130	9	21
Endosulfan sulfate	0.5303	0.5000	ug/L	106%		68-128	7	21
4,4'-DDD	0.4800	0.5000	ug/L	96%		65-130	11	22
Endrin aldehyde	0.4516	0.5000	ug/L	90%		67-124	8	20
Endrin ketone	0.5806	0.5000	ug/L	116%		69-137	2	21
4,4'-DDT	0.5169	0.5000	ug/L	103%		65-136	7	23
Methoxychlor	0.5628	0.5000	ug/L	113%		69-150	3	23
Surrogates								
TCMX	0.3680	0.5000	ug/L	74%		29-120		
Decachlorobiphenyl	0.5513	0.5000	ug/L	110%		33-132		

Type:	Lab Control Sample	Lab ID:	QC1343121	Batch:	396077
Matrix:	Water	Method:	EPA 8082	Prep Method:	EPA 3510C

QC1343121 Analyte	Result	Spiked	Units	Recovery	Qual	Limits
Aroclor-1016	5.021	5.000	ug/L	100%		69-120
Aroclor-1260	4.668	5.000	ug/L	93%		72-124
Surrogates						
Decachlorobiphenyl (PCB)	0.3945	0.5000	ug/L	79%		28-138

Type:	Lab Control Sample Duplicate	Lab ID:	QC1343122	Batch:	396077
Matrix:	Water	Method:	EPA 8082	Prep Method:	EPA 3510C

QC1343122 Analyte	Result	Spiked	Units	Recovery	Qual	Limits	RPD	RPD Lim
Aroclor-1016	4.883	5.000	ug/L	98%		69-120	3	22
Aroclor-1260	4.546	5.000	ug/L	91%		72-124	3	25
Surrogates								
Decachlorobiphenyl (PCB)	0.3967	0.5000	ug/L	79%		28-138		

ENTHALPY ANALYTICAL

Batch QC

Type: Blank	Lab ID: QC1344120	Batch: 396340
Matrix: Soil	Method: EPA 8082	Prep Method: EPA 3546

QC1344120 Analyte	Result	Qual	Units	RL	Prepared	Analyzed
Aroclor-1016	ND		ug/Kg	50	02/25/26	02/26/26
Aroclor-1221	ND		ug/Kg	50	02/25/26	02/26/26
Aroclor-1232	ND		ug/Kg	50	02/25/26	02/26/26
Aroclor-1242	ND		ug/Kg	50	02/25/26	02/26/26
Aroclor-1248	ND		ug/Kg	50	02/25/26	02/26/26
Aroclor-1254	ND		ug/Kg	50	02/25/26	02/26/26
Aroclor-1260	ND		ug/Kg	50	02/25/26	02/26/26
Aroclor-1262	ND		ug/Kg	50	02/25/26	02/26/26
Aroclor-1268	ND		ug/Kg	50	02/25/26	02/26/26
Total PCBs	ND		ug/Kg	50	02/25/26	02/26/26
Surrogates				**Limits**		
Decachlorobiphenyl (PCB)	76%		%REC	50-127	02/25/26	02/26/26

Type: Lab Control Sample	Lab ID: QC1344121	Batch: 396340
Matrix: Soil	Method: EPA 8082	Prep Method: EPA 3546

QC1344121 Analyte	Result	Spiked	Units	Recovery	Qual	Limits
Aroclor-1016	475.5	497.5	ug/Kg	96%		66-120
Aroclor-1260	418.6	497.5	ug/Kg	84%		63-126
Surrogates						
Decachlorobiphenyl (PCB)	35.17	49.75	ug/Kg	71%		50-127

Type: Matrix Spike	Lab ID: QC1344139	Batch: 396340
Matrix (Source ID): Soil (553784-001)	Method: EPA 8082	Prep Method: EPA 3546

QC1344139 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	DF
Aroclor-1016	495.1	ND	494.1	ug/Kg	100%		60-123	0.99
Aroclor-1260	491.7	ND	494.1	ug/Kg	100%		55-136	0.99
Surrogates								
Decachlorobiphenyl (PCB)	40.50		49.41	ug/Kg	82%		50-127	0.99

Type: Matrix Spike Duplicate	Lab ID: QC1344140	Batch: 396340
Matrix (Source ID): Soil (553784-001)	Method: EPA 8082	Prep Method: EPA 3546

QC1344140 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	RPD	RPD Lim	DF
Aroclor-1016	509.1	ND	499.0	ug/Kg	102%		60-123	2	37	1
Aroclor-1260	489.3	ND	499.0	ug/Kg	98%		55-136	1	41	1
Surrogates										
Decachlorobiphenyl (PCB)	39.61		49.90	ug/Kg	79%		50-127			1

Batch QC

#	CCV drift outside limits; average CCV drift within limits per method requirements
J	Estimated value
ND	Not Detected

Laboratory Job Number 553784

Subcontracted Products

AmeriSci Los Angeles

AmeriSci Richmond
13635 GENITO ROAD
MIDLOTHIAN, VIRGINIA 23112
TEL: (804) 763-1200 • FAX: (804) 763-0493

March 4, 2026

Enthalpy Analytical
Attn: Patty Mata
931 West Barkley Ave
Orange, CA 92868

RE: Enthalpy Analytical
Job Number 126022174
P.O. #099249
553784

Dear Patty Mata:

Enclosed are the results of Asbestos Analysis - Bulk Qualitative Protocol of the following Enthalpy Analytical samples, received at AmeriSci on Wednesday, February 25, 2026, for a 5 day turnaround:

CG-43-0.5, CG-43-2.5, CG-38-0.5, CG-38-2.5, CG-38-0.5-DUP, CG-38-2.5-DUP, CG-40-0.5, CG-40-2.5, CG-41-0.5, CG-41-2.5, CG-42-0.5, CG-42-2.5

The 12 samples, placed in glass jar, were shipped to AmeriSci via Fed Ex 717839739830. Enthalpy Analytical requested Bulk-Qualitative analysis of these samples.

The samples were prepared and analyzed by using a Standard Operating Procedure developed by AmeriSci, Inc.. After preparation, using non-quantitative matrix reduction if necessary, the presence or absence of asbestos is determined by PLM and/or TEM as indicated on the attached summary table. Quantification after the fact is not possible without a new preparation. This report relates ONLY to the analysis expressed as "asbestos present" or "no asbestos visible". This report must not be used to claim product endorsement or approval by AmeriSci, NVLAP, ELAP or any other associated AmeriSci certifying agency. The National Institute of Standards and Technology accreditation requirements, mandate that this report must not be reproduced, except in full without the approval of the laboratory.

AmeriSci appreciates this opportunity to serve your organization. Please contact us for any further assistance or with any questions.

Sincerely,



Glenn F. Massey

QA Manager | Authorized Signatory

AmeriSci Richmond
13635 GENITO ROAD
MIDLOTHIAN, VIRGINIA 23112
TEL: (804) 763-1200 • FAX: (804) 763-0493

PLM Bulk Asbestos Report

Enthalpy Analytical
Attn: Patty Mata
931 West Barkley Ave

Orange, CA 92868

Date Received 2/25/2026
Date Examined 03/02/26

AmeriSci Job # 126022174
P.O. # 099249

RE: 553784

Client No. / HGA	Lab No.	Asbestos Present	Total % Asbestos	Notes
CG-43-0.5	126022174-01	***No***	NVA by C. David Mintz on 03/02/26	*1*

Location:
Analyst Description: Dark, Homogeneous, Non-Fibrous, Soil
Asbestos Types:
Other Material: Non-fibrous Present

CG-43-2.5	126022174-02	***No***	NVA by C. David Mintz on 03/02/26	*1*

Location:
Analyst Description: Dark, Homogeneous, Non-Fibrous, Soil
Asbestos Types:
Other Material: Non-fibrous Present

CG-38-0.5	126022174-03	***No***	NVA by C. David Mintz on 03/02/26	*1*

Location:
Analyst Description: Dark, Homogeneous, Non-Fibrous, Soil
Asbestos Types:
Other Material: Non-fibrous Present

CG-38-2.5	126022174-04	***No***	NVA by C. David Mintz on 03/02/26	*1*

Location:
Analyst Description: Dark, Homogeneous, Non-Fibrous, Soil
Asbestos Types:
Other Material: Non-fibrous Present

CG-38-0.5-DUP	126022174-05	***No***	NVA by C. David Mintz on 03/02/26	*1*

Location:
Analyst Description: Dark, Homogeneous, Non-Fibrous, Soil
Asbestos Types:
Other Material: Non-fibrous Present

CG-38-2.5-DUP	126022174-06	***No***	NVA by C. David Mintz on 03/02/26	*1*

Location:
Analyst Description: Dark, Homogeneous, Non-Fibrous, Soil
Asbestos Types:
Other Material: Non-fibrous Present

See Reporting notes on last page

PLM Bulk Asbestos Report

553784

Client No. / HGA	Lab No.	Asbestos Present	Total % Asbestos	Notes
CG-40-0.5	126022174-07	***No***	NVA by C. David Mintz on 03/02/26	*1*
Location:				
Analyst Description: Dark, Homogeneous, Non-Fibrous, Soil				
Asbestos Types:				
Other Material: Non-fibrous Present				
CG-40-2.5	126022174-08	***No***	NVA by C. David Mintz on 03/02/26	*1*
Location:				
Analyst Description: Dark, Homogeneous, Non-Fibrous, Soil				
Asbestos Types:				
Other Material: Non-fibrous Present				
CG-41-0.5	126022174-09	***No***	NVA by C. David Mintz on 03/02/26	*1*
Location:				
Analyst Description: Dark, Homogeneous, Non-Fibrous, Soil				
Asbestos Types:				
Other Material: Non-fibrous Present				
CG-41-2.5	126022174-10	***No***	NVA by C. David Mintz on 03/02/26	*1*
Location:				
Analyst Description: Dark, Homogeneous, Non-Fibrous, Soil				
Asbestos Types:				
Other Material: Cellulose Present, Non-fibrous Present				
CG-42-0.5	126022174-11	***No***	NVA by C. David Mintz on 03/02/26	*1*
Location:				
Analyst Description: Dark, Homogeneous, Non-Fibrous, Soil				
Asbestos Types:				
Other Material: Non-fibrous Present				
CG-42-2.5	126022174-12	***No***	NVA by C. David Mintz on 03/02/26	*1*
Location:				
Analyst Description: Dark, Homogeneous, Non-Fibrous, Soil				
Asbestos Types:				
Other Material: Cellulose Present, Non-fibrous Present				



See Reporting notes on last page

PLM Bulk Asbestos Report

553784

Reporting Notes:

(1) Sample homogenized by grinding to a powder prior to analysis.

Analyzed by: C. David Mintz  Reviewed by: Glenn F. Massey 

Date: 3/2/2026

*NAD = no asbestos detected, Detection Limit <1%, Reporting Limits: CVES = 1%, 400 Pt Ct = 0.25%, 1000 Pt Ct = 0.1%; "Present" or NVA = "No Visible Asbestos" are observations made during a qualitative analysis (Not covered by NVLAP or NY ELAP accreditations); NA = not analyzed; NA/PS = not analyzed / positive stop; PLM Bulk Asbestos Analysis using Olympus, Model BH-2 microscope, Serial #210972, by EPA 600/R-93/116 per 40 CFR 763 (NVLAP Lab Code 101904-0) and ELAP PLM Analysis Protocol 198.1 for New York friable samples which includes quantitation of any vermiculite observed (198.6 for NOB samples) or EPA 400 pt ct by EPA 600/M4-82-020 (NYSDOH ELAP Lab # 10984); CA ELAP Lab # 2508; Note: PLM is not consistently reliable in detecting asbestos in floor coverings and similar NOB materials. NAD or Trace results by PLM are inconclusive, TEM is currently the only method that can be used to determine if this material can be considered or treated as non-asbestos-containing in New York State (also see EPA Advisory for floor tile, FR 59, 146, 38970, 8/1/94). NIST Accreditation requirements mandate that this report must not be reproduced except in full without the approval of the laboratory. This PLM report relates ONLY to the items tested.

ENTHALPY ANALYTICAL

931 West Barkley Ave
Orange, CA 92868
(714) 771-6900

1260222174

Subcontract Laboratory:
AmeriSci Los Angeles
24416 S. Main Street
Suite 308
Carson, CA 90745
ATTN: Sample Control
PO #: Required, to be sent via email

Enthalpy Order: EO-553784
PM: Patty Mata
Email: patty.mata@enthalpy.com
CC: incomingreports@enthalpy.com
Phone: (714) 771-6900

Results Due: Standard TAT
Report Level: II
Report To: RL
EDDs:

Notes:

Sample ID	Collected	Lab ID	# Cont.	Matrix	Analysis Requested	Comment
CG-43-0.5	19-FEB-2026 00:00	553784-033	1	Soil	Asbestos by PLM	PLM Qualitative
CG-43-2.5	19-FEB-2026 00:00	553784-034	1	Soil	Asbestos by PLM	PLM Qualitative
EB-01-260219	19-FEB-2026 15:30	553784-035	1	Water	Asbestos	Non-Potable water TEM — Already sent 2/23/26
CG-38-0.5	19-FEB-2026 00:00	553784-036	1	Soil	Asbestos by PLM	PLM Qualitative
CG-38-2.5	19-FEB-2026 00:00	553784-037	1	Soil	Asbestos by PLM	PLM Qualitative
CG-38-0.5-DUP	19-FEB-2026 00:00	553784-038	1	Soil	Asbestos by PLM	PLM Qualitative
CG-38-2.5-DUP	19-FEB-2026 00:00	553784-039	1	Soil	Asbestos by PLM	PLM Qualitative
CG-40-0.5	19-FEB-2026 00:00	553784-040	1	Soil	Asbestos by PLM	PLM Qualitative
CG-40-2.5	19-FEB-2026 00:00	553784-041	1	Soil	Asbestos by PLM	PLM Qualitative
CG-41-0.5	19-FEB-2026 00:00	553784-042	1	Soil	Asbestos by PLM	PLM Qualitative
CG-41-2.5	19-FEB-2026 00:00	553784-043	1	Soil	Asbestos by PLM	PLM Qualitative
CG-42-0.5	19-FEB-2026 00:00	553784-044	1	Soil	Asbestos by PLM	PLM Qualitative
CG-42-2.5	19-FEB-2026 00:00	553784-045	1	Soil	Asbestos by PLM	PLM Qualitative

Notes:	Relinquished By:	Received By:
	[signature]	M. RIVERO
	Date: 2.24.26 1313	Date: 2/24/26 0 1315
	M. RIVERO	
	Date: 2/24/26 0 1315	Date:
	Date:	Date:

Received
FEB 25 2026
KHM

AmeriSci Richmond
13635 GENITO ROAD
MIDLOTHIAN, VIRGINIA 23112
TEL: (804) 763-1200 • FAX: (804) 763-0493

March 4, 2026

Enthalpy Analytical
Attn: Patty Mata
931 West Barkley Ave
Orange, CA 92868

RE: Enthalpy Analytical
Job Number 126022213
P.O. #099249
553784

Dear Patty Mata:

Enclosed are the results for TEM asbestos analysis of the following Enthalpy Analytical samples received at AmeriSci on Thursday, February 26, 2026, for a 5 day turnaround:

EB-01-260219

The 1 samples were filtered and prepared according to Water analysis under the EPA-600/4-83-043 "Analytical Method for Determination of Asbestos Fibers in Water" (1983). Samples with high organic content may be prepared following EPA-600/4-80-005 if necessary and are so noted on the TEM count sheets. AmeriSci, Inc. uses the "Grid Square" method of counting and the concentration is calculated in millions of fibers per liter (MFL).

Table I represents a summary of all pertinent information used for the calculations. Included are the size of each structure counted, concentration, structure concentration greater than 10 microns in length, type of asbestiform material detected and the analytical sensitivity, which represents the concentration by the detection of one fiber in the TEM fiber count. Copies of the Fiber Count Sheets, show the raw data for examination. These data sheets contain information for fiber length/width, fiber type, structure morphology and pertinent information on EDS, SAED and photography.

This report relates ONLY to the sample analysis expressed as millions of fibers per liter (MFL). AmeriSci assumes no responsibility for customer supplied data such as “sample location” or “the condition of the water sample before arriving at AmeriSci”. This report must not be used to claim product endorsement by AmeriSci, NVLAP, ELAP or any agency of the U. S. Government. The National Institute of Standards and Technology accreditation requirements, mandate that this report must not be reproduced, except in full without the approval of the laboratory.

AmeriSci appreciates this opportunity to serve your organization. Please contact us for any further assistance or with any questions.

Sincerely,



Cory M. Parnell

Laboratory Director | Authorized Signatory

AmeriSci Job #: **126022213**
Client Name: Enthalpy Analytical

Table I
Summary of Transmission Electron Microscopy (TEM) Results for Asbestos (Water)


553784

AmeriSci Sample #	Client Sample No./Location	Liquid Filtered (liters)	Temp (Celcius)	Structures Detected* (total)	Structures Detected* (>10 µm)	Analytical Sensitivity (MF/L)	Asbestos Conc (total) (MF/L)	Asbestos Conc (>10 µm) (MF/L)	Asbestos Type
01	EB-01-260219	0.01	17.9	NSD	NSD	0.22	<0.22	<0.22	----

* NAD/NSD = no asbestos detected, NA = not analyzed, MF/L = million fibers per liter; Drinking Water accreditations do not cover waste water analysis. NOTE: Drinking water analysis by EPA-600/4-83-043 (100.1). Fiber criteria (>=0.5 microns, for 100.1; >10 microns for 100.2; 5:1 aspect ratio for both), organic rich waste water prepped by EPA-600/4-80-005. Analytical sensitivity calculated as though 1 fiber had been detected on the TEM GRID area analyzed. Sample temperatures reported above were measured upon receipt. Water samples are refrigerated upon receipt and filtered within four hours.

Reviewed By: _____ Analyzed By: Cory M. Parnell _____ Date: 3/4/2026

TEM Asbestos (Water) Count Sheet



Client Name:	Enthalpy Analytical		
Job #:	126022213	Volume (liters):	0.01
Lab Sample #:	01	Filter Type / Filter Area:	MCE 214 mm2
Client Sample #:	EB-01-260219	Grid Opening Size:	0.00967
Received:	2/26/2026 12:00:00	Area Examined:	0.09670 mm2
Date Analyzed:	3/4/2026	Magnification:	20,000
	Temp: 17.9	Accelerating Voltage:	100 KeV

Analysis Performed by: Cory M. Parnell

Location	Grid Opening	Fiber	Length µM	Width µM	Fiber Type	Morphology	EDS	Orient.	SAED	Photo
D4-J2	1	NSD							☐	
D4-J4	2	NSD							☐	
D4-J6	3	NSD							☐	
D4-J8	4	NSD							☐	
D4-J10	5	NSD							☐	
D3-C2	6	NSD							☐	
D3-C4	7	NSD							☐	
D3-C6	8	NSD							☐	
D3-C8	9	NSD							☐	
D3-C10	10	NSD							☐	

NSD: No Asbestos Structures Detected

Scope #: Front 4: Jeol JEM-100CX II, Serial No.156147-247

Comments

		Concentration (million fibers/liter)	Grid Evaluation
Total Grid Openings:	10		☑ Grid Openings Covered > 50%
Chrysotile Asbestos Structures:	0	<0.221	☑ Intact Grid Opening > 50%
Amphibole Asbestos Structures:	0	<0.221	☑ Undissolved Filter < 10%
Asbestos Structures >10 microns:	0	<0.221	☑ Folded Replica < 50%
Total Asbestos Structures:	0	<0.221	☑ Filter Loading < 25%
Analytical Sensitivity:		0.221	☑ Particulate Even

Subject: Re: Order Confirmation - 126022213 - NEED PO#
From: Jocelyn Nguyen <JocelynNguyen@enthalpy.com>
Date: 2/26/2026, 1:37 PM
To: "varesults@amerisci.com" <varesults@amerisci.com>
CC: Patricia Mata <patty.mata@enthalpy.com>

Hello,
Please use PO-099249 for this work order.

126-02-2213

Thank you,
Jocelyn Nguyen
Project Manager Assistant
Enthalpy Analytical
931 W Barkley Ave. | Orange, CA 92868
Office: +1-714-771-6900 X 10315
JocelynNguyen@enthalpy.com | enthalpy.com
Terms and Conditions

The information contained in this e-mail and any attachments from Montrose Environmental Group, Inc. may contain confidential and/or proprietary information, and is intended only for the named recipient to whom it was originally addressed. If you are not the intended recipient, any disclosure, distribution, or copying of this e-mail or its attachments is strictly prohibited. If you have received this e-mail in error, please notify the sender immediately by return e-mail and permanently delete the e-mail and any attachments.

CONFIDENTIALITY NOTICE: The contents of this email message and any attachments are intended solely for the addressee(s) and may contain confidential, proprietary and/or privileged information and may be legally protected from disclosure. If you are not the intended recipient of this message or their agent, or if this message has been addressed to you in error, please immediately alert the sender by reply email and then delete this message and any attachments and the reply from your system. If you are not the intended recipient, you are hereby notified that any disclosure, use, dissemination, copying, or storage of this message or its attachments is strictly prohibited.

ENTHALPY ANALYTICAL

931 West Barkley Ave
Orange, CA 92868
(714) 771-6900

126022213

Subcontract Laboratory:
AmeriSci Los Angeles
24416 S. Main Street
Suite 308
Carson, CA 90745
ATTN: Sample Control
PO #: Required, to be sent via email

Enthalpy Order: EO-553784
PM: Patty Mata
Email: patty.mata@enthalpy.com
CC: incomingreports@enthalpy.com
Phone: (714) 771-6900

Results Due: Standard TAT
Report Level: II
Report To: RL
EDDs:

Notes:

Sample ID	Collected	Lab ID	# Cont.	Matrix	Analysis Requested	Comment
CG-43-0.5	19-FEB-2026 00:00	553784-033	1	Soil	Asbestos by PLM	PLM Qualitative
CG-43-2.5	19-FEB-2026 00:00	553784-034	1	Soil	Asbestos by PLM	PLM Qualitative
EB-01-260219	19-FEB-2026 15:30	553784-035	1	Water	Asbestos	Non-Potable water TEM WATER ONLY
CG-38-0.5	19-FEB-2026 00:00	553784-036	1	Soil	Asbestos by PLM	PLM Qualitative
CG-38-2.5	19-FEB-2026 00:00	553784-037	1	Soil	Asbestos by PLM	PLM Qualitative
CG-38-0.5-DUP	19-FEB-2026 00:00	553784-038	1	Soil	Asbestos by PLM	PLM Qualitative
CG-38-2.5-DUP	19-FEB-2026 00:00	553784-039	1	Soil	Asbestos by PLM	PLM Qualitative
CG-40-0.5	19-FEB-2026 00:00	553784-040	1	Soil	Asbestos by PLM	PLM Qualitative
CG-40-2.5	19-FEB-2026 00:00	553784-041	1	Soil	Asbestos by PLM	PLM Qualitative
CG-41-0.5	19-FEB-2026 00:00	553784-042	1	Soil	Asbestos by PLM	PLM Qualitative
CG-41-2.5	19-FEB-2026 00:00	553784-043	1	Soil	Asbestos by PLM	PLM Qualitative
CG-42-0.5	19-FEB-2026 00:00	553784-044	1	Soil	Asbestos by PLM	PLM Qualitative
CG-42-2.5	19-FEB-2026 00:00	553784-045	1	Soil	Asbestos by PLM	PLM Qualitative

Notes:	Relinquished By:	Received By:
	[signature]	M. RIVERO
	Date: 2-23-26 1212	Date: 2/23/26 1215
	M. RIVERO	
	Date: 2/23/26 @ 1215	Date:
	Date:	Date:

Received
FEB 26 2026
RHM

Enthalpy Analytical
931 West Barkley Ave
Orange, CA 92868
(714) 771-6900

enthalpy.com

Lab Job Number	:	553922
Report Level	:	II
Report Date	:	03/18/2026
Revision	:	**2 (See narrative)**

Analytical Report *prepared for:*

Vanya Keyes
Terraphase Engineering
18401 Von Karman Ave, Suite #410
Irvine, CA 92612

Project: CENTENNIAL HS - Centennial High School, 2606 N Central Ave., Compton, CA 90222

Authorized for release by:



Patty Mata, Project Manager
patty.mata@enthalpy.com

This data package has been reviewed for technical correctness and completeness. Release of this data has been authorized by the Laboratory Manager or the Manager's designee, as verified by the above signature which applies to this PDF file as well as any associated electronic data deliverable files. The results contained in this report meet all requirements of NELAP and pertain only to those samples which were submitted for analysis. This report may be reproduced only in its entirety.

CA ELAP# 1338, CA ELAP #1338-S1, NELAP# 4038, SCAQMD LAP# 18LA0518, LACSD ID# 10105, ORELAP# 4197

ENTHALPY ANALYTICAL

Sample Summary

Vanya Keyes
Terraphase Engineering
18401 Von Karman Ave, Suite #410
Irvine, CA 92612

Lab Job #: 553922
Project No: CENTENNIAL HS
Location: Centennial High School, 2606 N Central Ave., Compton, CA 90222
Date Received: 02/20/26

Sample ID	Lab ID	Collected	Matrix
AOC5-SB-01-0.5	553922-001	02/20/26 10:30	Soil
AOC5-SB-01-2.5	553922-002	02/20/26 10:35	Soil
AOC5-SB-01-5.0	553922-003	02/20/26 10:40	Soil
AOC5-SB-02-0.5	553922-004	02/20/26 11:50	Soil
AOC5-SB-02-2.5	553922-005	02/20/26 11:57	Soil
AOC5-SB-02-5.0	553922-006	02/20/26 12:04	Soil
DUP-02-0.5-260220	553922-007	02/20/26 00:00	Soil
DUP-02-2.5-260220	553922-008	02/20/26 00:00	Soil
DUP-02-5.0-260220	553922-009	02/20/26 00:00	Soil
AOC5-SB-03-0.5	553922-010	02/20/26 10:48	Soil
AOC5-SB-03-2.5	553922-011	02/20/26 10:51	Soil
AOC5-SB-03-5.0	553922-012	02/20/26 11:00	Soil
AOC5-SB-05-0.5	553922-013	02/20/26 13:57	Soil
AOC5-SB-05-2.5	553922-014	02/20/26 14:02	Soil
DUP-03-0.5-260220	553922-015	02/20/26 00:00	Soil
DUP-03-2.5-260220	553922-016	02/20/26 00:00	Soil
AOC5-SB-06-0.5	553922-017	02/20/26 14:12	Soil
AOC5-SB-06-2.5	553922-018	02/20/26 14:20	Soil
AOC4-SB-46-0.5	553922-019	02/20/26 07:33	Soil
AOC4-SB-47-0.5	553922-020	02/20/26 07:41	Soil
AOC4-SB-48-0.5	553922-021	02/20/26 07:52	Soil
AOC4-SB-46-2.5	553922-022	02/20/26 07:38	Soil
AOC4-SB-47-2.5	553922-023	02/20/26 07:46	Soil
AOC4-SB-48-2.5	553922-024	02/20/26 07:59	Soil
AOC4-SB-52-0.5	553922-025	02/20/26 09:15	Soil
AOC4-SB-53-0.5	553922-026	02/20/26 09:28	Soil

ENTHALPY ANALYTICAL

Sample Summary

Vanya Keyes Terraphase Engineering 18401 Von Karman Ave, Suite #410 Irvine, CA 92612	Lab Job #: Project No: Location: Date Received:	553922 CENTENNIAL HS Centennial High School, 2606 N Central Ave., Compton, CA 90222 02/20/26

Sample ID	Lab ID	Collected	Matrix
AOC4-SB-54-0.5	553922-027	02/20/26 09:38	Soil
AOC4-SB-49-0.5	553922-028	02/20/26 08:00	Soil
AOC4-SB-50-0.5	553922-029	02/20/26 08:38	Soil
AOC4-SB-51-0.5	553922-030	02/20/26 09:00	Soil
DUP-01-0.5-260220	553922-031	02/20/26 00:00	Soil
AOC4-SB-49-2.5	553922-032	02/20/26 08:03	Soil
AOC4-SB-50-2.5	553922-033	02/20/26 08:43	Soil
AOC4-SB-51-2.5	553922-034	02/20/26 09:03	Soil
DUP-01-2.5-260220	553922-035	02/20/26 00:00	Soil
AOC4-SB-52-2.5	553922-036	02/20/26 09:20	Soil
AOC4-SB-53-2.5	553922-037	02/20/26 09:33	Soil
AOC4-SB-54-2.5	553922-038	02/20/26 09:42	Soil
EB-01-260220	553922-039	02/20/26 15:30	Water
TB-01-260220	553922-040	02/20/26 00:00	Water
CG-44-0.5	553922-041	02/20/26 00:00	Soil
CG-44-2.5	553922-042	02/20/26 00:00	Soil
CG-45-0.5	553922-043	02/20/26 00:00	Soil
CG-45-2.5	553922-044	02/20/26 00:00	Soil
CG-45-0.5-DUP	553922-045	02/20/26 00:00	Soil
CG-45-2.5-DUP	553922-046	02/20/26 00:00	Soil
CG-46-0.5-	553922-047	02/20/26 00:00	Soil
CG-46-2.5	553922-048	02/20/26 00:00	Soil
CG-47-0.5	553922-049	02/20/26 00:00	Soil
CG-47-2.5	553922-050	02/20/26 00:00	Soil

Case Narrative

Terraphase Engineering 18401 Von Karman Ave, Suite #410 Irvine, CA 92612 Vanya Keyes	Lab Job Number: 553922 Project No: CENTENNIAL HS Location: Centennial High School, 2606 N Central Ave., Compton, CA 90222 Date Received: 02/20/26

- This data package contains sample and QC results for seventeen soil samples, six three-point soil composites, and one water sample, requested for the above referenced project on 02/20/26. The samples were received in good condition. No analysis could be performed for sample TB-01-260220 due to receipt of Temperature Blank vials instead of Trip Blank vials.
- Revised report on 3/18/26 to include Dioxins results. This report had been revised on 3/16/26 to include an additional total Lead result as requested for sample AOC4-SB-46-2.5.
- EPA 6010B, EPA 6020, EPA 7471A, EPA 8015M, EPA 8081A, and EPA 8082 analyses were performed at 931 West Barkley Ave, Orange, CA, 92868.
- EPA 8015B and EPA 8260B analyses were performed at 2532 E Cerritos Ave., Anaheim, CA, 92806.

TPH-Purgeables and/or BTXE by GC (EPA 8015B) Water:
No analytical problems were encountered.

TPH-Purgeables and/or BTXE by GC (EPA 8015B) Soil:
No analytical problems were encountered.

TPH-Extractables by GC (EPA 8015M):

- The lab required one additional 1L amber glass bottle for sample EB-01-260220. The TPH-D/O test could not be performed for this sample due to need for additional 1L amber glass bottle of sample volume.
- Lab numbers 553922-001 and 553922-007 were diluted due to the dark color of the sample extracts. Extract color and/or viscosity are used as indicators of possible matrix interference. Elevated reporting limits were due to the necessary dilutions.
- No other analytical problems were encountered.

Volatile Organics by GC/MS (EPA 8260B) Water:
No analytical problems were encountered.

Volatile Organics by GC/MS (EPA 8260B) Soil:
No analytical problems were encountered.

Pesticides (EPA 8081A) Water:
No analytical problems were encountered.

Pesticides (EPA 8081A) Soil:

- Lab numbers 553922-041, 553922-043, 553922-045, and 553922-047 were diluted due to the color of the sample extracts. Extract color and/or viscosity are used as indicators of possible matrix interference. Elevated reporting limits were due to the necessary dilutions.
- No other analytical problems were encountered.

PCBs (EPA 8082) Water:
No analytical problems were encountered.

PCBs (EPA 8082) Soil:

- Lab numbers 553922-004, 553922-010, 553922-013, 553922-015, 553922-017, 553922-019, 553922-020, 553922-021, 553922-025, 553922-026, 553922-027, 553922-028, 553922-029, 553922-030, and 553922-031 were treated with sulfuric acid to reduce analytical interferences or due to the presence of color.
- No other analytical problems were encountered.

Metals (EPA 6010B) Water:

No analytical problems were encountered.

Metals (EPA 6010B, EPA 6020, and EPA 7471A) Soil:

- Low recoveries were observed for antimony in the MS/MSD of AOC5-SB-01-0.5 (lab # 553922-001); the LCS was within limits, and the associated RPD was within limits. High recovery was observed for barium in the MSD of AOC5-SB-01-0.5 (lab # 553922-001); the LCS was within limits, and the associated RPD was within limits.
- No other analytical problems were encountered.

100.1 Asbestos (EPA 100.1 Asbestos):

AmeriSci Los Angeles in Carson, CA performed the analysis (see sublab report section for certifications). Please see the AmeriSci Los Angeles case narrative.

Dioxins & Furans (EPA 8290):

Enthalpy - El Dorado Hills in El Dorado Hills, CA performed the analysis (see sublab report section for certifications). Please see the Enthalpy - El Dorado Hills case narrative.

Asbestos by PLM (EPA 600/R-93-116):

AmeriSci Los Angeles in Carson, CA performed the analysis (see sublab report section for certifications). Please see the AmeriSci Los Angeles case narrative.

ENTHALPY ANALYTICAL

Detection Summary

Vanya Keyes
Terraphase Engineering
18401 Von Karman Ave, Suite #410
Irvine, CA 92612

Lab Job #: 553922
Project No: CENTENNIAL HS
Location: Centennial High School, 2606 N Central Ave., Compton, CA 90222
Date Received: 02/20/26

Sample ID: AOC5-SB-01-0.5 **Lab ID: 553922-001** **Collected: 02/20/26 10:30**
Matrix: Soil

553922-001 Analyte	Result	Qual	Units	RL
Method: EPA 6020 Prep Method: EPA 3050B				
Arsenic	**3.1**		mg/Kg	0.99
Barium	**110**		mg/Kg	0.99
Chromium	**24**		mg/Kg	2.0
Cobalt	**8.5**		mg/Kg	0.99
Copper	**30**		mg/Kg	2.0
Lead	**37**		mg/Kg	0.99
Nickel	**19**		mg/Kg	0.99
Vanadium	**41**		mg/Kg	2.0
Zinc	**120**		mg/Kg	9.9
Method: EPA 8015M Prep Method: EPA 3580M				
DRO C10-C28	**120**		mg/Kg	50
ORO C28-C44	**240**		mg/Kg	100

Sample ID: AOC5-SB-02-0.5 **Lab ID: 553922-004** **Collected: 02/20/26 11:50**
Matrix: Soil

553922-004 Analyte	Result	Qual	Units	RL
Method: EPA 6010B Prep Method: EPA 3050B				
Lead	**3.9**		mg/Kg	0.97

Results for any subcontracted analyses are not included in this summary. Data qualifiers and additional information necessary for the interpretation of the test results are contained in the PDF file and may not be included in this summary.

ENTHALPY ANALYTICAL

Detection Summary

Sample ID: DUP-02-0.5-260220 **Lab ID: 553922-007** **Collected: 02/20/26**
Matrix: Soil

553922-007 Analyte	Result	Qual	Units	RL
Method: EPA 6020 Prep Method: EPA 3050B				
Arsenic	**3.4**		mg/Kg	0.98
Barium	**130**		mg/Kg	0.98
Chromium	**20**		mg/Kg	2.0
Cobalt	**8.6**		mg/Kg	0.98
Copper	**35**		mg/Kg	2.0
Lead	**33**		mg/Kg	0.98
Nickel	**16**		mg/Kg	0.98
Vanadium	**44**		mg/Kg	2.0
Zinc	**100**		mg/Kg	9.8
Method: EPA 8015M Prep Method: EPA 3580M				
DRO C10-C28	**200**		mg/Kg	50
ORO C28-C44	**350**		mg/Kg	99

Sample ID: AOC5-SB-03-0.5 **Lab ID: 553922-010** **Collected: 02/20/26 10:48**
Matrix: Soil

553922-010 Analyte	Result	Qual	Units	RL
Method: EPA 6010B Prep Method: EPA 3050B				
Lead	**6.8**		mg/Kg	1.0

Sample ID: AOC5-SB-05-0.5 **Lab ID: 553922-013** **Collected: 02/20/26 13:57**
Matrix: Soil

553922-013 Analyte	Result	Qual	Units	RL
Method: EPA 6010B Prep Method: EPA 3050B				
Lead	**21**		mg/Kg	0.95

Sample ID: DUP-03-0.5-260220 **Lab ID: 553922-015** **Collected: 02/20/26**
Matrix: Soil

553922-015 Analyte	Result	Qual	Units	RL
Method: EPA 6010B Prep Method: EPA 3050B				
Lead	**39**		mg/Kg	0.95

Results for any subcontracted analyses are not included in this summary. Data qualifiers and additional information necessary for the interpretation of the test results are contained in the PDF file and may not be included in this summary.

ENTHALPY ANALYTICAL

Detection Summary

Sample ID: AOC5-SB-06-0.5 **Lab ID: 553922-017** **Collected: 02/20/26 14:12**
Matrix: Soil

553922-017 Analyte	Result	Qual	Units	RL
Method: EPA 6010B Prep Method: EPA 3050B				
Lead	**48**		mg/Kg	0.96

Sample ID: AOC4-SB-46-0.5 **Lab ID: 553922-019** **Collected: 02/20/26 07:33**
Matrix: Soil

553922-019 Analyte	Result	Qual	Units	RL
Method: EPA 6010B Prep Method: EPA 3050B				
Lead	**81**		mg/Kg	0.99

Sample ID: AOC4-SB-47-0.5 **Lab ID: 553922-020** **Collected: 02/20/26 07:41**
Matrix: Soil

553922-020 Analyte	Result	Qual	Units	RL
Method: EPA 6010B Prep Method: EPA 3050B				
Lead	**32**		mg/Kg	1.0

Sample ID: AOC4-SB-48-0.5 **Lab ID: 553922-021** **Collected: 02/20/26 07:52**
Matrix: Soil

553922-021 Analyte	Result	Qual	Units	RL
Method: EPA 6010B Prep Method: EPA 3050B				
Lead	**33**		mg/Kg	0.98

Sample ID: AOC4-SB-46-2.5 **Lab ID: 553922-022** **Collected: 02/20/26 07:38**
Matrix: Soil

553922-022 Analyte	Result	Qual	Units	RL
Method: EPA 6010B Prep Method: EPA 3050B				
Lead	**5.1**		mg/Kg	0.99

Sample ID: AOC4-SB-52-0.5 **Lab ID: 553922-025** **Collected: 02/20/26 09:15**
Matrix: Soil

553922-025 Analyte	Result	Qual	Units	RL
Method: EPA 6010B Prep Method: EPA 3050B				
Lead	**23**		mg/Kg	0.96

Results for any subcontracted analyses are not included in this summary. Data qualifiers and additional information necessary for the interpretation of the test results are contained in the PDF file and may not be included in this summary.

ENTHALPY ANALYTICAL

Detection Summary

Sample ID: AOC4-SB-53-0.5 **Lab ID: 553922-026** **Collected: 02/20/26 09:28**
Matrix: Soil

553922-026 Analyte	Result	Qual	Units	RL
Method: EPA 6010B Prep Method: EPA 3050B				
Lead	**70**		mg/Kg	1.0

Sample ID: AOC4-SB-54-0.5 **Lab ID: 553922-027** **Collected: 02/20/26 09:38**
Matrix: Soil

553922-027 Analyte	Result	Qual	Units	RL
Method: EPA 6010B Prep Method: EPA 3050B				
Lead	**30**		mg/Kg	0.98

Sample ID: AOC4-SB-49-0.5 **Lab ID: 553922-028** **Collected: 02/20/26 08:00**
Matrix: Soil

553922-028 Analyte	Result	Qual	Units	RL
Method: EPA 6010B Prep Method: EPA 3050B				
Lead	**11**		mg/Kg	0.99

Sample ID: AOC4-SB-50-0.5 **Lab ID: 553922-029** **Collected: 02/20/26 08:38**
Matrix: Soil

553922-029 Analyte	Result	Qual	Units	RL
Method: EPA 6010B Prep Method: EPA 3050B				
Lead	**36**		mg/Kg	0.97

Sample ID: AOC4-SB-51-0.5 **Lab ID: 553922-030** **Collected: 02/20/26 09:00**
Matrix: Soil

553922-030 Analyte	Result	Qual	Units	RL
Method: EPA 6010B Prep Method: EPA 3050B				
Lead	**23**		mg/Kg	1.0

Sample ID: DUP-01-0.5-260220 **Lab ID: 553922-031** **Collected: 02/20/26**
Matrix: Soil

553922-031 Analyte	Result	Qual	Units	RL
Method: EPA 6010B Prep Method: EPA 3050B				
Lead	**22**		mg/Kg	1.0

Results for any subcontracted analyses are not included in this summary. Data qualifiers and additional information necessary for the interpretation of the test results are contained in the PDF file and may not be included in this summary.

ENTHALPY ANALYTICAL

Detection Summary

Sample ID: EB-01-260220	Lab ID: 553922-039	Collected: 02/20/26 15:30

No Detections

Sample ID: CG-44-0.5	Lab ID: 553922-041	Collected: 02/20/26

No Detections

Sample ID: CG-44-2.5	Lab ID: 553922-042	Collected: 02/20/26

No Detections

Sample ID: CG-45-0.5	Lab ID: 553922-043	Collected: 02/20/26

No Detections

Sample ID: CG-45-2.5	Lab ID: 553922-044	Collected: 02/20/26

No Detections

Sample ID: CG-45-0.5-DUP	Lab ID: 553922-045	Collected: 02/20/26

No Detections

Sample ID: CG-45-2.5-DUP	Lab ID: 553922-046	Collected: 02/20/26

No Detections

Sample ID: CG-46-0.5-	Lab ID: 553922-047	Collected: 02/20/26

No Detections

Sample ID: CG-46-2.5	Lab ID: 553922-048	Collected: 02/20/26

No Detections

Results for any subcontracted analyses are not included in this summary. Data qualifiers and additional information necessary for the interpretation of the test results are contained in the PDF file and may not be included in this summary.

Login 553922

931 W. Barkley Avenue, Orange, CA 92868

Phone 714-771-6900

ALPY TICAL

Chain of Custody Record

Lab No: 553922

Page: 1 of 6

Turn Around Time (rush by advanced notice only)

Standard:	X	5 Day:		3 Day:	
2 Day:		1 Day:		Custom TAT	

Matrix: A = Air, S = Soil/Solid, W = Water, DW = Drinking Water, P = Product, O = Oil, SD = Sediment, T = Tissue, WP = Wipe, WW = Wastewater, X = Other

Sample Type: C = Composite, G = Grab or Discrete, B = Blank, O = Other

Preservatives: 0 = none, 1 = $Na_2S_2O_3$, 2 = HCl, 3 = HNO_3, 4 = H_2SO_4, 5 = NaOH, 6 = Other

Sample Receipt Temp and Notes: (lab use only)

CUSTOMER INFORMATION

Company:	Terraphase Engineering Inc.
Report To:	Vanya Keyes
Email:	vanya.keyes@terraphase.com
Address:	18401 Von Karman Ave
Phone:	949-377-2227
Fax:	

PROJECT INFORMATION

Name:	Centennial High School
Number:	0215.002.002
P.O. #:	
Address:	2606 N Central Ave, Compton, CA, 90222
Global ID:	
Sampled By:	Portia C. Ibarra

Test Instructions / Comments

Please also send report to
clare.steedman@terraphase.com
portia.ibarra@terraphase.com

3.2/3.6
1.9/2.3 1,2-15

	Sample ID	Sampling Date	Sampling Time (24 hr)	Matrix	Sample Type	Pres.	Cont. No.	Cont. Size	Initials	Arsenic (6020)	Lead (6010B)	PCBs (8082)	Title 22 Metals (6020/7471A)	Dioxins & Furins (8290A)	VOCs (8260B)	TPH (8015)	Test Instructions / Comments
1	GOC5-SB-01-0.5	2/20/26	1030	S	G	6	6	80z Vials	PCl				X	X	X	X	
2	GOC5-SB-01-2.5		1035			0	1	80z									hold
3	GOC5-SB-01-5.0		1040			0	1	80z					PB				hold
4	GOC5-SB-02-0.5		1150			6	6	80z Vials			X	X			X	X	
5	GOC5-SB-02-2.5		1157			0	1	80z									hold
6	GOC5-SB-02-5.0		1204			0	1	↓									hold
7	~~DUP-01-260205~~ PB					0		80z									
8	DUP-02-0.5-260220		—			6	6	80z Vials					X	X	X	X	hold
9	DUP-02-2.5-260220		—	↓	↓	0	1	80z	↓								hold
10	DUP-02-5.0-260220	2/20/26	—	S	G	0	1	80z	PCl								hold

	Signature	Print Name	Company / Title	Date / Time
1 Relinquished By:		PCl/Terraphase	TE/GCA	2/20/26 1630
1 Received By:		GEMA O.	GANH	2-20-26 1630
2 Relinquished By:		GEMA	GANH	2/20/26 1730
2 Received By:		D.Sauceda	ENT	2/20/26 1740
3 Relinquished By:		D.Sauceda	ENT	2/20/26 1833

Rec: MeOH, EA ice/ice 1933

ENTHALPY ANALYTICAL

Chain of Custody Record

Lab No: 553922

Page: 2 of 6

Turn Around Time (rush by advanced notice only)

Standard:	X	5 Day:		3 Day:	
2 Day:		1 Day:		Custom TAT	

Enthalpy Analytical - Orange

931 W. Barkley Avenue, Orange, CA 92868

Phone 714-771-6900

Matrix: A = Air, S = Soil/Solid, W = Water, DW = Drinking Water, P = Product, O = Oil, SD = Sediment, T = Tissue, WP = Wipe, WW = Wastewater, X = Other

Sample Type: C = Composite, G = Grab or Discrete, B = Blank, O = Other

Preservatives: 0 = none, 1 = $Na_2S_2O_3$, 2 = HCl, 3 = HNO_3, 4 = H_2SO_4, 5 = NaOH, 6 = Other

Sample Receipt Temp and Notes: (lab use only)

CUSTOMER INFORMATION

Company:	Terraphase Engineering Inc.
Report To:	Vanya Keyes
Email:	vanya.keyes@terraphase.com
Address:	18401 Von Karman Ave
Phone:	949-377-2227
Fax:	

PROJECT INFORMATION

Name:	Centennial High School
Number:	0215.002.002
P.O. #:	
Address:	2606 N Central Ave, Compton, CA, 90222
Global ID:	
Sampled By:	Portia C. Ibarra

Test Instructions / Comments: Please also send report to clare.steedman@terraphase.com portia.ibarra@terraphase.com

	Sample ID	Sampling Date	Sampling Time (24 hr)	Matrix	Sample Type	Pres.	Cont. No.	Cont. Size	Initials	Arsenic (6020)	Lead (6010B)	PCBs (8082)	Title 22 Metals (6020/7471A)	Dioxins & Furins (8290A)	VOCs (8260B)	TPH (8015)	Test Instructions / Comments
1	AOC5-SB-03-0.5	2/20/26	1048	S	G	0	6	1 8oz 5 vons	PCL		X	X			X	X	
2	AOC5-SB-03-2.5		1051	S	G	0	1	8oz									hold
3	AOC5-SB-03-5.0		1120														hold
4	AOC5-SB-05-0.5		1357								X	X					
5	AOC5-SB-05-2.5		1402														hold
6	DUP-03-0.5-260220		—								X	X					
7	DUP-03-2.5-260220		—														hold
8	AOC5-SB-06-0.5		1412								X	X					
9	AOC5-SB-06-2.5	2/20/26	1420	S	G	0	1	8oz	PCL								hold
10																	

	Signature	Print Name	Company / Title	Date / Time
[1] Relinquished By:		portia ibarra	TE / AOC	2/20/26 1630
[1] Received By:		GEMA O	EARTH	2-20-26 1630
[2] Relinquished By:		GEMA O	EARTH	2-20-26 1730
[2] Received By:		D. Sanchez	EA	2/20/26 1240
[3] Relinquished By:		D. Sanchez	EA	2/20/26 1833

Rec: ADDA EA 2/20/26 1833

ENTHALPY ANALYTICAL

Chain of Custody Record

Lab No: 553922

Page: 3 of 6

Turn Around Time (rush by advanced notice only)

Standard:	X	5 Day:		3 Day:	
2 Day:		1 Day:		Custom TAT	

Enthalpy Analytical - Orange

931 W. Barkley Avenue, Orange, CA 92868

Phone 714-771-6900

Matrix: A = Air, S = Soil/Solid, W = Water, DW = Drinking Water, P = Product, O = Oil, SD = Sediment, T = Tissue, WP = Wipe, WW = Wastewater, X = Other

Sample Type: C = Composite, G = Grab or Discrete, B = Blank, O = Other

Preservatives: 0 = none, 1 = $Na_2S_2O_3$, 2 = HCl, 3 = HNO_3, 4 = H_2SO_4, 5 = NaOH, 6 = Other

Sample Receipt Temp and Notes: (lab use only)

CUSTOMER INFORMATION

Company:	Terraphase Engineering Inc.
Report To:	Vanya Keyes
Email:	vanya.keyes@terraphase.com
Address:	18401 Von Karman Ave
Phone:	949-377-2227
Fax:	

PROJECT INFORMATION

Name:	Centennial High School
Number:	0215.002.002
P.O. #:	
Address:	2606 N Central Ave, Compton, CA, 90222
Global ID:	
Sampled By:	Portia C. Ibarra

Test Instructions / Comments: Please also send report to clare.steedman@terraphase.com portia.ibarra@terraphase.com

	Sample ID	Sampling Date	Sampling Time (24 hr)	Matrix	Sample Type	Pres.	Cont. No.	Cont. Size	Initials	OCPs by USEPA 8081A	Asbestos by PLM	Lead 6010B	PCBs 8082	Test Instructions / Comments
1	AOC4-SB-46-0.5	2/20/26	0733	S	G	0	1	8oz	PCI			X	X	CG-44-0.5
2	AOC4-SB-47-0.5		0741									X	X	
3	AOC4-SB-48-0.5		0752									X	X	
4	AOC4-SB-46-2.5		0738											CG-44-2.5
5	AOC4-SB-47-2.5		0746											
6	AOC4-SB-48-2.5		0759											
7	AOC4-SB-52-0.5		0915									X	X	CG-46-0.5
8	AOC4-SB-53-0.5		0928									X	X	
9	AOC4-SB-54-0.5	2/20/26	0938	S	G	0	1	8oz	PCI			X	X	
10														

	Signature	Print Name	Company / Title	Date / Time
1 Relinquished By:		Portia Ibarra	TEI / Geol	2/20/26 1630
1 Received By:		CEMA O.	EANH	2/20/26 1630
2 Relinquished By:		CEMA	EANH	2/20/26 1730
2 Received By:		D. Sanchez	EA	2/20/26 1740
3 Relinquished By:		D. Sanchez	EA	2/20/26 1832

Rec: Add'l EA 2/20/26 1833

ENTHALPY ANALYTICAL

Chain of Custody Record

Lab No: 553922

Page: 4 of

Turn Around Time (rush by advanced notice only)

Standard:	X	5 Day:		3 Day:	
2 Day:		1 Day:		Custom TAT	

Enthalpy Analytical - Orange

931 W. Barkley Avenue, Orange, CA 92868

Phone 714-771-6900

Matrix: A = Air, S = Soil/Solid, W = Water, DW = Drinking Water, P = Product, O = Oil, SD = Sediment, T = Tissue, WP = Wipe, WW = Wastewater, X = Other

Sample Type: C = Composite, G = Grab or Discrete, B = Blank, O = Other

Preservatives: 0 = none, 1 = $Na_2S_2O_3$, 2 = HCl, 3 = HNO_3, 4 = H_2SO_4, 5 = NaOH, 6 = Other

Sample Receipt Temp and Notes: (lab use only)

CUSTOMER INFORMATION

Company:	Terraphase Engineering Inc.
Report To:	Vanya Keyes
Email:	vanya.keyes@terraphase.com
Address:	18401 Von Karman Ave
Phone:	949-377-2227
Fax:	

PROJECT INFORMATION

Name:	Centennial High School
Number:	0215.002.002
P.O. #:	
Address:	2606 N Central Ave, Compton, CA, 90222
Global ID:	
Sampled By:	Portia C. Ibarra

Test Instructions / Comments: Please also send report to clare.steedman@terraphase.com portia.ibarra@terraphase.com

	Sample ID	Sampling Date	Sampling Time (24 hr)	Matrix	Sample Type	Pres.	Cont. No.	Cont. Size	Initials	OCPs by USEPA 8081A	Asbestos by PLM	VOCs by 8260B	PCBs 8082					Test Instructions / Comments
1	AOC4-SB-49-0.5	2/20/26	0800	S	G	0	2	8oz	PCL			X	X					CG-45-0.5
2	AOC4-SB-50-0.5		0838				2	1				X	X					
3	AOC4-SB-51-0.5		0900				2					X	X					
4	DUP-01-0.5-260220		—				1					X	X					
5	AOC4-SB-49-2.5		0803				2											CG-45-2.5
6	AOC4-SB-50-2.5		0843				2											
7	AOC4-SB-51-2.5		0903				2											
8	DUP-01-2.5-260220	2/20/26	—	S	G	0	1	8oz	PCL									hold
9																		
10																		

	Signature	Print Name	Company / Title	Date / Time
1 Relinquished By:		Portia Ibarra	TEI / ghn	2/20/26 / 1630
1 Received By:		GEMA O.	EANH	2/20/26 1630
2 Relinquished By:		GEMA	EANH	2/20/26 1730
2 Received By:		D. Sanchez	EA	2/20/26 1740
3 Relinquished By:		D. Sanchez	EA	2/20/26 1833

Rec: Adda EA 2/20/26 1833

ENTHALPY ANALYTICAL

Chain of Custody Record

Lab No: 553922

Page: 5 of 6

Turn Around Time (rush by advanced notice only)

Standard:	X	5 Day:		3 Day:	
2 Day:		1 Day:		Custom TAT	

Enthalpy Analytical - Orange

931 W. Barkley Avenue, Orange, CA 92868

Phone 714-771-6900

Matrix: **A** = Air **S** = Soil/Solid **W** = Water **DW** = Drinking Water **P** = Product **O** = Oil **SD** = Sediment **T** = Tissue **WP** = Wipe **WW** = Wastewater **X** = Other

Sample Type: **C** = Composite **G** = Grab or Discrete **B** = Blank **O** = Other

Preservatives: **0** = none **1** = $Na_2S_2O_3$ **2** = HCl **3** = HNO_3 **4** = H_2SO_4 **5** = NaOH **6** = Other

Sample Receipt Temp and Notes: (lab use only)

CUSTOMER INFORMATION		PROJECT INFORMATION	
Company:	Terraphase Engineering Inc.	Name:	Centennial High School
Report To:	Vanya Keyes	Number:	
Email:	vanya.keyes@terraphase.com	P.O. #:	0215.002.002
Address:	18401 Von Karman Ave	Address:	2606 N Central Ave
			Compton, CA, 90222
Phone:	949-377-2227	Global ID:	
Fax:		Sampled By:	Portia C. Ibarra

Analysis Request

Test Instructions / Comments

Please also send report to clare.steedman@terraphase.com portia.ibarra@terraphase.com

	Sample ID	Sampling Date	Sampling Time (24 hr)	Matrix	Sample Type	Pres.	Cont. No.	Cont. Size	Initials	OCPs by USEPA 8081A	Asbestos by PLM	Lead 6010B	PCBs 8082	VOCs 8260B 15035	TPH 8015/5035			Test Instructions / Comments
1	GOCH-SB-S2-2.5	2/20/26	0920	S	G	0	1	8oz	PCI									} CG-46-2.5
2	GOCH-SB-S3-2.5	"	0933	"	"	"	"	"	"									
3	GOCH-SB-S4-2.5	"	0942	S	G	0	1	8oz	PCI									
4	EB-01-260220	"	1530	W	G	HCl/ HNO3	8	1 amb 1 poly 1 vial	PCI	X	X	X	X	X	X			
5	TB-01-260220	2/20/26	—	W	O	6	2	VOA	PCI					X	X			
6																		
7																		
8																		
9																		
10																		

	Signature	Print Name	Company / Title	Date / Time
1 Relinquished By:		Portia Ibarra	TER/GeoT	2/20/26 / 1630
1 Received By:		CTEMA	CHMT	2/20/26 1630
2 Relinquished By:		CTEMA	CHMT	2/20/26 1730
2 Received By:		D. Saucer	EA	2/20/26 1740
3 Relinquished By:		D. Saucer	EA	2/20/26 1833

Rec. Added by EA 2/20/26 1833

ENTHALPY ANALYTICAL

Chain of Custody Record

Lab No: 553922

Page: 6 of 6

Turn Around Time (rush by advanced notice only)

Standard:	X	5 Day:		3 Day:	
2 Day:		1 Day:		Custom TAT	

Enthalpy Analytical - Orange

931 W. Barkley Avenue, Orange, CA 92868

Phone 714-771-6900

Matrix: A = Air, S = Soil/Solid, W = Water, DW = Drinking Water, P = Product, O = Oil, SD = Sediment, T = Tissue, WP = Wipe, WW = Wastewater, X = Other

Sample Type: C = Composite, G = Grab or Discrete, B = Blank, O = Other

Preservatives: 0 = none, 1 = $Na_2S_2O_3$, 2 = HCl, 3 = HNO_3, 4 = H_2SO_4, 5 = NaOH, 6 = Other

Sample Receipt Temp and Notes: (lab use only)

CUSTOMER INFORMATION		PROJECT INFORMATION	
Company:	Terraphase Engineering Inc.	Name:	Centennial High School
Report To:	Vanya Keyes	Number:	
Email:	vanya.keyes@terraphase.com	P.O. #:	0215.002.002
Address:	18401 Von Karman Ave	Address:	2606 N Central Ave
			Compton, CA, 90222
Phone:	949-377-2227	Global ID:	
Fax:		Sampled By:	Portia C. Ibarra

	Sample ID	Sampling Date	Sampling Time (24 hr)	Matrix	Sample Type	Pres.	Cont. No.	Cont. Size	Initials	OCPs by USEPA 8081A	Asbestos by PLM	Test Instructions / Comments
1	CG-44-0.5									X	X	
2	CG-44-2.5									X	X	
3	CG-45-0.5									X	X	
4	CG-45-2.5									X	X	
5	CG-45-0.5-DUP									X	X	split from CG-45-0.5
6	CG-45-2.5-DUP									X	X	split from CG 45-2.5
7	CG-46-0.5-									X	X	
8	CG-46-2.5									X	X	
9	CG-47-0.5									X	X	2 (aoc5-05 & 06-0.5) missing aoc5-04-0.5
10	CG-47-2.5									X	X	5 (aoc5-05 & 06-2.5) missing aoc5-04-2.5

Analysis Request

CG-47-0.5 2.5

Is missing aoc5-04-0.5 2.5 (put on hold for now)

Please also send report to

clare.steedman@terraphase.com

portia.ibarra@terraphase.com

CG-47-0.5 2.5 : aoc5-SB-05 2.5, aoc5-SB-06

	Signature	Print Name	Company / Title	Date / Time
1 Relinquished By:		Portia Ibarra	TEL/geol	2/20/26 1650
1 Received By:		Gema O	eANH	2/20/26 1630
2 Relinquished By:		Gema	eANH	2/20/26 1730
2 Received By:		D. Sauceda	EA	2/20/26 1740
3 Relinquished By:		D. Sauceda	EA	2/20/26 1833

Rec: Addis EA 2/20/26 1833

SAMPLE RECEIPT CHECKLIST

Section 1: General Info

Date Received: 2/20/26 WO# 553922 Client: Terraphase

Section 2: Shipping / Custody **Are custody seals present?** ☐ Yes ☒ No

Custody seals intact on arrival? ■ N/A ☐ Yes ☐ No ☐ On cooler / box ☐ On samples

■ Courier ☐ Walk-In ☐ Field Sampling ☐ Shipping Info: _____

Section 3a: Condition / Packaging ☐ **Outside 0.0 - 6.0°C (0.0 - 10.0°C for microbiology) (PM notified)**

Date Opened 2/20/26 By (initials) DXS Type of ice used: ■ Wet ☐ Blue/Gel ☐ None

☐ Samples received on ice directly from the field; cooling process had begun. (if checked, skip temperatures)

☐ Sample matrix doesn't require cooling (e.g. air, bulk PCB). (if checked, skip temperatures)

If no cooler: Observed/Adjusted Temp (°C): _____ / _____ Thermometer/IR Gun: IR15 CF: +0.4

Cooler Temp (°C) #1: 3.2 / 3.6 #2: 1.9 / 2.3 #3: ____ / ____ #4: ____ / ____ #5: ____ / ____ #6: ____ / ____

Section 3b: Microbiology Samples ■ **No microbiology samples submitted (skip 3b)**

☐ Within temp range 0.0 - 10.0°C or received on ice directly from field.

☐ Adequate headspace for microbiology analysis.

Section 3c: Air Samples ■ **No air samples submitted (skip 3c)**

☐ 1.4L Canisters ☐ 6L Canisters ☐ Tedlar Bags ☐ MCE Cassettes ☐ Sorbent Tubes ☐ Other _____

Section 4: Containers / Labels / Samples	YES	NO	N/A
1) Were custody papers present, filled properly, and legible?		X	
2) Is the sampler's name present on the CoC?	X		
3) Were containers received in good condition (unbroken / unopened / uncompromised)?	X		
4) Were the samples bagged? (required for microbiology samples; recommended for soil samples)	X		
5) Were all of, and only, the correct samples received?	X		
6) Are sample labels present, legible, and in agreement with the CoC?	X*		
7) Does the container count match the CoC?	X		
8) Was sufficient sample volume / mass received for the analyses requested?		X	
9) Were samples received in proper containers for the analyses requested?		X	
10) Were samples received with > 1/2 holding time remaining?	X		
11) Are samples properly preserved as indicated by CoC / labels?	X		
12) Unpreserved VOAs received - If necessary, was the hold time changed in LIMS?			X
13) Are VOA vials free from headspace/bubbles > 6mm?	X		

Section 5: Explanations / Comments

(If no comments are made, then no discrepancies noted.)

4.1: Information obliterated on the COC.

4.6*/4.8/4.9: Sample -040: Received 2x digestion tubes labeled on the containers as Temperature Blank, received in a bubble wrap envelope labeled with the correct sample ID from the COC. TB-01-260220. Sample should be 2x 40mL vials preserved with HCl.

☐ **No additional discrepancies**

Date Logged 2/20/26 **By (print)** ABD **(sign)** AdDS

Date Labeled 2/20/26 **By (print)** AGR/MSK **(sign)** AdDS for AGR/MSK

Outlook

RE: [External] - RE: Analysis of deeper samples requested for Centennial

From Vanya Keyes <vanya.keyes@terraphase.com>
Date Thu 3/12/2026 11:50 AM
To Patricia Mata <patty.mata@enthalpy.com>
Cc Clare Steedman <clare.steedman@terraphase.com>

EXTERNAL EMAIL - This email was sent by a person from outside your organization. Exercise caution when clicking links, opening attachments or taking further action, before validating its authenticity.

Hi Patty,
I'd like to add these additional samples to be analyzed:

- Lead
  - AOC4-SB-46-2.5
  - AOC5-SB-28-2.5

Thank you!

Vanya Keyes
Senior Project Geologist
(949) 990-0182

From: Patricia Mata <patty.mata@enthalpy.com>
Sent: Monday, March 9, 2026 11:24 AM
To: Vanya Keyes <vanya.keyes@terraphase.com>
Cc: Clare Steedman <clare.steedman@terraphase.com>
Subject: Re: [External] - RE: Analysis of deeper samples requested for Centennial

Hi Vanya,

I'm back from vacation today and I will put in the 2 x PCB test requests on std 5 day TAT.

With Regards,
Patty Mata
Project Manager
Enthalpy Analytical
Direct: +1-714-771-9930 | Mobile: +1-714-323-2586
patty.mata@enthalpy.com

From: Vanya Keyes <vanya.keyes@terraphase.com>
Sent: Friday, March 6, 2026 11:42 AM
To: Patricia Mata <patty.mata@enthalpy.com>
Cc: Clare Steedman <clare.steedman@terraphase.com>
Subject: RE: [External] - RE: Analysis of deeper samples requested for Centennial

ENTHALPY ANALYTICAL

Analysis Results for 553922

Vanya Keyes
Terraphase Engineering
18401 Von Karman Ave, Suite #410
Irvine, CA 92612

Lab Job #: 553922
Project No: CENTENNIAL HS
Location: Centennial High School, 2606 N Central Ave., Compton, CA 90222
Date Received: 02/20/26

Sample ID: AOC5-SB-01-0.5 **Lab ID: 553922-001** **Collected: 02/20/26 10:30**
Matrix: Soil

553922-001 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6020 Prep Method: EPA 3050B									
Antimony	ND		mg/Kg	0.99	0.99	396206	02/24/26	02/25/26	KCD
Arsenic	**3.1**		mg/Kg	0.99	0.99	396206	02/24/26	02/25/26	KCD
Barium	**110**		mg/Kg	0.99	0.99	396206	02/24/26	02/25/26	KCD
Beryllium	ND		mg/Kg	0.99	0.99	396206	02/24/26	02/25/26	KCD
Cadmium	ND		mg/Kg	0.50	0.99	396206	02/24/26	02/25/26	KCD
Chromium	**24**		mg/Kg	2.0	0.99	396206	02/24/26	02/25/26	KCD
Cobalt	**8.5**		mg/Kg	0.99	0.99	396206	02/24/26	02/25/26	KCD
Copper	**30**		mg/Kg	2.0	0.99	396206	02/24/26	02/25/26	KCD
Lead	**37**		mg/Kg	0.99	0.99	396206	02/24/26	02/25/26	KCD
Molybdenum	ND		mg/Kg	0.99	0.99	396206	02/24/26	02/25/26	KCD
Nickel	**19**		mg/Kg	0.99	0.99	396206	02/24/26	02/25/26	KCD
Selenium	ND		mg/Kg	4.0	0.99	396206	02/24/26	02/25/26	KCD
Silver	ND		mg/Kg	0.50	0.99	396206	02/24/26	02/25/26	KCD
Thallium	ND		mg/Kg	0.99	0.99	396206	02/24/26	02/25/26	KCD
Vanadium	**41**		mg/Kg	2.0	0.99	396206	02/24/26	02/25/26	KCD
Zinc	**120**		mg/Kg	9.9	0.99	396206	02/24/26	02/25/26	KCD
Method: EPA 7471A Prep Method: EPA 7471A									
Mercury	ND		mg/Kg	0.17	1.2	396198	02/24/26	02/24/26	MLL
Method: EPA 8015B Prep Method: EPA 5035									
TPH Gasoline	ND		mg/Kg	3.9	1.3	396469	02/26/26	02/26/26	SXR
Surrogates				**Limits**					
Bromofluorobenzene (FID)	76%		%REC	59-122	1.3	396469	02/26/26	02/26/26	SXR
Method: EPA 8015M Prep Method: EPA 3580M									
GRO C8-C10	ND		mg/Kg	50	5	396457	02/25/26	02/26/26	NXY
DRO C10-C28	**120**		mg/Kg	50	5	396457	02/25/26	02/26/26	NXY
ORO C28-C44	**240**		mg/Kg	100	5	396457	02/25/26	02/26/26	NXY
Surrogates				**Limits**					
n-Triacontane	130%		%REC	59-136	5	396457	02/25/26	02/26/26	NXY
Method: EPA 8260B Prep Method: EPA 5035									
3-Chloropropene	ND		ug/Kg	7.8	1.6	396056	02/22/26	02/22/26	LYZ
cis-1,4-Dichloro-2-butene	ND		ug/Kg	7.8	1.6	396056	02/22/26	02/22/26	LYZ
trans-1,4-Dichloro-2-butene	ND		ug/Kg	7.8	1.6	396056	02/22/26	02/22/26	LYZ
Freon 12	ND		ug/Kg	7.8	1.6	396056	02/22/26	02/22/26	LYZ
Chloromethane	ND		ug/Kg	7.8	1.6	396056	02/22/26	02/22/26	LYZ
Vinyl Chloride	ND		ug/Kg	7.8	1.6	396056	02/22/26	02/22/26	LYZ
Bromomethane	ND		ug/Kg	7.8	1.6	396056	02/22/26	02/22/26	LYZ

Results for any subcontracted analyses are not included in this section.

ENTHALPY ANALYTICAL

Analysis Results for 553922

553922-001 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Chloroethane	ND		ug/Kg	7.8	1.6	396056	02/22/26	02/22/26	LYZ
Trichlorofluoromethane	ND		ug/Kg	7.8	1.6	396056	02/22/26	02/22/26	LYZ
Acetone	ND		ug/Kg	160	1.6	396056	02/22/26	02/22/26	LYZ
Freon 113	ND		ug/Kg	7.8	1.6	396056	02/22/26	02/22/26	LYZ
1,1-Dichloroethene	ND		ug/Kg	7.8	1.6	396056	02/22/26	02/22/26	LYZ
Methylene Chloride	ND		ug/Kg	7.8	1.6	396056	02/22/26	02/22/26	LYZ
MTBE	ND		ug/Kg	7.8	1.6	396056	02/22/26	02/22/26	LYZ
trans-1,2-Dichloroethene	ND		ug/Kg	7.8	1.6	396056	02/22/26	02/22/26	LYZ
1,1-Dichloroethane	ND		ug/Kg	7.8	1.6	396056	02/22/26	02/22/26	LYZ
2-Butanone	ND		ug/Kg	160	1.6	396056	02/22/26	02/22/26	LYZ
cis-1,2-Dichloroethene	ND		ug/Kg	7.8	1.6	396056	02/22/26	02/22/26	LYZ
2,2-Dichloropropane	ND		ug/Kg	7.8	1.6	396056	02/22/26	02/22/26	LYZ
Chloroform	ND		ug/Kg	7.8	1.6	396056	02/22/26	02/22/26	LYZ
Bromochloromethane	ND		ug/Kg	7.8	1.6	396056	02/22/26	02/22/26	LYZ
1,1,1-Trichloroethane	ND		ug/Kg	7.8	1.6	396056	02/22/26	02/22/26	LYZ
1,1-Dichloropropene	ND		ug/Kg	7.8	1.6	396056	02/22/26	02/22/26	LYZ
Carbon Tetrachloride	ND		ug/Kg	7.8	1.6	396056	02/22/26	02/22/26	LYZ
1,2-Dichloroethane	ND		ug/Kg	7.8	1.6	396056	02/22/26	02/22/26	LYZ
Benzene	ND		ug/Kg	7.8	1.6	396056	02/22/26	02/22/26	LYZ
Trichloroethene	ND		ug/Kg	7.8	1.6	396056	02/22/26	02/22/26	LYZ
1,2-Dichloropropane	ND		ug/Kg	7.8	1.6	396056	02/22/26	02/22/26	LYZ
Bromodichloromethane	ND		ug/Kg	7.8	1.6	396056	02/22/26	02/22/26	LYZ
Dibromomethane	ND		ug/Kg	7.8	1.6	396056	02/22/26	02/22/26	LYZ
4-Methyl-2-Pentanone	ND		ug/Kg	7.8	1.6	396056	02/22/26	02/22/26	LYZ
cis-1,3-Dichloropropene	ND		ug/Kg	7.8	1.6	396056	02/22/26	02/22/26	LYZ
Toluene	ND		ug/Kg	7.8	1.6	396056	02/22/26	02/22/26	LYZ
trans-1,3-Dichloropropene	ND		ug/Kg	7.8	1.6	396056	02/22/26	02/22/26	LYZ
1,1,2-Trichloroethane	ND		ug/Kg	7.8	1.6	396056	02/22/26	02/22/26	LYZ
1,3-Dichloropropane	ND		ug/Kg	7.8	1.6	396056	02/22/26	02/22/26	LYZ
Tetrachloroethene	ND		ug/Kg	7.8	1.6	396056	02/22/26	02/22/26	LYZ
Dibromochloromethane	ND		ug/Kg	7.8	1.6	396056	02/22/26	02/22/26	LYZ
1,2-Dibromoethane	ND		ug/Kg	7.8	1.6	396056	02/22/26	02/22/26	LYZ
Chlorobenzene	ND		ug/Kg	7.8	1.6	396056	02/22/26	02/22/26	LYZ
1,1,1,2-Tetrachloroethane	ND		ug/Kg	7.8	1.6	396056	02/22/26	02/22/26	LYZ
Ethylbenzene	ND		ug/Kg	7.8	1.6	396056	02/22/26	02/22/26	LYZ
m,p-Xylenes	ND		ug/Kg	16	1.6	396056	02/22/26	02/22/26	LYZ
o-Xylene	ND		ug/Kg	7.8	1.6	396056	02/22/26	02/22/26	LYZ
Styrene	ND		ug/Kg	7.8	1.6	396056	02/22/26	02/22/26	LYZ
Bromoform	ND		ug/Kg	7.8	1.6	396056	02/22/26	02/22/26	LYZ
Isopropylbenzene	ND		ug/Kg	7.8	1.6	396056	02/22/26	02/22/26	LYZ
1,1,2,2-Tetrachloroethane	ND		ug/Kg	7.8	1.6	396056	02/22/26	02/22/26	LYZ
1,2,3-Trichloropropane	ND		ug/Kg	7.8	1.6	396056	02/22/26	02/22/26	LYZ
Propylbenzene	ND		ug/Kg	7.8	1.6	396056	02/22/26	02/22/26	LYZ
Bromobenzene	ND		ug/Kg	7.8	1.6	396056	02/22/26	02/22/26	LYZ
1,3,5-Trimethylbenzene	ND		ug/Kg	7.8	1.6	396056	02/22/26	02/22/26	LYZ
2-Chlorotoluene	ND		ug/Kg	7.8	1.6	396056	02/22/26	02/22/26	LYZ
4-Chlorotoluene	ND		ug/Kg	7.8	1.6	396056	02/22/26	02/22/26	LYZ
tert-Butylbenzene	ND		ug/Kg	7.8	1.6	396056	02/22/26	02/22/26	LYZ
1,2,4-Trimethylbenzene	ND		ug/Kg	7.8	1.6	396056	02/22/26	02/22/26	LYZ
sec-Butylbenzene	ND		ug/Kg	7.8	1.6	396056	02/22/26	02/22/26	LYZ
para-Isopropyl Toluene	ND		ug/Kg	7.8	1.6	396056	02/22/26	02/22/26	LYZ
1,3-Dichlorobenzene	ND		ug/Kg	7.8	1.6	396056	02/22/26	02/22/26	LYZ

Results for any subcontracted analyses are not included in this section.

ENTHALPY ANALYTICAL

Analysis Results for 553922

553922-001 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
1,4-Dichlorobenzene	ND		ug/Kg	7.8	1.6	396056	02/22/26	02/22/26	LYZ
n-Butylbenzene	ND		ug/Kg	7.8	1.6	396056	02/22/26	02/22/26	LYZ
1,2-Dichlorobenzene	ND		ug/Kg	7.8	1.6	396056	02/22/26	02/22/26	LYZ
1,2-Dibromo-3-Chloropropane	ND		ug/Kg	7.8	1.6	396056	02/22/26	02/22/26	LYZ
1,2,4-Trichlorobenzene	ND		ug/Kg	7.8	1.6	396056	02/22/26	02/22/26	LYZ
Hexachlorobutadiene	ND		ug/Kg	7.8	1.6	396056	02/22/26	02/22/26	LYZ
Naphthalene	ND		ug/Kg	7.8	1.6	396056	02/22/26	02/22/26	LYZ
1,2,3-Trichlorobenzene	ND		ug/Kg	7.8	1.6	396056	02/22/26	02/22/26	LYZ
Xylene (total)	ND		ug/Kg	7.8	1.6	396056	02/22/26	02/22/26	LYZ
Surrogates				**Limits**					
Dibromofluoromethane	101%		%REC	70-130	1.6	396056	02/22/26	02/22/26	LYZ
1,2-Dichloroethane-d4	96%		%REC	70-130	1.6	396056	02/22/26	02/22/26	LYZ
Toluene-d8	98%		%REC	70-130	1.6	396056	02/22/26	02/22/26	LYZ
Bromofluorobenzene	99%		%REC	70-130	1.6	396056	02/22/26	02/22/26	LYZ

Results for any subcontracted analyses are not included in this section.

ENTHALPY ANALYTICAL

Analysis Results for 553922

Sample ID: AOC5-SB-02-0.5	Lab ID: 553922-004	Collected: 02/20/26 11:50
	Matrix: Soil	

553922-004 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3050B									
Lead	**3.9**		mg/Kg	0.97	0.97	396187	02/23/26	02/24/26	TWJ
Method: EPA 8015B Prep Method: EPA 5035									
TPH Gasoline	ND		mg/Kg	2.9	0.97	396469	02/26/26	02/26/26	SXR
Surrogates				**Limits**					
Bromofluorobenzene (FID)	88%		%REC	59-122	0.97	396469	02/26/26	02/26/26	SXR
Method: EPA 8015M Prep Method: EPA 3580M									
GRO C8-C10	ND		mg/Kg	10	1	396457	02/25/26	02/26/26	NXY
DRO C10-C28	ND		mg/Kg	10	1	396457	02/25/26	02/26/26	NXY
ORO C28-C44	ND		mg/Kg	20	1	396457	02/25/26	02/26/26	NXY
Surrogates				**Limits**					
n-Triacontane	90%		%REC	59-136	1	396457	02/25/26	02/26/26	NXY
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	50	1	396467	02/26/26	02/27/26	XLY
Aroclor-1221	ND		ug/Kg	50	1	396467	02/26/26	02/27/26	XLY
Aroclor-1232	ND		ug/Kg	50	1	396467	02/26/26	02/27/26	XLY
Aroclor-1242	ND		ug/Kg	50	1	396467	02/26/26	02/27/26	XLY
Aroclor-1248	ND		ug/Kg	50	1	396467	02/26/26	02/27/26	XLY
Aroclor-1254	ND		ug/Kg	50	1	396467	02/26/26	02/27/26	XLY
Aroclor-1260	ND		ug/Kg	50	1	396467	02/26/26	02/27/26	XLY
Aroclor-1262	ND		ug/Kg	50	1	396467	02/26/26	02/27/26	XLY
Aroclor-1268	ND		ug/Kg	50	1	396467	02/26/26	02/27/26	XLY
Total PCBs	ND		ug/Kg	50	1	396467	02/26/26	02/27/26	XLY
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	107%		%REC	50-127	1	396467	02/26/26	02/27/26	XLY
Method: EPA 8260B Prep Method: EPA 5035									
3-Chloropropene	ND		ug/Kg	4.9	0.98	396056	02/22/26	02/22/26	LYZ
cis-1,4-Dichloro-2-butene	ND		ug/Kg	4.9	0.98	396056	02/22/26	02/22/26	LYZ
trans-1,4-Dichloro-2-butene	ND		ug/Kg	4.9	0.98	396056	02/22/26	02/22/26	LYZ
Freon 12	ND		ug/Kg	4.9	0.98	396056	02/22/26	02/22/26	LYZ
Chloromethane	ND		ug/Kg	4.9	0.98	396056	02/22/26	02/22/26	LYZ
Vinyl Chloride	ND		ug/Kg	4.9	0.98	396056	02/22/26	02/22/26	LYZ
Bromomethane	ND		ug/Kg	4.9	0.98	396056	02/22/26	02/22/26	LYZ
Chloroethane	ND		ug/Kg	4.9	0.98	396056	02/22/26	02/22/26	LYZ
Trichlorofluoromethane	ND		ug/Kg	4.9	0.98	396056	02/22/26	02/22/26	LYZ
Acetone	ND		ug/Kg	98	0.98	396056	02/22/26	02/22/26	LYZ
Freon 113	ND		ug/Kg	4.9	0.98	396056	02/22/26	02/22/26	LYZ
1,1-Dichloroethene	ND		ug/Kg	4.9	0.98	396056	02/22/26	02/22/26	LYZ
Methylene Chloride	ND		ug/Kg	4.9	0.98	396056	02/22/26	02/22/26	LYZ
MTBE	ND		ug/Kg	4.9	0.98	396056	02/22/26	02/22/26	LYZ
trans-1,2-Dichloroethene	ND		ug/Kg	4.9	0.98	396056	02/22/26	02/22/26	LYZ
1,1-Dichloroethane	ND		ug/Kg	4.9	0.98	396056	02/22/26	02/22/26	LYZ

Results for any subcontracted analyses are not included in this section.

ENTHALPY ANALYTICAL

Analysis Results for 553922

553922-004 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
2-Butanone	ND		ug/Kg	98	0.98	396056	02/22/26	02/22/26	LYZ
cis-1,2-Dichloroethene	ND		ug/Kg	4.9	0.98	396056	02/22/26	02/22/26	LYZ
2,2-Dichloropropane	ND		ug/Kg	4.9	0.98	396056	02/22/26	02/22/26	LYZ
Chloroform	ND		ug/Kg	4.9	0.98	396056	02/22/26	02/22/26	LYZ
Bromochloromethane	ND		ug/Kg	4.9	0.98	396056	02/22/26	02/22/26	LYZ
1,1,1-Trichloroethane	ND		ug/Kg	4.9	0.98	396056	02/22/26	02/22/26	LYZ
1,1-Dichloropropene	ND		ug/Kg	4.9	0.98	396056	02/22/26	02/22/26	LYZ
Carbon Tetrachloride	ND		ug/Kg	4.9	0.98	396056	02/22/26	02/22/26	LYZ
1,2-Dichloroethane	ND		ug/Kg	4.9	0.98	396056	02/22/26	02/22/26	LYZ
Benzene	ND		ug/Kg	4.9	0.98	396056	02/22/26	02/22/26	LYZ
Trichloroethene	ND		ug/Kg	4.9	0.98	396056	02/22/26	02/22/26	LYZ
1,2-Dichloropropane	ND		ug/Kg	4.9	0.98	396056	02/22/26	02/22/26	LYZ
Bromodichloromethane	ND		ug/Kg	4.9	0.98	396056	02/22/26	02/22/26	LYZ
Dibromomethane	ND		ug/Kg	4.9	0.98	396056	02/22/26	02/22/26	LYZ
4-Methyl-2-Pentanone	ND		ug/Kg	4.9	0.98	396056	02/22/26	02/22/26	LYZ
cis-1,3-Dichloropropene	ND		ug/Kg	4.9	0.98	396056	02/22/26	02/22/26	LYZ
Toluene	ND		ug/Kg	4.9	0.98	396056	02/22/26	02/22/26	LYZ
trans-1,3-Dichloropropene	ND		ug/Kg	4.9	0.98	396056	02/22/26	02/22/26	LYZ
1,1,2-Trichloroethane	ND		ug/Kg	4.9	0.98	396056	02/22/26	02/22/26	LYZ
1,3-Dichloropropane	ND		ug/Kg	4.9	0.98	396056	02/22/26	02/22/26	LYZ
Tetrachloroethene	ND		ug/Kg	4.9	0.98	396056	02/22/26	02/22/26	LYZ
Dibromochloromethane	ND		ug/Kg	4.9	0.98	396056	02/22/26	02/22/26	LYZ
1,2-Dibromoethane	ND		ug/Kg	4.9	0.98	396056	02/22/26	02/22/26	LYZ
Chlorobenzene	ND		ug/Kg	4.9	0.98	396056	02/22/26	02/22/26	LYZ
1,1,1,2-Tetrachloroethane	ND		ug/Kg	4.9	0.98	396056	02/22/26	02/22/26	LYZ
Ethylbenzene	ND		ug/Kg	4.9	0.98	396056	02/22/26	02/22/26	LYZ
m,p-Xylenes	ND		ug/Kg	9.8	0.98	396056	02/22/26	02/22/26	LYZ
o-Xylene	ND		ug/Kg	4.9	0.98	396056	02/22/26	02/22/26	LYZ
Styrene	ND		ug/Kg	4.9	0.98	396056	02/22/26	02/22/26	LYZ
Bromoform	ND		ug/Kg	4.9	0.98	396056	02/22/26	02/22/26	LYZ
Isopropylbenzene	ND		ug/Kg	4.9	0.98	396056	02/22/26	02/22/26	LYZ
1,1,2,2-Tetrachloroethane	ND		ug/Kg	4.9	0.98	396056	02/22/26	02/22/26	LYZ
1,2,3-Trichloropropane	ND		ug/Kg	4.9	0.98	396056	02/22/26	02/22/26	LYZ
Propylbenzene	ND		ug/Kg	4.9	0.98	396056	02/22/26	02/22/26	LYZ
Bromobenzene	ND		ug/Kg	4.9	0.98	396056	02/22/26	02/22/26	LYZ
1,3,5-Trimethylbenzene	ND		ug/Kg	4.9	0.98	396056	02/22/26	02/22/26	LYZ
2-Chlorotoluene	ND		ug/Kg	4.9	0.98	396056	02/22/26	02/22/26	LYZ
4-Chlorotoluene	ND		ug/Kg	4.9	0.98	396056	02/22/26	02/22/26	LYZ
tert-Butylbenzene	ND		ug/Kg	4.9	0.98	396056	02/22/26	02/22/26	LYZ
1,2,4-Trimethylbenzene	ND		ug/Kg	4.9	0.98	396056	02/22/26	02/22/26	LYZ
sec-Butylbenzene	ND		ug/Kg	4.9	0.98	396056	02/22/26	02/22/26	LYZ
para-Isopropyl Toluene	ND		ug/Kg	4.9	0.98	396056	02/22/26	02/22/26	LYZ
1,3-Dichlorobenzene	ND		ug/Kg	4.9	0.98	396056	02/22/26	02/22/26	LYZ
1,4-Dichlorobenzene	ND		ug/Kg	4.9	0.98	396056	02/22/26	02/22/26	LYZ
n-Butylbenzene	ND		ug/Kg	4.9	0.98	396056	02/22/26	02/22/26	LYZ
1,2-Dichlorobenzene	ND		ug/Kg	4.9	0.98	396056	02/22/26	02/22/26	LYZ
1,2-Dibromo-3-Chloropropane	ND		ug/Kg	4.9	0.98	396056	02/22/26	02/22/26	LYZ
1,2,4-Trichlorobenzene	ND		ug/Kg	4.9	0.98	396056	02/22/26	02/22/26	LYZ
Hexachlorobutadiene	ND		ug/Kg	4.9	0.98	396056	02/22/26	02/22/26	LYZ
Naphthalene	ND		ug/Kg	4.9	0.98	396056	02/22/26	02/22/26	LYZ
1,2,3-Trichlorobenzene	ND		ug/Kg	4.9	0.98	396056	02/22/26	02/22/26	LYZ
Xylene (total)	ND		ug/Kg	4.9	0.98	396056	02/22/26	02/22/26	LYZ

Results for any subcontracted analyses are not included in this section.

Analysis Results for 553922

553922-004 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Surrogates				**Limits**					
Dibromofluoromethane	101%		%REC	70-130	0.98	396056	02/22/26	02/22/26	LYZ
1,2-Dichloroethane-d4	98%		%REC	70-130	0.98	396056	02/22/26	02/22/26	LYZ
Toluene-d8	97%		%REC	70-130	0.98	396056	02/22/26	02/22/26	LYZ
Bromofluorobenzene	97%		%REC	70-130	0.98	396056	02/22/26	02/22/26	LYZ

Results for any subcontracted analyses are not included in this section.

ENTHALPY ANALYTICAL

Analysis Results for 553922

Sample ID: DUP-02-0.5-260220	Lab ID: 553922-007	Collected: 02/20/26
	Matrix: Soil	

553922-007 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6020 Prep Method: EPA 3050B									
Antimony	ND		mg/Kg	0.98	0.98	396206	02/24/26	02/25/26	KCD
Arsenic	**3.4**		mg/Kg	0.98	0.98	396206	02/24/26	02/25/26	KCD
Barium	**130**		mg/Kg	0.98	0.98	396206	02/24/26	02/25/26	KCD
Beryllium	ND		mg/Kg	0.98	0.98	396206	02/24/26	02/25/26	KCD
Cadmium	ND		mg/Kg	0.49	0.98	396206	02/24/26	02/25/26	KCD
Chromium	**20**		mg/Kg	2.0	0.98	396206	02/24/26	02/25/26	KCD
Cobalt	**8.6**		mg/Kg	0.98	0.98	396206	02/24/26	02/25/26	KCD
Copper	**35**		mg/Kg	2.0	0.98	396206	02/24/26	02/25/26	KCD
Lead	**33**		mg/Kg	0.98	0.98	396206	02/24/26	02/25/26	KCD
Molybdenum	ND		mg/Kg	0.98	0.98	396206	02/24/26	02/25/26	KCD
Nickel	**16**		mg/Kg	0.98	0.98	396206	02/24/26	02/25/26	KCD
Selenium	ND		mg/Kg	3.9	0.98	396206	02/24/26	02/25/26	KCD
Silver	ND		mg/Kg	0.49	0.98	396206	02/24/26	02/25/26	KCD
Thallium	ND		mg/Kg	0.98	0.98	396206	02/24/26	02/25/26	KCD
Vanadium	**44**		mg/Kg	2.0	0.98	396206	02/24/26	02/25/26	KCD
Zinc	**100**		mg/Kg	9.8	0.98	396206	02/24/26	02/25/26	KCD
Method: EPA 7471A Prep Method: EPA 7471A									
Mercury	ND		mg/Kg	0.16	1.2	396198	02/24/26	02/24/26	MLL
Method: EPA 8015B Prep Method: EPA 5035									
TPH Gasoline	ND		mg/Kg	2.9	0.97	396469	02/26/26	02/26/26	SXR
Surrogates				**Limits**					
Bromofluorobenzene (FID)	64%		%REC	59-122	0.97	396469	02/26/26	02/26/26	SXR
Method: EPA 8015M Prep Method: EPA 3580M									
GRO C8-C10	ND		mg/Kg	50	5	396457	02/25/26	02/26/26	NXY
DRO C10-C28	**200**		mg/Kg	50	5	396457	02/25/26	02/26/26	NXY
ORO C28-C44	**350**		mg/Kg	99	5	396457	02/25/26	02/26/26	NXY
Surrogates				**Limits**					
n-Triacontane	126%		%REC	59-136	5	396457	02/25/26	02/26/26	NXY
Method: EPA 8260B Prep Method: EPA 5035									
3-Chloropropene	ND		ug/Kg	7.9	1.6	396056	02/22/26	02/22/26	LYZ
cis-1,4-Dichloro-2-butene	ND		ug/Kg	7.9	1.6	396056	02/22/26	02/22/26	LYZ
trans-1,4-Dichloro-2-butene	ND		ug/Kg	7.9	1.6	396056	02/22/26	02/22/26	LYZ
Freon 12	ND		ug/Kg	7.9	1.6	396056	02/22/26	02/22/26	LYZ
Chloromethane	ND		ug/Kg	7.9	1.6	396056	02/22/26	02/22/26	LYZ
Vinyl Chloride	ND		ug/Kg	7.9	1.6	396056	02/22/26	02/22/26	LYZ
Bromomethane	ND		ug/Kg	7.9	1.6	396056	02/22/26	02/22/26	LYZ
Chloroethane	ND		ug/Kg	7.9	1.6	396056	02/22/26	02/22/26	LYZ
Trichlorofluoromethane	ND		ug/Kg	7.9	1.6	396056	02/22/26	02/22/26	LYZ
Acetone	ND		ug/Kg	160	1.6	396056	02/22/26	02/22/26	LYZ
Freon 113	ND		ug/Kg	7.9	1.6	396056	02/22/26	02/22/26	LYZ
1,1-Dichloroethene	ND		ug/Kg	7.9	1.6	396056	02/22/26	02/22/26	LYZ

Results for any subcontracted analyses are not included in this section.

ENTHALPY ANALYTICAL

Analysis Results for 553922

553922-007 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Methylene Chloride	ND		ug/Kg	7.9	1.6	396056	02/22/26	02/22/26	LYZ
MTBE	ND		ug/Kg	7.9	1.6	396056	02/22/26	02/22/26	LYZ
trans-1,2-Dichloroethene	ND		ug/Kg	7.9	1.6	396056	02/22/26	02/22/26	LYZ
1,1-Dichloroethane	ND		ug/Kg	7.9	1.6	396056	02/22/26	02/22/26	LYZ
2-Butanone	ND		ug/Kg	160	1.6	396056	02/22/26	02/22/26	LYZ
cis-1,2-Dichloroethene	ND		ug/Kg	7.9	1.6	396056	02/22/26	02/22/26	LYZ
2,2-Dichloropropane	ND		ug/Kg	7.9	1.6	396056	02/22/26	02/22/26	LYZ
Chloroform	ND		ug/Kg	7.9	1.6	396056	02/22/26	02/22/26	LYZ
Bromochloromethane	ND		ug/Kg	7.9	1.6	396056	02/22/26	02/22/26	LYZ
1,1,1-Trichloroethane	ND		ug/Kg	7.9	1.6	396056	02/22/26	02/22/26	LYZ
1,1-Dichloropropene	ND		ug/Kg	7.9	1.6	396056	02/22/26	02/22/26	LYZ
Carbon Tetrachloride	ND		ug/Kg	7.9	1.6	396056	02/22/26	02/22/26	LYZ
1,2-Dichloroethane	ND		ug/Kg	7.9	1.6	396056	02/22/26	02/22/26	LYZ
Benzene	ND		ug/Kg	7.9	1.6	396056	02/22/26	02/22/26	LYZ
Trichloroethene	ND		ug/Kg	7.9	1.6	396056	02/22/26	02/22/26	LYZ
1,2-Dichloropropane	ND		ug/Kg	7.9	1.6	396056	02/22/26	02/22/26	LYZ
Bromodichloromethane	ND		ug/Kg	7.9	1.6	396056	02/22/26	02/22/26	LYZ
Dibromomethane	ND		ug/Kg	7.9	1.6	396056	02/22/26	02/22/26	LYZ
4-Methyl-2-Pentanone	ND		ug/Kg	7.9	1.6	396056	02/22/26	02/22/26	LYZ
cis-1,3-Dichloropropene	ND		ug/Kg	7.9	1.6	396056	02/22/26	02/22/26	LYZ
Toluene	ND		ug/Kg	7.9	1.6	396056	02/22/26	02/22/26	LYZ
trans-1,3-Dichloropropene	ND		ug/Kg	7.9	1.6	396056	02/22/26	02/22/26	LYZ
1,1,2-Trichloroethane	ND		ug/Kg	7.9	1.6	396056	02/22/26	02/22/26	LYZ
1,3-Dichloropropane	ND		ug/Kg	7.9	1.6	396056	02/22/26	02/22/26	LYZ
Tetrachloroethene	ND		ug/Kg	7.9	1.6	396056	02/22/26	02/22/26	LYZ
Dibromochloromethane	ND		ug/Kg	7.9	1.6	396056	02/22/26	02/22/26	LYZ
1,2-Dibromoethane	ND		ug/Kg	7.9	1.6	396056	02/22/26	02/22/26	LYZ
Chlorobenzene	ND		ug/Kg	7.9	1.6	396056	02/22/26	02/22/26	LYZ
1,1,1,2-Tetrachloroethane	ND		ug/Kg	7.9	1.6	396056	02/22/26	02/22/26	LYZ
Ethylbenzene	ND		ug/Kg	7.9	1.6	396056	02/22/26	02/22/26	LYZ
m,p-Xylenes	ND		ug/Kg	16	1.6	396056	02/22/26	02/22/26	LYZ
o-Xylene	ND		ug/Kg	7.9	1.6	396056	02/22/26	02/22/26	LYZ
Styrene	ND		ug/Kg	7.9	1.6	396056	02/22/26	02/22/26	LYZ
Bromoform	ND		ug/Kg	7.9	1.6	396056	02/22/26	02/22/26	LYZ
Isopropylbenzene	ND		ug/Kg	7.9	1.6	396056	02/22/26	02/22/26	LYZ
1,1,2,2-Tetrachloroethane	ND		ug/Kg	7.9	1.6	396056	02/22/26	02/22/26	LYZ
1,2,3-Trichloropropane	ND		ug/Kg	7.9	1.6	396056	02/22/26	02/22/26	LYZ
Propylbenzene	ND		ug/Kg	7.9	1.6	396056	02/22/26	02/22/26	LYZ
Bromobenzene	ND		ug/Kg	7.9	1.6	396056	02/22/26	02/22/26	LYZ
1,3,5-Trimethylbenzene	ND		ug/Kg	7.9	1.6	396056	02/22/26	02/22/26	LYZ
2-Chlorotoluene	ND		ug/Kg	7.9	1.6	396056	02/22/26	02/22/26	LYZ
4-Chlorotoluene	ND		ug/Kg	7.9	1.6	396056	02/22/26	02/22/26	LYZ
tert-Butylbenzene	ND		ug/Kg	7.9	1.6	396056	02/22/26	02/22/26	LYZ
1,2,4-Trimethylbenzene	ND		ug/Kg	7.9	1.6	396056	02/22/26	02/22/26	LYZ
sec-Butylbenzene	ND		ug/Kg	7.9	1.6	396056	02/22/26	02/22/26	LYZ
para-Isopropyl Toluene	ND		ug/Kg	7.9	1.6	396056	02/22/26	02/22/26	LYZ
1,3-Dichlorobenzene	ND		ug/Kg	7.9	1.6	396056	02/22/26	02/22/26	LYZ
1,4-Dichlorobenzene	ND		ug/Kg	7.9	1.6	396056	02/22/26	02/22/26	LYZ
n-Butylbenzene	ND		ug/Kg	7.9	1.6	396056	02/22/26	02/22/26	LYZ
1,2-Dichlorobenzene	ND		ug/Kg	7.9	1.6	396056	02/22/26	02/22/26	LYZ
1,2-Dibromo-3-Chloropropane	ND		ug/Kg	7.9	1.6	396056	02/22/26	02/22/26	LYZ
1,2,4-Trichlorobenzene	ND		ug/Kg	7.9	1.6	396056	02/22/26	02/22/26	LYZ

Results for any subcontracted analyses are not included in this section.

ENTHALPY ANALYTICAL

Analysis Results for 553922

553922-007 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Hexachlorobutadiene	ND		ug/Kg	7.9	1.6	396056	02/22/26	02/22/26	LYZ
Naphthalene	ND		ug/Kg	7.9	1.6	396056	02/22/26	02/22/26	LYZ
1,2,3-Trichlorobenzene	ND		ug/Kg	7.9	1.6	396056	02/22/26	02/22/26	LYZ
Xylene (total)	ND		ug/Kg	7.9	1.6	396056	02/22/26	02/22/26	LYZ
Surrogates				**Limits**					
Dibromofluoromethane	102%		%REC	70-130	1.6	396056	02/22/26	02/22/26	LYZ
1,2-Dichloroethane-d4	97%		%REC	70-130	1.6	396056	02/22/26	02/22/26	LYZ
Toluene-d8	97%		%REC	70-130	1.6	396056	02/22/26	02/22/26	LYZ
Bromofluorobenzene	99%		%REC	70-130	1.6	396056	02/22/26	02/22/26	LYZ

Results for any subcontracted analyses are not included in this section.

ENTHALPY ANALYTICAL

Analysis Results for 553922

Sample ID: AOC5-SB-03-0.5	Lab ID: 553922-010	Collected: 02/20/26 10:48
	Matrix: Soil	

553922-010 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3050B									
Lead	**6.8**		mg/Kg	1.0	1	396187	02/23/26	02/24/26	TWJ
Method: EPA 8015B Prep Method: EPA 5035									
TPH Gasoline	ND		mg/Kg	2.5	0.84	396469	02/26/26	02/26/26	SXR
Surrogates				**Limits**					
Bromofluorobenzene (FID)	89%		%REC	59-122	0.84	396469	02/26/26	02/26/26	SXR
Method: EPA 8015M Prep Method: EPA 3580M									
GRO C8-C10	ND		mg/Kg	9.9	0.99	396457	02/25/26	02/26/26	NXY
DRO C10-C28	ND		mg/Kg	9.9	0.99	396457	02/25/26	02/26/26	NXY
ORO C28-C44	ND		mg/Kg	20	0.99	396457	02/25/26	02/26/26	NXY
Surrogates				**Limits**					
n-Triacontane	88%		%REC	59-136	0.99	396457	02/25/26	02/26/26	NXY
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	50	0.99	396467	02/26/26	02/27/26	XLY
Aroclor-1221	ND		ug/Kg	50	0.99	396467	02/26/26	02/27/26	XLY
Aroclor-1232	ND		ug/Kg	50	0.99	396467	02/26/26	02/27/26	XLY
Aroclor-1242	ND		ug/Kg	50	0.99	396467	02/26/26	02/27/26	XLY
Aroclor-1248	ND		ug/Kg	50	0.99	396467	02/26/26	02/27/26	XLY
Aroclor-1254	ND		ug/Kg	50	0.99	396467	02/26/26	02/27/26	XLY
Aroclor-1260	ND		ug/Kg	50	0.99	396467	02/26/26	02/27/26	XLY
Aroclor-1262	ND		ug/Kg	50	0.99	396467	02/26/26	02/27/26	XLY
Aroclor-1268	ND		ug/Kg	50	0.99	396467	02/26/26	02/27/26	XLY
Total PCBs	ND		ug/Kg	50	0.99	396467	02/26/26	02/27/26	XLY
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	100%		%REC	50-127	0.99	396467	02/26/26	02/27/26	XLY
Method: EPA 8260B Prep Method: EPA 5035									
3-Chloropropene	ND		ug/Kg	4.0	0.81	396056	02/22/26	02/22/26	LYZ
cis-1,4-Dichloro-2-butene	ND		ug/Kg	4.0	0.81	396056	02/22/26	02/22/26	LYZ
trans-1,4-Dichloro-2-butene	ND		ug/Kg	4.0	0.81	396056	02/22/26	02/22/26	LYZ
Freon 12	ND		ug/Kg	4.0	0.81	396056	02/22/26	02/22/26	LYZ
Chloromethane	ND		ug/Kg	4.0	0.81	396056	02/22/26	02/22/26	LYZ
Vinyl Chloride	ND		ug/Kg	4.0	0.81	396056	02/22/26	02/22/26	LYZ
Bromomethane	ND		ug/Kg	4.0	0.81	396056	02/22/26	02/22/26	LYZ
Chloroethane	ND		ug/Kg	4.0	0.81	396056	02/22/26	02/22/26	LYZ
Trichlorofluoromethane	ND		ug/Kg	4.0	0.81	396056	02/22/26	02/22/26	LYZ
Acetone	ND		ug/Kg	81	0.81	396056	02/22/26	02/22/26	LYZ
Freon 113	ND		ug/Kg	4.0	0.81	396056	02/22/26	02/22/26	LYZ
1,1-Dichloroethene	ND		ug/Kg	4.0	0.81	396056	02/22/26	02/22/26	LYZ
Methylene Chloride	ND		ug/Kg	4.0	0.81	396056	02/22/26	02/22/26	LYZ
MTBE	ND		ug/Kg	4.0	0.81	396056	02/22/26	02/22/26	LYZ
trans-1,2-Dichloroethene	ND		ug/Kg	4.0	0.81	396056	02/22/26	02/22/26	LYZ
1,1-Dichloroethane	ND		ug/Kg	4.0	0.81	396056	02/22/26	02/22/26	LYZ

Results for any subcontracted analyses are not included in this section.

ENTHALPY ANALYTICAL

Analysis Results for 553922

553922-010 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
2-Butanone	ND		ug/Kg	81	0.81	396056	02/22/26	02/22/26	LYZ
cis-1,2-Dichloroethene	ND		ug/Kg	4.0	0.81	396056	02/22/26	02/22/26	LYZ
2,2-Dichloropropane	ND		ug/Kg	4.0	0.81	396056	02/22/26	02/22/26	LYZ
Chloroform	ND		ug/Kg	4.0	0.81	396056	02/22/26	02/22/26	LYZ
Bromochloromethane	ND		ug/Kg	4.0	0.81	396056	02/22/26	02/22/26	LYZ
1,1,1-Trichloroethane	ND		ug/Kg	4.0	0.81	396056	02/22/26	02/22/26	LYZ
1,1-Dichloropropene	ND		ug/Kg	4.0	0.81	396056	02/22/26	02/22/26	LYZ
Carbon Tetrachloride	ND		ug/Kg	4.0	0.81	396056	02/22/26	02/22/26	LYZ
1,2-Dichloroethane	ND		ug/Kg	4.0	0.81	396056	02/22/26	02/22/26	LYZ
Benzene	ND		ug/Kg	4.0	0.81	396056	02/22/26	02/22/26	LYZ
Trichloroethene	ND		ug/Kg	4.0	0.81	396056	02/22/26	02/22/26	LYZ
1,2-Dichloropropane	ND		ug/Kg	4.0	0.81	396056	02/22/26	02/22/26	LYZ
Bromodichloromethane	ND		ug/Kg	4.0	0.81	396056	02/22/26	02/22/26	LYZ
Dibromomethane	ND		ug/Kg	4.0	0.81	396056	02/22/26	02/22/26	LYZ
4-Methyl-2-Pentanone	ND		ug/Kg	4.0	0.81	396056	02/22/26	02/22/26	LYZ
cis-1,3-Dichloropropene	ND		ug/Kg	4.0	0.81	396056	02/22/26	02/22/26	LYZ
Toluene	ND		ug/Kg	4.0	0.81	396056	02/22/26	02/22/26	LYZ
trans-1,3-Dichloropropene	ND		ug/Kg	4.0	0.81	396056	02/22/26	02/22/26	LYZ
1,1,2-Trichloroethane	ND		ug/Kg	4.0	0.81	396056	02/22/26	02/22/26	LYZ
1,3-Dichloropropane	ND		ug/Kg	4.0	0.81	396056	02/22/26	02/22/26	LYZ
Tetrachloroethene	ND		ug/Kg	4.0	0.81	396056	02/22/26	02/22/26	LYZ
Dibromochloromethane	ND		ug/Kg	4.0	0.81	396056	02/22/26	02/22/26	LYZ
1,2-Dibromoethane	ND		ug/Kg	4.0	0.81	396056	02/22/26	02/22/26	LYZ
Chlorobenzene	ND		ug/Kg	4.0	0.81	396056	02/22/26	02/22/26	LYZ
1,1,1,2-Tetrachloroethane	ND		ug/Kg	4.0	0.81	396056	02/22/26	02/22/26	LYZ
Ethylbenzene	ND		ug/Kg	4.0	0.81	396056	02/22/26	02/22/26	LYZ
m,p-Xylenes	ND		ug/Kg	8.1	0.81	396056	02/22/26	02/22/26	LYZ
o-Xylene	ND		ug/Kg	4.0	0.81	396056	02/22/26	02/22/26	LYZ
Styrene	ND		ug/Kg	4.0	0.81	396056	02/22/26	02/22/26	LYZ
Bromoform	ND		ug/Kg	4.0	0.81	396056	02/22/26	02/22/26	LYZ
Isopropylbenzene	ND		ug/Kg	4.0	0.81	396056	02/22/26	02/22/26	LYZ
1,1,2,2-Tetrachloroethane	ND		ug/Kg	4.0	0.81	396056	02/22/26	02/22/26	LYZ
1,2,3-Trichloropropane	ND		ug/Kg	4.0	0.81	396056	02/22/26	02/22/26	LYZ
Propylbenzene	ND		ug/Kg	4.0	0.81	396056	02/22/26	02/22/26	LYZ
Bromobenzene	ND		ug/Kg	4.0	0.81	396056	02/22/26	02/22/26	LYZ
1,3,5-Trimethylbenzene	ND		ug/Kg	4.0	0.81	396056	02/22/26	02/22/26	LYZ
2-Chlorotoluene	ND		ug/Kg	4.0	0.81	396056	02/22/26	02/22/26	LYZ
4-Chlorotoluene	ND		ug/Kg	4.0	0.81	396056	02/22/26	02/22/26	LYZ
tert-Butylbenzene	ND		ug/Kg	4.0	0.81	396056	02/22/26	02/22/26	LYZ
1,2,4-Trimethylbenzene	ND		ug/Kg	4.0	0.81	396056	02/22/26	02/22/26	LYZ
sec-Butylbenzene	ND		ug/Kg	4.0	0.81	396056	02/22/26	02/22/26	LYZ
para-Isopropyl Toluene	ND		ug/Kg	4.0	0.81	396056	02/22/26	02/22/26	LYZ
1,3-Dichlorobenzene	ND		ug/Kg	4.0	0.81	396056	02/22/26	02/22/26	LYZ
1,4-Dichlorobenzene	ND		ug/Kg	4.0	0.81	396056	02/22/26	02/22/26	LYZ
n-Butylbenzene	ND		ug/Kg	4.0	0.81	396056	02/22/26	02/22/26	LYZ
1,2-Dichlorobenzene	ND		ug/Kg	4.0	0.81	396056	02/22/26	02/22/26	LYZ
1,2-Dibromo-3-Chloropropane	ND		ug/Kg	4.0	0.81	396056	02/22/26	02/22/26	LYZ
1,2,4-Trichlorobenzene	ND		ug/Kg	4.0	0.81	396056	02/22/26	02/22/26	LYZ
Hexachlorobutadiene	ND		ug/Kg	4.0	0.81	396056	02/22/26	02/22/26	LYZ
Naphthalene	ND		ug/Kg	4.0	0.81	396056	02/22/26	02/22/26	LYZ
1,2,3-Trichlorobenzene	ND		ug/Kg	4.0	0.81	396056	02/22/26	02/22/26	LYZ
Xylene (total)	ND		ug/Kg	4.0	0.81	396056	02/22/26	02/22/26	LYZ

Results for any subcontracted analyses are not included in this section.

ENTHALPY ANALYTICAL

Analysis Results for 553922

553922-010 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Surrogates				**Limits**					
Dibromofluoromethane	103%		%REC	70-130	0.81	396056	02/22/26	02/22/26	LYZ
1,2-Dichloroethane-d4	100%		%REC	70-130	0.81	396056	02/22/26	02/22/26	LYZ
Toluene-d8	95%		%REC	70-130	0.81	396056	02/22/26	02/22/26	LYZ
Bromofluorobenzene	98%		%REC	70-130	0.81	396056	02/22/26	02/22/26	LYZ

Sample ID: AOC5-SB-05-0.5 **Lab ID: 553922-013** **Collected: 02/20/26 13:57**
Matrix: Soil

553922-013 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3050B									
Lead	**21**		mg/Kg	0.95	0.95	396187	02/23/26	02/24/26	TWJ
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	49	0.98	396467	02/26/26	02/27/26	XLY
Aroclor-1221	ND		ug/Kg	49	0.98	396467	02/26/26	02/27/26	XLY
Aroclor-1232	ND		ug/Kg	49	0.98	396467	02/26/26	02/27/26	XLY
Aroclor-1242	ND		ug/Kg	49	0.98	396467	02/26/26	02/27/26	XLY
Aroclor-1248	ND		ug/Kg	49	0.98	396467	02/26/26	02/27/26	XLY
Aroclor-1254	ND		ug/Kg	49	0.98	396467	02/26/26	02/27/26	XLY
Aroclor-1260	ND		ug/Kg	49	0.98	396467	02/26/26	02/27/26	XLY
Aroclor-1262	ND		ug/Kg	49	0.98	396467	02/26/26	02/27/26	XLY
Aroclor-1268	ND		ug/Kg	49	0.98	396467	02/26/26	02/27/26	XLY
Total PCBs	ND		ug/Kg	49	0.98	396467	02/26/26	02/27/26	XLY
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	107%		%REC	50-127	0.98	396467	02/26/26	02/27/26	XLY

Sample ID: DUP-03-0.5-260220 **Lab ID: 553922-015** **Collected: 02/20/26**
Matrix: Soil

553922-015 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3050B									
Lead	**39**		mg/Kg	0.95	0.95	396187	02/23/26	02/24/26	TWJ
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	50	1	396467	02/26/26	02/27/26	XLY
Aroclor-1221	ND		ug/Kg	50	1	396467	02/26/26	02/27/26	XLY
Aroclor-1232	ND		ug/Kg	50	1	396467	02/26/26	02/27/26	XLY
Aroclor-1242	ND		ug/Kg	50	1	396467	02/26/26	02/27/26	XLY
Aroclor-1248	ND		ug/Kg	50	1	396467	02/26/26	02/27/26	XLY
Aroclor-1254	ND		ug/Kg	50	1	396467	02/26/26	02/27/26	XLY
Aroclor-1260	ND		ug/Kg	50	1	396467	02/26/26	02/27/26	XLY
Aroclor-1262	ND		ug/Kg	50	1	396467	02/26/26	02/27/26	XLY
Aroclor-1268	ND		ug/Kg	50	1	396467	02/26/26	02/27/26	XLY
Total PCBs	ND		ug/Kg	50	1	396467	02/26/26	02/27/26	XLY
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	109%		%REC	50-127	1	396467	02/26/26	02/27/26	XLY

Results for any subcontracted analyses are not included in this section.

Analysis Results for 553922

Sample ID: AOC5-SB-06-0.5	Lab ID: 553922-017	Collected: 02/20/26 14:12
	Matrix: Soil	

553922-017 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3050B									
Lead	**48**		mg/Kg	0.96	0.96	396187	02/23/26	02/24/26	TWJ
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	49	0.98	396467	02/26/26	02/27/26	XLY
Aroclor-1221	ND		ug/Kg	49	0.98	396467	02/26/26	02/27/26	XLY
Aroclor-1232	ND		ug/Kg	49	0.98	396467	02/26/26	02/27/26	XLY
Aroclor-1242	ND		ug/Kg	49	0.98	396467	02/26/26	02/27/26	XLY
Aroclor-1248	ND		ug/Kg	49	0.98	396467	02/26/26	02/27/26	XLY
Aroclor-1254	ND		ug/Kg	49	0.98	396467	02/26/26	02/27/26	XLY
Aroclor-1260	ND		ug/Kg	49	0.98	396467	02/26/26	02/27/26	XLY
Aroclor-1262	ND		ug/Kg	49	0.98	396467	02/26/26	02/27/26	XLY
Aroclor-1268	ND		ug/Kg	49	0.98	396467	02/26/26	02/27/26	XLY
Total PCBs	ND		ug/Kg	49	0.98	396467	02/26/26	02/27/26	XLY
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	107%		%REC	50-127	0.98	396467	02/26/26	02/27/26	XLY

Sample ID: AOC4-SB-46-0.5	Lab ID: 553922-019	Collected: 02/20/26 07:33
	Matrix: Soil	

553922-019 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3050B									
Lead	**81**		mg/Kg	0.99	0.99	396187	02/23/26	02/24/26	TWJ
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	50	1	396467	02/26/26	02/27/26	XLY
Aroclor-1221	ND		ug/Kg	50	1	396467	02/26/26	02/27/26	XLY
Aroclor-1232	ND		ug/Kg	50	1	396467	02/26/26	02/27/26	XLY
Aroclor-1242	ND		ug/Kg	50	1	396467	02/26/26	02/27/26	XLY
Aroclor-1248	ND		ug/Kg	50	1	396467	02/26/26	02/27/26	XLY
Aroclor-1254	ND		ug/Kg	50	1	396467	02/26/26	02/27/26	XLY
Aroclor-1260	ND		ug/Kg	50	1	396467	02/26/26	02/27/26	XLY
Aroclor-1262	ND		ug/Kg	50	1	396467	02/26/26	02/27/26	XLY
Aroclor-1268	ND		ug/Kg	50	1	396467	02/26/26	02/27/26	XLY
Total PCBs	ND		ug/Kg	50	1	396467	02/26/26	02/27/26	XLY
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	105%		%REC	50-127	1	396467	02/26/26	02/27/26	XLY

Results for any subcontracted analyses are not included in this section.

ENTHALPY ANALYTICAL

Analysis Results for 553922

Sample ID: AOC4-SB-47-0.5	Lab ID: 553922-020	Collected: 02/20/26 07:41
	Matrix: Soil	

553922-020 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3050B									
Lead	**32**		mg/Kg	1.0	1	396187	02/23/26	02/24/26	TWJ
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	49	0.99	396467	02/26/26	02/27/26	XLY
Aroclor-1221	ND		ug/Kg	49	0.99	396467	02/26/26	02/27/26	XLY
Aroclor-1232	ND		ug/Kg	49	0.99	396467	02/26/26	02/27/26	XLY
Aroclor-1242	ND		ug/Kg	49	0.99	396467	02/26/26	02/27/26	XLY
Aroclor-1248	ND		ug/Kg	49	0.99	396467	02/26/26	02/27/26	XLY
Aroclor-1254	ND		ug/Kg	49	0.99	396467	02/26/26	02/27/26	XLY
Aroclor-1260	ND		ug/Kg	49	0.99	396467	02/26/26	02/27/26	XLY
Aroclor-1262	ND		ug/Kg	49	0.99	396467	02/26/26	02/27/26	XLY
Aroclor-1268	ND		ug/Kg	49	0.99	396467	02/26/26	02/27/26	XLY
Total PCBs	ND		ug/Kg	49	0.99	396467	02/26/26	02/27/26	XLY
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	94%		%REC	50-127	0.99	396467	02/26/26	02/27/26	XLY

Sample ID: AOC4-SB-48-0.5	Lab ID: 553922-021	Collected: 02/20/26 07:52
	Matrix: Soil	

553922-021 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3050B									
Lead	**33**		mg/Kg	0.98	0.98	396187	02/23/26	02/24/26	TWJ
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	51	1	396467	02/26/26	02/27/26	XLY
Aroclor-1221	ND		ug/Kg	51	1	396467	02/26/26	02/27/26	XLY
Aroclor-1232	ND		ug/Kg	51	1	396467	02/26/26	02/27/26	XLY
Aroclor-1242	ND		ug/Kg	51	1	396467	02/26/26	02/27/26	XLY
Aroclor-1248	ND		ug/Kg	51	1	396467	02/26/26	02/27/26	XLY
Aroclor-1254	ND		ug/Kg	51	1	396467	02/26/26	02/27/26	XLY
Aroclor-1260	ND		ug/Kg	51	1	396467	02/26/26	02/27/26	XLY
Aroclor-1262	ND		ug/Kg	51	1	396467	02/26/26	02/27/26	XLY
Aroclor-1268	ND		ug/Kg	51	1	396467	02/26/26	02/27/26	XLY
Total PCBs	ND		ug/Kg	51	1	396467	02/26/26	02/27/26	XLY
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	94%		%REC	50-127	1	396467	02/26/26	02/27/26	XLY

Sample ID: AOC4-SB-46-2.5	Lab ID: 553922-022	Collected: 02/20/26 07:38
	Matrix: Soil	

553922-022 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3050B									
Lead	**5.1**		mg/Kg	0.99	0.99	397934	03/13/26	03/13/26	SBW

Results for any subcontracted analyses are not included in this section.

ENTHALPY ANALYTICAL

Analysis Results for 553922

Sample ID: AOC4-SB-52-0.5	Lab ID: 553922-025	Collected: 02/20/26 09:15
	Matrix: Soil	

553922-025 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3050B									
Lead	**23**		mg/Kg	0.96	0.96	396187	02/23/26	02/24/26	TWJ
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	51	1	396467	02/26/26	02/27/26	XLY
Aroclor-1221	ND		ug/Kg	51	1	396467	02/26/26	02/27/26	XLY
Aroclor-1232	ND		ug/Kg	51	1	396467	02/26/26	02/27/26	XLY
Aroclor-1242	ND		ug/Kg	51	1	396467	02/26/26	02/27/26	XLY
Aroclor-1248	ND		ug/Kg	51	1	396467	02/26/26	02/27/26	XLY
Aroclor-1254	ND		ug/Kg	51	1	396467	02/26/26	02/27/26	XLY
Aroclor-1260	ND		ug/Kg	51	1	396467	02/26/26	02/27/26	XLY
Aroclor-1262	ND		ug/Kg	51	1	396467	02/26/26	02/27/26	XLY
Aroclor-1268	ND		ug/Kg	51	1	396467	02/26/26	02/27/26	XLY
Total PCBs	ND		ug/Kg	51	1	396467	02/26/26	02/27/26	XLY
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	110%		%REC	50-127	1	396467	02/26/26	02/27/26	XLY

Sample ID: AOC4-SB-53-0.5	Lab ID: 553922-026	Collected: 02/20/26 09:28
	Matrix: Soil	

553922-026 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3050B									
Lead	**70**		mg/Kg	1.0	1	396187	02/23/26	02/24/26	TWJ
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	50	1	396467	02/26/26	02/27/26	XLY
Aroclor-1221	ND		ug/Kg	50	1	396467	02/26/26	02/27/26	XLY
Aroclor-1232	ND		ug/Kg	50	1	396467	02/26/26	02/27/26	XLY
Aroclor-1242	ND		ug/Kg	50	1	396467	02/26/26	02/27/26	XLY
Aroclor-1248	ND		ug/Kg	50	1	396467	02/26/26	02/27/26	XLY
Aroclor-1254	ND		ug/Kg	50	1	396467	02/26/26	02/27/26	XLY
Aroclor-1260	ND		ug/Kg	50	1	396467	02/26/26	02/27/26	XLY
Aroclor-1262	ND		ug/Kg	50	1	396467	02/26/26	02/27/26	XLY
Aroclor-1268	ND		ug/Kg	50	1	396467	02/26/26	02/27/26	XLY
Total PCBs	ND		ug/Kg	50	1	396467	02/26/26	02/27/26	XLY
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	102%		%REC	50-127	1	396467	02/26/26	02/27/26	XLY

Results for any subcontracted analyses are not included in this section.

Analysis Results for 553922

Sample ID: AOC4-SB-54-0.5	Lab ID: 553922-027	Collected: 02/20/26 09:38
	Matrix: Soil	

553922-027 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3050B									
Lead	**30**		mg/Kg	0.98	0.98	396187	02/23/26	02/24/26	TWJ
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	50	0.99	396467	02/26/26	02/27/26	XLY
Aroclor-1221	ND		ug/Kg	50	0.99	396467	02/26/26	02/27/26	XLY
Aroclor-1232	ND		ug/Kg	50	0.99	396467	02/26/26	02/27/26	XLY
Aroclor-1242	ND		ug/Kg	50	0.99	396467	02/26/26	02/27/26	XLY
Aroclor-1248	ND		ug/Kg	50	0.99	396467	02/26/26	02/27/26	XLY
Aroclor-1254	ND		ug/Kg	50	0.99	396467	02/26/26	02/27/26	XLY
Aroclor-1260	ND		ug/Kg	50	0.99	396467	02/26/26	02/27/26	XLY
Aroclor-1262	ND		ug/Kg	50	0.99	396467	02/26/26	02/27/26	XLY
Aroclor-1268	ND		ug/Kg	50	0.99	396467	02/26/26	02/27/26	XLY
Total PCBs	ND		ug/Kg	50	0.99	396467	02/26/26	02/27/26	XLY
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	101%		%REC	50-127	0.99	396467	02/26/26	02/27/26	XLY

Sample ID: AOC4-SB-49-0.5	Lab ID: 553922-028	Collected: 02/20/26 08:00
	Matrix: Soil	

553922-028 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3050B									
Lead	**11**		mg/Kg	0.99	0.99	396187	02/23/26	02/24/26	TWJ
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	50	1	396467	02/26/26	02/27/26	XLY
Aroclor-1221	ND		ug/Kg	50	1	396467	02/26/26	02/27/26	XLY
Aroclor-1232	ND		ug/Kg	50	1	396467	02/26/26	02/27/26	XLY
Aroclor-1242	ND		ug/Kg	50	1	396467	02/26/26	02/27/26	XLY
Aroclor-1248	ND		ug/Kg	50	1	396467	02/26/26	02/27/26	XLY
Aroclor-1254	ND		ug/Kg	50	1	396467	02/26/26	02/27/26	XLY
Aroclor-1260	ND		ug/Kg	50	1	396467	02/26/26	02/27/26	XLY
Aroclor-1262	ND		ug/Kg	50	1	396467	02/26/26	02/27/26	XLY
Aroclor-1268	ND		ug/Kg	50	1	396467	02/26/26	02/27/26	XLY
Total PCBs	ND		ug/Kg	50	1	396467	02/26/26	02/27/26	XLY
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	101%		%REC	50-127	1	396467	02/26/26	02/27/26	XLY

Results for any subcontracted analyses are not included in this section.

ENTHALPY ANALYTICAL

Analysis Results for 553922

Sample ID: AOC4-SB-50-0.5	Lab ID: 553922-029	Collected: 02/20/26 08:38
	Matrix: Soil	

553922-029 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3050B									
Lead	**36**		mg/Kg	0.97	0.97	396187	02/23/26	02/24/26	TWJ
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	49	0.99	396467	02/26/26	02/27/26	XLY
Aroclor-1221	ND		ug/Kg	49	0.99	396467	02/26/26	02/27/26	XLY
Aroclor-1232	ND		ug/Kg	49	0.99	396467	02/26/26	02/27/26	XLY
Aroclor-1242	ND		ug/Kg	49	0.99	396467	02/26/26	02/27/26	XLY
Aroclor-1248	ND		ug/Kg	49	0.99	396467	02/26/26	02/27/26	XLY
Aroclor-1254	ND		ug/Kg	49	0.99	396467	02/26/26	02/27/26	XLY
Aroclor-1260	ND		ug/Kg	49	0.99	396467	02/26/26	02/27/26	XLY
Aroclor-1262	ND		ug/Kg	49	0.99	396467	02/26/26	02/27/26	XLY
Aroclor-1268	ND		ug/Kg	49	0.99	396467	02/26/26	02/27/26	XLY
Total PCBs	ND		ug/Kg	49	0.99	396467	02/26/26	02/27/26	XLY
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	105%		%REC	50-127	0.99	396467	02/26/26	02/27/26	XLY

Sample ID: AOC4-SB-51-0.5	Lab ID: 553922-030	Collected: 02/20/26 09:00
	Matrix: Soil	

553922-030 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3050B									
Lead	**23**		mg/Kg	1.0	1	396187	02/23/26	02/24/26	TWJ
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	50	1	396467	02/26/26	02/27/26	XLY
Aroclor-1221	ND		ug/Kg	50	1	396467	02/26/26	02/27/26	XLY
Aroclor-1232	ND		ug/Kg	50	1	396467	02/26/26	02/27/26	XLY
Aroclor-1242	ND		ug/Kg	50	1	396467	02/26/26	02/27/26	XLY
Aroclor-1248	ND		ug/Kg	50	1	396467	02/26/26	02/27/26	XLY
Aroclor-1254	ND		ug/Kg	50	1	396467	02/26/26	02/27/26	XLY
Aroclor-1260	ND		ug/Kg	50	1	396467	02/26/26	02/27/26	XLY
Aroclor-1262	ND		ug/Kg	50	1	396467	02/26/26	02/27/26	XLY
Aroclor-1268	ND		ug/Kg	50	1	396467	02/26/26	02/27/26	XLY
Total PCBs	ND		ug/Kg	50	1	396467	02/26/26	02/27/26	XLY
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	106%		%REC	50-127	1	396467	02/26/26	02/27/26	XLY

Results for any subcontracted analyses are not included in this section.

Analysis Results for 553922

Sample ID: DUP-01-0.5-260220	Lab ID: 553922-031	Collected: 02/20/26
	Matrix: Soil	

553922-031 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3050B									
Lead	**22**		mg/Kg	1.0	1	396187	02/23/26	02/24/26	TWJ
Method: EPA 8082 Prep Method: EPA 3546									
Aroclor-1016	ND		ug/Kg	51	1	396467	02/26/26	02/27/26	XLY
Aroclor-1221	ND		ug/Kg	51	1	396467	02/26/26	02/27/26	XLY
Aroclor-1232	ND		ug/Kg	51	1	396467	02/26/26	02/27/26	XLY
Aroclor-1242	ND		ug/Kg	51	1	396467	02/26/26	02/27/26	XLY
Aroclor-1248	ND		ug/Kg	51	1	396467	02/26/26	02/27/26	XLY
Aroclor-1254	ND		ug/Kg	51	1	396467	02/26/26	02/27/26	XLY
Aroclor-1260	ND		ug/Kg	51	1	396467	02/26/26	02/27/26	XLY
Aroclor-1262	ND		ug/Kg	51	1	396467	02/26/26	02/27/26	XLY
Aroclor-1268	ND		ug/Kg	51	1	396467	02/26/26	02/27/26	XLY
Total PCBs	ND		ug/Kg	51	1	396467	02/26/26	02/27/26	XLY
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	104%		%REC	50-127	1	396467	02/26/26	02/27/26	XLY

Results for any subcontracted analyses are not included in this section.

ENTHALPY ANALYTICAL

Analysis Results for 553922

Sample ID: EB-01-260220	Lab ID: 553922-039	Collected: 02/20/26 15:30
	Matrix: Water	

553922-039 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 6010B Prep Method: EPA 3015A									
Lead	ND		mg/L	0.010	1	396062	02/22/26	02/22/26	TWJ
Method: EPA 8015B Prep Method: EPA 5030B									
TPH Gasoline	ND		ug/L	50	1	396341	02/25/26	02/25/26	SXR
Surrogates				**Limits**					
Bromofluorobenzene (FID)	86%		%REC	80-120	1	396341	02/25/26	02/25/26	SXR
Method: EPA 8081A Prep Method: EPA 3510C									
alpha-BHC	ND		ug/L	0.05	0.94	396077	02/22/26	02/25/26	XLY
beta-BHC	ND		ug/L	0.05	0.94	396077	02/22/26	02/25/26	XLY
gamma-BHC	ND		ug/L	0.05	0.94	396077	02/22/26	02/25/26	XLY
delta-BHC	ND		ug/L	0.05	0.94	396077	02/22/26	02/25/26	XLY
Heptachlor	ND		ug/L	0.05	0.94	396077	02/22/26	02/25/26	XLY
Aldrin	ND		ug/L	0.05	0.94	396077	02/22/26	02/25/26	XLY
Heptachlor epoxide	ND		ug/L	0.05	0.94	396077	02/22/26	02/25/26	XLY
Endosulfan I	ND		ug/L	0.05	0.94	396077	02/22/26	02/25/26	XLY
Dieldrin	ND		ug/L	0.09	0.94	396077	02/22/26	02/25/26	XLY
4,4'-DDE	ND		ug/L	0.09	0.94	396077	02/22/26	02/25/26	XLY
Endrin	ND		ug/L	0.09	0.94	396077	02/22/26	02/25/26	XLY
Endosulfan II	ND		ug/L	0.09	0.94	396077	02/22/26	02/25/26	XLY
Endosulfan sulfate	ND		ug/L	0.09	0.94	396077	02/22/26	02/25/26	XLY
4,4'-DDD	ND		ug/L	0.09	0.94	396077	02/22/26	02/25/26	XLY
Endrin aldehyde	ND		ug/L	0.09	0.94	396077	02/22/26	02/25/26	XLY
Endrin ketone	ND		ug/L	0.09	0.94	396077	02/22/26	02/25/26	XLY
4,4'-DDT	ND		ug/L	0.09	0.94	396077	02/22/26	02/25/26	XLY
Methoxychlor	ND		ug/L	0.09	0.94	396077	02/22/26	02/25/26	XLY
Toxaphene	ND		ug/L	1.9	0.94	396077	02/22/26	02/25/26	XLY
Chlordane (Technical)	ND		ug/L	0.9	0.94	396077	02/22/26	02/25/26	XLY
Surrogates				**Limits**					
TCMX	75%		%REC	29-120	0.94	396077	02/22/26	02/25/26	XLY
Decachlorobiphenyl	96%		%REC	33-132	0.94	396077	02/22/26	02/25/26	XLY
Method: EPA 8082 Prep Method: EPA 3510C									
Aroclor-1016	ND		ug/L	0.47	0.94	396077	02/22/26	02/25/26	XLY
Aroclor-1221	ND		ug/L	0.47	0.94	396077	02/22/26	02/25/26	XLY
Aroclor-1232	ND		ug/L	0.47	0.94	396077	02/22/26	02/25/26	XLY
Aroclor-1242	ND		ug/L	0.47	0.94	396077	02/22/26	02/25/26	XLY
Aroclor-1248	ND		ug/L	0.47	0.94	396077	02/22/26	02/25/26	XLY
Aroclor-1254	ND		ug/L	0.47	0.94	396077	02/22/26	02/25/26	XLY
Aroclor-1260	ND		ug/L	0.47	0.94	396077	02/22/26	02/25/26	XLY
Aroclor-1262	ND		ug/L	0.47	0.94	396077	02/22/26	02/25/26	XLY
Aroclor-1268	ND		ug/L	0.47	0.94	396077	02/22/26	02/25/26	XLY
Total PCBs	ND		ug/L	0.47	0.94	396077	02/22/26	02/25/26	XLY
Surrogates				**Limits**					
Decachlorobiphenyl (PCB)	67%		%REC	28-138	0.94	396077	02/22/26	02/25/26	XLY

Results for any subcontracted analyses are not included in this section.

ENTHALPY ANALYTICAL

Analysis Results for 553922

553922-039 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 8260B Prep Method: EPA 5030B									
3-Chloropropene	ND		ug/L	5.0	1	396207	02/24/26	02/24/26	ZST
Freon 12	ND		ug/L	5.0	1	396207	02/24/26	02/24/26	ZST
Chloromethane	ND		ug/L	5.0	1	396207	02/24/26	02/24/26	ZST
Vinyl Chloride	ND		ug/L	5.0	1	396207	02/24/26	02/24/26	ZST
Bromomethane	ND		ug/L	5.0	1	396207	02/24/26	02/24/26	ZST
Chloroethane	ND		ug/L	5.0	1	396207	02/24/26	02/24/26	ZST
Trichlorofluoromethane	ND		ug/L	5.0	1	396207	02/24/26	02/24/26	ZST
Acetone	ND		ug/L	100	1	396207	02/24/26	02/24/26	ZST
Freon 113	ND		ug/L	5.0	1	396207	02/24/26	02/24/26	ZST
1,1-Dichloroethene	ND		ug/L	5.0	1	396207	02/24/26	02/24/26	ZST
Methylene Chloride	ND		ug/L	5.0	1	396207	02/24/26	02/24/26	ZST
MTBE	ND		ug/L	5.0	1	396207	02/24/26	02/24/26	ZST
trans-1,2-Dichloroethene	ND		ug/L	5.0	1	396207	02/24/26	02/24/26	ZST
1,1-Dichloroethane	ND		ug/L	5.0	1	396207	02/24/26	02/24/26	ZST
2-Butanone	ND		ug/L	100	1	396207	02/24/26	02/24/26	ZST
cis-1,2-Dichloroethene	ND		ug/L	5.0	1	396207	02/24/26	02/24/26	ZST
2,2-Dichloropropane	ND		ug/L	5.0	1	396207	02/24/26	02/24/26	ZST
Chloroform	ND		ug/L	5.0	1	396207	02/24/26	02/24/26	ZST
Bromochloromethane	ND		ug/L	5.0	1	396207	02/24/26	02/24/26	ZST
1,1,1-Trichloroethane	ND		ug/L	5.0	1	396207	02/24/26	02/24/26	ZST
1,1-Dichloropropene	ND		ug/L	5.0	1	396207	02/24/26	02/24/26	ZST
Carbon Tetrachloride	ND		ug/L	5.0	1	396207	02/24/26	02/24/26	ZST
1,2-Dichloroethane	ND		ug/L	5.0	1	396207	02/24/26	02/24/26	ZST
Benzene	ND		ug/L	5.0	1	396207	02/24/26	02/24/26	ZST
Trichloroethene	ND		ug/L	5.0	1	396207	02/24/26	02/24/26	ZST
1,2-Dichloropropane	ND		ug/L	5.0	1	396207	02/24/26	02/24/26	ZST
Bromodichloromethane	ND		ug/L	5.0	1	396207	02/24/26	02/24/26	ZST
Dibromomethane	ND		ug/L	5.0	1	396207	02/24/26	02/24/26	ZST
4-Methyl-2-Pentanone	ND		ug/L	5.0	1	396207	02/24/26	02/24/26	ZST
cis-1,3-Dichloropropene	ND		ug/L	5.0	1	396207	02/24/26	02/24/26	ZST
Toluene	ND		ug/L	5.0	1	396207	02/24/26	02/24/26	ZST
trans-1,3-Dichloropropene	ND		ug/L	5.0	1	396207	02/24/26	02/24/26	ZST
1,1,2-Trichloroethane	ND		ug/L	5.0	1	396207	02/24/26	02/24/26	ZST
1,3-Dichloropropane	ND		ug/L	5.0	1	396207	02/24/26	02/24/26	ZST
Tetrachloroethene	ND		ug/L	5.0	1	396207	02/24/26	02/24/26	ZST
Dibromochloromethane	ND		ug/L	5.0	1	396207	02/24/26	02/24/26	ZST
1,2-Dibromoethane	ND		ug/L	5.0	1	396207	02/24/26	02/24/26	ZST
Chlorobenzene	ND		ug/L	5.0	1	396207	02/24/26	02/24/26	ZST
1,1,1,2-Tetrachloroethane	ND		ug/L	5.0	1	396207	02/24/26	02/24/26	ZST
Ethylbenzene	ND		ug/L	5.0	1	396207	02/24/26	02/24/26	ZST
m,p-Xylenes	ND		ug/L	10	1	396207	02/24/26	02/24/26	ZST
o-Xylene	ND		ug/L	5.0	1	396207	02/24/26	02/24/26	ZST
Styrene	ND		ug/L	5.0	1	396207	02/24/26	02/24/26	ZST
Bromoform	ND		ug/L	5.0	1	396207	02/24/26	02/24/26	ZST
Isopropylbenzene	ND		ug/L	5.0	1	396207	02/24/26	02/24/26	ZST
1,1,2,2-Tetrachloroethane	ND		ug/L	5.0	1	396207	02/24/26	02/24/26	ZST
1,2,3-Trichloropropane	ND		ug/L	5.0	1	396207	02/24/26	02/24/26	ZST
Propylbenzene	ND		ug/L	5.0	1	396207	02/24/26	02/24/26	ZST
Bromobenzene	ND		ug/L	5.0	1	396207	02/24/26	02/24/26	ZST
1,3,5-Trimethylbenzene	ND		ug/L	5.0	1	396207	02/24/26	02/24/26	ZST

Results for any subcontracted analyses are not included in this section.

ENTHALPY ANALYTICAL

Analysis Results for 553922

553922-039 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
2-Chlorotoluene	ND		ug/L	5.0	1	396207	02/24/26	02/24/26	ZST
4-Chlorotoluene	ND		ug/L	5.0	1	396207	02/24/26	02/24/26	ZST
tert-Butylbenzene	ND		ug/L	5.0	1	396207	02/24/26	02/24/26	ZST
1,2,4-Trimethylbenzene	ND		ug/L	5.0	1	396207	02/24/26	02/24/26	ZST
sec-Butylbenzene	ND		ug/L	5.0	1	396207	02/24/26	02/24/26	ZST
para-Isopropyl Toluene	ND		ug/L	5.0	1	396207	02/24/26	02/24/26	ZST
1,3-Dichlorobenzene	ND		ug/L	5.0	1	396207	02/24/26	02/24/26	ZST
1,4-Dichlorobenzene	ND		ug/L	5.0	1	396207	02/24/26	02/24/26	ZST
n-Butylbenzene	ND		ug/L	5.0	1	396207	02/24/26	02/24/26	ZST
1,2-Dichlorobenzene	ND		ug/L	5.0	1	396207	02/24/26	02/24/26	ZST
1,2-Dibromo-3-Chloropropane	ND		ug/L	5.0	1	396207	02/24/26	02/24/26	ZST
1,2,4-Trichlorobenzene	ND		ug/L	5.0	1	396207	02/24/26	02/24/26	ZST
Hexachlorobutadiene	ND		ug/L	5.0	1	396207	02/24/26	02/24/26	ZST
Naphthalene	ND		ug/L	5.0	1	396207	02/24/26	02/24/26	ZST
1,2,3-Trichlorobenzene	ND		ug/L	5.0	1	396207	02/24/26	02/24/26	ZST
cis-1,4-Dichloro-2-butene	ND		ug/L	5.0	1	396207	02/24/26	02/24/26	ZST
trans-1,4-Dichloro-2-butene	ND		ug/L	5.0	1	396207	02/24/26	02/24/26	ZST
Xylene (total)	ND		ug/L	5.0	1	396207	02/24/26	02/24/26	ZST
Surrogates				**Limits**					
Dibromofluoromethane	106%		%REC	70-130	1	396207	02/24/26	02/24/26	ZST
1,2-Dichloroethane-d4	102%		%REC	70-130	1	396207	02/24/26	02/24/26	ZST
Toluene-d8	100%		%REC	70-130	1	396207	02/24/26	02/24/26	ZST
Bromofluorobenzene	99%		%REC	70-130	1	396207	02/24/26	02/24/26	ZST

Results for any subcontracted analyses are not included in this section.

ENTHALPY ANALYTICAL

Analysis Results for 553922

Sample ID: CG-44-0.5	Lab ID: 553922-041	Collected: 02/20/26
	Matrix: Soil	

553922-041 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 8081A Prep Method: EPA 3546									
alpha-BHC	ND		ug/Kg	10	2	396454	02/26/26	02/27/26	HQN
beta-BHC	ND		ug/Kg	10	2	396454	02/26/26	02/27/26	HQN
gamma-BHC	ND		ug/Kg	10	2	396454	02/26/26	02/27/26	HQN
delta-BHC	ND		ug/Kg	10	2	396454	02/26/26	02/27/26	HQN
Heptachlor	ND		ug/Kg	10	2	396454	02/26/26	02/27/26	HQN
Aldrin	ND		ug/Kg	10	2	396454	02/26/26	02/27/26	HQN
Heptachlor epoxide	ND		ug/Kg	10	2	396454	02/26/26	02/27/26	HQN
Endosulfan I	ND		ug/Kg	10	2	396454	02/26/26	02/27/26	HQN
Dieldrin	ND		ug/Kg	10	2	396454	02/26/26	02/27/26	HQN
4,4'-DDE	ND		ug/Kg	10	2	396454	02/26/26	02/27/26	HQN
Endrin	ND		ug/Kg	10	2	396454	02/26/26	02/27/26	HQN
Endosulfan II	ND		ug/Kg	10	2	396454	02/26/26	02/27/26	HQN
Endosulfan sulfate	ND		ug/Kg	10	2	396454	02/26/26	02/27/26	HQN
4,4'-DDD	ND		ug/Kg	10	2	396454	02/26/26	02/27/26	HQN
Endrin aldehyde	ND		ug/Kg	10	2	396454	02/26/26	02/27/26	HQN
Endrin ketone	ND		ug/Kg	10	2	396454	02/26/26	02/27/26	HQN
4,4'-DDT	ND		ug/Kg	10	2	396454	02/26/26	02/27/26	HQN
Methoxychlor	ND		ug/Kg	20	2	396454	02/26/26	02/27/26	HQN
Toxaphene	ND		ug/Kg	200	2	396454	02/26/26	02/27/26	HQN
Chlordane (Technical)	ND		ug/Kg	100	2	396454	02/26/26	02/27/26	HQN
Surrogates				**Limits**					
TCMX	90%		%REC	58-120	2	396454	02/26/26	02/27/26	HQN
Decachlorobiphenyl	92%		%REC	47-120	2	396454	02/26/26	02/27/26	HQN

Results for any subcontracted analyses are not included in this section.

ENTHALPY ANALYTICAL

Analysis Results for 553922

Sample ID: CG-44-2.5	Lab ID: 553922-042	Collected: 02/20/26
	Matrix: Soil	

553922-042 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 8081A Prep Method: EPA 3546									
alpha-BHC	ND		ug/Kg	5.1	1	396712	02/28/26	03/02/26	XLY
beta-BHC	ND		ug/Kg	5.1	1	396712	02/28/26	03/02/26	XLY
gamma-BHC	ND		ug/Kg	5.1	1	396712	02/28/26	03/02/26	XLY
delta-BHC	ND		ug/Kg	5.1	1	396712	02/28/26	03/02/26	XLY
Heptachlor	ND		ug/Kg	5.1	1	396712	02/28/26	03/02/26	XLY
Aldrin	ND		ug/Kg	5.1	1	396712	02/28/26	03/02/26	XLY
Heptachlor epoxide	ND		ug/Kg	5.1	1	396712	02/28/26	03/02/26	XLY
Endosulfan I	ND		ug/Kg	5.1	1	396712	02/28/26	03/02/26	XLY
Dieldrin	ND		ug/Kg	5.1	1	396712	02/28/26	03/02/26	XLY
4,4'-DDE	ND		ug/Kg	5.1	1	396712	02/28/26	03/02/26	XLY
Endrin	ND		ug/Kg	5.1	1	396712	02/28/26	03/02/26	XLY
Endosulfan II	ND		ug/Kg	5.1	1	396712	02/28/26	03/02/26	XLY
Endosulfan sulfate	ND		ug/Kg	5.1	1	396712	02/28/26	03/02/26	XLY
4,4'-DDD	ND		ug/Kg	5.1	1	396712	02/28/26	03/02/26	XLY
Endrin aldehyde	ND		ug/Kg	5.1	1	396712	02/28/26	03/02/26	XLY
Endrin ketone	ND		ug/Kg	5.1	1	396712	02/28/26	03/02/26	XLY
4,4'-DDT	ND		ug/Kg	5.1	1	396712	02/28/26	03/02/26	XLY
Methoxychlor	ND		ug/Kg	10	1	396712	02/28/26	03/02/26	XLY
Toxaphene	ND		ug/Kg	100	1	396712	02/28/26	03/02/26	XLY
Chlordane (Technical)	ND		ug/Kg	51	1	396712	02/28/26	03/02/26	XLY
Surrogates				**Limits**					
TCMX	90%		%REC	58-120	1	396712	02/28/26	03/02/26	XLY
Decachlorobiphenyl	70%		%REC	47-120	1	396712	02/28/26	03/02/26	XLY

Results for any subcontracted analyses are not included in this section.

ENTHALPY ANALYTICAL

Analysis Results for 553922

Sample ID: CG-45-0.5	Lab ID: 553922-043	Collected: 02/20/26
	Matrix: Soil	

553922-043 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 8081A Prep Method: EPA 3546									
alpha-BHC	ND		ug/Kg	9.8	2	396454	02/26/26	02/27/26	HQN
beta-BHC	ND		ug/Kg	9.8	2	396454	02/26/26	02/27/26	HQN
gamma-BHC	ND		ug/Kg	9.8	2	396454	02/26/26	02/27/26	HQN
delta-BHC	ND		ug/Kg	9.8	2	396454	02/26/26	02/27/26	HQN
Heptachlor	ND		ug/Kg	9.8	2	396454	02/26/26	02/27/26	HQN
Aldrin	ND		ug/Kg	9.8	2	396454	02/26/26	02/27/26	HQN
Heptachlor epoxide	ND		ug/Kg	9.8	2	396454	02/26/26	02/27/26	HQN
Endosulfan I	ND		ug/Kg	9.8	2	396454	02/26/26	02/27/26	HQN
Dieldrin	ND		ug/Kg	9.8	2	396454	02/26/26	02/27/26	HQN
4,4'-DDE	ND		ug/Kg	9.8	2	396454	02/26/26	02/27/26	HQN
Endrin	ND		ug/Kg	9.8	2	396454	02/26/26	02/27/26	HQN
Endosulfan II	ND		ug/Kg	9.8	2	396454	02/26/26	02/27/26	HQN
Endosulfan sulfate	ND		ug/Kg	9.8	2	396454	02/26/26	02/27/26	HQN
4,4'-DDD	ND		ug/Kg	9.8	2	396454	02/26/26	02/27/26	HQN
Endrin aldehyde	ND		ug/Kg	9.8	2	396454	02/26/26	02/27/26	HQN
Endrin ketone	ND		ug/Kg	9.8	2	396454	02/26/26	02/27/26	HQN
4,4'-DDT	ND		ug/Kg	9.8	2	396454	02/26/26	02/27/26	HQN
Methoxychlor	ND		ug/Kg	20	2	396454	02/26/26	02/27/26	HQN
Toxaphene	ND		ug/Kg	200	2	396454	02/26/26	02/27/26	HQN
Chlordane (Technical)	ND		ug/Kg	98	2	396454	02/26/26	02/27/26	HQN
Surrogates				**Limits**					
TCMX	88%		%REC	58-120	2	396454	02/26/26	02/27/26	HQN
Decachlorobiphenyl	82%		%REC	47-120	2	396454	02/26/26	02/27/26	HQN

Results for any subcontracted analyses are not included in this section.

ENTHALPY ANALYTICAL

Analysis Results for 553922

Sample ID: CG-45-2.5	Lab ID: 553922-044	Collected: 02/20/26
	Matrix: Soil	

553922-044 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 8081A Prep Method: EPA 3546									
alpha-BHC	ND		ug/Kg	5.0	1	396454	02/26/26	02/26/26	KMB
beta-BHC	ND		ug/Kg	5.0	1	396454	02/26/26	02/26/26	KMB
gamma-BHC	ND		ug/Kg	5.0	1	396454	02/26/26	02/26/26	KMB
delta-BHC	ND		ug/Kg	5.0	1	396454	02/26/26	02/26/26	KMB
Heptachlor	ND		ug/Kg	5.0	1	396454	02/26/26	02/26/26	KMB
Aldrin	ND		ug/Kg	5.0	1	396454	02/26/26	02/26/26	KMB
Heptachlor epoxide	ND		ug/Kg	5.0	1	396454	02/26/26	02/26/26	KMB
Endosulfan I	ND		ug/Kg	5.0	1	396454	02/26/26	02/26/26	KMB
Dieldrin	ND		ug/Kg	5.0	1	396454	02/26/26	02/26/26	KMB
4,4'-DDE	ND		ug/Kg	5.0	1	396454	02/26/26	02/26/26	KMB
Endrin	ND		ug/Kg	5.0	1	396454	02/26/26	02/26/26	KMB
Endosulfan II	ND		ug/Kg	5.0	1	396454	02/26/26	02/26/26	KMB
Endosulfan sulfate	ND		ug/Kg	5.0	1	396454	02/26/26	02/26/26	KMB
4,4'-DDD	ND		ug/Kg	5.0	1	396454	02/26/26	02/26/26	KMB
Endrin aldehyde	ND		ug/Kg	5.0	1	396454	02/26/26	02/26/26	KMB
Endrin ketone	ND		ug/Kg	5.0	1	396454	02/26/26	02/26/26	KMB
4,4'-DDT	ND		ug/Kg	5.0	1	396454	02/26/26	02/26/26	KMB
Methoxychlor	ND		ug/Kg	10	1	396454	02/26/26	02/26/26	KMB
Toxaphene	ND		ug/Kg	100	1	396454	02/26/26	02/26/26	KMB
Chlordane (Technical)	ND		ug/Kg	50	1	396454	02/26/26	02/26/26	KMB
Surrogates				**Limits**					
TCMX	85%		%REC	58-120	1	396454	02/26/26	02/26/26	KMB
Decachlorobiphenyl	78%		%REC	47-120	1	396454	02/26/26	02/26/26	KMB

Results for any subcontracted analyses are not included in this section.

ENTHALPY ANALYTICAL

Analysis Results for 553922

Sample ID: CG-45-0.5-DUP	Lab ID: 553922-045	Collected: 02/20/26
	Matrix: Soil	

553922-045 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 8081A Prep Method: EPA 3546									
alpha-BHC	ND		ug/Kg	10	2	396454	02/26/26	02/27/26	KMB
beta-BHC	ND		ug/Kg	10	2	396454	02/26/26	02/27/26	KMB
gamma-BHC	ND		ug/Kg	10	2	396454	02/26/26	02/27/26	KMB
delta-BHC	ND		ug/Kg	10	2	396454	02/26/26	02/27/26	KMB
Heptachlor	ND		ug/Kg	10	2	396454	02/26/26	02/27/26	KMB
Aldrin	ND		ug/Kg	10	2	396454	02/26/26	02/27/26	KMB
Heptachlor epoxide	ND		ug/Kg	10	2	396454	02/26/26	02/27/26	KMB
Endosulfan I	ND		ug/Kg	10	2	396454	02/26/26	02/27/26	KMB
Dieldrin	ND		ug/Kg	10	2	396454	02/26/26	02/27/26	KMB
4,4'-DDE	ND		ug/Kg	10	2	396454	02/26/26	02/27/26	KMB
Endrin	ND		ug/Kg	10	2	396454	02/26/26	02/27/26	KMB
Endosulfan II	ND		ug/Kg	10	2	396454	02/26/26	02/27/26	KMB
Endosulfan sulfate	ND		ug/Kg	10	2	396454	02/26/26	02/27/26	KMB
4,4'-DDD	ND		ug/Kg	10	2	396454	02/26/26	02/27/26	KMB
Endrin aldehyde	ND		ug/Kg	10	2	396454	02/26/26	02/27/26	KMB
Endrin ketone	ND		ug/Kg	10	2	396454	02/26/26	02/27/26	KMB
4,4'-DDT	ND		ug/Kg	10	2	396454	02/26/26	02/27/26	KMB
Methoxychlor	ND		ug/Kg	20	2	396454	02/26/26	02/27/26	KMB
Toxaphene	ND		ug/Kg	200	2	396454	02/26/26	02/27/26	KMB
Chlordane (Technical)	ND		ug/Kg	100	2	396454	02/26/26	02/27/26	KMB
Surrogates				**Limits**					
TCMX	93%		%REC	58-120	2	396454	02/26/26	02/27/26	KMB
Decachlorobiphenyl	117%		%REC	47-120	2	396454	02/26/26	02/27/26	KMB

Results for any subcontracted analyses are not included in this section.

ENTHALPY ANALYTICAL

Analysis Results for 553922

Sample ID: CG-45-2.5-DUP	Lab ID: 553922-046	Collected: 02/20/26
	Matrix: Soil	

553922-046 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 8081A Prep Method: EPA 3546									
alpha-BHC	ND		ug/Kg	5.0	1	396454	02/26/26	02/27/26	KMB
beta-BHC	ND		ug/Kg	5.0	1	396454	02/26/26	02/27/26	KMB
gamma-BHC	ND		ug/Kg	5.0	1	396454	02/26/26	02/27/26	KMB
delta-BHC	ND		ug/Kg	5.0	1	396454	02/26/26	02/27/26	KMB
Heptachlor	ND		ug/Kg	5.0	1	396454	02/26/26	02/27/26	KMB
Aldrin	ND		ug/Kg	5.0	1	396454	02/26/26	02/27/26	KMB
Heptachlor epoxide	ND		ug/Kg	5.0	1	396454	02/26/26	02/27/26	KMB
Endosulfan I	ND		ug/Kg	5.0	1	396454	02/26/26	02/27/26	KMB
Dieldrin	ND		ug/Kg	5.0	1	396454	02/26/26	02/27/26	KMB
4,4'-DDE	ND		ug/Kg	5.0	1	396454	02/26/26	02/27/26	KMB
Endrin	ND		ug/Kg	5.0	1	396454	02/26/26	02/27/26	KMB
Endosulfan II	ND		ug/Kg	5.0	1	396454	02/26/26	02/27/26	KMB
Endosulfan sulfate	ND		ug/Kg	5.0	1	396454	02/26/26	02/27/26	KMB
4,4'-DDD	ND		ug/Kg	5.0	1	396454	02/26/26	02/27/26	KMB
Endrin aldehyde	ND		ug/Kg	5.0	1	396454	02/26/26	02/27/26	KMB
Endrin ketone	ND		ug/Kg	5.0	1	396454	02/26/26	02/27/26	KMB
4,4'-DDT	ND		ug/Kg	5.0	1	396454	02/26/26	02/27/26	KMB
Methoxychlor	ND		ug/Kg	10	1	396454	02/26/26	02/27/26	KMB
Toxaphene	ND		ug/Kg	100	1	396454	02/26/26	02/27/26	KMB
Chlordane (Technical)	ND		ug/Kg	50	1	396454	02/26/26	02/27/26	KMB
Surrogates				**Limits**					
TCMX	86%		%REC	58-120	1	396454	02/26/26	02/27/26	KMB
Decachlorobiphenyl	109%		%REC	47-120	1	396454	02/26/26	02/27/26	KMB

Results for any subcontracted analyses are not included in this section.

Analysis Results for 553922

Sample ID: CG-46-0.5-	Lab ID: 553922-047	Collected: 02/20/26
	Matrix: Soil	

553922-047 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 8081A Prep Method: EPA 3546									
alpha-BHC	ND		ug/Kg	25	5	396454	02/26/26	02/27/26	HQN
beta-BHC	ND		ug/Kg	25	5	396454	02/26/26	02/27/26	HQN
gamma-BHC	ND		ug/Kg	25	5	396454	02/26/26	02/27/26	HQN
delta-BHC	ND		ug/Kg	25	5	396454	02/26/26	02/27/26	HQN
Heptachlor	ND		ug/Kg	25	5	396454	02/26/26	02/27/26	HQN
Aldrin	ND		ug/Kg	25	5	396454	02/26/26	02/27/26	HQN
Heptachlor epoxide	ND		ug/Kg	25	5	396454	02/26/26	02/27/26	HQN
Endosulfan I	ND		ug/Kg	25	5	396454	02/26/26	02/27/26	HQN
Dieldrin	ND		ug/Kg	25	5	396454	02/26/26	02/27/26	HQN
4,4'-DDE	ND		ug/Kg	25	5	396454	02/26/26	02/27/26	HQN
Endrin	ND		ug/Kg	25	5	396454	02/26/26	02/27/26	HQN
Endosulfan II	ND		ug/Kg	25	5	396454	02/26/26	02/27/26	HQN
Endosulfan sulfate	ND		ug/Kg	25	5	396454	02/26/26	02/27/26	HQN
4,4'-DDD	ND		ug/Kg	25	5	396454	02/26/26	02/27/26	HQN
Endrin aldehyde	ND		ug/Kg	25	5	396454	02/26/26	02/27/26	HQN
Endrin ketone	ND		ug/Kg	25	5	396454	02/26/26	02/27/26	HQN
4,4'-DDT	ND		ug/Kg	25	5	396454	02/26/26	02/27/26	HQN
Methoxychlor	ND		ug/Kg	50	5	396454	02/26/26	02/27/26	HQN
Toxaphene	ND		ug/Kg	500	5	396454	02/26/26	02/27/26	HQN
Chlordane (Technical)	ND		ug/Kg	250	5	396454	02/26/26	02/27/26	HQN
Surrogates				**Limits**					
TCMX	102%		%REC	58-120	5	396454	02/26/26	02/27/26	HQN
Decachlorobiphenyl	88%		%REC	47-120	5	396454	02/26/26	02/27/26	HQN

Results for any subcontracted analyses are not included in this section.

ENTHALPY ANALYTICAL

Analysis Results for 553922

Sample ID: CG-46-2.5	Lab ID: 553922-048	Collected: 02/20/26
	Matrix: Soil	

553922-048 Analyte	Result	Qual	Units	RL	DF	Batch	Prepared	Analyzed	Chemist
Method: EPA 8081A Prep Method: EPA 3546									
alpha-BHC	ND		ug/Kg	4.9	0.98	396454	02/26/26	02/27/26	KMB
beta-BHC	ND		ug/Kg	4.9	0.98	396454	02/26/26	02/27/26	KMB
gamma-BHC	ND		ug/Kg	4.9	0.98	396454	02/26/26	02/27/26	KMB
delta-BHC	ND		ug/Kg	4.9	0.98	396454	02/26/26	02/27/26	KMB
Heptachlor	ND		ug/Kg	4.9	0.98	396454	02/26/26	02/27/26	KMB
Aldrin	ND		ug/Kg	4.9	0.98	396454	02/26/26	02/27/26	KMB
Heptachlor epoxide	ND		ug/Kg	4.9	0.98	396454	02/26/26	02/27/26	KMB
Endosulfan I	ND		ug/Kg	4.9	0.98	396454	02/26/26	02/27/26	KMB
Dieldrin	ND		ug/Kg	4.9	0.98	396454	02/26/26	02/27/26	KMB
4,4'-DDE	ND		ug/Kg	4.9	0.98	396454	02/26/26	02/27/26	KMB
Endrin	ND		ug/Kg	4.9	0.98	396454	02/26/26	02/27/26	KMB
Endosulfan II	ND		ug/Kg	4.9	0.98	396454	02/26/26	02/27/26	KMB
Endosulfan sulfate	ND		ug/Kg	4.9	0.98	396454	02/26/26	02/27/26	KMB
4,4'-DDD	ND		ug/Kg	4.9	0.98	396454	02/26/26	02/27/26	KMB
Endrin aldehyde	ND		ug/Kg	4.9	0.98	396454	02/26/26	02/27/26	KMB
Endrin ketone	ND		ug/Kg	4.9	0.98	396454	02/26/26	02/27/26	KMB
4,4'-DDT	ND		ug/Kg	4.9	0.98	396454	02/26/26	02/27/26	KMB
Methoxychlor	ND		ug/Kg	9.8	0.98	396454	02/26/26	02/27/26	KMB
Toxaphene	ND		ug/Kg	98	0.98	396454	02/26/26	02/27/26	KMB
Chlordane (Technical)	ND		ug/Kg	49	0.98	396454	02/26/26	02/27/26	KMB
Surrogates				**Limits**					
TCMX	91%		%REC	58-120	0.98	396454	02/26/26	02/27/26	KMB
Decachlorobiphenyl	105%		%REC	47-120	0.98	396454	02/26/26	02/27/26	KMB

ND Not Detected

Results for any subcontracted analyses are not included in this section.

ENTHALPY ANALYTICAL

Batch QC

Type: Blank	Lab ID: QC1343037	Batch: 396062
Matrix: Water	Method: EPA 6010B	Prep Method: EPA 3015A

QC1343037 Analyte	Result	Qual	Units	RL	Prepared	Analyzed
Lead	ND		mg/L	0.010	02/22/26	02/22/26

Type: Lab Control Sample	Lab ID: QC1343038	Batch: 396062
Matrix: Water	Method: EPA 6010B	Prep Method: EPA 3015A

QC1343038 Analyte	Result	Spiked	Units	Recovery	Qual	Limits
Lead	0.3389	0.4000	mg/L	85%		80-120

Type: Matrix Spike	Lab ID: QC1343039	Batch: 396062
Matrix (Source ID): Water (553938-001)	Method: EPA 6010B	Prep Method: EPA 3015A

QC1343039 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	DF
Lead	3.245	0.03048	4.000	mg/L	80%		75-125	10

Type: Matrix Spike Duplicate	Lab ID: QC1343040	Batch: 396062
Matrix (Source ID): Water (553938-001)	Method: EPA 6010B	Prep Method: EPA 3015A

QC1343040 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	RPD	RPD Lim	DF
Lead	3.197	0.03048	4.000	mg/L	79%		75-125	1	20	10

Type: Serial Dilution	Lab ID: QC1343059	Batch: 396062
Matrix (Source ID): Water (553938-001)	Method: EPA 6010B	Prep Method: EPA 3015A

QC1343059 Analyte	Result	Source Sample Result	Units	Qual	RPD	RPD Lim	DF
Lead	ND	0.03048	mg/L				50

Type: Blank	Lab ID: QC1343463	Batch: 396187
Matrix: Soil	Method: EPA 6010B	Prep Method: EPA 3050B

QC1343463 Analyte	Result	Qual	Units	RL	Prepared	Analyzed
Lead	ND		mg/Kg	1.0	02/23/26	02/24/26

Type: Lab Control Sample	Lab ID: QC1343464	Batch: 396187
Matrix: Soil	Method: EPA 6010B	Prep Method: EPA 3050B

QC1343464 Analyte	Result	Spiked	Units	Recovery	Qual	Limits
Lead	108.5	100.0	mg/Kg	109%		80-120

ENTHALPY ANALYTICAL

Batch QC

Type:	Matrix Spike	Lab ID:	QC1343465	Batch:	396187
Matrix (Source ID):	Soil (553922-004)	Method:	EPA 6010B	Prep Method:	EPA 3050B

QC1343465 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	DF
Lead	105.9	3.884	98.04	mg/Kg	104%		75-125	0.98

Type:	Matrix Spike Duplicate	Lab ID:	QC1343466	Batch:	396187
Matrix (Source ID):	Soil (553922-004)	Method:	EPA 6010B	Prep Method:	EPA 3050B

QC1343466 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	RPD	RPD Lim	DF
Lead	106.6	3.884	100.0	mg/Kg	103%		75-125	1	28	1

Type:	Post Digest Spike	Lab ID:	QC1343467	Batch:	396187
Matrix (Source ID):	Soil (553922-004)	Method:	EPA 6010B	Prep Method:	EPA 3050B

QC1343467 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	DF
Lead	95.71	3.884	97.09	mg/Kg	95%		75-125	0.97

Type:	Serial Dilution	Lab ID:	QC1343701	Batch:	396187
Matrix (Source ID):	Soil (553922-004)	Method:	EPA 6010B	Prep Method:	EPA 3050B

QC1343701 Analyte	Result	Source Sample Result	Units	Qual	RPD	RPD Lim	DF
Lead	3.803	3.884	mg/Kg	J			4.9

Type:	Blank	Lab ID:	QC1349603	Batch:	397934
Matrix:	Soil	Method:	EPA 6010B	Prep Method:	EPA 3050B

QC1349603 Analyte	Result	Qual	Units	RL	Prepared	Analyzed
Lead	ND		mg/Kg	1.0	03/13/26	03/13/26

Type:	Lab Control Sample	Lab ID:	QC1349604	Batch:	397934
Matrix:	Soil	Method:	EPA 6010B	Prep Method:	EPA 3050B

QC1349604 Analyte	Result	Spiked	Units	Recovery	Qual	Limits
Lead	81.06	100.0	mg/Kg	81%		80-120

ENTHALPY ANALYTICAL

Batch QC

Type:	Matrix Spike	Lab ID:	QC1349605	Batch:	397934
Matrix (Source ID):	Soil (555301-002)	Method:	EPA 6010B	Prep Method:	EPA 3050B

QC1349605 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	DF
Lead	111.2	10.28	97.09	mg/Kg	104%		75-125	0.97

Type:	Matrix Spike Duplicate	Lab ID:	QC1349606	Batch:	397934
Matrix (Source ID):	Soil (555301-002)	Method:	EPA 6010B	Prep Method:	EPA 3050B

QC1349606 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	RPD	RPD Lim	DF
Lead	112.3	10.28	97.09	mg/Kg	105%		75-125	1	28	0.97

Type:	Serial Dilution	Lab ID:	QC1349607	Batch:	397934
Matrix (Source ID):	Soil (555301-002)	Method:	EPA 6010B	Prep Method:	EPA 3050B

QC1349607 Analyte	Result	Source Sample Result	Units	Qual	RPD	RPD Lim	DF
Lead	7.739	10.28	mg/Kg				5

Type:	Post Digest Spike	Lab ID:	QC1349608	Batch:	397934
Matrix (Source ID):	Soil (555301-002)	Method:	EPA 6010B	Prep Method:	EPA 3050B

QC1349608 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	DF
Lead	108.9	10.28	99.01	mg/Kg	100%		75-125	0.99

ENTHALPY ANALYTICAL

Batch QC

Type:	**Blank**	**Lab ID:**	**QC1343537**	**Batch:**	**396206**
Matrix:	**Soil**	**Method:**	**EPA 6020**	**Prep Method:**	**EPA 3050B**

QC1343537 Analyte	Result	Qual	Units	RL	Prepared	Analyzed
Antimony	ND		mg/Kg	1.0	02/24/26	02/25/26
Arsenic	ND		mg/Kg	1.0	02/24/26	02/25/26
Barium	ND		mg/Kg	1.0	02/24/26	02/25/26
Beryllium	ND		mg/Kg	1.0	02/24/26	02/25/26
Cadmium	ND		mg/Kg	0.50	02/24/26	02/25/26
Chromium	ND		mg/Kg	1.0	02/24/26	02/25/26
Cobalt	ND		mg/Kg	1.0	02/24/26	02/25/26
Copper	ND		mg/Kg	1.0	02/24/26	02/25/26
Lead	ND		mg/Kg	0.50	02/24/26	02/25/26
Molybdenum	ND		mg/Kg	1.0	02/24/26	02/25/26
Nickel	ND		mg/Kg	1.0	02/24/26	02/25/26
Selenium	ND		mg/Kg	2.0	02/24/26	02/25/26
Silver	ND		mg/Kg	0.50	02/24/26	02/25/26
Thallium	ND		mg/Kg	1.0	02/24/26	02/25/26
Vanadium	ND		mg/Kg	2.0	02/24/26	02/25/26
Zinc	ND		mg/Kg	7.0	02/24/26	02/25/26

Type:	**Lab Control Sample**	**Lab ID:**	**QC1343538**	**Batch:**	**396206**
Matrix:	**Soil**	**Method:**	**EPA 6020**	**Prep Method:**	**EPA 3050B**

QC1343538 Analyte	Result	Spiked	Units	Recovery	Qual	Limits
Antimony	105.9	100.0	mg/Kg	106%		80-120
Arsenic	103.3	100.0	mg/Kg	103%		80-120
Barium	97.18	100.0	mg/Kg	97%		80-120
Beryllium	87.26	100.0	mg/Kg	87%		80-120
Cadmium	100.7	100.0	mg/Kg	101%		80-120
Chromium	103.0	100.0	mg/Kg	103%		80-120
Cobalt	105.7	100.0	mg/Kg	106%		80-120
Copper	103.7	100.0	mg/Kg	104%		80-120
Lead	101.0	100.0	mg/Kg	101%		80-120
Molybdenum	95.19	100.0	mg/Kg	95%		80-120
Nickel	106.0	100.0	mg/Kg	106%		80-120
Selenium	108.3	100.0	mg/Kg	108%		80-120
Silver	49.57	50.00	mg/Kg	99%		80-120
Thallium	98.14	100.0	mg/Kg	98%		80-120
Vanadium	102.8	100.0	mg/Kg	103%		80-120
Zinc	104.8	100.0	mg/Kg	105%		80-120

ENTHALPY ANALYTICAL

Batch QC

Type:	Matrix Spike	Lab ID:	QC1343539	Batch:	396206
Matrix (Source ID):	Soil (553922-001)	Method:	EPA 6020	Prep Method:	EPA 3050B

QC1343539 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	DF
Antimony	38.87	ND	95.24	mg/Kg	41%	*	75-125	0.95
Arsenic	102.9	3.065	95.24	mg/Kg	105%		75-125	0.95
Barium	225.9	107.9	95.24	mg/Kg	124%		75-125	0.95
Beryllium	87.95	0.3218	95.24	mg/Kg	92%		75-125	0.95
Cadmium	98.21	ND	95.24	mg/Kg	103%		75-125	0.95
Chromium	116.7	24.13	95.24	mg/Kg	97%		75-125	0.95
Cobalt	109.5	8.539	95.24	mg/Kg	106%		75-125	0.95
Copper	132.4	29.98	95.24	mg/Kg	108%		75-125	0.95
Lead	126.0	37.22	95.24	mg/Kg	93%		75-125	0.95
Molybdenum	85.62	ND	95.24	mg/Kg	90%		75-125	0.95
Nickel	115.7	18.79	95.24	mg/Kg	102%		75-125	0.95
Selenium	97.31	ND	95.24	mg/Kg	102%		75-125	0.95
Silver	46.84	ND	47.62	mg/Kg	98%		75-125	0.95
Thallium	95.63	ND	95.24	mg/Kg	100%		75-125	0.95
Vanadium	140.7	40.79	95.24	mg/Kg	105%		75-125	0.95
Zinc	201.7	120.6	95.24	mg/Kg	85%		75-125	0.95

Type:	Matrix Spike Duplicate	Lab ID:	QC1343540	Batch:	396206
Matrix (Source ID):	Soil (553922-001)	Method:	EPA 6020	Prep Method:	EPA 3050B

QC1343540 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	RPD	RPD Lim	DF
Antimony	37.90	ND	100.0	mg/Kg	38%	*	75-125	7	28	1
Arsenic	107.8	3.065	100.0	mg/Kg	105%		75-125	0	22	1
Barium	240.7	107.9	100.0	mg/Kg	133%	*	75-125	4	26	1
Beryllium	90.21	0.3218	100.0	mg/Kg	90%		75-125	2	20	1
Cadmium	102.6	ND	100.0	mg/Kg	103%		75-125	1	20	1
Chromium	122.2	24.13	100.0	mg/Kg	98%		75-125	1	20	1
Cobalt	113.9	8.539	100.0	mg/Kg	105%		75-125	1	20	1
Copper	139.4	29.98	100.0	mg/Kg	109%		75-125	1	28	1
Lead	146.6	37.22	100.0	mg/Kg	109%		75-125	12	25	1
Molybdenum	87.56	ND	100.0	mg/Kg	88%		75-125	3	20	1
Nickel	121.9	18.79	100.0	mg/Kg	103%		75-125	1	20	1
Selenium	98.60	ND	100.0	mg/Kg	99%		75-125	4	20	1
Silver	48.04	ND	50.00	mg/Kg	96%		75-125	2	20	1
Thallium	99.06	ND	100.0	mg/Kg	99%		75-125	1	20	1
Vanadium	145.6	40.79	100.0	mg/Kg	105%		75-125	0	20	1
Zinc	211.0	120.6	100.0	mg/Kg	90%		75-125	2	22	1

ENTHALPY ANALYTICAL

Batch QC

Type:	Post Digest Spike	Lab ID:	QC1343569	Batch:	396206
Matrix (Source ID):	Soil (553922-001)	Method:	EPA 6020	Prep Method:	EPA 3050B

QC1343569 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	DF
Antimony	101.8	ND	99.01	mg/Kg	103%		75-125	0.99
Arsenic	105.3	3.065	99.01	mg/Kg	103%		75-125	0.99
Barium	204.4	107.9	99.01	mg/Kg	97%		75-125	0.99
Beryllium	85.10	0.3218	99.01	mg/Kg	86%		75-125	0.99
Cadmium	98.27	ND	99.01	mg/Kg	99%		75-125	0.99
Chromium	123.8	24.13	99.01	mg/Kg	101%		75-125	0.99
Cobalt	110.2	8.539	99.01	mg/Kg	103%		75-125	0.99
Copper	134.7	29.98	99.01	mg/Kg	106%		75-125	0.99
Lead	134.9	37.22	99.01	mg/Kg	99%		75-125	0.99
Molybdenum	90.64	ND	99.01	mg/Kg	92%		75-125	0.99
Nickel	122.0	18.79	99.01	mg/Kg	104%		75-125	0.99
Selenium	96.06	ND	99.01	mg/Kg	97%		75-125	0.99
Silver	44.28	ND	49.50	mg/Kg	89%		75-125	0.99
Thallium	95.47	ND	99.01	mg/Kg	96%		75-125	0.99
Vanadium	139.2	40.79	99.01	mg/Kg	99%		75-125	0.99
Zinc	221.9	120.6	99.01	mg/Kg	102%		75-125	0.99

Type:	Serial Dilution	Lab ID:	QC1344039	Batch:	396206
Matrix (Source ID):	Soil (553922-001)	Method:	EPA 6020	Prep Method:	EPA 3050B

QC1344039 Analyte	Result	Source Sample Result	Units	Qual	RPD	RPD Lim	DF
Antimony	ND	ND	mg/Kg				5
Arsenic	2.545	3.065	mg/Kg	J			5
Barium	106.6	107.9	mg/Kg				5
Beryllium	ND	0.3218	mg/Kg				5
Cadmium	ND	ND	mg/Kg				5
Chromium	23.59	24.13	mg/Kg				5
Cobalt	8.975	8.539	mg/Kg				5
Copper	30.91	29.98	mg/Kg				5
Lead	36.92	37.22	mg/Kg				5
Molybdenum	ND	ND	mg/Kg				5
Nickel	19.23	18.79	mg/Kg				5
Selenium	ND	ND	mg/Kg				5
Silver	ND	ND	mg/Kg				5
Thallium	ND	ND	mg/Kg				5
Vanadium	42.96	40.79	mg/Kg				5
Zinc	120.6	120.6	mg/Kg				5

Type:	Blank	Lab ID:	QC1343506	Batch:	396198
Matrix:	Soil	Method:	EPA 7471A	Prep Method:	EPA 7471A

QC1343506 Analyte	Result	Qual	Units	RL	Prepared	Analyzed
Mercury	ND		mg/Kg	0.14	02/24/26	02/24/26

ENTHALPY ANALYTICAL

Batch QC

Type: Lab Control Sample	Lab ID: QC1343507	Batch: 396198
Matrix: Soil	Method: EPA 7471A	Prep Method: EPA 7471A

QC1343507 Analyte	Result	Spiked	Units	Recovery	Qual	Limits
Mercury	0.8022	0.8333	mg/Kg	96%		80-120

Type: Matrix Spike	Lab ID: QC1343508	Batch: 396198
Matrix (Source ID): Soil (553759-001)	Method: EPA 7471A	Prep Method: EPA 7471A

QC1343508 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	DF
Mercury	1.120	0.03138	0.9615	mg/Kg	113%		75-125	1.2

Type: Matrix Spike Duplicate	Lab ID: QC1343509	Batch: 396198
Matrix (Source ID): Soil (553759-001)	Method: EPA 7471A	Prep Method: EPA 7471A

QC1343509 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	RPD	RPD Lim	DF
Mercury	1.044	0.03138	0.9615	mg/Kg	105%		75-125	7	20	1.2

Type: Lab Control Sample	Lab ID: QC1344122	Batch: 396341
Matrix: Water	Method: EPA 8015B	Prep Method: EPA 5030B

QC1344122 Analyte	Result	Spiked	Units	Recovery	Qual	Limits
TPH Gasoline	608.1	500.0	ug/L	122%		80-131
Surrogates						
Bromofluorobenzene (FID)	177.9	200.0	ug/L	89%		80-120

Type: Matrix Spike	Lab ID: QC1344123	Batch: 396341
Matrix (Source ID): Water (554009-001)	Method: EPA 8015B	Prep Method: EPA 5030B

QC1344123 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	DF
TPH Gasoline	611.0	ND	500.0	ug/L	122%		80-128	1
Surrogates								
Bromofluorobenzene (FID)	177.7		200.0	ug/L	89%		80-120	1

Type: Matrix Spike Duplicate	Lab ID: QC1344124	Batch: 396341
Matrix (Source ID): Water (554009-001)	Method: EPA 8015B	Prep Method: EPA 5030B

QC1344124 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	RPD	RPD Lim	DF
TPH Gasoline	612.7	ND	500.0	ug/L	123%		80-128	0	20	1
Surrogates										
Bromofluorobenzene (FID)	180.8		200.0	ug/L	90%		80-120			1

ENTHALPY ANALYTICAL

Batch QC

Type: Blank	Lab ID: QC1344125	Batch: 396341
Matrix: Water	Method: EPA 8015B	Prep Method: EPA 5030B

QC1344125 Analyte	Result	Qual	Units	RL	Prepared	Analyzed
TPH Gasoline	ND		ug/L	50	02/25/26	02/25/26
Surrogates				**Limits**		
Bromofluorobenzene (FID)	86%		%REC	80-120	02/25/26	02/25/26

Type: Lab Control Sample	Lab ID: QC1344558	Batch: 396469
Matrix: Soil	Method: EPA 8015B	Prep Method: EPA 5035

QC1344558 Analyte	Result	Spiked	Units	Recovery	Qual	Limits
TPH Gasoline	5.730	5.000	mg/Kg	115%		80-124
Surrogates						
Bromofluorobenzene (FID)	0.1664	0.2000	mg/Kg	83%		59-122

Type: Matrix Spike	Lab ID: QC1344559	Batch: 396469
Matrix (Source ID): Soil (553919-001)	Method: EPA 8015B	Prep Method: EPA 5030B

QC1344559 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	DF
TPH Gasoline	5.744	ND	5.112	mg/Kg	112%		74-126	1
Surrogates								
Bromofluorobenzene (FID)	0.1712		0.2045	mg/Kg	84%		59-122	1

Type: Matrix Spike Duplicate	Lab ID: QC1344560	Batch: 396469
Matrix (Source ID): Soil (553919-001)	Method: EPA 8015B	Prep Method: EPA 5030B

QC1344560 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	RPD	RPD Lim	DF
TPH Gasoline	5.736	ND	5.102	mg/Kg	112%		74-126	0	24	1
Surrogates										
Bromofluorobenzene (FID)	0.1701		0.2041	mg/Kg	83%		59-122			1

Type: Blank	Lab ID: QC1344561	Batch: 396469
Matrix: Soil	Method: EPA 8015B	Prep Method: EPA 5035

QC1344561 Analyte	Result	Qual	Units	RL	Prepared	Analyzed
TPH Gasoline	ND		mg/Kg	3.0	02/26/26	02/26/26
Surrogates				**Limits**		
Bromofluorobenzene (FID)	86%		%REC	59-122	02/26/26	02/26/26

Batch QC

Type: Blank	Lab ID: QC1344502	Batch: 396457
Matrix: Soil	Method: EPA 8015M	Prep Method: EPA 3580M

QC1344502 Analyte	Result	Qual	Units	RL	Prepared	Analyzed
GRO C8-C10	ND		mg/Kg	10	02/25/26	02/25/26
DRO C10-C28	ND		mg/Kg	10	02/25/26	02/25/26
ORO C28-C44	ND		mg/Kg	20	02/25/26	02/25/26
Surrogates				**Limits**		
n-Triacontane	89%		%REC	59-136	02/25/26	02/25/26

Type: Lab Control Sample	Lab ID: QC1344503	Batch: 396457
Matrix: Soil	Method: EPA 8015M	Prep Method: EPA 3580M

QC1344503 Analyte	Result	Spiked	Units	Recovery	Qual	Limits
Diesel C10-C28	216.6	249.1	mg/Kg	87%		61-120
Surrogates						
n-Triacontane	8.660	9.965	mg/Kg	87%		59-136

Type: Matrix Spike	Lab ID: QC1344504	Batch: 396457
Matrix (Source ID): Soil (553759-001)	Method: EPA 8015M	Prep Method: EPA 3580M

QC1344504 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	DF
Diesel C10-C28	223.1	ND	249.4	mg/Kg	89%		47-127	1
Surrogates								
n-Triacontane	8.837		9.975	mg/Kg	89%		59-136	1

Type: Matrix Spike Duplicate	Lab ID: QC1344505	Batch: 396457
Matrix (Source ID): Soil (553759-001)	Method: EPA 8015M	Prep Method: EPA 3580M

QC1344505 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	RPD	RPD Lim	DF
Diesel C10-C28	225.2	ND	249.6	mg/Kg	90%		47-127	1	48	1
Surrogates										
n-Triacontane	8.780		9.985	mg/Kg	88%		59-136			1

ENTHALPY ANALYTICAL

Batch QC

Type:	**Blank**	**Lab ID:**	**QC1344486**	**Batch:**	**396454**
Matrix:	**Soil**	**Method:**	**EPA 8081A**	**Prep Method:**	**EPA 3546**

QC1344486 Analyte	Result	Qual	Units	RL	Prepared	Analyzed
alpha-BHC	ND		ug/Kg	5.0	02/26/26	02/26/26
beta-BHC	ND		ug/Kg	5.0	02/26/26	02/26/26
gamma-BHC	ND		ug/Kg	5.0	02/26/26	02/26/26
delta-BHC	ND		ug/Kg	5.0	02/26/26	02/26/26
Heptachlor	ND		ug/Kg	5.0	02/26/26	02/26/26
Aldrin	ND		ug/Kg	5.0	02/26/26	02/26/26
Heptachlor epoxide	ND		ug/Kg	5.0	02/26/26	02/26/26
Endosulfan I	ND		ug/Kg	5.0	02/26/26	02/26/26
Dieldrin	ND		ug/Kg	5.0	02/26/26	02/26/26
4,4'-DDE	ND		ug/Kg	5.0	02/26/26	02/26/26
Endrin	ND		ug/Kg	5.0	02/26/26	02/26/26
Endosulfan II	ND		ug/Kg	5.0	02/26/26	02/26/26
Endosulfan sulfate	ND		ug/Kg	5.0	02/26/26	02/26/26
4,4'-DDD	ND		ug/Kg	5.0	02/26/26	02/26/26
Endrin aldehyde	ND		ug/Kg	5.0	02/26/26	02/26/26
Endrin ketone	ND		ug/Kg	5.0	02/26/26	02/26/26
4,4'-DDT	ND		ug/Kg	5.0	02/26/26	02/26/26
Methoxychlor	ND		ug/Kg	10	02/26/26	02/26/26
Toxaphene	ND		ug/Kg	100	02/26/26	02/26/26
Chlordane (Technical)	ND		ug/Kg	50	02/26/26	02/26/26
Surrogates				**Limits**		
TCMX	88%		%REC	58-120	02/26/26	02/26/26
Decachlorobiphenyl	78%		%REC	47-120	02/26/26	02/26/26

ENTHALPY ANALYTICAL

Batch QC

Type:	**Lab Control Sample**	**Lab ID:**	**QC1344487**	**Batch:**	**396454**
Matrix:	**Soil**	**Method:**	**EPA 8081A**	**Prep Method:**	**EPA 3546**

QC1344487 Analyte	Result	Spiked	Units	Recovery	Qual	Limits
alpha-BHC	47.49	50.00	ug/Kg	95%		53-132
beta-BHC	47.84	50.00	ug/Kg	96%		59-131
gamma-BHC	48.26	50.00	ug/Kg	97%		54-132
delta-BHC	47.81	50.00	ug/Kg	96%		54-134
Heptachlor	45.50	50.00	ug/Kg	91%		50-130
Aldrin	40.73	50.00	ug/Kg	81%		46-120
Heptachlor epoxide	41.33	50.00	ug/Kg	83%		52-127
Endosulfan I	41.82	50.00	ug/Kg	84%		53-132
Dieldrin	41.68	50.00	ug/Kg	83%		53-134
4,4'-DDE	44.30	50.00	ug/Kg	89%		53-140
Endrin	46.88	50.00	ug/Kg	94%		53-142
Endosulfan II	45.12	50.00	ug/Kg	90%		53-138
Endosulfan sulfate	43.53	50.00	ug/Kg	87%		50-134
4,4'-DDD	43.03	50.00	ug/Kg	86%		50-136
Endrin aldehyde	37.23	50.00	ug/Kg	74%		15-120
Endrin ketone	41.21	50.00	ug/Kg	82%		50-146
4,4'-DDT	37.78	50.00	ug/Kg	76%		46-142
Methoxychlor	40.79	50.00	ug/Kg	82%		48-156
Surrogates						
TCMX	43.74	50.00	ug/Kg	87%		58-120
Decachlorobiphenyl	38.55	50.00	ug/Kg	77%		47-120

Batch QC

Type:	**Matrix Spike**	**Lab ID:**	**QC1344493**	**Batch:**	**396454**
Matrix (Source ID):	**Soil (553922-042)**	**Method:**	**EPA 8081A**	**Prep Method:**	**EPA 3546**

QC1344493 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	DF
alpha-BHC	45.89	ND	50.00	ug/Kg	92%		52-120	1
beta-BHC	53.75	ND	50.00	ug/Kg	108%		57-126	1
gamma-BHC	46.96	ND	50.00	ug/Kg	94%		54-122	1
delta-BHC	45.85	ND	50.00	ug/Kg	92%		44-127	1
Heptachlor	44.06	ND	50.00	ug/Kg	88%		51-122	1
Aldrin	40.36	ND	50.00	ug/Kg	81%		51-120	1
Heptachlor epoxide	40.68	ND	50.00	ug/Kg	81%		50-122	1
Endosulfan I	41.01	ND	50.00	ug/Kg	82%		48-123	1
Dieldrin	41.65	ND	50.00	ug/Kg	83%		48-128	1
4,4'-DDE	43.81	ND	50.00	ug/Kg	88%		50-139	1
Endrin	45.36	ND	50.00	ug/Kg	91%		53-132	1
Endosulfan II	44.51	ND	50.00	ug/Kg	89%		47-131	1
Endosulfan sulfate	41.50	ND	50.00	ug/Kg	83%		40-126	1
4,4'-DDD	43.24	ND	50.00	ug/Kg	86%		48-130	1
Endrin aldehyde	34.70	ND	50.00	ug/Kg	69%		26-120	1
Endrin ketone	40.02	ND	50.00	ug/Kg	80%		51-133	1
4,4'-DDT	36.04	ND	50.00	ug/Kg	72%		40-144	1
Methoxychlor	48.40	ND	50.00	ug/Kg	97%		49-148	1
Surrogates								
TCMX	42.42		50.00	ug/Kg	85%		58-120	1
Decachlorobiphenyl	37.26		50.00	ug/Kg	75%		47-120	1

ENTHALPY ANALYTICAL

Batch QC

Type:	**Matrix Spike Duplicate**	**Lab ID:**	**QC1344494**	**Batch:**	**396454**
Matrix (Source ID):	**Soil (553922-042)**	**Method:**	**EPA 8081A**	**Prep Method:**	**EPA 3546**

QC1344494 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	RPD	RPD Lim	DF
alpha-BHC	48.44	ND	50.00	ug/Kg	97%		52-120	5	37	1
beta-BHC	53.37	ND	50.00	ug/Kg	107%		57-126	1	38	1
gamma-BHC	49.69	ND	50.00	ug/Kg	99%		54-122	6	39	1
delta-BHC	48.94	ND	50.00	ug/Kg	98%		44-127	7	54	1
Heptachlor	46.65	ND	50.00	ug/Kg	93%		51-122	6	44	1
Aldrin	42.51	ND	50.00	ug/Kg	85%		51-120	5	39	1
Heptachlor epoxide	43.19	ND	50.00	ug/Kg	86%		50-122	6	39	1
Endosulfan I	43.47	ND	50.00	ug/Kg	87%		48-123	6	47	1
Dieldrin	44.05	ND	50.00	ug/Kg	88%		48-128	6	43	1
4,4'-DDE	46.17	ND	50.00	ug/Kg	92%		50-139	5	42	1
Endrin	47.78	ND	50.00	ug/Kg	96%		53-132	5	45	1
Endosulfan II	46.71	ND	50.00	ug/Kg	93%		47-131	5	46	1
Endosulfan sulfate	43.65	ND	50.00	ug/Kg	87%		40-126	5	52	1
4,4'-DDD	45.61	ND	50.00	ug/Kg	91%		48-130	5	46	1
Endrin aldehyde	37.04	ND	50.00	ug/Kg	74%		26-120	7	57	1
Endrin ketone	42.60	ND	50.00	ug/Kg	85%		51-133	6	43	1
4,4'-DDT	37.77	ND	50.00	ug/Kg	76%		40-144	5	56	1
Methoxychlor	45.97	ND	50.00	ug/Kg	92%		49-148	5	53	1
Surrogates										
TCMX	44.36		50.00	ug/Kg	89%		58-120			1
Decachlorobiphenyl	36.45		50.00	ug/Kg	73%		47-120			1

ENTHALPY ANALYTICAL

Batch QC

Type:	**Blank**	**Lab ID:**	**QC1345368**	**Batch:**	**396712**
Matrix:	**Soil**	**Method:**	**EPA 8081A**	**Prep Method:**	**EPA 3546**

QC1345368 Analyte	Result	Qual	Units	RL	Prepared	Analyzed
alpha-BHC	ND		ug/Kg	5.1	02/28/26	03/01/26
beta-BHC	ND		ug/Kg	5.1	02/28/26	03/01/26
gamma-BHC	ND		ug/Kg	5.1	02/28/26	03/01/26
delta-BHC	ND		ug/Kg	5.1	02/28/26	03/01/26
Heptachlor	ND		ug/Kg	5.1	02/28/26	03/01/26
Aldrin	ND		ug/Kg	5.1	02/28/26	03/01/26
Heptachlor epoxide	ND		ug/Kg	5.1	02/28/26	03/01/26
Endosulfan I	ND		ug/Kg	5.1	02/28/26	03/01/26
Dieldrin	ND		ug/Kg	5.1	02/28/26	03/01/26
4,4'-DDE	ND		ug/Kg	5.1	02/28/26	03/01/26
Endrin	ND		ug/Kg	5.1	02/28/26	03/01/26
Endosulfan II	ND		ug/Kg	5.1	02/28/26	03/01/26
Endosulfan sulfate	ND		ug/Kg	5.1	02/28/26	03/01/26
4,4'-DDD	ND		ug/Kg	5.1	02/28/26	03/01/26
Endrin aldehyde	ND		ug/Kg	5.1	02/28/26	03/01/26
Endrin ketone	ND		ug/Kg	5.1	02/28/26	03/01/26
4,4'-DDT	ND		ug/Kg	5.1	02/28/26	03/01/26
Methoxychlor	ND		ug/Kg	10	02/28/26	03/01/26
Toxaphene	ND		ug/Kg	100	02/28/26	03/01/26
Chlordane (Technical)	ND		ug/Kg	51	02/28/26	03/01/26
Surrogates				**Limits**		
TCMX	92%		%REC	58-120	02/28/26	03/01/26
Decachlorobiphenyl	94%		%REC	47-120	02/28/26	03/01/26

ENTHALPY ANALYTICAL

Batch QC

Type: Lab Control Sample	**Lab ID: QC1345369**	**Batch: 396712**
Matrix: Soil	**Method: EPA 8081A**	**Prep Method: EPA 3546**

QC1345369 Analyte	Result	Spiked	Units	Recovery	Qual	Limits
alpha-BHC	52.64	51.02	ug/Kg	103%		53-132
beta-BHC	49.48	51.02	ug/Kg	97%		59-131
gamma-BHC	53.90	51.02	ug/Kg	106%		54-132
delta-BHC	57.06	51.02	ug/Kg	112%		54-134
Heptachlor	49.91	51.02	ug/Kg	98%		50-130
Aldrin	45.99	51.02	ug/Kg	90%		46-120
Heptachlor epoxide	49.00	51.02	ug/Kg	96%		52-127
Endosulfan I	50.04	51.02	ug/Kg	98%		53-132
Dieldrin	48.26	51.02	ug/Kg	95%		53-134
4,4'-DDE	53.33	51.02	ug/Kg	105%		53-140
Endrin	54.79	51.02	ug/Kg	107%	#	53-142
Endosulfan II	49.90	51.02	ug/Kg	98%		53-138
Endosulfan sulfate	53.35	51.02	ug/Kg	105%		50-134
4,4'-DDD	49.26	51.02	ug/Kg	97%		50-136
Endrin aldehyde	44.57	51.02	ug/Kg	87%		15-120
Endrin ketone	58.42	51.02	ug/Kg	115%		50-146
4,4'-DDT	49.72	51.02	ug/Kg	97%		46-142
Methoxychlor	52.62	51.02	ug/Kg	103%		48-156
Surrogates						
TCMX	44.63	51.02	ug/Kg	87%		58-120
Decachlorobiphenyl	43.68	51.02	ug/Kg	86%		47-120

ENTHALPY ANALYTICAL

Batch QC

Type:	**Matrix Spike**	**Lab ID:**	**QC1345375**	**Batch:**	**396712**
Matrix (Source ID):	**Soil (553880-001)**	**Method:**	**EPA 8081A**	**Prep Method:**	**EPA 3546**

QC1345375 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	DF
alpha-BHC	45.36	ND	50.00	ug/Kg	91%		52-120	1
beta-BHC	39.43	ND	50.00	ug/Kg	79%		57-126	1
gamma-BHC	45.82	ND	50.00	ug/Kg	92%		54-122	1
delta-BHC	49.54	ND	50.00	ug/Kg	99%		44-127	1
Heptachlor	43.29	ND	50.00	ug/Kg	87%		51-122	1
Aldrin	42.10	ND	50.00	ug/Kg	84%		51-120	1
Heptachlor epoxide	44.75	2.930	50.00	ug/Kg	84%		50-122	1
Endosulfan I	41.56	ND	50.00	ug/Kg	83%		48-123	1
Dieldrin	52.88	10.68	50.00	ug/Kg	84%		48-128	1
4,4'-DDE	96.83	47.97	50.00	ug/Kg	98%		50-139	1
Endrin	49.35	ND	50.00	ug/Kg	99%	#	53-132	1
Endosulfan II	43.01	ND	50.00	ug/Kg	86%		47-131	1
Endosulfan sulfate	46.23	ND	50.00	ug/Kg	92%		40-126	1
4,4'-DDD	28.18	ND	50.00	ug/Kg	56%		48-130	1
Endrin aldehyde	37.65	ND	50.00	ug/Kg	75%		26-120	1
Endrin ketone	48.95	ND	50.00	ug/Kg	98%		51-133	1
4,4'-DDT	65.74	16.63	50.00	ug/Kg	98%		40-144	1
Methoxychlor	46.25	ND	50.00	ug/Kg	93%		49-148	1
Surrogates								
TCMX	38.95		50.00	ug/Kg	78%		58-120	1
Decachlorobiphenyl	47.26		50.00	ug/Kg	95%		47-120	1

ENTHALPY ANALYTICAL

Batch QC

Type:	**Matrix Spike Duplicate**	**Lab ID:**	**QC1345376**	**Batch:**	**396712**
Matrix (Source ID):	**Soil (553880-001)**	**Method:**	**EPA 8081A**	**Prep Method:**	**EPA 3546**

QC1345376 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	RPD	RPD Lim	DF
alpha-BHC	48.50	ND	51.02	ug/Kg	95%		52-120	5	37	1
beta-BHC	42.64	ND	51.02	ug/Kg	84%		57-126	6	38	1
gamma-BHC	48.67	ND	51.02	ug/Kg	95%		54-122	4	39	1
delta-BHC	53.73	ND	51.02	ug/Kg	105%		44-127	6	54	1
Heptachlor	46.18	ND	51.02	ug/Kg	91%		51-122	4	44	1
Aldrin	46.10	ND	51.02	ug/Kg	90%		51-120	7	39	1
Heptachlor epoxide	47.41	2.930	51.02	ug/Kg	87%		50-122	4	39	1
Endosulfan I	46.66	ND	51.02	ug/Kg	91%		48-123	10	47	1
Dieldrin	56.23	10.68	51.02	ug/Kg	89%		48-128	4	43	1
4,4'-DDE	100.1	47.97	51.02	ug/Kg	102%		50-139	2	42	1
Endrin	51.38	ND	51.02	ug/Kg	101%	#	53-132	2	45	1
Endosulfan II	46.66	ND	51.02	ug/Kg	91%		47-131	6	46	1
Endosulfan sulfate	49.34	ND	51.02	ug/Kg	97%		40-126	4	52	1
4,4'-DDD	45.41	ND	51.02	ug/Kg	89%		48-130	45	46	1
Endrin aldehyde	41.95	ND	51.02	ug/Kg	82%		26-120	9	57	1
Endrin ketone	52.39	ND	51.02	ug/Kg	103%		51-133	5	43	1
4,4'-DDT	64.44	16.63	51.02	ug/Kg	94%		40-144	4	56	1
Methoxychlor	49.78	ND	51.02	ug/Kg	98%		49-148	5	53	1
Surrogates										
TCMX	39.25		51.02	ug/Kg	77%		58-120			1
Decachlorobiphenyl	48.05		51.02	ug/Kg	94%		47-120			1

Batch QC

Type: Blank	Lab ID: QC1343118	Batch: 396077
Matrix: Water		

QC1343118 Analyte	Result	Qual	Units	RL	Prepared	Analyzed
Method: EPA 8081A Prep Method: EPA 3510C						
alpha-BHC	ND		ug/L	0.05	02/22/26	02/25/26
beta-BHC	ND		ug/L	0.05	02/22/26	02/25/26
gamma-BHC	ND		ug/L	0.05	02/22/26	02/25/26
delta-BHC	ND		ug/L	0.05	02/22/26	02/25/26
Heptachlor	ND		ug/L	0.05	02/22/26	02/25/26
Aldrin	ND		ug/L	0.05	02/22/26	02/25/26
Heptachlor epoxide	ND		ug/L	0.05	02/22/26	02/25/26
Endosulfan I	ND		ug/L	0.05	02/22/26	02/25/26
Dieldrin	ND		ug/L	0.1	02/22/26	02/25/26
4,4'-DDE	ND		ug/L	0.1	02/22/26	02/25/26
Endrin	ND		ug/L	0.1	02/22/26	02/25/26
Endosulfan II	ND		ug/L	0.1	02/22/26	02/25/26
Endosulfan sulfate	ND		ug/L	0.1	02/22/26	02/25/26
4,4'-DDD	ND		ug/L	0.1	02/22/26	02/25/26
Endrin aldehyde	ND		ug/L	0.1	02/22/26	02/25/26
Endrin ketone	ND		ug/L	0.1	02/22/26	02/25/26
4,4'-DDT	ND		ug/L	0.1	02/22/26	02/25/26
Methoxychlor	ND		ug/L	0.1	02/22/26	02/25/26
Toxaphene	ND		ug/L	2.0	02/22/26	02/25/26
Chlordane (Technical)	ND		ug/L	1.0	02/22/26	02/25/26
Surrogates				**Limits**		
TCMX	61%		%REC	29-120	02/22/26	02/25/26
Decachlorobiphenyl	90%		%REC	33-132	02/22/26	02/25/26
Method: EPA 8082 Prep Method: EPA 3510C						
Aroclor-1016	ND		ug/L	0.50	02/22/26	02/25/26
Aroclor-1221	ND		ug/L	0.50	02/22/26	02/25/26
Aroclor-1232	ND		ug/L	0.50	02/22/26	02/25/26
Aroclor-1242	ND		ug/L	0.50	02/22/26	02/25/26
Aroclor-1248	ND		ug/L	0.50	02/22/26	02/25/26
Aroclor-1254	ND		ug/L	0.50	02/22/26	02/25/26
Aroclor-1260	ND		ug/L	0.50	02/22/26	02/25/26
Aroclor-1262	ND		ug/L	0.50	02/22/26	02/25/26
Aroclor-1268	ND		ug/L	0.50	02/22/26	02/25/26
Total PCBs	ND		ug/L	0.50	02/22/26	02/25/26
Surrogates				**Limits**		
Decachlorobiphenyl (PCB)	66%		%REC	28-138	02/22/26	02/25/26

ENTHALPY ANALYTICAL

Batch QC

Type:	**Lab Control Sample**	**Lab ID:**	**QC1343119**	**Batch:**	**396077**
Matrix:	**Water**	**Method:**	**EPA 8081A**	**Prep Method:**	**EPA 3510C**

QC1343119 Analyte	Result	Spiked	Units	Recovery	Qual	Limits
alpha-BHC	0.5820	0.5000	ug/L	116%		66-121
beta-BHC	0.5036	0.5000	ug/L	101%		73-120
gamma-BHC	0.5751	0.5000	ug/L	115%		68-125
delta-BHC	0.6048	0.5000	ug/L	121%		68-131
Heptachlor	0.5575	0.5000	ug/L	112%		63-120
Aldrin	0.5066	0.5000	ug/L	101%		56-120
Heptachlor epoxide	0.5066	0.5000	ug/L	101%		65-120
Endosulfan I	0.5282	0.5000	ug/L	106%		68-124
Dieldrin	0.5117	0.5000	ug/L	102%		66-124
4,4'-DDE	0.5771	0.5000	ug/L	115%		67-131
Endrin	0.5664	0.5000	ug/L	113%		68-135
Endosulfan II	0.5169	0.5000	ug/L	103%		71-130
Endosulfan sulfate	0.5706	0.5000	ug/L	114%		68-128
4,4'-DDD	0.5348	0.5000	ug/L	107%		65-130
Endrin aldehyde	0.4895	0.5000	ug/L	98%		67-124
Endrin ketone	0.5896	0.5000	ug/L	118%		69-137
4,4'-DDT	0.5526	0.5000	ug/L	111%		65-136
Methoxychlor	0.5817	0.5000	ug/L	116%		69-150
Surrogates						
TCMX	0.4030	0.5000	ug/L	81%		29-120
Decachlorobiphenyl	0.5506	0.5000	ug/L	110%		33-132

ENTHALPY ANALYTICAL

Batch QC

Type:	Lab Control Sample Duplicate	Lab ID:	QC1343120	Batch:	396077
Matrix:	Water	Method:	EPA 8081A	Prep Method:	EPA 3510C

QC1343120 Analyte	Result	Spiked	Units	Recovery	Qual	Limits	RPD	RPD Lim
alpha-BHC	0.5242	0.5000	ug/L	105%		66-121	10	20
beta-BHC	0.4595	0.5000	ug/L	92%		73-120	9	20
gamma-BHC	0.5102	0.5000	ug/L	102%		68-125	12	20
delta-BHC	0.5429	0.5000	ug/L	109%		68-131	11	20
Heptachlor	0.4883	0.5000	ug/L	98%		63-120	13	24
Aldrin	0.4468	0.5000	ug/L	89%		56-120	13	30
Heptachlor epoxide	0.4498	0.5000	ug/L	90%		65-120	12	20
Endosulfan I	0.4733	0.5000	ug/L	95%		68-124	11	20
Dieldrin	0.4657	0.5000	ug/L	93%		66-124	9	22
4,4'-DDE	0.5143	0.5000	ug/L	103%		67-131	12	21
Endrin	0.5116	0.5000	ug/L	102%		68-135	10	20
Endosulfan II	0.4701	0.5000	ug/L	94%		71-130	9	21
Endosulfan sulfate	0.5303	0.5000	ug/L	106%		68-128	7	21
4,4'-DDD	0.4800	0.5000	ug/L	96%		65-130	11	22
Endrin aldehyde	0.4516	0.5000	ug/L	90%		67-124	8	20
Endrin ketone	0.5806	0.5000	ug/L	116%		69-137	2	21
4,4'-DDT	0.5169	0.5000	ug/L	103%		65-136	7	23
Methoxychlor	0.5628	0.5000	ug/L	113%		69-150	3	23
Surrogates								
TCMX	0.3680	0.5000	ug/L	74%		29-120		
Decachlorobiphenyl	0.5513	0.5000	ug/L	110%		33-132		

Type:	Lab Control Sample	Lab ID:	QC1343121	Batch:	396077
Matrix:	Water	Method:	EPA 8082	Prep Method:	EPA 3510C

QC1343121 Analyte	Result	Spiked	Units	Recovery	Qual	Limits
Aroclor-1016	5.021	5.000	ug/L	100%		69-120
Aroclor-1260	4.668	5.000	ug/L	93%		72-124
Surrogates						
Decachlorobiphenyl (PCB)	0.3945	0.5000	ug/L	79%		28-138

Type:	Lab Control Sample Duplicate	Lab ID:	QC1343122	Batch:	396077
Matrix:	Water	Method:	EPA 8082	Prep Method:	EPA 3510C

QC1343122 Analyte	Result	Spiked	Units	Recovery	Qual	Limits	RPD	RPD Lim
Aroclor-1016	4.883	5.000	ug/L	98%		69-120	3	22
Aroclor-1260	4.546	5.000	ug/L	91%		72-124	3	25
Surrogates								
Decachlorobiphenyl (PCB)	0.3967	0.5000	ug/L	79%		28-138		

ENTHALPY ANALYTICAL

Batch QC

Type: Blank	Lab ID: QC1344552	Batch: 396467
Matrix: Soil	Method: EPA 8082	Prep Method: EPA 3546

QC1344552 Analyte	Result	Qual	Units	RL	Prepared	Analyzed
Aroclor-1016	ND		ug/Kg	50	02/26/26	02/26/26
Aroclor-1221	ND		ug/Kg	50	02/26/26	02/26/26
Aroclor-1232	ND		ug/Kg	50	02/26/26	02/26/26
Aroclor-1242	ND		ug/Kg	50	02/26/26	02/26/26
Aroclor-1248	ND		ug/Kg	50	02/26/26	02/26/26
Aroclor-1254	ND		ug/Kg	50	02/26/26	02/26/26
Aroclor-1260	ND		ug/Kg	50	02/26/26	02/26/26
Aroclor-1262	ND		ug/Kg	50	02/26/26	02/26/26
Aroclor-1268	ND		ug/Kg	50	02/26/26	02/26/26
Total PCBs	ND		ug/Kg	50	02/26/26	02/26/26
Surrogates				**Limits**		
Decachlorobiphenyl (PCB)	101%		%REC	50-127	02/26/26	02/26/26

Type: Lab Control Sample	Lab ID: QC1344553	Batch: 396467
Matrix: Soil	Method: EPA 8082	Prep Method: EPA 3546

QC1344553 Analyte	Result	Spiked	Units	Recovery	Qual	Limits
Aroclor-1016	455.2	498.0	ug/Kg	91%		66-120
Aroclor-1260	471.2	498.0	ug/Kg	95%		63-126
Surrogates						
Decachlorobiphenyl (PCB)	42.20	49.80	ug/Kg	85%		50-127

Type: Matrix Spike	Lab ID: QC1344554	Batch: 396467
Matrix (Source ID): Soil (553922-004)	Method: EPA 8082	Prep Method: EPA 3546

QC1344554 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	DF
Aroclor-1016	464.1	ND	501.0	ug/Kg	93%		60-123	1
Aroclor-1260	505.0	ND	501.0	ug/Kg	101%		55-136	1
Surrogates								
Decachlorobiphenyl (PCB)	49.05		50.10	ug/Kg	98%		50-127	1

Type: Matrix Spike Duplicate	Lab ID: QC1344555	Batch: 396467
Matrix (Source ID): Soil (553922-004)	Method: EPA 8082	Prep Method: EPA 3546

QC1344555 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	RPD	RPD Lim	DF
Aroclor-1016	456.4	ND	503.5	ug/Kg	91%		60-123	2	37	1
Aroclor-1260	518.8	ND	503.5	ug/Kg	103%		55-136	2	41	1
Surrogates										
Decachlorobiphenyl (PCB)	50.56		50.35	ug/Kg	100%		50-127			1

ENTHALPY ANALYTICAL

Batch QC

Type: Lab Control Sample	Lab ID: QC1343541	Batch: 396207
Matrix: Water	Method: EPA 8260B	Prep Method: EPA 5030B

QC1343541 Analyte	Result	Spiked	Units	Recovery	Qual	Limits
1,1-Dichloroethene	42.89	50.00	ug/L	86%		69-128
MTBE	49.99	50.00	ug/L	100%		66-125
Benzene	46.02	50.00	ug/L	92%		76-121
Trichloroethene	46.22	50.00	ug/L	92%		76-124
Toluene	45.54	50.00	ug/L	91%		76-120
Chlorobenzene	46.92	50.00	ug/L	94%		78-120
Surrogates						
Dibromofluoromethane	53.01	50.00	ug/L	106%		70-130
1,2-Dichloroethane-d4	48.37	50.00	ug/L	97%		70-130
Toluene-d8	49.79	50.00	ug/L	100%		70-130
Bromofluorobenzene	50.24	50.00	ug/L	100%		70-130

Type: Lab Control Sample Duplicate	Lab ID: QC1343542	Batch: 396207
Matrix: Water	Method: EPA 8260B	Prep Method: EPA 5030B

QC1343542 Analyte	Result	Spiked	Units	Recovery	Qual	Limits	RPD	RPD Lim
1,1-Dichloroethene	36.61	50.00	ug/L	73%		69-128	16	23
MTBE	43.81	50.00	ug/L	88%		66-125	13	22
Benzene	40.38	50.00	ug/L	81%		76-121	13	21
Trichloroethene	41.46	50.00	ug/L	83%		76-124	11	22
Toluene	41.37	50.00	ug/L	83%		76-120	10	21
Chlorobenzene	42.19	50.00	ug/L	84%		78-120	11	20
Surrogates								
Dibromofluoromethane	51.94	50.00	ug/L	104%		70-130		
1,2-Dichloroethane-d4	50.10	50.00	ug/L	100%		70-130		
Toluene-d8	51.19	50.00	ug/L	102%		70-130		
Bromofluorobenzene	51.08	50.00	ug/L	102%		70-130		

ENTHALPY ANALYTICAL

Batch QC

Type:	**Blank**	**Lab ID:**	**QC1343546**	**Batch:**	**396207**
Matrix:	**Water**	**Method:**	**EPA 8260B**	**Prep Method:**	**EPA 5030B**

QC1343546 Analyte	Result	Qual	Units	RL	Prepared	Analyzed
3-Chloropropene	ND		ug/L	5.0	02/24/26	02/24/26
Freon 12	ND		ug/L	5.0	02/24/26	02/24/26
Chloromethane	ND		ug/L	5.0	02/24/26	02/24/26
Vinyl Chloride	ND		ug/L	5.0	02/24/26	02/24/26
Bromomethane	ND		ug/L	5.0	02/24/26	02/24/26
Chloroethane	ND		ug/L	5.0	02/24/26	02/24/26
Trichlorofluoromethane	ND		ug/L	5.0	02/24/26	02/24/26
Acetone	ND		ug/L	100	02/24/26	02/24/26
Freon 113	ND		ug/L	5.0	02/24/26	02/24/26
1,1-Dichloroethene	ND		ug/L	5.0	02/24/26	02/24/26
Methylene Chloride	ND		ug/L	5.0	02/24/26	02/24/26
MTBE	ND		ug/L	5.0	02/24/26	02/24/26
trans-1,2-Dichloroethene	ND		ug/L	5.0	02/24/26	02/24/26
1,1-Dichloroethane	ND		ug/L	5.0	02/24/26	02/24/26
2-Butanone	ND		ug/L	100	02/24/26	02/24/26
cis-1,2-Dichloroethene	ND		ug/L	5.0	02/24/26	02/24/26
2,2-Dichloropropane	ND		ug/L	5.0	02/24/26	02/24/26
Chloroform	ND		ug/L	5.0	02/24/26	02/24/26
Bromochloromethane	ND		ug/L	5.0	02/24/26	02/24/26
1,1,1-Trichloroethane	ND		ug/L	5.0	02/24/26	02/24/26
1,1-Dichloropropene	ND		ug/L	5.0	02/24/26	02/24/26
Carbon Tetrachloride	ND		ug/L	5.0	02/24/26	02/24/26
1,2-Dichloroethane	ND		ug/L	5.0	02/24/26	02/24/26
Benzene	ND		ug/L	5.0	02/24/26	02/24/26
Trichloroethene	ND		ug/L	5.0	02/24/26	02/24/26
1,2-Dichloropropane	ND		ug/L	5.0	02/24/26	02/24/26
Bromodichloromethane	ND		ug/L	5.0	02/24/26	02/24/26
Dibromomethane	ND		ug/L	5.0	02/24/26	02/24/26
4-Methyl-2-Pentanone	ND		ug/L	5.0	02/24/26	02/24/26
cis-1,3-Dichloropropene	ND		ug/L	5.0	02/24/26	02/24/26
Toluene	ND		ug/L	5.0	02/24/26	02/24/26
trans-1,3-Dichloropropene	ND		ug/L	5.0	02/24/26	02/24/26
1,1,2-Trichloroethane	ND		ug/L	5.0	02/24/26	02/24/26
1,3-Dichloropropane	ND		ug/L	5.0	02/24/26	02/24/26
Tetrachloroethene	ND		ug/L	5.0	02/24/26	02/24/26
Dibromochloromethane	ND		ug/L	5.0	02/24/26	02/24/26
1,2-Dibromoethane	ND		ug/L	5.0	02/24/26	02/24/26
Chlorobenzene	ND		ug/L	5.0	02/24/26	02/24/26
1,1,1,2-Tetrachloroethane	ND		ug/L	5.0	02/24/26	02/24/26
Ethylbenzene	ND		ug/L	5.0	02/24/26	02/24/26
m,p-Xylenes	ND		ug/L	10	02/24/26	02/24/26
o-Xylene	ND		ug/L	5.0	02/24/26	02/24/26
Styrene	ND		ug/L	5.0	02/24/26	02/24/26
Bromoform	ND		ug/L	5.0	02/24/26	02/24/26
Isopropylbenzene	ND		ug/L	5.0	02/24/26	02/24/26
1,1,2,2-Tetrachloroethane	ND		ug/L	5.0	02/24/26	02/24/26
1,2,3-Trichloropropane	ND		ug/L	5.0	02/24/26	02/24/26

ENTHALPY ANALYTICAL

Batch QC

QC1343546 Analyte	Result	Qual	Units	RL	Prepared	Analyzed
Propylbenzene	ND		ug/L	5.0	02/24/26	02/24/26
Bromobenzene	ND		ug/L	5.0	02/24/26	02/24/26
1,3,5-Trimethylbenzene	ND		ug/L	5.0	02/24/26	02/24/26
2-Chlorotoluene	ND		ug/L	5.0	02/24/26	02/24/26
4-Chlorotoluene	ND		ug/L	5.0	02/24/26	02/24/26
tert-Butylbenzene	ND		ug/L	5.0	02/24/26	02/24/26
1,2,4-Trimethylbenzene	ND		ug/L	5.0	02/24/26	02/24/26
sec-Butylbenzene	ND		ug/L	5.0	02/24/26	02/24/26
para-Isopropyl Toluene	ND		ug/L	5.0	02/24/26	02/24/26
1,3-Dichlorobenzene	ND		ug/L	5.0	02/24/26	02/24/26
1,4-Dichlorobenzene	ND		ug/L	5.0	02/24/26	02/24/26
n-Butylbenzene	ND		ug/L	5.0	02/24/26	02/24/26
1,2-Dichlorobenzene	ND		ug/L	5.0	02/24/26	02/24/26
1,2-Dibromo-3-Chloropropane	ND		ug/L	5.0	02/24/26	02/24/26
1,2,4-Trichlorobenzene	ND		ug/L	5.0	02/24/26	02/24/26
Hexachlorobutadiene	ND		ug/L	5.0	02/24/26	02/24/26
Naphthalene	ND		ug/L	5.0	02/24/26	02/24/26
1,2,3-Trichlorobenzene	ND		ug/L	5.0	02/24/26	02/24/26
cis-1,4-Dichloro-2-butene	ND		ug/L	5.0	02/24/26	02/24/26
trans-1,4-Dichloro-2-butene	ND		ug/L	5.0	02/24/26	02/24/26
Xylene (total)	ND		ug/L	5.0	02/24/26	02/24/26
Surrogates				**Limits**		
Dibromofluoromethane	104%		%REC	70-130	02/24/26	02/24/26
1,2-Dichloroethane-d4	98%		%REC	70-130	02/24/26	02/24/26
Toluene-d8	101%		%REC	70-130	02/24/26	02/24/26
Bromofluorobenzene	102%		%REC	70-130	02/24/26	02/24/26

Type:	**Matrix Spike**	**Lab ID:**	**QC1343593**	**Batch:**	**396207**
Matrix (Source ID):	**Water (553928-001)**	**Method:**	**EPA 8260B**	**Prep Method:**	**EPA 5030B**

QC1343593 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	DF
1,1-Dichloroethene	18.31	ND	20.00	ug/L	92%		62-131	1
MTBE	22.38	ND	20.00	ug/L	112%		61-124	1
Benzene	20.14	ND	20.00	ug/L	101%		70-123	1
Trichloroethene	19.46	ND	20.00	ug/L	97%		65-131	1
Toluene	19.08	ND	20.00	ug/L	95%		69-120	1
Chlorobenzene	20.57	ND	20.00	ug/L	103%		72-121	1
Surrogates								
Dibromofluoromethane	55.03		50.00	ug/L	110%		70-130	1
1,2-Dichloroethane-d4	52.97		50.00	ug/L	106%		70-130	1
Toluene-d8	48.11		50.00	ug/L	96%		70-130	1
Bromofluorobenzene	50.01		50.00	ug/L	100%		70-130	1

ENTHALPY ANALYTICAL

Batch QC

Type:	Matrix Spike Duplicate	Lab ID:	QC1343594	Batch:	396207
Matrix (Source ID):	Water (553928-001)	Method:	EPA 8260B	Prep Method:	EPA 5030B

QC1343594 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	RPD	RPD Lim	DF
1,1-Dichloroethene	16.76	ND	20.00	ug/L	84%		62-131	9	31	1
MTBE	21.04	ND	20.00	ug/L	105%		61-124	6	30	1
Benzene	18.79	ND	20.00	ug/L	94%		70-123	7	31	1
Trichloroethene	18.86	ND	20.00	ug/L	94%		65-131	3	31	1
Toluene	18.59	ND	20.00	ug/L	93%		69-120	3	29	1
Chlorobenzene	19.68	ND	20.00	ug/L	98%		72-121	4	29	1
Surrogates										
Dibromofluoromethane	53.50		50.00	ug/L	107%		70-130			1
1,2-Dichloroethane-d4	51.63		50.00	ug/L	103%		70-130			1
Toluene-d8	49.75		50.00	ug/L	100%		70-130			1
Bromofluorobenzene	48.97		50.00	ug/L	98%		70-130			1

Type:	Lab Control Sample	Lab ID:	QC1343001	Batch:	396056
Matrix:	Soil	Method:	EPA 8260B	Prep Method:	EPA 5035

QC1343001 Analyte	Result	Spiked	Units	Recovery	Qual	Limits
1,1-Dichloroethene	47.98	50.00	ug/Kg	96%		72-130
MTBE	47.42	50.00	ug/Kg	95%		69-127
Benzene	51.53	50.00	ug/Kg	103%		76-126
Trichloroethene	47.74	50.00	ug/Kg	95%		74-121
Toluene	45.44	50.00	ug/Kg	91%		78-121
Chlorobenzene	47.64	50.00	ug/Kg	95%		80-121
Surrogates						
Dibromofluoromethane	52.35	50.00	ug/Kg	105%		70-130
1,2-Dichloroethane-d4	47.35	50.00	ug/Kg	95%		70-130
Toluene-d8	48.83	50.00	ug/Kg	98%		70-130
Bromofluorobenzene	49.21	50.00	ug/Kg	98%		70-130

Type:	Lab Control Sample Duplicate	Lab ID:	QC1343002	Batch:	396056
Matrix:	Soil	Method:	EPA 8260B	Prep Method:	EPA 5035

QC1343002 Analyte	Result	Spiked	Units	Recovery	Qual	Limits	RPD	RPD Lim
1,1-Dichloroethene	47.60	50.00	ug/Kg	95%		72-130	1	26
MTBE	47.92	50.00	ug/Kg	96%		69-127	1	25
Benzene	52.02	50.00	ug/Kg	104%		76-126	1	24
Trichloroethene	46.53	50.00	ug/Kg	93%		74-121	3	26
Toluene	45.21	50.00	ug/Kg	90%		78-121	0	24
Chlorobenzene	47.73	50.00	ug/Kg	95%		80-121	0	23
Surrogates								
Dibromofluoromethane	52.66	50.00	ug/Kg	105%		70-130		
1,2-Dichloroethane-d4	48.23	50.00	ug/Kg	96%		70-130		
Toluene-d8	48.49	50.00	ug/Kg	97%		70-130		
Bromofluorobenzene	48.67	50.00	ug/Kg	97%		70-130		

ENTHALPY ANALYTICAL

Batch QC

Type:	Matrix Spike	Lab ID:	QC1343005	Batch:	396056
Matrix (Source ID):	Soil (553915-001)	Method:	EPA 8260B	Prep Method:	EPA 5030B

QC1343005 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	DF
1,1-Dichloroethene	19.71	ND	20.49	ug/Kg	96%		56-129	1
MTBE	21.22	ND	20.49	ug/Kg	104%		47-130	1
Benzene	22.29	ND	20.49	ug/Kg	109%		54-128	1
Trichloroethene	20.95	ND	20.49	ug/Kg	102%		48-128	1
Toluene	19.15	ND	20.49	ug/Kg	93%		53-123	1
Chlorobenzene	20.83	ND	20.49	ug/Kg	102%		50-125	1
Surrogates								
Dibromofluoromethane	53.40		51.23	ug/Kg	104%		70-130	1
1,2-Dichloroethane-d4	49.68		51.23	ug/Kg	97%		70-130	1
Toluene-d8	49.46		51.23	ug/Kg	97%		70-130	1
Bromofluorobenzene	50.32		51.23	ug/Kg	98%		70-130	1

Type:	Matrix Spike Duplicate	Lab ID:	QC1343006	Batch:	396056
Matrix (Source ID):	Soil (553915-001)	Method:	EPA 8260B	Prep Method:	EPA 5030B

QC1343006 Analyte	Result	Source Sample Result	Spiked	Units	Recovery	Qual	Limits	RPD	RPD Lim	DF
1,1-Dichloroethene	18.26	ND	20.49	ug/Kg	89%		56-129	8	41	1
MTBE	18.96	ND	20.49	ug/Kg	93%		47-130	11	44	1
Benzene	20.03	ND	20.49	ug/Kg	98%		54-128	11	45	1
Trichloroethene	18.76	ND	20.49	ug/Kg	92%		48-128	11	47	1
Toluene	17.03	ND	20.49	ug/Kg	83%		53-123	12	43	1
Chlorobenzene	17.87	ND	20.49	ug/Kg	87%		50-125	15	44	1
Surrogates										
Dibromofluoromethane	52.48		51.23	ug/Kg	102%		70-130			1
1,2-Dichloroethane-d4	48.54		51.23	ug/Kg	95%		70-130			1
Toluene-d8	48.61		51.23	ug/Kg	95%		70-130			1
Bromofluorobenzene	49.96		51.23	ug/Kg	98%		70-130			1

ENTHALPY ANALYTICAL

Batch QC

Type:	**Blank**	**Lab ID:**	**QC1343008**	**Batch:**	**396056**
Matrix:	**Soil**	**Method:**	**EPA 8260B**	**Prep Method:**	**EPA 5035**

QC1343008 Analyte	Result	Qual	Units	RL	Prepared	Analyzed
3-Chloropropene	ND		ug/Kg	5.0	02/22/26	02/22/26
cis-1,4-Dichloro-2-butene	ND		ug/Kg	5.0	02/22/26	02/22/26
trans-1,4-Dichloro-2-butene	ND		ug/Kg	5.0	02/22/26	02/22/26
Freon 12	ND		ug/Kg	5.0	02/22/26	02/22/26
Chloromethane	ND		ug/Kg	5.0	02/22/26	02/22/26
Vinyl Chloride	ND		ug/Kg	5.0	02/22/26	02/22/26
Bromomethane	ND		ug/Kg	5.0	02/22/26	02/22/26
Chloroethane	ND		ug/Kg	5.0	02/22/26	02/22/26
Trichlorofluoromethane	ND		ug/Kg	5.0	02/22/26	02/22/26
Acetone	ND		ug/Kg	100	02/22/26	02/22/26
Freon 113	ND		ug/Kg	5.0	02/22/26	02/22/26
1,1-Dichloroethene	ND		ug/Kg	5.0	02/22/26	02/22/26
Methylene Chloride	ND		ug/Kg	5.0	02/22/26	02/22/26
MTBE	ND		ug/Kg	5.0	02/22/26	02/22/26
trans-1,2-Dichloroethene	ND		ug/Kg	5.0	02/22/26	02/22/26
1,1-Dichloroethane	ND		ug/Kg	5.0	02/22/26	02/22/26
2-Butanone	ND		ug/Kg	100	02/22/26	02/22/26
cis-1,2-Dichloroethene	ND		ug/Kg	5.0	02/22/26	02/22/26
2,2-Dichloropropane	ND		ug/Kg	5.0	02/22/26	02/22/26
Chloroform	ND		ug/Kg	5.0	02/22/26	02/22/26
Bromochloromethane	ND		ug/Kg	5.0	02/22/26	02/22/26
1,1,1-Trichloroethane	ND		ug/Kg	5.0	02/22/26	02/22/26
1,1-Dichloropropene	ND		ug/Kg	5.0	02/22/26	02/22/26
Carbon Tetrachloride	ND		ug/Kg	5.0	02/22/26	02/22/26
1,2-Dichloroethane	ND		ug/Kg	5.0	02/22/26	02/22/26
Benzene	ND		ug/Kg	5.0	02/22/26	02/22/26
Trichloroethene	ND		ug/Kg	5.0	02/22/26	02/22/26
1,2-Dichloropropane	ND		ug/Kg	5.0	02/22/26	02/22/26
Bromodichloromethane	ND		ug/Kg	5.0	02/22/26	02/22/26
Dibromomethane	ND		ug/Kg	5.0	02/22/26	02/22/26
4-Methyl-2-Pentanone	ND		ug/Kg	5.0	02/22/26	02/22/26
cis-1,3-Dichloropropene	ND		ug/Kg	5.0	02/22/26	02/22/26
Toluene	ND		ug/Kg	5.0	02/22/26	02/22/26
trans-1,3-Dichloropropene	ND		ug/Kg	5.0	02/22/26	02/22/26
1,1,2-Trichloroethane	ND		ug/Kg	5.0	02/22/26	02/22/26
1,3-Dichloropropane	ND		ug/Kg	5.0	02/22/26	02/22/26
Tetrachloroethene	ND		ug/Kg	5.0	02/22/26	02/22/26
Dibromochloromethane	ND		ug/Kg	5.0	02/22/26	02/22/26
1,2-Dibromoethane	ND		ug/Kg	5.0	02/22/26	02/22/26
Chlorobenzene	ND		ug/Kg	5.0	02/22/26	02/22/26
1,1,1,2-Tetrachloroethane	ND		ug/Kg	5.0	02/22/26	02/22/26
Ethylbenzene	ND		ug/Kg	5.0	02/22/26	02/22/26
m,p-Xylenes	ND		ug/Kg	10	02/22/26	02/22/26
o-Xylene	ND		ug/Kg	5.0	02/22/26	02/22/26
Styrene	ND		ug/Kg	5.0	02/22/26	02/22/26
Bromoform	ND		ug/Kg	5.0	02/22/26	02/22/26
Isopropylbenzene	ND		ug/Kg	5.0	02/22/26	02/22/26

ENTHALPY ANALYTICAL

Batch QC

QC1343008 Analyte	Result	Qual	Units	RL	Prepared	Analyzed
1,1,2,2-Tetrachloroethane	ND		ug/Kg	5.0	02/22/26	02/22/26
1,2,3-Trichloropropane	ND		ug/Kg	5.0	02/22/26	02/22/26
Propylbenzene	ND		ug/Kg	5.0	02/22/26	02/22/26
Bromobenzene	ND		ug/Kg	5.0	02/22/26	02/22/26
1,3,5-Trimethylbenzene	ND		ug/Kg	5.0	02/22/26	02/22/26
2-Chlorotoluene	ND		ug/Kg	5.0	02/22/26	02/22/26
4-Chlorotoluene	ND		ug/Kg	5.0	02/22/26	02/22/26
tert-Butylbenzene	ND		ug/Kg	5.0	02/22/26	02/22/26
1,2,4-Trimethylbenzene	ND		ug/Kg	5.0	02/22/26	02/22/26
sec-Butylbenzene	ND		ug/Kg	5.0	02/22/26	02/22/26
para-Isopropyl Toluene	ND		ug/Kg	5.0	02/22/26	02/22/26
1,3-Dichlorobenzene	ND		ug/Kg	5.0	02/22/26	02/22/26
1,4-Dichlorobenzene	ND		ug/Kg	5.0	02/22/26	02/22/26
n-Butylbenzene	ND		ug/Kg	5.0	02/22/26	02/22/26
1,2-Dichlorobenzene	ND		ug/Kg	5.0	02/22/26	02/22/26
1,2-Dibromo-3-Chloropropane	ND		ug/Kg	5.0	02/22/26	02/22/26
1,2,4-Trichlorobenzene	ND		ug/Kg	5.0	02/22/26	02/22/26
Hexachlorobutadiene	ND		ug/Kg	5.0	02/22/26	02/22/26
Naphthalene	ND		ug/Kg	5.0	02/22/26	02/22/26
1,2,3-Trichlorobenzene	ND		ug/Kg	5.0	02/22/26	02/22/26
Xylene (total)	ND		ug/Kg	5.0	02/22/26	02/22/26
Surrogates				**Limits**		
Dibromofluoromethane	101%		%REC	70-130	02/22/26	02/22/26
1,2-Dichloroethane-d4	95%		%REC	70-130	02/22/26	02/22/26
Toluene-d8	97%		%REC	70-130	02/22/26	02/22/26
Bromofluorobenzene	97%		%REC	70-130	02/22/26	02/22/26

#	CCV drift outside limits; average CCV drift within limits per method requirements
*	Value is outside QC limits
J	Estimated value
ND	Not Detected

Laboratory Job Number 553922

Subcontracted Products

AmeriSci Los Angeles

AmeriSci Richmond
13635 GENITO ROAD
MIDLOTHIAN, VIRGINIA 23112
TEL: (804) 763-1200 • FAX: (804) 763-0493

March 4, 2026

Enthalpy Analytical
Attn: Patty Mata
931 West Barkley Ave
Orange, CA 92868

RE: Enthalpy Analytical
Job Number 126022173
P.O. #099250
553922

Dear Patty Mata:

Enclosed are the results of Asbestos Analysis - Bulk Qualitative Protocol of the following Enthalpy Analytical samples, received at AmeriSci on Wednesday, February 25, 2026, for a 5 day turnaround:

CG-44-0.5, CG-44-2.5, CG-45-0.5, CG-45-2.5, CG-45-0.5-DUP, CG-45-2.5-DUP, CG-46-0.5, CG-46-2.5

The 8 samples, placed in glass jar, were shipped to AmeriSci via Fed Ex 717839739830. Enthalpy Analytical requested Bulk-Qualitative analysis of these samples.

The samples were prepared and analyzed by using a Standard Operating Procedure developed by AmeriSci, Inc.. After preparation, using non-quantitative matrix reduction if necessary, the presence or absence of asbestos is determined by PLM and/or TEM as indicated on the attached summary table. Quantification after the fact is not possible without a new preparation. This report relates ONLY to the analysis expressed as "asbestos present" or "no asbestos visible". This report must not be used to claim product endorsement or approval by AmeriSci, NVLAP, ELAP or any other associated AmeriSci certifying agency. The National Institute of Standards and Technology accreditation requirements, mandate that this report must not be reproduced, except in full without the approval of the laboratory.

AmeriSci appreciates this opportunity to serve your organization. Please contact us for any further assistance or with any questions.

Sincerely,



Glenn F. Massey

QA Manager | Authorized Signatory

AmeriSci Richmond
13635 GENITO ROAD
MIDLOTHIAN, VIRGINIA 23112
TEL: (804) 763-1200 • FAX: (804) 763-0493

PLM Bulk Asbestos Report

Enthalpy Analytical
Attn: Patty Mata
931 West Barkley Ave

Orange, CA 92868

Date Received 2/25/2026
Date Examined 02/27/26
RE: 553922

AmeriSci Job # 126022173
P.O. # 099250

Client No. / HGA	Lab No.	Asbestos Present	Total % Asbestos	Notes
CG-44-0.5	126022173-01	***No***	NVA by C. David Mintz on 02/27/26	*1*

Location:
Analyst Description: Dark Brown, Homogeneous, Non-Fibrous, Soil
Asbestos Types:
Other Material: Cellulose Present, Non-fibrous Present

CG-44-2.5	126022173-02	***No***	NVA by C. David Mintz on 02/27/26	*1*

Location:
Analyst Description: Dark Brown, Homogeneous, Non-Fibrous, Soil
Asbestos Types:
Other Material: Cellulose Present, Non-fibrous Present

CG-45-0.5	126022173-03	***No***	NVA by C. David Mintz on 02/27/26	*1*

Location:
Analyst Description: Dark Brown, Homogeneous, Non-Fibrous, Soil
Asbestos Types:
Other Material: Cellulose Present, Non-fibrous Present

CG-45-2.5	126022173-04	***No***	NVA by C. David Mintz on 02/27/26	*1*

Location:
Analyst Description: Dark Brown, Homogeneous, Non-Fibrous, Soil
Asbestos Types:
Other Material: Cellulose Present, Non-fibrous Present

CG-45-0.5-DUP	126022173-05	***No***	NVA by C. David Mintz on 02/27/26	*1*

Location:
Analyst Description: Dark Brown, Homogeneous, Non-Fibrous, Soil
Asbestos Types:
Other Material: Non-fibrous Present

CG-45-2.5-DUP	126022173-06	***No***	NVA by C. David Mintz on 02/27/26	*1*

Location:
Analyst Description: Dark Brown, Homogeneous, Non-Fibrous, Soil
Asbestos Types:
Other Material: Non-fibrous Present

See Reporting notes on last page

PLM Bulk Asbestos Report

553922

Client No. / HGA	Lab No.	Asbestos Present	Total % Asbestos	Notes
CG-46-0.5	126022173-07	***No***	NVA by C. David Mintz on 02/27/26	*1*

Location:
Analyst Description: Dark Brown, Homogeneous, Non-Fibrous, Soil
Asbestos Types:
Other Material: Non-fibrous Present


CG-46-2.5	126022173-08	***No***	NVA by C. David Mintz on 02/27/26	*1*

Location:
Analyst Description: Dark Brown, Homogeneous, Non-Fibrous, Soil
Asbestos Types:
Other Material: Non-fibrous Present

Reporting Notes:

(1) Sample homogenized by grinding to a powder prior to analysis.

Analyzed by: C. David Mintz
Date: 2/27/2026



Reviewed by: Glenn F. Massey



*NAD = no asbestos detected, Detection Limit <1%, Reporting Limits: CVES = 1%, 400 Pt Ct = 0.25%, 1000 Pt Ct = 0.1%; "Present" or NVA = "No Visible Asbestos" are observations made during a qualitative analysis (Not covered by NVLAP or NY ELAP accreditations); NA = not analyzed; NA/PS = not analyzed / positive stop; PLM Bulk Asbestos Analysis using Olympus, Model BH-2 microscope, Serial #210972, by EPA 600/R-93/116 per 40 CFR 763 (NVLAP Lab Code 101904-0) and ELAP PLM Analysis Protocol 198.1 for New York friable samples which includes quantitation of any vermiculite observed (198.6 for NOB samples) or EPA 400 pt ct by EPA 600/M4-82-020 (NYSDOH ELAP Lab # 10984); CA ELAP Lab # 2508; Note: PLM is not consistently reliable in detecting asbestos in floor coverings and similar NOB materials. NAD or Trace results by PLM are inconclusive, TEM is currently the only method that can be used to determine if this material can be considered or treated as non-asbestos-containing in New York State (also see EPA Advisory for floor tile, FR 59, 146, 38970, 8/1/94). NIST Accreditation requirements mandate that this report must not be reproduced except in full without the approval of the laboratory. This PLM report relates ONLY to the items tested.

ENTHALPY ANALYTICAL
931 West Barkley Ave
Orange, CA 92868
(714) 771-6900

126022173

Subcontract Laboratory:
AmeriSci Los Angeles
24416 S. Main Street
Suite 308
Carson, CA 90745
ATTN: Sample Control
PO #: Required, to be sent via email

Enthalpy Order: EO-553922
PM: Patty Mata
Email: patty.mata@enthalpy.com
CC: incomingreports@enthalpy.com
Phone: (714) 771-6900

Results Due: Standard TAT
Report Level: II
Report To: RL
EDDs:

Notes:

Sample ID	Collected	Lab ID	# Cont.	Matrix	Analysis Requested	Comment
EB-01-260220	20-FEB-2026 15:30	553922-039	1	Water	Asbestos	Non-potable water TEM
CG-44-0.5	20-FEB-2026 00:00	553922-041	1	Soil	Asbestos by PLM	PLM Qualitative
CG-44-2.5	20-FEB-2026 00:00	553922-042	1	Soil	Asbestos by PLM	PLM Qualitative
CG-45-0.5	20-FEB-2026 00:00	553922-043	1	Soil	Asbestos by PLM	PLM Qualitative
CG-45-2.5	20-FEB-2026 00:00	553922-044	1	Soil	Asbestos by PLM	PLM Qualitative
CG-45-0.5-DUP	20-FEB-2026 00:00	553922-045	1	Soil	Asbestos by PLM	PLM Qualitative
CG-45-2.5-DUP	20-FEB-2026 00:00	553922-046	1	Soil	Asbestos by PLM	PLM Qualitative
CG-46-0.5-	20-FEB-2026 00:00	553922-047	1	Soil	Asbestos by PLM	PLM Qualitative
CG-46-2.5	20-FEB-2026 00:00	553922-048	1	Soil	Asbestos by PLM	PLM Qualitative

Notes:	Relinquished By:	Received By:
	[signature]	M. RIVERO
	Date: 2-24-26 1313	Date: 2/24/26 @ 1315
	M. RIVERO	
	Date: 2/24/26 @ 1315	Date:
	Date:	Date:

Received
FEB 25 2026
[signature]

ENTHALPY ANALYTICAL

931 West Barkley Ave
Orange, CA 92868
(714) 771-6900

126022173

Subcontract Laboratory:
AmeriSci Los Angeles
24416 S. Main Street
Suite 308
Carson, CA 90745
ATTN: Sample Control
PO #: Required, to be sent via email

Enthalpy Order: EO-553922
PM: Patty Mata
Email: patty.mata@enthalpy.com
CC: incomingreports@enthalpy.com
Phone: (714) 771-6900

Results Due: Standard TAT
Report Level: II
Report To: RL
EDDs:

Notes:

Sample ID	Collected	Lab ID	# Cont.	Matrix	Analysis Requested	Comment
EB-01-260220	20-FEB-2026 15:30	553922-039	1	Water	Asbestos	Non-potable water TEM
CG-44-0.5	20-FEB-2026 00:00	553922-041	1	Soil	Asbestos by PLM	PLM Qualitative
CG-44-2.5	20-FEB-2026 00:00	553922-042	1	Soil	Asbestos by PLM	PLM Qualitative
CG-45-0.5	20-FEB-2026 00:00	553922-043	1	Soil	Asbestos by PLM	PLM Qualitative
CG-45-2.5	20-FEB-2026 00:00	553922-044	1	Soil	Asbestos by PLM	PLM Qualitative
CG-45-0.5-DUP	20-FEB-2026 00:00	553922-045	1	Soil	Asbestos by PLM	PLM Qualitative
CG-45-2.5-DUP	20-FEB-2026 00:00	553922-046	1	Soil	Asbestos by PLM	PLM Qualitative
CG-46-0.5-	20-FEB-2026 00:00	553922-047	1	Soil	Asbestos by PLM	PLM Qualitative
CG-46-2.5	20-FEB-2026 00:00	553922-048	1	Soil	Asbestos by PLM	PLM Qualitative

Notes:	Relinquished By:	Received By:
	[signature]	M. RIVERO
	Date: 2-24-26 1312	Date: 2/24/26 @ 1315
	M. RIVERO	
	Date: 2/24/26 @ 1315	Date:
	Date:	Date:

Received
FEB 25 2026
BHM

Subject: Re: [External] - Await Enthalpy PO - Amerisci 126-02 2173 2180 2266 2267 2268 2269
From: Patricia Mata <patty.mata@enthalpy.com>
Date: 3/2/2026, 11:39 AM
To: Angel Warden <varesults@amerisci.com>, Jocelyn Nguyen <JocelynNguyen@enthalpy.com>, Zaid Padilla <zaid.padilla@enthalpy.com>

Hello,

For Patty's 553922 jobs, please use PO-099250.

With Regards,
Patty Mata
Project Manager
Enthalpy Analytical
Direct: +1-714-771-9930 | Mobile: +1-714-323-2586
patty.mata@enthalpy.com

126-02-2173
2180

From: Angel Warden <varesults@amerisci.com>
Sent: Monday, March 2, 2026 6:15 AM
To: Jocelyn Nguyen <JocelynNguyen@enthalpy.com>; Patricia Mata <patty.mata@enthalpy.com>; Zaid Padilla <zaid.padilla@enthalpy.com>
Subject: [External] - Await Enthalpy PO - Amerisci 126-02 2173 2180 2266 2267 2268 2269

EXTERNAL EMAIL - This email was sent by a person from outside your organization. Exercise caution when clicking links, opening attachments or taking further action, before validating its authenticity.

Hello Jocelyn
Here are the Enthalpy Jobs awaiting PO.
*** Patty.Mata**
1. 126-02-2173 and 2180 (553922)
*** Zaid Padilla**
126-02
1. 2266 (554007)
2. 2267 (554008)
3. 2268 (554010)
4. 2269 (554027)

Thank you
Angel Warden
Amerisci

--
Confidentiality Notice: Unless otherwise indicated, the information contained in this communication is confidential information for use of

AmeriSci Richmond
13635 GENITO ROAD
MIDLOTHIAN, VIRGINIA 23112
TEL: (804) 763-1200 • FAX: (804) 763-0493

March 3, 2026

Enthalpy Analytical
Attn: Patty Mata
931 West Barkley Ave
Orange, CA 92868

RE: Enthalpy Analytical
Job Number 126022180
P.O. #099250
553922

Dear Patty Mata:

Enclosed are the results for TEM asbestos analysis of the following Enthalpy Analytical samples received at AmeriSci on Wednesday, February 25, 2026, for a 5 day turnaround:

EB-01-260220

The 1 samples were filtered and prepared according to Water analysis under the EPA-600/4-83-043 "Analytical Method for Determination of Asbestos Fibers in Water" (1983). Samples with high organic content may be prepared following EPA-600/4-80-005 if necessary and are so noted on the TEM count sheets. AmeriSci, Inc. uses the "Grid Square" method of counting and the concentration is calculated in millions of fibers per liter (MFL).

Table I represents a summary of all pertinent information used for the calculations. Included are the size of each structure counted, concentration, structure concentration greater than 10 microns in length, type of asbestiform material detected and the analytical sensitivity, which represents the concentration by the detection of one fiber in the TEM fiber count. Copies of the Fiber Count Sheets, show the raw data for examination. These data sheets contain information for fiber length/width, fiber type, structure morphology and pertinent information on EDS, SAED and photography.

This report relates ONLY to the sample analysis expressed as millions of fibers per liter (MFL). AmeriSci assumes no responsibility for customer supplied data such as “sample location” or “the condition of the water sample before arriving at AmeriSci”. This report must not be used to claim product endorsement by AmeriSci, NVLAP, ELAP or any agency of the U. S. Government. The National Institute of Standards and Technology accreditation requirements, mandate that this report must not be reproduced, except in full without the approval of the laboratory.

AmeriSci appreciates this opportunity to serve your organization. Please contact us for any further assistance or with any questions.

Sincerely,



Cory M. Parnell

Laboratory Director | Authorized Signatory

AmeriSci Job #: **126022180**
Client Name: Enthalpy Analytical

Table I
Summary of Transmission Electron Microscopy (TEM) Results for Asbestos (Water)


553922

AmeriSci Sample #	Client Sample No./Location	Liquid Filtered (liters)	Temp (Celcius)	Structures Detected* (total)	Structures Detected* (>10 µm)	Analytical Sensitivity (MF/L)	Asbestos Conc (total) (MF/L)	Asbestos Conc (>10 µm) (MF/L)	Asbestos Type
01	EB-01-260220	0.01	21.4	NSD	NSD	0.22	<0.22	<0.22	----

* NAD/NSD = no asbestos detected, NA = not analyzed, MF/L = million fibers per liter; Drinking Water accreditations do not cover waste water analysis. NOTE: Drinking water analysis by EPA-600/4-83-043 (100.1). Fiber criteria (>=0.5 microns, for 100.1; >10 microns for 100.2; 5:1 aspect ratio for both), organic rich waste water prepped by EPA-600/4-80-005. Analytical sensitivity calculated as though 1 fiber had been detected on the TEM GRID area analyzed. Sample temperatures reported above were measured upon receipt. Water samples are refrigerated upon receipt and filtered within four hours.

Reviewed By: _____ Analyzed By: Cory M. Parnell _____ Date: 3/3/2026

TEM Asbestos (Water) Count Sheet



Client Name:	Enthalpy Analytical		
Job #:	126022180	Volume (liters):	0.01
Lab Sample #:	01	Filter Type / Filter Area:	MCE 214 mm2
Client Sample #:	EB-01-260220	Grid Opening Size:	0.00967
Received:	2/25/2026 12:00:00	Area Examined:	0.09670 mm2
Date Analyzed:	3/3/2026	Magnification:	20,000
	Temp: 21.4	Accelerating Voltage:	100 KeV

Analysis Performed by: Cory M. Parnell

Location	Grid Opening	Fiber	Length µM	Width µM	Fiber Type	Morphology	EDS	Orient.	SAED	Photo
A3-C2	1	NSD							☐	
A3-C4	2	NSD							☐	
A3-C6	3	NSD							☐	
A3-C8	4	NSD							☐	
A3-C10	5	NSD							☐	
A4-J1	6	NSD							☐	
A4-J3	7	NSD							☐	
A4-J5	8	NSD							☐	
A4-J7	9	NSD							☐	
A4-J9	10	NSD							☐	

NSD: No Asbestos Structures Detected

Scope #: Front 4: Jeol JEM-100CX II, Serial No.156147-247

Comments

		Concentration (million fibers/liter)	Grid Evaluation
Total Grid Openings:	10		☑ Grid Openings Covered > 50%
Chrysotile Asbestos Structures:	0	<0.221	☑ Intact Grid Opening > 50%
Amphibole Asbestos Structures:	0	<0.221	☑ Undissolved Filter < 10%
Asbestos Structures >10 microns:	0	<0.221	☑ Folded Replica < 50%
Total Asbestos Structures:	0	<0.221	☑ Filter Loading < 25%
Analytical Sensitivity:		0.221	☑ Particulate Even

ENTHALPY ANALYTICAL

931 West Barkley Ave
Orange, CA 92868
(714) 771-6900

1260221 80

Subcontract Laboratory:
AmeriSci Los Angeles
24416 S. Main Street
Suite 308
Carson, CA 90745
ATTN: Sample Control
PO #: Required, to be sent via email

Enthalpy Order: EO-553922
PM: Patty Mata
Email: patty.mata@enthalpy.com
CC: incomingreports@enthalpy.com
Phone: (714) 771-6900

Results Due: Standard TAT
Report Level: II
Report To: RL
EDDs:

Notes:

Sample ID	Collected	Lab ID	# Cont.	Matrix	Analysis Requested	Comment
EB-01-260220	20-FEB-2026 15:30	553922-039	1	Water	Asbestos	Non-potable water TEM
CG-44-0.5	20-FEB-2026 00:00	553922-041	1	Soil	Asbestos by PLM	PLM Qualitative
CG-44-2.5	20-FEB-2026 00:00	553922-042	1	Soil	Asbestos by PLM	PLM Qualitative
CG-45-0.5	20-FEB-2026 00:00	553922-043	1	Soil	Asbestos by PLM	PLM Qualitative
CG-45-2.5	20-FEB-2026 00:00	553922-044	1	Soil	Asbestos by PLM	PLM Qualitative
CG-45-0.5-DUP	20-FEB-2026 00:00	553922-045	1	Soil	Asbestos by PLM	PLM Qualitative
CG-45-2.5-DUP	20-FEB-2026 00:00	553922-046	1	Soil	Asbestos by PLM	PLM Qualitative
CG-46-0.5-	20-FEB-2026 00:00	553922-047	1	Soil	Asbestos by PLM	PLM Qualitative
CG-46-2.5	20-FEB-2026 00:00	553922-048	1	Soil	Asbestos by PLM	PLM Qualitative

Notes:	Relinquished By:	Received By:
	[signature]	M. RIVERO
	Date: 2-24-26 1313	Date: 2/24/26 @ 1315
	M. RIVERO	
	Date: 2/24/26 @ 1315	Date:
	Date:	Date:

Received
FEB 25 2026
BHM

ENTHALPY ANALYTICAL

931 West Barkley Ave
Orange, CA 92868
(714).771-6900

1260221 80

Subcontract Laboratory:
AmeriSci Los Angeles
24416 S. Main Street
Suite 308
Carson, CA 90745
ATTN: Sample Control
PO #: Required, to be sent via email

Enthalpy Order: EO-553922
PM: Patty Mata
Email: patty.mata@enthalpy.com
CC: incomingreports@enthalpy.com
Phone: (714) 771-6900

Results Due: Standard TAT
Report Level: II
Report To: RL
EDDs:

Notes:

Sample ID	Collected	Lab ID	# Cont.	Matrix	Analysis Requested	Comment
EB-01-260220	20-FEB-2026 15:30	553922-039	1	Water	Asbestos	Non-potable water TEM
CG-44-0.5	20-FEB-2026 00:00	553922-041	1	Soil	Asbestos by PLM	PLM Qualitative
CG-44-2.5	20-FEB-2026 00:00	553922-042	1	Soil	Asbestos by PLM	PLM Qualitative
CG-45-0.5	20-FEB-2026 00:00	553922-043	1	Soil	Asbestos by PLM	PLM Qualitative
CG-45-2.5	20-FEB-2026 00:00	553922-044	1	Soil	Asbestos by PLM	PLM Qualitative
CG-45-0.5-DUP	20-FEB-2026 00:00	553922-045	1	Soil	Asbestos by PLM	PLM Qualitative
CG-45-2.5-DUP	20-FEB-2026 00:00	553922-046	1	Soil	Asbestos by PLM	PLM Qualitative
CG-46-0.5-	20-FEB-2026 00:00	553922-047	1	Soil	Asbestos by PLM	PLM Qualitative
CG-46-2.5	20-FEB-2026 00:00	553922-048	1	Soil	Asbestos by PLM	PLM Qualitative

Notes:	Relinquished By:	Received By:
	[signature]	M. RIVERO
	Date: 2-24-26 1313	Date: 2/24/26 @ 1315
	M. RIVERO	
	Date: 2/24/26 @ 1315	Date:
	Date:	Date:

Received
FEB 25 2026
KHM

Subject: Re: [External] - Await Enthalpy PO - Amerisci 126-02 2173 2180 2266 2267 2268 2269
From: Patricia Mata <patty.mata@enthalpy.com>
Date: 3/2/2026, 11:39 AM
To: Angel Warden <varesults@amerisci.com>, Jocelyn Nguyen <JocelynNguyen@enthalpy.com>, Zaid Padilla <zaid.padilla@enthalpy.com>

Hello,

For Patty's 553922 jobs, please use PO-099250.

With Regards,
Patty Mata
Project Manager
Enthalpy Analytical
Direct: +1-714-771-9930 | Mobile: +1-714-323-2586
patty.mata@enthalpy.com

126-02-2173
2180

From: Angel Warden <varesults@amerisci.com>
Sent: Monday, March 2, 2026 6:15 AM
To: Jocelyn Nguyen <JocelynNguyen@enthalpy.com>; Patricia Mata <patty.mata@enthalpy.com>; Zaid Padilla <zaid.padilla@enthalpy.com>
Subject: [External] - Await Enthalpy PO - Amerisci 126-02 2173 2180 2266 2267 2268 2269

EXTERNAL EMAIL - This email was sent by a person from outside your organization. Exercise caution when clicking links, opening attachments or taking further action, before validating its authenticity.

Hello Jocelyn
Here are the Enthalpy Jobs awaiting PO.
*** Patty.Mata**
1. 126-02-2173 and 2180 (553922)
*** Zaid Padilla**
126-02
1. 2266 (554007)
2. 2267 (554008)
3. 2268 (554010)
4. 2269 (554027)

Thank you
Angel Warden
Amerisci

--
Confidentiality Notice: Unless otherwise indicated, the information contained in this communication is confidential information for use of

Laboratory Job Number 553922

Subcontracted Products

Enthalpy - Wilmington

Enthalpy Analytical - Orange

931 W. Barkley Ave.
Orange, CA 92868

Client Project# EO-553922
Samples Received: 2/24/2026

Analytical Report
0226-1227

EPA Method 8290A Solid

Report Issue Date: 3/18/2026

I certify that to the best of my knowledge all analytical data presented in this report have been checked for completeness, accuracy, errors and legibility in addition to having been conducted in accordance with approved protocol, and that all deviations and analytical problems are summarized in the appropriate narrative(s). This analytical report was prepared in Portable Document Format (.PDF) and contains 22 pages. This report shall not be reproduced except in full without approval of the laboratory. This will provide assurance that parts of the report are not taken out of context.

Amendment(s):

Signature:



Laura Boivin, QA Associate II

Enthalpy Analytical, LLC – Wilmington
Christina Kurnath, Senior Project Manager
chkurnath@montrose-env.com / www.enthalpy.com
O: 910-876-6895
2714 Exchange Drive, Wilmington, NC 28405

Table of Contents

Case Narrative . . . 3
General Reporting Notes . . . 6
Results . . . 9
    Summary of Results . . . 10
    Detailed Results . . . 11
QC Data . . . 15
    Blanks . . . 16
    Controls . . . 18
Sample Custody . . . 20
    Chain of Custody . . . 21