

Request for Proposal (RFP)

Parking Lot Crack Sealing, Sealcoating, and Line Striping

Issued By

Central Susquehanna Intermediate Unit (CSIU)

Ken Erb

Phone: 570-713-7180

Email: kenneth.erb@csiu.org

RFP Issue Date

May 27, 2026

Proposal Due Date

June 15, 2026

Project Locations

15 Lawton Lane, Milton, PA

90 Lawton Lane, Milton, PA

1100 Main Street, Watsontown, PA

Project Scope of Work

Crack Sealing

- Clean and prepare cracks using compressed air or mechanical methods.
- Apply hot rubberized crack sealant suitable for asphalt pavement.
- Ensure cracks are fully sealed to prevent water intrusion.

Sealcoating

- Clean asphalt surfaces prior to sealcoat application.
- Apply one coat of commercial-grade asphalt sealcoat evenly across the entire parking lot surface.
- Contractor shall barricade areas as needed and allow adequate curing time before reopening to traffic.

Line Striping

- Re-stripe all parking spaces and traffic markings after sealcoat curing.
- Use traffic-grade reflective striping paint.
- Layout should match existing striping unless otherwise directed.

Project Schedule

Earliest Start Date: June 22, 2026

Final Completion Deadline: August 3, 2026