Salas O'Brien

ADDENDUM NO. 2


June 1, 2026

Project: Beaumont ISD – Chiller Replacement Project (Guess E.S.) (CSP 26.15)

Prepared by: Salas O'Brien Engineers
10930 W. Sam Houston Parkway N., Suite 900
Houston, Texas 77064

SOBE Project No.: 2650-00566

Prepared For: Prospective Proposers



6/01/26

PART A: NOTICE TO PROPOSERS

1. Receipt of this Addendum shall be acknowledged on the Proposal Form. Failure to do so may subject Proposers to disqualification. Each Proposer shall make necessary adjustments and submit his proposal with full knowledge of all modifications, clarifications, and supplemental data included therein.

2. This Addendum forms part of the Contract Documents and shall be incorporated integrally therewith. Where provisions of the following supplemental data differ from those of previously issued documents, this Addendum shall govern.

3. The following Contract Documents have been issued to date delineating the Work (Project). Contract Documents dated: **April 17, 2026**

4. This Addendum consists of 2 typewritten pages and 0 page of attachments for a total of 2 pages.

PART B: CHANGES TO PRIOR ADDENDUM

"Any changes to prior issued addendum materials are listed here."

1. None

PART C: CHANGES TO THE PROJECT MANUAL

"Any changes to specifications are listed here."

1. Section 23 65 28 Air-Cooled Variable Speed Rotary Screw Chiller
   a. Part 2 Products, Article 2.8 Control Panel, paragraph H, revise short circuit current rating from 65,000 A to 25,000 A.

PART D: CHANGES TO THE DRAWINGS

1. Sheet E1.1 ELECTRICAL FLOOR PLANS – MECHANICAL YARD
   a. Provide rack mounted 3P/1200A/1000AF/N3R 35,000A SCCR fused disconnect adjacent to ACC-1.
   b. Revise keyed note #3 to read "MAKE FINAL CONNECTION TO REPLACEMENT AIR COOLED CHILLER FROM EXISTING CIRCUITS LEFT IN PLACE AFTER DEMOLITION VIA NEW FUSED DISCONNECT. EXTEND 240V CIRCUIT CONDUCTORS WITH NEW 2-SETS EACH WITH (2)3#250kCMIL, 1#2/0G. AND NEW FLEXIBLE 3"C. AS REQUIRED. EXTEND 120V CIRCUIT CONDUCTORS/CONDUIT WITH MATCHING SIZE AND PROVIDE NEW LOCAL DISCONNECT AS SHOWN. EXTEND BMCS AND ASSOCIATED CONTROL CONDUCTORS/CONDUIT AS

REQUIRED.”.

PART E: **RE-ISSUED DRAWING SHEET** *(30” x 42”)*
“Insert the following sheets and omit the previously issued sheets of the same number.”
1. None

PART F: **NEW DRAWINGS SHEETS** *(30” x 42”)*
1. None

PART G: **QUESTIONS/CLARIFICATIONS**
1. None

PART H: **ATTACHMENTS**
1. None

END OF ADDENDUM 2